

# PIC18F26/46/56Q84

# 28/40/44/48-Pin, Low-Power, High-Performance Microcontroller with XLP Technology

### Introduction

The PIC18-Q84 microcontroller family is available in 28/40/44/48-pin devices for many automotive and industrial applications. The many communication peripherals found on the product family, such as CAN, SPI, I<sup>2</sup>C, two UARTs, can handle a wide range of wired and wireless (using external modules) communication protocols for intelligent applications. Combined with the Core Independent Peripherals integration capabilities, this capacity enables functions for motor control, power supply, sensor, signal and user interface applications. Additionally, this family includes a 12-bit ADC with Computation and Context Switching extensions for automated signal analysis to reduce the complexity of the application.

# PIC18-Q84 Family Types

Table 1. Devices Included in This Data Sheet

Device	Program Memory Flash (bytes)	Data SRAM (bytes)	Data EEPROM (bytes)	Memory Access Partition/ Device Information Area	I/O Pins/ Peripheral Pin Select	8-Bit Timer with HLT/ 16-Bit Timers	16-Bit Dual PWM/ CCP	Complimentary Waveform Generator	Signal Measurement Timer	16-Bit Universal Timer	Numerically Controlled Oscillator	Configurable Logic Cell	12-Bit ADC w/Computation and Context Switching (channels)	8-Bit DAC	Comparator/ Zero-Cross Detect	High-Low Voltage Detect	CAN FD	SPIN <sup>2</sup> C	UART/ UART with Protocol Support	Direct Memory Access (DMA)	Windowed Watchdog Timer	32-Bit CRC with Scanner	Vectored Interrupts	Peripheral Module Disable	Temperature Indicator	JTAG Boundary Scan
PIC18F26Q84	128k	12800	1024	Y/Y	25/Y	3/3	4/3	3	1	2	3	8	24	1	2/1	1	Υ	2/1	3/2	8	Υ	Υ	Υ	Υ	Υ	Y
PIC18F46Q84	128k	12800	1024	Y/Y	36/Y	3/3	4/3	3	1	2	3	8	35	1	2/1	1	Υ	2/1	3/2	8	Υ	Υ	Υ	Υ	Υ	Υ
PIC18F56Q84	128k	12800	1024	Y/Y	44/Y	3/3	4/3	3	1	2	3	8	43	1	2/1	1	Υ	2/1	3/2	8	Υ	Υ	Υ	Υ	Υ	Υ

### **Features**

- · C Compiler Optimized RISC Architecture
- Operating Speed:
  - DC 64 MHz clock input
  - 62.5 ns minimum instruction cycle
- · Eight Direct Memory Access (DMA) Controllers:
  - Data transfers to SFR/GPR spaces from either Program Flash Memory, Data EEPROM or SFR/GPR spaces

- User programmable source and destination sizes
- Hardware and software triggered data transfers
- Vectored Interrupt Capability:
  - Selectable high/low priority
  - Fixed interrupt latency of three instruction cycles
  - Programmable vector table base address
  - Backwards compatible with previous interrupt capabilities
- 128-Level Deep Hardware Stack
- Low-Current Power-on Reset (POR)
- Configurable Power-up Timer (PWRT)
- Brown-out Reset (BOR)
- · Low-Power BOR (LPBOR) Option
- · Windowed Watchdog Timer (WWDT):
  - Watchdog Reset on too long or too short interval between watchdog clear events
  - Variable prescaler selection
  - Variable window size selection

# Memory

- · Up to 128 KB of Program Flash Memory
- · Up to 13 KB of Data SRAM Memory
- 1024 Bytes Data EEPROM
- Memory Access Partition: The Program Flash Memory can be partitioned into:
  - Application Block
  - Boot Block
  - Storage Area Flash (SAF) Block
- Programmable Code Protection and Write Protection
- Device Information Area (DIA) Stores:
  - Temperature indicator factory calibrated data
  - Fixed Voltage Reference measurement data
  - Microchip unique identifier
- · Device Characteristics Information (DCI) Area Stores:
  - Program/erase row sizes
  - Pin count details
  - EEPROM size
- · Direct, Indirect and Relative Addressing modes

# **Operating Characteristics**

- Operating Voltage Range:
  - 1.8V to 5.5V
- Temperature Range:
  - Industrial: -40°C to 85°C
  - Extended: -40°C to 125°C

# **Power-Saving Functionality**

- Doze: CPU and Peripherals Running at Different Cycle Rates (typically CPU is lower)
- · Idle: CPU Halted While Peripherals Operate

- · Sleep: Lowest Power Consumption
- Peripheral Module Disable (PMD):
  - Ability to selectively disable hardware module to minimize active power consumption of unused peripherals
- Low-Power Mode Features:
  - Sleep: < 1µA typical @ 3V</li>
  - Operating Current:
    - 48µA @ 32 kHz, 3V, typical

# **Digital Peripherals**

- · Four 16-Bit Pulse-Width Modulators (PWM):
  - Dual outputs for each PWM module
  - Integrated 16-bit timer/counter
  - Double-buffered user registers for duty cycles
  - Right/Left/Center/Variable aligned modes of operation
  - Multiple clock and Reset signal selections
- Three 16-Bit Timers (TMR0/1/3)
- · Three 8-Bit Timers (TMR2/4/6) with Hardware Limit Timer (HLT)
- Two Universal Timers (TMRU16A/16B):
  - New Timer modules with features of TMR0/TMR1/TMR2 (Gate, Hardware Limit)
  - Two 16-bit timers can be chained together to create a combined 32-bit timer
- · Eight Configurable Logic Cell (CLC):
  - Integrated combinational and sequential logic
- Three Complimentary Waveform Generators (CWG):
  - Rising and falling edge dead-band control
  - Full-bridge, half-bridge, 1-channel drive
  - Multiple signal sources
  - Programmable dead band
  - Fault-shutdown input
- · Three Capture/Compare/PWM (CCP) modules:
  - 16-bit resolution for Capture/Compare modes
  - 10-bit resolution for PWM mode
- Three Numerically Controlled Oscillators (NCO):
  - Generates true linear frequency control and increased frequency resolution
  - Input clock up to 64 MHz
- Signal Measurement Timer (SMT):
  - 24-bit timer/counter with prescaler
  - Several modes of operation like Time-of-Flight, Period and Duty Cycle measurement, etc.
- · Data Signal Modulator (DSM):
  - Multiplex two carrier clocks, with glitch prevention feature
  - Multiple sources for each carrier
- Programmable CRC with Memory Scan:
  - Reliable data/program memory monitoring for Fail-Safe operation (e.g., Class B)
  - Calculate 16-bit CRC over any portion of Program Flash Memory
- · CAN Flexible Data-Rate (FD) module:
  - Functional in CAN FD or CAN 2.0B modes
  - One dedicated transmit FIFO
  - Three Programmable Transmit/Receive FIFOs
  - One Transmit Event Queue

- 12 Acceptance Masks/Filters
- · Five UART modules:
  - LIN master and slave, DMX mode, DALI gear and device protocols
  - Asynchronous UART, RS-232, RS-485 compatible
  - Automatic and user timed BREAK period generation
  - Automatic checksums
  - Programmable 1, 1.5, and two Stop bits
  - Wake-up on BREAK reception
  - DMA compatible
- · Two SPI modules:
  - Configurable length bytes
  - Arbitrary length data packets
  - Transmit-without-receive and receive-without-transmit options
  - Transfer byte counter
  - Separate transmit and receive buffers with 2-byte FIFO and DMA capabilities
- One l<sup>2</sup>C module, SMBus, PMBus<sup>™</sup> Compatible:
  - 7-bit and 10-bit addressing modes with address masking modes
  - Dedicated address, transmit and receive buffers and DMA capabilities
  - Bus collision detection with arbitration
  - Bus time-out detection and handling
  - I<sup>2</sup>C, SMBus 2.0 and SMBus 3.0, and 1.8V input level selections
  - Multi-Master mode, including self-addressing
- · Device I/O Port Features:
  - 25 I/O pins (PIC18F26/27Q84)
  - 36 I/O pins (PIC18F46/47Q84)
  - 44 I/O pins (PIC18F56/57Q84)
  - Individually programmable I/O direction, open-drain, slew rate and weak pull-up control
  - Interrupt-on-change on most pins
  - Three programmable external interrupt pins
- Peripheral Pin Select (PPS):
  - Enables pin mapping of digital I/O

# **Analog Peripherals**

- · Analog-to-Digital Converter with Computation and Context Switching:
  - Up to 43 external channels
  - Automated math functions on input signals:
    - · Averaging, filter calculations, oversampling and threshold comparison
  - Four Separate Contexts (settings and results) saved and accessible separately
  - Contexts can be accessed through firmware or DMA
  - Operates in Sleep
  - Five internal analog channels
  - Hardware Capacitive Voltage Divider (CVD) Support:
    - · Adjustable sample and hold capacitor array
    - · Guard ring digital output drive
    - Automates touch sampling and reduces software size and CPU usage when touch or proximity sensing is required
- 8-Bit Digital-to-Analog Converter (DAC):
  - Buffered output available on two I/O pins
  - Internal connections to ADC and Comparators

- Two Comparators (CMP):
  - Four external inputs
  - Configurable output polarity
  - External output via Peripheral Pin Select
- Zero-Cross Detect (ZCD):
  - Detect when AC signal on pin crosses ground
- · Voltage Reference:
  - Fixed Voltage Reference with 1.024V, 2.048V and 4.096V output levels
  - Internal connections to ADC, Comparator and DAC

# **Clocking Structure**

- · High-Precision Internal Oscillator Block (HFINTOSC):
  - Selectable frequencies up to 64 MHz
  - ±1% at calibration
  - Active Clock Tuning of HFINTOSC for better accuracy
- 32 kHz Low-Power Internal Oscillator (LFINTOSC)
- External 32 kHz Crystal Oscillator (SOSC)
- External High-frequency Oscillator Block:
  - Three crystal/resonator modes
  - Digital Clock Input mode
  - 4x PLL with external sources
- · Fail-Safe Clock Monitor:
  - Allows for operational recovery if external clock stops
- · Oscillator Start-up Timer (OST):
  - Ensures stability of crystal oscillator sources

# **Programming/Debug Features**

- In-Circuit Serial Programming<sup>™</sup> (ICSP<sup>™</sup>) via Two Pins
- · In-Circuit Debug (ICD) with Three Breakpoints via Two Pins
- Debug Integrated On-Chip

# **Table of Contents**

Intro	oduction	1
PIC	18-Q84 Family Types	1
Fea	tures	1
1.	Packages	9
2.	Pin Diagrams	10
3.	Pin Allocation Tables	14
4.	Guidelines for Getting Started with PIC18-Q84 Microcontrollers	19
5.	Register and Bit Naming Conventions	24
6.	Register Legend	26
7.	PIC18 CPU	27
8.	Device Configuration	45
9.	Memory Organization	68
10.	NVM - Nonvolatile Memory Module	99
11.	VIC - Vectored Interrupt Controller Module	124
12.	OSC - Oscillator Module (With Fail-Safe Clock Monitor)	. 205
13.	CRC - Cyclic Redundancy Check Module with Memory Scanner	232
14.	Resets	254
15.	WWDT - Windowed Watchdog Timer	267
16.	DMA - Direct Memory Access	278
17.	Power-Saving Modes	318
18.	PMD - Peripheral Module Disable	326
19.	I/O Ports	337
20.	IOC - Interrupt-on-Change	353
21.	PPS - Peripheral Pin Select Module	. 359
22.	CLC - Configurable Logic Cell	373
23.	CLKREF - Reference Clock Output Module	394
24.	TMR0 - Timer0 Module	399
25.	TMR1 - Timer1 Module with Gate Control	407
26.	TMR2 - Timer2 Module	. 424

27.	SMT - Signal Measurement Timer	. 448
28.	UTMR - Universal Timer Module	474
29.	CCP - Capture/Compare/PWM Module	512
30.	Capture, Compare, and PWM Timers Selection	525
31.	PWM - Pulse-Width Modulator with Compare	528
32.	CWG - Complementary Waveform Generator Module	555
33.	NCO - Numerically Controlled Oscillator Module	583
34.	DSM - Data Signal Modulator Module	593
35.	UART - Universal Asynchronous Receiver Transmitter with Protocol Support	604
36.	SPI - Serial Peripheral Interface Module	650
37.	I <sup>2</sup> C - Inter-Integrated Circuit Module	. 683
38.	CAN FD - Controller Area Network, Flexible Data-Rate	. 769
39.	JTAG Boundary Scan	875
40.	HLVD - High/Low-Voltage Detect	882
41.	FVR - Fixed Voltage Reference	. 890
42.	Temperature Indicator Module	. 894
43.	ADC - Analog-to-Digital Converter with Computation and Context Module	899
44.	DAC - Digital-to-Analog Converter Module	952
45.	CMP - Comparator Module	957
46.	ZCD - Zero-Cross Detection Module	968
47.	Instruction Set Summary	975
48.	ICSP <sup>™</sup> - In-Circuit Serial Programming <sup>™</sup>	1060
49.	Register Summary	1063
50.	Electrical Specifications	1083
51.	DC and AC Characteristics Graphs and Tables	.1112
52.	Packaging Information	.1113
53.	Appendix A: Revision History	1139
The	Microchip Website	1140
Pro	duct Change Notification Service	1140
Cus	stomer Support	1140

Product Identification System	1141
Microchip Devices Code Protection Feature	1141
Legal Notice	1142
Trademarks	1142
Quality Management System	1143
Worldwide Sales and Service	1144

# 1. Packages

# Table 1-1. Packages

Device	28-pin SPDIP	28-pin SOIC	28-pin SSOP	28-pin VQFN 4x4x1	40-pin PDIP	40-pin VQFN 5x5x0.9	44-pin TQFP	48-pin TQFP 7x7x1	48-pin VQFN 6x6x0.9
PIC18F26Q84	•	•	•	•					
PIC18F46Q84					•	•	•		
PIC18F56Q84								•	•

#### 2. **Pin Diagrams**

Figure 2-1. 28-Pin SPDIP 28-Pin SSOP 28-Pin SOIC





Figure 2-2. 28-Pin VQFN



Note: It is recommended that the exposed bottom pad be connected to V<sub>SS</sub>; however, it must not be the only V<sub>SS</sub> connection to the device.

Figure 2-3. 40-Pin PDIP





Figure 2-4. 40-Pin VQFN



Note: It is recommended that the exposed bottom pad be connected to V<sub>SS</sub>; however, it must not be the only V<sub>SS</sub> connection to the device.

Figure 2-5. 44-Pin TQFP






Figure 2-6. 48-Pin VQFN



Note: It is recommended that the exposed bottom pad be connected to  $V_{SS}$ ; however, it must not be the only  $V_{SS}$ connection to the device.

Figure 2-7. 48-Pin TQFP



**Pin Allocation Tables** 

PIC18F26/46/56Q84

**Pin Allocation Tables** 

Table 3-1. 28-Pin Allocation Table

I/O <sup>(2)</sup>	28- Pin SPDIP, SOIC, SSOP	28- Pin VQFN	A/D	Reference	Comparator	ZCD	Timers/SMT	16-Bit PWM/ CCP	CWG	CLC	SPI	ı²c	UART	DSM	юс	Interrupt	CAN FD	CRC on Boot	JTAG	Basic
RA0	2	27	ANA0	_	C1IN0- C2IN0-	_	_	_	_	CLCIN <sub>0</sub> (1) CLCIN <sub>4</sub> (1)	-	_	_	_	IOCA0	-	_	_	TMS	_
RA1	3	28	ANA1	_	C1IN1- C2IN1-	_	_	_	_	CLCIN1(1) CLCIN5(1)	_	-	_	_	IOCA1	_	_	-	_	-
RA2	4	1	ANA2	DAC1OUT1 VREF- (DAC) VREF- (ADC)	C1IN0+ C2IN0+	_	_	_	_	_	_	_	_	_	IOCA2	_	_	BOOTA2	_	-
RA3	5	2	ANA3	V <sub>REF</sub> + (DAC) V <sub>REF</sub> + (ADC)	C1IN1+	_	_	_	_	_	_	_	_	MDCARL(1)	IOCA3	_	_	_	_	_
RA4	6	3	ANA4	_	_	_	T0CKI(1)	_	_	_	SS2(1)	_	CTS5(1)	MDCARH(1)	IOCA4	_	_	ВООТА4	_	_
RA5	7	4	ANA5	_	_	_	_	_	_	_	SS1(1)	_	RX5(1)	MDSRC(1)	IOCA5	_	_	_	TCK	_
RA6	10	7	ANA6	_	_	_	_	_	_	_	_	_	CTS3(1)	_	IOCA6	_	_	_	_	CLKOUT OSC2
RA7	9	6	ANA7	_	_	_	_	_	_	_	_	_	RX3(1)	_	IOCA7	_	_	_	_	OSC1 CLKIN
RB0	21	18	ANB0	_	C2IN1+	ZCDIN	_	_	CWG1(1)	_	_	_	_	_	IOCB0	INT0(1)	_	_	_	_
RB1	22	19	ANB1	_	C1IN3- C2IN3-	-	_	_	CWG2(1)	_	_	_(4)	_	_	IOCB1	INT1(1)	_	_	-	_
RB2	23	20	ANB2	_	_	_	_	_	CWG3(1)	_	SDI2(1)	(4)	_	_	IOCB2	INT2(1)	_	_	_	_
RB3	24	21	ANB3	_	C1IN2- C2IN2-	_	_	_	_	_	SCK2(1)	_	_	_	IOCB3	_	CANRX(1)	_	TDO	_
RB4	25	22	ANB4 ADACT(1)	_	_	_	<sub>T5G</sub> (1)	_	_	_	_	_	CTS4(1)	_	IOCB4	_	_	_	-	_
RB5	26	23	ANB5	_	_	_	T1G(1)	CCP3(1)	_	_	_	_	RX4(1)	_	IOCB5	_	_	_	TDI	_
RB6	27	24	ANB6	_	_	_	_	_	_	CLCIN2(1) CLCIN6(1)	_	_	CTS2(1)	_	IOCB6	_	_	_	-	ICSPCLK
RB7	28	25	ANB7	DAC1OUT2	_	_	T6IN(1)	PWM3ERS(1)	-	CLCIN3 <sup>(1)</sup> CLCIN7 <sup>(1)</sup>	_	_	RX2(1)	_	IOCB7	_	_	-	-	ICSPDAT
RC0	11	8	ANC0	_	_	_	T1CKI(1) T3CKI(1) T3G(1) SMT1WIN(1)	_	_	_	_	_	_	-	IOCC0	_	_	_	_	sosco

с	ontinued																			
1/0(2)	28- Pin SPDIP, SOIC, SSOP	28- Pin VQFN	A/D	Reference	Comparator	ZCD	Timers/SMT	16-Bit PWM/ CCP	cwg	CLC	SPI	ı²с	UART	DSM	юс	Interrupt	CAN FD	CRC on Boot	JTAG	Basic
RC1	12	9	ANC1	_	_	_	SMT1SIG(1)	CCP2(1)	_	_	_	_	_	-	IOCC1	_	_	_	_	SOSCIN SOSCI
RC2	13	10	ANC2	_	_	_	T5CKI(1)	PWMIN0(1) CCP1(1)	_	_	_	_	_	_	IOCC2	_	_	_	_	_
RC3	14	11	ANC3	_	_	_	T2IN(1)	PWM1ERS(1)	-	_	SCK1(1)	SCL1(3,4)	-	-	IOCC3	_	_	_	_	_
RC4	15	12	ANC4	_	_	_	_	_	_	_	SDI1(1)	SDA(3,4)	_	_	IOCC4	_	_	BOOTC4	_	_
RC5	16	13	ANC5		_	_	T4IN(1)	PWM2ERS(1)	_	_	_	_		_	IOCC5	_	_	BOOTC5	_	_
RC6	17	14	ANC6		_	_	_	PWMIN1(1)	_	_	_	_	CTS1(1)		IOCC6		_	_	_	_
RC7	18	15	ANC7		_	_	_	_		_	_	_	RX1(1)		IOCC7		_	_	_	_
RE3	1	26	_		_	_	_	_		_	_	_	_		IOCE3		_	_	_	Vpp/MCLR
V <sub>SS</sub>	19	16 17	_	_	_	_	_	_	_	_	_	_	_		_		_	_	_	V <sub>SS</sub>
VSS	8	5	_	_	_	_	_	_	_	_	_	_	_		_	_	_	_	_	V <sub>SS</sub>
OUT <sup>(2)</sup>		_	ADGRDA ADGRDB	-	C1OUT C2OUT	_	TMR0	PWM11 PWM12 PWM21 PWM22 PWM31 PWM32 CCP1 CCP2 CCP3	CWG1A CWG1B CWG1C CWG1D CWG2A CWG2B CWG2C	CLC1OUT CLC2OUT CLC3OUT CLC4OUT CLC5OUT CLC6OUT CLC7OUT CLC8OUT	SS1 SCK1 SDO1 SS2 SCK2	SDA1 SCL1	DTR1 RTS1 TX1 DTR2 RTS2 TX2 DTR3 RTS3 TX3 DTR4 RTS4 TX4 DTR5 RTS5 TX5	DSM1	_	-	CANTX	_	_	_

#### Notes:

- 1. This is a PPS remappable input signal. The input function may be moved from the default location shown to one of several other PORTx pins. Refer to the peripheral input selection table for details on which PORT pins may be used for this signal.
- 2. All output signals shown in this row are PPS remappable. These signals may be mapped to output onto one of several PORTx pin options as described in the peripheral output selection table.
- 3. This is a bidirectional signal. For normal module operation, the firmware should map this signal to the same pin in both the PPS input and PPS output registers.
- 4. These pins are configured for 1<sup>2</sup>C logic levels; The SCLx/SDAx signals may be assigned to any of these pins. PPS assignments to the other pins (e.g., RB1) will operate, but input logic levels will be standard TTL/ST as selected by the INLVL register, instead of the 1<sup>2</sup>C specific or SMBus input buffer thresholds.

PIC18F26/46/56Q84

**Pin Allocation Tables** 

5. A 0.1 uF bypass capacitor to  $V_{SS}$  is required on the  $V_{DD}$  pin.

PIC18F26/46/56Q84
Pin Allocation Tables

Table 3-2. 40/44/48-Pin Allocation Table

				,	Cation																	
I/O <sup>(2)</sup>	40- Pin PDIP	40- Pin VQFN	44- Pin TQFP	48- Pin TQFP / VQFN	A/D	Reference	Comparator	ZCD	Timers/SM T	16-Bit PWM/ CCP	cwg	CLC	SPI	I <sup>2</sup> C	UART	DSM	юс	Interrupt	CAN FD	CRC on Boot	JTAG	Basic
RA0	2	17	19	21	ANA0	_	C1IN0- C2IN0-	_	_	_		CLCIN0(1) CLCIN4(1)		_	_	_	IOCA0	_	_	-	TMS	-
RA1	3	18	20	22	ANA1	_	C1IN1- C2IN1-	_	_	_	_	CLCIN1 <sup>(1)</sup> CLCIN5 <sup>(1)</sup>	_	_	_	_	IOCA1	_	_	_	_	_
RA2	4	19	21	23	ANA2	DAC1OUT1  VREF- (DAC)  VREF- (ADC)	C1IN0+ C2IN0+	_	-	_	_	_	_	_	_	_	IOCA2	_	_	BOOTA2	_	_
RA3	5	20	22	24	ANA3	VREF+ (DAC) VREF+ (ADC)	C1IN1+	_	-	-	_	_	_	_	_	MDCARL(1)	IOCA3	_	_	-	_	_
RA4	6	21	23	25	ANA4	_	_	_	T0CKI(1)	_	_	_	SS2(1)	_	CTS5(1)	MDCARH(1)	IOCA4	_	_	воота4	_	_
RA5	7	22	24	26	ANA5	_	_	_	_	_	_	_	SS1(1)	_	RX5(1)	MDSRC(1)	IOCA5	_	_	_	TCK	_
RA6	14	29	31	33	ANA6	_	_	_	_	_	_	_	_	_	CTS3(1)	_	IOCA6	_	_	_	_	CLKOUT OSC2
RA7	13	28	30	32	ANA7	_	_	_	-	-	_	_	_	_	RX3(1)	_	IOCA7	_	_	_	_	OSC1 CLKIN
RB0	33	8	8	8	ANB0	_	C2IN1+	ZCDIN	_	_	CWG1(1)	_	_	_	_	_	IOCB0	INT0(1)	_	_	_	_
RB1	34	9	9	9	ANB1	_	C1IN3- C2IN3-	_	_	_	CWG2(1)	_	_	(4)	_	_	IOCB1	INT1(1)	_	_	_	_
RB2	35	10	10	10	ANB2	_	_	_	_	_	CWG3(1)	_	SDI2(1)	(4)	_	_	IOCB2	INT2(1)	_	_	_	_
RB3	36	11	11	11	ANB3	_	C1IN2- C2IN2-	_	_	_	_	_	SCK2(1)	_	_	_	IOCB3	_	_	_	TDO	_
RB4	37	12	14	16	ANB4 ADACT(1)	_	_	_	<sub>T5G</sub> (1)	_	_	_	_	_	CTS4(1)	_	IOCB4	_	_	_	_	_
RB5	38	13	15	17	ANB5	_	_	_	T1G(1)	CCP3(1)	_	_	_	_	RX4(1)	_	IOCB5	_	_	_	TDI	_
RB6	39	14	16	18	ANB6	_	_	_	_	_	_	CLCIN2 <sup>(1)</sup> CLCIN6 <sup>(1)</sup>		_	CTS2(1)	_	IOCB6	_	_	_	_	ICSPCLK

c	ontinue	ed																				
I/O <sup>(2)</sup>	40- Pin PDIP	40- Pin VQFN	44- Pin TQFP	48- Pin TQFP / VQFN	A/D	Reference	Comparator	ZCD	Timers/SM T	16-Bit PWM/ CCP	CWG	CLC	SPI	ı²c	UART	DSM	ЮС	Interrupt	CAN FD	CRC on Boot	JTAG	Basic
RB7	40	15	17	19	ANB7	DAC1OUT2	_	_	T6IN(1)	PWM3ERS(1)		CLCIN3 <sup>(1)</sup> CLCIN7 <sup>(1)</sup>	_	_	RX2(1)	-	IOCB7	_	_	_	-	ICSPDAT
RC0	15	30	32	34	ANC0	_	_	_	T1CKI(1)  T3CKI(1)  T3G(1)  SMT1WIN(1)	_	_	_	_	_	_	_	IOCC0	_	_	_	_	sosco
RC1	16	31	35	35	ANC1	_	_	_	SMT1SIG(1)	CCP2 <sup>(1)</sup>	-	_		-	_	_	IOCC1	_	_	-	-	SOSCIN SOSCI
RC2	17	32	36	40	ANC2	_	_	_	T5CKI(1)	PWMIN0(1) CCP1(1)	_	_	_	_	_	_	IOCC2	_	_	_	_	_
RC3	18	33	37	41	ANC3	_	_	_	T2IN(1)	PWM1ERS(1)	_	_	SCK1(1)	SCL1(3,4)	_	_	IOCC3	_	_		_	_
RC4	23	38	42	46	ANC4	_	_	_	_	_	_	_	SDI1(1)	SDA(3,4)	_	_	IOCC4	_	_	воотс4	_	_
RC5	24	39	43	47	ANC5	_	_	_	T4IN(1)	PWM2ERS(1)	_	_	_	_	_	_	IOCC5	_	_	воотс5	_	_
RC6	25	40	44	48	ANC6	_	_	_	_	PWMIN1(1)	_	_	_	_	CTS1(1)	_	IOCC6	_	_	_	_	_
RC7	26	1	1	1	ANC7	_	_	_	_	_	_	_	_	_	RX1(1)	_	IOCC7	_	_	_	_	_
RD0	19	34	38	42	AND0	_	_	_	_	_	_	_	_	_	_	_	_	_	_		_	_
RD1	20	35	39	43	AND1	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
RD2	21	36	40	44	AND2	_	_	_	_	_	_	_	_	_	_	_	_	_	_		_	_
RD3	22	37	41	45	AND3	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
RD4	27	2	2	2	AND4	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
RD5	28	3	3	3	AND5	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
RD6	29	4	4	4	AND6	_	_	_	_	_	_	_	_	_	_	_	_	_	_		_	_
RD7	30	5	5	5	AND7	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
RE0	8	23	25	27	ANE0	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
RE1	9	24	26	28	ANE1	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
RE2	10	25	27	29	ANE2	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
RE3	1	16	18	20	_	_	_	-	_	-	_	_	_	_	-	-	IOCE3	_	_	_	_	Vpp/ MCLR
RF0	_	_	_	36	ANF0	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
RF1	_	_	_	37	ANF1	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
RF2	_	_	_	38	ANF2	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	
RF3	_	_	_	39	ANF3	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	
RF4	_	_	_	12	ANF4	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	
RF5	_	_	_	13	ANF5	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	

PIC18F26/46/56Q84

**Pin Allocation Tables** 

с	ontinue	d																				
I/O <sup>(2)</sup>	40- Pin PDIP	40- Pin VQFN	44- Pin TQFP	48- Pin TQFP / VQFN	A/D	Reference	Comparator	ZCD	Timers/SM T	16-Bit PWM/ CCP	cwg	CLC	SPI	ı²c	UART	DSM	юс	Interrupt	CAN FD	CRC on Boot	JTAG	Basic
RF6	_	_	_	14	ANF6	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	
RF7	_	_	_	15	ANF7	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	
	12, 31		6, 29	6,31	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	Vss
V <sub>DD</sub> (5)	11, 32	7, 26	7, 28	7, 30	_	_	_	_	_	_	_	_	_	_	_	_	_	_		_	_	<sub>VDD</sub> (5)
OUT <b>(2)</b>					ADGRDA ADGRDB	_	C1OUT C2OUT		TMR0	PWM11 PWM12 PWM21 PWM22 PWM31 PWM32 CCP1 CCP2 CCP3	CWG1D CWG2A CWG2B CWG2C CWG2D CWG3A	CLC1OUT CLC2OUT CLC3OUT CLC4OUT CLC5OUT CLC6OUT CLC7OUT CLC8OUT	SCK1 SDO1 SS2 SCK2	SDA1 SCL1	DTR1 RTS1 TX1 DTR2 RTS2 TX2 DTR3 RTS3 TX3 DTR4 RTS4 TX4 DTR5 RTS5 TX5	DSM1	_	_	_	-	_	

#### Notes:

- 1. This is a PPS remappable input signal. The input function may be moved from the default location shown to one of several other PORTx pins. Refer to the peripheral input selection table for details on which PORT pins may be used for this signal.
- 2. All output signals shown in this row are PPS remappable. These signals may be mapped to output onto one of several PORTx pin options as described in the peripheral output selection table.
- 3. This is a bidirectional signal. For normal module operation, the firmware should map this signal to the same pin in both the PPS input and PPS output registers.
- 4. These pins are configured for I<sup>2</sup>C logic levels; The SCLx/SDAx signals may be assigned to any of these pins. PPS assignments to the other pins (e.g., RB1) will operate, but input logic levels will be standard TTL/ST as selected by the INLVL register, instead of the I<sup>2</sup>C specific or SMBus input buffer thresholds.

PIC18F26/46/56Q84

**Pin Allocation Tables** 

A 0.1 uF bypass capacitor to VSS is required on all VDD pins.

# 4. Guidelines for Getting Started with PIC18-Q84 Microcontrollers

#### 4.1 Basic Connection Requirements

Getting started with the PIC18-Q84 family of 8-bit microcontrollers requires attention to a minimal set of device pin connections before proceeding with development.

The following pins must always be connected:

- All V<sub>DD</sub> and V<sub>SS</sub> pins (see Power Supply Pins)
- MCLR pin (see Master Clear (MCLR) Pin)

These pins must also be connected if they are being used in the end application:


- ICSPCLK/ICSPDAT pins used for In-Circuit Serial Programming<sup>™</sup> (ICSP<sup>™</sup>) and debugging purposes (see In-Circuit Serial Programming (ICSP) Pins)
- OSCI and OSCO pins when an external oscillator source is used (see External Oscillator Pins)

Additionally, the following pins may be required:

V<sub>REF</sub>+/V<sub>REF</sub>- pins are used when external voltage reference for analog modules is implemented

The minimum mandatory connections are shown in the figure below.

Figure 4-1. Recommended Minimum Connections



#### Key

C1: 0.1 µF, 20V ceramic (recommended)

R1: 10 kΩ (recommended)

R2:  $100\Omega$  to  $470\Omega$  (recommended)

C2: 0.1 µF, 20V ceramic (required)

# 4.2 Power Supply Pins

#### 4.2.1 Decoupling Capacitors

The use of decoupling capacitors on every pair of power supply pins ( $V_{DD}$  and  $V_{SS}$ ) is required.

Consider the following criteria when using decoupling capacitors:

- Value and type of capacitor: A 0.1 μF (100 nF), 10-20V capacitor is recommended. The capacitor should be a low-ESR device, with a resonance frequency in the range of 200 MHz and higher. Ceramic capacitors are recommended.
- Placement on the printed circuit board: The decoupling capacitors should be placed as close to the pins as possible. It is recommended to place the capacitors on the same side of the board as the device. If space is constricted, the capacitor can be placed on another layer on the PCB using a via; however, ensure that the trace length from the pin to the capacitor is no greater than 0.25 inch (6 mm).

# Guidelines for Getting Started with PIC18-Q84 Micr...

- Handling high-frequency noise: If the board is experiencing high-frequency noise (upward of tens of MHz), add a
  second ceramic type capacitor in parallel to the above described decoupling capacitor. The value of the second
  capacitor can be in the range of 0.01 μF to 0.001 μF. Place this second capacitor next to each primary
  decoupling capacitor. In high-speed circuit designs, consider implementing a decade pair of capacitances as
  close to the power and ground pins as possible (e.g., 0.1 μF in parallel with 0.001 μF).
- Maximizing performance: On the board layout from the power supply circuit, run the power and return traces to
  the decoupling capacitors first, and then to the device pins. This ensures that the decoupling capacitors are first
  in the power chain. Equally important is to keep the trace length between the capacitor and the power pins to a
  minimum, thereby reducing PCB trace inductance.

#### 4.2.2 Tank Capacitors

On boards with power traces running longer than six inches in length, it is suggested to use a tank capacitor for integrated circuits, including microcontrollers, to supply a local power source. The value of the tank capacitor should be determined based on the trace resistance that connects the power supply source to the device, and the maximum current drawn by the device in the application. In other words, select the tank capacitor that meets the acceptable voltage sag at the device. Typical values range from 4.7 µF to 47 µF.


# 4.3 Master Clear (MCLR) Pin

The  $\overline{MCLR}$  pin provides two specific device functions: Device Reset, and Device Programming and Debugging. If programming and debugging are not required in the end application, a direct connection to  $V_{DD}$  may be all that is required. The addition of other components, to help increase the application's resistance to spurious Resets from voltage sags, may be beneficial. A typical configuration is shown in Figure 4-1. Other circuit designs may be implemented, depending on the application's requirements.

During programming and debugging, the resistance and capacitance that can be added to the pin must be considered. Device programmers and debuggers drive the  $\overline{MCLR}$  pin. Consequently, specific voltage levels ( $V_{IH}$  and  $V_{IL}$ ) and fast signal transitions must not be adversely affected. Therefore, specific values of R1 and C1 will need to be adjusted based on the application and PCB requirements. For example, it is recommended that the capacitor, C1, be isolated from the  $\overline{MCLR}$  pin during programming and debugging operations by using a jumper (Figure 4-2). The jumper is replaced for normal run-time operations.

Any components associated with the MCLR pin should be placed within 0.25 inch (6 mm) of the pin.

Figure 4-2. Example of MCLR Pin Connections



#### Notes:

- R1 ≤ 10 kΩ is recommended. A suggested starting value is 10 kΩ. Ensure that the MCLR pin V<sub>IH</sub> and V<sub>IL</sub> specifications are met.
- R2 ≤ 470Ω will limit any current flowing into MCLR from the extended capacitor, C1, in the event of MCLR pin breakdown, due to Electrostatic Discharge (ESD) or Electrical Overstress (EOS). Ensure that the MCLR pin V<sub>IH</sub> and V<sub>II</sub> specifications are met.

# 4.4 In-Circuit Serial Programming<sup>™</sup> (ICSP<sup>™</sup>) Pins

The ICSPCLK and ICSPDAT pins are used for ICSP and debugging purposes. It is recommended to keep the trace length between the ICSP connector and the ICSP pins on the device as short as possible. If the ICSP connector is expected to experience an ESD event, a series resistor is recommended, with the value in the range of a few tens of ohms, not to exceed  $100\Omega$ .

# PIC18F26/46/56Q84

### Guidelines for Getting Started with PIC18-Q84 Micr...

Pull-up resistors, series diodes and capacitors on the ICSPCLK and ICSPDAT pins are not recommended as they can interfere with the programmer/debugger communications to the device. If such discrete components are an application requirement, they should be removed from the circuit during programming and debugging. Alternatively, refer to the AC/DC characteristics and timing requirements information in the respective device Flash programming specification for information on capacitive loading limits, and pin input voltage high (V<sub>IH</sub>) and input low (V<sub>IL</sub>) requirements.

For device emulation, ensure that the "Communication Channel Select" (i.e., ICSPCLK/ICSPDAT pins), programmed into the device, matches the physical connections for the ICSP to the Microchip debugger/emulator tool.

#### 4.5 External Oscillator Pins


Many microcontrollers have options for at least two oscillators: a high-frequency primary oscillator and a low-frequency secondary oscillator.

The oscillator circuit should be placed on the same side of the board as the device. Place the oscillator circuit close to the respective oscillator pins with no more than 0.5 inch (12 mm) between the circuit components and the pins. The load capacitors should be placed next to the oscillator itself, on the same side of the board.


Use a grounded copper pour around the oscillator circuit to isolate it from surrounding circuits. The grounded copper pour should be routed directly to the MCU ground. Do not run any signal traces or power traces inside the ground pour. Also, if using a two-sided board, avoid any traces on the other side of the board where the crystal is placed.

Layout suggestions are shown in the following figure. In-line packages may be handled with a single-sided layout that completely encompasses the oscillator pins. With fine-pitch packages, it is not always possible to completely surround the pins and components. A suitable solution is to tie the broken guard sections to a mirrored ground layer. In all cases, the guard trace(s) must be returned to ground.

Figure 4-3. Suggested Placement of the Oscillator Circuit



#### Fine-Pitch (Dual-Sided) Layouts:



In planning the application's routing and I/O assignments, ensure that adjacent PORT pins, and other signals in close proximity to the oscillator, are benign (i.e., free of high frequencies, short rise and fall times, and other similar noise).

For additional information and design guidance on oscillator circuits, refer to these Microchip Application Notes, available at the corporate website (www.microchip.com):

- AN826, "Crystal Oscillator Basics and Crystal Selection for rfPIC™ and PICmicro® Devices"
- AN849, "Basic PICmicro<sup>®</sup> Oscillator Design"
- AN943, "Practical PICmicro<sup>®</sup> Oscillator Analysis and Design"
- AN949, "Making Your Oscillator Work"

## 4.6 Unused I/Os

Unused I/O pins should be configured as outputs and driven to a logic low state. Alternatively, connect a 1 k $\Omega$  to 10 k $\Omega$  resistor to V<sub>SS</sub> on unused pins to drive the output to logic low.

# 5. Register and Bit Naming Conventions

### 5.1 Register Names

When there are multiple instances of the same peripheral in a device, the Peripheral Control registers will be depicted as the concatenation of a peripheral identifier, peripheral instance, and control identifier. The control registers section will show just one instance of all the register names with an 'x' in the place of the peripheral instance number. This naming convention may also be applied to peripherals when there is only one instance of that peripheral in the device to maintain compatibility with other devices in the family that contain more than one.

#### 5.2 Bit Names

There are two variants for bit names:

- · Short name: Bit function abbreviation
- · Long name: Peripheral abbreviation + short name

#### 5.2.1 Short Bit Names

Short bit names are an abbreviation for the bit function. For example, some peripherals are enabled with the EN bit. The bit names shown in the registers are the short name variant.

Short bit names are useful when accessing bits in C programs. The general format for accessing bits by the short name is RegisterNamebits.ShortName. For example, the enable bit, ON, in the ADCON0 register can be set in C programs with the instruction ADCON0bits.ON = 1.

Short names are generally not useful in assembly programs because the same name may be used by different peripherals in different bit positions. When this occurs, during the include file generation, all instances of that short bit name are appended with an underscore plus the name of the register in which the bit resides to avoid naming contentions.

#### 5.2.2 Long Bit Names

Long bit names are constructed by adding a peripheral abbreviation prefix to the short name. The prefix is unique to the peripheral, thereby making every long bit name unique. The long bit name for the ADC enable bit is the ADC prefix, AD, appended with the enable bit short name, ON, resulting in the unique bit name ADON.

Long bit names are useful in both C and assembly programs. For example, in C the ADCON0 enable bit can be set with the ADON = 1 instruction. In assembly, this bit can be set with the BSF ADCON0, ADON instruction.

#### 5.2.3 Bit Fields

Bit fields are two or more adjacent bits in the same register. Bit fields adhere only to the short bit naming convention. For example, the three Least Significant bit of the ADCON2 register contain the ADC Operating Mode Selection bit. The short name for this field is MD and the long name is ADMD. Bit field access is only possible in C programs. The following example demonstrates a C program instruction for setting the ADC to operate in Accumulate mode:

```
ADCON2bits.MD = 0b001;
```

Individual bits in a bit field can also be accessed with long and short bit names. Each bit is the field name appended with the number of the bit position within the field. For example, the Most Significant mode bit has the short bit name MD2 and the long bit name is ADMD2. The following two examples demonstrate assembly program sequences for setting the ADC to operate in Accumulate mode:

```
MOVLW ~(1<<MD2 | 1<<MD1)
ANDWF ADCON2,F
```

1< <md0 ADCON2,F</md0 		
ADCON2, ADMD2 ADCON2, ADMD1 ADCON2, ADMD0		

# 5.3 Register and Bit Naming Exceptions

## 5.3.1 Status, Interrupt, and Mirror Bits

Status, Interrupt enables, Interrupt flags, and Mirror bits are contained in registers that span more than one peripheral. In these cases, the bit name shown is unique so there is no prefix or short name variant.

# 6. Register Legend

Table 6-1. Register Legend


Symbol	Definition
R	Readable bit
W	Writable bit
HS	Hardware settable bit
НС	Hardware clearable bit
S	Set only bit
С	Clear only bit
U	Unimplemented bit, read as '0'
'1'	Bit value is set
<b>'</b> 0'	Bit value is cleared
X	Bit value is unknown
u	Bit value is unchanged
q	Bit value depends on condition
m	Bit value is predefined

## PIC18 CPU

This family of devices contains a PIC18 8-bit CPU core based on the modified Harvard architecture. The PIC18 CPU supports:

- · System arbitration which decides memory access allocation depending on user priorities
- · Vectored interrupt capability with automatic two-level deep context saving
- · 127-level deep hardware stack with overflow and underflow Reset capabilities
- · Support Direct, Indirect, and Relative Addressing modes
- 8x8 hardware multiplier

Figure 7-1. Family Block Diagram



# 7.1 System Arbitration


The system arbiter resolves memory access between the system level selections (i.e., Main, Interrupt Service Routine) and peripheral selection (e.g., DMA and Scanner) based on user-assigned priorities. A block diagram of the system arbiter can be found below. Each of the system level and peripheral selections has its own priority selection registers. Memory access priority is resolved using the number written to the corresponding Priority registers, 0 being the highest priority selection and the maximum value being the lowest priority. All system level and peripheral level

selections default to the lowest priority configuration. If the same value is in two or more Priority registers, priority is given to the higher-listed selection according to the following table.

**Table 7-1. Default Priorities** 

Selection		Priority Register Reset Value
System Level	ISR	7
	MAIN	7
Peripheral	DMA1	7
	DMA2	7
	DMA3	7
	DMA4	7
	DMA5	7
	DMA6	7
	SCANNER	7

Figure 7-2. System Arbiter Block Diagram



#### 7.1.1 Priority Lock

The system arbiter grants memory access to the peripheral selections (DMAx, Scanner) as long as the PRLOCKED bit is set. Priority selections are locked by setting the PRLOCKED bit. Setting and clearing this bit requires a special sequence as an extra precaution against inadvertent changes. The following code examples demonstrate the Priority Lock and Priority Unlock sequences.

```
Example 7-1. Priority Lock Sequence

INTCONObits.GIE = 0; // Disable Interrupts;

PRLOCK = 0x55;

PRLOCK = 0xAA;
```

```
PRLOCKbits.PRLOCKED = 1;  // Grant memory access to peripherals;
INTCONObits.GIE = 1;  // Enable Interrupts;

Example 7-2. Priority Unlock Sequence

INTCONObits.GIE = 0;  // Disable Interrupts;
PRLOCK = 0x55;
PRLOCK = 0xAA;
PRLOCKbits.PRLOCKED = 0;  // Allow changing priority settings;
INTCONObits.GIE = 1;  // Enable Interrupts;
```

# 7.2 Memory Access Scheme

The user can assign priorities to both system level and peripheral selections based on which the system arbiter grants memory access. Let us consider the following priority scenarios between ISR, MAIN and peripherals.

#### 7.2.1 ISR Priority > Main Priority > Peripheral Priority

When the peripheral priority (e.g., DMA, Scanner) is lower than ISR and MAIN priority, and the peripheral requires:

- Access to the Program Flash Memory, then the peripheral waits for an instruction cycle in which the CPU does
  not need to access the PFM (such as a branch instruction) and uses that cycle to do its own Program Flash
  Memory access, unless a PFM Read/Write operation is in progress.
- 2. Access to the SFR/GPR, then the peripheral waits for an instruction cycle in which the CPU does not need to access the SFR/GPR (such as MOVLW, CALL, NOP) and uses that cycle to do its own SFR/GPR access.
- 3. Access to the Data EEPROM, then the peripheral has access to Data EEPROM unless a Data EEPROM Read/Write operation is being performed.

This results in the lowest throughput for the peripheral to access the memory, and does so without any impact on execution times.

#### 7.2.2 Peripheral Priority > ISR Priority > Main Priority

When the peripheral priority (DMA, Scanner) is higher than ISR and MAIN priority, the CPU operation is stalled when the peripheral requests memory. The CPU is held in its current state until the peripheral completes its operation. This results in the highest throughput for the peripheral to access the memory, but has the cost of stalling other execution while it occurs.

#### 7.2.3 ISR Priority > Peripheral Priority > Main Priority

In this case, interrupt routines and peripheral operation (DMAx, Scanner) will stall the Main loop. Interrupt will preempt peripheral operation, which results in lowest interrupt latency.

#### 7.2.4 Peripheral 1 Priority > ISR Priority > Main Priority > Peripheral 2 Priority

In this case, the Peripheral 1 will stall the execution of the CPU. However, Peripheral 2 can access the memory in cycles unused by Peripheral 1, ISR and the Main Routine.

### 7.3 8x8 Hardware Multiplier

This device includes an 8x8 hardware multiplier as part of the ALU within the CPU. The multiplier performs an unsigned operation and yields a 16-bit result that is stored in the product register, PROD. The multiplier's operation does not affect any flags in the STATUS register.

Making multiplication a hardware operation allows it to be completed in a single instruction cycle. This has the advantages of higher computational throughput and reduced code size for multiplication algorithms and allows the device to be used in many applications previously reserved for digital signal processors. A comparison of various hardware and software multiply operations, along with the savings in memory and execution time, is shown in Table 7-2.

Table 7-2. Performance Comparison for Various Multiply Operations

B	M 10: 1 N 11: 1	Program	Cycles	Time			
Routine	Multiply Method	Memory (Words)	(Max)	@ 64 MHz	@ 40 MHz	@ 10 MHz	@ 4 MHz
8x8 unsigned	Without hardware multiply	13	69	4.3 µs	6.9 µs	27.6 µs	69 µs
oxo urisigiled	Hardware multiply	1	1	62.5 ns	100 ns	400 ns	1 µs
8x8 signed	Without hardware multiply	33	91	5.7 µs	9.1 µs	36.4 µs	91 µs
oxo signed	Hardware multiply	6	6	375 ns	600 ns	2.4 µs	6 µs
16v16 ungianed	Without hardware multiply	21	242	15.1 µs	24.2 µs	96.8 µs	242 µs
16x16 unsigned	Hardware multiply	28	28	1.8 µs	2.8 µs	11.2 µs	28 µs
16v16 signed	Without hardware multiply	52	254	15.9 µs	25.4 µs	102.6 µs	254 µs
16x16 signed	Hardware multiply	35	40	2.5 µs	4.0 µs	16.0 µs	40 µs

### 7.3.1 Operation

Example 7-3 shows the instruction sequence for an 8x8 unsigned multiplication. Only one instruction is required when one of the arguments is already loaded in the WREG register. Example 7-4 shows the sequence to do an 8x8 signed multiplication. To account for the sign bits of the arguments, each argument's Most Significant bit (MSb) is tested and the appropriate subtractions are done.

```
Example 7-3. 8x8 Unsigned Multiply Routine

MOVF ARG1, W ;

MULWF ARG2 ; ARG1 * ARG2 -> PRODH: PRODL
```

```
Example 7-4. 8x8 Signed Multiply Routine
                   ARG1, W
          MOVE
                               ; ARG1 * ARG2 -> PRODH: PRODL
          MULWF
                   ARG2
                   ARG2, SB ; Test Sign Bit
PRODH, F ; PRODH = PRODH - ARG1
          BTFSC
          SUBWF
          MOVF
                   ARG2, W
          BTFSC
                   ARG1, SB
                               ; Test Sign Bit
          SUBWF
                   PRODH, F
                                ; PRODH = PRODH - ARG2
```

#### 7.3.2 16x16 Unsigned Multiplication Algorithm

Example 7-6 shows the sequence to do a 16x16 unsigned multiplication. Example 7-5 shows the algorithm that is used. The 32-bit result is stored in four registers.

```
Example 7-5. 16x16 Unsigned Multiply Algorithm

RES3:RES0 = ARG1H:ARG1L \bullet ARG2H:ARG2L = \left(ARG1H \bullet ARG2H \bullet 2^{16}\right) + \left(ARG1H \bullet ARG2L \bullet 2^{8}\right) + \left(ARG1L \bullet ARG2H \bullet 2^{8}\right) + \left(ARG1L \bullet ARG2L\right)
```

```
Example 7-6. 16x16 Unsigned Multiply Routine

MOVF ARG1L, W
MULWF ARG2L ; ARG1L * ARG2L → PRODH: PRODL
MOVFF PRODH, RES1 ;
```

```
MOVFF
        PRODL, RESO
MOVE
        ARG1H, W
                        ; ARG1H * ARG2H → PRODH: PRODL
MULWF
        ARG2H
MOVFF
        PRODH, RES3
MOVFF
        PRODL, RES2
MOVE
        ARG1L, W
                        : ARG1L * ARG2H → PRODH: PRODL
MULWF
        ARG2H
MOVE
        PRODL, W
ADDWF
        RES1, F
                        ; Add cross products
MOVF
        PRODH, W
ADDWFC RES2, F
CLRF
        WREG
ADDWFC
       RES3, F
MOVE
        ARG1H, W
                        ; ARG1H * ARG2L → PRODH:PRODL
MULWF
        ARG2L
MOVF
        PRODL, W
ADDWF
        RES1, F
                        ; Add cross products
MOVF
        PRODH, W
ADDWFC RES2, F
CLRF
        WREG
ADDWFC RES3, F
```

#### 7.3.3 16x16 Signed Multiplication Algorithm

Example 7-8 shows the sequence to do a 16x16 signed multiply. Example 7-7 shows the algorithm used. The 32-bit result is stored in four registers. To account for the sign bits of the arguments, the MSb for each argument pair is tested and the appropriate subtractions are done.

```
Example 7-7. 16x16 Signed Multiply Algorithm RES3:RES0 = ARG1H:ARG1L \bullet ARG2H:ARG2L = \left(ARG1H \bullet ARG2H \bullet 2^{16}\right) + \left(ARG1H \bullet ARG2L \bullet 2^{8}\right) + \left(ARG1L \bullet ARG2H \bullet 2^{8}\right) + \left(ARG1L \bullet ARG2H \bullet 2^{8}\right) + \left(ARG1L \bullet ARG2H \bullet 2^{16}\right) + \left(-1 \bullet ARG2H < 7 > \bullet ARG1H:ARG1L \bullet 2^{16}\right) + \left(-1 \bullet ARG1H < 7 > \bullet ARG2H:ARG2L \bullet 2^{16}\right)
```

```
Example 7-8. 16x16 Signed Multiply Routine
                 ARG1L, W
         MOVE
         MULW
                 ARG2L
                                  ; ARG1L * ARG2L → PRODH:PRODL
         MOVE
                 PRODH, RES1
                PRODL, RESO
         MOVFF
         MOVE
                 ARG1H. W
         MULWF
                 ARG2H
                                  ; ARG1H * ARG2H → PRODH: PRODL
                 PRODH, RES3
         MOVFF
                 PRODL, RES2
         MOVFF
         MOVF
                 ARG1L, W
         MULWF
                 ARG2H
                                  ; ARG1L * ARG2H → PRODH:PRODL
                 PRODL, W
         MOVF
                 RES1, F
         ADDWF
                                  ; Add cross products
         MOVF
                 PRODH, W
         ADDWFC
                RES2, F
         CLRF
                 WREG
         ADDWFC RES3, F
         MOVE
                 ARG1H, W
         MULWF
                 ARG2L
                                  : ARG1H * ARG2L → PRODH: PRODL
         MOVF
                 PRODL, W
         ADDWF
                 RES1, F
                                  ; Add cross products
         MOVE
                 PRODH, W
         ADDWFC RES2, F
         CLRF
                 WREG
         ADDWFC RES3, F
```

```
BTFSS
                 ARG2H, 7
                                    ARG2H: ARG2L neg?
                 SIGN ARG1
        BRA
                                     no, check ARG1
        MOVE
                 ARG1L, W
        SUBWE
                 RES2
        MOVE
                 ARG1H. W
        SUBWFB
                 RES3
SIGN_ARG1:
        BTFSS
                 ARG1H, 7
                                   : ARG1H: ARG1L neg?
                 CONT CODE
        BRA
                                   ; no, done
        MOVE
                 ARG2L. W
        SUBWE
                 RES2
        MOVE
                 ARG2H, W
        SUBWFB
                 RES3
CONT CODE:
```


# 7.4 PIC18 Instruction Cycle

#### 7.4.1 Instruction Flow/Pipelining

An "Instruction Cycle" consists of four cycles of the oscillator clock. The instruction fetch and execute are pipelined in such a manner that a fetch takes one instruction cycle, while the decode and execute take another instruction cycle. However, due to the pipelining, each instruction effectively executes in one cycle. If an instruction causes the Program Counter (PC) to change (e.g., GOTO), then two cycles are required to complete the instruction (Figure 7-3).

A fetch cycle begins with the Program Counter (PC) incrementing followed by the execution cycle. In the execution cycle, the fetched instruction is latched into the Instruction Register (IR). This instruction is then decoded and executed during the next few oscillator clock cycles. Data memory is read (operand read) and written (destination write) during the execution cycle as well.

Figure 7-3. Instruction Pipeline Flow



**Note:** There are some instructions that take multiple cycles to execute. Refer to the "**Instruction Set Summary**" section for details.

#### 7.4.2 Instructions in Program Memory

The program memory is addressed in bytes. Instructions are stored as either two bytes, four bytes, or six bytes in program memory. The Least Significant Byte of an instruction word is always stored in a program memory location with an even address (LSb = 0). To maintain alignment with instruction boundaries, the PC increments in steps of two and the LSb will always read '0'. See the "**Program Counter**" section in the "**Memory Organization**" chapter for more details. The instructions in the Program Memory figure below shows how instruction words are stored in the program memory.

The CALL and GOTO instructions have the absolute program memory address embedded into the instruction. Since instructions are always stored on word boundaries, the data contained in the instruction is a word address. The word address is written to the corresponding bits of the Program Counter register, which accesses the desired byte address in program memory. Instruction #2 in the example shows how the instruction GOTO 0006h is encoded in the

Word Address

000000h
000002h
000004h
000006h
000008h
00000Ch
00000Ch
000010h
000012h
000014h
000018h
000018h
000018h

program memory. Program branch instructions, which encode a relative address offset, operate in the same manner. The offset value stored in a branch instruction represents the number of single-word instructions that the PC will be offset by.

Figure 7-4. Instructions in Program Memory

			LSB = 1	LSB = (
	Program Me	,		
	Byte Location	ons		
Instruction 1:	MOVLW	055h	0Fh	55h
Instruction 2:	GOTO	0006h	EFh	03h
			F0h	00h
Instruction 3:	MOVFF	123h, 456h	C1h	23h
			F4h	56h
Instruction 4:	MOVFFL	123h, 456h	00h	60h
			F4h	8Ch
			F4h	56h

#### 7.4.3 Multi-Word Instructions

The standard PIC18 instruction set has six two-word instructions: CALL, MOVFF, GOTO, LFSR, MOVSF and MOVSS and two three-word instructions: MOVFFL and MOVSFL. In all cases, the second and the third word of the instruction always has 1111 as its four Most Significant bits; the other 12 bits are literal data, usually a data memory address.

The use of 1111 in the four MSbs of an instruction specifies a special form of NOP. If the instruction is executed in proper sequence, immediately after the first word, the data in the second word is accessed and used by the instruction sequence. If the first word is skipped for some reason and the second word is executed by itself, a NOP is executed instead. This is necessary for cases when the two-word instruction is preceded by a conditional instruction that changes the PC.

Table 7-3 and Table 7-4 show more details of how two-word instructions work. Table 7-5 and Table 7-6 show more details of how three-word instructions work.



Important: See the "PIC18 Instruction Execution and the Extended Instruction Set" section for information on two-word instructions in the extended instruction set.

Table 7-3. Two-Word Instructions (Case 1)

Object Code	Source Code	Comment
0110 0110 0000 0000	TSTFSZ REG1	; is RAM location 0?
1100 0001 0101 0011	MOVFF REG1, REG2	; No, skip this word
1111 0100 0101 0110		; Execute this word as NOP
0010 0100 0000 0000	ADDWF REG3	; continue code

Table 7-4. Two-Word Instructions (Case 2)

Object Code	Source Code	Comment
0110 0110 0000 0000	TSTFSZ REG1	; is RAM location 0?
1100 0001 0101 0011	MOVFF REG1, REG2	; Yes, execute this word

continued			
Object Code	Source Code	Comment	
1111 0100 0101 0110		; 2nd word of instruction	
0010 0100 0000 0000	ADDWF REG3	; continue code	

#### Table 7-5. Three-Word Instructions (Case 1)

Object Code	Source Code	Comment
0110 0110 0000 0000	TSTFSZ REG1	; is RAM location 0?
0000 0000 0110 0000	MOVFFL REG1, REG2	; Yes, skip this word
1111 0100 1000 1100		; Execute this word as NOP
1111 0100 0101 0110		; Execute this word as NOP
0010 0100 0000 0000	ADDWF REG3	; continue code

#### Table 7-6. Three-Word Instructions (Case 2)

Object Code	Source Code	Comment
0110 0110 0000 0000	TSTFSZ REG1	; is RAM location 0?
0000 0000 0110 0000	MOVFFL REG1, REG2	; No, execute this word
1111 0100 1000 1100		; 2nd word of instruction
1111 0100 0101 0110		; 3rd word of instruction
0010 0100 0000 0000	ADDWF REG3	; continue code

# 7.5 STATUS Register

The STATUS register contains the arithmetic status of the ALU. As with any other SFR, it can be the operand for any instruction. If the STATUS register is the destination for an instruction that affects the Z, DC, C, OV or N bits, the results of the instruction are not written; instead, the STATUS register is updated according to the instruction performed. Therefore, the result of an instruction with the STATUS register as its destination may be different than intended. As an example, CLRF STATUS will set the Z bit and leave the remaining Status bits unchanged ('000u u1uu').

It is recommended that only BCF, BSF, SWAPF, MOVFF and MOVWF instructions are used to alter the STATUS register, because these instructions do not affect the Z, C, DC, OV or N bits in the STATUS register. For other instructions that do not affect Status bits, see the instruction set summaries.



Important: The C and DC bits operate as the Borrow and Digit Borrow bits, respectively, in subtraction.

# 7.6 Call Shadow Register

When CALL instruction is used, the WREG, BSR and STATUS are automatically saved in hardware and can be accessed using the WREG CSHAD, BSR CSHAD and STATUS CSHAD registers.



### Important:

The contents of these registers should be handled correctly to avoid erroneous code execution.

7.7 Register Definitions: System Arbiter

## 7.7.1 ISRPR

Name: ISRPR Offset: 0x0BF

Interrupt Service Routine Priority Register



Bits 2:0 - PR[2:0] Interrupt Service Routine Priority Selection

Value	Description
111	System Arbiter Priority Level: 7 (Lowest Priority)
110	System Arbiter Priority Level: 6
101	System Arbiter Priority Level: 5
100	System Arbiter Priority Level: 4
011	System Arbiter Priority Level: 3
010	System Arbiter Priority Level: 2
001	System Arbiter Priority Level: 1
000	System Arbiter Priority Level: 0 (Highest Priority)

PIC18 CPU

# 7.7.2 MAINPR

Name: MAINPR Offset: 0x0BE

Main Routine Priority Register



Bits 2:0 - PR[2:0] Main Routine Priority Selection


Value	Description
111	System Arbiter Priority Level: 7 (Lowest Priority)
110	System Arbiter Priority Level: 6
101	System Arbiter Priority Level: 5
100	System Arbiter Priority Level: 4
011	System Arbiter Priority Level: 3
010	System Arbiter Priority Level: 2
001	System Arbiter Priority Level: 1
000	System Arbiter Priority Level: 0 (Highest Priority)

# 7.7.3 DMAxPR

Name: DMAxPR

**Offset:** 0x0B6,0x0B7,0x0B8,0x0B9,0x0BA,0x0BB,0x0BC,0x0BD

**DMAx Priority Register** 



Bits 2:0 - PR[2:0] DMAx Priority Selection

Value	Description
111	System Arbiter Priority Level: 7 (Lowest Priority)
110	System Arbiter Priority Level: 6
101	System Arbiter Priority Level: 5
100	System Arbiter Priority Level: 4
011	System Arbiter Priority Level: 3
010	System Arbiter Priority Level: 2
001	System Arbiter Priority Level: 1
000	System Arbiter Priority Level: 0 (Highest Priority)

# 7.7.4 SCANPR

Name: SCANPR Offset: 0x0B5

Scanner Priority Register



Bits 2:0 - PR[2:0] Scanner Priority Selection

Value	Description
111	System Arbiter Priority Level: 7 (Lowest Priority)
110	System Arbiter Priority Level: 6
101	System Arbiter Priority Level: 5
100	System Arbiter Priority Level: 4
011	System Arbiter Priority Level: 3
010	System Arbiter Priority Level: 2
001	System Arbiter Priority Level: 1
000	System Arbiter Priority Level: 0 (Highest Priority)

### 7.7.5 PRLOCK

Name: PRLOCK Offset: 0x0B4

Priority Lock Register



#### Bit 0 - PRLOCKED PR Register Lock

Value	Description
1	Priority registers are locked and cannot be written; Peripherals do not have access to the memory
0	Priority registers can be modified by write operations; Peripherals do not have access to the memory



### Important:

- 1. The PRLOCKED bit can only be set or cleared after the unlock sequence.
- 2. If the Configuration Bit PR1WAY = 1, the PRLOCKED bit cannot be cleared after it has been set. A device Reset will clear the bit and allow one more set.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 40

### 7.7.6 PROD

Name: PROD Offset: 0x4F3

Timer Register Product Register Pair

Bit	15	14	13	12	11	10	9	8
	PROD[15:8]							
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
				PROI	D[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	X	X	X	X	X	X	X	X

Bits 15:0 - PROD[15:0] PROD Most Significant

Notes: The individual bytes in this multi-byte register can be accessed with the following register names:

- PRODH: Accesses the high byte PROD[15:8]
- PRODL: Accesses the low byte PROD[7:0]

### **7.7.7 STATUS**

Name: STATUS Offset: 0x4D8

STATUS Register

Bit	7	6	5	4	3	2	1	0
		TO	PD	N	OV	Z	DC	С
Access		R	R	R/W	R/W	R/W	R/W	R/W
Reset		1	1	0	0	0	0	0

### Bit 6 - TO Time-Out

Reset States: POR/BOR = 1

All Other Resets = q

	• 1
Value	Description
1	Set at power-up or by execution of CLRWDT or SLEEP instruction
0	A WDT Time-out occurred

### Bit 5 - PD Power-Down

Reset States: POR/BOR = 1

All Other Resets = a

	• 1
Value	Description
1	Set at power-up or by execution of CLRWDT instruction
0	Cleared by execution of the SLEEP instruction

#### Bit 4 - N Negative

Used for signed arithmetic (two's complement); indicates if the result is negative,

(ALU MSb = 1).

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	The result is negative
0	The result is positive

### Bit 3 - OV Overflow

Used for signed arithmetic (two's complement); indicates an overflow of the 7-bit magnitude, which causes the sign

bit (bit 7) to change state.

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	Overflow occurred for current signed arithmetic operation
0	No overflow occurred

## Bit 2 - Z Zero

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	The result of an arithmetic or logic operation is zero
0	The result of an arithmetic or logic operation is not zero

### Bit 1 - DC Digit Carry / Borrow

ADDWF, ADDLW, SUBLW, SUBWF instructions(1)

Reset States: POR/BOR = 0 All Other Resets = u

Value	Description
1	A carry-out from the 4th low-order bit of the result occurred

Value	Description
0	No carry-out from the 4th low-order bit of the result

## Bit 0 - C Carry / Borrow

ADDWF, ADDLW, SUBLW, SUBWF instructions(1,2)

Reset States: POR/BOR = 0 All Other Resets = u

Value	Description
1	A carry-out from the Most Significant bit of the result occurred
0	No carry-out from the Most Significant bit of the result occurred

#### Notes:

- 1. For Borrow, the polarity is reversed. A subtraction is executed by adding the two's complement of the second operand.
- 2. For Rotate (RRCF, RLCF) instructions, this bit is loaded with either the high or low-order bit of the Source register.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 43

# 7.8 Register Summary - System Arbiter Control

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0	
0x00											
 0xB3	Reserved										
0xB4	PRLOCK	7:0								PRLOCKED	
0xB5	SCANPR	7:0							PR[2:0]		
0xB6	DMA1PR	7:0							PR[2:0]		
0xB7	DMA2PR	7:0							PR[2:0]		
0xB8	DMA3PR	7:0							PR[2:0]		
0xB9	DMA4PR	7:0							PR[2:0]		
0xBA	DMA5PR	7:0							PR[2:0]		
0xBB	DMA6PR	7:0							PR[2:0]		
0xBC	DMA7PR	7:0							PR[2:0]		
0xBD	DMA8PR	7:0							PR[2:0]		
0xBE	MAINPR	7:0							PR[2:0]		
0xBF	ISRPR	7:0							PR[2:0]		
0xC0											
	Reserved										
0x0372											
0x0373	STATUS_CSHAD	7:0		ТО	PD	N	OV	Z	DC	С	
0x0374	WREG_CSHAD	7:0				WRE	G[7:0]				
0x0375	BSR_CSHAD	7:0					BSF	R[5:0]			
0x0376	Reserved										
0x0377	STATUS_SHAD	7:0		ТО	PD	N	OV	Z	DC	С	
0x0378	WREG_SHAD	7:0				WRE	G[7:0]				
0x0379	BSR_SHAD	7:0					BSF	R[5:0]			
0x037A	Reserved										
0x037B	PCLAT_SHAD	7:0		PCLATH[7:0]							
	I OLAI_OHAD	15:8		PCLATU[4:0]							
0x037D	FSR0_SHAD	7:0		FSRL[7:0]							
onco. B		15:8						H[5:0]			
0x037F	FSR1_SHAD	7:0				FSR	L[7:0]				
UNIO I		15:8		FSRH[5:0]							
0x0381	FSR2_SHAD	7:0				FSR	L[7:0]				
5,,0001		15:8						H[5:0]			
0x0383	PROD_SHAD	7:0		PROD[7:0]							
		15:8		ı		PROI	D[15:8]				
0x0385											
	Reserved										
0x04D7				==				_			
0x04D8	STATUS	7:0		TO	PD	N	OV	Z	DC	С	
0x04D9	D 1										
	Reserved										
0x04F2		7.0				P.P.O	D17 01				
0x04F3	PROD	7:0					D[7:0]				
		15:8				PROL	D[15:8]				

# 8. Device Configuration

## 8.1 Configuration Settings

The Configuration settings allow the user to setup the device with several choices of oscillators, Resets and memory protection options. These are implemented at 30 0000h - 30 0022h.



**Important:** The DEBUG Configuration bit is managed automatically by device development tools including debuggers and programmers. For normal device operation, this bit should be maintained as a '1'.

### 8.2 Code Protection

Code protection allows the device to be protected from unauthorized access. Internal access to the program memory is unaffected by any code protection setting. A single code protect bit controls the access for both program memory and data EEPROM memory.

The entire program memory and Data EEPROM space is protected from external reads and writes by the  $\overline{CP}$  bit. When  $\overline{CP}$  = 0, external reads and writes are inhibited and a read will return all '0's. The CPU can continue to read the memory, regardless of the protection bit settings. Self-writing the program memory is dependent upon the write protection setting.

### 8.3 User ID

32 words in the memory space (20 0000h - 20 003Fh) are designated as ID locations where the user can store checksum or other code identification numbers. These locations are readable and writable during normal execution. See the "User ID, Device ID and Configuration Settings Access, DIA and DCI" section for more information on accessing these memory locations. For more information on checksum calculation, see the "PIC18FXXQ84 Family Programming Specification", (DS-40002137).

### 8.4 Device ID and Revision ID

The 16-bit device ID word is located at 0x3FFFFE and the 16-bit revision ID is located at 0x3FFFFC. These locations are read-only and cannot be erased or modified.

Development tools, such as device programmers and debuggers, may be used to read the Device ID, Revision ID and Configuration bits. Refer to the "NVM - Nonvolatile Memory Module" section for more information on accessing these locations.

# 8.5 Register Definitions: Configuration Words

## 8.5.1 **CONFIG1**

Name: CONFIG1 Offset: 30 0000h

Configuration Byte 1

Bit	7	6	5	4	3	2	1	0
			RSTOSC[2:0]				FEXTOSC[2:0]	
Access		R/W	R/W	R/W		R/W	R/W	R/W
Reset		1	1	1		1	1	1

## Bits 6:4 - RSTOSC[2:0] Power-up Default Value for COSC

This value is the Reset default value for COSC and selects the oscillator first used by user software. Refer to the COSC operation.

Value	Description
111	EXTOSC operating per FEXTOSC bits
110	HFINTOSC with HFFRQ = 4 MHz and CDIV = 4:1. Resets COSC/NOSC to b'110'.
101	LFINTOSC
100	SOSC
011	Reserved
010	EXTOSC with 4x PLL, with EXTOSC operating per FEXTOSC bits
001	Reserved
000	HFINTOSC with HFFRQ = 64 MHz and CDIV = 1:1. Resets COSC/NOSC to b'110'.

# Bits 2:0 - FEXTOSC[2:0] External Oscillator Mode Selection

Value	Description
111	ECH (external clock) above 8 MHz
110	ECM (external clock) for 500 kHz to 8 MHz
101	ECL (external clock) below 500 kHz
100	Oscillator not enabled
011	Reserved (do not use)
010	HS (crystal oscillator) above 4 MHz
001	XT (crystal oscillator) above 500 kHz, below 4 MHz
000	LP (crystal oscillator) optimized for 32.768 kHz

### 8.5.2 **CONFIG2**

Name: CONFIG2 Offset: 30 0001h

Configuration Byte 2

Bit	7	6	5	4	3	2	1	0
	FCMENS	FCMENP	FCMEN	JTAGEN	CSWEN		PR1WAY	CLKOUTEN
Access	R/W	R/W	R/W	R/W	R/W		R/W	R/W
Reset	1	1	1	1	1		1	1

#### Bit 7 - FCMENS Fail-Safe Clock Monitor Enable for Secondary Crystal Oscillator Enable

Value	Description
1	Fail-Safe Clock Monitor enabled for Secondary Crystal, Fail-Safe timer will set the FSCMS bit and
	trigger OSFIF interrupt on secondary crystal failure
0	Fail-Safe Clock Monitor disabled for Secondary Crystal

### Bit 6 - FCMENP Fail-Safe Clock Monitor Enable for Primary Crystal Oscillator

Value	Description
1	Fail-Safe Clock Monitor enabled for Primary Crystal Oscillator, Fail-Safe timer will set FSCMP bit and
	trigger OSFIF interrupt on primary crystal failure
0	Fail-Safe Clock Monitor disabled for Primary Crystal Oscillator

#### Bit 5 - FCMEN Fail-Safe Clock Monitor Enable for FOSC

Value	Description
1	Fail-Safe Clock Monitor enabled, Fail-Safe timer will initiate a clock switch and trigger OSFIF interrupt
	on FOSC failure
0	Fail-Safe Clock Monitor disabled

### Bit 4 - JTAGEN JTAG Boundary Scan Enable

Value	Description
1	Enable JTAG Boundary Scan mode and pins
0	Disable JTAG Boundary Scan mode, JTAG pins revert to user functions

#### Bit 3 - CSWEN Clock Switch Enable

Value	Description
1	Writing to NOSC and NDIV is allowed
0	The NOSC and NDIV bits cannot be changed by user software

#### Bit 1 - PR1WAY PRLOCKED One-Way Set Enable

Value	Description
1	The PRLOCKED bit can be cleared and set only once; Priority registers remain locked after one clear/set cycle
0	The PRLOCKED bit can be set and cleared repeatedly (subject to the unlock sequence)

## Bit 0 - CLKOUTEN Clock Out Enable

If FEXTOSC = HS, XT, LP, then this bit is ignored.

Otherwise:

Value	Description
1	CLKOUT function is disabled; I/O function on OSC2
0	CLKOUT function is enabled; F <sub>OSC</sub> /4 clock appears at OSC2

### 8.5.3 **CONFIG3**

Name: CONFIG3 Offset: 30 0002h

Configuration Byte 3

Bit	7	6	5	4	3	2	1	0
	BOREN[1:0]		LPBOREN	IVT1WAY	MVECEN	PWRT	S[1:0]	MCLRE
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	1	1	1	1	1	1

## Bits 7:6 - BOREN[1:0] Brown-out Reset Enable

When enabled, Brown-out Reset Voltage (V<sub>BOR</sub>) is set by the BORV bit.

Value	Description
11	Brown-out Reset enabled, SBOREN bit is ignored
10	Brown-out Reset enabled while running, disabled in Sleep; SBOREN is ignored
01	Brown-out Reset enabled according to SBOREN
00	Brown-out Reset disabled

### Bit 5 - **LPBOREN** Low-Power BOR Enable

Value	Description
1	Low-Power Brown-out Reset is disabled
0	Low-Power Brown-out Reset is enabled

# Bit 4 - IVT1WAY IVTLOCK One-Way Set Enable

7	/alue	Description
-	_	IVTLOCK bit can be cleared and set only once; IVT registers remain locked after one clear/set cycle
(	)	IVTLOCK bit can be set and cleared repeatedly (subject to the unlock sequence)

#### Bit 3 - MVECEN Multivector Enable

Value	Description
1	Multivector is enabled; vector table used for interrupts
0	Legacy interrupt behavior

### Bits 2:1 - PWRTS[1:0] Power-up Timer Selection

Value	Description
11	PWRT is disabled
10	PWRT is set at 64 ms
01	PWRT is set at 16 ms
00	PWRT is set at 1 ms

## Bit 0 - MCLRE Master Clear (MCLR) Enable

Value	Condition	Description
X	If LVP = 1	RA3 pin function is MCLR
1	If LVP = 0	MCLR pin is MCLR
0	If LVP = 0	MCLR pin function is a port-defined function

### 8.5.4 **CONFIG4**

Name: CONFIG4 Offset: 30 0003h

Configuration Byte 4

Bit	7	6	5	4	3	2	1	0
	XINST		LVP	STVREN	PPS1WAY	ZCD	BOR	V[1:0]
Access	R/W		R/W	R/W	R/W	R/W	R/W	R/W
Reset	1		1	1	1	1	1	1

#### Bit 7 - XINST Extended Instruction Set Enable

Value	Description
1	Extended Instruction Set and Indexed Addressing mode disabled (Legacy mode)
0	Extended Instruction Set and Indexed Addressing mode enabled

#### Bit 5 - LVP Low-Voltage Programming Enable

The LVP bit cannot be written (to zero) while operating from the LVP programming interface. The purpose of this rule is to prevent the user from dropping out of LVP mode while programming from LVP mode, or accidentally eliminating LVP mode from the Configuration state.

Value	Description
1	Low-Voltage Programming enabled. MCLR/V <sub>PP</sub> pin function is MCLR. MCLRE Configuration bit is
	ignored.
0	HV on MCLR/V <sub>PP</sub> must be used for programming

#### Bit 4 - STVREN Stack Overflow/Underflow Reset Enable

	<b>V</b> alue	Description
-	1	Stack Overflow or Underflow will cause a Reset
(	)	Stack Overflow or Underflow will not cause a Reset

#### Bit 3 - PPS1WAY PPSLOCKED One-Way Set Enable

Value	Description
1	The PPSLOCKED bit can only be set once after an unlocking sequence is executed; once PPSLOCK
	is set, all future changes to PPS registers are prevented
0	The PPSLOCKED bit can be set and cleared as needed (unlocking sequence is required)

## Bit 2 - ZCD ZCD Disable

Value	Description
1	ZCD disabled, ZCD can be enabled by setting the ZCDSEN bit of ZCDCON
0	ZCD always enabled, PMDx[ZCDMD] bit is ignored

#### Bits 1:0 - BORV[1:0] Brown-out Reset Voltage Selection(1)

Value	Description
11	Brown-out Reset Voltage (V <sub>BOR</sub> ) set to 1.90V
10	Brown-out Reset Voltage (V <sub>BOR</sub> ) set to 2.45V
01	Brown-out Reset Voltage (V <sub>BOR</sub> ) set to 2.7V
00	Brown-out Reset Voltage (V <sub>BOR</sub> ) set to 2.85V

#### Note:

1. The higher voltage setting is recommended for operation at or above 16 MHz.

# 8.5.5 **CONFIG5**

Name: CONFIG5 Offset: 30 0004h

Configuration Byte 5

Bit	7	6	5	4	3	2	1	0
		WDT	E[1:0]			WDTCPS[4:0]		
Access		R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset		0	0	1	1	1	1	1

Bits 6:5 - WDTE[1:0] WDT Operating Mode

Value	Description
11	WDT enabled regardless of Sleep; the SEN bit in WDTCON0 is ignored
10	WDT enabled while Sleep = 0, suspended when Sleep = 1; the SEN bit in WDTCON0 is ignored
01	WDT enabled/disabled by the SEN bit in WDTCON0
00	WDT disabled, the SEN bit in WDTCON0 is ignored

## Bits 4:0 - WDTCPS[4:0] WDT Period Select

WDTCON0[WDTPS] at POR							
WDTCPS	Value	Divider Ratio		Typical Time Out (F <sub>IN</sub> = 31 kHz)	Software Control of WDTPS?		
11111	01011	1:65536	2 <sup>16</sup>	2s	Yes		
11110 to 10011	11110 to 10011	1:32	2 <sup>5</sup>	1 ms	No		
10010	10010	1:8388608	2 <sup>23</sup>	256s	No		
10001	10001	1:4194304	222	128s	No		
10000	10000	1:2097152	2 <sup>21</sup>	64s	No		
01111	01111	1:1048576	2 <sup>20</sup>	32s	No		
01110	01110	1:524288	2 <sup>19</sup>	16s	No		
01101	01101	1:262144	2 <sup>18</sup>	8s	No		
01100	01100	1:131072	2 <sup>17</sup>	4s	No		
01011	01011	1:65536	2 <sup>16</sup>	2s	No		
01010	01010	1:32768	2 <sup>15</sup>	1s	No		
01001	01001	1:16384	2 <sup>14</sup>	512 ms	No		
01000	01000	1:8192	2 <sup>13</sup>	256 ms	No		
00111	00111	1:4096	2 <sup>12</sup>	128 ms	No		
00110	00110	1:2048	2 <sup>11</sup>	64 ms	No		
00101	00101	1:1024	2 <sup>10</sup>	32 ms	No		
00100	00100	1:512	2 <sup>9</sup>	16 ms	No		
00011	00011	1:256	28	8 ms	No		
00010	00010	1:128	27	4 ms	No		
00001	00001	1:64	2 <sup>6</sup>	2 ms	No		
00000	00000	1:32	2 <sup>5</sup>	1 ms	No		

# 8.5.6 **CONFIG6**

Name: CONFIG6 Offset: 30 0005h

Configuration Byte 6

Bit	7	6	5	4	3	2	1	0
				WDTCCS[2:0]			WDTCWS[2:0]	
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			1	1	1	1	1	1

Bits 5:3 - WDTCCS[2:0] WDT Input Clock Selector

		.put olocit
Value	Condition	Description
Х	<b>WDTE =</b> 00	These bits have no effect
111	WDTE ≠ 00	Software control
110 to	WDTE ≠ 00	Reserved
011		
010	WDTE ≠ 00	WDT reference clock is the SOSC
001	WDTE ≠ 00	WDT reference clock is the 31.25 kHz MFINTOSC
000	WDTE ≠ 00	WDT reference clock is the 31.0 kHz LFINTOSC

# Bits 2:0 - WDTCWS[2:0] WDT Window Select

		WDTCON1[WINDO	W] at POR	Software Control of	Koyod Aggasa	
WDTCWS	Value	Window Delay Percent of Time	Window Opening Percent of Time	WINDOW	Keyed Access Required?	
111	111	n/a	100	Yes	No	
110	110	n/a	100			
101	101	25	75			
100	100	37.5	62.5			
011	011	50	50	No	Yes	
010	010	62.5	37.5			
001	001	75	25			
000	000	87.5	12.5			

### 8.5.7 **CONFIG7**

Name: CONFIG7 Offset: 30 0006h

Configuration Byte 7

Bit	7	6	5	4	3	2	1	0
			DEBUG	SAFEN	BBEN		BBSIZE[2:0]	
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			1	1	1	1	1	1

### Bit 5 - DEBUG Debugger Enable

Value	Description
1	Background debugger disabled
0	Background debugger enabled

## Bit 4 - SAFEN Storage Area Flash (SAF) Enable(1)

Value	Description
1	SAF is disabled
0	SAF is enabled

### Bit 3 - BBEN Boot Block Enable(1)

Vá	alue	Description	
1		Boot Block is disabled	
0		Boot Block is enabled	

## Bits 2:0 - BBSIZE[2:0] Boot Block Size Selection(2)

#### Table 8-1. Boot Block Size

BBEN	BBSIZE	End Address of	Boot Block Size (words)		
DDEN			PIC18Fx6Q83/Q84	PIC18Fx7Q83/Q84	
1	XXX	_	-	_	
0	111	00 03FFh	5′	12	
0	110	00 07FFh	1024		
0	101	00 0FFFh	2048		
0	100	00 1FFFh	4096		
0	011	00 3FFFh	8192		
0	010	00 7FFFh	16384		
0	001	00 FFFFh	- 32768		
0	000	01 FFFFh	-		

#### Notes:

- Once protection is enabled through ICSP<sup>™</sup> or a self-write, it can only be reset through a Bulk Erase.
- 2. BBSIZE[2:0] bits can only be changed when BBEN = 1. Once BBEN = 0, BBSIZE[2:0] can only be changed through a Bulk Erase.

### 8.5.8 **CONFIG8**

Name: CONFIG8 Offset: 30 0007h

Configuration Byte 8

Bit	7	6	5	4	3	2	1	0
	WRTAPP				WRTSAF	WRTD	WRTC	WRTB
Access	R/W				R/W	R/W	R/W	R/W
Reset	1				1	1	1	1

## Bit 7 - WRTAPP Application Block Write Protection<sup>(1)</sup>

Value	Description	
1	Application Block is NOT write-protected	
0	Application Block is write-protected	

### Bit 3 – WRTSAF Storage Area Flash (SAF) Write Protection<sup>(1,2)</sup>

Value Description		Description
	1	SAF is NOT write-protected
	0	SAF is write-protected

### Bit 2 - WRTD Data EEPROM Write Protection(1)

Value	Description
1	Data EEPROM is NOT write-protected
0	Data EEPROM is write-protected

# Bit 1 – WRTC Configuration Register Write Protection<sup>(1)</sup>

Value	Description
1	Configuration registers are NOT write-protected
0	Configuration registers are write-protected

### Bit 0 - WRTB Boot Block Write Protection(1,3)

Value Description	
1	Boot Block is NOT write-protected
0	Boot Block is write-protected

#### Notes:

- 1. Once protection is enabled through ICSP<sup>™</sup> or a self-write, it can only be reset through a Bulk Erase.
- 2. Applicable only if  $\overline{SAFEN} = 0$ .
- 3. Applicable only if  $\overline{BBEN} = 0$ .

# 8.5.9 **CONFIG9**

Name: CONFIG9 Offset: 30 0008h

Configuration Byte 9

Bit	7	6	5	4	3	2	1	0
			ODCON	BPEN			BOOTPI	NSEL[1:0]
Access			R/W	R/W			R/W	R/W
Reset			1	1			1	1

# Bit 5 – ODCON CRC-on-Boot Pin Open-Drain Configuration

Value	Description
1	CRC-on-boot output drives both high-going and low-going signals (source and sink current)
0	CRC-on-boot output drives only low-going signals (sink current only)

## Bit 4 - BPEN CRC-on-Boot Output Pin Enable

Value Description		Description
	1	CRC-on-boot output pin disabled
	0	CRC-on-boot output pin determined by BOOTPINSEL[1:0]


## Bits 1:0 - BOOTPINSEL[1:0] CRC-on-Boot Pin Select

Value	Description
11	CRC-on-boot output pin is RC5
10	CRC-on-boot output pin is RC4
01	CRC-on-boot output pin is RA2
00	CRC-on-boot output pin is RA4

## 8.5.10 CONFIG10

Name: CONFIG10 Offset: 30 0009h

Configuration Byte 10



Bit 0 –  $\overline{\text{CP}}$  User Program Flash Memory and Data EEPROM Code Protection<sup>(1)</sup>

Va	lue	Description
1		User Program Flash Memory and Data EEPROM code protection are disabled
0		User Program Flash Memory and Data EEPROM code protection are enabled

### Note:

1. Once this bit is enabled, it can only be reset through a Bulk Erase.

### 8.5.11 CONFIG11

Name: CONFIG11 Offset: 30 000Ah

Configuration Byte 11

Bit	7	6	5	4	3	2	1	0
	BOOTPOR	COE	CFGSCEN	DATSCEN	SAFSCEN	APPSCEN	BOOTCOE	BOOTSCEN
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

### Bit 7 - BOOTPOR CRC-on-Boot Enable

Value	Description
1	CRC-on-boot disabled, device will immediately execute user code upon device Reset
0	CRC-on-boot enabled, device will perform CRC check of configured memory before executing user
	code upon device Reset

### Bit 6 - COE Continue on Error for Non-Boot Block Areas Enable

Value	Description					
1	Device will halt if a mismatch is found between expected and calculated CRC values for the non-boot					
	block areas of memory					
0	Device will continue execution even if a mismatch is found between expected and calculated CRC					
	values for the non-boot block areas of memory					

### Bit 5 - CFGSCEN Non-Boot Block Area CRC Configuration Fuse Scan Enable

Value	Description
1	Non-boot block area CRC scan/calculation will not include Configuration Fuse values in its calculation
0	Non-boot block area CRC scan/calculation will include all Configuration Fuse values except
	CONFIG14H-CONFIG16L in its calculation

## Bit 4 - DATSCEN Non-Boot Block Area CRC Data EEPROM Scan Enable

Value	Description
1	Non-boot block area CRC scan/calculation will not include Data EEPROM values in its calculation
0	Non-boot block area CRC scan/calculation will include Data EEPROM values in its calculation

#### Bit 3 - SAFSCEN Non-Boot Block Area CRC SAF Area Scan Enable

Value	Description
1	Non-boot block area CRC scan/calculation will not include SAF area of Flash memory in its calculation if SAF area is enabled
0	Non-boot block area CRC scan/calculation will include SAF area of Flash memory in its calculation if SAF area is enabled

### Bit 2 – APPSCEN Non-Boot Block Area CRC Application Code Area Scan Enable

Value	Description
1	Non-boot block area CRC scan/calculation will not include main application code area of Flash memory
	in its calculations
0	Non-boot block area CRC scan/calculation will include main application code area of Flash memory in
	its calculations

### Bit 1 - BOOTCOE Continue on Error for Boot Block Areas Enable

Value	Description
1	Device will halt if a mismatch is found between expected and calculated CRC values for the boot block
	areas of memory
0	Device will continue execution even if a mismatch is found between expected and calculated CRC
	values for the boot block areas of memory

# PIC18F26/46/56Q84

# **Device Configuration**

## Bit 0 - BOOTSCEN Boot Block Area CRC Scan Enable

V	alue	Description
1		CRC Scan/calculation on boot block area will not be run
0		CRC Scan/calculation on boot block area will be run

# 8.5.12 CRC Boot Polynomial

Name: CRC Boot Polynomial

**Offset:** 30 000Bh

The Polynomial for the CRC of the boot block segment of memory

**Note:** The CRC-on-boot module uses a 32-bit polynomial, as such the polynomial configuration spans from CONFIG12 to CONFIG15, with the MSB of CONFIG12 being the XOR of polynomial term  $X^{31}$  and the LSB of CONFIG15 being the XOR of polynomial term  $X^{0}$ .

Bit	31	30	29	28	27	26	25	24		
	BCRCPOL[31:24]									
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	1	1	1	1	1	1	1	1		
Bit	23	22	21	20	19	18	17	16		
				BCRCPC	DL[23:16]					
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	1	1	1	1	1	1	1	1		
Bit	15	14	13	12	11	10	9	8		
				BCRCP	OL[15:8]					
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	1	1	1	1	1	1	1	1		
Bit	7	6	5	4	3	2	1	0		
	BCRCPOL[7:0]									
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	1	1	1	1	1	1	1	1		

Bits 31:0 - BCRCPOL[31:0] XOR of Polynomial Term X<sup>n</sup> Enable bits

### 8.5.13 CRC Boot Seed

Name: CRC Boot Seed Offset: 30 000Fh

The Seed for the CRC of the boot block segment of memory

**Note:** The CRC-on-boot module uses a 32-bit polynomial, as such the boot block seed spans from CONFIG16 to CONFIG19, with the MSB of CONFIG16 being the MSB of the seed and the LSB of CONFIG19 being the LSB of the seed.

Bit	31	30	29	28	27	26	25	24
				BCRCSE	ED[31:24]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1
Bit	23	22	21	20	19	18	17	16
				BCRCSE	ED[23:16]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1
Bit	15	14	13	12	11	10	9	8
				BCRCSE	ED[15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1
Bit	7	6	5	4	3	2	1	0
				BCRCSI	EED[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

Bits 31:0 - BCRCSEED[31:0] Boot Block CRC Seed Field

# 8.5.14 CRC Boot Expected Value

Name: CRC Boot Expected Value

Offset: 30 0013h

The Expected Value for the CRC of the boot block segment of memory

**Note:** The CRC-on-boot module uses a 32-bit polynomial, as such the expected value spans from CONFIG20 to CONFIG23, with the MSB of CONFIG20 being the MSB of the expected value, and the LSB of CONFIG23 being the LSB of the expected value.

Bit	31	30	29	28	27	26	25	24
				BCRCER	ES[31:24]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1
Bit	23	22	21	20	19	18	17	16
				BCRCER	ES[23:16]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1
Bit	15	14	13	12	11	10	9	8
				BCRCEF	RES[15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1
Bit	7	6	5	4	3	2	1	0
				BCRCEI	RES[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

Bits 31:0 - BCRCERES[31:0] Boot Block Area CRC Expected Result

# 8.5.15 CRC Polynomial

Name: CRC Polynomial Offset: 30 0017h

The Polynomial for the CRC of the non-boot block segments of memory

**Note:** The CRC-on-boot module uses a 32-bit polynomial, as such the polynomial configuration spans from CONFIG24 to CONFIG27, with the MSB of CONFIG24 being the XOR of polynomial term  $X^{31}$  and the LSB of CONFIG27 being the XOR of polynomial term  $X^{0}$ .

Bit	31	30	29	28	27	26	25	24
				CRCPO	L[31:24]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1
Bit	23	22	21	20	19	18	17	16
				CRCPO	L[23:16]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1
Bit	15	14	13	12	11	10	9	8
				CRCPC	DL[15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1
Bit	7	6	5	4	3	2	1	0
				CRCP	OL[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

Bits 31:0 – CRCPOL[31:0] XOR of Polynomial Term X<sup>n</sup> Enable bits

### 8.5.16 CRC Seed

Name: CRC Seed Offset: 30 001Bh

The Seed for the CRC of the non-boot block segments of memory

**Note:** The CRC-on-boot module uses a 32-bit polynomial, as such the seed spans from CONFIG28 to CONFIG31, with the MSB of CONFIG28 being the MSB of the seed and the LSB of CONFIG31 being the LSB of the seed.

Bit	31	30	29	28	27	26	25	24
				CRCSEE	D[31:24]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1
Bit	23	22	21	20	19	18	17	16
				CRCSEE	ED[23:16]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1
Bit	15	14	13	12	11	10	9	8
				CRCSE	ED[15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1
Bit	7	6	5	4	3	2	1	0
				CRCSE	ED[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

Bits 31:0 - CRCSEED[31:0] Non-Boot Block Area CRC Seed Field

# 8.5.17 CRC Expected Value

Name: CRC Expected Value

**Offset:** 30 001Fh

The Expected Value for the CRC of the non-boot block segments of memory

**Note:** The CRC-on-boot module uses a 32-bit polynomial, as such the expected value spans from CONFIG32 to CONFIG35, with the MSB of CONFIG32 being the MSB of the expected value, and the LSB of CONFIG35 being the LSB of the expected value.

Bit	31	30	29	28	27	26	25	24	
				CRCERE	S[31:24]				
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	1	1	1	1	1	1	1	1	
Bit	23	22	21	20	19	18	17	16	
				CRCERE	S[23:16]				
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	1	1	1	1	1	1	1	1	
Bit	15	14	13	12	11	10	9	8	
				CRCER	ES[15:8]				
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	1	1	1	1	1	1	1	1	
Bit	7	6	5	4	3	2	1	0	
	CRCERES[7:0]								
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	1	1	1	1	1	1	1	1	

Bits 31:0 - CRCERES[31:0] Non-Boot Block Area CRC Expected Result

# 8.6 Register Summary - Configuration Settings

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0	
00											
	Reserved										
2FFFFF											
300000	CONFIG1	7:0			RSTOSC[2:0]	-			FEXTOSC[2:0	]	
300001	CONFIG2	7:0	FCMENS	FCMENP	FCMEN	JTAGEN	CSWEN		PR1WAY	CLKOUTEN	
300002	CONFIG3	7:0	BORE	BOREN[1:0] LPBOREN IVT1WAY MVECEN PWRTS[1:0]					ΓS[1:0]	MCLRE	
300003	CONFIG4	7:0	XINST		LVP	STVREN	PPS1WAY	ZCD	BOR	V[1:0]	
300004	CONFIG5	7:0		WDT	E[1:0]		•	WDTCPS[4:0]			
300005	CONFIG6	7:0				WDTCCS[2:0]			WDTCWS[2:0	]	
300006	CONFIG7	7:0			DEBUG	SAFEN	BBEN		BBSIZE[2:0]		
300007	CONFIG8	7:0	WRTAPP				WRTSAF	WRTD	WRTC	WRTB	
300008	CONFIG9	7:0			ODCON	BPEN			BOOTPI	NSEL[1:0]	
300009	CONFIG10	7:0								CP	
30000A30 000A	CONFIG11	7:0	BOOTPOR	COE	CFGSCEN	DATSCEN	SAFSCEN	APPSCEN	воотсое	BOOTSCEN	
		7:0				BCRCF	OL[7:0]				
30000B30	CRC Boot	15:8				BCRCP	OL[15:8]				
000B	Polynomial	23:16				BCRCPC	DL[23:16]				
		31:24				BCRCPC	DL[31:24]				
		7:0	BCRCSEED[7:0]								
30000F30	CRC Boot Seed	15:8	BCRCSEED[15:8]								
000F	CRC Boot Seed	23:16				BCRCSE	ED[23:16]				
		31:24				BCRCSE	ED[31:24]				
		7:0				BCRCE	RES[7:0]				
30001330	CRC Boot Expected	15:8				BCRCEF	RES[15:8]				
0013	Value	23:16				BCRCER	ES[23:16]				
		31:24				BCRCER	ES[31:24]				
		7:0				CRCP	OL[7:0]				
30001730	ODO Dalamanaial	15:8				CRCPC	DL[15:8]				
0017	CRC Polynomial	23:16				CRCPO	L[23:16]				
		31:24				CRCPO	L[31:24]				
		7:0					ED[7:0]				
30001B30	0000	15:8	5:8 CRCSEED[15:8]								
001B	CRC Seed	23:16					D[23:16]				
		31:24	CRCSEED[31:24]								
		7:0	CRCERES[7:0]								
30001F30	CRC Expected	15:8					ES[15:8]				
001F	Value	23:16				CRCERE	ES[23:16]				
		31:24					ES[31:24]				

# 8.7 Register Definitions: Device ID and Revision ID

# 8.7.1 Device ID

Name: DEVICEID Ox3FFFFE

Device ID Register

Bit	15	14	13	12	11	10	9	8
				DEV	[15:8]			
Access	R	R	R	R	R	R	R	R
Reset	q	q	q	q	q	q	q	q
Bit	7	6	5	4	3	2	1	0
				DEV	<b>/</b> [7:0]			
Access	R	R	R	R	R	R	R	R
Reset	q	q	q	q	q	q	q	q

# Bits 15:0 - DEV[15:0] Device ID

Device	Device ID
PIC18F26Q84	A300h
PIC18F46Q84	A301h
PIC18F56Q84	A302h

#### 8.7.2 **Revision ID**

Name: **REVISIONID** Offset: 0x3FFFFC

Revision ID Register

Bit	15	14	13	12	11	10	9	8	
		1010	0[3:0]		MJRREV[5:2]				
Access	R	R	R	R	RO	RO	RO	RO	
Reset	1	0	1	0	q	q	q	q	
Bit	7	6	5	4	3	2	1	0	
	MJRREV[1:0] MNRREV[5:0]								
Access	RO	RO	RO	RO	RO	RO	RO	RO	
Reset	q	q	q	q	q	q	q	q	

#### Bits 15:12 - 1010[3:0] Read as 'b1010

These bits are fixed with value 'b1010 for all devices in this family.

## Bits 11:6 - MJRREV[5:0] Major Revision ID

These bits are used to identify a major revision (A0, B0, C0, etc.).

**Revision A = '**b00 0000 Revision B = 'b00 0001

### Bits 5:0 - MNRREV[5:0] Minor Revision ID

These bits are used to identify a minor revision.

Revision A0 = 'b00 0000 Revision B0 = 'b00 0000 **Revision B1 = '**b00 0001



Tip: For example, the REVISIONID register value for revision B1 will be 0xA041.

# 8.8 Register Summary - DEVID/REVID

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x3FFFFB										
0x3FFFFC	REVISIONID	7:0	MJRRI	EV[1:0]			MNRR	EV[5:0]		
UXSFFFFC	REVISIONID	15:8		1010	[3:0]			MJRR	EV[5:2]	
0x3FFFFE DEVICEID 7:0 DEV[7:0]										
UXSFFFFE	DEVICEID	15:8				DEV	[15:8]			

# 9. Memory Organization

There are three types of memory in PIC18 microcontroller devices:

- · Program Memory
- · Data RAM
- Data EEPROM

In Harvard architecture devices, the data and program memories use separate buses that allow for concurrent access of the two memory spaces. The data EEPROM, for practical purposes, can be regarded as a peripheral device, since it is addressed and accessed through a set of control registers.

Additional detailed information on the operation of the Program Flash Memory and data EEPROM memory is provided in the "NVM - Nonvolatile Memory Module" section.

# 9.1 Program Memory Organization

PIC18 microcontrollers implement a 21-bit Program Counter, which is capable of addressing a 2 Mbyte program memory space. Accessing a location between the upper boundary of the physically implemented memory and the 2 Mbyte address will return all '0's (a NOP instruction).

Refer to the following tables for device memory maps and code protection Configuration bits associated with the various sections of PFM.

The Reset vector address is at 000000h. The PIC18-Q84 devices feature a vectored interrupt controller with a dedicated interrupt vector table stored in the program memory. Refer to the "VIC - Vectored Interrupt Controller Module" chapter for more details.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 68

Figure 9-1. Program and Data Memory Map

Rev. 40-000101 4/20/20

	Dev	/ice						
Address	PIC18Fx6Q84	PIC18Fx7Q84						
00 0000h								
to								
00 3FFFh								
00 4000h	Program Flash							
to	Memory	Program Flash						
00 7FFFh	(32 KW) <sup>(1)</sup>	Memory						
00 8000h		(64 KW) <sup>(1)</sup>						
to 00 FFFFh		, , ,						
01 0000h								
to 01 FFFFh	Not							
	Present <sup>(2)</sup>							
02 0000h to	riesent	Not						
1F FFFFh		Present <sup>(2)</sup>						
20 0000h								
to	User IDs (3	2 Words) <sup>(3)</sup>						
20 001Fh		·						
20 0020h								
to	Rese	erved						
2B FFFFh 2C 0000h								
to	Device Information	on Area (DIA) <sup>(3)(5)</sup>						
2C 00FFh	201100 1111011111111	5, u.o.a (2)						
2C 0100h								
to	Rese	erved						
2F FFFFh 30 0000h								
to	Configuration	on Words <sup>(3)</sup>						
30 0022h	Comgulation	on words						
30 0023h								
to	Rese	erved						
37 FFFFh								
38 0000h to	Data EEPROM	1 (1024 Bytes)						
38 03FFh	Data LEI NON	(1024 Dytes)						
38 0400h								
to	Rese	erved						
3B FFFFh								
3C 0000h		(3)(4)(5)						
to	Device Configuration Information <sup>(3)(4)(5)</sup>							
3C 000Ah 3C 000Bh								
to	Reserved							
3F FFFBh	Neserveu							
3F FFFCh								
to	Revision ID (1 Word) <sup>(3)(4)(5)</sup>							
3F FFFDh		Novision 15 (1 Word)						
3F FFFEh		NA / IN (3)(4)(5)						
to 2E EEEEh	Device ID (1	Word) <sup>(3)(4)(5)</sup>						
3F FFFFh								

Note 1: Storage Area Flash is implemented as the last 128 Words of User Flash, if enabled.

- 2: The addresses do not roll over. The region is read as '0'.
- **3:** Not code-protected.
- 4: Hard-coded in silicon.
- 5: This region cannot be written by the user and it's not affected by a Bulk Erase.

## 9.1.1 Memory Access Partition

In the PIC18-Q84 devices, the program memory can be further partitioned into the following sub-blocks:

- Application block
- · Boot block
- · Storage Area Flash (SAF) block

Refer to the Program Flash Memory Partition table for more details.

#### 9.1.1.1 Application Block

Application block is where the user's firmware resides by default. Default settings of the Configuration bits ( $\overline{BBEN} = 1$  and  $\overline{SAFEN} = 1$ ) assign all memory in the program Flash memory area to the application block. The  $\overline{WRTAPP}$  Configuration bit is used to write-protect the application block.

#### 9.1.1.2 Boot Block

Boot block is an area in program memory that is ideal for storing bootloader code. Code placed in this area can be executed by the CPU. The boot block can be write-protected, independent of the main application block. The Boot Block is enabled by the BBEN Configuration bit and size is based on the value of the BBSIZE Configuration bits. The WRTB Configuration bit is used to write-protect the Boot Block.

## 9.1.1.3 Storage Area Flash

Storage Area Flash (SAF) is the area in program memory that can be used as data storage. SAF is enabled by the SAFEN Configuration bit. If enabled, the code placed in this area cannot be executed by the CPU. The SAF block is placed at the end of memory and spans 128 Words. The WRTSAF Configuration bit is used to write-protect the Storage Area Flash.



Important: If write-protected locations are written to, memory is not changed and the WRERR bit is set.

Table 9-1. Program Flash Memory Partition

		Partition <sup>(3)</sup>						
Region	Address	BBEN = 1 SAFEN = 1	BBEN = 1 SAFEN = 0	BBEN = 0 SAFEN = 1	BBEN = 0 SAFEN = 0			
Program Flash Memory	00 0000h Last Boot Block Memory Address			Boot Block	Boot Block			
	Last Boot Block Memory Address <sup>(1)</sup> + 1 Last Program Memory Address <sup>(2)</sup> - 100h	Application Block	Application Block		Application Block			
	Last Program  Memory  Address <sup>(2)</sup> -  FEh <sup>(4)</sup> Last Program  Memory  Address <sup>(2)</sup>		Storage Area Flash Block	Application Block	Storage Area Flash Block			

#### Notes:

- Last Boot Block address is based on BBSIZE bits. Refer to the "Device Configuration" chapter for more details.
- 2. For Last Program Memory address refer the table above.
- 3. Refer to the "Device Configuration" chapter for BBEN and SAFEN bit definitions.
- 4. Storage Area Flash is implemented as the last 128 Words of user Flash memory.

#### 9.1.2 Program Counter

The Program Counter (PC) specifies the address of the instruction to fetch for execution. The PC is 21 bits wide and is contained in three separate 8-bit registers. The low byte, known as the PCL register, is both readable and writable. The high byte, or PCH register, contains the PC[15:8] bits; it is not directly readable or writable. Updates to the PCH register are performed through the PCLATH register. The upper byte is called PCU. This register contains the PC[20:16] bits; it is also not directly readable or writable. Updates to the PCU register are performed through the PCLATU register.

The contents of PCLATH and PCLATU are transferred to the Program Counter by any operation that writes PCL. Similarly, the upper two bytes of the Program Counter are transferred to PCLATH and PCLATU by an operation that reads PCL. This is useful for computed offsets to the PC (see Computed GOTO).

The PC addresses bytes in the program memory. To prevent the PC from becoming misaligned with word instructions, the Least Significant bit of PCL is fixed to a value of '0'. The PC increments by two to address sequential instructions in the program memory.

The CALL, RCALL, GOTO and program branch instructions write to the Program Counter directly. For these instructions, the contents of PCLATH and PCLATU are not transferred to the Program Counter.

#### 9.1.3 Return Address Stack

The return address stack allows any combination of up to 127 program calls and interrupts to occur. The PC is pushed onto the stack when a CALL or RCALL instruction is executed or an interrupt is Acknowledged. The PC value is pulled off the stack on a RETURN, RETLW or a RETFIE instruction. PCLATU and PCLATH are not affected by any of the RETURN or CALL instructions.

The Stack Pointer is readable and writable and the address on the top of the stack is readable and writable through the Top-of-Stack (TOS) Special File registers. Data can also be pushed to, or popped from the stack, using these registers.

A CALL type instruction causes a push onto the stack; the Stack Pointer is first incremented and the location pointed to by the Stack Pointer is written with the contents of the PC (already pointing to the instruction following the CALL). A RETURN type instruction causes a pop from the stack; the contents of the location pointed to by the STKPTR are transferred to the PC and then the Stack Pointer is decremented.


The Stack Pointer is initialized to 0x00 after all Resets.

#### 9.1.3.1 Top-of-Stack Access

Only the top of the return address stack (TOS) is readable and writable. A set of three registers, TOSU:TOSH:TOSL, hold the contents of the stack location pointed to by the STKPTR register (see Figure 9-2). This allows users to implement a software stack if necessary. After a CALL, RCALL or interrupt, the software can read the pushed value by reading the TOSU:TOSH:TOSL registers. These values can be placed on a user defined software stack. At return time, the software can return these values to TOSU:TOSH:TOSL and do a return.

The user must disable the Global Interrupt Enable (GIE) bits while accessing the stack to prevent inadvertent stack corruption.

Figure 9-2. Return Address Stack and Associated Registers



#### 9.1.3.2 Return Stack Pointer

The STKPTR register contains the Stack Pointer value. The STKOVF (Stack Overflow) Status bit and the STKUNF (Stack Underflow) Status bit can be accessed using the PCON0 register. The value of the Stack Pointer can be zero through 127. On Reset, the Stack Pointer value will be zero. The user may read and write the Stack Pointer value. After the PC is pushed onto the stack 128 times (without popping any values off the stack), the STKOVF bit is set. The STKOVF bit is cleared by software or by a POR. The action that takes place when the stack becomes full depends on the state of the STVREN (Stack Overflow Reset Enable) Configuration bit.

If STVREN is set (default), a Reset will be generated and a Stack Overflow will be indicated by the STKOVF bit. This includes CALL and CALLW instructions, as well as stacking the return address during an interrupt response. The STKOVF bit will remain set and the Stack Pointer will be set to zero.

If STVREN is cleared, the STKOVF bit will be set on the 128<sup>th</sup> push and the Stack Pointer will remain at 127 but no Reset will occur. Any additional pushes will overwrite the 127<sup>st</sup> push but the STKPTR will remain unchanged.

Setting STKOVF = 1 in software will change the bit, but will not generate a Reset.

The STKUNF bit is set when a stack pop returns a value of zero. The STKUNF bit is cleared by software or by POR. The action that takes place when the stack becomes full depends on the state of the STVREN (Stack Overflow Reset Enable) Configuration bit.

If STVREN is set (default) and the stack has been popped enough times to unload the stack, the next pop will return a value of zero to the PC, it will set the STKUNF bit and a Reset will be generated. This condition can be generated by the RETURN, RETLW and RETFIE instructions.

If STVREN is cleared, the STKUNF bit will be set, but no Reset will occur.



**Important:** Returning a value of zero to the PC on an underflow has the effect of vectoring the program to the Reset vector, where the stack conditions can be verified and appropriate actions can be taken. This is not the same as a Reset, as the contents of the SFRs are not affected.

### 9.1.3.3 PUSH and POP Instructions

Since the Top-of-Stack is readable and writable, the ability to push values onto the stack and pull values off the stack without disturbing normal program execution is a desirable feature. The PIC18 instruction set includes two instructions, PUSH and POP, that permit the TOS to be manipulated under software control. TOSU, TOSH and TOSL can be modified to place data or a return address on the stack.

The PUSH instruction places the current PC value onto the stack. This increments the Stack Pointer and loads the current PC value onto the stack.

The POP instruction discards the current TOS by decrementing the Stack Pointer. The previous value pushed onto the stack then becomes the TOS value.

# 9.1.3.4 Fast Register Stack

There are three levels of fast stack registers available - one for CALL type instructions and two for interrupts. A fast register stack is provided for the STATUS, WREG and BSR registers, to provide a "fast return" option for interrupts. It is loaded with the current value of the corresponding register when the processor vectors for an interrupt. All interrupt sources will push values into the stack registers. The values in the registers are then loaded back into their associated registers if the RETFIE, FAST instruction is used to return from the interrupt. Refer to "Call Shadow Register" section for interrupt call shadow registers.

The following example shows a source code example that uses the Fast Register Stack during a subroutine call and return.

```
Example 9-1. Fast Register Stack Code Example

CALL SUB1, FAST ;STATUS, WREG, BSR SAVED IN FAST REGISTER STACK

SUB1:

RETURN, FAST ;RESTORE VALUES SAVED IN FAST REGISTER STACK
```

# 9.1.4 Look-up Tables in Program Memory

There may be programming situations that require the creation of data structures, or look-up tables, in program memory. For PIC18 devices, look-up tables can be implemented in two ways:

- Computed GOTO
- · Table Reads

### 9.1.4.1 **Computed** GOTO

A computed GOTO is accomplished by adding an offset to the Program Counter. An example is shown in the following code example.

A look-up table can be formed with an ADDWF PCL instruction and a group of RETLW nn instructions. The W register is loaded with an offset into the table before executing a call to that table. The first instruction of the called routine is

the ADDWF PCL instruction. The next instruction executed will be one of the RETLW nn instructions that returns the value 'nn' to the calling function.

The offset value (in WREG) specifies the number of bytes that the Program Counter should advance and must be multiples of two (LSb = 0).

In this method, only one data byte may be stored in each instruction location and room on the return address stack is required.

```
Example 9-2. Computed GOTO Using an Offset Value
      RINCE
              OFFSET, W ; W must be an even number, Max OFFSET = 127
      CALL
              TABLE
      ORG
              nnOOh
                       ; 00 in LSByte ensures no addition overflow
 TABLE:
                       ; Add OFFSET to program counter
      ADDWF
              PCL
             A
      RETLW
                       ; Value @ OFFSET=0
                      ; Value @ OFFSET=1
      RETLW
              B
      RETLW
                       ; Value @ OFFSET=2
             C
```

### 9.1.4.2 Program Flash Memory Access

A more compact method of storing data in program memory allows two bytes of data to be stored in each instruction location.

Look-up table data may be stored two bytes per program word by using table reads and writes. The Table Pointer (TBLPTR) register specifies the byte address and the Table Latch (TABLAT) register contains the data that is read from or written to program memory. Data is transferred to or from program memory one byte at a time.

Table read and table write operations are discussed further in the "Table Read Operations" and "Table Write Operations" sections in the "NVM - Nonvolatile Memory Module" chapter.

### 9.2 Device Information Area

The Device Information Area (DIA) is a dedicated region in the program memory space. The DIA contains the calibration data for the internal temperature indicator module, the Microchip Unique Identifier words, and the Fixed Voltage Reference voltage readings measured in mV.

The complete DIA table is shown below, followed by a description of each region and its functionality. The data is mapped from 2C0000h to 2C003Fh. These locations are read-only and cannot be erased or modified. The data is programmed into the device during manufacturing.

**Table 9-2. Device Information Area** 

Address Range	Name of Region	Standard Device Information				
	MUI0					
	MUI1					
	MUI2					
	MUI3					
2C0000h-2C0011h	MUI4	Microchip Unique Identifier (9 Words)				
	MUI5					
	MUI6					
	MUI7					
	MUI8					
2C0012h-2C0013h	MUI9	Reserved (1 Word)				
	EUI0					
	EUI1					
	EUI2					
2C0014h-2C0023h	EUI3	Optional External Unique Identifier (8 Words)				
2000 1411-20002311	EUI4	Optional External Onique Identifier (6 Words)				
	EUI5					
	EUI6					
	EUI7					
2C0024h-2C0025h	TSLR1 <sup>(1)</sup>	$Gain = \frac{0.1C \times 256}{count} $ (low range setting)				
2C0026h-2C0027h	TSLR2 <sup>(1)</sup>	Temperature indicator ADC reading at 90°C (low range setting)				
2C0028h-2C0029h	TSLR3 <sup>(1)</sup>	Offset (low range setting)				
2C002Ah-2C002Bh	TSHR1 <sup>(2)</sup>	$Gain = \frac{0.1C \times 256}{count}$ (high range setting)				
2C002Ch-2C002Dh	TSHR2 <sup>(2)</sup>	Temperature indicator ADC reading at 90°C (high range setting)				
2C002Eh-2C002Fh	TSHR3 <sup>(2)</sup>	Offset (high range setting)				
2C0030h-2C0031h	FVRA1X	ADC FVR1 Output voltage for 1x setting (in mV)				
2C0032h-2C0033h	FVRA2X	ADC FVR1 Output Voltage for 2x setting (in mV)				
2C0034h-2C0035h	FVRA4X	ADC FVR1 Output Voltage for 4x setting (in mV)				
2C0036h-2C0037h	FVRC1X	Comparator FVR2 output voltage for 1x setting (in mV)				
2C0038h-2C0039h	FVRC2X	Comparator FVR2 output voltage for 2x setting (in mV)				
2C003Ah-2C003Bh	FVRC4X	Comparator FVR2 output voltage for 4x setting (in mV)				

continued								
Address Range	Name of Region	Standard Device Information						
2C003Ch-2C003Fh		Unassigned (2 Words)						

### Notes:

- TSLR: Address 2C0024h-2C0029h store the measurements for the low range setting of the temperature sensor at V<sub>DD</sub> = 3V, V<sub>RFF</sub>+ = 2.048V from FVR1.
- 2. TSHR: Address 2C002Ah-2C002Fh store the measurements for the high range setting of the temperature sensor at  $V_{DD}$  = 3V,  $V_{REF}$ + = 2.048V from FVR1.

### 9.2.1 Microchip Unique Identifier (MUI)

This family of devices is individually encoded during final manufacturing with a Microchip Unique Identifier (MUI). The MUI cannot be user-erased. This feature allows for manufacturing traceability of Microchip Technology devices in applications where this is required. It may also be used by the application manufacturer for a number of functions that require unverified unique identification, such as:

- · Tracking the device
- · Unique serial number

The MUI is stored in read-only locations, located between 2C0000h to 2C0013h in the DIA space. The DIA table lists the addresses of the identifier words.



**Important:** For applications that require verified unique identification, contact your Microchip Technology sales office to create a Serialized Quick Turn Programming option.

### 9.2.2 External Unique Identifier (EUI)

The EUI data is stored at locations 2C0014h-2C0023h in the program memory region. This region is an optional space for placing application specific information. The data is coded per customer requirements during manufacturing. The EUI cannot be erased by a Bulk Erase command.



**Important:** Data is stored in this address range on receiving a request from the customer. The customer may contact the local sales representative or Field Applications Engineer, and provide them the unique identifier information that is required to be stored in this region.

### 9.2.3 Standard Parameters for the Temperature Sensor

The purpose of the temperature indicator module is to provide a temperature-dependent voltage that can be measured by an analog module. The DIA table contains standard parameters for the temperature sensor for low and high range. The values are measured during test and are unique to each device. The calibration data can be used to plot the approximate sensor output voltage, V<sub>TSENSE</sub> vs. Temperature curve. The "Temperature Indicator Module" chapter explains the operation of the Temperature Indicator module and defines terms such as the low range and high range settings of the sensor.

### 9.2.4 Fixed Voltage Reference Data

The DIA stores measured FVR voltages for this device in mV for the different buffer settings of 1x, 2x or 4x at program memory locations. For more information on the FVR, refer to the "FVR - Fixed Voltage Reference" chapter.

# 9.3 Device Configuration Information

The Device Configuration Information (DCI) is a dedicated region in the program memory mapped from 3C0000h to 3C0009h. The data stored in these location is read-only and cannot be erased. Refer to the table below for the

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 76

complete DCI table address and description. The DCI holds information about the device, which is useful for programming and Bootloader applications.

The erase size is the minimum erasable unit in the PFM, expressed as rows. The total device Flash memory capacity is (Erase size \* Number of user-erasable pages).

Table 9-3. Device Configuration Information for PIC18-Q84 Devices

ADDRESS	NAME	DESCRIPTION	VAL	UNITS	
ADDRESS	NAME	DESCRIPTION	PIC18F26/46/56Q84	PIC18F27/47/57Q84	UNITS
3C0000h-3C0001h	ERSIZ	Erase page size	128	128	Words
3C0002h-3C0003h	WLSIZ	Number of write latches per row	0	0	Words
3C0004h-3C0005h	URSIZ	Number of user- erasable pages	256	512	Pages
3C0006h-3C0007h	EESIZ	Data EEPROM memory size	1024	1024	Bytes
3C0008h-3C0009h	PCNT	Pin count	28/40 <sup>(1)</sup> /48	28/40 <sup>(1)</sup> /48	Pins

### Note:

# 9.4 Data Memory Organization



**Important:** The operation of some aspects of data memory are changed when the PIC18 extended instruction set is enabled. See PIC18 Instruction Execution and the Extended Instruction Set for more information.

The data memory in PIC18 devices is implemented as static RAM. The memory space is divided into as many as 64 banks that contain 256 bytes each. The figure below shows the data memory organization for all devices in the device family.

The data memory contains Special Function Registers (SFRs) and General Purpose Registers (GPRs). The SFRs are used for control and status of the controller and peripheral functions, while GPRs are used for data storage and scratchpad operations in the user's application. Any read of an unimplemented location will read as '0'.


The value in the Bank Select Register (BSR) determines which bank is being accessed. The instruction set and architecture allow operations across all banks. The entire data memory may be accessed by Direct, Indirect or Indexed Addressing modes. Addressing modes are discussed later in this subsection.

To ensure that commonly used registers (SFRs and select GPRs) can be accessed in a single cycle, PIC18 devices implement an Access Bank. This is a virtual 256-byte memory space that provides fast access to SFRs and the top half of GPR Bank 5 without using the Bank Select Register. The Access Bank section provides a detailed description of the Access RAM.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 77

<sup>1.</sup> Pin count of 40 is also used for 44-pin part.

Figure 9-3. Data Memory Map



### 9.4.1 Bank Select Register

To rapidly access the RAM space in PIC18 devices, the memory is split using the banking scheme. This divides the memory space into contiguous banks of 256 bytes each. Depending on the instruction, each location can be addressed directly by its full address, or an 8-bit low-order address and a bank pointer.

Most instructions in the PIC18 instruction set make use of the bank pointer known as the Bank Select Register (BSR). This SFR holds the Most Significant bits of a location's address; the instruction itself includes the eight Least Significant bits. The BSR can be loaded directly by using the MOVLB instruction.

The value of the BSR indicates the bank in data memory being accessed; the eight bits in the instruction show the location in the bank and can be thought of as an offset from the bank's lower boundary. The relationship between the BSR's value and the bank division in data memory is shown in Figure 9-4.

When writing the firmware in assembly, the user must always be careful to ensure that the proper bank is selected before performing a data read or write. When using the C compiler to write the firmware, the BSR is tracked and maintained by the compiler.

While any bank can be selected, only those banks that are actually implemented can be read or written to. Writes to unimplemented banks are ignored, while reads from unimplemented banks will return '0'. Refer Figure 9-3 for a list of implemented banks.

**Data Memory** BSR<sup>(1)</sup> From Opcode 0 n 0000h 00h Bank 0 0 1 1 1 1 1 1 0 0 0 0 0 0 1 FFh 00h 0100h Bank 1 Bank Select FFh 0200h 00hBank 2 FFh 0300h Bank 3 through Bank 61 3E00h 00h Bank 62

Figure 9-4. Use of the Bank Select Register (Direct Addressing)

Note 1: The Access RAM bit of the instruction can be used to force an override of the selected bank (BSR value) to the registers of the Access Bank.

Bank 63

3F00h

3FFFh

FFh

00h

FFh

### 9.4.2 Access Bank

While the use of the BSR with an embedded 8-bit address allows users to address the entire range of data memory, it also means that the user must always ensure that the correct bank is selected. Otherwise, data may be read from or written to the wrong location. Verifying and/or changing the BSR for each read or write to data memory can become very inefficient.

To streamline access for the most commonly used data memory locations, the data memory is configured with a virtual Access Bank, which allows users to access a mapped block of memory without specifying a BSR. The Access Bank consists of the first 96 bytes of memory in Bank 5 (0500h-055Fh) and the last 160 bytes of memory in Bank 4 (0460h-04FFh). The upper half is known as the "Access RAM" and is composed of GPRs. The lower half is where the device's SFRs are mapped. These two areas are mapped contiguously as the virtual Access Bank and can be addressed in a linear fashion by an 8-bit address (see Data Memory Map).

# **Memory Organization**

The Access Bank is used by core PIC18 instructions that include the Access RAM bit (the 'a' parameter in the instruction). When 'a' is equal to '1', the instruction uses the BSR and the 8-bit address included in the opcode for the data memory address. When 'a' is '0', however, the instruction ignores the BSR and uses the Access Bank address map.

Using this "forced" addressing allows the instruction to operate on a data address in a single cycle, without updating the BSR first. Access RAM also allows for faster and more code efficient context saving and switching of variables.

The mapping of the Access Bank is slightly different when the extended instruction set is enabled (XINST Configuration bit = 1). This is discussed in more detail in the Mapping the Access Bank in Indexed Liberal Offset Mode section.

# 9.5 Data Addressing Modes



**Important:** The execution of some instructions in the core PIC18 instruction set are changed when the PIC18 extended instruction set is enabled. See Data Memory and the Extended Instruction Set for more information.

Information in the data memory space can be addressed in several ways. For most instructions, the Addressing mode is fixed. Other instructions may use up to three modes, depending on which operands are used and whether or not the extended instruction set is enabled.

The Addressing modes are:

- Inherent
- Literal
- Direct
- Indirect

An additional Addressing mode, Indexed Literal Offset, is available when the extended instruction set is enabled (XINST Configuration bit = 1). Its operation is discussed in greater detail in Indexed Addressing with Literal Offset.

### 9.5.1 Inherent and Literal Addressing

Many PIC18 control instructions do not need any argument at all; they either perform an operation that globally affects the device or they operate implicitly on one register. This Addressing mode is known as Inherent Addressing. Examples include SLEEP, RESET and DAW.

Other instructions work in a similar way but require an additional explicit argument in the opcode. This is known as Literal Addressing mode because they require some literal value as an argument. Examples include ADDLW and MOVLW, which respectively, add or move a literal value to the W register. Other examples include CALL and GOTO, which include a program memory address.

### 9.5.2 Direct Addressing

Direct Addressing specifies all or part of the source and/or destination address of the operation within the opcode itself. The options are specified by the arguments accompanying the instruction.

In the core PIC18 instruction set, bit-oriented and byte-oriented instructions use some version of Direct Addressing by default. All of these instructions include some 8-bit literal address as their Least Significant Byte. This address specifies either a register address in one of the banks of data RAM (see Data Memory Organization) or a location in the Access Bank (see Access Bank) as the data source for the instruction.

The Access RAM bit 'a' determines how the address is interpreted. When 'a' is '1', the contents of the BSR (see Bank Select Register) are used with the address to determine the complete 12-bit address of the register. When 'a' is '0', the address is interpreted as being a register in the Access Bank.

The destination of the operation's results is determined by the destination bit 'd'. When 'd' is '1', the results are stored back in the source register, overwriting its original contents. When 'd' is '0', the results are stored in the W register.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 80

Instructions without the 'd' argument have a destination that is implicit in the instruction; their destination is either the target register being operated on or the W register.

### 9.5.3 Indirect Addressing

Indirect Addressing allows the user to access a location in data memory without giving a fixed address in the instruction. This is done by using File Select Registers (FSRs) as pointers to the locations which are to be read or written. Since the FSRs are themselves located in RAM as Special File Registers, they can also be directly manipulated under program control. This makes FSRs very useful in implementing data structures, such as tables and arrays in data memory.

The registers for Indirect Addressing are also implemented with Indirect File Operands (INDFs) that permit automatic manipulation of the pointer value with auto-incrementing, auto-decrementing or offsetting with another value. This allows for efficient code, using loops, such as the following example of clearing an entire RAM bank.

#### Example 9-3. How to Clear RAM (Bank 1) Using Indirect Addressing LFSR FSR0,100h ; Set FSR0 to beginning of Bank1 NEXT: CLRF POSTINCO ; Clear location in Bank1 then increment FSR0 BTFSS FSROH,1 ; Has high FSRO byte incremented to next bank? ; NO, clear next byte in Bank1 BRA NEXT CONTINUE: ; YES, continue

### 9.5.3.1 FSR Registers and the INDF Operand

At the core of Indirect Addressing are three sets of registers: FSR0, FSR1 and FSR2. Each represent a pair of 8-bit registers, FSRnH and FSRnL. Each FSR pair holds the full address of the RAM location. The FSR value can address the entire range of the data memory in a linear fashion. The FSR register pairs, then, serve as pointers to data memory locations.

Indirect Addressing is accomplished with a set of Indirect File Operands, INDF0 through INDF2. These can be thought of as "virtual" registers; they are mapped in the SFR space but are not physically implemented. Reading or writing to a particular INDF register actually accesses its corresponding FSR register pair. A read from INDF1, for example, reads the data at the address indicated by FSR1H:FSR1L. Instructions that use the INDF registers as operands actually use the contents of their corresponding FSR as a pointer to the instruction's target. The INDF operand is just a convenient way of using the pointer.

Because Indirect Addressing uses a full address, the FSR value can target any location in any bank regardless of the BSR value. However, the Access RAM bit must be cleared to zero to ensure that the INDF register in Access space is the object of the operation instead of a register in one of the other banks. The assembler default value for the Access RAM bit is zero when targeting any of the indirect operands.

# 9.5.3.2 FSR Registers and POSTINC, POSTDEC, PREINC and PLUSW

In addition to the INDF operand, each FSR register pair also has four additional indirect operands. Like INDF, these are "virtual" registers that cannot be directly read or written. Accessing these registers actually accesses the location to which the associated FSR register pair points, and also performs a specific action on the FSR value. They are:

- POSTDEC: accesses the location to which the FSR points, then automatically decrements the FSR by 1
  afterwards
- POSTINC: accesses the location to which the FSR points, then automatically increments the FSR by 1 afterwards
- PREINC: automatically increments the FSR by one, then uses the location to which the FSR points in the operation
- PLUSW: adds the signed value of the W register (range of -127 to 128) to that of the FSR and uses the location to which the result points in the operation.


In this context, accessing an INDF register uses the value in the associated FSR register without changing it. Similarly, accessing a PLUSW register gives the FSR value an offset by that in the W register; however, neither W nor the FSR is actually changed in the operation. Accessing the other virtual registers changes the value of the FSR register.

Figure 9-5. Indirect Addressing

Using an instruction with one of the indirect addressing registers as the operand....

...uses the 14-bit address stored in the FSR pair associated with that register....

...to determine the data memory location to be used in that operation. In this case, the FSR1 pair contains 3ECCh. This means the contents of location 3ECCh will be added to that of the W register and stored back in 3ECCh.



Operations on the FSRs with POSTDEC, POSTINC and PREINC affect the entire register pair; that is, rollovers of the FSRnL register from FFh to 00h carry over to the FSRnH register. On the other hand, results of these operations do not change the value of any flags in the STATUS register (e.g., Z, N, OV, etc.).

The PLUSW register can be used to implement a form of Indexed Addressing in the data memory space. By manipulating the value in the W register, users can reach addresses that are fixed offsets from pointer addresses. In some applications, this can be used to implement some powerful program control structure, such as software stacks, inside of data memory.

# 9.5.3.3 Operations by FSRs on FSRs

Indirect Addressing operations that target other FSRs or virtual registers represent special cases. For example, using an FSR to point to one of the virtual registers will not result in successful operations. As a specific case, assume that FSR0H:FSR0L contains the address of INDF1. Attempts to read the value of the INDF1 using INDF0 as an operand will return 00h. Attempts to write to INDF1 using INDF0 as the operand will result in a NOP.

On the other hand, using the virtual registers to write to an FSR pair may not occur as planned. In these cases, the value will be written to the FSR pair but without any incrementing or decrementing. Thus, writing to either the INDF2 or POSTDEC2 register will write the same value to the FSR2H:FSR2L.

Since the FSRs are physical registers mapped in the SFR space, they can be manipulated through all direct operations. Users should proceed cautiously when working on these registers, particularly if their code uses Indirect Addressing.

Similarly, operations by Indirect Addressing are generally permitted on all other SFRs. Users should exercise the appropriate caution that they do not inadvertently change settings that might affect the operation of the device.

# 9.6 Data Memory and the Extended Instruction Set

Enabling the PIC18 extended instruction set ( $\overline{\text{XINST}}$  Configuration bit = 1) significantly changes certain aspects of data memory and its addressing. Specifically, the use of the Access Bank for many of the core PIC18 instructions is different; this is due to the introduction of a new Addressing mode for the data memory space.

What does not change is just as important. The size of the data memory space is unchanged, as well as its linear addressing. The SFR map remains the same. Core PIC18 instructions can still operate in both Direct and Indirect

Addressing mode; inherent and literal instructions do not change at all. Indirect addressing with FSR0 and FSR1 also remain unchanged.

### 9.6.1 Indexed Addressing with Literal Offset

Enabling the PIC18 extended instruction set changes the behavior of Indirect Addressing using the FSR2 register pair within Access RAM. Under the proper conditions, instructions that use the Access Bank – that is, most bitoriented and byte-oriented instructions – can invoke a form of Indexed Addressing using an offset specified in the instruction. This special Addressing mode is known as Indexed Addressing with Literal Offset, or Indexed Literal Offset mode.

When using the extended instruction set, this Addressing mode requires the following:

- The use of the Access Bank is forced ('a' = 0) and
- · The file address argument is less than or equal to 5Fh.

Under these conditions, the file address of the instruction is not interpreted as the lower byte of an address (used with the BSR in Direct Addressing), or as an 8-bit address in the Access Bank. Instead, the value is interpreted as an offset value to an Address Pointer, specified by FSR2. The offset and the contents of FSR2 are added to obtain the target address of the operation.

### 9.6.2 Instructions Affected by Indexed Literal Offset Mode

Any of the core PIC18 instructions that can use Direct Addressing are potentially affected by the Indexed Literal Offset Addressing mode. This includes all byte-oriented and bit-oriented instructions, or almost one-half of the standard PIC18 instruction set. Instructions that only use Inherent or Literal Addressing modes are unaffected.

Additionally, byte-oriented and bit-oriented instructions are not affected if they do not use the Access Bank (Access RAM bit is '1'), or include a file address of 60h or above. Instructions meeting these criteria will continue to execute as before. A comparison of the different possible Addressing modes when the extended instruction set is enabled is shown in the following figure.

Those who desire to use byte-oriented or bit-oriented instructions in the Indexed Literal Offset mode should note the changes to assembler syntax for this mode. This is described in more detail in the "Extended Instruction Syntax" section.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 83

Figure 9-6. Comparing Addressing Options for Bit-Oriented and Byte-Oriented Instructions (Extended Instruction Set Enabled)

**EXAMPLE INSTRUCTION:** ADDWF, f, d, a (Opcode: 0010 01da ffff ffff)

### When 'a' = 0 and f ≥ 60h

The instruction executes in Direct Forced mode. 'f is interpreted as a location in the Access RAM between 060h and 0FFh. This is the same as locations 460h to 4FFh (Bank4) of data memory. Locations below 60h are not available in this addressing mode.


### 

### When 'a' = 0 and $f \le 5Fh$

The instruction executes in Indexed Literal Offset mode. 'f' is interpreted as an offset to the address value in FSR2. The two are added together to obtain the address of the target register for the instruction. The address can be anywhere in the data memory space.


Note that in this mode, the correct syntax is now:

 $\label{eq:ADDWF} \begin{tabular}{ll} ADDWF & [k], & d \\ \begin{tabular}{ll} where 'k' is the same as 'f'. \\ \end{tabular}$ 



### When 'a' = 1 (all values of f)

The instruction executes in Direct mode (also known as Direct Long mode). 'f' is interpreted as a location in one of the 63 banks of the data memory space. The bank is designated by the Bank Select Register (BSR). The address can be in any implemented bank in the data memory space.



# 9.6.3 Mapping the Access Bank in Indexed Literal Offset Mode

The use of Indexed Literal Offset Addressing mode effectively changes how the first 96 locations of Access RAM (00h to 5Fh) are mapped. Rather than containing just the contents of the top section of Bank 5, this mode maps the contents from a user defined "window" that can be located anywhere in the data memory space. The value of FSR2 establishes the lower boundary of the addresses mapped into the window, while the upper boundary is defined by FSR2 plus 95 (5Fh). Addresses in the Access RAM above 5Fh are mapped as previously described (see Access Bank). An example of Access Bank remapping in this Addressing mode is shown in the following figure.

Figure 9-7. Remapping the Access Bank with Indexed Literal Offset Addressing


### **EXAMPLE:**

ADDWF, f, d, a  $FSR2H:FSR2L = 0 \times 0 A20$ 

Locations in the region from the FSR2 pointer (A20h) to the pointer plus 05Fh (A7Fh) are mapped to the Access RAM (000h-05Fh).

Special File Registers at 460h through 4FFh are mapped to 60h through FFh, as usual.

Bank 4 addresses below 5Fh can still be addressed by using the BSR.



Remapping of the Access Bank applies only to operations using the Indexed Literal Offset mode. Operations that use the BSR (Access RAM bit is '1') will continue to use Direct Addressing as before.

### 9.6.4 PIC18 Instruction Execution and the Extended Instruction Set

Enabling the extended instruction set adds additional commands to the existing PIC18 instruction set. These instructions are executed as described in the "Extended Instruction Set" section.

# 9.7 Register Definitions: Memory Organization

#### 9.7.1 **PCL**

Name: PCL Offset: 0x4F9

Low byte of the Program Counter Register

Bit	7	6	5	4	3	2	1	0
				PCL	[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - PCL[7:0] Provides direct read and write access to the Program Counter

### 9.7.2 PCLAT

Name: PCLAT Offset: 0x4FA

**Program Counter Latches** 

Holding register for bits [21:9] of the Program Counter (PC). Reads of the PCL register transfer the upper PC bits to the PCLAT register. Writes to PCL register transfer the PCLAT value to the PC.

Bit	15	14	13	12	11	10	9	8
						PCLATU[4:0]		
Access				R/W	R/W	R/W	R/W	R/W
Reset				0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
				PCLAT	TH[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

**Bits 12:8 – PCLATU[4:0]** Upper PC Latch Register Holding register for Program Counter [21:17]

**Bits 7:0 – PCLATH[7:0]** High PC Latch Register Holding register for Program Counter [16:8]

# 9.7.3 TOS

Name: TOS Offset: 0x4FD Top-of-Stack Register

Contents of the stack pointed to by the STKPTR register. This is the value that will be loaded into the Program Counter upon a RETURN or RETFIE instruction.

Bit	23	22	21	20	19	18	17	16		
						TOS[20:16]				
Access				R/W	R/W	R/W	R/W	R/W		
Reset				0	0	0	0	0		
Bit	15	14	13	12	11	10	9	8		
	TOS[15:8]									
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		
Bit	7	6	5	4	3	2	1	0		
				TOS	[7:0]					
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		

Bits 20:0 - TOS[20:0] Top-of-Stack

Notes: The individual bytes in this multi-byte register can be accessed with the following register names:

- TOSU: Accesses the upper byte TOS[20:16]
- TOSH: Accesses the high byte TOS[15:8]
- TOSL: Accesses the low byte TOS[7:0]

#### 9.7.4 **STKPTR**

Name: STKPTR Offset: 0x4FC

Stack Pointer Register

Bit	7	6	5	4	3	2	1	0
					STKPTR[6:0]			
Access		R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset		0	0	0	0	0	0	0

Bits 6:0 - STKPTR[6:0] Stack Pointer Location

# 9.7.5 WREG

Name: WREG Offset: 0x4E8

Working Data Register

Bit	7	6	5	4	3	2	1	0
				WRE	G[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	X	Х	X	X	X	X	Х	X

Bits 7:0 - WREG[7:0]

# 9.7.6 INDF

Name: INDFx

Offset: 0x4EF,0x4E7,0x4DF

Indirect Data Register

This is a virtual register. The GPR/SFR register addressed by the FSRx register is the target for all operations involving the INDFx register.

Bit	7	6	5	4	3	2	1	0
				INDF	[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - INDF[7:0] Indirect data pointed to by the FSRx register

### 9.7.7 POSTDEC

Name: POSTDECx

Offset: 0x4ED,0x4E5,0x4DD

Indirect Data Register with post decrement

This is a virtual register. The GPR/SFR register addressed by the FSRx register is the target for all operations involving the POSTDECx register. FSRx is decremented after the read or write operation.

Bit	7	6	5	4	3	2	1	0
				POSTD	EC[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - POSTDEC[7:0]

### 9.7.8 POSTINC

Name: POSTINCx

**Offset:** 0x4EE,0x4E6,0x4DE

Indirect Data Register with post increment

This is a virtual register. The GPR/SFR register addressed by the FSRx register is the target for all operations involving the POSTINCx register. FSRx is incremented after the read or write operation.

Bit	7	6	5	4	3	2	1	0
				POSTI	NC[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - POSTINC[7:0]

### 9.7.9 **PREINC**

Name: PREINCx

Offset: 0x4EC,0x4E4,0x4DC

Indirect Data Register with pre-increment

This is a virtual register. The GPR/SFR register addressed by the FSRx register plus 1 is the target for all operations involving the PREINCx register. FSRx is incremented before the read or write operation.

Bit	7	6	5	4	3	2	1	0
				PREIN	IC[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - PREINC[7:0]

### 9.7.10 PLUSW

Name: PLUSWx

**Offset:** 0x4EB,0x4E3,0x4DB

Indirect Data Register with WREG offset

This is a virtual register. The GPR/SFR register addressed by the sum of the FSRx register plus the signed value of the W register is the target for all operations involving the PLUSWx register.

Bit	7	6	5	4	3	2	1	0
				PLUS	W[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - PLUSW[7:0]

DS40002259A-page 96

# 9.7.11 FSR

Name: FSRx

**Offset:** 0x4E9,0x4E1,0x4D9

Indirect Address Register

The FSR value is the address of the data to which the INDF register points.

Bit	15	14	13	12	11	10	9	8
					FSRI	H[5:0]		
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
				FSR	L[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 13:8 - FSRH[5:0] Most Significant address of INDF data

Bits 7:0 - FSRL[7:0] Least Significant address of INDF data

#### 9.7.12 **BSR**

Name: BSR Offset: 0x4E0 Bank Select Register

The BSR indicates the data memory bank of the GPR address.

Bit	7	6	5	4	3	2	1	0
					BSR	[5:0]		
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			0	0	0	0	0	0

Bits 5:0 - BSR[5:0] Most Significant bits of the data memory address

# 9.8 Register Summary - Memory Organization

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0	
0x00											
	Reserved										
0x04D8											
0x04D9	FSR2	7:0				FSR	L[7:0]				
		15:8						H[5:0]			
0x04DB	PLUSW2	7:0					W[7:0]				
0x04DC	PREINC2	7:0					NC[7:0]				
0x04DD	POSTDEC2	7:0					EC[7:0]				
0x04DE	POSTINC2	7:0					NC[7:0]				
0x04DF	INDF2	7:0				IND	<del>-</del> [7:0]				
0x04E0	BSR	7:0						R[5:0]			
0x04E1	FSR1	7:0				FSR	L[7:0]				
		15:8						H[5:0]			
0x04E3	PLUSW1	7:0		PLUSW[7:0]							
0x04E4	PREINC1	7:0		PREINC[7:0]							
0x04E5	POSTDEC1	7:0					EC[7:0]				
0x04E6	POSTINC1	7:0					NC[7:0]				
0x04E7	INDF1	7:0					<del>-</del> [7:0]				
0x04E8	WREG	7:0					G[7:0]				
0x04E9	FSR0	7:0				FSR	L[7:0]				
000469	1 310	15:8						H[5:0]			
0x04EB	PLUSW0	7:0				PLUS	W[7:0]				
0x04EC	PREINC0	7:0		PREINC[7:0]							
0x04ED	POSTDEC0	7:0				POSTE	EC[7:0]				
0x04EE	POSTINC0	7:0		POSTINC[7:0]							
0x04EF	INDF0	7:0				IND	<del>-</del> [7:0]				
0x04F0											
	Reserved										
0x04F8											
0x04F9	PCL	7:0	PCL[7:0]								
0x04FA	PCLAT	7:0	PCLATH[7:0]								
0X041 A	FOLAI	15:8	PCLATU[4:0]								
0x04FC	STKPTR	7:0					STKPTR[6:0]				
		7:0				TOS	[7:0]				
0x04FD	TOS	15:8				TOS	[15:8]				
		23:16						TOS[20:16]			

# 10. NVM - Nonvolatile Memory Module

The Nonvolatile Memory (NVM) module provides run-time read and write access to the Program Flash Memory (PFM), Data Flash Memory (DFM) and Configuration bits. PFM includes the program memory and user ID space. DFM is also referred to as EEPROM which is accessed one byte at a time and the erase before write is automatic.

The Table Pointer provides read-only access to the PFM, DFM and Configuration bits. The NVM controls provide both read and write access to PFM, DFM and Configuration bits.

Reads and writes to and from the DFM are limited to single byte operations, whereas those for PFM are 16-bit word or 128-word page operations. The page buffer memory occupies one full bank of RAM space located in the RAM bank following the last occupied GPR bank. Refer to the "**Memory Organization**" chapter for more details about the buffer RAM.

The registers used for control, address and data are as follows:

- NVMCON0 Operation start and active status
- NVMCON1 Operation type and error status
- NVMLOCK Write-only register to guard against accidental writes
- NVMADR Read/write target address (multi-byte register)
- NVMDAT Read/write target data (multi-byte register)
- TBLPTR Table Pointer PFM target address for reads and buffer RAM address for writes (multi-byte register)
- TABLAT Table Pointer read/write target data (single byte register)

The write and erase times are controlled by an on-chip timer. The write and erase voltages are generated by an on-chip charge pump rated to function over the operating voltage range of the device.

PFM and DFM can be protected in two ways: code protection and write protection. Code protection (Configuration bit  $\overline{CP}$ ) disables read and write access through an external device programmer. Write protection prevents user software writes to NVM areas tagged for protection by the  $\overline{WRTn}$  Configuration bits. Code protection does not affect the self-write and erase functionality, whereas write protection does. Attempts to write a protected location will set the WRERR bit. Code protection and write protection can only be reset on a Bulk Erase performed by an external programmer.

The Bulk Erase command is used to completely erase different memory regions. The area to be erased is selected using a bit field combination. The Bulk Erase command can only be issued through an external programmer. There is no run time access for this command.

If the device is code-protected and a Bulk Erase command for the configuration memory is issued; all other memory regions are also erased. Refer to the "**Programming Specifications**" for more details.

# 10.1 Operations

NVM write operations are controlled by selecting the desired action with the NVMCMD bits and then starting the operation by executing the unlock sequence. NVM read operations are started by setting the GO bit after setting the read operation. Available NVM operations are shown in the following table.

Table 10-1. NVM Operations

NVMCMD	Unlock	Operation	DFM	PFM	Source/Destination	WRERR	INT
000	No	Read	byte	word	NVM to NVMDAT	No	No
001	No	Read and Post Increment	byte	word	NVM to NVMDAT	No	No
010	No	Read Page		page	NVM to Buffer RAM	No	No
011	Yes	Write	byte	word	NVMDAT to NVM	Yes	Yes
100	Yes	Write and Post Increment	byte	word	NVMDAT to NVM	Yes	Yes
101	Yes	Write Page	_	page	Buffer RAM to NVM	Yes	Yes

contin	continued						
NVMCMD	Unlock	Operation	DFM	PFM	Source/Destination	WRERR	INT
110	Yes	Erase Page	_	page	n/a	Yes	Yes
111	No	Reserved (No Operation)	_	_	_	No	No



**Important:** When the GO bit is set, writes operations are blocked on all NVM registers. The GO bit is cleared by hardware when the operation is complete. The GO bit cannot be cleared by software.

# 10.2 Unlock Sequence

As an additional layer of protection against memory corruption, a specific code execution unlock sequence is required to initiate a write or erase operation. All interrupts should be disabled before starting the unlock sequence to ensure proper execution.

```
Example 10-1. Unlock sequence in C

NVMLOCK = 0x55;
NVMLOCK = 0xAA;
NVMCON0bits.GO = 1;
```

# 10.3 Program Flash Memory (PFM)

The Program Flash Memory is readable, writable and erasable over the entire V<sub>DD</sub> range.

A 128-word PFM page is the only size that can be erased by user software. A Bulk Erase operation cannot be issued from user code. A read from program memory is executed either one byte, one word or a 128-word page at a time. A write to program memory can be executed as either 1 or 128 words at a time.

Writing or erasing program memory will cease instruction fetches until the operation is complete. The program memory cannot be accessed during the write or erase, so code cannot execute. An internal programming timer controls the write time of program memory writes and erases.

A value written to program memory does not need to be a valid instruction. Executing a program memory location that forms an invalid instruction results in a NOP.

It is important to understand the PFM memory structure for erase and programming operations. Program memory word size is 16 bits wide.

After a page has been erased, all or a portion of this page can be programmed. Data can be written directly into PFM one 16-bit word at a time using the NVMADR, NVMDAT and NVMCON1 controls or as a full page from the buffer RAM. The buffer RAM is directly accessible as any other SFR/GPR register and also may be loaded via sequential writes using the TABLAT and TBLPTR registers.



**Important:** To modify only a portion of a previously programmed page, the contents of the entire page must be read and saved in the buffer RAM prior to the page erase. The Read Page operation is the easiest way to do this. The page should be erased so that the new data can be written into the buffer RAM to reprogram the page of PFM. However, any unprogrammed locations can be written using the single word Write operation without first erasing the page.

### 10.3.1 Page Erase

The erase size is always 128 words. Only through the use of an external programmer can larger areas of program memory be Bulk Erased. Word erase in the program memory is not supported.

When initiating an erase sequence from user code, a page of 128 words of program memory is erased. The NVMADR[21:8] bits point to the page being erased. The NVMADR[7:0] bits are ignored. The NVMCON0 and NVMCON1 registers command the erase operation. The NVMCMD bits are set to select the erase operation. The GO bit is set to initiate the erase operation as the last step in the unlock sequence.

The NVM unlock sequence described in the Unlock Sequence section must be used; this guards against accidental writes. Instruction execution is halted during the erase cycle. The erase cycle is terminated by the internal programming timer.

The sequence of events for erasing a page of PFM is:


- Set the NVMADR registers to an address within the intended page.
- 2. Set the NVMCMD control bits to 'b110 (Page Erase).
- Disable all interrupts.
- 4. Perform the unlock sequence as described in the Unlock Sequence section.
- 5. Set the GO bit to start the PFM page erase.
- 6. Monitor the GO bit or NVMIF interrupt flag to determine when the erase has completed.
- 7. Interrupts can be enabled after the GO bit is clear.
- 8. Set the NVMCMD control bits to 'b000.

If the PFM address is write-protected, the GO bit will be cleared, the erase operation will not take place, and the WRERR bit will be set.

While erasing the PFM page, the CPU operation is suspended and then resumes when the operation is complete. Upon erase completion, the GO bit is cleared in hardware, the NVMIF is set, and an interrupt will occur (if the NVMIE bit is set and interrupts are enabled).

The buffer RAM data are not affected by erase operations and the NVMCMD bits will remain unchanged throughout the erase operation.

Figure 10-1. PFM Page Erase Flowchart



# Example 10-2. Erasing a page of Program Flash Memory in C

```
// Code sequence to erase one page of PFM
// PFM target address is specified by PAGE ADDR
// Save interrupt enable bit value
uint8 t GIEBitValue = INTCONObits.GIE
// Load NVMADR with the base address of the memory page
NVMADR = PAGE ADDR:
NVMCON1bits.CMD = 0x06;
                                  // Set the page erase command
INTCONObits.GIE = 0;
                                  // Disable interrupts
         -- Required Unlock Sequence -
NVMI.OCK = 0x55
NVMLOCK = 0xAA;
NVMCON0bits.GO = 1;
                                 // Start page erase
while (NVMCONObits.GO); // Wait for the erase operation to complete
// Verify erase operation success and call the recovery function if needed
if (NVMCON1bits.WRERR) {
  ERASE FAULT RECOVERY();
INTCONObits.GIE = GIEBitValue;  // Restore interrupt enable bit value
NVMCON1bits.CMD = 0x00;
                                  // Disable writes to memory
```



### Important:

- If a write or erase operation is terminated by an unexpected reset, the WRERR bit will be set and the
  user can check to decide whether a rewrite of the location(s) is needed.
- If a write or erase operation is attempted on a write-protected area, the WRERR bit will be set.
- If a write or erase operation is attempted on an invalid address location, the WRERR bit is set. (Refer
  to the Program and Data Memory Map in the "Memory Organization" chapter for more information
  on valid address locations.)

### 10.3.2 Page Read

PFM can be read one word or 128-word page at a time. A page is read by setting the NVMADR registers to an address within the target page and setting the NVMCMD bits to 'b010. The page content is then transferred from PFM to the buffer RAM by starting the read operation by setting the GO bit.

The sequence of events for reading a 128-word page of PFM is:

- 1. Set the NVMADR registers to an address within the intended page.
- 2. Set the NVMCMD control bits to 'b010 (Page Read).
- 3. Set the GO bit to start the PFM page read.
- 4. Monitor the GO bit or NVMIF interrupt flag to determine when the read has completed.

```
Example 10-3. Reading a Page of Program Flash Memory in C

// Code sequence to read one page of PFM to Buffer Ram
// PFM target address is specified by PAGE_ADDR

// Load NVMADR with the base address of the memory page
NVMADR = PAGE_ADDR;

NVMCON1bits.CMD = 0x02;  // Set the page read command
NVMCON0bits.GO = 1;  // Start page read
while (NVMCON0bits.GO);  // Wait for the read operation to complete
```

### 10.3.3 Word Read

A single 16-bit word is read by setting the NVMADR registers to the target address and setting the NVMCMD bits to 'b000. The word is then transferred from PFM to the NVMDAT registers by starting the read operation by setting the GO bit.

The sequence of events for reading a word of PFM is:

- 1. Set the NVMADR registers to the target address.
- 2. Set the NVMCMD control bits to 'b000 (Word Read).
- 3. Set the GO bit to start the PFM word read.
- 4. Monitor the GO bit or NVMIF interrupt flag to determine when the read has completed.

```
Example 10-4. Reading a Word from Program Flash Memory in C

// Code sequence to read one word from PFM
// PFM target address is specified by WORD_ADDR

// Variable to store the word value from desired location in PFM
uint16_t WordValue;

// Load NVMADR with the desired word address
NVMADR = WORD_ADDR;
NVMCON1bits.CMD = 0x00;
NVMCON1bits.CMD = 0x00;
// Set the word read command
NVMCON0bits.GO = 1;
while (NVMCON0bits.GO);
// Wait for the read operation to complete
WordValue = NVMDAT;
// Store the read value to a variable
```

# 10.3.4 Page Write

A page is written by first loading the buffer registers in the buffer RAM. All buffer registers are then written to PFM by setting the NVMADR to an address within the intended address range of the target PFM page, setting the NVMCMD bits to 'b101, and then executing the unlock sequence and setting the GO bit.

If the PFM address in the NVMADR is write-protected, or if NVMADR points to an invalid location, the GO bit is cleared without any effect and the WRERR bit is set.

CPU operation is suspended during a page write cycle and resumes when the operation is complete. The page write operation completes in one extended instruction cycle. When complete, the GO bit is cleared by hardware and NVMIF is set. An interrupt will occur if NVMIE is also set. The buffer registers and NVMCMD bits are not changed throughout the write operation.

The internal programming timer controls the write time. The write/erase voltages are generated by an on-chip charge pump and rated to operate over the voltage range of the device.



**Important:** Individual bytes of program memory may be modified, provided that the modification does not attempt to change any NVM bit from a '0' to a '1'. When modifying individual bytes with a page write operation, it is necessary to load all buffer registers with either 0xFF or the existing contents of memory before executing a page write operation. The fastest way to do this is by performing a page read operation.

In this device a PFM page is 128 words (256 bytes). This is the same size as one bank of general purpose RAM (GPR). This area of GPR space is dedicated as a buffer area for NVM page operations. The buffer areas for each device in the family are shown in the following table:

Table 10-2. NVM Buffer Banks

Device	GPR Bank Number
PIC18Fx7Q84	37
PIC18Fx6Q84	21

There are several ways to address the data in the GPR buffer space:

- Using the TBLRD and TBLWT instructions
- · Using the indirect FSR registers
- · Direct read and writes to specific GPR locations

Neglecting the bank select bits, the 8 address bits of the GPR buffer space correspond to the 8 LSbs of each PFM page. In other words, there is a one-to-one correspondence between the NVMADRL register and the FSRxL register, where the x in FSRx is 0, 1 or 2.

The sequence of events for programming a page of PFM is:

- 1. Set the NVMADR registers to an address within the intended page.
- 2. Set the NVMCMD to 'b110 (Erase Page).
- 3. Disable all interrupts.
- 4. Perform the unlock sequence as described in the Unlock Sequence section.
- 5. Set the GO bit to start the PFM page erase.
- 6. Monitor the GO bit or NVMIF interrupt flag to determine when the erase has completed.
- 7. Set NVMCMD to 'b101 (Page Write).
- 8. Perform the unlock sequence.
- 9. Set the GO bit to start the PFM page write.
- 10. Monitor the GO bit or NVMIF interrupt flag to determine when the write has completed.
- 11. Interrupts can be enabled after the GO bit is clear.
- 12. Set the NVMCMD control bits to 'b000.

```
Example 10-5. Writing a Page of Program Flash Memory in C
 // Code sequence to write a page of PFM
 // Input[] is the user data that needs to be written to PFM
 // PFM target address is specified by PAGE_ADDR
 #define PAGESIZE 128
                                   // PFM page size
 // Save Interrupt Enable bit Value
 uint8 t GIEBitValue = INTCONObits.GIE;
 // The BufferRAMStartAddr will be changed based on the device, refer
 // to the "Memory Organization" chapter for more detail
 uint16 t bufferRAM at (BufferRAMStartAddr);
 // Defining a pointer to the first location of the Buffer RAM
 uint16 t *bufferRamPtr = (uint16_t*) & bufferRAM;
 //Copy application buffer contents to the Buffer RAM
 for (uint8 t i = 0; i < PAGESIZE; i++) {</pre>
     *bufferRamPtr++ = Input[i];
 // Load NVMADR with the base address of the memory page
 NVMADR = PAGE ADDR;
 NVMCON1bits.CMD = 0x06; // Set the page erase command
 INTCONObits.GIE = 0;
                                  // Disable interrupts
 //---- Required Unlock Sequence --
 NVMLOCK = 0x55;
 NVMLOCK = 0xAA;
 NVMCON0bits.GO = 1;
                                 // Start page erase
 while (NVMCONObits.GO);  // Wait for the erase operation to complete
 // Verify erase operation success and call the recovery function if needed
 if (NVMCON1bits.WRERR) {
   ERASE_FAULT_RECOVERY();
 // NVMADR is already pointing to target page
 NVMCON1bits.CMD = 0x05; // Set the page write command
 //---- Required Unlock Sequence --
 NVMLOCK = 0x55
 NVMLOCK = 0xAA;
 NVMCONObits.GO = 1;  // Start page write
```

### 10.3.5 Word Write

PFM can be written one word at a time to a pre-erased memory location. Refer to "Word Modify" section for more information on writing to a pre-written memory location.

A single word is written by setting the NVMADR to the target address and loading NVMDAT with the desired word. The word is then transferred to PFM by setting the NVMCMD bits to 'b011 then executing the unlock sequence and setting the GO bit.

The sequence of events for programming single word to a pre-erased location of PFM is:

- 1. Set the NVMADR registers to the target address.
- Load the NVMDAT with desired word.
- 3. Set the NVMCMD control bits to 'b011 (Word Write).
- Disable all interrupts.
- 5. Perform the unlock sequence as described in the Unlock Sequence section.
- 6. Set the GO bit to start the PFM word write.
- 7. Monitor the GO bit or NVMIF interrupt flag to determine when the write has completed.
- 8. Interrupts can be enabled after the GO bit is clear.
- 9. Set the NVMCMD control bits to 'b000.

```
Example 10-6. Writing a Word of Program Flash Memory in C
 // Code sequence to program one word to a pre-erased location in PFM
   PFM target address is specified by WORD ADDR
 // Target data is specified by WordValue
 // Save interrupt enable bit value
 uint8 t GIEBitValue = INTCONObits.GIE;
 // Load NVMADR with the target address of the word
 NVMADR = WORD ADDR;
 NVMDAT = WordValue;
                                    // Load NVMDAT with the desired value
NVMCON1bits.CMD = 0x03;
                                   // Set the word write command
 INTCONObits.GIE = 0;
                                    // Disable interrupts
          -- Required Unlock Sequence
 NVMI_OCK = 0 \times 55:
 NVMLOCK = 0xAA;
 NVMCON0bits.GO = 1;
                                  // Start word write
 while (NVMCONObits.GO);
                                  // Wait for the write operation to complete
 // Verify word write operation success and call the recovery function if needed
 if (NVMCON1bits.WRERR) {
    WRITE FAULT RECOVERY();
 INTCONObits.GIE = GIEBitValue;  // Restore interrupt enable bit value
 NVMCON1bits.CMD = 0x00;
                                   // Disable writes to memory
```

### 10.3.6 Word Modify

Changing a word in PFM requires erasing the word before it is re-written. However, the PFM cannot be erased by less than a page at a time. Changing a single word requires reading the page, erasing the page, and then re-writing the page with the modified word. The NVM command set includes page operations to simplify this task.

The steps necessary to change one or more words in PFM space are as follows:

- 1. Set the NVMADR registers to the target address.
- 2. Set the NVMCMD to 'b010 (Page Read).
- 3. Set the GO bit to start the PFM read into the GPR buffer.
- 4. Monitor the GO bit or NVMIF interrupt flag to determine when the read has completed.
- 5. Make the desired changes to the GPR buffer data.
- 6. Set NVMCMD to 'b110 (Page Erase).
- 7. Disable all interrupts.
- 8. Perform the unlock sequence as described in the Unlock Sequence section.
- 9. Set the GO bit to start the PFM page erase.
- 10. Monitor the GO bit or NVMIF interrupt flag to determine when the erase has completed.
- 11. Set NVMCMD to 'b101 (Page Write).
- 12. Perform the unlock sequence.
- 13. Set the GO bit to start the PFM page write.
- 14. Monitor the GO bit or NVMIF interrupt flag to determine when the write has completed.
- 15. Interrupts can be enabled after the GO bit is clear.
- 16. Set the NVMCMD control bits to 'b000.

```
Example 10-7. Modifying a Word in Program Flash Memory in C
 // Code sequence to modify one word in a programmed page of PFM
 // The variable with desired value is specified by ModifiedWord
 // PFM target address is specified by WORD_ADDR
 // PFM page size is specified by PAGESIZE
 // The Buffer RAM start address is specified by BufferRAMStartAddr. This value
 // will be changed based on the device, refer to the "Memory Organization"
 //chapter for more detail.
 // Save Interrupt Enable bit Value
 uint8 t GIEBitValue = INTCONObits.GIE;
 uint16_t bufferRAM __at(BufferRAMStartAddr);
 // Defining a pointer to the first location of the Buffer RAM
 uint16 t *bufferRamPtr = (uint16 t*) & bufferRAM;
 // Load NVMADR with the base address of the memory page
 NVMADR = WORD ADDR;

NVMCON1bits.CMD = 0x02;

INTCON0bits.GIE = 0;


NVMCON0bits.GO = 1;

NVMCON0bits.GO = 1;
 NVMADR = WORD ADDR;
                                   // Set the page read command
                                   // Disable interrupts
// Start page read
// Wait for the read operation to complete
 while (NVMCON0bits.GO);
 // NVMADR is already pointing to target page
 NVMCON1bits.CMD = 0x06; // Set the page erase command
 //---- Required Unlock Sequence -
 NVMLOCK = 0x55;
 NVMLOCK = 0xAA;
 NVMCON0bits.GO = 1;
                                  // Start page erase
 // Verify erase operation success and call the recovery function if needed
 if (NVMCON1bits.WRERR) {
   ERASE_FAULT_RECOVERY();
 //Modify Buffer RAM for the given word to be written to PFM
 uint8 t offset = (uint8 t) ((WORD ADDR & ((PAGESIZE * 2) - 1)) / 2);
 bufferRamPtr += offset;
 *bufferRamPtr = ModifiedWord;
 // NVMADR is already pointing to target page
 NVMCON1bits.CMD = 0x05;
                                // Set the page write command
 //---- Required Unlock Sequence -
 NVMLOCK = 0x55;
 NVMLOCK = 0xAA;
```

# 10.3.7 Write Verify

Depending on the application, good programming practice can dictate that the value written to the memory shall be verified against the original value. This can be used in applications where excessive writes can stress bits near the specification limit. Since program memory is stored as a full page, the stored program memory contents are compared with the intended data stored in the buffer RAM after the last write is complete.

Figure 10-2. Program Flash Memory Write Verify Flowchart



# 10.3.8 Unexpected Termination of Write Operation

If a write is terminated by an unplanned event, such as loss of power or an unexpected Reset, the memory location just programmed should be verified and reprogrammed, if needed. If the write operation is interrupted by a  $\overline{\text{MCLR}}$  Reset or a WDT Time-out Reset during normal operation, the WRERR bit will be set, which the user can check to decide whether a rewrite of the location(s) is needed.

# 10.3.9 User ID, Device ID, Configuration Settings Access, DIA and DCI

The NVMADR value determines which NVM address space is accessed. The User IDs and Configuration areas allow read and write access, whereas Device and Revision IDs are limited to read-only.

Reading and writing User ID space is identical to reading and writing PFM space as described in the preceding paragraphs.

Writing to the Configuration bits is performed in the same manner as writing to the Data Flash Memory (DFM). Configuration settings are modified one byte at a time with the NVM Read and Write operations. When a Write operation is performed on a Configuration byte, an erase byte is performed automatically before the new byte is written. Any code protection settings that are not enabled will remain not enabled after the Write operation, unless the new values enable them. However, any code protection settings that are enabled cannot be disabled by a self-write of the configuration space. The user can modify the configuration space by the following steps:

- 1. Read the target Configuration byte by setting the NVMADR with the target address.
- 2. Retrieve the Configuration byte with the Read operation (NVMCMD = 'b000).
- 3. Modify the Configuration byte in NVMDAT register.
- 4. Write the NVMDAT register to the Configuration byte using the Write operation (NVMCMD = 'b011) and unlock sequence.

### 10.3.10 Table Pointer Operations

In order to read and write program memory, there are two operations that allow the processor to move bytes between the program memory space and the data RAM:

- Table Read (TBLRD\*)
- Table Write (TBLWT\*)

The SFR registers associated with these operations include:

- TABLAT register
- · TBLPTR registers

The program memory space is 16 bits wide, while the data RAM space is eight bits wide. The TBLPTR registers determine the address of one byte of the NVM memory. Table reads move one byte of data from NVM space to the TABLAT register, and table writes move the TABLAT data to the buffer RAM ready for a subsequent write to NVM space with the NVM controls.

### 10.3.10.1 Table Pointer Register

The Table Pointer (TBLPTR) register addresses a byte within the program memory. The TBLPTR comprises three SFR registers: Table Pointer Upper Byte, Table Pointer High Byte and Table Pointer Low Byte (TBLPTRU:TBLPTRH:TBLPTRL). These three registers join to form a 22-bit wide pointer (bits 0 through 21). The bits 0 through 20 allow the device to address up to 2 Mbytes of program memory space. Bit 21 allows access to the Device ID, the User ID, Configuration bits as well as the DIA and DCI.

The Table Pointer register, TBLPTR, is used by the <code>TBLRD</code> and <code>TBLWT</code> instructions. These instructions can increment and decrement the TBLPTR, depending on specific appended characters shown in the following table. The increment and decrement operations on the TBLPTR affect only bits 0 through 20.

Table 10-3. Table Pointer Operations with TBLRD and TBLWT Instructions

Example	Operation on Table Pointer
TBLRD* TBLWT*	TBLPTR is not modified

TBLRD*+ TBLWT*+	TBLPTR is incremented after the read/write
TBLRD*- TBLWT*-	TBLPTR is decremented after the read/write
TBLRD+* TBLWT+*	TBLPTR is incremented before the read/write

### 10.3.10.2 Table Latch Register


The Table Latch (TABLAT) is an 8-bit register mapped into the SFR space. The Table Latch register receives one byte of NVM data resulting from a TBLRD\* instruction and is the source of the 8-bit data sent to the holding register space as a result of a TBLWT\* instruction.

#### 10.3.10.3 Table Read Operations

The table read operation retrieves one byte of data directly from program memory pointed to by the TBLPTR registers and places it into the TABLAT register. The following figure shows the operation of a table read.

Figure 10-3. Table Read Operation

Instruction: TBLRD\*




Note 1: The Table Pointer register points to a byte in program memory.

### 10.3.10.4 Table Write Operations

The table write operation stores one byte of data from the TABLAT register into a buffer RAM register. The following figure shows the operation of a table write from the TABLAT register to the buffer RAM space. The procedure to write the contents of the buffer RAM into program memory is detailed in the "Writing to Program Flash Memory" section.

Figure 10-4. Table Write Operation

Instruction: TBLWT\*



**Note 1:** During table writes the Table Pointer does not point directly to program memory. TBLPTRL actually points to an address within the buffer registers. TBLPTRU:TBLPTRH points to program memory where the entire buffer space will eventually be written with the NVM commands.

Table operations work with byte entities. Tables containing data, rather than program instructions, are not required to be word-aligned. Therefore, a table can start and end at any byte address. If a table write is being used to write executable code into program memory, program instructions will need to be word-aligned.

#### 10.3.10.5 Table Pointer Boundaries

The TBLPTR register is used in reads of the Program Flash Memory. Writes using the TBLPTR register go into to a buffer RAM from which the data can eventually be transferred to Program Flash Memory using the NVMADR register and NVM commands.


When a TBLRD instruction is executed, all 22 bits of the TBLPTR determine which byte is read from program memory directly into the TABLAT register.

When a TBLWT instruction is executed, the byte in the TABLAT register is written, though not to Flash memory but to a buffer register in preparation for a program memory write. All the buffer registers together form a write block of size 128 words/256 bytes. The LSbs of the TBLPTR register determine to which specific address within the buffer register block the write affects. The size of the write block determines the number of LSbs that are affected. The MSbs of the TBLPTR register have no effect during TBLWT operations.

When a program memory page write is executed, the entire buffer register block is written to the Flash memory at the address determined by the MSbs of the NVMADR register. The LSbs are ignored during Flash memory writes.

The following figure illustrates the relevant boundaries of the TBLPTR register based on NVM operations.

Figure 10-5. Table Pointer Boundaries Based on Operation



#### Note:

1. Refer to the "Memory Organization" chapter for more details about the the size of the buffer registers block.

## 10.3.10.6 Reading the Program Flash Memory

The TBLRD instruction retrieves data from program memory at the location to which the TBLPTR register points and places it into the TABLAT SFR register. Table reads from program memory are performed one byte at a time. The instruction set includes incrementing the TBLPTR register automatically for the next table read operation.

The CPU operation is suspended during the read, and resumes operation immediately after. From the user point of view, the value in the TABLAT register is valid in the next instruction cycle.

The internal program memory is typically organized by words. The Least Significant bit of the address selects between the high and low bytes of the word. The following figure illustrates the interface between the internal program memory and the TABLAT register.

Figure 10-6. Reads from Program Flash Memory





Figure 10-7. Program Flash Memory Read Flowchart



```
Example 10-8. Reading a Program Flash Memory Word
    MOVLW
            CODE ADDR UPPER
                               ; Load TBLPTR with the base
    MOVWF
            TBLPTRU
                               ; address of the word
            CODE ADDR HIGH
    MOVLW
    MOVWF
            TBLPTRH
    MOVLW
            CODE ADDR LOW
    MOVWF
            TBLPTRL
 READ WORD:
    TBLRD*+
                              ; read into TABLAT and increment
    MOVF
           TABLAT, W
                               ; get data
    MOVWF
            WORD EVEN
    TBLRD*+
                               ; read into TABLAT and increment
    MOVFW
           TABLAT, W
                               ; get data
            WORD ODD
    MOVF
```

# 10.4 Data Flash Memory (DFM)

The Data Flash Memory is a nonvolatile memory array, also referred to as EEPROM. The DFM is mapped above program memory space. The DFM can be accessed using the Table Pointer or NVM Special Function Registers (SFRs). The DFM is readable and writable during normal operation over the entire V<sub>DD</sub> range.

The DFM can only be read and written one byte at a time. When interfacing to the data memory block, the NVMDATL register holds the 8-bit data for read/write and the NVMADR register holds the address of the DFM location being accessed.

The DFM is rated for high erase/write cycle endurance. A byte write automatically erases the location and writes the new data (erase-before-write). The write time is controlled by an internal programming timer; it will vary with voltage and temperature as well as from device-to-device. Refer to the data EEPROM memory parameters in the "Electrical specifications" chapter for the limits.

#### 10.4.1 Reading the DFM

To read a DFM location, the user must write the address to the NVMADR register, set the NVMCMD bits for a single read operation (NVMCMD = 'b000), and then set the GO control bit. The data is available on the very next instruction cycle. Therefore, the NVMDATL register can be read by the next instruction. NVMDATL will hold this value until another read operation, or until it is written to by the user (during a write operation).


Note: Only byte reads are supported for DFM. Reading DFM with the Read Page operation is not supported.

The sequence of events for reading a byte of DFM is:

- 1. Set the NVMADR registers to an address within the intended page.
- 2. Set the NVMCMD control bits to 'b000. (Byte Read)
- 3. Set the GO bit to start the DFM byte read.
- 4. Monitor the GO bit or NVMIF interrupt flag to determine when the read has completed.

This process is also shown in the following flowchart.

Figure 10-8. DFM Read Flowchart



```
Example 10-9. Reading a Byte from Data Flash Memory in C

// Code sequence to read one byte from DFM
// DFM target address is specified by DFM_ADDR

// Variable to store the byte value from desired location in DFM
uint8_t ByteValue;

// Load NVMADR with the desired byte address
NVMADR = DFM_ADDR;
NVMCON1bits.CMD = 0x00;
NVMCON1bits.CMD = 0x00;
// Set the byte read command
NVMCON0bits.GO = 1;
// Start byte read
while (NVMCON0bits.GO);
// Wait for the read operation to complete
ByteValue = NVMDATL;
// Store the read value to a variable
```

#### 10.4.2 Writing to DFM

To write a DFM location, the address must first be written to the NVMADR register, the data written to the NVMDATL register, and the Write operation command set in the NVMCMD bits. The sequence shown in Unlock Sequence must be followed to initiate the write cycle. Multi-byte Page writes are not supported for the DFM.

The write will not begin if the NVM unlock sequence is not exactly followed for each byte. It is strongly recommended to disable interrupts during this code segment.

When not actively writing to the DFM, the NVMCMD bits should be kept clear at all times as an extra precaution against accidental writes. The NVMCMD bits are not cleared by hardware.

After a write sequence has been initiated, NVMCON0, NVMCON1, NVMADR and NVMDAT cannot be modified.

Each DFM write operation includes an implicit erase cycle for that byte. CPU execution continues in parallel and at the completion of the write cycle, the GO bit is cleared in hardware and the NVM Interrupt Flag bit (NVMIF) is set. The user can either enable the interrupt or poll the bit. NVMIF must be cleared by software.

The sequence of events for programming one byte of DFM is:

- 1. Set NVMADR registers with the target byte address.
- Load NVMDATL register with desired byte.
- 3. Set the NVMCMD control bits to 'b011. (Byte Write)
- 4. Disable all interrupts.
- 5. Perform the unlock sequence as described in the Unlock Sequence section.
- 6. Set the GO bit to start the DFM byte write.
- 7. Monitor the GO bit or NVMIF interrupt flag to determine when the write has been completed.
- 8. Interrupts can be enabled after the GO bit is clear.
- 9. Set the NVMCMD control bits to 'b000.

```
Example 10-10. Writing a Byte to Data Flash memory in C
 // Code sequence to write one byte to a DFM
 // DFM target address is specified by DFM ADDR
 // Target data is specified by ByteValue
 // Save interrupt enable bit value
 uint8 t GIEBitValue = INTCONObits.GIE;
 // Load NVMADR with the target address of the byte
 NVMADR = DFM ADDR;
 NVMDATL = ByteValue;
                                    // Load NVMDAT with the desired value
NVMCON1bits.CMD = 0x03;
                                    // Set the byte write command
 INTCONObits.GIE = 0;
                                    // Disable interrupts
          -- Required Unlock Sequence --
 NVMLOCK = 0x55;
 NVMLOCK = 0xAA;
 NVMCON0bits.GO = 1;
                                   // Start byte write
 while (NVMCON0bits.GO); // Wait for the write operation to complete
 // Verify byte write operation success and call the recovery function if needed
 if (NVMCON1bits.WRERR) {
    WRITE_FAULT_RECOVERY();
 INTCONObits GIE = GIEBitValue; // Restore interrupt enable // Disable writes to memory
                                    // Restore interrupt enable bit value
```

### 10.4.3 Erasing the DFM

The DFM does not support the Page Erase operation. However, the DFM can be erased by writing 0xFF to all locations in the memory that need to be erased. The simple code example bellow shows how to erase 'n' number of bytes in DFM. Refer to the "**Memory Organization**" chapter for more detail about the DFM size and valid address locations.

```
Example 10-11. Erasing n Bytes of Data Flash Memory in C

// Code sequence to erase n bytes of DFM
// DFM target start address is specified by PAGE_ADDR
// Number of bytes to be eares is specified by n

// Save interrupt enable bit value
uint8_t GIEBitValue = INTCON0bits.GIE;

// Load NVMADR with the target address of the byte
NVMADR = DFM_ADDR;
NVMDATL = 0xFF;
NVMCON1bits.CMD = 0x04;
INTCON0bits.GIE = 0;
// Set the write and post increment command
INTCON0bits.GIE = 0;
// Disable interrupts
```

```
for (uint8_t i = 0; i < n; i++)(</pre>
        NV\overline{M}LOCK = 0x55;
        NVMLOCK = 0xAA;
        NVMCON0bits.GO = 1;
// Verify byte erase operation success and call the recovery function if needed
if (NVMCON1bits.WRERR) {
   ERASE_FAULT_RECOVERY();
INTCONObits.GIE = GIEBitValue;
                                      // Restore interrupt enable bit value
NVMCON1bits.CMD = 0;
                                      // Disable writes to memory
```

#### **DFM Write Verify** 10.4.4

Depending on the application, good programming practice can dictate that the value written to the memory shall be verified against the original value. This can be used in applications where excessive writes can stress bits near the specification limit to ensure that the intended values are written correctly to the specified memory locations.

#### 10.4.5 **Operation During Code-Protect and Write-Protect**

The DFM can be code-protected using the CP Configuration Bit. In-Circuit Serial Programming read and write operations are disabled when code protection is enabled. However, internal reads operate normally. Internal writes operate normally provided that write protection is not enabled.

If the DFM is write-protected or if NVMADR points at an invalid address location, attempts to set the GO bit will fail and the WRERR bit will be set.

#### 10.4.6 **Protection Against Spurious Writes**

A write sequence is valid only when both the following conditions are met. This prevents spurious writes that might lead to data corruption.

- All NVM read, write and erase operations are enabled with the NVMCMD control bits. It is suggested to have the NVMCMD bits cleared at all times except during memory writes. This prevents memory operations if any of the control bits are set accidentally.
- The NVM unlock sequence must be performed each time before all operations except the memory read operation.

#### 10.5 Register Definitions: NVM

## 10.5.1 NVMCON0

Name: NVMCON0 Offset: 0x040

Nonvolatile Memory Control Register 0



Bit 0 - GO Start Operation Control

Start the operation specified by the NVMCMD bits

Value	Description
1	Start operation (must be set after UNLOCK sequence for all operations except READ)
0	Operation is complete

### 10.5.2 NVMCON1

Name: NVMCON1 Offset: 0x041

Nonvolatile Memory Control Register 1

Bit	7	6	5	4	3	2	1	0
	WRERR					NVMCMD[2:0]		
Access	R/C/HS					R/W	R/W	R/W
Reset	0					0	0	0

### Bit 7 - WRERR NVM Write Error

Reset States: POR = 0

All other resets = u

Value	Description						
1	A write operation was interrupted by a Reset,						
	or a write or erase operation was attempted on a write-protected area,						
	or a write or erase operation was attempted on an unimplemented area,						
	or a write or erase operation was attempted while locked,						
	or a page operation was directed to a DFM area						
0	All write/erase operations have completed successfully						

# Bits 2:0 - NVMCMD[2:0] NVM Command

## Table 10-4. NVM Operations

NVMCMD	Unlock	Operation	DFM	PFM	Source/Destination	WRERR	INT
000	No	Read	byte	word	NVM to NVMDAT	No	No
001	No	Read and Post Increment	byte	word	NVM to NVMDAT	No	No
010	No	Read Page		page	NVM to Buffer RAM	No	No
011	Yes	Write	byte	word	NVMDAT to NVM	Yes	Yes
100	Yes	Write and Post Increment	byte	word	NVMDAT to NVM	Yes	Yes
101	Yes	Write Page	_	page	Buffer RAM to NVM	Yes	Yes
110	Yes	Erase Page	_	page	n/a	Yes	Yes
111	No	Reserved (No Operation)	_	_	<del>-</del>	No	No

# PIC18F26/46/56Q84

# **NVM - Nonvolatile Memory Module**

## 10.5.3 NVMLOCK

Name: NVMLOCK Offset: 0x042

Nonvolatile Memory Write Restriction Control Register

NVM write and erase operations require writing 0x55 then 0xAA to this register immediately before the operation execution.

Bit	7	6	5	4	3	2	1	0			
	NVMLOCK[7:0]										
Access	WO	WO	WO	WO	WO	WO	WO	WO			
Reset	0	0	0	0	0	0	0	0			

## Bits 7:0 - NVMLOCK[7:0]

Reading this register always returns '0'.

### 10.5.4 NVMADR

Name: NVMADR Offset: 0x043

Nonvolatile Memory Address Register

Bit	23	22	21	20	19	18	17	16
					NVMAD	R[21:16]		
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			0	0	0	0	0	0
Bit	15	14	13	12	11	10	9	8
				NVMAD	PR[15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
				NVMAI	DR[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 21:0 - NVMADR[21:0] NVM Address

Notes: The individual bytes in this multi-byte register can be accessed with the following register names:

- NVMADRU: Accesses the upper byte NVMADR[21:16]
- NVMADRH: Accesses the high byte NVMADR[15:8]
- NVMADRL: Accesses the low byte NVMADR[7:0]

## 10.5.5 **NVMDAT**

Name: NVMDAT Offset: 0x046

Nonvolatile Memory Data Register

Bit	15	14	13	12	11	10	9	8				
	NVMDAT[15:8]											
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W				
Reset	0	0	0	0	0	0	0	0				
Bit	7	6	5	4	3	2	1	0				
				NVMD	AT[7:0]							
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W				
Reset	0	0	0	0	0	0	0	0				

Bits 15:0 - NVMDAT[15:0] NVM Data

Notes: The individual bytes in this multi-byte register can be accessed with the following register names:

- NVMDATH: Accesses the high byte NVMDAT[15:8]
- NVMDATL: Accesses the low byte NVMDAT[7:0]

### 10.5.6 TBLPTR

Name: TBLPTR Offset: 0x4F6

Table Pointer Register

Bit	23	22	21	20	19	18	17	16
			TBLPTR21			TBLPTR[20:16]		
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			0	0	0	0	0	0
Bit	15	14	13	12	11	10	9	8
				TBLPT	R[15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
				TBLP	ΓR[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bit 21 - TBLPTR21 NVM Most Significant Address bit

Value	Description
1	Access Configuration, User ID, Device ID, and Revision ID spaces
0	Access Program Flash Memory space

## Bits 20:0 - TBLPTR[20:0] NVM Address bits

Notes: The individual bytes in this multi-byte register can be accessed with the following register names:

- TBLPTRU: Accesses the upper byte TBLPTR[21:16]
- TBLPTRH: Accesses the high byte TBLPTR[15:8]
- TBLPTRL: Accesses the low byte TBLPTR[7:0]

# PIC18F26/46/56Q84

# **NVM - Nonvolatile Memory Module**

### 10.5.7 TABLAT

Name: TABLAT Offset: 0x4F5

Table Latch Register

Bit	7	6	5	4	3	2	1	0			
	TABLAT[7:0]										
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W			
Reset	0	0	0	0	0	0	0	0			

**Bits 7:0 – TABLAT[7:0]** The value of the NVM memory byte returned from the address contained in TBLPTR after a TBLRD command, or the data written to the latch by a TBLWT command.

# 10.6 Register Summary - NVM

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0		
0x00												
 0x3F	Reserved											
0x40	NVMCON0	7:0								GO		
0x41	NVMCON1	7:0	WRERR						NVMCMD[2:0]			
0x42	NVMLOCK	7:0		NVMLOCK[7:0]								
	NVMADR	7:0		NVMADR[7:0]								
0x43		15:8	NVMADR[15:8]									
		23:16	NVMADR[21:16]									
0x46	NVMDAT	7:0			-	NVMD	AT[7:0]					
0.40	INVIVIDAT	15:8	NVMDAT[15:8]									
0x48												
	Reserved											
0x04F4												
0x04F5	TABLAT	7:0				TABL	AT[7:0]					
		7:0				TBLP <sup>-</sup>	TR[7:0]					
0x04F6	TBLPTR	15:8				TBLPT	R[15:8]					
		23:16			TBLPTR21			TBLPTR[20:16	6]			

# 11. VIC - Vectored Interrupt Controller Module

#### 11.1 Overview

The Vectored Interrupt Controller (VIC) module reduces the numerous peripheral interrupt request signals to a single interrupt request signal to the CPU. This module includes the following major features:

- Interrupt Vector Table (IVT) with a unique vector for each interrupt source
- · Fixed and ensured interrupt latency
- · Programmable base address for IVT with lock
- · Two user-selectable priority levels High priority and low priority
- Two levels of context saving
- · Interrupt state Status bits to indicate the current execution status of the CPU

The VIC module assembles all of the interrupt request signals and resolves the interrupts based on both a fixed natural order priority (i.e., determined by the IVT), and a user-assigned priority (i.e., determined by the IPRx registers), thereby eliminating scanning of interrupt sources.

## 11.2 Interrupt Control and Status Registers

The devices in this family implement the following registers for the interrupt controller:

- INTCON0, INTCON1 Control Registers
- PIRx Peripheral Interrupt Status Registers
- · PIEx Peripheral Interrupt Enable Registers
- · IPRx Peripheral Interrupt Priority Registers
- IVTBASE Address Registers
- IVTLOCK Register

Global interrupt control functions and external interrupts are controlled from the INTCON0 register. The INTCON1 register contains the status flags for the interrupt controller.

The PIRx registers contain all of the interrupt request flags. Each source of interrupt has a Status bit, which is set by the respective peripherals or an external signal, and is either cleared via software or automatically cleared by hardware upon clearing of the interrupt condition, depending on the peripheral and bit.

The PIEx registers contain all of the interrupt enable bits. These control bits are used to individually enable interrupts from the peripherals or external signals.

The IPRx registers are used to set the interrupt priority level for each source of interrupt. Each user interrupt source can be assigned to either a high or low priority.

The IVTBASE register is user programmable and is used to determine the start address of the IVT and the IVTLOCK register is used to prevent any unintended writes to the IVTBASE register.

There are two other Configuration bits that control the way the interrupt controller can be configured: the MVECEN bit and the IVT1WAY bit.

The MVECEN bit determines whether the IVT is used to determine the interrupt priorities. The IVT1WAY bit determines the number of times that the IVTLOCKED bit can be cleared and set after a device Reset. See Interrupt Vector Table Address Calculation for details.

### 11.3 Interrupt Vector Table

The interrupt controller supports an IVT that contains the vector address location for each interrupt request source.

The IVT resides in program memory, starting at the address location determined by IVTBASE The IVT contains one vector for each source of interrupt. Each interrupt vector location contains the starting address of the associated Interrupt Service Routine (ISR).

The MVECEN Configuration bit controls the availability of the vector table.

#### 11.3.1 Interrupt Vector Table Base Address (IVTBASE)

The start address of the vector table is user-programmable through the IVTBASE. The user must ensure the start address is such that it can encompass the entire vector table inside the program memory.

Each vector address is a 16-bit word (or two address locations on PIC18 devices). For 'n' interrupt sources, there are '2n' address locations necessary to hold the table, starting from IVTBASE as the first location. Thus, the starting address should be chosen such that the address range from IVTBASE to "IVTBASE+2n-1" can be encompassed within the program Flash memory.

For example, if the highest vector number was 81, IVTBASE should be chosen such that "IVTBASE+0xA1" is less than the last memory location in program Flash memory.

A programmable vector table base address is useful in situations to switch between different sets of vector tables, depending on the application. It can also be used when the application program needs to update the existing vector table (vector address values).



Important: It is required that the user assign an even address to IVTBASE for correct operation.

#### 11.3.2 Interrupt Vector Table Contents

#### MVECEN = 0

When MVECEN = 0, the address location pointed to by IVTBASE has a GOTO instruction for a high-priority interrupt. Similarly, the corresponding low-priority vector also has a GOTO instruction, which is executed in case of a low-priority interrupt.

#### MVECEN = 1

When MVECEN = 1, the value in the vector table of each interrupt points to the address location of the first instruction of the Interrupt Service Routine, hence: ISR Location = Interrupt Vector Table entry << 2.

#### 11.3.3 Interrupt Vector Table Address Calculation

#### MVECEN = 0

When the MVECEN Configuration bit is cleared, the address pointed to by IVTBASE is used as the high-priority interrupt vector address. The low-priority interrupt vector address is offset eight instruction words from the address in IVTBASE.

For PIC18 devices, IVTBASE defaults to 000008h, hence the high-priority interrupt vector address will be 000008h and the low-priority interrupt vector address will be 000018h.

#### MVECEN = 1

Each interrupt has a unique vector number associated with it as defined in the IVT. This vector number is used for calculating the location of the interrupt vector for a particular interrupt source.

Interrupt Vector Address = IVTBASE + (2\*Vector Number).

This calculated interrupt vector address value is stored in IVTAD register when an interrupt is received.

User-assigned software priority, when assigned using the IPRx registers, does not affect address calculation and is only used to resolve concurrent interrupts.

# PIC18F26/46/56Q84

# **VIC - Vectored Interrupt Controller Module**



**Important:** If for any reason the address of the ISR could not be fetched from the vector table, it will cause the system to Reset and clear the Memory Execution Violation flag in the Power Control register. This can occur due to any one of the following:

- · The entry for the interrupt in the vector table lies outside the executable program memory area.
- ISR pointed by the vector table lies outside the executable program memory area.

### Table 11-1. IVT Calculations Summary

IVT Address Calcula	ntion	Interrupt Priority INTCON0 Register, IPEN bit		
		0	1	
	0	IVTBASE	High Priority IVTBASE	
Multivector Enable, MVECEN Configuration bit			Low Priority IVTBASE + 8 words	
	1	IVTBASE + 2*(Vector Number)		

#### 11.3.4 Access Control for IVTBASE Registers

The interrupt controller has an IVTLOCKED bit, which can be set to avoid inadvertent changes to the contents of IVTBASE. Setting and clearing this bit requires a special sequence as an extra precaution against inadvertent changes.

To allow writes to IVTBASE, the interrupts must be disabled (GIEH = 0) and IVTLOCKED bit must be cleared. The user must follow the sequence shown below to clear the IVTLOCKED bit.

```
Example 11-1. IVT UNLOCK SEQUENCE

; Disable Interrupts:
    BCF INTCON0, GIE;

; Bank to IVTLOCK register
    BANKSEL IVTLOCK;
    MOVLW 55h;

; Required sequence, next 4 instructions
    MOVWF IVTLOCK;
    MOVLW AAh;
    MOVWF IVTLOCK;

; Clear IVTLOCKED bit to enable writes
    BCF IVTLOCK, IVTLOCKED;

; Enable Interrupts
    BSF INTCON0, GIE;
```

The user must follow the following sequence to set IVTLOCKED bit.

```
Example 11-2. IVT LOCK SEQUENCE

; Disable Interrupts:
    BCF INTCONO, GIE;

; Bank to IVTLOCK register
    BANKSEL IVTLOCK;
    MOVLW 55h;

; Required sequence, next 4 instructions
    MOVWF IVTLOCK;
    MOVLW AAh;
    MOVWF IVTLOCK;

; Set IVTLOCKED bit to enable writes
    BSF IVTLOCK, IVTLOCKED;

; Enable Interrupts
    BSF INTCONO, GIE;
```

When the IVT1WAY Configuration bit is set, IVTLOCKED bit can be cleared and set only once after a device Reset. The unlock operation will have no effect after the lock sequence is used to set the IVTLOCKED bit. Unlocking is inhibited until a system Reset occurs.

# 11.4 Interrupt Priority

The final priority level for any pending source of interrupt is determined first by the user-assigned priority of that source in the IPRx register, then by the natural order priority within the IVT. The sections below detail the operation of interrupt priorities.

#### 11.4.1 User (Software) Priority

User-assigned interrupt priority is enabled by setting IPEN. Each peripheral interrupt source can be assigned a high-or low-priority level by the user. The user-assignable interrupt priority control bits for each interrupt are located in the IPRx registers, which are device-specific and can be found in the respective data sheet for each device.

The interrupts are serviced based on a predefined interrupt priority scheme detailed below.

- Interrupts set by the user as a high-priority interrupt have higher precedence of execution. High-priority interrupts will override a low-priority request when:
  - 1.1. A low-priority interrupt has been requested or its request is already pending.
  - 1.2. A low and high-priority interrupt are triggered concurrently (i.e., on the same instruction cycle).<sup>(1)</sup>
  - 1.3. A low-priority interrupt was requested and the corresponding Interrupt Service Routine is currently executing. In this case, the lower priority interrupt routine will be interrupted then complete executing after the high-priority interrupt has been serviced.<sup>(2)</sup>
- 2. Interrupts set by the user as low priority have a lower priority of execution and are preempted by any highpriority interrupt.
- 3. Interrupts defined with the same software priority cannot preempt or interrupt each other. Concurrent pending interrupts with the same user priority are resolved using the natural order priority (when vectored interrupts are enabled) or in the order the interrupt flag bits are polled in the ISR (when vectored interrupts are disabled).



#### Important:

- When a high-priority interrupt preempts a concurrent low-priority interrupt, GIEL may be cleared in the high-priority Interrupt Service Routine. If GIEL is cleared, the low-priority interrupt will NOT be serviced, even if it was originally requested. The corresponding interrupt flag needs to be cleared in user code.
- When a high-priority interrupt is requested while a low-priority Interrupt Service Routine is
  executing, GIEL may be cleared in the high-priority Interrupt Service Routine. The pending lowpriority interrupt will resume, even if GIEL is cleared.

## 11.4.2 Natural Order (Hardware) Priority

When vectored interrupts are enabled and more than one interrupt with the same user specified priority level is requested, the priority conflict is resolved by using a method called "Natural Order Priority". Natural order priority is a fixed priority scheme that is based on the IVT.

Table 11-2. Interrupt Vector Priority Table

Vector Number	Interrupt source	Vector Number	Interrupt source
		(cont.)	(cont.)
0x0	Software Interrupt	0x40	U2RX
0x1	HLVD (High/Low-Voltage Detect)	0x41	U2TX
0x2	OSF (Oscillator Fail)	0x42	U2E
0x3	CSW (Clock Switching)	0x43	U2
0x4	TU16A (Universal Timer 16A)	0x44	TMR5
0x5	CLC1 (Configurable Logic Cell)	0x45	TMR5G
0x6	CAN (CAN general)	0x46	CCP2
0x7	IOC (Interrupt-On-Change)	0x47	SCAN
0x8	INT0	0x48	U3RX
0x9	ZCD (Zero-Cross Detection)	0x49	U3TX
0xA	AD (ADC Conversion Complete)	0x4A	U3E
0xB	ACT (Active Clock Tuning)	0x4B	U3
0xC	CM1 (Comparator)	0x4C	_
0xD	SMT1 (Signal Measurement Timer)	0x4D	CLC4
0xE	SMT1PRA	0x4E	PWM4RINT
0xF	SMT1PWA	0x4F	PWM4GINT
0x10	ADT/ADCH1 (ADC Context 1)	0x50	INT2

# **VIC - Vectored Interrupt Controller Module**

continued							
Vector	Interrupt	Vector Number	Interrupt source				
Number	source						
		(cont.)	(cont.)				
0x11	ADCH2 (ADC Context 2)	0x51	CLC5				
0x12	ADCH3 (ADC Context 3)	0x52	CWG2 (Complementary Waveform Generator)				
0x13	ADCH4 (ADC Context 4)	0x53	NCO2				
0x14	DMA1SCNT (Direct Memory Access)	0x54	DMA3SCNT				
0x15	DMA1DCNT	0x55	DMA3DCNT				
0x16	DMA10R	0x56	DMA3OR				
0x17	DMA1A	0x57	DMA3A				
0x18	SPI1RX (Serial Peripheral Interface) SPI1TX	0x58	CCP3				
0x19	SPI1	0x59	CLC6				
0x1A 0x1B	TMR2	0x5A 0x5B	CWG3 TMR4				
0x1C	TMR1	0x5C	DMA4SCNT				
0x1C 0x1D	TMR1G	0x5C	DMA4DCNT				
0x1E	CCP1 (Capture/Compare/PWM)	0x5E	DMA4OR				
0x1E	TMR0	0x5E	DMA4A				
0x10	U1RX	0x60	U4RX				
0x21	U1TX	0x61	U4TX				
0x22	U1E	0x62	U4E				
0x23	U1	0x63	U4				
0x24	CANRX (CAN receive)	0x64	DMA5SCNT				
0x25	CANTX (CAN transmit)	0x65	DMA5DCNT				
0x26	PWM1RINT	0x66	DMA5OR				
0x27	PWM1GINT	0x67	DMA5A				
0x28	SPI2RX	0x68	U5RX				
0x29	SPI2TX	0x69	U5TX				
0x2A	SPI2	0x6A	U5E				
0x2B	TU16B (Universal Timer 16B)	0x6B	U5				
0x2C	TMR3	0x6C	DMA6SCNT				
0x2D	TMR3G	0x6D	DMA6DCNT				
0x2E	PWM2RINT	0x6E	DMA6OR				
0x2F	PWM2GINT	0x6F	DMA6A				
0x30	INT1	0x70	_				
0x31	CLC2	0x71	CLC7				
0x32	CWG1 (Complementary Waveform Generator)	0x72	CM2				
0x33	NCO1 (Numerically Controlled Oscillator)	0x73	NCO3				
0x34	DMA2SCNT	0x74	DMA7SCNT				
0x35	DMA2DCNT	0x75	DMA7DCNT				
0x36	DMA2OR	0x76	DMA7OR				
0x37	DMA2A	0x77	DMA7A				
0x38	I2C1RX	0x78	NVM				
0x39	I2C1TX	0x79	CLC8				
0x3A	I2C1	0x7A	CRC (Cyclic Redundancy Check)				
0x3B	I2C1E	0x7B	TMR6				

# VIC - Vectored Interrupt Controller Module

con	continued								
Vector Number	Interrupt source	Vector Number (cont.)	Interrupt source (cont.)						
0x3C	<del>-</del>	0x7C	DMA8SCNT						
0x3D	CLC3	0x7D	DMA8DCNT						
0x3E	PWM3RINT	0x7E	DMA8OR						
0x3F	PWM3GINT	0x7F	DMA8A						
		0x80 - 0x8F	_						

The natural order priority scheme goes from high-to-low with increasing vector numbers, with 0 being the highest priority and decreasing from there.

For example, when two concurrently occurring interrupt sources that are both designated high priority, using the IPRx register will be resolved using the natural order priority (i.e., the interrupt with a lower corresponding vector number will preempt the interrupt with the higher vector number).

The ability for the user to assign every interrupt source to high- or low-priority levels means that the user program can give an interrupt with a low natural priority, a higher overall priority level.

# 11.5 Interrupt Operation

All pending interrupts are indicated by their respective flag bit being equal to a '1' in the PIRx register. All pending interrupts are resolved using the priority scheme explained in Interrupt Priority section.

Once the interrupt source to be serviced is resolved, the program execution vectors to the resolved interrupt vector addresses, as explained in Interrupt Vector Table section. The vector number is also stored in the WREG register. Most of the flag bits are required to be cleared by the application software, but in some cases, device hardware clears the interrupt automatically. Some flag bits are read-only in the PIRx registers. These flags are a summary of the source interrupts and the corresponding interrupt flags of the source must be cleared.


A valid interrupt can be either a high- or low-priority interrupt when in the main routine or a high-priority interrupt when in a low priority Interrupt Service Routine. Depending on the order of interrupt requests received and their relative timing, the CPU will be in a state of execution indicated by STAT bit

The state machine shown in Figure 11-1 and the subsequent sections detail the execution of interrupts when received in different orders.



**Important:** The state of GIEH/L is not changed by the hardware when servicing an interrupt. The internal state machine is used to keep track of execution states. These bits can be manipulated in the user code, resulting in transferring execution to the main routine and ignoring existing interrupts.


Figure 11-1. Vectored Interrupts State Transition Diagram



## 11.5.1 Serving a High- or Low-Priority Interrupt while the Main Routine Code is Executing

When a high- or low-priority interrupt is requested while the main routine code is executing, the main routine execution is halted and the ISR is addressed. Upon a return from the ISR (by executing the RETFIE instruction), the main routine resumes execution.

Figure 11-2. Interrupt Execution: High/Low-Priority Interrupt while Executing Main Routine




### 11.5.2 Serving a High-Priority Interrupt while a Low-Priority Interrupt is Pending

A high priority interrupt request will always take precedence over any interrupt of a lower priority. The high-priority interrupt is acknowledged first, then the low-priority interrupt is acknowledged. Upon a return from the high-priority ISR (by executing the RETFIE instruction), the low-priority interrupt is serviced.

If any other high-priority interrupts are pending and enabled, they are serviced before servicing the pending low-priority interrupt. If no other high-priority interrupt requests are active, the low-priority interrupt is serviced.

Figure 11-3. Interrupt Execution: High-Priority Interrupt with a Low-Priority Interrupt Pending






# 11.5.3 Preempting Low-Priority Interrupts

Low-priority interrupts can be preempted by high-priority interrupts. While in the low-priority ISR, if a high-priority interrupt arrives, the high-priority interrupt request is generated and the low-priority ISR is suspended, while the high-priority ISR is executed.

After the high-priority ISR is complete and if any other high-priority interrupt requests are not active, the execution returns to the preempted low-priority ISR.

Figure 11-4. Interrupt Execution: High-Priority Interrupt Preempting Low-Priority Interrupts




#### 11.5.4 Simultaneous High- and Low-Priority Interrupts

When both high- and low-priority interrupts are active in the same instruction cycle (i.e., simultaneous interrupt events), both the high- and low-priority requests are generated. The high-priority ISR is serviced first before servicing the low-priority interrupt.

Figure 11-5. Interrupt Execution: Simultaneous High- and Low- Priority Interrupts





# 11.6 Context Saving

The interrupt controller supports a two-level deep context saving system (main routine context and low ISR context). Refer to the state machine shown in Figure 11-6 for details.

The Program Counter (PC) is saved on the dedicated device PC stack. The CPU registers saved include STATUS, WREG, BSR, FSR0/1/2, PRODL/H and PCLATH/U.

After WREG has been saved to the context registers, the resolved vector number of the interrupt source to be serviced is copied into WREG. Context save and restore operation is completed by the interrupt controller based on the current state of the interrupts and the order in which they were sent to the CPU.


Context save/restore works the same way in both states of MVECEN. When IPEN = 0, there is only one level of interrupt active. Hence, only the main context is saved when an interrupt is received.

### 11.6.1 Accessing Shadow Registers

The interrupt controller automatically saves the context information in the shadow registers. Both the saved context values (i.e., main routine and low ISR) can be accessed using the same set of shadow registers. By clearing SHADLO, the CPU register values saved for main routine context can be accessed. Low ISR context is automatically restored to the CPU registers upon exiting the high ISR. Similarly, the main context is automatically restored to the CPU registers upon exiting the low ISR.

The shadow registers are readable and writable, so if the user desires to modify the context, then the corresponding shadow register should be modified and the value will be restored when exiting the ISR. Depending on the user's application, other registers may also need to be saved.

Figure 11-6. Context Save State Machine Diagram



# 11.7 Returning from Interrupt Service Routine (ISR)

The "Return from Interrupt" instruction (RETFIE) is used to mark the end of an ISR.

When the RETFIE 1 instruction is executed, the PC is loaded with the saved PC value from the top of the PC stack. Saved context is also restored with the execution of this instruction. Thus, execution returns to the state of operation that existed before the interrupt occurred.

When the RETFIE 0 instruction is executed, the saved context is not restored back to the registers.


# 11.8 Interrupt Latency

When MVECEN = 1, there is a fixed latency of three instruction cycles between the completion of the instruction active when the interrupt occurred, and the first instruction of the Interrupt Service Routine. Figure 11-7, Figure 11-8, and Figure 11-9 illustrate the sequence of events when a peripheral interrupt is asserted, when the last executed instruction is one-cycle, two-cycle and three-cycle, respectively.

After the Interrupt Flag Status bit is set, the current instruction completes executing. In the first latency cycle, the contents of the PC, STATUS, WREG, BSR, FSR0/1/2, PRODL/H and PCLATH/U registers are context saved and the IVTBASE + Vector number is calculated. In the second latency cycle, the PC is loaded with the calculated vector table address for the interrupt source and the starting address of the ISR is fetched. In the third latency cycle, the PC is loaded with the ISR address. All the latency cycles are executed as NOP instructions.


When MVECEN = 0, the interrupt controller requires two clock cycles to vector to the ISR from the main routine. Note that as this mode requires additional software to determine which interrupt source caused the interrupt, the actual latency between the trigger and the beginning of the specific ISR for each individual interrupt will be longer than two clock cycles and will vary, when not using vectored interrupts.

Figure 11-7. Interrupt Timing Diagram: One-Cycle Instruction



Note: 1. Instruction @ X is a One-cycle Instruction

Figure 11-8. Interrupt Timing Diagram: Two-Cycle Instruction



Note: 1. Instruction @ Y is a Two-cycle Instruction

Rev. 10-000 269D 1/4/201 9

. 10-000 289C 1/4/201 9 (1) (2) (3) (4) (5) (6) (7)(8) (9) (10) (11) (12) System Ćlock Program Z+2 Z+2 Z+2 0x82 0x218 0x21A 0x21C Counter Instruction Inst @ Z<sup>(1)</sup> Inst @ Z<sup>(1)</sup> Inst @ Z<sup>(1)</sup> **FNOP** FNOP **FNOP FNOP** Inst @ Z+2 Inst @ Z+4 0x218 BCF Register 0x21A RETFIE Routine MAIN **FNOP** MAIN **FNOP IVTBASE** 0x80 Vector 1 Number Program Memor 0x86 0x82 Interrupt Location = Interrupt vector table entry << 2 = 0x86 << 2 = 0x218

Figure 11-9. Interrupt Timing Diagram: Three-Cycle Instruction

Note: 1. Instruction @ Z is a Three-cycle Instruction


### 11.8.1 Aborting Interrupts

If the last instruction before the interrupt controller vectors to the ISR from the main routine clears the GIE, PIE, or PIR bit associated with the interrupt, the controller executes one forced NOP instruction cycle before it returns to the main routine.

Figure 11-10 illustrates the sequence of events when a peripheral interrupt is asserted and then cleared on the last executed instruction cycle.

If the GIE, PIE or PIR bit associated with the interrupt is cleared prior to vectoring to the ISR, then the controller continues executing the main routine.

Figure 11-10. Interrupt Timing Diagram: Aborting Interrupts



Note: 1: Inst @ X clears the interrupt flag, Example BCF INTCON0, GIE

# 11.9 Interrupt Setup Procedure

1. When using interrupt priority levels, set IPEN and then select the user-assigned priority level for the interrupt source by writing the control bits in the appropriate IPRx control register.



**Important:** At a device Reset, the IPRx registers are initialized such that all user interrupt sources are assigned to high priority.

- 2. Clear the Interrupt Flag Status bit associated with the peripheral in the associated PIRx STATUS register.
- 3. Enable the interrupt source by setting the interrupt enable control bit associated with the source in the appropriate PIEx register.
- 4. If the vector table is used (MVECEN = 1), then setup the start address for the Interrupt Vector Table using IVTBASE. See Interrupt Vector Table Contents section for more details.
- 5. Once IVTBASE is written to, set the interrupt enable bits in INTCON0.
- 6. An example of setting up interrupts and ISRs using assembly and C can be found in Example 11-3 and Example 11-4.

### Example 11-3. Setting up Vectored Interrupts using MPASM

```
; Each ISR routine must have a predetermined origin otherwise there will be
; an assembly error because the address is not determined until link time
; which is too late to do the divide by 4 math on the address.
; Predetermined addresses must be evenly divisible by 4.
ISRSW CODE 0x3E00
; SW interrupt service code here.
   BANKSEL
              PIR0
    BCF
             PIRO, SWIF
   RETFIE
              FAST
ISRHLVD CODE 0x3E40
; HLVD interrupt service code here.
   BANKSEL PIRO
   BCF
              PIRO, HLVDIF
   RETETE
             FAST
ISROSF
       CODE 0x3E60
; OSF interrupt service code here.
   BANKSEL PIRO
   BCF
              PTRO. OSFTF
   RETFIE FAST
   ; Disable all interrupts
              INTCONO, GIE, ACCESS
    ; Set IVTBASE (optional - default is 0x000008)
          IVTBASEU, ACCESS
               0x3F
   MOVLW
              IVTBASEH, ACCESS
   MOVWF
   CLRF
              IVTBASEL, ACCESS
    ; Clear any interrupt flags before enabling interrupts
             PIR0
   BANKSEL
   BCF
               PIRO, SWIF
   BCF
              PIRO, HLVDIF
               PIRO, OSFIF
    ; Enable interrupts
   BANKSEL PIE0
               PIEO, SWIE
        PIEU, SWIE
PIEO, HLVDIE
PIEO, OSFIE
   BSF
    ; Set interrupt priorities if necessary
   BANKSEL IPRO
              INTCONO, IPEN_INTCONO, ACCESS ; Enable interrupt property ; Make HLVD interrupt low priority
   BSF
                                              ; Enable interrupt priority
   BCF
    ; Enable interrupts
   BSF INTCONO, GIEH, ACCESS
               INTCONO, GIEL, ACCESS
   RETURN 1
; Save SWISR in vector table (IVTBASE+0*2)
ISR1 CODE 0x3F00
             (0x3E40>>2)
                          ; (SWISR/4)
       DW
; Save HLVDISR in vector table (IVTBASE+1*2)
ISR2 CODE 0x3F02
             (0x3E60>>2)
                                ; (HLVDISR/4)
; Save CLC2ISR in vector table (IVTBASE+2*2)
ISR3 CODE 0x3F04
       DW (0x3E00>>2)
                                ; (OSFISR/4)
```

### Example 11-4. Setting up Vectored Interrupts using XC8

```
// NOTE 1: If IVTBASE is changed from its default value of 0x000008, then the
 // "base(...)" argument must be provided in the ISR. Otherwise the vector % \left( \frac{1}{2}\right) =\frac{1}{2}\left( \frac{1}{2}\right) =\frac
// table will be placed at 0x0008 by default regardless of the IVTBASE value.
 // NOTE 2: When MVECEN=0 and IPEN=1, a separate argument as "high priority"
 // or "low_priority" can be used to distinguish between the two ISRs.
 // If the argument is not provided, the ISR is considered high priority
// by default.
// NOTE 3: Multiple interrupts can be handled by the same ISR if they are // specified in the "irq(...)" argument. Ex: irq(IRQ_SW, IRQ_HLVD)
void interrupt(irq(IRQ SW), base(0x3008)) SW ISR(void)
                   PIRObits.SWIF = 0; // Clear the interrupt flag LATCbits.LATC0 ^= 1; // ISR code goes here
void interrupt(irq(default), base(0x3008)) DEFAULT ISR(void)
                     // Unhandled interrupts go here
void INTERRUPT Initialize (void)
                   INTCONObits.GIEH = 1;  // Enable high priority interrupts
                  INTCONOBITS.GIEL = 1;  // Enable low priority interrupts
INTCONObits.IPEN = 1;  // Enable interrupt priority
PIEObits.SWIE = 1;  // Enable SW interrupt
PIEObits.HLVDIE = 1;  // Enable HLVD interrupt
IPRObits.SWIP = 0;  // Make SW interrupt low priority
                    // Change IVTBASE if required
                   IVTBASEU = 0 \times 00; // Optional
                    IVTBASEH = 0 \times 30;
                                                                                                                                                 // Default is 0x000008
                   IVTBASEL = 0 \times 08;
```

# 11.10 External Interrupt Pins

Devices may have several external interrupt sources that can be assigned to pins on different ports based on PPS settings. Refer to the "PPS - Peripheral Pin Select Module" chapter for possible routing options for these external interrupts. The external interrupt sources are edge-triggered. If the corresponding INTxEDG bit in INTCON0 is set, the interrupt is triggered by a rising edge. If the bit is clear, the trigger is on the falling edge.

When a valid edge appears on the INTx pin, the corresponding flag bit (INTxF in the PIRx registers) is set. This interrupt can be disabled by clearing the corresponding enable bit, INTxE. The flag bit INTxF must be cleared by software in the Interrupt Service Routine before re-enabling the interrupt.

All external interrupts can wake up the processor from Idle or Sleep modes if bit INTxE was set prior to going into those modes. If GIE/GIEH bit is set, the processor will branch to the interrupt vector following wake-up. Interrupt priority is determined by the value contained in the respective INTxIP interrupt priority bits of the IPRx registers.

# 11.11 Wake-up from Sleep

The interrupt controller provides a wake-up request to the CPU whenever an interrupt event occurs, if the interrupt event is enabled. This occurs regardless of whether the part is in Run, Idle/Doze or Sleep modes. The status of GIE/GIEH and GIEL bits have no effect on the wake-up request. This wake-up request is asynchronous to all clocks.

# 11.12 Interrupt Compatibility

When the MVECEN bit is cleared, the IVT feature is disabled and interrupts are compatible with previous high performance 8-bit PIC18 microcontroller devices. In this mode, the IVT priority has no effect.

# PIC18F26/46/56Q84

# **VIC - Vectored Interrupt Controller Module**

When IPEN is also cleared, the interrupt priority feature is disabled and interrupts are compatible with PIC16 microcontroller midrange devices. All interrupts branch to address 0008h, since the interrupt priority is disabled.

11.13 Register Definitions: Interrupt Control

### 11.13.1 INTCON0

Name: INTCON0 Offset: 0x4D6

Interrupt Control Register 0

Bit	7	6	5	4	3	2	1	0
	GIE/GIEH	GIEL	IPEN			INT2EDG	INT1EDG	INT0EDG
Access	R/W	R/W	R/W			R/W	R/W	R/W
Reset	0	0	0			1	1	1

#### Bit 7 - GIE/GIEH Global Interrupt Enable

Dit / CIL/	OILII CIODA	in interrupt Endole
Value	Condition	Description
1	IPEN = 0	Enables all masked interrupts
0	IPEN = 0	Disables all interrupts
1	IPEN = 1	Enables all unmasked high-priority interrupts: bit also needs to be set for enabling low-priority interrupts
0	IPEN = 1	Disables all interrupts

### Bit 6 - GIEL Global Low Priority Interrupt Enable

Value	Condition	Description
n	IPEN = 0	Reserved, read as 0
1	IPEN = 1	Enables all unmasked low-priority interrupts, GIEH also needs to be set for low priority interrupts
0	IPEN = 1	Disables all low priority interrupts

### Bit 5 - IPEN Interrupt Priority Enable

Vá	alue	Description
1		Enable priority levels on interrupts
0		Disable priority levels on interrupts, all interrupts are treated as high priority interrupts

#### Bit 2 - INT2EDG External Interrupt 2 Edge Select

Value	Description
1	Interrupt on rising edge of INT2 pin
0	Interrupt on falling edge of INT2 pin

# Bit 1 – INT1EDG External Interrupt 1 Edge Select

Value	Description
1	Interrupt on rising edge of INT1 pin
0	Interrupt on falling edge of INT1 pin

#### Bit 0 - INT0EDG External Interrupt 0 Edge Select

Value	Description
1	Interrupt on rising edge of INT0 pin
0	Interrupt on falling edge of INT0 pin

## 11.13.2 INTCON1

Name: INTCON1 Offset: 0x4D7

Interrupt Control Register 1

Bit	7	6	5	4	3	2	1	0
	STAT[1:0]							
Access	R	R						
Reset	Λ	0						

## Bits 7:6 - STAT[1:0] Interrupt State Status

Value	Description
11	High priority ISR executing, high-priority interrupt was received while a low-priority ISR was executing
10	High priority ISR executing, high-priority interrupt was received in main routine
01	Low priority ISR executing, low-priority interrupt was received in main routine
00	Main routine executing

### 11.13.3 IVTBASE

Name: IVTBASE Offset: 0x45D

Interrupt Vector Table Base Address Register

Bit	23	22	21	20	19	18	17	16		
				IVTBASEU[4:0]						
Access				R/W	R/W	R/W	R/W	R/W		
Reset				0	0	0	0	0		
Bit	15	14	13	12	11	10	9	8		
	IVTBASEH[7:0]									
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		
Bit	7	6	5	4	3	2	1	0		
	IVTBASEL[7:0]									
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		

Bits 20:16 - IVTBASEU[4:0] Interrupt Vector Table Base Address Most Significant 5 bits

Bits 15:8 - IVTBASEH[7:0] Interrupt Vector Table Base Address Middle 8 bits

Bits 7:0 - IVTBASEL[7:0] Interrupt Vector Table Base Address Least Significant 8 bits

### 11.13.4 IVTAD

Name: IVTAD Offset: 0x45A

Interrupt Vector Table Address

Bit	23	22	21	20	19	18	17	16		
				IVTADU[4:0]						
Access				R	R	R	R	R		
Reset				0	0	0	0	0		
Bit	15	14	13	12	11	10	9	8		
	IVTADH[7:0]									
Access	R	R	R	R	R	R	R	R		
Reset	0	0	0	0	0	0	0	0		
Bit	7	6	5	4	3	2	1	0		
	IVTADL[7:0]									
Access	R	R	R	R	R	R	R	R		
Reset	0	0	0	0	0	0	0	0		

Bits 20:16 - IVTADU[4:0] Interrupt Vector Table Address Most Significant 5 bits

Bits 15:8 - IVTADH[7:0] Interrupt Vector Table Address Middle 8 bits

Bits 7:0 - IVTADL[7:0] Interrupt Vector Table Address Least Significant 8 bits

# 11.13.5 IVTLOCK

Name: IVTLOCK Offset: 0x459

Interrupt Vector Table Lock Register



# Bit 0 - IVTLOCKED IVT Registers Lock(1,2)

Value	Description
1	IVTBASE Registers are locked and cannot be written
0	IVTBASE Registers can be modified by write operations

- 1. The IVTLOCKED bit can only be set or cleared after the unlock sequence in Example 11-1.
- 2. If IVT1WAY = 1, the IVTLOCKED bit cannot be cleared after it has been set.

# 11.13.6 SHADCON

Name: SHADCON Offset: 0x376

**Shadow Control Register** 



Bit 0 - SHADLO Interrupt Shadow Register Access Switch

Value	Description		
1 Access Main Context for Interrupt Shadow registers			
0	Access Low-Priority Interrupt Context for Interrupt Shadow registers		

# 11.13.7 PIE0

Name: PIE0 Offset: 0x49E

Peripheral Interrupt Enable Register 0

Bit	7	6	5	4	3	2	1	0
	IOCIE	CANIE	CLC1IE	TU16AIE	CSWIE	OSFIE	HLVDIE	SWINTIE
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

### Bit 7 - IOCIE Interrupt-on-Change Enable

Value	Description
1	Enabled
0	Disabled

## Bit 6 - CANIE CAN Main Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 5 - CLC1IE CLC1 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 4 - TU16AIE Universal Timer 16A interrupt enable

1	Value	Description
	1	Enabled
	0	Disabled

## Bit 3 - CSWIE Clock Switch Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 2 - OSFIE Oscillator Failure Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 1 - HLVDIE High/Low-Voltage Detect Interrupt Enable

Value	Description		
1	Enabled		
0	Disabled		

#### Bit 0 - SWINTIE Software Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# 11.13.8 PIE1

Name: PIE1 Offset: 0x49F

Peripheral Interrupt Enable Register 1

Bit	7	6	5	4	3	2	1	0
	SMT1PWAIE	SMT1PRAIE	SMT1IE	CM1IE	ACTIE	ADIE	ZCDIE	INT0IE
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

# Bit 7 - SMT1PWAIE SMT1 Pulse-Width Acquisition Interrupt Enable

Value	Description	
1	Enabled	
0	Disabled	

## Bit 6 - SMT1PRAIE SMT1 Period Acquisition Interrupt Enable

П	Value	Description
	1	Enabled
	0	Disabled

# Bit 5 - SMT1IE SMT1 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 4 - CM1IE CMP1 Interrupt Enable

D.C + 0.0	164 OM Timorapt Endoic				
Value	Description				
1	Enabled				
0	Disabled				

# Bit 3 - ACTIE Active Clock Tuning Interrupt Enable

Value	Description		
1	Enabled		
0	Disabled		

# Bit 2 - ADIE ADC Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 1 - ZCDIE ZCD Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 0 - INTOIE External Interrupt 0 Interrupt Enable

Value	Description		
1	Enabled		
0	Disabled		

# 11.13.9 PIE2

Name: PIE2 Offset: 0x4A0

Peripheral Interrupt Enable Register 2

Bit	7	6	5	4	3	2	1	0
	DMA1AIE	DMA10RIE	DMA1DCNTIE	DMA1SCNTIE	ADCH4IE	ADCH3IE	ADCH2IE	ADCH1IE
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

# Bit 7 - DMA1AIE DMA1 Abort Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 6 - DMA1ORIE DMA1 Overrun Interrupt Enable

Value	Description
0	Enabled
1	Disabled

# Bit 5 - DMA1DCNTIE DMA1 Destination Count Interrupt Enable

	/alue	Description
(	)	Enabled
-	L	Disabled

### Bit 4 - DMA1SCNTIE DMA1 Source Count Interrupt Enable

Value	Description
0	Enabled
1	Disabled

## Bit 3 - ADCH4IE ADC Context 4 Threshold Interrupt Enable

V	'alue	Description
0		Enabled
1		Disabled

# Bit 2 - ADCH3IE ADC Context 3 Threshold Interrupt Enable

Value	Description
0	Enabled
1	Disabled

## Bit 1 - ADCH2IE ADC Context 2 Threshold Interrupt Enable

Va	lue	Description
0		Enabled
1		Disabled

#### Bit 0 - ADCH1IE ADC Context 1 Threshold Interrupt Enable

Value	Description	
0	Enabled	
1	Disabled	

# 11.13.10 PIE3

Name: PIE3 Offset: 0x4A1

Peripheral Interrupt Enable Register 3

Bit	7	6	5	4	3	2	1	0
	TMR0IE	CCP1IE	TMR1GIE	TMR1IE	TMR2IE	SPI1IE	SPI1TXIE	SPI1RXIE
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R
Reset	0	0	0	0	0	0	0	0

# Bit 7 - TMR0IE TMR0 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 6 - CCP1IE CCP1 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

### Bit 5 - TMR1GIE TMR1 Gate Interrupt Enable

Value	Description
1	Enabled
0	Disabled

### Bit 4 - TMR1IE TMR1 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 3 - TMR2IE TMR2 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

#### Bit 2 - SPI1IE SPI1 Interrupt Enable

	2.1.2 9.1.1.2 9.1.1 miorialy 2.1.4.1.		
Value	Description		
1	Enabled		
0	Disabled		

## Bit 1 - SPI1TXIE SPI1 Transmit Interrupt Enable

Value	Description
1	Enabled
0	Disabled

#### Bit 0 - SPI1RXIE SPI1 Receive Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# 11.13.11 PIE4

Name: PIE4 Offset: 0x4A2

Peripheral Interrupt Enable Register 4

Bit	7	6	5	4	3	2	1	0
	PWM1IE	PWM1PIE	CANTIE	CANRIE	U1IE	U1EIE	U1TXIE	U1RXIE
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

# Bit 7 - PWM1IE PWM1 Parameter Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 6 - PWM1PIE PWM1 Period Interrupt Enable

Value	Description
1	Enabled
0	Disabled

### Bit 5 - CANTIE CAN Transmit Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 4 - CANRIE CAN Receive Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 3 - U1IE UART1 Interrupt Enable

Valu	ıe	Description
1		Enabled
0		Disabled

# Bit 2 - U1EIE UART1 Framing Error Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 1 - U1TXIE UART1 Transmit Interrupt Enable

<b>Value</b>	Description
1	Enabled
)	Disabled

#### Bit 0 - U1RXIE UART 1 Receive Interrupt Enable

	<u> </u>
Value	Description
1	Enabled
0	Disabled

# 11.13.12 PIE5

Name: PIE5 Offset: 0x4A3

Peripheral Interrupt Enable Register 5

Bit	7	6	5	4	3	2	1	0
	PWM2IE	PWM2PIE	TMR3GIE	TMR3IE	TU16BIE	SPI2IE	SPI2TXIE	SPI2RXIE
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

### Bit 7 - PWM2IE PWM2 Parameter Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 6 - PWM2PIE PWM2 Period Interrupt Enable

Value	Description
1	Enabled
0	Disabled

### Bit 5 - TMR3GIE TMR3 Gate Interrupt Enable

Value	Description
1	Enabled
0	Disabled

### Bit 4 - TMR3IE TMR3 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 3 - TU16BIE 16-bit Universal Timer B Interrupt Enable

V	alue	Description
1		Enabled
0		Disabled

# Bit 2 - SPI2IE SPI2 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 1 - SPI2TXIE SPI2 Transmit Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 0 - SPI2RXIE SPI2 Receive Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# 11.13.13 PIE6

Name: PIE6 Offset: 0x4A4

Peripheral Interrupt Enable Register 6

Bit	7	6	5	4	3	2	1	0
	DMA2AIE	DMA2ORIE	DMA2DCNTIE	DMA2SCNTIE	NCO1IE	CWG1IE	CLC2IE	INT1IE
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

# Bit 7 - DMA2AIE DMA2 Abort Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 6 - DMA2ORIE DMA2 Overrun Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 5 - DMA2DCNTIE DMA2 Destination Count Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 4 - DMA2SCNTIE DMA2 Source Count Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 3 - NCO1IE NCO1 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 2 - CWG1IE CWG1 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 1 - CLC2IE CLC2 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 0 - INT1IE External Interrupt 1 Interrupt Enable

Value	Description		
1	Enabled		
0	Disabled		

# 11.13.14 PIE7

Name: PIE7 Offset: 0x4A5

Peripheral Interrupt Enable Register 7

Bit	7	6	5	4	3	2	1	0
	PWM3IE	PWM3PIE	CLC3IE		I2C1EIE	I2C1IE	I2C1TXIE	I2C1RXIE
Access	R/W	R/W	R/W		R/W	R/W	R/W	R/W
Reset	0	0	0		0	0	0	0

# Bit 7 - PWM3IE PWM3 Parameter Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 6 - PWM3PIE PWM3 Period Interrupt Enable

Value	Description
1	Enabled
0	Disabled

### Bit 5 - CLC3IE CLC3 Interrupt Enable

١	/alue	Description
1	•	Enabled
C	)	Disabled

# Bit 3 – I2C1EIE I2C1 Error Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 2 - I2C1IE I2C1 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 1 - I2C1TXIE I2C1 Transmit Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 0 - I2C1RXIE I2C1 Receive Interrupt Enable

Va	alue	Description
1		Enabled
0		Disabled

# 11.13.15 PIE8

Name: PIE8 Offset: 0x4A6

Peripheral Interrupt Enable Register 8

Bit	7	6	5	4	3	2	1	0
	SCANIE	CCP2IE	TMR5GIE	TMR5IE	U2IE	U2EIE	U2TXIE	U2RXIE
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

# Bit 7 - SCANIE Memory Scanner Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 6 - CCP2IE CCP2 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

### Bit 5 - TMR5GIE TMR5 Gate Interrupt Enable

Value	Description
1	Enabled
0	Disabled

### Bit 4 - TMR5IE TMR5 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 3 - U2IE UART2 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 2 – U2EIE UART2 Framing Error Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 1 - U2TXIE UART2 Transmit Interrupt Enable

<b>Value</b>	Description
1	Enabled
)	Disabled

#### Bit 0 - U2RXIE UART2 Receive Interrupt Enable

	· · · · · · · · · · · · · · · · · · ·
Value	Description
1	Enabled
0	Disabled

# 11.13.16 PIE9

Name: PIE9 Offset: 0x4A7

Peripheral Interrupt Enable Register 9

Bit	7	6	5	4	3	2	1	0
	PWM4IE	PWM4PIE	CLC4IE		U3IE	U3EIE	U3TXIE	U3RXIE
Access	R/W	R/W	R/W		R/W	R/W	R/W	R/W
Reset	0	0	0		0	0	0	0

# Bit 7 - PWM4IE PWM4 Parameter Interrupt Enable

Value	Description
1	Enabled
0	Disabled

### Bit 6 - PWM4PIE PWM4 Period Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 5 - CLC4IE CLC4 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 3 - U3IE UART3 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 2 - U3EIE UART3 Framing Error Interrupt Enable

Value Description	
1	Enabled
0	Disabled

# Bit 1 - U3TXIE UART3 Transmit Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 0 - U3RXIE UART3 Receive Interrupt Enable

	<b>V</b> alue	Description
	1	Enabled
(	)	Disabled

# 11.13.17 PIE10

Name: PIE10 Offset: 0x4A8

Peripheral Interrupt Enable Register 10

Bit	7	6	5	4	3	2	1	0
	DMA3AIE	DMA3ORIE	DMA3DCNTIE	DMA3SCNTIE	NCO2IE	CWG2IE	CLC5IE	INT2IE
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

# Bit 7 - DMA3AIE DMA3 Abort Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 6 - DMA3ORIE DMA3 Overrun Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 5 - DMA3DCNTIE DMA3 Destination Count Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 4 - DMA3SCNTIE DMA3 Source Count Interrupt Enable

1	Value	Description
	1	Enabled
	0	Disabled

## Bit 3 - NCO2IE NCO2 Interrupt Enable

ĺ	Value	Description
	1	Enabled
	0	Disabled

# Bit 2 - CWG2IE CWG2 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 1 - CLC5IE CLC5 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 0 - INT2IE External Interrupt 2 Interrupt Enable

Value	Description		
1	Enabled		
0	Disabled		

# 11.13.18 PIE11

Name: PIE11 Offset: 0x4A9

Peripheral Interrupt Enable Register 11

Bit	7	6	5	4	3	2	1	0
	DMA4AIE	DMA4ORIE	DMA4DCNTIE	DMA4SCNTIE	TMR4IE	CWG3IE	CLC6IE	CCP3IE
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

# Bit 7 - DMA4AIE DMA4 Abort Interrupt Enable

Value	Description
1	Enabled
0	Disabled

### Bit 6 - DMA4ORIE DMA4 Overrun Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 5 - DMA4DCNTIE DMA4 Destination Count Interrupt Enable

1	Value	Description
	1	Enabled
	0	Disabled

# Bit 4 - DMA4SCNTIE DMA4 Source Count Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 3 - TMR4IE TMR4 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 2 - CWG3IE CWG3 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 1 - CLC6IE CLC6 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

#### Bit 0 - CCP3IE CCP3 Interrupt Enable

	· • • • · · · · · · · · · · · · · · ·
Value	Description
1	Enabled
0	Disabled

# 11.13.19 PIE12

Name: PIE12 Offset: 0x4AA

Peripheral Interrupt Request Register 12

Bit	7	6	5	4	3	2	1	0
	DMA5AIE	DMA5ORIE	DMA5DCNTIE	DMA5SCNTIE	U4IE	U4EIE	U4TXIE	U4RXIE
Access	R/W	R/W/HS	R/W/HS	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

# Bit 7 - DMA5AIE DMA5 Abort Interrupt Enable

Value	Description
1	Enabled
0	Disabled

### Bit 6 - DMA5ORIE DMA5 Overrun Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 5 - DMA5DCNTIE DMA5 Destination Count Interrupt Enable

1	/alue	Description
1		Enabled
C		Disabled

# Bit 4 - DMA5SCNTIE DMA5 Source Count Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 3 - U4IE UART 4 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 2 - U4EIE UART4 Framing Error Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 1 - U4TXIE UART4 Transmit Interrupt Enable

<b>Value</b>	Description
1	Enabled
)	Disabled

#### Bit 0 - U4RXIE UART4 Receive Interrupt Enable

	· · · · · · · · · · · · · · · · · · ·
Value	Description
1	Enabled
0	Disabled

# 11.13.20 PIE13

Name: PIE13 Offset: 0x4AB

Peripheral Interrupt Enable Register 13

Bit	7	6	5	4	3	2	1	0
	DMA6AIE	DMA6ORIE	DMA6DCNTIE	DMA6SCNTIE	U5IE	U5EIE	U5TXIE	U5RXIE
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

# Bit 7 - DMA6AIE DMA6 Abort Interrupt Enable

Value	Description
1	Enabled
0	Disabled

### Bit 6 - DMA6ORIE DMA6 Overrun Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 5 - DMA6DCNTIE DMA6 Destination Count Interrupt Enable

1	/alue	Description
1		Enabled
C		Disabled

# Bit 4 - DMA6SCNTIE DMA6 Source Count Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 3 - U5IE UART5 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 2 - U5EIE UART5 Framing Error Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 1 - U5TXIE UART5 Transmit Interrupt Enable

<b>Value</b>	Description
1	Enabled
)	Disabled

#### Bit 0 - U5RXIE UART5 Receive Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# 11.13.21 PIE14

Name: PIE14 Offset: 0x4AC

Peripheral Interrupt Enable Register 14

Bit	7	6	5	4	3	2	1	0
	DMA7AIE	DMA7ORIE	DMA7DCNTIE	DMA7SCNTIE	NCO3IE	CM2IE	CLC7IE	
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	0	0	0	0	0	0	0	

# Bit 7 - DMA7AIE DMA7 Abort Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 6 - DMA7ORIE DMA7 Overrun Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 5 - DMA7DCNTIE DMA7 Destination Count Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 4 - DMA7SCNTIE DMA7 Source Count Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 3 - NCO3IE NCO3 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 2 - CM2IE CMP2 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 1 - CLC7IE CLC7 Interrupt Enable

٧	'alue	Description
1		Enabled
0		Disabled

# 11.13.22 PIE15

Name: PIE15 Offset: 0x4AD

Peripheral Interrupt Enable Register 15

Bit	7	6	5	4	3	2	1	0
	DMA8AIE	DMA8ORIE	DMA8DCNTIE	DMA8SCNTIE	TMR6IE	CRCIE	CLC8IE	NVMIE
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

# Bit 7 - DMA8AIE DMA8 Abort Interrupt Enable

Value	Description
1	Enabled
0	Disabled

### Bit 6 - DMA8ORIE DMA8 Overrun Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 5 - DMA8DCNTIE DMA8 Destination Count Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 4 - DMA8SCNTIE DMA8 Source Count Interrupt Enable

1	Value	Description
	1	Enabled
	0	Disabled

## Bit 3 - TMR6IE TMR6 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

# Bit 2 - CRCIE CRC Interrupt Enable

Value	Description
1	Enabled
0	Disabled

## Bit 1 - CLC8IE CLC8 Interrupt Enable

Value	Description
1	Enabled
0	Disabled

#### Bit 0 - NVMIE NVM Interrupt Enable

	····= ···········
Value	Description
1	Enabled
0	Disabled

# 11.13.23 PIR0

Name: PIR0 Offset: 0x4AE

Peripheral Interrupt Request Register 0

Bit	7	6	5	4	3	2	1	0
	IOCIF	CANIF	CLC1IF	TU16AIF	CSWIF	OSFIF	HLVDIF	SWIF
Access	R	R	R/W/HS	R	R/W/HS	R/W/HS	R/W/HS	R/W
Reset	0	0	0	0	0	0	0	0

# Bit 7 - IOCIF Interrupt-on-Change Interrupt Flag<sup>(2)</sup>

Value	Description			
1	Interrupt has occ	curred		
0	Interrupt event h	as not oc	curred	

## Bit 6 - CANIF CAN Main Interrupt Flag

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

# Bit 5 - CLC1IF CLC1 Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

# Bit 4 - TU16AIF Universal Timer 16A interrupt flag

Valu	ıe	Description
1		Interrupt has occurred
0		Interrupt event has not occurred

# Bit 3 - CSWIF Clock Switch Interrupt Flag(3)

V	alue	Description
1		Interrupt has occurred (must be cleared by software)
0		Interrupt event has not occurred

# Bit 2 - OSFIF Oscillator Failure Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

# Bit 1 - HLVDIF High/Low-Voltage Detect Interrupt Flag

					<u> </u>
Value	Description				
1	Interrupt has	occurred (m	ust be clear	ed by	y software)
0	Interrupt ever	nt has not oc	curred		

# Bit 0 - SWIF Software Interrupt Flag

Value	Description
1	Interrupt will trigger (bit is set and cleared by user software)
0	Interrupt event has not occurred

# PIC18F26/46/56Q84

# **VIC - Vectored Interrupt Controller Module**

- Interrupt flag bits get set when an interrupt condition occurs, regardless of the state of its corresponding enable bit, or the global enable bit. User software should ensure the appropriate Interrupt Flag bits are clear prior to enabling an interrupt.
- 2. IOCIF is a read-only bit. To clear the interrupt condition, all bits in the IOCxF registers must be cleared
- 3. The CSWIF interrupt will not wake the system from Sleep. The system will Sleep until another interrupt causes the wake-up.

# 11.13.24 PIR1

Name: PIR1 Offset: 0x4AF

Peripheral Interrupt Request Register 1

Bit	7	6	5	4	3	2	1	0
	SMT1PWAIF	SMT1PRAIF	SMT1IF	CM1IF	ACTIF	ADIF	ZCDIF	INT0IF
Access	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS
Reset	0	0	0	0	0	0	0	0

# Bit 7 - SMT1PWAIF SMT1 Pulse-Width Acquisition Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

## Bit 6 - SMT1PRAIF SMT1 Period Acquisition Interrupt Flag

Va	alue	Description
1		Interrupt has occurred (must be cleared by software)
0		Interrupt event has not occurred

# Bit 5 - SMT1IF SMT1 Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

# Bit 4 - CM1IF CMP1 Interrupt Flag

٧	'alue	Description
1		Interrupt has occurred (must be cleared by software)
0		Interrupt event has not occurred

## Bit 3 - ACTIF Active Clock Tuning Interrupt Flag

	<b>V</b> alue	Description
	1	Interrupt has occurred (must be cleared by software)
(	)	Interrupt event has not occurred

# Bit 2 - ADIF ADC Interrupt Flag

Value	Description		
1	Interrupt has occurred (must be cleared by software)		
0	Interrupt event has not occurred		

# Bit 1 - ZCDIF ZCD Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

# Bit 0 - INTOIF External Interrupt 0 Interrupt Flag<sup>(2)</sup>

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

# PIC18F26/46/56Q84

# **VIC - Vectored Interrupt Controller Module**

- Interrupt flag bits get set when an interrupt condition occurs, regardless of the state of its corresponding enable bit, or the global enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.
- 2. The external interrupt GPIO pin is selected by the INTxPPS register.

# 11.13.25 PIR2

Name: PIR2 Offset: 0x4B0

Peripheral Interrupt Request Register 2

Bit	7	6	5	4	3	2	1	0
	DMA1AIF	DMA10RIF	DMA1DCNTIF	DMA1SCNTIF	ADCH4IF	ADCH3IF	ADCH2IF	ADCH1IF
Access	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

# Bit 7 - DMA1AIF DMA1 Abort Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

#### Bit 6 - DMA1ORIF DMA1 Overrun Interrupt Flag

Value	Description
0	Interrupt event has not occurred
1	Interrupt has occurred

# Bit 5 - DMA1DCNTIF DMA1 Destination Count Interrupt Flag

Val	lue	Description
0		Interrupt event has not occurred
1		Interrupt has occurred

### Bit 4 - DMA1SCNTIF DMA1 Source Count Interrupt Flag

Value	Description
0	Interrupt event has not occurred
1	Interrupt has occurred

## Bit 3 - ADCH4IF ADC Context 4 Threshold Interrupt Flag

Va	alue	Description
0		Interrupt event has not occurred
1		Interrupt has occurred

# Bit 2 - ADCH3IF ADC Context 3 Threshold Interrupt Flag

Value	Description
0	Interrupt event has not occurred
1	Interrupt has occurred

## Bit 1 - ADCH2IF ADC Context 2 Threshold Interrupt Flag

Value	Description
0	Interrupt event has not occurred
1	Interrupt has occurred

#### Bit 0 - ADCH1IF ADC Context 1 Threshold Interrupt Flag

	210 TESTIN TES CONCORT THEORIGIA MICHAPIT TAG					
Value	Description					
0	Interrupt event has not occurred					
1	Interrupt has occurred					

#### Note:

1. Interrupt flag bits get set when an interrupt condition occurs, regardless of the state of its corresponding enable bit, or the global enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.

# 11.13.26 PIR3

Name: PIR3 Offset: 0x4B1

Peripheral Interrupt Request Register 3

Bit	7	6	5	4	3	2	1	0
	TMR0IF	CCP1IF	TMR1GIF	TMR1IF	TMR2IF	SPI1IF	SPI1TXIF	SPI1RXIF
Access	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R	R	R
Reset	0	0	0	0	0	0	0	0

# Bit 7 - TMR0IF TMR0 Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

# Bit 6 - CCP1IF CCP1 Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

# Bit 5 - TMR1GIF TMR1 Gate Interrupt Flag

	<u> </u>
Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

# Bit 4 - TMR1IF TMR1 Interrupt Flag

٧	'alue	Description
1		Interrupt has occurred (must be cleared by software)
0		Interrupt event has not occurred

## Bit 3 - TMR2IF TMR2 Interrupt Flag

Val	lue	Description
1		Interrupt has occurred (must be cleared by software)
0		Interrupt event has not occurred

# Bit 2 – SPI1IF SPI1 Interrupt Flag<sup>(2)</sup>

Valu	ue	Description			
1		Interrupt has occurred			
0		Interrupt event has not occurred			

# Bit 1 - SPI1TXIF SPI1 Transmit Interrupt Flag<sup>(3)</sup>

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

### Bit 0 - SPI1RXIF SPI1 Receive Interrupt Flag(3)

	=					
Value	Description					
1	Interrupt has occurred					
0	Interrupt event has not occurred					

# PIC18F26/46/56Q84

# **VIC - Vectored Interrupt Controller Module**

- 1. Interrupt flag bits get set when an interrupt condition occurs, regardless of the state of its corresponding enable bit, or the global enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.
- 2. SPI1IF is a read-only bit. To clear the interrupt condition, all bits in the SPI1INTF register must be cleared.
- 3. SPI1TXIF and SPI1RXIF are read-only bits and cannot be set/cleared by software.

# 11.13.27 PIR4

Name: PIR4 Offset: 0x4B2

Peripheral Interrupt Request Register 4

Bit	7	6	5	4	3	2	1	0
	PWM1IF	PWM1PIF	CANTIF	CANRIF	U1IF	U1EIF	U1TXIF	U1RXIF
Access	R	R/W/HS	R	R	R	R	R	R
Reset	0	0	0	0	0	0	0	0

# Bit 7 – PWM1IF PWM1 Parameter Interrupt Flag<sup>(2)</sup>

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

## Bit 6 - PWM1PIF PWM1 Period Interrupt Flag

Value	e Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

### Bit 5 - CANTIF CAN Transmit Interrupt Flag

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

# Bit 4 - CANRIF CAN Receive Interrupt Flag

Valu	ıe	Description
1		Interrupt has occurred
0		Interrupt event has not occurred

# Bit 3 - U1IF UART1 Interrupt Flag(3)

Vá	alue	Description
1		Interrupt has occurred
0		Interrupt event has not occurred

# Bit 2 - U1EIF UART1 Framing Error Interrupt Flag<sup>(4)</sup>

Valu	ue	Description
1		Interrupt has occurred
0		Interrupt event has not occurred

# Bit 1 – U1TXIF UART1 Transmit Interrupt Flag<sup>(5)</sup>

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

### Bit 0 - U1RXIF UART 1 Receive Interrupt Flag<sup>(5)</sup>

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

# PIC18F26/46/56Q84

# **VIC - Vectored Interrupt Controller Module**

- 1. Interrupt flag bits get set when an interrupt condition occurs, regardless of the state of its corresponding enable bit, or the global enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.
- 2. PWM1IF is a read-only bit. To clear the interrupt condition, all bits in the PWM1GIR register must be cleared
- 3. U1IF is a read-only bit. To clear the interrupt condition, all bits in the U1UIR register must be cleared
- 4. U1EIF is a read-only bit. To clear the interrupt condition, all bits in the U1ERR register must be cleared.
- 5. U1TXIF and U1RXIF are read-only bits and cannot be set/cleared by software.

# 11.13.28 PIR5

Name: PIR5 Offset: 0x4B3

Peripheral Interrupt Request Register 5

Bit	7	6	5	4	3	2	1	0
	PWM2IF	PWM2PIF	TMR3GIF	TMR3IF	TU16BIF	SPI2IF	SPI2TXIF	SPI2RXIF
Access	R	R/W/HS	R/W/HS	R/W/HS	R/W	R	R	R
Reset	0	0	0	0	0	0	0	0

# Bit 7 – PWM2IF PWM2 Parameter Interrupt Flag<sup>(2)</sup>

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

## Bit 6 - PWM2PIF PWM2 Period Interrupt Flag

Value	e Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

### Bit 5 - TMR3GIF TMR3 Gate Interrupt Flag

	<u> </u>
Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

# Bit 4 - TMR3IF TMR3 Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

# Bit 3 - TU16BIF 16-bit Universal Timer B Interrupt Flag

	Value	Description
	1	Interrupt has occurred (must be cleared by software)
(	0	Interrupt event has not occurred

# Bit 2 - SPI2IF SPI2 Interrupt Flag<sup>(3)</sup>

Valu	ue	Description
1		Interrupt has occurred
0		Interrupt event has not occurred

# Bit 1 – SPI2TXIF SPI2 Transmit Interrupt Flag<sup>(4)</sup>

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

### Bit 0 - SPI2RXIF SPI2 Receive Interrupt Flag(4)

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

# PIC18F26/46/56Q84

# **VIC - Vectored Interrupt Controller Module**

- 1. Interrupt flag bits get set when an interrupt condition occurs, regardless of the state of its corresponding enable bit, or the global enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.
- 2. PWM2IF is a read-only bit. To clear the interrupt condition, all bits in the PWM2GIR register must be cleared.
- 3. SPI2IF is a read-only bit. To clear the interrupt condition, all bits in the SPI2INTF register must be cleared.
- 4. SPI2TXIF and SPI2RXIF are read-only bits and cannot be set/cleared by software.

# 11.13.29 PIR6

Name: PIR6 Offset: 0x4B4

Peripheral Interrupt Request Register 6

Bit	7	6	5	4	3	2	1	0
	DMA2AIF	DMA2ORIF	DMA2DCNTIF	DMA2SCNTIF	NCO1IF	CWG1IF	CLC2IF	INT1IF
Access	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS
Reset	0	0	0	0	0	0	0	0

### Bit 7 - DMA2AIF DMA2 Abort Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

#### Bit 6 - DMA2ORIF DMA2 Overrun Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

### Bit 5 - DMA2DCNTIF DMA2 Destination Count Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

### Bit 4 - DMA2SCNTIF DMA2 Source Count Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

## Bit 3 - NCO1IF NCO1 Interrupt Flag

٧	/alue	Description		
1		Interrupt has occurred (must be cleared by software)		
0		Interrupt event has not occurred		

# Bit 2 - CWG1IF CWG1 Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

## Bit 1 - CLC2IF CLC2 Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

### Bit 0 - INT1IF External Interrupt 1 Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

#### Note:

1. Interrupt flag bits get set when an interrupt condition occurs, regardless of the state of its corresponding enable bit, or the global enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.

# 11.13.30 PIR7

Name: PIR7 Offset: 0x4B5

Peripheral Interrupt Request Register 7

Bit	7	6	5	4	3	2	1	0
	PWM3IF	PWM3PIF	CLC3IF		I2C1EIF	I2C1IF	I2C1TXIF	I2C1RXIF
Access	R	R/W/HS	R/W/HS		R	R	R	R
Reset	0	0	0		0	0	0	0

## Bit 7 – PWM3IF PWM3 Parameter Interrupt Flag<sup>(2)</sup>

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

#### Bit 6 - PWM3PIF PWM3 Period Interrupt Flag

<b>Value</b>	Description						
1	Interrupt has occurred (must be cleared by software)						
)	Interrupt event has not occurred						

#### Bit 5 - CLC3IF CLC3 Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

# Bit 3 - I2C1EIF I2C1 Error Interrupt Flag<sup>(3)</sup>

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

## Bit 2 - I2C1IF I2C1 Interrupt Flag(4)

Value	Description					
1	Interrupt has occurred					
0	Interrupt event has not occurred					

# Bit 1 - I2C1TXIF I2C1 Transmit Interrupt Flag<sup>(5)</sup>

Value	Description				
1	Interrupt has occurred				
0	Interrupt event has not occurred				

# Bit 0 - I2C1RXIF I2C1 Receive Interrupt Flag<sup>(5)</sup>

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

- 1. Interrupt flag bits get set when an interrupt condition occurs, regardless of the state of its corresponding enable bit, or the global enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.
- 2. PWM3IF is a read-only bit. To clear the interrupt condition, all bits in the PWM3GIR register must be cleared.
- 3. I2C1EIF is a read-only bit. To clear the interrupt condition, all bits in the I2C1ERR register must be cleared.
- 4. I2C1IF is a read-only bit. To clear the interrupt condition, all bits in the I2C1PIR register must be cleared.
- 5. I2C1TXIF and I2C1RXIF are read-only bits. To clear the interrupt condition, the CLRBF bit in I2C1STAT1 must be set.

# 11.13.31 PIR8

Name: PIR8 Offset: 0x4B6

Peripheral Interrupt Request Register 8

Bit	7	6	5	4	3	2	1	0
	SCANIF	CCP2IF	TMR5GIF	TMR5IF	U2IF	U2EIF	U2TXIF	U2RXIF
Access	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R	R	R	R
Reset	0	0	0	0	0	0	0	0

# Bit 7 - SCANIF Memory Scanner Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

# Bit 6 - CCP2IF CCP2 Interrupt Flag

Value	e Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

# Bit 5 - TMR5GIF TMR5 Gate Interrupt Flag

Valu	ue	Description	
1		Interrupt has occurred (must be cleared by software)	
0		Interrupt event has not occurred	

# Bit 4 - TMR5IF TMR5 Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

# Bit 3 - U2IF UART2 Interrupt Flag(2)

Value	Description	
1	Interrupt has occurred	
0	Interrupt event has not occurred	

# Bit 2 - U2EIF UART2 Framing Error Interrupt Flag<sup>(3)</sup>

Valu	ue	Description
1		Interrupt has occurred
0		Interrupt event has not occurred

# Bit 1 – U2TXIF UART2 Transmit Interrupt Flag<sup>(4)</sup>

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

### Bit 0 - U2RXIF UART2 Receive Interrupt Flag<sup>(4)</sup>

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

# PIC18F26/46/56Q84

# **VIC - Vectored Interrupt Controller Module**

- 1. Interrupt flag bits get set when an interrupt condition occurs, regardless of the state of its corresponding enable bit, or the global enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.
- 2. U2IF is a read-only bit. To clear the interrupt condition, all bits in the U2UIR register must be cleared.
- 3. U2EIF is a read-only bit. To clear the interrupt condition, all bits in the U2ERR register must be cleared.
- 4. U2TXIF and U2RXIF are read-only bits and cannot be set/cleared by software.

# 11.13.32 PIR9

Name: PIR9 Offset: 0x4B7

Peripheral Interrupt Request Register 9

Bit	7	6	5	4	3	2	1	0
	PWM4IF	PWM4PIF	CLC4IF		U3IF	U3EIF	U3TXIF	U3RXIF
Access	R	R/W	R/W/HS		R	R	R	R
Reset	0	0	0		0	0	0	0

### Bit 7 - PWM4IF PWM4 Parameter Interrupt Flag

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

#### Bit 6 - PWM4PIF PWM4 Period Interrupt Flag

Value	e Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

### Bit 5 - CLC4IF CLC4 Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

# Bit 3 - U3IF UART3 Interrupt Flag<sup>(2)</sup>

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

## Bit 2 - U3EIF UART3 Framing Error Interrupt Flag<sup>(3)</sup>

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

# Bit 1 - U3TXIF UART3 Transmit Interrupt Flag<sup>(4)</sup>

Valu	ue	Description
1		Interrupt has occurred
0		Interrupt event has not occurred

# Bit 0 - U3RXIF UART3 Receive Interrupt Flag(4)

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

- Interrupt flag bits get set when an interrupt condition occurs, regardless of the state of its corresponding enable bit, or the global enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.
- 2. U3IF is a read-only bit. To clear the interrupt condition, all bits in the U3UIR register must be cleared
- 3. U3EIF is a read-only bit. To clear the interrupt condition, all bits in the U3ERR register must be cleared.
- 4. U3TXIF and U3RXIF are read-only bits and cannot be set/cleared by software.

# 11.13.33 PIR10

Name: PIR10 Offset: 0x4B8

Peripheral Interrupt Request Register 10

Bit	7	6	5	4	3	2	1	0
	DMA3AIF	DMA3ORIF	DMA3DCNTIF	DMA3SCNTIF	NCO2IF	CWG2IF	CLC5IF	INT2IF
Access	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS
Reset	0	0	0	0	0	0	0	0

### Bit 7 - DMA3AIF DMA3 Abort Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

#### Bit 6 - DMA3ORIF DMA3 Overrun Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

### Bit 5 - DMA3DCNTIF DMA3 Destination Count Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

### Bit 4 - DMA3SCNTIF DMA3 Source Count Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

## Bit 3 - NCO2IF NCO2 Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

# Bit 2 - CWG2IF CWG2 Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

## Bit 1 - CLC5IF CLC5 Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

# Bit 0 - INT2IF External Interrupt 2 Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

#### Note:

1. Interrupt flag bits get set when an interrupt condition occurs, regardless of the state of its corresponding enable bit, or the global enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.

# 11.13.34 PIR11

Name: PIR11 Offset: 0x4B9

Peripheral Interrupt Request Register 11

Bit	7	6	5	4	3	2	1	0
	DMA4AIF	DMA4ORIF	DMA4DCNTIF	DMA4SCNTIF	TMR4IF	CWG3IF	CLC6IF	CCP3IF
Access	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS
Reset	0	0	0	0	0	0	0	0

### Bit 7 - DMA4AIF DMA4 Abort Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

#### Bit 6 - DMA4ORIF DMA4 Overrun Interrupt Flag

Value	Description	
1	Interrupt has occurred (must be cleared by software)	
0	Interrupt event has not occurred	

# Bit 5 - DMA4DCNTIF DMA4 Destination Count Interrupt Flag

Valu	ie	Description	
1		Interrupt has occurred (must be cleared by software)	
0		Interrupt event has not occurred	

### Bit 4 - DMA4SCNTIF DMA4 Source Count Interrupt Flag

Value	Description	
1	Interrupt has occurred (must be cleared by software)	
0	Interrupt event has not occurred	

## Bit 3 - TMR4IF TMR4 Interrupt Flag

Val	ue	Description
1		Interrupt has occurred (must be cleared by software)
0		Interrupt event has not occurred

# Bit 2 - CWG3IF CWG3 Interrupt Flag

Value	Description	
1	Interrupt has occurred (must be cleared by software)	
0	Interrupt event has not occurred	

## Bit 1 - CLC6IF CLC6 Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

# Bit 0 - CCP3IF CCP3 Interrupt Flag

Value	Description	
1	Interrupt has occurred (must be cleared by software)	
0	Interrupt event has not occurred	

#### Note:

1. Interrupt flag bits get set when an interrupt condition occurs, regardless of the state of its corresponding enable bit, or the global enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.

## 11.13.35 PIR12

Name: PIR12 Offset: 0x4BA

Peripheral Interrupt Request Register 12

Bit	7	6	5	4	3	2	1	0
	DMA5AIF	DMA5ORIF	DMA5DCNTIF	DMA5SCNTIF	U4IF	U4EIF	U4TXIF	U4RXIF
Access	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R	R	R	R
Reset	0	0	0	0	0	0	0	0

## Bit 7 - DMA5AIF DMA5 Abort Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

## Bit 6 - DMA5ORIF DMA5 Overrun Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

## Bit 5 - DMA5DCNTIF DMA5 Destination Count Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

# Bit 4 - DMA5SCNTIF DMA5 Source Count Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

## Bit 3 - U4IF UART 4 Interrupt Flag<sup>(2)</sup>

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

## Bit 2 - U4EIF UART4 Framing Error Interrupt Flag<sup>(3)</sup>

Valu	ue	Description
1		Interrupt has occurred
0		Interrupt event has not occurred

# Bit 1 – U4TXIF UART4 Transmit Interrupt Flag<sup>(4)</sup>

Va	lue	Description
1		Interrupt has occurred
0		Interrupt event has not occurred

#### Bit 0 - U4RXIF UART4 Receive Interrupt Flag<sup>(4)</sup>

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

# PIC18F26/46/56Q84

# **VIC - Vectored Interrupt Controller Module**

#### Notes:

- 1. Interrupt flag bits get set when an interrupt condition occurs, regardless of the state of its corresponding enable bit, or the global enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.
- 2. U4IF is a read-only bit. To clear the interrupt condition, all bits in the U4UIR register must be cleared.
- 3. U4EIF is a read-only bit. To clear the interrupt condition, all bits in the U4ERR register must be cleared.
- 4. U4TXIF and U4RXIF are read-only bits and cannot be set/cleared by software.

## 11.13.36 PIR13

Name: PIR13 Offset: 0x4BB

Peripheral Interrupt Request Register 13

Bit	7	6	5	4	3	2	1	0
	DMA6AIF	DMA6ORIF	DMA6DCNTIF	DMA6SCNTIF	U5IF	U5EIF	U5TXIF	U5RXIF
Access	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R	R	R	R
Reset	0	0	0	0	0	0	0	0

## Bit 7 - DMA6AIF DMA6 Abort Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

## Bit 6 - DMA6ORIF DMA6 Overrun Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

## Bit 5 - DMA6DCNTIF DMA6 Destination Count Interrupt Flag

Valu	ie	Description	
1		Interrupt has occurred (must be cleared by software)	
0		Interrupt event has not occurred	

# Bit 4 - DMA6SCNTIF DMA6 Source Count Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

## Bit 3 - U5IF UART5 Interrupt Flag<sup>(2)</sup>

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

## Bit 2 – U5EIF UART5 Framing Error Interrupt Flag<sup>(3)</sup>

Valu	ue	Description
1		Interrupt has occurred
0		Interrupt event has not occurred

# Bit 1 – U5TXIF UART5 Transmit Interrupt Flag<sup>(4)</sup>

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

#### Bit 0 - U5RXIF UART5 Receive Interrupt Flag<sup>(4)</sup>

Value	Description
1	Interrupt has occurred
0	Interrupt event has not occurred

# PIC18F26/46/56Q84

# **VIC - Vectored Interrupt Controller Module**

#### Notes:

- 1. Interrupt flag bits get set when an interrupt condition occurs, regardless of the state of its corresponding enable bit, or the global enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.
- 2. U5IF is a read-only bit. To clear the interrupt condition, all bits in the U5UIR register must be cleared.
- 3. U5EIF is a read-only bit. To clear the interrupt condition, all bits in the U5ERR register must be cleared.
- 4. U5TXIF and U5RXIF are read-only bits and cannot be set/cleared by software.

## 11.13.37 PIR14

Name: PIR14 Offset: 0x4BC

Peripheral Interrupt Request Register 14

Bit	7	6	5	4	3	2	1	0
	DMA7AIF	DMA7ORIF	DMA7DCNTIF	DMA7SCNTIF	NCO3IF	CM2IF	CLC7IF	
Access	R/W	R/W	R/W	R/W	R/W/HS	R/W/HS	R/W/HS	
Reset	0	0	0	0	0	0	0	

## Bit 7 - DMA7AIF DMA7 Abort Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

#### Bit 6 - DMA7ORIF DMA7 Overrun Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

## Bit 5 - DMA7DCNTIF DMA7 Destination Count Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

#### Bit 4 - DMA7SCNTIF DMA7 Source Count Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

#### Bit 3 - NCO3IF NCO3 Interrupt Flag

Valu	Description		
1	Interrupt has occurred (must be cleared by software)		
0	Interrupt event has not occurred		

## Bit 2 - CM2IF CMP2 Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

#### Bit 1 - CLC7IF CLC7 Interrupt Flag

Va	lue	Description
1		Interrupt has occurred (must be cleared by software)
0		Interrupt event has not occurred

#### Note:

 Interrupt flag bits get set when an interrupt condition occurs, regardless of the state of its corresponding enable bit, or the global enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.

## 11.13.38 PIR15

Name: PIR15 Offset: 0x4BD

Peripheral Interrupt Request Register 15

Bit	7	6	5	4	3	2	1	0
	DMA8AIF	DMA8ORIF	DMA8DCNTIF	DMA8SCNTIF	TMR6IF	CRCIF	CLC8IF	NVMIF
Access	R/W	R/W	R/W	R/W	R/W/HS	R/W/HS	R/W/HS	R/W/HS
Reset	0	0	0	0	0	0	0	0

#### Bit 7 - DMA8AIF DMA8 Abort Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

#### Bit 6 – DMA8ORIF DMA8 Overrun Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

## Bit 5 - DMA8DCNTIF DMA8 Destination Count Interrupt Flag

I	Value	Description
	1	Interrupt has occurred (must be cleared by software)
	0	Interrupt event has not occurred

#### Bit 4 - DMA8SCNTIF DMA8 Source Count Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

#### Bit 3 - TMR6IF TMR6 Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

## Bit 2 - CRCIF CRC Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

#### Bit 1 - CLC8IF CLC8 Interrupt Flag

Va	lue	Description
1		Interrupt has occurred (must be cleared by software)
0		Interrupt event has not occurred

## Bit 0 - NVMIF NVM Interrupt Flag

Value	Description
1	Interrupt has occurred (must be cleared by software)
0	Interrupt event has not occurred

#### Note:

 Interrupt flag bits get set when an interrupt condition occurs, regardless of the state of its corresponding enable bit, or the global enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.

## 11.13.39 IPR0

Name: IPR0 Offset: 0x362

Peripheral Interrupt Request Register 0

Bit	7	6	5	4	3	2	1	0
	IOCIP	CANIP	CLC1IP	TU16AIP	CSWIP	OSFIP	HLVDIP	SWINTIP
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	0	1	0	1	1	1	1

#### Bit 7 - IOCIP Interrupt-on-Change Priority

Value	Description		
1	High Priority		
0	Low Priority		

#### Bit 6 - CANIP CAN Main Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 5 - CLC1IP CLC1 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 4 - TU16AIP Universal Timer 16A interrupt priority

Value	Description
1	High Priority
0	Low Priority

## Bit 3 - CSWIP Clock Switch Interrupt Priority

	To the content mentaper noney				
Value	Description				
1	High Priority				
0	Low Priority				

## Bit 2 - OSFIP Oscillator Failure Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 1 - HLVDIP High/Low-Voltage Detect Priority Flag

	J .		,	J	
Value	Description				
1	High Priority				
0	Low Priority				

## Bit 0 - SWINTIP Software Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## 11.13.40 IPR1

Name: IPR1 Offset: 0x363

Peripheral Interrupt Priority Register 1

Bit	7	6	5	4	3	2	1	0
	SMT1PWAIP	SMT1PRAIP	SMT1IP	CM1IP	ACTIP	ADIP	ZCDIP	INT0IP
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

## Bit 7 - SMT1PWAIP SMT1 Pulse-Width Acquisition Interrupt Priority

Value	Description		
1	High Priority		
0	Low Priority		

#### Bit 6 - SMT1PRAIP SMT1 Period Acquisition Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 5 - SMT1IP SMT1 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 4 - CM1IP CMP1 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 3 - ACTIP Active Clock Tuning Interrupt Priority

Valu	Description
1	High Priority
0	Low Priority

## Bit 2 - ADIP ADC Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

#### Bit 1 - ZCDIP ZCD Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

# Bit 0 – INT0IP External Interrupt 0 Interrupt Priority

		 	,		
Value	Description				
1	High Priority				
0	Low Priority				

## 11.13.41 IPR2

Name: IPR2 Offset: 0x364

Peripheral Interrupt Priority Register 2

Bit	7	6	5	4	3	2	1	0
	DMA1AIP	DMA10RIP	DMA1DCNTIP	DMA1SCNTIP	ADCH4IP	ADCH3IP	ADCH2IP	ADCH1IP
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	0	0	0	0

#### Bit 7 - DMA1AIP DMA1 Abort Interrupt Priority

Value	Description		
1	High Priority		
0	Low Priority		

#### Bit 6 - DMA1ORIP DMA1 Overrun Interrupt Priority

Value	Description
0	High Priority
1	Low Priority

## Bit 5 - DMA1DCNTIP DMA1 Destination Count Interrupt Priority

Value	Description
0	High Priority
1	Low Priority

## Bit 4 - DMA1SCNTIP DMA1 Source Count Interrupt Priority

Value	Description
0	High Priority
1	Low Priority

#### Bit 3 - ADCH4IP ADC Context 4 Threshold Interrupt Priority

Value	Description
0	High Priority
1	Low Priority

## Bit 2 - ADCH3IP ADC Context 3 Threshold Interrupt Priority

Value	Description
0	High Priority
1	Low Priority

#### Bit 1 - ADCH2IP ADC Context 2 Threshold Interrupt Priority

Valu	e Description	
0	High Priority	
1	Low Priority	

## Bit 0 - ADCH1IP ADC Context 1 Threshold Interrupt Priority

Value	Description
0	High Priority
1	Low Priority

## 11.13.42 IPR3

Name: IPR3 Offset: 0x365

Peripheral Interrupt Priority Register 3

Bit	7	6	5	4	3	2	1	0
	TMR0IP	CCP1IP	TMR1GIP	TMR1IP	TMR2IP	SPI1IP	SPI1TXIP	SPI1RXIP
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

## Bit 7 - TMR0IP TMR0 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

#### Bit 6 - CCP1IP CCP1 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 5 - TMR1GIP TMR1 Gate Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 4 - TMR1IP TMR1 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

#### Bit 3 - TMR2IP TMR2 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 2 - SPI1IP SPI1 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 1 - SPI1TXIP SPI1 Transmit Interrupt Priority

Value	<b>Description</b>
1	High Priority
0	Low Priority

#### Bit 0 - SPI1RXIP SPI1 Receive Interrupt Priority

	Description
Value	Description
1	High Priority
0	Low Priority

## 11.13.43 IPR4

Name: IPR4 Offset: 0x366

Peripheral Interrupt Priority Register 4

Bit	7	6	5	4	3	2	1	0
	PWM1IP	PWM1PIP	CANTIP	CANRIP	U1IP	U1EIP	U1TXIP	U1RXIP
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	0	0	1	1	1	1

#### Bit 7 - PWM1IP PWM1 Parameter Interrupt Priority

Value	Description	
1	High Priority	
0	Low Priority	

#### Bit 6 - PWM1PIP PWM1 Period Interrupt Priority

Va	lue	Description
1		High Priority
0		Low Priority

## Bit 5 - CANTIP CAN Transmit Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 4 - CANRIP CAN Receive Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

#### Bit 3 - U1IP UART1 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 2 - U1EIP UART1 Framing Error Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 1 - U1TXIP UART1 Transmit Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

#### Bit 0 - U1RXIP UART 1 Receive Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## 11.13.44 IPR5

Name: IPR5 Offset: 0x367

Peripheral Interrupt Priority Register 5

Bit	7	6	5	4	3	2	1	0
	PWM2IP	PWM2PIP	TMR3GIP	TMR3IP	TU16BIP	SPI2IP	SPI2TXIP	SPI2RXIP
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	0	1	1	1

#### Bit 7 - PWM2IP PWM2 Parameter Interrupt Priority

Value	Description	
1	High Priority	
0	Low Priority	

#### Bit 6 - PWM2PIP PWM2 Period Interrupt Priority

Va	lue	Description
1		High Priority
0		Low Priority

## Bit 5 - TMR3GIP TMR3 Gate Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 4 - TMR3IP TMR3 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 3 - TU16BIP 16-bit Universal Timer B Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 2 - SPI2IP SPI2 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

#### Bit 1 - SPI2TXIP SPI2 Transmit Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

#### Bit 0 - SPI2RXIP SPI2 Receive Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## 11.13.45 IPR6

Name: IPR6 Offset: 0x368

Peripheral Interrupt Priority Register 6

Bit	7	6	5	4	3	2	1	0
	DMA2AIP	DMA2ORIP	DMA2DCNTIP	DMA2SCNTIP	NCO1IP	CWG1IP	CLC2IP	INT1IP
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

## Bit 7 - DMA2AIP DMA2 Abort Interrupt Priority

Value	Description		
1	High Priority		
0	Low Priority		

#### Bit 6 - DMA2ORIP DMA2 Overrun Interrupt Priority

١	/alue	Description
-	=	High Priority
(	)	Low Priority

## Bit 5 - DMA2DCNTIP DMA2 Destination Count Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 4 - DMA2SCNTIP DMA2 Source Count Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 3 - NCO1IP NCO1 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 2 - CWG1IP CWG1 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 1 - CLC2IP CLC2 Interrupt Priority

V	alue	Description		
1		High Priority		
0		Low Priority		

#### Bit 0 - INT1IP External Interrupt 1 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## 11.13.46 IPR7

Name: IPR7 Offset: 0x369

Peripheral Interrupt Priority Register 7

Bit	7	6	5	4	3	2	1	0
	PWM3IP	PWM3PIP	CLC3IP		I2C1EIP	I2C1IP	I2C1TXIP	I2C1RXIP
Access	R/W	R/W	R/W		R/W	R/W	R/W	R/W
Reset	1	1	1		1	1	1	1

## Bit 7 - PWM3IP PWM3 Parameter Interrupt Priority

Value	Description	
1	High Priority	
0	Low Priority	

#### Bit 6 - PWM3PIP PWM3 Period Interrupt Priority

1	Value	Description
ſ	1	High Priority
	0	Low Priority

## Bit 5 - CLC3IP CLC3 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 3 - I2C1EIP I2C1 Error Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 2 - I2C1IP I2C1 Interrupt Priority

	in the first state of the state								
Value	e Description								
1	High Priority								
0	Low Priority								

## Bit 1 - I2C1TXIP I2C1 Transmit Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

#### Bit 0 - I2C1RXIP I2C1 Receive Interrupt Priority

Value	Description		
1	High Priority		
0	Low Priority		

## 11.13.47 IPR8

Name: IPR8 Offset: 0x36A

Peripheral Interrupt Priority Register 8

Bit	7	6	5	4	3	2	1	0
	SCANIP	CCP2IP	TMR5GIP	TMR5IP	U2IP	U2EIP	U2TXIP	U2RXIP
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

## Bit 7 - SCANIP Memory Scanner Interrupt Priority

Value	Description		
1	High Priority		
0	Low Priority		

#### Bit 6 - CCP2IP CCP2 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 5 - TMR5GIP TMR5 Gate Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 4 - TMR5IP TMR5 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 3 - U2IP UART2 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 2 - U2EIP UART2 Framing Error Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 1 - U2TXIP UART2 Transmit Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

#### Bit 0 - U2RXIP UART2 Receive Interrupt Priority

	·····				
Value	Description				
1	High Priority				
0	Low Priority				

## 11.13.48 IPR9

Name: IPR9 Offset: 0x36B

Peripheral Interrupt Priority Register 9

Bit	7	6	5	4	3	2	1	0
	PWM4IP	PWM4PIP	CLC4IP		U3IP	U3EIP	U3TXIP	U3RXIP
Access	R/W	R/W	R/W		R/W	R/W	R/W	R/W
Reset	0	0	1		1	1	1	1

#### Bit 7 - PWM4IP PWM4 Parameter Interrupt Priority

Value	Description	
1	High Priority	
0	Low Priority	

#### Bit 6 - PWM4PIP PWM4 Period Interrupt Priority

Va	lue	Description
1		High Priority
0		Low Priority

#### Bit 5 - CLC4IP CLC4 Priority Flag

Value	Description				
1	High Priority				
0	Low Priority				

## Bit 3 - U3IP UART3 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 2 - U3EIP UART3 Framing Error Interrupt Priority

Value	Description Description
1	High Priority
0	Low Priority

## Bit 1 - U3TXIP UART3 Transmit Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

#### Bit 0 - U3RXIP UART3 Receive Interrupt Priority

Value	Description		
1	High Priority		
0	Low Priority		

## 11.13.49 IPR10

Name: IPR10 Offset: 0x36C

Peripheral Interrupt Priority Register 10

Bit	7	6	5	4	3	2	1	0
	DMA3AIP	DMA3ORIP	DMA3DCNTIP	DMA3SCNTIP	NCO2IP	CWG2IP	CLC5IP	INT2IP
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

## Bit 7 - DMA3AIP DMA3 Abort Interrupt Priority

Value	Description		
1	High Priority		
0	Low Priority		

#### Bit 6 - DMA3ORIP DMA3 Overrun Interrupt Priority

١	/alue	Description
-	=	High Priority
(	)	Low Priority

## Bit 5 - DMA3DCNTIP DMA3 Destination Count Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 4 - DMA3SCNTIP DMA3 Source Count Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

#### Bit 3 - NCO2IP NCO2 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 2 - CWG2IP CWG2 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 1 - CLC5IP CLC5 Interrupt Priority

V	alue	Description		
1		High Priority		
0		Low Priority		

#### Bit 0 - INT2IP External Interrupt 2 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## 11.13.50 IPR11

Name: IPR11 Offset: 0x36D

Peripheral Interrupt Priority Register 11

Bit	7	6	5	4	3	2	1	0
	DMA4AIP	DMA4ORIP	DMA4DCNTIP	DMA4SCNTIP	TMR4IP	CWG3IP	CLC6IP	CCP3IP
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

## Bit 7 - DMA4AIP DMA4 Abort Interrupt Priority

Value	Description		
1	High Priority		
0	Low Priority		

#### Bit 6 - DMA4ORIP DMA4 Overrun Interrupt Priority

١	/alue	Description
-	=	High Priority
(	)	Low Priority

## Bit 5 - DMA4DCNTIP DMA4 Destination Count Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 4 - DMA4SCNTIP DMA4 Source Count Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

#### Bit 3 - TMR4IP TMR4 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 2 - CWG3IP CWG3 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

#### Bit 1 – CLC6IP CLC6 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 0 - CCP3IP CCP3 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## 11.13.51 IPR12

Name: IPR12 Offset: 0x36E

Peripheral Interrupt Priority Register 12

Bit	7	6	5	4	3	2	1	0
	DMA5AIP	DMA5ORIP	DMA5DCNTIP	DMA5SCNTIP	U4IP	U4EIP	U4TXIP	U4RXIP
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

## Bit 7 - DMA5AIP DMA5 Abort Interrupt Priority

Value	Description		
1	High Priority		
0	Low Priority		

#### Bit 6 - DMA5ORIP DMA5 Overrun Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 5 - DMA5DCNTIP DMA5 Destination Count Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 4 - DMA5SCNTIP DMA5 Source Count Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

#### Bit 3 - U4IP UART 4 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 2 - U4EIP UART4 Framing Error Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 1 - U4TXIP UART4 Transmit Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 0 - U4RXIP UART4 Receive Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## 11.13.52 IPR13

Name: IPR13 Offset: 0x36F

Peripheral Interrupt Priority Register 13

Bit	7	6	5	4	3	2	1	0
	DMA6AIP	DMA6ORIP	DMA6DCNTIP	DMA6SCNTIP	U5IP	U5EIP	U5TXIP	U5RXIP
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

## Bit 7 - DMA6AIP DMA6 Abort Interrupt Priority

Value	Description		
1	High Priority		
0	Low Priority		

#### Bit 6 - DMA6ORIP DMA6 Overrun Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 5 - DMA6DCNTIP DMA6 Destination Count Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 4 - DMA6SCNTIP DMA6 Source Count Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

#### Bit 3 - U5IP UART5 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 2 - U5EIP UART5 Framing Error Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 1 - U5TXIP UART5 Transmit Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

#### Bit 0 - U5RXIP UART5 Receive Interrupt Priority

	······································
Value	Description
1	High Priority
0	Low Priority

## 11.13.53 IPR14

Name: IPR14 Offset: 0x370

Peripheral Interrupt Priority Register 14

Bit	7	6	5	4	3	2	1	0
	DMA7AIP	DMA7ORIP	DMA7DCNTIP	DMA7SCNTIP	NCO3IP	CM2IP	CLC7IP	
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	0	0	0	0	1	1	1	

#### Bit 7 - DMA7AIP DMA7 Abort Interrupt Priority

Value	Description		
1	High Priority		
0	Low Priority		

#### Bit 6 - DMA7ORIP DMA7 Overrun Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 5 - DMA7DCNTIP DMA7 Destination Count Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 4 - DMA7SCNTIP DMA7 Source Count Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 3 - NCO3IP NCO3 Interrupt Priority

 The trace menuper none,				
<b>√</b> alue	Description			
1	High Priority			
)	Low Priority			

## Bit 2 - CM2IP CMP2 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 1 - CLC7IP CLC7 Interrupt Priority

Value	Description	
1	High Priority	
0	Low Priority	

## 11.13.54 IPR15

Name: IPR15 Offset: 0x371

Peripheral Interrupt Priority Register 15

Bit	7	6	5	4	3	2	1	0
	DMA8AIP	DMA8ORIP	DMA8DCNTIP	DMA8SCNTIP	TMR6IP	CRCIP	CLC8IP	NVMIP
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	1	1	1	1

## Bit 7 - DMA8AIP DMA8 Abort Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

#### Bit 6 - DMA8ORIP DMA8 Overrun Interrupt Priority

١	/alue	Description
-	=	High Priority
(	)	Low Priority

## Bit 5 - DMA8DCNTIP DMA8 Destination Count Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 4 - DMA8SCNTIP DMA8 Source Count Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

#### Bit 3 - TMR6IP TMR6 Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

## Bit 2 - CRCIP CRC Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

#### Bit 1 - CLC8IP CLC8 Interrupt Priority

V	alue	Description		
1		High Priority		
0		Low Priority		

## Bit 0 - NVMIP NVM Interrupt Priority

Value	Description
1	High Priority
0	Low Priority

# 11.14 Register Summary - Interrupts

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0	
0x00											
	Reserved										
0x0361											
0x0362	IPR0	7:0	IOCIP	CANIP	CLC1IP	TU16AIP	CSWIP	OSFIP	HLVDIP	SWINTIP	
0x0363	IPR1	7:0	SMT1PWAIP	SMT1PRAIP	SMT1IP	CM1IP	ACTIP	ADIP	ZCDIP	INT0IP	
0x0364	IPR2	7:0	DMA1AIP	DMA10RIP	DMA1DCNTIP	DMA1SCNTIP	ADCH4IP	ADCH3IP	ADCH2IP	ADCH1IP	
0x0365	IPR3	7:0	TMR0IP	CCP1IP	TMR1GIP	TMR1IP	TMR2IP	SPI1IP	SPI1TXIP	SPI1RXIP	
0x0366	IPR4	7:0	PWM1IP	PWM1PIP	CANTIP	CANRIP	U1IP	U1EIP	U1TXIP	U1RXIP	
0x0367	IPR5	7:0	PWM2IP	PWM2PIP	TMR3GIP	TMR3IP	TU16BIP	SPI2IP	SPI2TXIP	SPI2RXIP	
0x0368	IPR6	7:0	DMA2AIP	DMA2ORIP	-	DMA2SCNTIP	NCO1IP	CWG1IP	CLC2IP	INT1IP	
0x0369	IPR7	7:0	PWM3IP	PWM3PIP	CLC3IP		I2C1EIP	I2C1IP	I2C1TXIP	I2C1RXIP	
0x036A	IPR8	7:0	SCANIP	CCP2IP	TMR5GIP	TMR5IP	U2IP	U2EIP	U2TXIP	U2RXIP	
0x036B	IPR9	7:0	PWM4IP	PWM4PIP	CLC4IP		U3IP	U3EIP	U3TXIP	U3RXIP	
0x036C	IPR10	7:0	DMA3AIP	DMA3ORIP	DMA3DCNTIP		NCO2IP	CWG2IP	CLC5IP	INT2IP	
0x036D	IPR11	7:0	DMA4AIP	DMA4ORIP	-	DMA4SCNTIP	TMR4IP	CWG3IP	CLC6IP	CCP3IP	
0x036E	IPR12	7:0	DMA5AIP		DMA5DCNTIP		U4IP	U4EIP	U4TXIP	U4RXIP	
0x036F	IPR13	7:0	DMA6AIP	DMA6ORIP	DMA6DCNTIP		U5IP	U5EIP	U5TXIP	U5RXIP	
0x0370	IPR14	7:0	DMA7AIP		DMA7DCNTIP		NCO3IP	CM2IP	CLC7IP	N. (A 415)	
0x0371	IPR15	7:0	DMA8AIP	DMA8ORIP	DMA8DCN TIP	DMA8SCNTIP	TMR6IP	CRCIP	CLC8IP	NVMIP	
0x0372	Reserved										
0x0375	Reserved										
0x0376	SHADCON	7:0								SHADLO	
0x0377	CHADOON	7.0								OT II/ (BEO	
	Reserved										
0x0458											
0x0459	IVTLOCK	7:0								IVTLOCKED	
		7:0									
0x045A	IVTAD	15:8				IVTAD					
		23:16						IVTADU[4:0]			
		7:0				IVTBAS	EL[7:0]				
0x045D	IVTBASE	15:8				IVTBAS	EH[7:0]				
		23:16						IVTBASEU[4:0]			
0x0460											
	Reserved										
0x049D											
0x049E	PIE0	7:0	IOCIE	CANIE	CLC1IE	TU16AIE	CSWIE	OSFIE	HLVDIE	SWINTIE	
0x049F	PIE1	7:0	SMT1PWAIE	SMT1PRAIE	SMT1IE	CM1IE	ACTIE	ADIE	ZCDIE	INT0IE	
0x04A0	PIE2	7:0	DMA1AIE		DMA1DCNTIE		ADCH4IE	ADCH3IE	ADCH2IE	ADCH1IE	
0x04A1	PIE3	7:0	TMR0IE	CCP1IE	TMR1GIE	TMR1IE	TMR2IE	SPI1IE	SPI1TXIE	SPI1RXIE	
0x04A2	PIE4	7:0	PWM1IE	PWM1PIE PWM2PIE	CANTIE TMR3GIE	CANRIE	U1IE	U1EIE	U1TXIE	U1RXIE	
0x04A3 0x04A4	PIE5	7:0	PWM2IE		-	TMR3IE	TU16BIE	SPI2IE CWG1IE	SPI2TXIE CLC2IE	SPI2RXIE	
0x04A4 0x04A5	PIE6 PIE7	7:0 7:0	DMA2AIE PWM3IE	PWM3PIE	DMA2DCNTIE CLC3IE	DIVIAZOCIVITE	NCO1IE I2C1EIE	CWG1IE I2C1IE	I2C1TXIE	INT1IE I2C1RXIE	
0x04A5 0x04A6	PIE7	7:0	SCANIE	CCP2IE	TMR5GIE	TMR5IE	U2IE	U2EIE	U2TXIE	U2RXIE	
0x04A6 0x04A7	PIE9	7:0	PWM4IE	PWM4PIE	CLC4IE	TIVIINOIE	U3IE	U3EIE	U3TXIE	U3RXIE	
0x04A7	PIE10	7:0	DMA3AIE		DMA3DCNTIE	DMA3SCNTIE	NCO2IE	CWG2IE	CLC5IE	INT2IE	
0x04A0	PIE11	7:0	DMA4AIE		DMA4DCNTIE		TMR4IE	CWG2IL CWG3IE	CLC6IE	CCP3IE	
0x04A9	PIE12	7:0	DMA5AIE		DMA5DCNTIE		U4IE	U4EIE	U4TXIE	U4RXIE	
0x04AB	PIE13	7:0	DMA6AIE		DMA6DCNTIE		USIE	U5EIE	U5TXIE	U5RXIE	
0x04AC	PIE14	7:0	DMA7AIE		DMA7DCNTIE		NCO3IE	CM2IE	CLC7IE	20.000	
0x04AD	PIE15	7:0	DMA8AIE		DMA8DCNTIE		TMR6IE	CRCIE	CLC8IE	NVMIE	
0x04AE	PIR0	7:0	IOCIF	CANIF	CLC1IF	TU16AIF	CSWIF	OSFIF	HLVDIF	SWIF	
0x04AF	PIR1	7:0	SMT1PWAIF	SMT1PRAIF	SMT1IF	CM1IF	ACTIF	ADIF	ZCDIF	INTOIF	
0x04B0	PIR2	7:0	DMA1AIF		DMA1DCNTIF		ADCH4IF	ADCH3IF	ADCH2IF	ADCH1IF	
0x04B1	PIR3	7:0	TMR0IF	CCP1IF	TMR1GIF	TMR1IF	TMR2IF	SPI1IF	SPI1TXIF	SPI1RXIF	
	***	1									

# PIC18F26/46/56Q84

# **VIC - Vectored Interrupt Controller Module**

continued										
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x04B2	PIR4	7:0	PWM1IF	PWM1PIF	CANTIF	CANRIF	U1IF	U1EIF	U1TXIF	U1RXIF
0x04B3	PIR5	7:0	PWM2IF	PWM2PIF	TMR3GIF	TMR3IF	TU16BIF	SPI2IF	SPI2TXIF	SPI2RXIF
0x04B4	PIR6	7:0	DMA2AIF	DMA2ORIF	DMA2DCNTIF	DMA2SCNTIF	NCO1IF	CWG1IF	CLC2IF	INT1IF
0x04B5	PIR7	7:0	PWM3IF	PWM3PIF	CLC3IF		I2C1EIF	I2C1IF	I2C1TXIF	I2C1RXIF
0x04B6	PIR8	7:0	SCANIF	CCP2IF	TMR5GIF	TMR5IF	U2IF	U2EIF	U2TXIF	U2RXIF
0x04B7	PIR9	7:0	PWM4IF	PWM4PIF	CLC4IF		U3IF	U3EIF	U3TXIF	U3RXIF
0x04B8	PIR10	7:0	DMA3AIF	DMA3ORIF	DMA3DCNTIF	DMA3SCNTIF	NCO2IF	CWG2IF	CLC5IF	INT2IF
0x04B9	PIR11	7:0	DMA4AIF	DMA40RIF	DMA4DCNTIF	DMA4SCNTIF	TMR4IF	CWG3IF	CLC6IF	CCP3IF
0x04BA	PIR12	7:0	DMA5AIF	DMA5ORIF	DMA5DCNTIF	DMA5SCNTIF	U4IF	U4EIF	U4TXIF	U4RXIF
0x04BB	PIR13	7:0	DMA6AIF	DMA6ORIF	DMA6DCNTIF	DMA6SCNTIF	U5IF	U5EIF	U5TXIF	U5RXIF
0x04BC	PIR14	7:0	DMA7AIF	DMA70RIF	DMA7DCNTIF	DMA7SCNTIF	NCO3IF	CM2IF	CLC7IF	
0x04BD	PIR15	7:0	DMA8AIF	DMA8ORIF	DMA8DCNTIF	DMA8SCNTIF	TMR6IF	CRCIF	CLC8IF	NVMIF
0x04BE										
 0x04D5	Reserved									
0x04D6	INTCON0	7:0	GIE/GIEH	GIEL	IPEN			INT2EDG	INT1EDG	INT0EDG
0x04D7	INTCON1	7:0	STAT	Γ[1:0]						

# 12. OSC - Oscillator Module (With Fail-Safe Clock Monitor)

The oscillator module contains multiple clock sources and selection features that allow it to be used in a wide range of applications while maximizing performance and minimizing power consumption.

Clock sources can be supplied either internally or externally. External sources include:

- · External clock oscillators
- · Quartz crystal resonators
- · Ceramic resonators
- Secondary Oscillator (SOSC)

#### Internal sources include:

- · High-Frequency Internal Oscillator (HFINTOSC)
- Low-Frequency Internal Oscillator (LFINTOSC)
- Analog-to-Digital Converter RC Oscillator (ADCRC)

Special features of the oscillator module include:

- Oscillator Start-up Timer (OST): Ensures stability of quartz crystal or ceramic resonators.
- 4x Phase-Locked Loop (PLL): Frequency multiplier for external clock sources.
- HFINTOSC Frequency Adjustment: Provides the ability to adjust the HFINTOSC frequency.
- Clock switching: Allows the system clock to switch between internal or external sources via software during run time.
- Fail-Safe Clock Monitor (FSCM): Designed to detect failure of the system clock (FOSC), primary external clock (EXTOSC), or secondary external clock (SOSC) sources. The FSCM automatically switches to an internal clock source upon detection of a system clock (FOSC) failure.

The Reset Oscillator (RSTOSC) Configuration bits determine the type of oscillator that will be used when the device runs after a Reset, including when the device is first powered up (see table below).

Table 12-1. RSTOSC Selection Table

DOTOGO		SFR Reset Values	Clock Source				
RSTOSC	NOSC / COSC	NDIV / CDIV	OSCFRQ	Clock Source			
111	111	0000 (1:1)		EXTOSC per FEXTOSC			
110	110			HFINTOSC @ 1 MHz			
101	101	0000 (1:1)	0010 <b>(4 MHz)</b>	LFINTOSC			
100	100	0000 (1:1)		SOSC			
011			Reserved				
010	010	0000 (1:1)	0010 <b>(4 MHz)</b>	EXTOSC + 4x PLL <sup>(1)</sup>			
001		Reserved					
000	000	0000 (1:1)	1000 <b>(64 MHz)</b>	HFINTOSC @ 64 MHz			

#### Note:

1. EXTOSC must meet the PLL specifications (see data sheet Electrical Specifications).

If an external clock source is selected by the RSTOSC bits, the External Oscillator Mode Select (FEXTOSC) Configuration bits must be used to select the external clock mode. These modes include:


- ECL: External Clock Low-Power mode
- ECM: External Clock Medium-Power mode
- ECH: External Clock High-Power mode
- · LP: 32 kHz Low-Gain Crystal mode

- XT: Medium-Gain Crystal or Ceramic Resonator mode
- · HS: High-Gain Crystal or Ceramic Resonator mode

The ECH, ECM, and ECL modes rely on an external logic-level signal as the device clock source. The LP, XT, and HS modes rely on an external quartz crystal or ceramic resonator as the device clock source. Each mode is optimized for a specific frequency range. The internal oscillator block produces both low-frequency and high-frequency clock signals, designated LFINTOSC and HFINTOSC, respectively. Multiple system operating frequencies may be derived from these clock sources.

The figure below illustrates a block diagram of the oscillator module.

Figure 12-1. Clock Source Block Diagram



# 12.1 Clock Source Types

Clock sources can be classified as external or internal.

External clock sources rely on external circuitry for the clock source to function. Examples of external clock sources include:

- · Digital oscillator modules
- Quartz crystal resonators
- · Ceramic resonators

A 4x PLL is provided for use with external clock sources.

Internal clock sources are contained within the oscillator module. The internal oscillator block features two internal oscillators that are used to generate internal system clock sources. The High-Frequency Internal Oscillator (HFINTOSC) can produce a wide range of frequencies which are determined via the HFINTOSC Frequency Selection (OSCFRQ) register. The Low-Frequency Internal Oscillator (LFINTOSC) generates a fixed nominal 31 kHz clock

signal. The internal oscillator block also features an RC oscillator which is dedicated to the Analog-to-Digital Converter (ADC).

The oscillator module allows the system clock source or system clock frequency to be changed through clock switching. Clock source selections are made via the New Oscillator Source Request (NOSC) bits. Once the clock source has been selected, the clock source base frequency can be divided (post-scaled) via the New Divider Selection Request (NDIV) bits.

The instruction clock ( $F_{OSC}/4$ ) can be routed to the OSC2/CLKOUT pin when the pin is not in use. The Clock Out Enable ( $\overline{\text{CLKOUTEN}}$ ) Configuration bit controls the functionality of the CLKOUT signal. When  $\overline{\text{CLKOUTEN}}$  is clear ( $\overline{\text{CLKOUTEN}}$  = 0), the CLKOUT signal is routed to the OSC2/CLKOUT pin. When  $\overline{\text{CLKOUTEN}}$  is set ( $\overline{\text{CLKOUTEN}}$  = 1), the OSC2/CLKOUT pin functions as an I/O pin.

#### 12.1.1 External Clock Sources

An external clock source can be used as the device system clock by performing one of the following actions:

- Program the RSTOSC and FEXTOSC Configuration bits to select an external clock source that will be used as the default system clock upon a device Reset.
- Write the NOSC and NDIV bits to switch the system clock source during run time.

#### 12.1.1.1 EC Mode

The External Clock (EC) mode allows an externally generated logic level signal to be the system clock source. When operating in EC mode, an external clock source is connected to the OSC1/CLKIN input pin. The OSC2/CLKOUT pin is available as a general purpose I/O pin or as the CLKOUT signal pin.


EC mode provides three power mode selections:

- · ECH: High-power mode
- · ECM: Medium-power mode
- · ECL: Low-power mode

The Oscillator Start-up Timer (OST) is disabled when EC mode is selected; therefore, there is no delay in operation after a Power-on Reset (POR) or wake-up from Sleep. Because the PIC® MCU design is fully static, stopping the external clock input will have the effect of halting the device while leaving all data intact. Upon restarting the external clock, the device will resume operation as if no time had elapsed.

The figure below shows the pin connections for EC mode.

Figure 12-2. External Clock (EC) Mode Operation



#### Note:

Output depends on the setting of the <u>CLKOUTEN</u> Configuration bit.

#### 12.1.1.2 LP, XT, HS Modes

The LP, XT, and HS modes support the use of quartz crystals or ceramic resonators connected to the OSC1 and OSC2 pins as shown in the figures below. These three modes select a low, medium, or high gain setting of the internal inverter-amplifier to support various resonator types and speeds.


The **LP** Oscillator mode selects the lowest gain setting of the internal inverter-amplifier, and consumes the least amount of current. LP mode is designed to drive 32.768 kHz tuning-fork type crystals (watch crystals), but can operate up to 100 kHz.

The **XT** Oscillator mode selects the intermediate gain setting of the internal inverter-amplifier. Current consumption is at a medium level when compared to the other two modes. XT mode is best suited to drive crystal and ceramic resonators with a frequency range up to 4 MHz.

The **HS** Oscillator mode selects the highest gain setting of the internal inverter-amplifier, and consumes the most current. This mode is best suited for crystal and ceramic resonators that require operating frequencies up to 20 MHz.

The figures below show typical circuits for quartz crystal and ceramic resonators.


Figure 12-3. Quartz Crystal Operation



## Notes:

- 1. A series resistor (R<sub>S</sub>) may be required for quartz crystals with low drive level.
- 2. The value of  $R_F$  varies with the oscillator mode selected (typically between 2 M $\Omega$  and 10 M $\Omega$ ).

Figure 12-4. Ceramic Resonator Operation



#### Notes:

- 1. A series resistor (R<sub>S</sub>) may be required for ceramic resonators with low drive level.
- 2. The value of  $R_F$  varies with the oscillator mode selected (typically between 2 M $\Omega$  and 10 M $\Omega$ ).
- 3. An additional parallel feedback resistor (R<sub>P</sub>) may be required for proper ceramic resonator operation.

#### 12.1.1.3 Oscillator Start-Up Timer (OST)

The Oscillator Start-up Timer (OST) ensures that the oscillator circuit has started and is providing a stable system clock to the oscillator module. Quartz crystals or ceramic resonators do not start immediately, and may take a few hundred cycles before the oscillator becomes stable. The oscillations must build up until sufficient amplitude is generated to properly toggle between logic states. The OST counts 1024 oscillation periods from the OSC1 input following a Power-on Reset (POR), Brown-out Reset (BOR), or wake-up from Sleep event to ensure that the oscillator has enough time to reach stable and accurate operation. Once the OST has completed its count, module hardware sets the External Oscillator Ready (EXTOR) bit, indicating that the oscillator is stable and ready to use.

#### 12.1.1.4 4x PLL

The oscillator module contains a 4x Phase-Locked Loop (PLL) circuit that can be used with the external clock sources to provide a system clock source. The input frequency for the PLL must fall within a specified range. See the PLL Clock Timing Specifications found in the "**Electrical Specifications**" chapter for more information.

The PLL can be enabled for use through one of two methods:

- 1. Program the RSTOSC Configuration bits to select the 'EXTOSC with 4x PLL' option.
- 2. Write the NOSC bits to select the 'EXTOSC with 4x PLL' option.

## 12.1.1.5 Secondary Oscillator

The Secondary Oscillator (SOSC) is a separate external oscillator block that can be used as an alternate system clock source or as a Timer clock source. The SOSC is optimized for 32.768 kHz, and can be used with either an external quartz crystal connected to the SOSCI and SOSCO pins, or with an external clock source connected to the SOSCI pin as shown in the figures below.

Figure 12-5. SOSC 32.768 kHz Quartz Crystal Oscillator Operation





Figure 12-6. SOSC 32.768 kHz External Clock Operation



The SOSC can be enabled through one of two methods:

- Programming the RSTOSC Configuration bits to select the SOSC as the system clock.
- Programming the NOSC bits to select the SOSC during run time.

Two power modes are available for the secondary oscillator, and are selected using the Secondary Oscillator Power Mode Select (SOSCPWR) bit. When SOSCPWR is clear (SOSCPWR = 0), the oscillator operates in Low-Power mode, which is ideal for crystal oscillators with low drive strength. When SOSCPWR is set (SOSCPWR = 1), the oscillator operates in High-Power mode, which is ideal for crystal oscillators with high drive strength or high Equivalent Series Resistance (ESR).



**Important:** The SOSC module must be disabled before changing power modes. Changes to the Power mode during operation may result in undefined oscillator behavior.

## 12.1.1.5.1 SOSC Start-Up Timing

The SOSC utilizes the Oscillator Start-up Timer (OST) to ensure that the 32.768 kHz crystal oscillator has started and is available for use. Since crystal oscillators do not start immediately and may take a few hundred cycles before achieving stable operation, the OST counts 1024 oscillation periods from the SOSCI input. Once the OST completes its count, module hardware sets the Secondary Oscillator Ready (SOR) bit, indicating that the SOSC is stable and ready to use.

#### 12.1.2 Internal Clock Sources

The internal oscillator block contains two independent oscillators that can produce two internal system clock sources:

- High-Frequency Internal Oscillator (HFINTOSC)
- Low-Frequency Internal Oscillator (LFINTOSC)

Internal oscillator selection is performed one of two ways:

- Program the RSTOSC Configuration bits to select one of the INTOSC sources which will be used upon a
  device Reset.
- 2. Write the New Oscillator Source Request (NOSC) bits to select an internal oscillator during run time.

In INTOSC mode, the OSC1/CLKIN and OSC2/CLKOUT pins are available for use as a general purpose I/Os, provided that no external oscillator is connected. The function of the OSC2/CLKOUT pin is determined by the  $\overline{\text{CLKOUTEN}}$  Configuration bit. When  $\overline{\text{CLKOUTEN}}$  is set ( $\overline{\text{CLKOUTEN}}$  = 1), the pin functions as a general-purpose I/O. When  $\overline{\text{CLKOUTEN}}$  is clear ( $\overline{\text{CLKOUTEN}}$  = 0), the system instruction clock ( $\overline{\text{F}_{OSC}}$ /4) is available as an output signal on the pin.

#### 12.1.2.1 HFINTOSC

The High-Frequency Internal Oscillator (HFINTOSC) is a factory-calibrated, precision digitally-controlled internal clock source that produces a wide range of stable clock frequencies. The HFINTOSC can be enabled through one of the following methods:

- Program the RSTOSC Configuration bits to select the HFINTOSC upon device Reset or power-up
- Write to the New Oscillator Source Request (NOSC) bits to select the HFINTOSC during run time.

The HFINTOSC frequency is selected via the HFINTOSC Frequency Selection (FRQ) bits. Fine-tuning of the HFINTOSC is done via the HFINTOSC Frequency Tuning (TUN) bits. The HFINTOSC output frequency can be divided (post-scaled) via the New Divider Selection Request (NDIV) bits.

#### 12.1.2.1.1 HFINTOSC Frequency Tuning

The HFINTOSC frequency can be fine-tuned via the HFINTOSC Tuning Register (OSCTUNE). The OSCTUNE register is used by Active Clock Tuning hardware or user software to provide small adjustments to the HFINTOSC nominal frequency.

The OSCTUNE register contains the HFINTOSC Frequency Tuning (TUN) bits. The TUN bits default to a 6-bit, two's compliment value of 0x00, which indicates that the oscillator is operating at the selected frequency. When a value between 0x01 and 0x1F is written to the TUN bits, the HFINTOSC frequency is increased. When a value between 0x3F and 0x20 is written to the TUN bits, the HFINTOSC frequency is decreased.

When the OSCTUNE register is modified, the oscillator will begin to shift to the new frequency. Code execution continues during this shift. There is no indication that the frequency shift occurred.



**Important:** OSCTUNE tuning does not affect the LFINTOSC frequency.

#### 12.1.2.2 MFINTOSC

The Medium-Frequency Internal Oscillator (MFINTOSC) generates two constant clock outputs (500 kHz and 31.25 kHz). The MFINTOSC clock signals are created from the HFINTOSC using dynamic divider logic, which provides constant MFINTOSC clock rates regardless of selected HFINTOSC frequency.

The MFINTOSC cannot be used as the system clock, but can be used as a clock source for certain peripherals, such as a Timer.

#### 12.1.2.3 LFINTOSC

The Low-Frequency Internal Oscillator (LFINTOSC) is a factory-calibrated 31 kHz internal clock source.

The LFINTOSC can be used as a system clock source, and may be used by certain peripheral modules as a clock source. Additionally, the LFINTOSC provides a time base for the following:

- Power-up Timer (PWRT)
- Watchdog Timer (WDT)/Windowed Watchdog Timer (WWDT)
- Fail-Safe Clock Monitor (FSCM)

The LFINTOSC is enabled through one of the following methods:

- Program the RSTOSC Configuration bits to select LFINTOSC
- Write the NOSC bits to select LFINTOSC during run time

#### 12.1.2.4 ADCRC

The Analog-to-Digital RC (ADCRC) oscillator is dedicated to the ADC module. This oscillator is also referred to as the FRC clock. The ADCRC operates at a fixed frequency of approximately 600 kHz, and is used as a conversion clock source. The ADCRC allows the ADC module to operate in Sleep mode, which can reduce system noise during the ADC conversion. The ADCRC is automatically enabled when it is selected as the clock source for the ADC module, or when selected as the clock source of any peripheral that may use it. The ADCRC may also be manually enabled via the ADC Oscillator Enable (ADOEN) bit, thereby avoiding start-up delays when this source is used intermittently.

## 12.1.3 Oscillator Status and Manual Enable

The Oscillator Status (OSCSTAT) register displays the Ready status for each of the following oscillators:

- · External oscillator
- HFINTOSC
- MFINTOSC
- LFINTOSC
- SOSC
- ADCRC

The OSCSTAT register also displays the Ready status for the 4xPLL.

The HFINTOSC Oscillator Ready (HFOR) and MFINTOSC Oscillator Ready (MFOR) Status bits indicate whether the respective oscillators are ready for use. Both clock sources are available for use at any time, but may require a finite amount of time before they have reached the specified accuracy levels. When the HFINTOSC or MFINTOSC are ready and achieved the specified accuracy, module hardware sets the HFOR/MFOR bits, respectively.

When a new value is loaded into the OSCFRQ register, the HFOR and MFOR bits are cleared by hardware, and will be set again once the respective oscillator is ready. During pending OSCFRQ changes, the MFINTOSC will stall at either a high or a low state until the HFINTOSC locks in the new frequency and resumes operation.

The Oscillator Enable (OSCEN) register can be used to manually enable the following oscillators:

- External oscillator
- HFINTOSC
- MFINTOSC
- LFINTOSC
- sosc
- ADCRC



**Important:** OSCEN cannot be used to manually enable the 4xPLL.

## 12.2 Clock Switching

The system clock source can be switched between external and internal clock sources via software using the New Oscillator Source Request (NOSC) and New Divider Selection Request (NDIV) bits. The following sources can be selected:

- External Oscillator (EXTOSC)
- · EXTOSC with 4x PLL
- · High-Frequency Internal Oscillator (HFINTOSC)
- Low-Frequency Internal Oscillator (LFINTOSC)
- · Secondary Oscillator (SOSC)

The Clock Switch Enable (CSWEN) Configuration bit can be used to enable or disable the clock switching capability. When CSWEN is set (CSWEN = 1), writes to NOSC and NDIV by user software will allow the system clock to switch between sources or frequencies. When CSWEN is clear (CSWEN = 0), writes to NOSC and NDIV are ignored, preventing the system clock from switching from one source to another.

#### 12.2.1 NOSC and NDIV Bits

The New Oscillator Source Request (NOSC) and the New Divider Selection Request (NDIV) bits are used to select the system clock source and clock frequency divider that will be used by the CPU and peripherals (see tables below).

When new values are written into NOSC and/or NDIV, the current oscillator selection will continue to operate as the system clock while waiting for the new source to indicate that it is ready. Writes to NDIV without changing the clock source (e.g., changing the HFINTOSC frequency from 1 MHz to 2 MHz) are handled in the same manner as a clock switch.

When the new oscillator selection is ready, the New Oscillator is Ready (NOSCR) bit and the Clock Switch Interrupt Flag (CSWIF) are set by module hardware. If the Clock Switch Interrupt Enable (CSWIE) bit is set (CSWIE = 1), an interrupt will be generated when CSWIF is set. Additionally, the Oscillator Ready (ORDY) bit can be polled to determine that the clock switch has completed and the new oscillator source has replaced the old source as the system clock.



**Important:** The CSWIF interrupt does not wake the device from Sleep.

Table 12-2. NOSC/COSC Clock Source Selection Table

NOSC / COSC	Clock Source
111	EXTOSC <sup>(1)</sup>
110	HFINTOSC <sup>(2)</sup>
101	LFINTOSC
100	SOSC
011	Reserved
010	EXTOSC + 4xPLL <sup>(3)</sup>
001	Reserved
000	Reserved

#### Notes:

- 1. EXTOSC is configured via the FEXTOSC Configuration bits.
- 2. HFINTOSC frequency is determined by the FRQ bits.
- 3. EXTOSC must meet the PLL specifications (see data sheet Electrical Specifications).

Table 12-3. NDIV/CDIV Clock Divider Selection Table

NDIV / CDIV	Clock Divider
1111-1010	Reserved
1001	512
1000	256
0111	128
0110	64
0101	32
0100	16
0011	8
0010	4
0001	2
0000	1

#### 12.2.2 COSC and CDIV Bits

The Current Oscillator Source Select (COSC) bits and the Current Divider Select (CDIV) bits indicate the current oscillator source and clock divider, respectively. When a new oscillator or divider is requested via the NOSC/NDIV bits, the COSC and CDIV bits remain unchanged until the clock switch actually occurs. When the switch actually occurs, hardware copies the NOSC and NDIV values into COSC and CDIV, the Oscillator Ready (ORDY) bit is set, and the NOSCR bit is cleared by hardware, indicating that the clock switch is complete.

#### 12.2.3 **CSWHOLD**

When the system oscillator changes frequencies, peripherals using the system clock may be affected. For example, if the  $I^2C$  module is actively using the system clock as its Serial Clock (SCL) time base, changing the system clock frequency will change the SCL frequency. The Clock Switch Hold (CSWHOLD) bit can be used to suspend a requested clock switch. In this example, software can request a new clock source, use the CSWHOLD bit to suspend the switch, wait for the  $I^2C$  bus to become Idle, then reconfigure the SCL frequency based on the new clock source. Once the  $I^2C$  has been reconfigured, software can use CSWHOLD to complete the clock switch without causing any issues with the  $I^2C$  bus.

When CSWHOLD is set (CSWHOLD = 1), a write to NOSC and/or NDIV is accepted, but the clock switch is suspended and does not automatically complete. While the switch is suspended, code execution continues using the old (current) clock source. Module hardware will still enable the new oscillator selection and set the NOSCR bit. Once the NOSCR bit is set, software should either:

- clear CSWHOLD so that the clock switch can complete, or
- copy the Current Oscillator Source Select (COSC) value into NOSC to abandon the clock switch.

When CSWHOLD is clear (CSWHOLD = 0), the clock switch will occur when the NOSCR bit is set. When NOSCR is set, the CSWIF is also set, and if CSWIE is set, the generated interrupt will be serviced using the new oscillator.

#### 12.2.4 PLL Input Switch

Switching between the PLL and any non-PLL source is handled in the same manner as any other clock source change.

When the NOSC selects a source with a PLL, the system continues to operate using the current oscillator until the new oscillator is ready. When the new source is ready, the associated Status bit in the Oscillator Status (OSCSTAT) register is set, and once the PLL is locked and ready for use, the PLL is Ready (PLLR) bit is set. Once both the source and PLL are ready, the switch will complete.

#### 12.2.5 Clock Switch and Sleep


If the NOSC/NDIV bits are written with new values and the device is put to Sleep before the clock switch completes, the switch will not take place and the device will enter Sleep mode.

When the device wakes up from Sleep and CSWHOLD is clear (CSWHOLD = 0), the clock switch will complete and the device will wake with the new clock active, setting CSWIF.

When the device wakes from Sleep and CSWHOLD is set (CSWHOLD = 1), the device will wake up with the old clock active, and the new clock source will be requested again.

If Doze mode is in effect, the clock switch occurs on the next clock cycle regardless of whether or not the CPU is active during that clock cycle.


Figure 12-7. Clock Switch (CSWHOLD = 0)



#### Notes:

- CSWIF is asserted coincident with NOSCR; interrupt is serviced at OSC#2 speed.
- 2. The assertion of NOSCR may not be seen by the user as it is only set for the duration of the switch.


Figure 12-8. Clock Switch (CSWHOLD = 1)



#### Note:

CSWIF may be cleared before or after clearing CSWHOLD.

Figure 12-9. Clock Switch Abandoned



#### Note:

1. CSWIF may be cleared before or after rewriting NOSC; CSWIF is not automatically cleared.


# 12.3 Fail-Safe Clock Monitor (FSCM)

The Fail-Safe Clock Monitor (FSCM) allows the device to continue operating in the event of an oscillator failure. The FSCM also provides diagnostic data pertaining to potential primary and secondary oscillator failures. The FSCM serves three separate functions:

- · Monitoring of FOSC using the FSCMFEV bit.
- Monitoring of EXTOSC (primary external oscillator) using the FSCMPEV bit.
- · Monitoring of SOSC (secondary external oscillator) using the FSCMSEV bit.

The primary external oscillator FSCM (FSCMP) is enabled by setting the Fail-Safe Clock Monitor for Primary Crystal Oscillator (FCMENP) Configuration bit. The secondary external oscillator FSCM (FSCMS) is enabled by setting the Fail-Safe Clock Monitor for Secondary Crystal Oscillator (FCMENS) configuration bit. The FOSC FSCM is enabled by setting the Fail-Safe Clock Monitor Enable for FOSC (FCMEN) configuration bit. The figure below shows the FSCM block diagram.





#### 12.3.1 Fail-Safe Detection

Each FSCM detects a failed oscillator by comparing the external oscillator to the FSCM sample clock. The sample clock is generated by dividing the LFINTOSC by 64. The fail detector logic block contains a latch that is set upon each falling edge of the external clock. The latch is cleared on the rising edge of the sample clock. A failure is detected when a half-period of the sample clock elapses before the external clock goes low and the corresponding FSCM failure status bit will be set.

# 12.3.2 Fail-Safe Operation - FOSC Fail-Safe Clock Monitor

When the system clock (FOSC) fails, the Oscillator Fail Interrupt Flag (OSFIF) bit of the PIR registers will be set, as well as the corresponding FSCM failure status bit (FSCMFEV). If the Oscillator Fail Interrupt Enable (OSFIE) bit was set, an interrupt will be generated when OSFIF is high. If enabled, the FOSC Fail-Safe Clock Monitor will switch the system clock to HFINTOSC when a failure is detected by overwriting the NOSC/COSC bits. The frequency of HFINTOSC will depend on the previous state of the FRQ bits and the state of the NDIV/CDIV bits. Once a failure is detected, software can be used to take steps to mitigate the repercussions of the oscillator failure. The FSCM will switch the system clock to HFINTOSC, and the device will continue to operate from HFINTOSC until the external oscillator has been restarted. Once the external source is operational, it is up to the user to confirm that the clock source is stable and to switch the system clock back to the external oscillator using the NOSC/NDIV bits.

# 12.3.3 Fail-Safe Operation - Primary and Secondary Fail-Safe Clock Monitors

When the primary external clock (EXTOSC) or the secondary external clock (SOSC) fail, the Oscillator Fail Interrupt Flag (OSFIF) bit of the PIR registers will set. Additionally, the corresponding FSCM failure status bit (FSCMPEV or FSCMSEV respectively) will set. If the Oscillator Fail Interrupt Enable (OSFIE) bit has been set, an interrupt will be generated when OSFIF is high. It is important to note that neither the primary or secondary Fail-Safe Clock Monitors will cause a clock switch to occur in the event of a failure, and it is up to the user to address the clock fail event.

#### 12.3.4 Fail-Safe Clock Monitor Fault Injection

Each of the Fail-Safe Clock monitors on this device has its own respective Fault Injection bit. The fault injection bit is used to verify in software that the FSCM functions work properly and will detect a clock failure during normal operation. If the FSCM fault injection bit is set, the FSCM sample clock input will be blocked, forcing a clock failure. Writing to the FOSC FSCM fault injection bit (FSCMFFI) will result in the system clock switching to HFINTOSC and

# OSC - Oscillator Module (With Fail-Safe Clock ...

the FSCMFEV bit will be set as well as the Oscillator Fail Interrupt Flag (OSFIF) of the PIR registers. Writing to the primary and secondary external FSCM fault injection bits (FSCMPFI and FSCMSFI) will result in the respective FSCM fault status bits being set (FSCMPEV and FSCMSEV) but the system clock will not switch. Additionally, the Oscillator Fail Interrupt Flag (OSFIF) of the PIR registers will also be set.

# 12.3.5 Fail-Safe Condition Clearing

For the FOSC FSCM, the Fail-Safe condition is cleared after either a device Reset, execution of a SLEEP instruction, or a change to the NOSC/NDIV bits. When switching to the external oscillator or PLL, the Oscillator Start-up Timer (OST) is restarted. While the OST is running, the device continues to operate from HFINTOSC. When the OST expires, the Fail-Safe condition is cleared after successfully switching to the external clock source.



**Important:** Software must clear the OSFIF bit before switching to the external oscillator. If the Fail-Safe condition still exists, the OSFIF bit will be set again by module hardware.

### 12.3.6 Reset or Wake-Up From Sleep

The FSCM is designed to detect an oscillator failure after the OST has expired. The OST is used after waking up from Sleep or after any type of Reset, when in either LP, XT, or HS modes. If the device is using EC mode, the FSCM will be active as soon as the Reset or wake-up event has completed.

# 12.4 Active Clock Tuning (ACT)

Many applications, such as those using UART communication, require an oscillator with an accuracy of  $\pm$  1% over the full temperature and voltage range. To meet this level of accuracy, the Active Clock Tuning (ACT) feature utilizes the SOSC frequency of 32.768 kHz to adjust the frequency of the HFINTOSC over voltage and temperature.



**Important:** Active Clock Tuning requires the use of a 32.768 kHz external oscillator connected to the SOSCI/SOSCO pins.


Active Clock Tuning is enabled via the Active Clock Tuning Enable (ACTEN) bit. When ACTEN is set (ACTEN = 1), the ACT module uses the SOSC time base to measure the HFINTOSC frequency, and uses the HFINTOSC Frequency Tuning (TUN) bits to adjust the HFINTOSC frequency. When ACTEN is clear (ACTEN = 0), the ACT feature is disabled, and user software can utilize the TUN bits to adjust the HFINTOSC frequency.



**Important:** When the ACT feature is enabled, the TUN bits are controlled directly through module hardware and become read-only bits to user software. Writes to the TUN bits when the ACT feature is enabled are ignored.

The figure below shows the Active Clock Tuning block diagram.

Figure 12-11. Active Clock Tuning (ACT) Block Diagram



#### 12.4.1 ACT Lock Status

The Active Clock Tuning Lock Status (ACTLOCK) bit can be used to determine when the HFINTOSC has been tuned. When ACTLOCK is set (ACTLOCK = 1), the HFINTOSC frequency has been locked to within ± 1% of the nominal frequency. When ACTLOCK is clear (ACTLOCK = 0), the following conditions may be true:

- The HFINTOSC frequency has not been locked to within ± 1%
- · A device Reset occurred
- · The ACT feature is disabled



Important: The ACTLOCK bit is read-only. Writes to ACTLOCK are ignored.

### 12.4.2 ACT Out-Of-Range Status

When Active Clock Tuning is enabled, module hardware uses the TUN bits to achieve high accuracy levels. If the module requires a TUN value outside of its range, the ACT Out-of-Range Status (ACTORS) bit is set by hardware (ACTORS = 1).

The ACTORS bit will be set when:

- The HFINTOSC is tuned to its lowest frequency as determined by the TUN bits, and would require a value lower than the TUN bits can provide to achieve accuracy within ± 1%.
- The HFINTOSC is tuned to its highest frequency as determined by the TUN bits, and would require a value higher than the TUN bits can provide to achieve accuracy within ± 1%.

When an ACT out-of-range event occurs, the HFINTOSC will continue to use the last TUN value until the HFINTOSC frequency returns to the tunable range. Once the HFINTOSC returns to the tunable range, module hardware clears the ACTORS bit.



**Important:** The ACTORS bit is read-only. Writes to ACTORS are ignored.

# 12.4.3 ACT Update Disable

When Active Clock Tuning is enabled, the OSCTUNE register is continuously updated every ACT clock cycle. The ACT Update Disable (ACTUD) bit can be used to suspend updates to the OSCTUNE register. When ACTUD is set

# PIC18F26/46/56Q84

# OSC - Oscillator Module (With Fail-Safe Clock ...

(ACTUD = 1), updates to OSCTUNE are suspended, although the module continues to operate. The last value written to OSCTUNE is used for tuning, and the ACTLOCK bit is continually updated for each ACT cycle. When ACTUD is clear (ACTUD = 0), the module updates OSCTUNE register every ACT cycle.

### 12.4.4 ACT Interrupts

When Active Clock Tuning is enabled (ACTEN = 1) and either the ACTLOCK or ACTORS bits change state (e.g., from a Locked to an Unlocked state), the ACT Interrupt Flag (ACTIF) of the PIR registers is set (ACTIF = 1). If the ACT Interrupt Enable (ACTIE) bit is set (ACTIE = 1), an interrupt will be generated when ACTIF becomes set. No interrupts are generated for each OSCTUNE update unless the update results in a change of Lock status or Out-of-Range status.

# 12.5 Register Definitions: Oscillator Module

# 12.5.1 ACTCON

Name: ACTCON Offset: 0x0AC

Active Clock Tuning Control Register

Bit	7	6	5	4	3	2	1	0
	ACTEN	ACTUD			ACTLOCK		ACTORS	
Access	R/W	R/W			R		R	
Reset	0	0			0		0	

# Bit 7 - ACTEN Active Clock Tuning Enable

Value	Description
1	ACT enabled: HFINTOSC tuning is controlled by the ACT
0	ACT disabled: HFINTOSC tuning is controlled by the OSCTUNE register via user software

### Bit 6 - ACTUD Active Clock Tuning Update Disable

Value	Condition	Description
1	ACTEN = 1	Updates to the OSCTUNE register from ACT hardware are disabled
0	ACTEN = 1	Updates to the OSCTUNE register from ACT hardware are allowed
1	ACTEN = 0	Updates to the OSCTUNE register through user software are disabled
0	ACTEN = 0	Updates to the OSCTUNE register through user software are allowed

# Bit 3 – ACTLOCK Active Clock Tuning Lock Status

Value	Description
1	Locked: HFINTOSC is within ± 1% of its nominal value
0	Not locked: HFINTOSC may or may not be within ± 1% of its nominal value


# Bit 1 - ACTORS Active Clock Tuning Out-of-Range Status

Value	Description
1	Value required for tuning is outside of the OSCTUNE range
0	Value required for tuning is within the OSCTUNE range

# 12.5.2 OSCCON1

Name: OSCCON1 Offset: 0x0AD

Oscillator Control Register 1



Bits 6:4 - NOSC[2:0] New Oscillator Source Request<sup>(1,2,3)</sup>

Requests a new oscillator source per the NOSC/COSC Clock Source Selection Table

### Bits 3:0 - NDIV[3:0] New Divider Selection Request

Requests the new post-scaler division ratio per the NDIV/CDIV Clock Divider Selection Table


### Notes:

- 1. The default value is determined by the RSTOSC Configuration bits. See Reset Oscillator (RSTOSC) selection table for RSTOSC selections.
- 2. If NOSC is written with a reserved value, the operation is ignored and neither NOSC nor NDIV is written.
- 3. When CSWEN = 0, these bits are read-only and cannot be changed from the RSTOSC value.

# 12.5.3 OSCCON2

Name: OSCCON2 Offset: 0x0AE

Oscillator Control Register 2



Bits 6:4 – COSC[2:0] Current Oscillator Source Select (read-only)<sup>(1)</sup>
Indicates the current oscillator source per the NOSC/COSC Clock Source Selection Table

Bits 3:0 – CDIV[3:0] Current Divider Select (read-only)
Indicates the current post-scaler divider ratio per the NDIV/CDIV Clock Divider Table


# Note:

1. The RSTOSC value is the value present when user code execution begins. Refer to the RSTOSC configuration bits or the RSTOSC selection table for the Reset Oscillator selections.

# 12.5.4 OSCCON3

Name: OSCCON3 Offset: 0x0AF

Oscillator Control Register 3



# Bit 7 - CSWHOLD Clock Switch Hold Control

Value	Description
1	Clock switch (and interrupt) will hold when the oscillator selected by NOSC is ready
0	Clock switch will proceed when the oscillator selected by NOSC is ready

# Bit 6 - SOSCPWR Secondary Oscillator Power Mode Select

Value	Description
1	Secondary Oscillator operates in High-Power mode
0	Secondary Oscillator operates in Low-Power mode

### Bit 4 - ORDY Oscillator Ready (read-only)

	- J ( J/
Value	Description
1	OSCCON1 = OSCCON2; the current system clock is the clock specified by NOSC
0	A clock switch is in progress

# Bit 3 - NOSCR New Oscillator is Ready (read-only)(1)

	/alue	Description
	L	A clock switch is in progress and the oscillator selected by NOSC indicates a 'ready' condition
(	)	A clock switch is not in progress, or the NOSC-selected oscillator is not ready


### Note:

1. If CSWHOLD = 0, the user may not see this bit set (NOSCR = 1). When the oscillator becomes ready, there may be a delay of one instruction cycle before NOSCR is set. The clock switch occurs in the next instruction cycle and NOSCR is cleared.

# **12.5.5 OSCTUNE**

Name: OSCTUNE Offset: 0x0B0

HFINTOSC Frequency Tuning Register




Bits 5:0 - TUN[5:0] HFINTOSC Frequency Tuning

TUN	Condition
01 1111	Maximum frequency
•	•
•	•
•	•
00 0000	Center frequency. Oscillator is operating at the selected nominal frequency. (Default value)
•	•
•	•
•	•
10 0000	Minimum frequency

# 12.5.6 OSCFRQ

Name: OSCFRQ Offset: 0x0B1

HFINTOSC Frequency Selection Register



Bits 3:0 - FRQ[3:0] HFINTOSC Frequency Selection

FRQ	Nominal Freq (MHz)
1111-1001	Reserved
1000	64
0111	48
0110	32
0101	16
0100	12
0011	8
0010	4
0001	2
0000	1

# 12.5.7 OSCSTAT

Name: OSCSTAT Offset: 0x0B2

Oscillator Status Register

Bit	7	6	5	4	3	2	1	0
	EXTOR	HFOR	MFOR	LFOR	SOR	ADOR		PLLR
Access	R	R	R	R	R	R		R
Reset	0	0	0	0	0	0		0

# Bit 7 - EXTOR External Oscillator Ready

Value	Description
1	The External oscillator is ready for use
0	The External oscillator is not enabled, or is not ready for use

# Bit 6 - HFOR HFINTOSC Ready

Value	Description		
1	The HFINTOSC is ready for use		
0	The HFINTOSC is not enabled, or it is not ready for use		

# Bit 5 - MFOR MFINTOSC Ready

Value	Description	
1	The MFINTOSC is ready for use	
0	The MFINTOSC is not enabled, or it is not ready for use	

# Bit 4 - LFOR LFINTOSC Ready

Value	Description
1	The LFINTOSC is ready for use
0	The LFINTOSC is not enabled, or is not ready for use

# Bit 3 - SOR Secondary Oscillator (SOSC) Ready

Value	Description
1	The Secondary oscillator is ready for use
0	The Secondary oscillator is not enabled, or is not ready for use

# Bit 2 - ADOR ADCRC Oscillator Ready

Value	е	Description	
1		The ADCRC oscillator is ready for use	
0		The ADCRC oscillator is not enabled, or is not ready for use	

### Bit 0 - PLLR PLL is Ready

Value	Description
1	The PLL is ready for use
0	The PLL is not enabled, the required input source is not ready, or the PLL is not locked

# 12.5.8 OSCEN

Name: OSCEN Offset: 0x0B3

Oscillator Enable Register

Bit	7	6	5	4	3	2	1	0
	EXTOEN	HFOEN	MFOEN	LFOEN	SOSCEN	ADOEN		PLLEN
Access	R/W	R/W	R/W	R/W	R/W	R/W		R/W
Reset	0	0	0	0	0	0		0

### Bit 7 - EXTOEN External Oscillator Enable

Value	Description	
1	EXTOSC is explicitly enabled, operating as specified by FEXTOSC	
0	EXTOSC can be enabled by a peripheral request	

#### Bit 6 - HFOEN HFINTOSC Enable

Value	Description
1	HFINTOSC is explicitly enabled, operating as specified by OSCFRQ
0	HFINTOSC can be enabled by a peripheral request

### Bit 5 - MFOEN MFINTOSC Enable

Value	Description	
1	MFINTOSC is explicitly enabled	
0	MFINTOSC can be enabled by a peripheral request	

# Bit 4 - LFOEN LFINTOSC Enable

Value	Description
1	LFINTOSC is explicitly enabled
0	LFINTOSC can be enabled by a peripheral request

### Bit 3 - SOSCEN Secondary Oscillator Enable

Value Description						
1		SOSC is explicitly enabled, operating as specified by SOSCPWR				
0		SOSC can be enabled by a peripheral request				

### Bit 2 - ADOEN ADCRC Oscillator Enable

Value	Description			
1	ADCRC is explicitly enabled			
0	ADCRC may be enabled by a peripheral request			

# Bit 0 - PLLEN PLL Enable(1)

	Value	Description
	1	EXTOSC multiplied by the 4x system PLL is used by a peripheral request
0 EXTOSC is used by a peripheral request		EXTOSC is used by a peripheral request

#### Note:

1. This bit only controls external clock source supplied to the peripherals and has no effect on the system clock.

### 12.5.9 **FSCMCON**

Name: FSCMCON Offset: 0x458

Fail-Safe Clock Monitor Control and Status Register

Bit	3it 7 6		5	4	3	2	1	0
			FSCMSFI	FSCMSEV	FSCMPFI	FSCMPEV	FSCMFFI	FSCMFEV
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			0	0	0	0	0	0

#### Bit 5 - FSCMSFI SOSC Fail-Safe Clock Monitor Fault Injection(1)

		Telement Coco rain care creak member raak injection						
	Value	Description						
1 SOSC FSCM clock input is blocked; FSCM will time-out								
	0	SOSC FSCM clock input is enabled; FSCM functions as indicated						

#### Bit 4 – FSCMSEV SOSC Fail-Safe Clock Monitor Status<sup>(2)</sup>

Value	Description			
1	SOSC clock showed a failure			
0	FSCM is detecting SOSC input clocks, or the bit was cleared by the user			

# Bit 3 – FSCMPFI Primary Oscillator Fail-Safe Clock Monitor Fault Injection<sup>(1)</sup>

1	/alue	Description
1	=	Primary Oscillator FSCM clock input is blocked; FSCM will time-out
C	)	Primary Oscillator FSCM clock input is enabled; FSCM functions as indicated

# Bit 2 - FSCMPEV Primary Oscillator Fail-Safe Clock Monitor Status(2)

Value	Description
1	Primary Oscillator clock showed a failure
0	FSCM is detecting primary oscillator input clocks, or the bit was cleared by the user

### Bit 1 - FSCMFFI FOSC Fail-Safe Clock Monitor Fault Injection(1)

Va	alue	Description					
1		FOSC FSCM clock input is blocked; FSCM will time-out					
0		FOSC FSCM clock input is enabled; FSCM functions as indicated					

### Bit 0 - FSCMFEV FOSC Fail-Safe Clock Monitor Status(2)

ı	Value	Description	
	1	FOSC clock showed a failure	
	0	FSCM is detecting FOSC input clocks, or the bit was cleared by the user	

### Notes:

- This bit is used to demonstrate that FSCM can detect clock failure, the bit must be cleared for normal operation
- 2. This bit will not be cleared by hardware upon clock recovery, must be cleared by the user

# 12.6 Register Summary - Oscillator Module

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0	
0x00  0xAB	Reserved										
0xAC	ACTCON	7:0	ACTEN	ACTUD			ACTLOCK		ACTORS		
0xAD	OSCCON1	7:0			NOSC[2:0]			NDIV[3:0]			
0xAE	OSCCON2	7:0			COSC[2:0]			CDI	/[3:0]		
0xAF	OSCCON3	7:0	CSWHOLD	SOSCPWR		ORDY	NOSCR				
0xB0	OSCTUNE	7:0					TUN	[5:0]			
0xB1	OSCFRQ	7:0						FRC	[3:0]		
0xB2	OSCSTAT	7:0	EXTOR	HFOR	MFOR	LFOR	SOR	ADOR		PLLR	
0xB3	OSCEN	7:0	EXTOEN	HFOEN	MFOEN	LFOEN	SOSCEN	ADOEN		PLLEN	
0xB4  0x0457	Reserved										
0x0458	FSCMCON	7:0			FSCMSFI	FSCMSEV	FSCMPFI	FSCMPEV	FSCMFFI	FSCMFEV	

# 13. CRC - Cyclic Redundancy Check Module with Memory Scanner

The Cyclic Redundancy Check (CRC) module provides a software-configurable hardware-implemented CRC checksum generator. This module includes the following features:

- · Any standard CRC up to 32 bits can be used
- · Configurable polynomial
- · Any seed value up to 32 bits can be used
- · Standard and reversed bit order available
- · Augmented zeros can be added automatically or by the user
- · Memory scanner for core-independent CRC calculations on any program memory locations
- Software configurable data registers for communication CRCs

### 13.1 Module Overview

The CRC module is coupled with a memory scanner that provides a means of performing CRC calculations in hardware, without CPU intervention. The memory scanner can automatically provide data from program Flash memory to the CRC module. The CRC module can also be operated by directly writing data to SFRs, without using a scanner.

The CRC module can be used to detect bit errors in the Flash memory using the built-in memory scanner or through user input RAM. The CRC module can accept up to a 32-bit polynomial with up to a 32-bit seed value. A CRC calculated check value (or checksum) will then be generated into the CRCOUT registers for user storage. The CRC module uses an XOR shift register implementation to perform the polynomial division required for the CRC calculation. This feature is useful for calculating CRC values of data being transmitted or received using communications peripherals such as the SPI, UART or I<sup>2</sup>C.

# 13.2 Polynomial Implementation

The CRC polynomial equation is user configurable, allowing any polynomial equation to be used for the CRC checksum calculation. The polynomial and accumulator sizes are determined by the PLEN bits. For an n-bit accumulator, PLEN = n-1 and the corresponding polynomial is n+1 bits. This allows the accumulator to be any size up to 32 bits with a corresponding polynomial up to 33 bits. The MSb and LSb of the polynomial are always '1' which is forced by hardware. Therefore, the LSb of the CRCXOR Low Byte register is hardwired high and always reads as '1'.

All polynomial bits between the MSb and LSb are specified by the CRCXOR registers. For example, when using the standard CRC32, the polynomial is defined as 0x4C11DB7

 $(x^{32} + x^{26} + x^{23} + x^{22} + x^{16} + x^{12} + x^{11} + x^{10} + x^8 + x^7 + x^5 + x^4 + x^2 + x + 1)$ . In this polynomial, the X<sup>32</sup> and X<sup>0</sup> terms are the MSb and LSb controlled by hardware. The X<sup>31</sup> and X<sup>1</sup> terms are specified by setting the CRCXOR[31:0] bits with the corresponding polynomial value, which in this example is  $0 \times 0.04 \text{Cl1DB6}$ . Reading the CRCXOR registers will return  $0 \times 0.04 \text{Cl1DB7}$  because the LSb is always '1'. Refer to the following example for more details.


```
Example 13-1. CRC32 Example Standard CRC32 Polynomial (33 bits):  (x^{32} + x^{26} + x^{23} + x^{22} + x^{16} + x^{12} + x^{11} + x^{10} + x^8 + x^7 + x^5 + x^4 + x^2 + x + 1)  Standard 32-bit Polynomial Representation: 0 \times 0.04 \times 0.010 \times 0.010 \times 0.000 \times 0.0
```

```
Data Sequence: 0x55, 0x66, 0x77, 0x88
DLEN = 0b00111 // Number of bits written to CRCDATA registers (Data
Length)
PLEN = 0b11111 // MSb position of the polynomial (Polynomial Length)
Data passed into the CRC:
// SHIFTM = 0(Shift Mode: MSb first)
0x55 0x66 0x77 0x88 = 01010101 01100110 01110111 10001000
// SHIFTM = 1(Shift Mode: LSb first)
0x55 0x66 0x77 0x88 = 10101010 01100110 11101110 00010001
CRC Check Value (ACCM = 1, data is augmented with zeros)
// When SHIFTM = 0, CRC Check Value = 0x12D0733D
CRCOUTT = 0x12 = 0b00010010
CRCOUTU = 0 \times D0 = 0b11010000
CRCOUTH = 0x73 = 0b01110011
CRCOUTL = 0x3D = 0b00111101
// When SHIFTM = 1, CRC Check Value = 0xE5856F7F
CRCOUTT = 0xE5 = 0b11100101
CRCOUTU = 0x85 = 0b10000101
CRCOUTH = 0x6F = 0b01101111
CRCOUTL = 0x7F = 0b011111111
Note:
     Bit 0 is unimplemented. The LSb of any CRC polynomial is always '1' and will always be
     treated as a '1' by the CRC for calculating the CRC check value. This bit will be read in
     software as a '0'.
```

#### 13.3 Data Sources

Data is supplied to the CRC module using the CRCDATA registers and can either be loaded manually or automatically by using the scanner module. The length of the data word being supplied to the CRC module is specified by the DLEN bits and can be configured for data words up to 32 bits in length. The DLEN field indicates how many bits in the CRCDATA registers are valid and any bits outside of the specified data word size will be ignored. Data is moved into the CRCSHIFT registers as an intermediate to calculate the check value located in the CRCOUT registers. The SHIFTM bit is used to determine the bit order of the data being shifted into the accumulator and the bit order of the result.

### Figure 13-1. CRC Process



When the SHIFTM bit is not set, data will be shifted into the CRC, MSb first and the result will be big-endian. When the SHIFTM bit is set, data will be shifted into the accumulator in the reversed order (LSb first) and the result will be little-endian. The CRC module can be seeded with an initial value by setting the CRCOUT registers to the appropriate value before beginning the CRC process.

### 13.3.1 CRC from User Data

Data can be supplied to the CRC module by writing to the CRCDATA registers. Once data has been loaded into the CRCDATA registers, it will then be latched into the CRC Shift (CRCSHIFT) registers. If data is still being shifted from an earlier write to the CRCDATA registers and the user attempts to write more data, the most recently written data will be held in the CRCDATA registers until the previous shift has completed.

# 13.3.2 CRC from Flash

Data can also be supplied to the CRC module using the memory scanner, as opposed to writing the data manually using the CRCDATA registers, allowing users to automate CRC calculations. An automated scan of Program Flash Memory or Data EEPROM can be performed by configuring the scanner accordingly, to copy data into the CRCDATA registers. The user can initialize the program memory scanner as defined in Scanner Module Overview and Configuring the Scanner.

### 13.4 CRC Check Value

The CRC check value can be accessed using the CRCOUT registers after a CRC calculation has completed. The check value is dependent on the configuration of the ACCM and SHIFTM mode settings. When the ACCM bit is set, the CRC module will augment the data with a number of zeros equal to the length of the polynomial to align the final check value. When the ACCM bit is not set, the CRC will stop at the end of the data and no additional zeroes will be augmented to the final value. The user can manually augment a number of additional zeroes equal to the length of the polynomial by entering them into the CRCDATA register, which would yield the same check value as augmented mode. Alternatively, the expected check value can be entered at this point to make the final result equal zero.

When the CRC check value is computed with the SHIFTM (LSb first) and ACCM bits set, the final value in the CRCOUT registers will be reversed such that the LSb will be in the MSb position and vice versa (Figure 13-1).

When creating a check value to be appended to a data stream, then a reversal must be performed on the final value to achieve the correct checksum. The CRC can be used to do this reversal by following the steps below.

# CRC - Cyclic Redundancy Check Module with Memory S...

- 1. Save CRCOUT value in user RAM space.
- Clear the CRCOUT registers.
- 3. Clear the CRCXOR registers.
- 4. Write the saved CRCOUT value to the CRCDATA input.

If the steps listed above were followed completely, the properly orientated check value will be in the CRCOUT registers as the result.

# 13.5 CRC Interrupt

The CRC module will generate an interrupt when the BUSY bit transitions from '1' to '0'. The CRC Interrupt Flag (CRCIF) bit of the corresponding PIR register will be set every time the BUSY bit transitions, regardless of whether or not the CRC Interrupt Enable (CRCIE) has been set. The CRCIF bit must be cleared by software by the user. If the user has the CRCIE bit set, then the CPU will jump to the Interrupt Service Routine (ISR) every time that the CRCIF bit is set.

# 13.6 Configuring the CRC Module

The following steps illustrate how to properly configure the CRC:

- 1. Determine if the automatic program memory scan will be used with the scanner or manual calculation through the SFR interface and perform the actions specified in the CRC Data Sources section.
  - 1.1. To configure the scanner module to be used with CRC, refer to Configuring the Scanner for more information.
- 2. When applicable, seed a starting CRC value into the CRCOUT registers.
- 3. Program the CRCXOR registers with the desired generator polynomial.
- Program the DLEN bits with the length of the data word (refer to Figure 13-1). This value determines how
  many times the shifter will shift into the accumulator for each data word.
- 5. Program the PLEN bits with the length of the polynomial (refer to Figure 13-1).
- Determine whether shifting in trailing zeroes is desired and set the ACCM bit accordingly.
- 7. Determine whether the MSb or LSb first shifting is desired, and write the SHIFTM bit accordingly.
- 8. Set the GO bit to begin the shifting process.
- 9. If manual SFR entry is used, monitor the FULL bit.
  - 9.1. When FULL = 0, another word of data can be written to the CRCDATA registers. It is important to note that the Most Significant Byte (CRCDATAH) must be written first if the data has more than eight bits, as the shifter will begin upon the CRCDATAL register being written.
  - 9.2. If the scanner is used, the scanner will automatically load words into the CRCDATA registers as needed, as long as the GO bit is set.
- If using the Flash memory scanner, monitor the SCANIF bit of the corresponding PIR register to determine when the scanner has finished pushing data into the CRCDATA registers.
  - 10.1. After the scan is completed, monitor the SGO bit to determine that the CRC has been completed and the check value can be read from the CRCOUT registers.
  - 10.2. When both the interrupt flags are set (or both BUSY and SGO bits are cleared), the completed CRC calculation can be read from the CRCOUT registers.
- 11. If manual entry is used, monitor the BUSY bit to determine when the CRCOUT registers hold the valid check value.

# 13.6.1 Register Overlay

The CRCOUT, CRCSHIFT and CRCXOR registers are grouped together and share SFR space. Since these register groups are located within the same addresses, the SETUP bits must be configured accordingly, to access any of these registers. Refer to the CRCCON2 register for more information about how the SETUP bits can be configured to access each of the available CRC registers.

### 13.7 Scanner Module Overview

The scanner allows segments of the Program Flash Memory or Data EEPROM to be read out (scanned) to the CRC peripheral. The scanner module interacts with the CRC module and supplies it data, one word at a time. Data is fetched from the address range defined by SCANLADR registers up to the SCANHADR registers. The scanner begins operation when the SGO bit is set and ends when either SGO is cleared by the user or when SCANLADR increments past SCANHADR. The SGO bit is also cleared when the EN bit in the CRCCONO register is cleared.

# 13.8 Scanning Modes

The interaction of the scanner with the system operation is controlled by the priority selection in the system arbiter (Refer to the "Memory Access Scheme" section for more details.). When using the scanner module in conjunction with the CRC module, the system arbiter should be configured such that the scanner has a higher priority than the CPU to ensure that a memory access request is granted when it occurs. Additionally, BURSTMD and TRIGEN bits also determine the operation of the scanner.

#### 13.8.1 TRIGEN = 0, BURSTMD = 0

In this case, the memory access request is granted to the scanner if no other higher priority source is requesting access. All sources with lower priority than the scanner will get the memory access cycles that are not utilized by the scanner.

### **13.8.2** TRIGEN = 1, BURSTMD = 0

In this case, the memory access request is generated when the CRC module is ready to accept. The memory access request is granted to the scanner if no other higher priority source is requesting access. All sources with lower priority than the scanner will get the memory access cycles that are not utilized by the scanner.

### 13.8.3 TRIGEN = x, BURSTMD = 1

In this case, the memory access is always requested by the scanner. The memory access request is granted to the scanner if no other higher priority source is requesting access. The memory access cycles will not be granted to lower priority sources than the scanner until it completes operation, i.e. SGO = 0.



**Important:** If TRIGEN = 1 and BURSTMD = 1, the user should ensure that the trigger source is active for the scanner operation to complete.

### 13.8.4 WWDT Interaction

The Windowed Watch Dog Timer (WWDT) operates in the background during scanner activity. It is possible that long scans, particularly in Burst mode, may exceed the WWDT time-out period and result in an undesired device Reset. This must be considered when performing memory scans with an application that also utilizes WWDT.

# 13.9 Configuring the Scanner

The scanner module may be used in conjunction with the CRC module to perform a CRC calculation over a range of program memory or Data EEPROM addresses. In order to set up the scanner to work with the CRC, perform the following steps:

- Set up the CRC module (See Configuring the CRC Module) and enable the scanner module by setting the EN bit in the SCANCON0 register.
- Choose which memory region the scanner module should operate on and set the MREG bit appropriately.
- If trigger is used for scanner operation, set the TRIGEN bit and select the trigger source using the SCANTRIG register. Select the trigger source using the SCANTRIG register and then set the TRIGEN bit.
- If Burst mode of operation is desired, set the BURSTMD bit.

# CRC - Cyclic Redundancy Check Module with Memory S...

- Set the SCANLADR and SCANHADR registers with the beginning and ending locations in memory that are to be scanned.
- Select the priority level for the scanner module. (Refer to the "System Arbitration" and the "Priority Lock" sections for more details.)
  - **Note:** The default priority levels of the system arbiter may need to be changed to ensure the scanner operates as intended and that a memory access request is granted when it occurs.
- Both EN and GO bits in the CRCCON0 register must be enabled to use the scanner. Setting the SGO bit will start the scanner operation.

# 13.10 Scanner Interrupt

The scanner will trigger an interrupt when the SGO bit transitions from '1' to '0'. The SCANIF interrupt flag of one of the PIR registers is set when the last memory location is reached and the data is entered into the CRCDATA registers. The SCANIF bit must be cleared by software. The SCAN interrupt enable is the SCANIE bit of the corresponding PIE register.

# 13.11 Peripheral Module Disable

Both the CRC and scanner module can be disabled individually by setting the CRCMD and SCANMD bits of one of the PMD registers (see the "Peripheral Module Disable" chapter for more details). The SCANMD bit can be used to enable or disable the scanner module only if the SCANE configuration bit is set. If the SCANE bit is cleared, then the scanner module is not available for use and the SCANMD bit is ignored.

### 13.12 CRC-on-Boot Module Overview

The CRC-on-boot module performs a CRC (Cyclic Redundancy Check) on user-defined segments of non-volatile memory on device power-up and compares the resulting values to predetermined expected values. This check acts independent of program memory and executes before any user code. If a mismatch occurs, the CRC-on-boot module can be configured to indicate this mismatch in several configurable ways.

The CRC-on-boot has the following features:

- · Scanning Program Memory Boot Block
- Scanning Non-Boot Block Non-Volatile Memory
  - Program Memory Application Block
  - Program Memory SAF segment
  - Configuration Words
  - Data EEPROM
- Ability to either halt the device on mismatch or continue to user code execution
- · Mismatch indicating the output can be enabled/disabled, relocated and configured as open-drain

### 13.12.1 Enabling the Module

To enable the CRC-on-boot module, the BOOTPOR Configuration bit must be cleared. While this bit is set, the device will always bypass the CRC upon start-up and begin execution at the Reset vector of program memory.

# 13.12.2 Polynomial, Seed, and Expected Values

The CRC-on-boot module runs CRC scans and calculations on two regions of memory: the boot segment and the non-boot segment (which comprises of all non-boot program memory area, data EEPROM and Configuration memory). Each of these two regions has 12 configuration bytes for the CRC calculation: four each for the 32-bit polynomial, seed and expected values.

# 13.12.3 Memory Selection

The CRC-on-boot module can be configured to scan and perform a CRC on five NVM regions: The boot, application, SAF segments of program memory, data EEPROM memory and Configuration Words. Each is enabled individually

# **CRC - Cyclic Redundancy Check Module with Memory S...**

by clearing Configuration bits CFGSCEN, DATSCEN, SAFSCEN, APPSCEN and BOOTSCEN for the configuration memory, EEPROM, SAF section, application section and boot section, respectively. Each memory segment is treated slightly differently and can vary based on other configuration settings:

- The data EEPROM segment scans the entire data EEPROM memory of the device.
- The configuration memory scans all configuration memory, except the four bytes for the non-boot CRC expected value (as this would be self-referencing and cause issues in CRC calculation).
- The SAF area scans the Storage Area Flash region (the last 128 words of program memory) if the SAFEN Configuration bit is cleared (Storage Area Flash enabled). If the Storage Area Flash is disabled, attempting to scan this region will result in the CRC-on-boot indicating a mismatch.
- The boot area scans the region of program memory defined by the BBEN and BBSIZE Configuration bits. If the BBEN bit is set (disabling boot area), attempting to scan this region will result in the CRC-on-boot indicating a mismatch.
- The application area scans the remainder of program memory not specifically designated for the Boot Block or the SAF.

# 13.12.4 Output Pin Setup

The output of the CRC-on-boot module will output low while performing the CRC calculation, and will output high upon confirming a match. The ODCON Configuration bit, when set, allows the pin to drive both high and low. Clearing the ODCON bit will cause the pin to only drive low, relying on an external pull-up for the high level. The BOOTPINSEL Configuration bits allow for a selection of four different CRC mismatch error output pins. The selected pin will be completely controlled by the CRC-on-boot module and therefore will be unusable by any other modules. Clearing the BPEN Configuration bit enables the output of the CRC-on-boot module. While this bit is set, the CRC may still occur, but the output pin selected by BOOTPINSEL will not indicate the status of the check and remain available for other peripheral functions.

#### 13.12.5 CRC Calculation

When the module is enabled (upon POR), the device will scan the regions selected (as defined in 13.12.3 Memory Selection) and run respective CRCs for them, using the 32-bit CRC module. For the boot section, the CRC polynomial (CRCXOR) is determined by the BCRCPOL value in configuration memory, the seed value (CRCOUT) is determined by the BCRCSEED value in configuration memory, the CRC accumulator mode is configured to augment the data with zeroes (ACCM = 1) and the data is read in 16-bit segments (CRCCON2 = 0x0F). The resulting check value is compared to the BCRCERES value in configuration memory.

For the non-boot sections (application, SAF, configuration and data EEPROM), all selected sections are scanned and calculated together using the polynomial from the CRCPOL value in configuration memory, the seed from the CRCSEED value in configuration memory and is compared against the CRCERES value in configuration memory. Like the boot section, the CRC for non-boot sections is configured to augment the data with zeroes (ACCM = 1). For the application and SAF sections, the data is read in 16-bit segments (CRCCON2 = 0x0F), while for the configuration and data EEPROM sections, the data is read in 8-bit segments (CRCCON2 = 0x07).

#### 13.12.6 Mismatch Condition

If the CRC-on-boot module detects a mismatch between the calculated check value and the expected value for the boot section, three events occur:

- The output pin of the CRC-on-boot module (if any is selected) remains driven low.
- The B0 bit of the BOOTREG register remains 0.
- The module checks the BCOE configuration bit. If it is clear, the module will continue to the non-Boot CRC
  check (if enabled), otherwise, it will continue to user code. If it is set, the module will halt and not execute any
  further code.

If the CRC-on-Boot module detects a mismatch between the calculated check value and the expected value for the non-Boot section, three events occur:

- The output pin of the CRC-on-Boot module (if any is selected) remains driven low
- The B1 bit of the BOOTREG register remains `0'.
- The module checks the COE configuration bit. If it is clear, the module will continue to user code. If it is set, the
  module will halt and not execute any further code.

# PIC18F26/46/56Q84

# CRC - Cyclic Redundancy Check Module with Memory S...

If a mismatch is not detected in a section (or if scanning of that section is disabled), the associated bit of BOOTREG associated with that section (B0 for boot, B1 for non-boot) will be set. If all calculated CRC check values match their expected values, the output pin of the CRC-on-boot module (if any is selected) will be either driven high or released (depending on the ODCON Configuration bit) and user code will be executed beginning from the Reset vector.

# 13.13 Register Definitions: CRC and Scanner Control

Long bit name prefixes for the CRC are shown in the table below. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 13-1. CRC Long Bit Name Prefixes

Peripheral	Bit Name Prefix
CRC	CRC

# 13.13.1 CRCCON0

Name: CRCCON0 Offset: 0x357

CRC Control Register 0

Bit	7	6	5	4	3	2	1	0
	EN	GO	BUSY	ACCM	SETUP[1:0]		SHIFTM	FULL
Access	R/W	R/W	R	R/W	R/W		R/W	R
Reset	0	0	0	0	0		0	0

# Bit 7 - EN CRC Enable

Value	Description
1	CRC module is released from Reset
0	CRC is disabled and consumes no operating current

#### Bit 6 - GO CRC Start

Value	Description
1	Start CRC serial shifter
0	CRC serial shifter turned off

# Bit 5 - BUSY CRC Busy

Value	Description
1	Shifting in progress or pending
0	All valid bits in shifter have been shifted into accumulator and EMPTY = 1

# Bit 4 - ACCM Accumulator Mode

Val	lue	Description
1		Data is augmented with zeros
0		Data is not augmented with zeros

# Bits 4:3 - SETUP[1:0]

Register Overlay Setup

rtegister t	register Overlay Octup					
Value	Description					
11	CRC Register Overlay Selection; Read / Write access to CRCOUT					
10	CRC Register Overlay Selection; Read / Write access to CRCXOR					
01	CRC Register Overlay Selection; Read / Write access to CRCSHIFT					
00	CRC Register Overlay Selection; Read / Write access to CRCOUT					

# Bit 1 - SHIFTM Shift Mode

Value	Description
1	Shift right (LSb first)
0	Shift left (MSb first)


#### Bit 0 - FULL Data Path Full Indicator

Value	Description						
1	CRCDATAT/U/H/L registers are full						
0	CRCDATAT/U/H/L registers have shifted their data into the shifter						

# 13.13.2 CRCCON1

Name: CRCCON1 Offset: 0x358

CRC Control Register 1




Bits 4:0 – PLEN[4:0] Polynomial Length Denotes the length of the polynomial (n-1)

# 13.13.3 CRCCON2

Name: CRCCON2 Offset: 0x359

CRC Control Register 2



Bits 4:0 – DLEN[4:0] Data Length Denotes the length of the data word (n-1)

# 13.13.4 CRCDATA

Name: CRCDATA Offset: 0x34F

**CRC Data Registers** 

Bit	31	30	29	28	27	26	25	24		
	CRCDATAT[7:0]									
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		
Bit	23	22	21	20	19	18	17	16		
				CRCDA	TAU[7:0]					
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		
Bit	15	14	13	12	11	10	9	8		
				CRCDA	TAH[7:0]					
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		
Bit	7	6	5	4	3	2	1	0		
				CRCDA	TAL[7:0]					
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		

Bits 31:24 - CRCDATAT[7:0] CRC Data Top Byte

Bits 23:16 - CRCDATAU[7:0] CRC Data Upper Byte

Bits 15:8 - CRCDATAH[7:0] CRC Data High Byte

Bits 7:0 - CRCDATAL[7:0] CRC Data Low Byte

# 13.13.5 CRCOUT

Name: CRCOUT Offset: 0x353

**CRC Output Registers** 

Bit	31	30	29	28	27	26	25	24		
	CRCOUTT[7:0]									
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		
Bit	23	22	21	20	19	18	17	16		
				CRCOL	JTU[7:0]					
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		
Bit	15	14	13	12	11	10	9	8		
				CRCOL	JTH[7:0]					
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		
Bit	7	6	5	4	3	2	1	0		
	CRCOUTL[7:0]									
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		

# Bits 31:24 - CRCOUTT[7:0] CRC Output Register Top Byte

Writing to this register writes the Most Significant Byte of the CRC output register. Reading from this register reads the Most Significant Byte of the CRC output.

Bits 23:16 - CRCOUTU[7:0] CRC Output Register Upper Byte

Bits 15:8 - CRCOUTH[7:0] CRC Output Register High Byte

# Bits 7:0 - CRCOUTL[7:0] CRC Output Register Low Byte

Writing to this register writes the Least Significant Byte of the CRC output register. Reading from this register reads the Least Significant Byte of the CRC output.

# 13.13.6 CRCSHIFT

Name: CRCSHIFT Offset: 0x353

**CRC Shift Registers** 

Bit	31	30	29	28	27	26	25	24		
	CRCSHIFTT[7:0]									
Access	R	R	R	R	R	R	R	R		
Reset	0	0	0	0	0	0	0	0		
Bit	23	22	21	20	19	18	17	16		
				CRCSH	IFTU[7:0]					
Access	R	R	R	R	R	R	R	R		
Reset	0	0	0	0	0	0	0	0		
Bit	15	14	13	12	11	10	9	8		
				CRCSH	IFTH[7:0]					
Access	R	R	R	R	R	R	R	R		
Reset	0	0	0	0	0	0	0	0		
Bit	7	6	5	4	3	2	1	0		
	CRCSHIFTL[7:0]									
Access	R	R	R	R	R	R	R	R		
Reset	0	0	0	0	0	0	0	0		

Bits 31:24 - CRCSHIFTT[7:0] CRC Shift Register Top Byte

Reading from this register reads the Most Significant Byte of the CRC Shifter.

Bits 23:16 - CRCSHIFTU[7:0] CRC Shift Register Upper Byte

Bits 15:8 - CRCSHIFTH[7:0] CRC Shift Register High Byte

Bits 7:0 - CRCSHIFTL[7:0] CRC Shift Register Low Byte

Reading from this register reads the Least Significant Byte of the CRC Shifter.

# 13.13.7 CRCXOR

Name: CRCXOR Offset: 0x353

**CRC XOR Registers** 

Bit	31	30	29	28	27	26	25	24			
	CRCXORT[7:0]										
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W			
Reset	0	0	0	0	0	0	0	0			
Bit	23	22	21	20	19	18	17	16			
				CRCXC	RU[7:0]						
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W			
Reset	0	0	0	0	0	0	0	0			
Bit	15	14	13	12	11	10	9	8			
				CRCXC	RH[7:0]						
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W			
Reset	0	0	0	0	0	0	0	0			
Bit	7	6	5	4	3	2	1	0			
	CRCXORL[7:0]										
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W			
Reset	0	0	0	0	0	0	0	0			

Bits 31:24 - CRCXORT[7:0] XOR of Polynomial Term XN Enable Top Byte

Bits 23:16 - CRCXORU[7:0] XOR of Polynomial Term XN Enable Upper Byte

Bits 15:8 - CRCXORH[7:0] XOR of Polynomial Term XN Enable High Byte

Bits 7:0 - CRCXORL[7:0] XOR of Polynomial Term XN Enable Low Byte

# 13.13.8 SCANCON0

Name: SCANCON0 Offset: 0x360

Scanner Access Control Register 0

Bit	7	6	5	4	3	2	1	0
	EN	TRIGEN	SGO			MREG	BURSTMD	BUSY
Access	R/W	R/W	R/W/HC			R/W	R/W	R/W
Reset	0	0	0			1	0	0

# Bit 7 - EN Scanner Enable(1)

Value	Description
1	Scanner is enabled
0	Scanner is disabled

# Bit 6 - TRIGEN Scanner Trigger Enable<sup>(2,5)</sup>

Value	Description
1	Scanner trigger is enabled
0	Scanner trigger is disabled

# Bit 5 - SGO Scanner GO(3,4)

Value	Description
1	When the CRC is ready, the Memory region set by the MREG bit will be accessed and data is passed to the CRC peripheral.
0	Scanner operations will not occur

# Bit 2 - MREG Scanner Memory Region Select<sup>(2)</sup>

_	
Value	Description
1	Scanner address points to Data EEPROM
0	Scanner address points to Program Flash Memory

# Bit 1 - BURSTMD Scanner Burst Mode<sup>(5)</sup>

Value	Description
1	Memory access request to the CPU Arbiter is always true
0	Memory access request to the CPU Arbiter is dependent on the CRC request and Trigger

# Bit 0 - BUSY Scanner Busy Indicator

Value	Description
1	Scanner cycle is in process
0	Scanner cycle is compete (or never started)

#### Notes:

- 1. Setting EN = 0 does not affect any other register content.
- 2. Scanner trigger selection can be set using the SCANTRIG register.
- 3. This bit can be cleared in software. It is cleared in hardware when LADR > HADR (and a data cycle is not occurring) or when CRCGO = 0.
- 4. CRCEN and CRCGO bits must be set before setting the SGO bit.
- 5. See Table 13-2.

**Table 13-2. Scanner Operating Modes** 

TRIGEN	BURSTMD	Scanner Operation
0	0	Memory access is requested when the CRC module is ready to accept data; the request is granted if no other higher priority source request is pending.
1	0	Memory access is requested when the CRC module is ready to accept data and trigger selection is true; the request is granted if no other higher priority source request is pending.
х	1	Memory access is always requested; the request is granted if no other higher priority source request is pending.

**Note:** Refer to the "**System Arbitration**" and the "**Memory Access Scheme**" sections for more details about Priority selection and Memory Access Scheme.

# 13.13.9 SCANLADR

Name: SCANLADR

Scan Low Address Registers

Bit	23	22	21	20	19	18	17	16
					SCANLA	DRU[5:0]		
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			0	0	0	0	0	0
Bit	15	14	13	12	11	10	9	8
				SCANLA	DRH[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
				SCANLA	DRL[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

### Bits 21:16 - SCANLADRU[5:0] Scan Start/Current Address upper byte

Upper bits of the current address to be fetched from, value increments on each fetch of memory.

# Bits 15:8 - SCANLADRH[7:0] Scan Start/Current Address high byte

High byte of the current address to be fetched from, value increments on each fetch of memory.

### Bits 7:0 - SCANLADRL[7:0] Scan Start/Current Address low byte

Low byte of the current address to be fetched from, value increments on each fetch of memory.

#### Notes:

- 1. Registers SCANLADRU/H/L form a 22-bit value, but are not guarded for atomic or asynchronous access; registers may only be read or written while SGO = 0.
- 2. While SGO = 1, writing to this register is ignored.

# 13.13.10 SCANHADR

Name: SCANHADR

Scan High Address Registers

Bit	23	22	21	20	19	18	17	16
					SCANHA	.DRU[5:0]		
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			1	1	1	1	1	1
Bit	15	14	13	12	11	10	9	8
				SCANHA	DRH[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1
Bit	7	6	5	4	3	2	1	0
				SCANHA	DRL[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

# Bits 21:16 - SCANHADRU[5:0] Scan End Address

Upper bits of the address at the end of the designated scan

# Bits 15:8 - SCANHADRH[7:0] Scan End Address

High byte of the address at the end of the designated scan

### Bits 7:0 - SCANHADRL[7:0] Scan End Address

Low byte of the address at the end of the designated scan


### Notes:

- 1. Registers SCANHADRU/H/L form a 22-bit value but are not guarded for atomic or asynchronous access; registers may only be read or written while SGO = 0.
- 2. While SGO = 1, writing to this register is ignored.

# 13.13.11 SCANTRIG

Name: SCANTRIG Offset: 0x361

SCAN Trigger Selection Register



Bits 4:0 - TSEL[4:0] Scanner Data Trigger Input Selection

Table 13-3. Scanner Data Trigger Input Sources

TSEL Value	Trigger Input Sources
11111-10110	_
10110	CLC8_OUT
10101	CLC7_OUT
10100	CLC6_OUT
10011	CLC5_OUT
10010	CLC4_OUT
10001	CLC3_OUT
10000	CLC2_OUT
01111	CLC1_OUT
01110	SMT1_OUT
01101	Reserved
01100	Reserved
01011	Reserved
01010	TU16B_OUT
01001	TU16A_OUT
01000	TMR6_Postscaler_OUT
00111	TMR5_OUT
00110	TMR4_Postscaler_OUT
00101	TMR3_OUT
00100	TMR2_Postscaler_OUT
00011	TMR1_OUT
00010	TMR0_OUT
00001	CLCKREF_OUT
00000	LFINTOSC <sup>(1)</sup>

# Note:

1. The number of implemented bits varies by device.

# 13.13.12 BOOTREG

Name: BOOTREG Offset: 0x038

CRC on Boot Status Register



# Bit 7 - BPOUT CRC-on-Boot Output Pin Value

1	Value	Description
	1	Drive CRC-on-Boot Output Pin to 1/Tri-state pin (depending on setting of nODCON configuration bit
	0	Drive CRC-on-Boot Output Pin to 0

# Bit 6 - BOOTDONE CRC-on-Boot on Previous Reset Status/ CRC-on-Bot on Next Reset Configuration

ı	Value	Description
	1	CRC-on-Boot has run on previous reset, run user code on next non-POR reset
	0	Run CRC-on-Boot on next non-POR reset

# Bit 1 - B1 CRC-on-Boot Output 1

Value	Description
1	No CRC mismatch in non-Boot Sector (Application sector, SAF sector, data EEPROM, CONFIG)
0	CRC mismatch in non-Boot Sector

# Bit 0 - B0 CRC-on-Boot Output 0

1	/alue	Description
1		No CRC mismatch in Boot Sector
C	)	CRC mismatch in Boot Sector

# 13.14 Register Summary - CRC

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x37										
0x38	BOOTREG	7:0	BPOUT	BOOTDONE					B1	В0
0x39										
 0x034E	Reserved									
		7:0	CRCDATAL[7:0]							
0x034F	CRCDATA	15:8				CRCDA	TAH[7:0]			
UXU34F	CRODAIA	23:16				CRCDA	TAU[7:0]			
		31:24		CRCDATAT[7:0]						
		7:0	7:0 CRCOUTL[7:0]							
0x0353	CRCOUT	15:8	CRCOUTH[7:0]							
	CRCOOT	23:16	CRCOUTU[7:0]							
		31:24	CRCOUTT[7:0]							
		7:0				CRCSH	IFTL[7:0]			
0x0353	CRCSHIFT	15:8	CRCSHIFTH[7:0]							
UXUSSS	CRCSHIFT	23:16	CRCSHIFTU[7:0]							
		31:24				CRCSH	IFTT[7:0]			
		7:0				CRCXC	DRL[7:0]			
0x0353	CRCXOR	15:8	CRCXORH[7:0]							
UXUSSS	CRCAUR	23:16	CRCXORU[7:0]							
		31:24				CRCXC	DRT[7:0]			
0x0357	CRCCON0	7:0	EN	GO	BUSY	ACCM	SETU	IP[1:0]	SHIFTM	FULL
0x0358	CRCCON1	7:0						PLEN[4:0]		
0x0359	CRCCON2	7:0						DLEN[4:0]		
0x035A										
	Reserved									
0x035F										
0x0360	SCANCON0	7:0	EN	TRIGEN	SGO			MREG	BURSTMD	BUSY
0x0361	SCANTRIG	7:0						TSEL[4:0]		


## 14. Resets

There are multiple ways to reset the device:

- Power-on Reset (POR)
- Brown-out Reset (BOR)
- · Low-Power Brown-out Reset (LPBOR)
- MCLR Reset
- WDT Reset
- RESET instruction
- Stack Overflow
- Stack Underflow
- · Programming mode exit
- · Memory Execution Violation Reset
- · Main LDO Voltage Regulator Reset
- Configuration Memory Reset

A simplified block diagram of the On-Chip Reset Circuit is shown in the block diagram below.

Figure 14-1. Simplified Block Diagram of On-Chip Reset Circuit



#### Note:

1. See BOR Operating Modes table for BOR active conditions.

## 14.1 Power-on Reset (POR)

The POR circuit holds the device in Reset until  $V_{DD}$  has reached an acceptable level for minimum operation. Slow rising  $V_{DD}$ , fast operating speeds or analog performance may require greater than minimum  $V_{DD}$ . The PWRT, BOR or  $\overline{\text{MCLR}}$  features can be used to extend the start-up period until all device operation conditions have been met. The  $\overline{\text{POR}}$  bit will be set to '0' if a Power-on Reset has occurred.

## 14.2 Brown-out Reset (BOR)

The BOR circuit holds the device in Reset when  $V_{DD}$  reaches a selectable minimum level. Between the POR and BOR, complete voltage range coverage for execution protection can be implemented. The  $\overline{BOR}$  bit will be set to '0' if a Brown-out Reset has occurred.

The Brown-out Reset module has four operating modes controlled by the BOREN Configuration bits. The four operating modes are:

- · BOR is always on
- · BOR is off when in Sleep
- · BOR is controlled by software
- · BOR is always off

Refer to the BOR Operating Modes table for more information.

A  $V_{DD}$  noise rejection filter prevents the BOR from triggering on small events. If  $V_{DD}$  falls below  $V_{BOR}$  for a duration greater than parameter  $T_{BORDC}$ , the device will reset. Refer to the "**Electrical Specifications**" chapter for more details.

#### 14.2.1 BOR is Always ON

When the BOREN Configuration bits are programmed to 'b11, the BOR is always on. The device start-up will be delayed until the BOR is ready and  $V_{DD}$  is higher than the BOR threshold.

BOR protection is active during Sleep. The BOR does not delay wake-up from Sleep.

#### 14.2.2 BOR is OFF in Sleep

When the BOREN Configuration bits are programmed to 'b10, the BOR is on, except in Sleep. The device start-up will be delayed until the BOR is ready and V<sub>DD</sub> is higher than the BOR threshold.

BOR protection is not active during Sleep. The device wake-up will be delayed until the BOR is ready.

#### 14.2.3 BOR Controlled by Software

When the BOREN Configuration bits are programmed to 'b01, the BOR is controlled by the SBOREN bit. The device start-up is not delayed by the BOR ready condition or the  $V_{DD}$  level.

BOR protection begins as soon as the BOR circuit is ready. The status of the BOR circuit is reflected in the BORRDY bit.

BOR protection selected by SBOREN bit is unchanged by Sleep.

#### 14.2.4 BOR is always OFF

When the BOREN Configuration bits are programmed to 'b00, the BOR is off at all times. The device start-up is not delayed by the BOR ready condition or the  $V_{DD}$  level.

Table 14-1. BOR Operating Modes


PODEN	SPOREN	Dovice Mede	POR Mode	Instruction Execu	tion upon:
BOREN SBOREN		Device Mode	BOR WIOGE	Release of POR	Wake-up from Sleep
11(1)	х	Х	Active	Wait for release of BOR (BORRDY = 1)	Begins immediately
10	Awak	Awake	Active	Wait for release of BOR (BORRDY = 1)	N/A
10	^	Sleep	Hibernate	N/A	Wait for release of BOR (BORRDY = 1)

continued							
PODEN	CROBEN	CRODEN	Davisa Mada	POP Mode	Instruction Execution upon:		
BOREN SBOREN Device Mod		Device Mode	BOR Wode	Release of POR	Wake-up from Sleep		
0.1	1	X	Active	Wait for release of BOR (BORRDY	Begins immediately		
01	0	X	Hibernate	= 1)	Degins ininediately		
00	X	X	Disabled	Begins immediately			

#### Note:

1. In this specific case, "Release of POR" and "Wake-up from Sleep", there is no BOR ready delay in start-up. The BOR ready flag, (BORRDY = 1), will be set before the CPU is ready to execute instructions because the BOR circuit is forced on by the BOREN bits.

Figure 14-2. Brown-out Situations



#### Note:

1. T<sub>PWRT</sub> delay only if the Configuration bits enable the Power-up Timer.

#### 14.2.5 BOR and Bulk Erase

BOR is forced ON during PFM Bulk Erase operations to make sure that the system code protection cannot be compromised by reducing  $V_{DD}$ .


During Bulk Erase, the BOR is enabled at the lowest BOR threshold level, even if it is configured to some other value. If  $V_{DD}$  falls, the erase cycle will be aborted, but the device will not be reset.

# 14.3 Low-Power Brown-out Reset (LPBOR)

The Low-Power Brown-out Reset (LPBOR) provides an additional BOR circuit for low-power operation. Refer to the figure below to see how the BOR interacts with other modules.

The LPBOR is used to monitor the external  $V_{DD}$  pin. When too low of a voltage is detected, the device is held in Reset.

Figure 14-3. LPBOR, BOR, POR Relationship



#### 14.3.1 Enabling LPBOR

The LPBOR is controlled by the LPBOREN Configuration bit. When the device is erased, the LPBOR module defaults to disabled.

#### 14.3.2 LPBOR Module Output

The output of the LPBOR module indicates whether or not a Reset is to be asserted. This signal is OR'd with the Reset signal of the BOR module to provide the generic BOR signal, which goes to the PCON0 register and to the power control block.

# 14.4 MCLR Reset

 $\overline{\text{MCLR}}$  is an optional external input that can reset the device. The  $\overline{\text{MCLR}}$  function is controlled by the MCLRE and LVP Configuration bits (see table below). The  $\overline{\text{RMCLR}}$  bit will be set to '0' if a  $\overline{\text{MCLR}}$  has occurred.

Table 14-2. MCLR Configuration

MCLRE	LVP	MCLR
х	1	Enabled
1	0	Enabled
0	0	Disabled

#### 14.4.1 MCLR Enabled

When  $\overline{MCLR}$  is enabled and the pin is held low, the device is held in Reset. The  $\overline{MCLR}$  pin is connected to  $V_{DD}$  through an internal weak pull-up.

The device has a noise filter in the MCLR Reset path. The filter will detect and ignore small pulses.



**Important:** An internal Reset event (RESET instruction, BOR, WWDT, POR, STKOVF, STKUNF) does not drive the  $\overline{MCLR}$  pin low.

#### 14.4.2 MCLR Disabled

When MCLR is disabled, the MCLR pin becomes input-only and pin functions such as internal weak pull-ups are under software control.

# 14.5 Windowed Watchdog Timer (WWDT) Reset

The Windowed Watchdog Timer generates a Reset if the firmware does not issue a CLRWDT instruction within the time-out period or window set. The  $\overline{\text{TO}}$  and  $\overline{\text{PD}}$  bits in the STATUS register and the  $\overline{\text{RWDT}}$  bit are changed to indicate a WDT Reset. The  $\overline{\text{WDTWV}}$  bit indicates if the WDT Reset has occurred due to a time-out or a window violation.

#### 14.6 RESET Instruction

A RESET instruction will cause a device Reset. The  $\overline{RI}$  bit will be set to '0'. See Table 14-3 for default conditions after a RESET instruction has occurred.

#### 14.7 Stack Overflow/Underflow Reset

The device can be reset when the Stack Overflows or Underflows. The STKOVF or STKUNF bits indicate the Reset condition. These Resets are enabled by setting the STVREN Configuration bit.

#### 14.8 Programming Mode Exit

Upon exit of Programming mode, the device will operate as if a POR had just occurred.

# 14.9 Power-up Timer (PWRT)

The Power-up Timer provides a selected time-out duration on POR or Brown-out Reset.

The device is held in Reset as long as PWRT is active. The PWRT delay allows additional time for  $V_{DD}$  to rise to an acceptable level. The Power-up Timer is selected by setting the PWRTS Configuration bits accordingly.

The Power-up Timer starts after the release of the POR and BOR/LPBOR if enabled, as shown in Figure 14-4.


#### 14.10 Start-up Sequence

Upon the release of a POR or BOR, the following must occur before the device will begin executing:

- 1. Power-up Timer runs to completion (if enabled).
- 2. Oscillator Start-up Timer runs to completion (if required for selected oscillator source).
- 3. MCLR must be released (if enabled).

The total time-out will vary based on the oscillator configuration and Power-up Timer configuration.

The Power-up Timer and Oscillator Start-up Timer run independently of MCLR Reset. If MCLR is kept low long enough, the Power-up Timer and Oscillator Start-up Timer will expire. Upon bringing MCLR high, the device will begin execution after 10 F<sub>OSC</sub> cycles (see figure below). This is useful for testing purposes or to synchronize more than one device operating in parallel.



# 14.10.1 Memory Execution Violation

A memory execution violation Reset occurs if executing an instruction being fetched from outside the valid execution area. The invalid execution areas are:

- 1. Addresses outside implemented program memory
- 2. Storage Area Flash (SAF) inside program memory, if it is enabled

When a memory execution violation is generated, the device is reset and the MEMV bit is cleared to signal the cause of the Reset. The MEMV bit must be set in the user code after a memory execution violation Reset has occurred to detect further violation Resets.

# 14.11 Determining the Cause of a Reset

Upon any Reset, multiple bits in the STATUS and PCON0 registers are updated to indicate the cause of the Reset. The following table shows the Reset conditions of these registers.

Table 14-3. Reset Condition for Special Registers

Condition	Program Counter	STATUS Register <sup>(1,2)</sup>	PCON0 Register	PCON1 Register
Power-on Reset	0	-110 0000	0011 110x	111
Brown-out Reset	0	-110 0000	0011 11u0	u1u

continued				
Condition	Program Counter	STATUS Register <u><sup>(1,2)</sup></u>	PCON0 Register	PCON1 Register
MCLR Reset during normal operation	0	-uuu uuuu	uuuu Ouuu	uuu
MCLR Reset during Sleep	0	-10u uuuu	uuuu Ouuu	uuu
WDT Time-out Reset	0	-0uu uuuu	uuu0 uuuu	uuu
WDT Wake-up from Sleep	PC + 2	-00u uuuu	uuuu uuuu	uuu
WWDT Window Violation Reset	0	-uuu uuuu	uu0u uuuu	uuu
Interrupt Wake-up from Sleep	PC + 2 <sup>(3)</sup>	-10u uuuu	uuuu uuuu	uuu
RESET Instruction Executed	0	-uuu uuuu	uuuu u0uu	uuu
Stack Overflow Reset (STVREN = 1)	0	-uuu uuuu	1uuu uuuu	uuu
Stack Underflow Reset (STVREN = 1)	0	-uuu uuuu	uluu uuuu	uuu
Data Protection (Fuse Fault)	0	-uuu uuuu	uuuu uuuu	uu0
VREG or ULP Ready Fault	0	-110 0000	0011 110u	0u1
Memory Violation Reset	0	-uuu uuuu	uuuu uuuu	u0u

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, reads as '0'.

#### Notes:

- 1. If a Status bit is not implemented, that bit will be read as '0'.
- 2. Status bits Z, C, DC are reset by POR/BOR.
- 3. When the wake-up is due to an interrupt and Global Interrupt Enable bit (GIE) is set, the return address is pushed on the stack and PC is loaded with the corresponding interrupt vector (depending on source, high or low priority) after execution of PC + 2.

# 14.12 Power Control (PCON0/PCON1) Registers

The Power Control (PCON0/PCON1) registers contains flag bits to differentiate between the following reset events:

- Brown-out Reset (BOR)
- Power-on Reset (POR)
- Reset Instruction Reset (RI)
- MCLR Reset (RMCLR)
- Watchdog Timer Reset (RWDT)
- Watchdog Window Violation (WDTWV)
- Stack Underflow Reset (STKUNF)
- Stack Overflow Reset (STKOVF)
- Configuration Memory Reset (RCM)

- Memory Violation Reset (MEMV)
- Main LDO Voltage Regulator Reset (RVREG)

Hardware will change the corresponding register bit or bits as a result of the Reset event. Bits for other Reset events remain unchanged. See Table 14-3 for more details.

Software should reset the bit to the Inactive state after restart. (Hardware will not reset the bit.)

Software may also set any PCON0 bit to the Active state, so that user code may be tested, but no Reset action will be generated.

# 14.13 Register Definitions: Power Control

## 14.13.1 BORCON

Name: BORCON Offset: 0x049

Brown-out Reset Control Register



#### Bit 7 - SBOREN Software Brown-out Reset Enable

Reset States: POR/BOR = 1

All Other Resets = u

Value	Condition	Description
_	If BOREN ≠ 01	SBOREN is read/write, but has no effect on the BOR
1	If BOREN = 01	BOR Enabled
0	If BOREN = 01	BOR Disabled

## Bit 0 - BORRDY Brown-out Reset Circuit Ready Status

Reset States: POR/BOR = q

All Other Resets = u

Value	Description
1	The Brown-out Reset Circuit is active and armed
0	The Brown-out Reset Circuit is disabled or is warming up

#### 14.13.2 PCON0

Name: PCON0 Offset: 0x4F0

Power Control Register 0

Bit	7	6	5	4	3	2	1	0
	STKOVF	STKUNF	WDTWV	RWDT	RMCLR	RĪ	POR	BOR
Access	R/W/HS	R/W/HS	R/W/HC	R/W/HC	R/W/HC	R/W/HC	R/W/HC	R/W/HC
Reset	0	0	1	1	1	1	0	q

## Bit 7 - STKOVF Stack Overflow Flag

Reset States: POR/BOR = 0

All Other Resets = q

	• 1
Value	Description
1	A Stack Overflow occurred (more CALLs than fit on the stack)
0	A Stack Overflow has not occurred or set to '0' by firmware

#### Bit 6 - STKUNF Stack Underflow Flag

Reset States: POR/BOR = 0

All Other Resets = q

Value	Description
1	A Stack Underflow occurred (more RETURNS than CALLS)
0	A Stack Underflow has not occurred or set to '0' by firmware

## Bit 5 - WDTWV Watchdog Window Violation Flag

Reset States: POR/BOR = 1

All Other Resets = q

	· · · · · · · · · · · · · · · · · · ·
Value	Description
1	A WDT window violation has not occurred or set to '1' by firmware
0	A CLRWDT instruction was issued when the WDT Reset window was closed (set to '0' in hardware
	when a WDT window violation Reset occurs)

#### Bit 4 – RWDT WDT Reset Flag Reset States: POR/BOR = 1

All Other Resets = q

ı	Value	Description					
	1	A WDT overflow/time-out Reset has not occurred or set to '1' by firmware					
	0	A WDT overflow/time-out Reset has occurred (set to '0' in hardware when a WDT Reset occurs)					

#### Bit 3 - RMCLR MCLR Reset Flag

Reset States: POR/BOR = 1

All Other Resets = q

Value	Description						
1	A MCLR Reset has not occurred or set to '1' by firmware						
0	A MCLR Reset has occurred (set to '0' in hardware when a MCLR Reset occurs)						

## Bit 2 - RI RESET Instruction Flag

Reset States: POR/BOR = 1

All Other Resets = q

Value	Description			
1	A RESET instruction has not been executed or set to '1' by firmware			
0	A RESET instruction has been executed (set to '0' in hardware upon executing a RESET instruction)			

#### Bit 1 - POR Power-on Reset Status

# PIC18F26/46/56Q84

Resets

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	No Power-on Reset occurred or set to '1' by firmware
0	A Power-on Reset occurred (set to '0' in hardware when a Power-on Reset occurs)

**Bit 0 – BOR** Brown-out Reset Status Reset States: POR/BOR = q

All Other Resets = u

Value	Description					
1	No Brown-out Reset occurred or set to '1' by firmware					
0	A Brown-out Reset occurred (set to '0' in hardware when a Brown-out Reset occurs)					

#### 14.13.3 PCON1

Name: PCON1 Offset: 0x4F1

Power Control Register 1

Bit	7	6	5	4	3	2	1	0
						RVREG	MEMV	RCM
Access						R/W/HC	R/W/HC	R/W/HC
Reset						1	0	q

## Bit 2 - RVREG Main LDO Voltage Regulator Reset Flag

Reset States: POR/BOR = 1

All Other Resets = q

Value	Description						
1	No LDO or ULP "ready" Reset has occurred or set to '1' by firmware						
0	LDO or ULP "ready" Reset has occurred (VDDCORE reached its minimum spec)						

## Bit 1 - MEMV Memory Violation Reset Flag

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	No memory violation Reset occurred or set to '1' by firmware
0	A memory violation Reset occurred (set to '0' in hardware when a Memory Violation occurs)

# Bit 0 - RCM Configuration Memory Reset Flag

Reset States: POR/BOR = q

All Other Resets = u

Value	Description
1	A Reset occurred due to corruption of the configuration and/or calibration data latches
0	The configuration and calibration latches have not been corrupted

# 14.14 Register Summary - BOR Control and Power Control

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x48										
0x49	BORCON	7:0	SBOREN							BORRDY
0x4A										
	Reserved									
0x04EF										
0x04F0	PCON0	7:0	STKOVF	STKUNF	WDTWV	RWDT	RMCLR	RI	POR	BOR
0x04F1	PCON1	7:0						RVREG	MEMV	RCM


# 15. WWDT - Windowed Watchdog Timer

A Watchdog Timer (WDT) is a system timer that generates a Reset if the firmware does not issue a CLRWDT instruction within the time-out period. A Watchdog Timer is typically used to recover the system from unexpected events. The Windowed Watchdog Timer (WWDT) differs from non-windowed operation in that CLRWDT instructions are only accepted when they are performed within a specific window during the time-out period.

The WWDT has the following features:

- · Selectable clock source
- · Multiple operating modes
  - WWDT is always on
  - WWDT is off when in Sleep
  - WWDT is controlled by software
  - WWDT is always off
- Configurable time-out period from 1 ms to 256s (nominal)
- · Configurable window size from 12.5% to 100% of the time-out period
- · Multiple Reset conditions

Figure 15-1. Windowed Watchdog Timer Block Diagram



# 15.1 Independent Clock Source

The WWDT can derive its time base from either the 31 KHz LFINTOSC or 31.25 kHz MFINTOSC internal oscillators, depending on the value of WDT Operating Mode (WDTE) Configuration bits. If WDTE = 'b1x, then the clock source will be enabled depending on the WDTCCS Configuration bits. If WDTE = 'b01, the SEN bit should be set by software to enable WWDT, and the clock source is enabled by the CS bits. Time intervals in this chapter are based on a minimum nominal interval of 1 ms. See the device Electrical Specifications for LFINTOSC and MFINTOSC tolerances.

# 15.2 WWDT Operating Modes

The Windowed Watchdog Timer module has four operating modes that are controlled by the WDTE Configuration bit. The table below summarizes the different WWDT operating modes.

Table 15-1. WWDT Operating Modes

WDTE	SEN	Device Mode	WWDT Mode
11	X	X	Active
10	X	Awake	Active
10	Λ	Sleep	Disabled
01	1	X	Active
01	0	X	Disabled
00	X	X	Disabled

### 15.2.1 WWDT Is Always On

When the WDTE Configuration bits are set to 'b11, the WWDT is always on. WWDT protection is active during Sleep.

#### 15.2.2 WWDT is Off in Sleep

When the WDTE Configuration bits are set to 'b10, the WWDT is on, except in Sleep. WWDT protection is not active during Sleep

#### 15.2.3 WWDT Controlled by Software

hen the WDTE Configuration bits are set to 'b01, the WWDT is controlled by the SEN bit. WWDT protection is unchanged by Sleep. See Table 15-1 for more details.

#### 15.3 Time-out Period


When the WDTCPS Configuration bits are set to the default value of 'b11111, the PS bits set the time-out period from 1 ms to 256 seconds (nominal). If any value other than the default value is assigned to the WDTCPS Configuration bits, then the timer period will be based on the WDTCPS Configuration bits. After a Reset, the default time-out period is 2s.

# 15.4 Watchdog Window

The Windowed Watchdog Timer has an optional Windowed mode that is controlled by either the WDTCWS Configuration bits or the WINDOW bits. In the Windowed mode (WINDOW < 'b1111), the CLRWDT instruction must occur within the allowed window of the WDT period. Any CLRWDT instruction that occurs outside of this window will trigger a window violation and will cause a WWDT Reset, similar to a WWDT time out. See Figure 15-2 for an example.

When the WDTCWS Configuration bits are 'b111 then the window size is controlled by the WINDOW bits, otherwise the window size is controlled by the WDTCWS bits. The five Most Significant bits of the WDTTMR register are used to determine whether the window is open, as defined by the window size. In the event of a window violation, a Reset will be generated and the WDTWV bit of the PCON0 register will be cleared. This bit is set by a POR and can be set by software.

Figure 15-2. Window Period and Delay



# 15.5 Clearing the Watchdog Timer

The Watchdog Timer is cleared when any of the following conditions occur:

- · Any Reset
- A valid CLRWDT instruction is executed
- · The device enters Sleep
- · The devices exits Sleep by Interrupt
- · The WWDT is disabled
- The Oscillator Start-up Timer (OST) is running
- Any write to the WDTCON0 or WDTCON1 registers

#### 15.5.1 CLRWDT Considerations (Windowed Mode)

When in Windowed mode, the WWDT must be armed before a CLRWDT instruction will clear the timer. This is performed by reading the WDTCON0 register. Executing a CLRWDT instruction without performing such an arming action will trigger a window violation regardless of whether the window is open or not. See Table 15-2 for more information.

# 15.6 Operation During Sleep

When the device enters Sleep, the Watchdog Timer is cleared. If the WWDT is enabled during Sleep, the Watchdog Timer resumes counting. When the device exits Sleep, the Watchdog Timer is cleared again. The Watchdog Timer remains clear until the Oscillator Start-up Timer (OST) completes, if enabled. When a WWDT time-out occurs while the device is in Sleep, no Reset is generated. Instead, the device wakes up and resumes operation. The  $\overline{\text{TO}}$  and  $\overline{\text{PD}}$  bits in the STATUS register are changed to indicate the event. The  $\overline{\text{RWDT}}$  bit in the PCON0 register indicates that a Watchdog Reset has occurred.

Table 15-2. WWDT Clearing Conditions

Conditions	WWDT	
WDTE = 'b00		
WDTE = 'b01 and SEN = 0		
WDTE = 'b10 and enter Sleep	Cleared	
CLRWDT Command	Cleared	
Oscillator Fail Detected		
Exit Sleep + System Clock = SOSC, EXTRC, INTOSC, EXTCLK		
Exit Sleep + System Clock = XT, HS, LP	Cleared until the end of OST	

# PIC18F26/46/56Q84

# **WWDT - Windowed Watchdog Timer**

continued							
Conditions	WWDT						
Change INTOSC divider (IRCF bits)	Unaffected						

# 15.7 Register Definitions: Windowed Watchdog Timer Control

Long bit name prefixes for the Reference Clock peripherals are shown in the following table. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Peripheral	Bit Name Prefix		
WDT	WDT		

#### 15.7.1 WDTCON0

Name: WDTCON0 Offset: 0x078

Watchdog Timer Control Register 0

Bit	7	6	5	4	3	2	1	0
					PS[4:0]			SEN
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			q	q	q	q	q	0

Bits 5:1 - PS[4:0] Watchdog Timer Prescaler Select(2)

DIG 5.1 - F	valchdog filmer Prescaler Selectify
Value	Description
11111 to	Reserved. Results in minimum interval (1 ms)
10011	
10010	1:8388608 (2 <sup>23</sup> ) (Interval 256s nominal)
10001	1:4194304 (2 <sup>22</sup> ) (Interval 128s nominal)
10000	1:2097152 (2 <sup>21</sup> ) (Interval 64s nominal)
01111	1:1048576 (2 <sup>20</sup> ) (Interval 32s nominal)
01110	1:524288 (2 <sup>19</sup> ) (Interval 16s nominal)
01101	1:262144 (2 <sup>18</sup> ) (Interval 8s nominal)
01100	1:131072 (2 <sup>17</sup> ) (Interval 4s nominal)
01011	1:65536 (Interval 2s nominal) (Reset value)
01010	1:32768 (Interval 1s nominal)
01001	1:16384 (Interval 512 ms nominal)
01000	1:8192 (Interval 256 ms nominal)
00111	1:4096 (Interval 128 ms nominal)
00110	1:2048 (Interval 64 ms nominal)
00101	1:1024 (Interval 32 ms nominal)
00100	1:512 (Interval 16 ms nominal)
00011	1:256 (Interval 8 ms nominal)
00010	1:128 (Interval 4 ms nominal)
00001	1:64 (Interval 2 ms nominal)
00000	1:32 (Interval 1 ms nominal)

## Bit 0 - SEN Software Enable/Disable for Watchdog Timer

Value	Condition	Description
X	If WDTE = 1x	This bit is ignored
1	If WDTE = 01	WDT is turned on
0	If WDTE = 01	WDT is turned off
X	If WDTE = 00	This bit is ignored

#### Notes:

- 1. When the WDTCPS Configuration bits = 'b11111, the Reset value (q) of WDTPS is 'b01011. Otherwise, the Reset value of WDTPS is equal to the WDTCPS in Configuration bits.
- 2. When the WDTCPS in Configuration bits ≠ 'b11111, these bits are read-only.

#### 15.7.2 WDTCON1

Name: WDTCON1 Offset: 0x079

Watchdog Timer Control Register 1

Bit	7	6	5	4	3	2	1	0
			CS[2:0]				WINDOW[2:0]	
Access		R/W	R/W	R/W		R/W	R/W	R/W
Reset		q	q	q		q	q	q

Bits 6:4 - CS[2:0] Watchdog Timer Clock Select<sup>(1,3)</sup>

cs	Clock Source
111-100	Reserved
011	EXTOSC
010	SOSC
001	MFINTOSC (31.25 kHz)
000	LFINTOSC (31 kHz)

Bits 2:0 – WINDOW[2:0] Watchdog Timer Window Select<sup>(2,4)</sup>

WINDOW	Window Delay Percent of Time	Window Opening Percent of Time
111	N/A	100
110	12.5	87.5
101	25	75
100	37.5	62.5
011	50	50
010	62.5	37.5
001	75	25
000	87.5	12.5

#### Notes:

- 1. When the WDTCCS in Configuration bits = '0b111, the Reset value of WDTCS is 'b000.
- 2. The Reset value (q) of WINDOW is determined by the value of WDTCWS in the Configuration bits.
- 3. When the WDTCCS in Configuration bits ≠ 'b111, these bits are read-only.
- 4. When the WDTCWS in Configuration bits ≠ 'b111, these bits are read-only.

# PIC18F26/46/56Q84

# **WWDT - Windowed Watchdog Timer**

#### 15.7.3 WDTPSH

Name: WDTPSH Offset: 0x07B

WWDT Prescaler Select Register (Read-Only)

Bit	7	6	5	4	3	2	1	0
	PSCNTH[7:0]							
Access	R	R	R	R	R	R	R	R
Reset	0	0	0	0	0	0	0	0

Bits 7:0 – PSCNTH[7:0] Prescaler Select High Byte<sup>(1)</sup>

#### Note:

1. The 18-bit WDT prescaler value, PSCNT[17:0] includes the WDTPSL, WDTPSH and the lower bits of the WDTTMR registers. PSCNT[17:0] is intended for debug operations and should be read during normal operation.

# PIC18F26/46/56Q84

# **WWDT - Windowed Watchdog Timer**

#### 15.7.4 WDTPSL

Name: WDTPSL Offset: 0x07A

WWDT Prescaler Select Register (Read-Only)

Bit	7	6	5	4	3	2	1	0
	PSCNTL[7:0]							
Access	R	R	R	R	R	R	R	R
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - PSCNTL[7:0] Prescaler Select Low Byte<sup>(1)</sup>

#### Note:

1. The 18-bit WDT prescaler value, PSCNT[17:0] includes the WDTPSL, WDTPSH and the lower bits of the WDTTMR registers. PSCNT[17:0] is intended for debug operations and should be read during normal operation.

#### 15.7.5 WDTTMR

Name: WDTTMR Offset: 0x07C

WDT Timer Register (Read-Only)

Bit	7	6	5	4	3	2	1	0
	TMR[4:0]						PSCN1	Γ[17:16]
Access	R	R	R	R	R	R	R	R
Reset	0	0	0	0	0	0	0	0

## Bits 7:3 - TMR[4:0] Watchdog Window Value

WINDOW	WDT Wine	Open Percent	
	Closed	Open	
111	N/A	00000-11111	100
110	00000-00011	00100-11111	87.5
101	00000-00111	01000-11111	75
100	00000-01011	01100-11111	62.5
011	00000-01111	10000-11111	50
010	00000-10011	10100-11111	37.5
001	00000-10111	11000-11111	25
000	00000-11011	11100-11111	12.5

#### Bit 2 - STATE WDT Armed Status

Value	Description
1	WDT is armed
0	WDT is not armed

# Bits 1:0 - PSCNT[17:16] Prescaler Select Upper Byte<sup>(1)</sup>

#### Note:

1. The 18-bit WDT prescaler value, PSCNT[17:0] includes the WDTPSL, WDTPSH and the lower bits of the WDTTMR registers. PSCNT[17:0] is intended for debug operations and should not be read during normal operation.

# 15.8 Register Summary: WDT Control

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x77										
0x78	WDTCON0	7:0		PS[4:0] SEN					SEN	
0x79	WDTCON1	7:0		CS[2:0] WINDOW[2:0]						
0x7A	WDTPSL	7:0	PSCNTL[7:0]							
0x7B	WDTPSH	7:0	PSCNTH[7:0]							
0x7C	WDTTMR	7:0			TMR[4:0]			STATE	PSCNT	[17:16]

# 16. DMA - Direct Memory Access

The Direct Memory Access (DMA) module is designed to service data transfers between different memory regions directly, without intervention from the CPU. By eliminating the need for CPU-intensive management of handling interrupts intended for data transfers, the CPU now can spend more time on other tasks.

The DMA modules can be independently programmed to transfer data between different memory locations, move different data sizes, and use a wide range of hardware triggers to initiate transfers. The DMA modules can even be programmed to work together, in order to carry out more complex data transfers without CPU overhead.

Key features of the DMA module include:

- · Support access to the following memory regions:
  - GPR and SFR space (R/W)
  - Program Flash memory (R only)
  - Data EEPROM memory (R only)
- Programmable priority between the DMA and CPU operations. Refer to the "System Arbitration" section in the "PIC18 CPU" chapter for details.
- Programmable Source and Destination Address modes:
  - Fixed address
  - Post-increment address
  - Post-decrement address
- · Programmable source and destination sizes
- · Source and Destination Pointer register, dynamically updated and reloadable
- · Source and Destination Count register, dynamically updated and reloadable
- · Programmable auto-stop based on source or destination counter
- · Software triggered transfers
- · Multiple user-selectable sources for hardware triggered transfers
- Multiple user-selectable sources for aborting DMA transfers

# 16.1 DMA Registers

The operation of the DMA module is controlled by the following registers:


- DMA Instance Selection register (DMASELECT)
- Control registers (DMAnCON0, DMAnCON1)
- Data Buffer register (DMAnBUF)
- Source Start Address register (DMAnSSA)
- Source Pointer register (DMAnSPTR)
- Source Message Size register (DMAnSSZ)
- Source Count register (DMAnSCNT)
- Destination Start Address register (DMAnDSA)
- Destination Pointer register (DMAnDPTR)
- Destination Message Size register (DMAnDSZ)
- Destination Count register (DMAnDCNT)
- Start Interrupt Request Source register (DMAnSIRQ)
- Abort Interrupt Request Source register (DMAnAIRQ)

The registers are detailed in Register Definitions: DMA.

# 16.2 DMA Organization

The DMA module is designed to move data by using the existing instruction bus and data bus without the need for any dual-porting of memory or peripheral systems (Figure 16-1). The DMA accesses the required bus when granted by the system arbiter.

Figure 16-1. DMA Functional Block Diagram



Depending on the priority of the DMA with respect to CPU execution (Refer to section "Memory Access Scheme" in the "PIC18 CPU" chapter for more information), the DMA Controller can move data through two methods:

- Stalling the CPU execution until it has completed its transfers (DMA has higher priority over the CPU in this mode of operation).
- Utilizing unused CPU cycles for DMA transfers (CPU has higher priority over the DMA in this mode of
  operation). Unused CPU cycles are referred to as bubbles, which are instruction cycles available for use by the
  DMA to perform read and write operations. In this way, the effective bandwidth for handling data is increased; at
  the same time, DMA operations can proceed without causing a processor stall.

## 16.3 DMA Interface

The DMA module transfers data from the source to the destination one byte at a time, this smallest data movement is called a DMA data transaction. A DMA message refers to one or more DMA data transactions.

Each DMA data transaction consists of two separate actions:

- · Reading the source address memory and storing the value in the DMA Buffer register
- · Writing the contents of the DMA Buffer register to the destination address memory



**Important:** DMA data movement is a two-cycle operation.

The XIP bit is a Status bit to indicate whether or not the data in the DMAnBUF register has been written to the destination address. If the bit is set, then data is waiting to be written to the destination. If clear, it means that either data has been written to the destination or that no source read has occurred.

The DMA has read access to PFM, Data EEPROM, and SFR/GPR space, and write access to SFR/GPR space. Based on these memory access capabilities, the DMA can support the following memory transactions:

**Table 16-1. DMA MEMORY ACCESS** 

Read Source	Write Destination
Program Flash Memory	GPR
Program Flash Memory	SFR
Data EE	GPR
Data EE	SFR
GPR	GPR
GPR	SFR
SFR	GPR
SFR	SFR



**Important:** Even though the DMA module has access to all memory and peripherals that are also available to the CPU, it is recommended that the DMA does not access any register that is part of the system arbitration. The DMA, as a system arbitration client should not be read or written by itself or by another DMA instantiation.

The following sections discuss the various control interfaces required for DMA data transfers.

#### 16.3.1 Special Function Registers with DMA Access only

The DMA can transfer data to any GPR or SFR location. For better user accessibility, some of the more commonly used SFR spaces have their mirror registers placed in a separate data memory location. These mirror registers can be only accessed by the DMA module through the DMA Source and Destination Address registers. The figure below shows the register map for these registers.

These registers are useful to multiple peripherals together like the Timers, PWMs and also other DMA modules using one of the DMA modules.

Figure 16-2. Special Function Register Map (DMA Access Only)

40FFh		40DFh	CX4_ADPREH_M1	40BFh	CX3_ADPREH_M1	409Fh	CX2_ADPREH_M1	407Fh	CX1_ADPREH_M1	405Fh		403Fh		401Fh	PWM4S1P2H_M1
40FEh		40DEh	CX4_ADPREL_M1	40BEh	CX3_ADPREL_M1	409Eh	CX2_ADPREL_M1	407Eh	CX1_ADPREL_M1	405Eh		403Eh		401Eh	PWM4S1P2L_M1
40FDh		40DDh	CX4_ADRESH_M1	40BDh	CX3_ADRESH_M1	409Dh	CX2_ADRESH_M1	407Dh	CX1_ADRESH_M1	405Dh		403Dh		401Dh	PWM4S1P1H_M2
40FCh		40DCh	CX4_ADRESL_M1	40BCh	CX3_ADRESL_M1	409Ch	CX2_ADRESL_M1	407Ch	CX1_ADRESL_M1	405Ch		403Ch		401Ch	PWM4S1P1L_M2
40FBh		40DBh	CX4_ADPCH_M1	40BBh	CX3_ADPCH_M1	409Bh	CX2_ADPCH_M1	407Bh	CX1_ADPCH_M1	405Bh		403Bh		401Bh	PWM3S1P2H_M1
40FAh		40DAh	CX4_ADCLK_M1	40BAh	CX3_ADCLK_M1	409Ah	CX2_ADCLK_M1	407Ah	CX1_ADCLK_M1	405Ah		403Ah		401Ah	PWM3S1P2L_M1
40F9h		40D9h	CX4_ADACT_M1	40B9h	CX3_ADACT_M1	4099h	CX2_ADACT_M1	4079h	CX1_ADACT_M1	4059h		4039h		4019h	PWM3S1P1H_M2
40F8h		40D8h	CX4_ADREF_M1	40B8h	CX3_ADREF_M1	4098h	CX2_ADREF_M1	4078h	CX1_ADREF_M1	4058h		4038h		4018h	PWM3S1P1L_M2
40F7h		40D7h	CX4_ADCON3_M1	40B7h	CX3_ADCON3_M1	4097h	CX2_ADCON3_M1	4077h	CX1_ADCON3_M1	4057h		4037h	PWM4PRH_M1	4017h	PWM2S1P2H_M1
40F6h	ADRESH_M1	40D6h	CX4_ADCON2_M1	40B6h	CX3_ADCON2_M1	4096h	CX2_ADCON2_M1	4076h	CX1_ADCON2_M1	4056h		4036h	PWM4PRL_M1	4016h	PWM2S1P2L_M1
40F5h	ADRESL_M1	40D5h	CX4_ADCON1_M1	40B5h	CX3_ADCON1_M1	4095h	CX2_ADCON1_M1	4075h	CX1_ADCON1_M1	4055h		4035h	PWM4S1P2H_M2	4015h	PWM2S1P1H_M2
40F4h	ADPCH_M1	40D4h	CX4_ADCON0_M1	40B4h	CX3_ADCON0_M1	4094h	CX2_ADCON0_M1	4074h	CX1_ADCON0_M1	4054h		4034h	PWM4S1P2L_M2	4014h	PWM2S1P1L_M2
40F3h	ADCAP_M1	40D3h	CX4_ADCAP_M1	40B3h	CX3_ADCAP_M1	4093h	CX2_ADCAP_M1	4073h	CX1_ADCAP_M1	4053h		4033h	PWM4S1P1H_M3	4013h	PWM1S1P2H_M1
40F2h	ADACQH_M1	40D2h	CX4_ADACQH_M1	40B2h	CX3_ADACQH_M1	4092h	CX2_ADACQH_M1	4072h	CX1_ADACQH_M1	4052h		4032h	PWM4S1P1L_M3	4012h	PWM1S1P2L_M1
40F1h	ADACQL_M1	40D1h	CX4_ADACQL_M1	40B1h	CX3_ADACQL_M1	4091h	CX2_ADACQL_M1	4071h	CX1_ADACQL_M1	4051h		4031h	PWM3PRH_M1	4011h	PWM1S1P1H_M2
40F0h	ADPREVH_M1	40D0h	CX4_ADPREVH_M1	40B0h	CX3_ADPREVH_M1	4090h	CX2_ADPREVH_M1	4070h	CX1_ADPREVH_M1	4050h		4030h	PWM3PRL_M1	4010h	PWM1S1P1L_M2
40EFh	ADPREVL_M1	40CFh	CX4_ADPREVL_M1	40AFh	CX3_ADPREVL_M1	408Fh	CX2_ADPREVL_M1	406Fh	CX1_ADPREVL_M1	404Fh		402Fh	PWM3S1P2H_M2	400Fh	-
40EEh	ADRPT_M1	40CEh	CX4_ADRPT_M1	40AEh	CX3_ADRPT_M1	408Eh	CX2_ADRPT_M1	406Eh	CX1_ADRPT_M1	404Eh		402Eh	PWM3S1P2L_M2	400Eh	-
40EDh	ADCNT_M1	40CDh	CX4_ADCNT_M1	40ADh	CX3_ADCNT_M1	408Dh	CX2_ADCNT_M1	406Dh	CX1_ADCNT_M1	404Dh		402Dh	PWM3S1P1H_M3	400Dh	PWM4S1P1H_M1
40ECh	ADACCU_M1	40CCh	CX4_ADACCU_M1	40ACh	CX3_ADACCU_M1	408Ch	CX2_ADACCU_M1	406Ch	CX1_ADACCU_M1	404Ch		402Ch	PWM3S1P1L_M3	400Ch	PWM4S1P1L_M1
40CBh	ADACCH_M1	40CBh	CX4_ADACCH_M1	40ABh	CX3_ADACCH_M1	408Bh	CX2_ADACCH_M1	406Bh	CX1_ADACCH_M1	404Bh		402Bh	PWM2PRH_M1	400Bh	PWM3S1P1H_M1
40EAh	ADACCL_M1	40CAh	CX4_ADACCL_M1	40AAh	CX3_ADACCL_M1	408Ah	CX2_ADACCL_M1	406Ah	CX1_ADACCL_M1	404Ah		402Ah	PWM2PRL_M1	400Ah	PWM3S1P1L_M1
40E9h	ADFLTRH_M1	40C9h	CX4_ADFLTRH_M1	40A9h	CX3_ADFLTRH_M1	4089h	CX2_ADFLTRH_M1	4069h	CX1_ADFLTRH_M1	4049h		4029h	PWM2S1P2H_M2	4009h	PWM2S1P1H_M1
40E8h	ADFLTRL_M1	40C8h	CX4_ADFLTRL_M1	40A8h	CX3_ADFLTRL_M1	4088h	CX2_ADFLTRL_M1	4068h	CX1_ADFLTRL_M1	4048h	T6PR_M1	4028h	PWM2S1P2L_M2	4008h	PWM2S1P1L_M1
40E7h	ADSTPTH_M1	40C7h	CX4_ADSTPTH_M1	40A7h	CX3_ADSTPTH_M1	4087h	CX2_ADSTPTH_M1	4067h	CX1_ADSTPTH_M1	4047h	CCPR3H_M2	4027h	PWM2S1P1H_M3	4007h	PWM1S1P1H_M1
40E6h	ADSTPTL_M1	40C6h	CX4_ADSTPTL_M1	40A6h	CX3_ADSTPTL_M1	4086h	CX2_ADSTPTL_M1	4066h	CX1_ADSTPTL_M1	4046h	CCPR3L_M2	4026h	PWM2S1P1L_M3	4006h	PWM1S1P1L_M1
40E5h	ADERRH_M1	40C5h	CX4_ADERRH_M1	40A5h	CX3_ADERRH_M1	4085h	CX2_ADERRH_M1	4065h	CX1_ADERRH_M1	4045h	T4PR_M1	4025h	PWM1PRH_M1	4005h	CCPR3H_M1
40E4h	ADERRL_M1	40C4h	CX4_ADERRL_M1	40A4h	CX3_ADERRL_M1	4084h	CX2_ADERRL_M1	4064h	CX1_ADERRL_M1	4044h	CCPR2H_M2	4024h	PWM1PRL_M1	4004h	CCPR3L_M1
40E3h	ADUTHH_M1	40C3h	CX4_ADUTHH_M1	40A3h	CX3_ADUTHH_M1	4083h	CX2_ADUTHH_M1	4063h	CX1_ADUTHH_M1	4043h	CCPR2L_M2	4023h	PWM1S1P2H_M2	4003h	CCPR2H_M1
40E2h	ADUTHL_M1	40C2h	CX4_ADUTHL_M1	40A2h	CX3_ADUTHL_M1	4082h	CX2_ADUTHL_M1	4062h	CX1_ADUTHL_M1	4042h	T2PR_M1	4022h	PWM1S1P2L_M2	4002h	CCPR2L_M1
40E1h	ADLTHH_M1	40C1h	CX4_ADLTHH_M1	40A1h	CX3_ADLTHH_M1	4081h	CX2_ADLTHH_M1	4061h	CX1_ADLTHH_M1	4041h	CCPR1H_M2	4021h	PWM1S1P1H_M3	4001h	CCPR1H_M1
40E0h	ADLTHL_M1	40C0h	CX4_ADLTHL_M1	40A0h	CX3_ADLTHL_M1	4080h	CX2_ADLTHL_M1	4060h	CX1_ADLTHL_M1	4040h	CCPR1L_M2	4020h	PWM1S1P1L_M3	4000h	CCPR1L_M1

_												_			
41FFh		41DFh	-	41BFh	-	419Fh	DMAnAIRQ_DMA7	417Fh	DMAnSPTRH_DMA6	415Fh	DMAnDPTRL_DMA5	413Fh	DMAnSSAH_DMA3	411Fh	DMAnDSAH_DMA2
41FEh		41DEh	-	41BEh	-	419Eh	DMAnCON1_DMA7	417Eh	DMAnSPTRL_DMA6	415Eh	DMAnDCNTH_DMA5	413Eh	DMAnSSAL_DMA3	411Eh	DMAnDSAL_DMA2
41FDh		41DDh	-	41BDh		419Dh	DMAnCON0_DMA7	417Dh	DMAnSCNTH_DMA6	415Dh	DMAnDCNTL_DMA5	413Dh	DMAnSSZH_DMA3	411Dh	DMAnDSZH_DMA2
41FCh		41DCh	-	41BCh	-	419Ch	DMAnSSAU_DMA7	417Ch	DMAnSCNTL_DMA6	415Ch	DMAnBUF_DMA5	413Ch	DMAnSSZL_DMA3	411Ch	DMAnDSZL_DMA2
41FBh	TMR5H_M1	41DBh	-	41BBh	-	419Bh	DMAnSSAH_DMA7	417Bh	DMAnDSAH_DMA6	415Bh	DMAnSIRQ_DMA4	413Bh	DMAnSPTRU_DMA3	411Bh	DMAnDPTRH_DMA2
41FAh	TMR5L_M1	41DAh	-	41BAh	-	419Ah	DMAnSSAL_DMA7	417Ah	DMAnDSAL_DMA6	415Ah	DMAnAIRQ_DMA4	413Ah	DMAnSPTRH_DMA3	411Ah	DMAnDPTRL_DMA2
41F9h	TMR3H_M1	41D9h	-	41B9h		4199h	DMAnSSZH_DMA7	4179h	DMAnDSZH_DMA6	4159h	DMAnCON1_DMA4	4139h	DMAnSPTRL_DMA3	4119h	DMAnDCNTH_DMA2
41F8h	TMR3L_M1	41D8h	-	41B8h	-	4198h	DMAnSSZL_DMA7	4178h	DMAnDSZL_DMA6	4158h	DMAnCON0_DMA4	4138h	DMAnSCNTH_DMA3	4118h	DMAnDCNTL_DMA2
41F7h	TMR1H_M1	41D7h	-	41B7h	DMAnSIRQ_DMA8	4197h	DMAnSPTRU_DMA7	4177h	DMAnDPTRH_DMA6	4157h	DMAnSSAU_DMA4	4137h	DMAnSCNTL_DMA3	4117h	DMAnBUF_DMA2
41F6h	TMR1L_M1	41D6h	-	41B6h	DMAnAIRQ_DMA8	4196h	DMAnSPTRH_DMA7	4176h	DMAnDPTRL_DMA6	4156h	DMAnSSAH_DMA4	4136h	DMAnDSAH_DMA3	4116h	DMAnSIRQ_DMA1
41F5h		41D5h	-	41B5h	DMAnCON1_DMA8	4195h	DMAnSPTRL_DMA7	4175h	DMAnDCNTH_DMA6	4155h	DMAnSSAL_DMA4	4135h	DMAnDSAL_DMA3	4115h	DMAnAIRQ_DMA1
41F4h		41D4h	-	41B4h	DMAnCON0_DMA8	4194h	DMAnSCNTH_DMA7	4174h	DMAnDCNTL_DMA6	4154h	DMAnSSZH_DMA4	4134h	DMAnDSZH_DMA3	4114h	DMAnCON1_DMA1
41F3h		41D3h	-	41B3h	DMAnSSAU_DMA8	4193h	DMAnSCNTL_DMA7	4173h	DMAnBUF_DMA6	4153h	DMAnSSZL_DMA4	4133h	DMAnDSZL_DMA3	4113h	DMAnCON0_DMA1
41F2h		41D2h	-	41B2h	DMAnSSAH_DMA8	4192h	DMAnDSAH_DMA7	4172h	DMAnSIRQ_DMA5	4152h	DMAnSPTRU_DMA4	4132h	DMAnDPTRH_DMA3	4112h	DMAnSSAU_DMA1
41F1h		41D1h	-	41B1h	DMAnSSAL_DMA8	4191h	DMAnDSAL_DMA7	4171h	DMAnAIRQ_DMA5	4151h	DMAnSPTRH_DMA4	4131h	DMAnDPTRL_DMA3	4111h	DMAnSSAH_DMA1
41F0h		41D0h	-	41B0h	DMAnSSZH_DMA8	4190h	DMAnDSZH_DMA7	4170h	DMAnCON1_DMA5	4150h	DMAnSPTRL_DMA4	4130h	DMAnDCNTH_DMA3	4110h	DMAnSSAL_DMA1
41EFh		41CFh	-	41AFh	DMAnSSZL_DMA8	418Fh	DMAnDSZL_DMA7	416Fh	DMAnCON0_DMA5	414Fh	DMAnSCNTH_DMA4	412Fh	DMAnDCNTL_DMA3	410Fh	DMAnSSZH_DMA1
41EEh		41CEh	-	41AEh	DMAnSPTRU_DMA8	418Eh	DMAnDPTRH_DMA7	416Eh	DMAnSSAU_DMA5	414Eh	DMAnSCNTL_DMA4	412Eh	DMAnBUF_DMA3	410Eh	DMAnSSZL_DMA1
41EDh		41CDh	-	41ADh	DMAnSPTRH_DMA8	418Dh	DMAnDPTRL_DMA7	416Dh	DMAnSSAH_DMA5	414Dh	DMAnDSAH_DMA4	412Dh	DMAnSIRQ_DMA2	410Dh	DMAnSPTRU_DMA1
41ECh		41CCh	-	41ACh	DMAnSPTRL_DMA8	418Ch	DMAnDCNTH_DMA7	416Ch	DMAnSSAL_DMA5	414Ch	DMAnDSAL_DMA4	412Ch	DMAnAIRQ_DMA2	410Ch	DMAnSPTRH_DMA1
41CBh		41CBh	-	41ABh	DMAnSCNTH_DMA8	418Bh	DMAnDCNTL_DMA7	416Bh	DMAnSSZH_DMA5	414Bh	DMAnDSZH_DMA4	412Bh	DMAnCON1_DMA2	410Bh	DMAnSPTRL_DMA1
41EAh		41CAh	-	41AAh	DMAnSCNTL_DMA8	418Ah	DMAnBUF_DMA7	416Ah	DMAnSSZL_DMA5	414Ah	DMAnDSZL_DMA4	412Ah	DMAnCON0_DMA2	410Ah	DMAnSCNTH_DMA1
41E9h		41C9h	-	41A9h	DMAnDSAH_DMA8	4189h	DMAnSIRQ_DMA6	4169h	DMAnSPTRU_DMA5	4149h	DMAnDPTRH_DMA4	4129h	DMAnSSAU_DMA2	4109h	DMAnSCNTL_DMA1
41E8h		41C8h	-	41A8h	DMAnDSAL_DMA8	4188h	DMAnAIRQ_DMA6	4168h	DMAnSPTRH_DMA5	4148h	DMAnDPTRL_DMA4	4128h	DMAnSSAH_DMA2	4108h	DMAnDSAH_DMA1
41E7h	•	41C7h	-	41A7h	DMAnDSZH_DMA8	4187h	DMAnCON1_DMA6	4167h	DMAnSPTRL_DMA5	4147h	DMAnDCNTH_DMA4	4127h	DMAnSSAL_DMA2	4107h	DMAnDSAL_DMA1
41E6h		41C6h	-	41A6h	DMAnDSZL_DMA8	4186h	DMAnCON0_DMA6	4166h	DMAnSCNTH_DMA5	4146h	DMAnDCNTL_DMA4	4126h	DMAnSSZH_DMA2	4106h	DMAnDSZH_DMA1
41E5h		41C5h	-	41A5h	DMAnDPTRH_DMA8	4185h	DMAnSSAU_DMA6	4165h	DMAnSCNTL_DMA5	4145h	DMAnBUF_DMA4	4125h	DMAnSSZL_DMA2	4105h	DMAnDSZL_DMA1
41E4h		41C4h	-	41A4h	DMAnDPTRL_DMA8	4184h	DMAnSSAH_DMA6	4164h	DMAnDSAH_DMA5	4144h	DMAnSIRQ_DMA3	4124h	DMAnSPTRU_DMA2	4104h	DMAnDPTRH_DMA1
41E3h	IOCEF_M1	41C3h	-	41A3h	DMAnDCNTH_DMA8	4183h	DMAnSSAL_DMA6	4163h	DMAnDSAL_DMA5	4143h	DMAnAIRQ_DMA3	4123h	DMAnSPTRH_DMA2	4103h	DMAnDPTRL_DMA1
41E2h	IOCCF_M1	41C2h	-	41A2h	DMAnDCNTL_DMA8	4182h	DMAnSSZH_DMA6	4162h	DMAnDSZH_DMA5	4142h	DMAnCON1_DMA3	4122h	DMAnSPTRL_DMA2	4102h	DMAnDCNTH_DMA1
41E1h	IOCBF_M1	41C1h	-	41A1h	DMAnBUF_DMA8	4181h	DMAnSSZL_DMA6	4161h	DMAnDSZL_DMA5	4141h	DMAnCON0_DMA3	4121h	DMAnSCNTH_DMA2	4101h	DMAnDCNTL_DMA1
41E0h	IOCAF_M1	41C0h	-	41A0h	DMAnSIRQ_DMA7	4180h	DMAnSPTRU_DMA6	4160h	DMAnDPTRH_DMA5	4140h	DMAnSSAU_DMA3	4120h	DMAnSCNTL_DMA2	4100h	DMAnBUF_DMA1

#### 16.3.2 DMA Addressing

The start addresses for the source read and destination write operations are set using the DMAnSSA and DMAnDSA registers, respectively.


When the DMA message transfers are in progress, the DMAnSPTR and DMAnDPTR registers contain the current Address Pointers for each source read and destination write operation. These registers are modified after each transaction based on the Address mode selection bits.


The SMODE and DMODE bits determine the address modes of operation by controlling how the DMAnSPTR and DMAnDPTR registers are updated after every DMA data transaction (Figure 16-3).

Each address can be separately configured to:

- Remain unchanged
- Increment by 1
- · Decrement by 1

Figure 16-3. DMA Pointers Block Diagram





The DMA can initiate data transfers from the PFM, Data EEPROM or SFR/GPR space. The SMR bits are used to select the type of memory being pointed to by the Source Address Pointer. The SMR bits are required because the PFM and SFR/GPR spaces have overlapping addresses that do not allow the specified address to uniquely define the memory location to be accessed.



#### Important:

- For proper memory read access to occur, the combination of address and space selection must be valid.
- The destination does not have space selection bits because it can only write to the SFR/GPR space.

#### 16.3.3 DMA Message Size/Counters

A transaction is the transfer of one byte. A message consists of one or more transactions. A complete DMA process consists of one or more messages. The size registers determine how many transactions are in a message. The DMAnSSZ registers determine the source size and DMAnDSZ registers determine the destination size.

# PIC18F26/46/56Q84

# **DMA - Direct Memory Access**

When a DMA transfer is initiated, the size registers are copied to corresponding counter registers that control the duration of the message. The DMAnSCNT registers count the source transactions and the DMAnDCNT registers count the destination transactions. Both are simultaneously decremented by one after each transaction.

A message is started by setting the DGO bit and terminates when the smaller of the two counters reaches zero.

When either counter reaches zero, the DGO bit is cleared and the counter and pointer registers are immediately reloaded with the corresponding size and address data. If the other counter did not reach zero, then the next message will continue with the count and address corresponding to that register. Refer to Figure 16-4.

When the Source and Destination Size registers are not equal, then the ratio of the largest to the smallest size determines how many messages are in the DMA process. For example, when the destination size is six and the source size is two, then each message will consist of two transactions and the complete DMA process will consist of three messages. When the larger size is not an even integer of the smaller size, then the last message in the process will terminate early when the larger count reaches zero. In that case, the larger counter will reset and the smaller counter will have a remainder skewing any subsequent messages by that amount.

Table 16-2 has a few examples of configuring DMA Message sizes.




**Important:** Reading the DMAnSCNT or DMAnDCNT registers will never return zero. When either register is decremented from '1', it is immediately reloaded from the corresponding size register.

Table 16-2. EXAMPLE MESSAGE SIZE TABLE

Operation	Example	SCNT	DCNT	Comments
Read from single SFR location to RAM	UART Receive Buffer	1	N	N equals the number of bytes desired in the destination buffer. N≥1.
Write to single SFR location from RAM	UART Transmit Buffer	N	1	N equals the number of bytes desired in the source buffer. N≥1.
Read from multiple SFR location	ADC Result registers	2	2*N	N equals the number of ADC results to be stored in memory. N≥1
Write to Multiple SFR registers	PWM Duty Cycle registers	2*N	2	N equals the number of PWM duty cycle values to be loaded from a memory table. N≥1

Figure 16-4. DMA COUNTERS BLOCK DIAGRAM



# 16.3.4 DMA Message Transfers

Once the Enable bit is set to start DMA message transfers, the Source/Destination Pointer and Counter registers are initialized to the conditions shown in the table below.

**Table 16-3. DMA INITIAL CONDITIONS** 

Register	Value Loaded
DMAnSPTR	DMAnSSA
DMAnSCNT	DMAnSSZ
DMAnDPTR	DMAnDSA
DMAnDCNT	DMAnDSZ

During the DMA operation after each transaction, Table 16-4 and Table 16-5 indicate how the Source/ Destination Pointer and Counter registers are modified.

The following sections discuss how to initiate and terminate DMA transfers.

Table 16-4. DMA SOURCE POINTER/COUNTER DURING OPERATION

Register	Modified Source Counter/Pointer Value
	DMAnSCNT = DMAnSCNT -1
DMAnSCNT!= 1	SMODE = 00: DMAnSPTR = DMAnSPTR
DIVIAIISCINT !- I	SMODE = 01: DMAnSPTR = DMAnSPTR + 1
	SMODE = 10: DMAnSPTR = DMAnSPTR - 1
DMAnSCNT == 1	DMAnSCNT = DMAnSSZ
DIMAISCINT I	DMAnSPTR = DMAnSSA

#### Table 16-5. DMA DESTINATION POINTER/COUNTER DURING OPERATION

Register	Modified Destination Counter/Pointer Value
	DMAnDCNT = DMAnDCNT -1
DMA-DCNT I- 4	DMODE = 00: DMAnDPTR = DMAnDPTR
DMAnDCNT != 1	DMODE = 01: DMAnDPTR = DMAnDPTR + 1
	DMODE = 10: DMAnDPTR = DMAnDPTR - 1
DMAnDCNT == 1	DMAnDCNT = DMAnDSZ
DIVIANDENT 1	DMAnDPTR = DMAnDSA

#### 16.3.4.1 Starting DMA Message Transfers

The DMA can initiate data transactions by either of the following two conditions:

- · User software control
- · Hardware trigger, SIRQ

#### 16.3.4.1.1 User Software Control

Software starts or stops DMA transaction by setting/clearing the DGO bit. The DGO bit is also used to indicate whether a DMA hardware trigger has been received and a message is in progress.



#### Important:

- 1. Software start can only occur when the EN bit is set.
- If the CPU writes to the DGO bit while it is already set, there is no effect on the system, the DMA will continue to operate normally.

#### 16.3.4.1.2 Hardware Trigger, SIRQ

A hardware trigger is an interrupt request from another module sent to the DMA with the purpose of starting a DMA message. The DMA start trigger source is user-selectable using the DMAnSIRQ register.

The SIRQEN bit is used to enable sampling of external interrupt triggers by which a DMA transfer can be started. When set, the DMA will sample the selected interrupt source and when cleared, the DMA will ignore the interrupt source. Clearing the SIRQEN bit does not stop a DMA transaction currently in progress, it only stops more hardware request signals from being received.

#### 16.3.4.2 Stopping DMA Message Transfers

The DMA controller can stop data transactions by any of the following conditions:

- Clearing the DGO bit
- · Hardware abort trigger, AIRQ
- · Source count reload
- · Destination count reload
- · Clearing the EN bit

#### 16.3.4.2.1 User Software Control

If the user clears the DGO bit, the message will be stopped and the DMA will remain in the current configuration.

For example, if the user clears the DGO bit after source data has been read, but before it is written to the destination, then the data in the DMAnBUF register will not reach its destination.

This is also referred to as a soft-stop as the operation can resume, if desired, by setting the DGO bit again.

#### 16.3.4.2.2 Hardware Trigger, AIRQ

The AIRQEN bit is used to enable sampling of external interrupt triggers by which a DMA transaction can be aborted.

Once an abort interrupt request has been received, the DMA will perform a soft-stop by clearing the DGO bit, as well as clearing the SIRQEN bit so overruns do not occur. The AIRQEN bit is also cleared to prevent additional abort signals from triggering false aborts.

If desired, the DGO bit can be set again and the DMA will resume operation from where it left off after the soft stop had occurred, as none of the DMA state information is changed in the event of an abort.

#### 16.3.4.2.3 Source Count Reload

A DMA message is considered to be complete when the Source Count register is decremented from 1 and then reloaded (i.e., once the last byte from either the source read or destination write has occurred). When the SSTP bit is set and the Source Count register is reloaded, then further message transfer is stopped.

#### 16.3.4.2.4 Destination Count Reload

A DMA message is considered to be complete when the Destination Count register is decremented from 1 and then reloaded (i.e., once the last byte from either the source read or destination write has occurred). When the DSTP bit is set and the Destination Count register is reloaded then further message transfer is stopped.



**Important:** Reading the DMAnSCNT or DMAnDCNT registers will never return zero. When either register is decremented from '1', it is immediately reloaded from the corresponding size register.

#### 16.3.4.2.5 Clearing the EN bit

If the user clears the EN bit, the message will be stopped and the DMA will return to its default configuration. This is also referred to as a hard stop, as the DMA cannot resume operation from where it was stopped.



**Important:** After the DMA message transfer is stopped, it requires an extra instruction cycle before the Stop condition takes effect. Thus, after the Stop condition has occurred, a source read or a destination write can occur depending on the source or destination bus availability.

# 16.4 Disable DMA Message Transfer Upon Completion

Once the DMA message is complete, it may be desirable to disable the trigger source to prevent overrun or under run of data. This can be done by any of the following methods:

- · Clearing the SIRQEN bit
- · Setting the SSTP bit
- Setting the DSTP bit

#### 16.4.1 Clearing the SIRQEN bit

Clearing the SIRQEN bit stops the sampling of external start interrupt triggers, hence preventing further DMA message transfers.

An example would be a communications peripheral with a level-triggered interrupt. The peripheral will continue to request data (because its buffer is empty) even though there is no more data to be moved. Disabling the SIRQEN bit prevents the DMA from processing these requests.

#### 16.4.2 Source/Destination Stop

The SSTP and DSTP bits determine whether or not to disable the hardware triggers (SIRQEN = 0), once a DMA message has completed.

When the SSTP bit is set and the DMAnSCNT = 0, then the SIRQEN bit will be cleared. Similarly, when the DSTP bit is set and the DMAnDCNT = 0, the SIRQEN bit will be cleared.



**Important:** The SSTP and DSTP bits are independent functions and do not depend on each other. It is possible for a message to be stopped by either counter at message end or both counters at message end.

# 16.5 Types of Hardware Triggers

The DMA has two different trigger inputs, the source trigger and the abort trigger. Each of these trigger sources is user configurable using the DMAnSIRQ and DMAnAIRQ registers.

Based on the source selected for each trigger, there are two types of requests that can be sent to the DMA:

- · Edge triggers
- Level triggers

#### 16.5.1 Edge Trigger Requests

An edge request occurs only once when a given module interrupt requirements are true. Examples of edge triggers are the ADC conversion complete and the interrupt-on-change interrupts.

#### 16.5.2 Level Trigger Requests

A level request is asserted as long as the condition that causes the interrupt is true. Examples of level triggers are the UART receive and transmit interrupts.

## 16.6 Types of Data Transfers

Based on the memory access capabilities of the DMA (see Table 16-1), the following sections discuss the different types of data movement between the source and destination memory regions.

- N:1
  - This type of transfer is common when sending predefined data packets (such as strings) through a single interface point (such as communications modules transmit registers).
- N·N
  - This type of transfer is useful for moving information out of the program Flash or Data EEPROM to SRAM for manipulation by the CPU or other peripherals.
- 1:1
  - This type of transfer is common when bridging two different modules data streams together (communications bridge).
- 1:N
  - This type of transfer is useful for moving information from a single data source into a memory buffer (communications receive registers).

## 16.7 DMA Interrupts

Each DMA has its own set of four interrupt flags, used to indicate a range of conditions during data transfers. The interrupt flag bits can be accessed using the corresponding PIR registers (refer to the "VIC - Vectored Interrupt Controller" chapter).

#### 16.7.1 DMA Source Count Interrupt

The Source Count Interrupt flag (DMAxSCNTIF) is set every time the DMAnSCNT register reaches zero and is reloaded to its starting value.

#### **16.7.2 DMA Destination Count Interrupt**

The Destination Count Interrupt flag (DMAxDCNTIF) is set every time the DMAnDCNT register reaches zero and is reloaded to its starting value.

The DMA source and destination count interrupts signal the CPU when the DMA messages are completed.

#### 16.7.3 Abort Interrupt

The Abort Interrupt Flag (DMAxAIF) is used to signal that the DMA has halted activity due to an abort signal from one of the abort sources. This is used to indicate that the transaction has been halted by a hardware event.

#### 16.7.4 Overrun Interrupt

When the DMA receives a trigger to start a new message before the current message is completed, then the Overrun Interrupt Flag (DMAxORIF) bit is set.

This condition indicates that the DMA is being requested before its current transaction is finished. This implies that the active DMA may not be able to keep up with the demands from the peripheral module being serviced, which may result in data loss.

The DMAxORIF flag being set does not cause the current DMA transfer to terminate.

The overrun interrupt is only available for trigger sources that are edge-based and not available for sources that are level-based. Therefore, a level-based interrupt source does not trigger a DMA overrun error due to the potential latency issues in the system.

An example of an interrupt that could use the overrun interrupt would be a timer overflow (or period match) interrupt. This event only happens every time the timer rolls over and is not dependent on any other system conditions.

An example of an interrupt that does not allow the overrun interrupt would be the UART TX buffer. The UART will continue to assert the interrupt until the DMA is able to process the message. Due to latency issues, the DMA may not be able to service an empty buffer immediately, but the UART continues to assert its transmit interrupt until it is serviced. If overrun was allowed in this case, the overrun would occur almost immediately as the module samples the interrupt sources every instruction cycle.

#### 16.8 DMA Setup and Operation

The following steps illustrate how to configure the DMA for data transfer:


- 1. Select the desired DMA using the DMASELECT register.
- 2. Program the appropriate source and destination addresses for the transaction into the DMAnSSA and DMAnDSA registers.
- 3. Select the source memory region that is being addressed by the DMAnSSA register, using the SMR bits.
- 4. Program the SMODE and DMODE bits to select the addressing mode.
- 5. Program the source size (DMAnSSZ) and destination size (DMAnDSZ) registers with the number of bytes to be transferred. It is recommended for proper operation that the size registers be a multiple of each other.
- 6. If the user desires to disable data transfers once the message has completed, then the SSTP and DSTP bits need to be set. (see Source/Destination Stop).
- 7. If using hardware triggers for data transfer, setup the hardware trigger interrupt sources for the starting and aborting DMA transfers (DMAnSIRQ and DMAnAIRQ), and set the corresponding interrupt request enable bits (SIRQEN and AIRQEN).
- 8. Select the priority level for the DMA (see "System Arbitration" section in the "PIC18 CPU" chapter) and lock the priorities (see "Priority Lock" section in the "PIC18 CPU" chapter).
- Enable the DMA by setting the EN bit.
- 10. If using software control for data transfer, set the DGO bit, else this bit will be set by the hardware trigger.

Once the DMA is set up, Figure 16-5 describes the sequence of operation when the DMA uses hardware triggers and utilizes the unused CPU cycles (bubble) for DMA transfers.

The following sections describe with visual reference the sequence of events for different configurations of the DMA module.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 290


Figure 16-5. DMA Operation with Hardware Trigger



#### 16.8.1 Source Stop

When the Source Stop bit is set (SSTP = 1) and the DMAnSCNT register reloads, the DMA clears the SIRQEN bit to stop receiving new start interrupt request signals and sets the DMAnSCNTIF flag. Refer to the figure below for more details.

Figure 16-6. GPR-GPR Transactions with Hardware Triggers, SSTP = 1




- 1. SR Source Read
- 2. DW Destination Write

#### 16.8.2 Destination Stop

When the Destination Stop bit is set (DSTP = 1) and the DMAnDCNT register reloads, the DMA clears the SIRQEN bit to stop receiving new start interrupt request signals and sets the DMAxDCNTIF flag.

Figure 16-7. GPR-GPR Transactions with Hardware Triggers, DSTP = 1




- 1. SR Source Read
- 2. DW Destination Write

#### 16.8.3 Continuous Transfer

When the Source or the Destination Stop bit is cleared (SSTP, DSTP = 0), the transactions continue unless stopped by the user. The DMAxSCNTIF and DMAxDCNTIF flags are set whenever the respective counter registers are reloaded.

Figure 16-8. GPR-GPR Transactions with Hardware Triggers, SSTP, DSTP = 0




- 1. SR Source Read
- 2. DW Destination Write

#### 16.8.4 Transfer from SFR to GPR

The following visual reference describes the sequence of events when copying ADC results to a GPR location. The ADC Interrupt flag can be chosen as the source hardware trigger, the source address can be set to point to the ADC Result registers (e.g., at 0x3EEF), the destination address can be set to point to any GPR location of our choice (e.g., at 0x100).

Figure 16-9. SFR Space to GPR Space Transfer




- 1. SR Source Read
- 2. DW Destination Write

#### 16.8.5 **Overrun Condition**

The Overrun Interrupt flag is set if the DMA receives a trigger to start a new message before the current message is completed.

#### Figure 16-10. Overrun Interrupt




- 1. SR - Source Read
- DW Destination Write

#### 16.8.6 Abort Trigger, Message Complete

The AIRQEN needs to be set in order for the DMA to sample abort interrupt sources. When an abort interrupt is received, the SIRQEN bit is cleared and the AIRQEN bit is cleared to avoid receiving further abort triggers.

Figure 16-11. Abort at the End of Message




- 1. SR Source Read
- 2. DW Destination Write

#### 16.8.7 Abort Trigger, Message in Progress

When an abort interrupt request is received in a DMA transaction, the DMA will perform a soft-stop by clearing the DGO bit (i.e., if the DMA was reading the source register, it will complete the read operation and then clear the DGO bit).

The SIRQEN bit is cleared to prevent any overrun and the AIRQEN bit is cleared to prevent any false aborts. When the DGO bit is set again, the DMA will resume operation from where it left off after the soft-stop.

Figure 16-12. Abort During Message Transfer



- SR Source Read 1.
- 2. DW - Destination Write

#### 16.9 Reset

The DMA registers are set to the default state on any Reset. The registers are also reset to the default state when the enable bit is cleared (EN = 0). User firmware needs to setup all the registers to resume DMA operation.

#### 16.10 Power-Saving Mode Operation

The DMA utilizes system clocks and it is treated as a peripheral when it comes to power-saving operations. Like other peripherals, the DMA also uses Peripheral Module Disable bits to further tailor its operation in low-power states.

#### 16.10.1 Sleep Mode

When the device enters Sleep mode, the system clock to the module is shut down, therefore no DMA operation is supported in Sleep. Once the system clock is disabled, the requisite read and write clocks are also disabled, without which the DMA cannot perform any of its tasks.

Any transfers that may be in progress are resumed on exiting from Sleep mode. Register contents are not affected by the device entering or leaving Sleep mode. It is recommended that DMA transactions be allowed to finish before entering Sleep mode.

#### 16.10.2 Idle Mode

In Idle mode, all of the system clocks (including the read and write clocks) are still operating, but the CPU is not using them to save power.

Therefore, every instruction cycle is available to the system arbiter and if the bubble is granted to the DMA, it may be utilized to move data.

#### 16.10.3 Doze Mode

Similar to the Idle mode, the CPU does not utilize all of the available instruction cycles slots that are available to it in order to save power. It only executes instructions based on its Doze mode settings.

Therefore, every instruction not used by the CPU is available for system arbitration and may be utilized by the DMA, if granted by the arbiter.

#### 16.10.4 Peripheral Module Disable

The Peripheral Module Disable (PMD) registers provide a method to disable DMA by gating all clock sources supplied to it. The respective DMAxMD bit needs to be set in order to disable the DMA.

#### 16.11 Example Setup Code

This code example illustrates using DMA1 to transfer 10 bytes of data from 0x1000 in Flash memory to the UART transmit buffer.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 299

```
void initializeDMA(){
//Select DMA1 by setting DMASELECT register to 0x00
    DMASELECT = 0 \times 00;
//DMAnCON1 - DPTR remains, Source Memory Region PFM, SPTR increments, SSTP
    DMAnCON1 = 0x0B;
//Source registers
//Source size
   DMAnSSZH = 0x00;
    DMAnSSZL = 0x0A;
//Source start address, 0x1000
    DMAnSSAU = 0 \times 00;
    DMAnSSAH = 0x10;
    DMAnSSAL = 0 \times 00;
//Destination registers
//Destination size
    DMAnDSZH = 0x00;
    DMAnDSZL = 0 \times 01;
//Destination start address,
    DMAnDSA = &U1TXB;
//Start trigger source U1TX. Refer the datasheet for the correct code
    DMAnSIRQ = 0xnn;
//Change arbiter priority if needed and perform lock operation
    DMA1PR = 0x01; // Change the priority only if needed
                           // This sequence
    PRLOCK = 0x55;
    PRLOCK = 0xAA; // is mandatory
PRLOCKbits.PRLOCKED = 1; // for DMA operation
//Enable the DMA & the trigger to start DMA transfer
    DMAnCON0 = 0xC0;
```

### 16.12 Register Overlay

All DMA instances in this device share the same set of registers. Only one DMA instance is accessible at a time. The value in the DMASELECT register is one less than the selected DMA instance. For example, a DMASELECT value of '0' selects DMA1.

#### 16.13 Register Definitions: DMA

#### **16.13.1 DMASELECT**

Name: DMASELECT Offset: 0x0E8

DMA Instance Selection Register

Selects which DMA instance is accessed by the DMA registers



Bits 2:0 - SLCT[2:0] DMA Instance Selection

Value	Description
n	Shared DMA registers of instance n+1 are selected for read and write operations.

#### 16.13.2 DMAnCON0

Name: DMAnCON0
Offset: 0x0FC

DMA Control Register 0

Bit	7	6	5	4	3	2	1	0
	EN	SIRQEN	DGO			AIRQEN		XIP
Access	R/W	R/W/HC	R/W/HS/HC			R/W/HC		R/HS/HC
Reset	0	0	0			0		0

#### Bit 7 - EN DMA Module Enable

Value	Description
1	Enables module
0	Disables module

#### Bit 6 - SIRQEN Start of Transfer Interrupt Request Enable

Value	Description
1	Hardware triggers are allowed to start DMA transfers
0	Hardware triggers are not allowed to start the DMA transfers

#### Bit 5 - DGO DMA Transaction

Value	Description
1	DMA transaction is in progress
0	DMA transaction is not in progress

#### Bit 2 - AIRQEN Abort of Transfer Interrupt Request Enable

ı	Value	Description
	1	Hardware triggers are allowed to abort DMA transfers
	0	Hardware triggers are not allowed to abort the DMA transfers

#### Bit 0 - XIP Transfer in Progress Status

Value	Description
1	The DMA buffer register currently holds contents from a read operation and has not transferred data to
_	the destination.
0	The DMA buffer register is empty or has successfully transferred data to the destination address.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 302

#### 16.13.3 DMAnCON1

Name: DMAnCON1 Offset: 0x0FD

DMA Control Register 1

Bit	7	6	5	4	3	2	1	0
	DMO	DE[1:0]	DSTP	SMR	R[1:0]	SMOD	E[1:0]	SSTP
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

#### Bits 7:6 - DMODE[1:0] Destination Address Mode Selection

Value	Description
11	Reserved, do not use
10	Destination Pointer (DMADPTR) is decremented after each transfer
01	Destination Pointer (DMADPTR) is incremented after each transfer
00	Destination Pointer (DMADPTR) remains unchanged after each transfer

#### Bit 5 - DSTP Destination Counter Reload Stop

Value	Description
1	SIRQEN bit is cleared when destination counter reloads
0	SIRQEN bit is not cleared when destination counter reloads

#### Bits 4:3 - SMR[1:0] Source Memory Region Selection

Value	Description
1x	Data EEPROM is selected as the DMA source memory
01	Program Flash Memory is selected as the DMA source memory
00	SFR/GPR data space is selected as the DMA source memory

#### Bits 2:1 - SMODE[1:0] Source Address Mode Selection

Value	Description
11	Reserved, do not use
10	Source Pointer (DMASPTR) is decremented after each transfer
01	Source Pointer (DMASPTR) is incremented after each transfer
00	Source Pointer (DMASPTR) remains unchanged after each transfer

#### Bit 0 - SSTP Source Counter Reload Stop

Value	Description
1	SIRQEN bit is cleared when source counter reloads
0	SIRQEN bit is not cleared when source counter reloads

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 303

# PIC18F26/46/56Q84

### **DMA - Direct Memory Access**

#### 16.13.4 DMAnBUF

Name: DMAnBUF Offset: 0x0E9

DMA Data Buffer Register

Bit	7	6	5	4	3	2	1	0			
	BUF[7:0]										
Access	R	R	R	R	R	R	R	R			
Reset	0	0	0	0	0	0	0	0			

#### Bits 7:0 - BUF[7:0] DMA Data Buffer

#### Description

These bits reflect the content of the internal data buffer the DMA peripheral uses to hold the data being moved from the source to destination.

#### 16.13.5 DMAnSSA

Name: DMAnSSA Offset: 0x0F9

DMA Source Start Address Register

Bit	23	22	21	20	19	18	17	16
					SSA[2	21:16]		
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			0	0	0	0	0	0
Bit	15	14	13	12	11	10	9	8
				SSA	[15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
				SSA	[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0


Bits 21:0 - SSA[21:0] Source Start Address

- 1. DMAnSSAU: Accesses the upper most byte [23:16].
- 2. DMAnSSAH: Accesses the high byte [15:8].
- 3. DMAnSSAL: Access the low byte [7:0].

#### 16.13.6 DMAnSSZ

Name: DMAnSSZ Offset: 0x0F7

DMA Source Size Register




Bits 11:0 - SSZ[11:0] Source Message Size

- I. DMAnSSZH: Accesses the high byte [15:8].
- 2. DMAnSSZL: Access the low byte [7:0].

#### 16.13.7 DMAnSCNT

Name: DMAnSCNT Offset: 0x0F2

**DMA Source Count Register** 



Bits 11:0 - SCNT[11:0] Current Source Byte Count

- I. DMAnSCNTH: Accesses the high byte [15:8].
- 2. DMAnSCNTL: Access the low byte [7:0].

#### 16.13.8 **DMAnSPTR**

Name: DMAnSPTR Offset: 0x0F4

DMA Source Pointer Register

Bit	23	22	21	20	19	18	17	16			
					SPTR	[21:16]					
Access		·	R	R	R	R	R	R			
Reset			0	0	0	0	0	0			
Bit	15	14	13	12	11	10	9	8			
	SPTR[15:8]										
Access	R	R	R	R	R	R	R	R			
Reset	0	0	0	0	0	0	0	0			
Bit	7	6	5	4	3	2	1	0			
				SPTI	₹[7:0]						
Access	R	R	R	R	R	R	R	R			
Reset	0	0	0	0	0	0	0	0			

Bits 21:0 - SPTR[21:0] Current Source Address Pointer

- 1. DMAnSPTRU: Accesses the upper most byte [23:16].
- 2. DMAnSPTRH: Accesses the high byte [15:8].
- 3. DMAnSPTRL: Access the low byte [7:0].

#### 16.13.9 DMAnDSA

Name: DMAnDSA Offset: 0x0F0

DMA Destination Start Address Register

Bit	15	14	13	12	11	10	9	8			
	DSA[15:8]										
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W			
Reset	0	0	0	0	0	0	0	0			
Bit	7	6	5	4	3	2	1	0			
				DSA	[7:0]						
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W			
Reset	0	0	0	0	0	0	0	0			


Bits 15:0 - DSA[15:0] Destination Start Address

- 1. DMAnDSAH: Accesses the high byte [15:8].
- 2. DMAnDSAL: Access the low byte [7:0].

#### 16.13.10 DMAnDSZ

Name: DMAnDSZ Offset: 0x0EE

**DMA Destination Size Register** 




Bits 11:0 - DSZ[11:0] Destination Message Size

- DMAnDSZH: Accesses the high byte [15:8].
- 2. DMAnDSZL: Access the low byte [7:0].

#### 16.13.11 DMAnDCNT

Name: DMAnDCNT Offset: 0x0EA

**DMA Destination Count Register** 



Bits 11:0 - DCNT[11:0] Current Destination Byte Count

- 1. DMAnDCNTH: Accesses the high byte [15:8].
- 2. DMAnDCNTL: Access the low byte Destination Message Size bits [7:0].

#### 16.13.12 DMAnDPTR

Name: DMAnDPTR Offset: 0x0EC

**DMA Destination Pointer Register** 

Bit	15	14	13	12	11	10	9	8			
	DPTR[15:8]										
Access	R	R	R	R	R	R	R	R			
Reset	0	0	0	0	0	0	0	0			
Bit	7	6	5	4	3	2	1	0			
				DPTI	R[7:0]						
Access	R	R	R	R	R	R	R	R			
Reset	0	0	0	0	0	0	0	0			

Bits 15:0 - DPTR[15:0] Current Destination Address Pointer

- 1. DMAnDPTRH: Accesses the high byte [15:8].
- 2. DMAnDPTRL: Access the low byte [7:0].

#### 16.13.13 DMAnSIRQ

Name: DMAnSIRQ Offset: 0x0FF

DMA Start Interrupt Request Source Selection Register

Bit	7	6	5	4	3	2	1	0				
	SIRQ[7:0]											
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W				
Reset	0	0	0	0	0	0	0	0				

Bits 7:0 - SIRQ[7:0] DMA Start Interrupt Request Source Selection

#### Table 16-6. DMAxSIRQ AND DMAxAIRQ INTERRUPT SOURCES

Vector	Interrupt	Vector Number	Interrupt source
Number	source	(cont.)	(cont.)
0x0		0x4C	·
0x1	HLVD (High/Low-Voltage Detect)	0x4D	CLC4
0x2	OSF (Oscillator Fail)	0x4E	PWM4RINT
0x3	CSW (Clock Switching)	0x4F	PWM4GINT
0x4	TU16A	0x50	INT2
0x5	CLC1 (Configurable Logic Cell)	0x51	CLC5
0x6	CAN (CAN Error)	0x52	CWG2 (Complementary Waveform Generator)
0x7	IOC (Interrupt On Change)	0x53	NCO2
0x8	INT0	0x54	DMA3SCNT
0x9	ZCD (Zero-Cross Detection)	0x55	DMA3DCNT
0xA	AD (ADC Conversion Complete)		DMA3OR
0xB	ACT (Active Clock Tuning)	0x57	DMA3A
0xC	CM1 (Comparator)	0x58	CCP3
0xD	SMT1 (Signal Measurement Timer)	0x59	CLC6
0xE	SMT1PRA	0x5A	CWG3
0xF	SMT1PWA	0x5B	TMR4
0x10	ADCH0	0x5C	DMA4SCNT
0x11	ADCH1	0x5D	DMA4DCNT
0x12	ADCH2	0x5E	DMA4OR
0x13	ADCH3	0x5F	DMA4A
0x14	DMA1SCNT (Direct Memory Access)	0x60	U4RX
0x15	DMA1DCNT	0x61	U4TX
0x16	DMA1OR	0x62	U4E
0x17	DMA1A	0x63	U4
0x18	SPI1RX (Serial Peripheral Interface)	0x64	DMA5SCNT
0x19	SPI1TX	0x65	DMA5DCNT
0x1A	SPI1	0x66	DMA5OR
0x1B	TMR2	0x67	DMA5A
0x1C	TMR1	0x68	U5RX
0x1D	TMR1G	0x69	U5TX
0x1E	CCP1 (Capture/Compare/PWM)	0x6A	U5E
0x1F	TMR0	0x6B	U5

conti	nued		
Vector	Interrupt	Vector	Interrupt
Number	source	Number	source
		(cont.)	(cont.)
0x20	U1RX	0x6C	DMA6SCNT
0x21	U1TX	0x6D	DMA6DCNT
0x22	U1E	0x6E	DMA6OR
0x23	U1	0x6F	DMA6A
0x24	CANRX	0x70	-
0x25	CANTX	0x71	CLC7
0x26	PWM1RINT	0x72	CM2
0x27	PWM1GINT	0x73	NCO3
0x28	SPI2RX	0x74	DMA7SCNT
0x29	SPI2TX	0x75	DMA7DCNT
0x2A	SPI2	0x76	DMA7OR
0x2B	TU16B	0x77	DMA7ABRT
0x2C	TMR3	0x78	NVM
0x2D	TMR3G	0x79	CLC8
0x2E	PWM2RINT	0x7A	CRC (Cyclic Redundancy Check)
0x2F	PWM2GINT	0x7B	TMR6
0x30	INT1	0x7C	DMA8SCNT
0x31	CLC2	0x7D	DMA8DCNT
0x32	CWG1 (Complementary Waveform Generator)	0x7E	DMA8OR
0x33	NCO1 (Numerically Controlled Oscillator)	0x7F	DMA8ABRT
0x34	DMA2SCNT	0x80	TU16APR
0x35	DMA2DCNT	0x81	TU16ACAPT
0x36	DMA2OR	0x82	TU16AZERO
0x37	DMA2A	0x83	TU16BPR
0x38	I2C1RX	0x84	TU16BCAPT
0x39	I2C1TX	0x85	TU16BZERO
0x3A	I2C1	0x86	-
0x3B	I2C1E	0x87	-
0x3C	<del>-</del>	0x88	-
0x3D	CLC3	0x89	-
0x3E	PWM3RINT	0x8A	-
0x3F	PWM3GINT	0x8B	-
0x40	U2RX	0x8C	-
0x41	U2TX	0x8D	-
0x42	U2E	0x8E	-
0x43	U2	0x8F	-
0x44	TMR5	0x90	PWM1.S1P1 (PWM1 Parameter 1 of Slice 1)
0x45	TMR5G	0x91	PWM1.S1P2 (PWM1 Parameter 2 of Slice 1)
0x46	CCP2	0x92	PWM2S1P1
0x47	SCAN	0x93	PWM2S1P2
0x48	U3RX	0x94	PWM3S1P1
0x49	U3TX	0x95	PWM3S1P2
0x4A	U3E	0x96	PWM4S1P1

# PIC18F26/46/56Q84

**DMA - Direct Memory Access** 

con	continued										
Vector Number	Interrupt source	Vector Number	Interrupt source								
	Source	(cont.)	(cont.)								
0x4B	U3	0x97	PWM4S1P2								

# PIC18F26/46/56Q84

# **DMA - Direct Memory Access**

#### 16.13.14 DMAnAIRQ

Name: DMAnAIRQ Offset: 0x0FE

DMA Abort Interrupt Request Source Selection Register

Bit	7	6	5	4	3	2	1	0			
	AIRQ[7:0]										
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W			
Reset	0	0	0	0	0	0	0	0			

**Bits 7:0 – AIRQ[7:0]** DMA Abort Interrupt Request Source Selection Refer to DMA Interrupt Sources Table.

# 16.14 Register Summary - DMA

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0xE7										
0xE8	DMASELECT	7:0							SLCT[2:0]	
0xE9	DMAnBUF	7:0				BUF	<del>-</del> [7:0]			
0xEA	DMAnDCNT	7:0				DCN	T[7:0]			
UXLA	DIVIAIDON	15:8						DCN <sup>-</sup>	Γ[11:8]	
0xEC	DMAnDPTR	7:0				DPT	R[7:0]			
UXLC	DIVIALIDETIX	15:8				DPTF	R[15:8]			
0xEE	DMAnDSZ	7:0				DSZ	Z[7:0]			
UXEE	DIVIANDSZ	15:8		DSZ[11:8]						
0xF0	DMAnDSA	7:0		DSA[7:0]						
UXFU	DIVIANDSA	15:8				DSA	[15:8]			
0xF2	DMAnSCNT	7:0				SCN	T[7:0]			
UXFZ	DIVIANSONT	15:8						SCN	Γ[11:8]	
		7:0		•		SPT	R[7:0]			
0xF4	DMAnSPTR	15:8				SPTF	R[15:8]			
		23:16					SPTR	[21:16]		
٥. 57	D144 007	7:0				SSZ	<b>[</b> [7:0]			
0xF7	DMAnSSZ	15:8						SSZ	[11:8]	
		7:0			-	SSA	A[7:0]			
0xF9	DMAnSSA	15:8				SSA	[15:8]			
		23:16					SSA[	21:16]		
0xFC	DMAnCON0	7:0	EN	SIRQEN	DGO			AIRQEN		XIP
0xFD	DMAnCON1	7:0	DMO	DE[1:0]	DSTP	SMF	R[1:0]	SMOI	DE[1:0]	SSTP
0xFE	DMAnAIRQ	7:0				AIRO	Q[7:0]	-		
0xFF	DMAnSIRQ	7:0				SIRO	Q[7:0]			

### 17. Power-Saving Modes

The purpose of the Power-Saving modes is to reduce power consumption. There are three Power-Saving modes:

- · Doze mode
- · Sleep mode
- · Idle mode

#### 17.1 Doze Mode

Doze mode allows for power saving by reducing CPU operation and Program Flash Memory (PFM) access, without affecting peripheral operation. Doze mode differs from Sleep mode because the band gap and system oscillators continue to operate, while only the CPU and PFM are affected. The reduced execution saves power by eliminating unnecessary operations within the CPU and memory.


When the Doze Enable bit is set (DOZEN = 'b1) the CPU executes only one instruction cycle out of every N cycles as defined by the DOZE bits. For example, if DOZE = 001, the instruction cycle ratio is 1:4. The CPU and memory execute for one instruction cycle and then lay idle for three instruction cycles. During the unused cycles, the peripherals continue to operate at the system clock speed.

#### 17.1.1 Doze Operation

The Doze operation is illustrated in Figure 17-1. As with normal operation, the instruction is fetched for the next instruction cycle while the previous instruction is executed. The Q-clocks to the peripherals continue throughout the periods in which no instructions are fetched or executed. The following configuration settings apply for this example:

- Doze enabled (DOZEN = 1)
- CPU instruction cycle to peripheral instruction cycle ratio of 1:4
- Recover-on-Interrupt enabled (ROI = 1)

Figure 17-1. Doze Mode Operation Example



#### Notes:

1. Multicycle instructions are executed to completion before fetching 0x0004.

**Example 17-1. Doze Software Example** 

2. If the prefetched instruction clears GIE, the ISR will not occur, but DOZEN is still cleared and the CPU will resume execution at full speed.

#### 17.1.2 Interrupts During Doze

System behavior for interrupts that may occur during Doze mode are be configured using the ROI bit and the DOE bit. Refer to the example below for details about system behavior in all cases for a transition from Main to ISR back to Main.

#### // Mainline operation bool somethingToDo = FALSE; void main() { initializeSystem(); // DOZE = 64:1 (for example) // ROI = 1; GIE = 1; // enable interrupts while (1) { // If ADC completed, process data if (somethingToDo) { doSomething(); DOZEN = 1; // resume low-power // Data interrupt handler void interrupt() { // DOZEN = 0 because ROI = 1 if (ADIF) {

#### Note:

User software can change DOE bit in the ISR.

somethingToDo = TRUE;

// else check other interrupts...

ADIF = 0;

if (TMR0IF) {
 timerTick++;

DOE = 0; // make main() go fast

DOE = 1; // make main() go slow TMR0IF = 0;

### 17.2 Sleep Mode

Sleep mode provides the greatest power savings because both the CPU and selected peripherals cease to operate. However, some peripheral clocks continue to operate during sleep. The peripherals that use those clocks also continue to operate. Sleep mode is entered by executing the SLEEP instruction, while the IDLEN bit is clear. Upon entering Sleep mode, the following conditions exist:

- 1. The WDT will be cleared but keeps running if enabled for operation during Sleep
- 2. The PD bit of the STATUS register is cleared
- 3. The TO bit of the STATUS register is set
- 4. The CPU clock is disabled
- 5. LFINTOSC, SOSC, HFINTOSC, and ADCRC (FRC) are unaffected. Peripherals using them may continue operation during Sleep.
- 6. I/O ports maintain the status they had before Sleep was executed (driving high, low, or high-impedance)

7. Resets other than WDT are not affected by Sleep mode



**Important:** Refer to individual chapters for more details on peripheral operation during Sleep.

To minimize current consumption, the following conditions should be considered:

- I/O pins should not be floating
- External circuitry sinking current from I/O pins
- · Internal circuitry sourcing current to I/O pins
- · Current draw from pins with internal weak pull-ups
- · Peripherals using clock source unaffected by Sleep

I/O pins that are high-impedance inputs should be pulled to  $V_{DD}$  or  $V_{SS}$  externally to avoid switching currents caused by floating inputs. Examples of internal circuitry that might be consuming current include modules such as the DAC and FVR peripherals.

#### 17.2.1 Wake-up from Sleep

The device can wake-up from Sleep through one of the following events:

- 1. External Reset input on MCLR pin, if enabled
- 2. BOR Reset, if enabled
- 3. Low-Power Brown-Out Reset (LPBOR), if enabled
- 4. POR Reset
- 5. Windowed Watchdog Timer, if enabled
- 6. All interrupt sources except clock switch interrupt can wake-up the part.



**Important:** The first five events will cause a device Reset. The last event in the list is considered a continuation of program execution. Fore more information about determining whether a device Reset or wake-up event occurred, refer to the "**Resets**" chapter.

When the SLEEP instruction is being executed, the next instruction (PC + 2) is prefetched. For the device to wake-up through an interrupt event, the corresponding Interrupt Enable bit must be enabled in the PIEx register. Wake-up will occur regardless of the state of the Global Interrupt Enable (GIE) bit. If the GIE bit is disabled, the device will continue execution at the instruction after the SLEEP instruction. If the GIE bit is enabled, the device executes the instruction after the SLEEP instruction and then call the Interrupt Service Routine (ISR).



Important: It is recommended to add a NOP as the immediate instruction after the SLEEP instruction.

The WDT is cleared when the device wakes-up from Sleep, regardless of the source of wake-up. Upon a wake-from-Sleep event, the core will wait for a combination of three conditions before beginning execution. The conditions are:

- · PFM Ready
- · System Clock Ready
- · BOR Ready (unless BOR is disabled)

#### 17.2.2 Wake-up Using Interrupts


When global interrupts are disabled (GIE cleared) and any interrupt source, with the exception of the clock switch interrupt, has both its interrupt enable bit and interrupt flag bit set, one of the following will occur:

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 320

- If the interrupt occurs before the execution of a SLEEP instruction
  - SLEEP instruction will execute as a NOP
  - WDT and WDT prescaler will not be cleared
  - TO bit of the STATUS register will not be set
  - PD bit of the STATUS register will not be cleared
- If the interrupt occurs during or after the execution of a SLEEP instruction
  - SLEEP instruction will be completely executed
  - Device will immediately wake-up from Sleep
  - WDT and WDT prescaler will be cleared
  - TO bit of the STATUS register will be set
  - PD bit of the STATUS register will be cleared

In the event where flag bits were checked before executing a SLEEP instruction, it may be possible for flag bits to have become set before the SLEEP instruction completes. To determine whether a SLEEP instruction executed, test the  $\overline{PD}$  bit. If the  $\overline{PD}$  bit is set, the SLEEP instruction was executed as a NOP.

Figure 17-2. Wake-up From Sleep Through Interrupt



#### Notes:

- 1. External clock High, Medium, Low mode assumed.
- 2. CLKOUT is shown here for timing reference.
- 3.  $T_{OST}$  = 1024  $T_{OSC}$ . This delay does not apply to EC and INTOSC Oscillator modes.
- 4. GIE = 1 assumed. In this case after wake-up, the processor calls the ISR at 0x0004. If GIE = 0, execution will continue in-line.

#### 17.2.3 Low-Power Sleep Mode

This device family contains an internal Low Dropout (LDO) voltage regulator, which allows the device I/O pins to operate at voltages up to  $V_{DD}$  while the internal device logic operates at a lower voltage. The LDO and its associated reference circuitry must remain active in Sleep but can operate in different power modes. This allows the user to optimize the operating current in Sleep mode, depending on the application requirements.

#### 17.2.3.1 Sleep Current vs. Wake-up Time

The Low-Power Sleep mode can be selected by setting the VREGPM bits as following:

- VREGPM = 'b00; the voltage regulator is in High-Power mode. In this mode, the voltage regulator and reference circuitry remain in the normal configuration while in Sleep. Hence, there is no delay needed for these circuits to stabilize after wake-up. (fastest wake-up from Sleep)
- VREGPM = 'b01; the voltage regulator is in Low-Power mode. In this mode, when waking up from Sleep, an extra delay time is required for the voltage regulator and reference circuitry to return to the normal configuration and stabilize. (faster wake-up from Sleep)
- VREGPM = 'b10; the voltage regulator is in Ultra-Low-Power mode. In this mode, the voltage regulator and reference circuitry are in the lowest current consumption mode and all the auxiliary circuits remain shut down. Wake up from Sleep in this mode need the longest delay time for the voltage regulator and reference circuitry to stabilize. (lowest current consumption)

VREGPM = 'b11; this mode is the same as VREGPM = 'b01, and is recommended <u>ONLY</u> for extended temperature ranges at or above 70°C.

Х

#### 17.2.3.2 Peripheral Usage in Sleep

Some peripherals that can operate in High-Power Sleep mode (VREGPM = 'b00) will not operate as intented in the Low-Power Sleep modes (VREGPM = 'b01 and 'b11). The Low-Power Sleep modes are intended for use with the following peripherals:

- · Brown-out Reset (BOR)
- Windowed Watchdog Timer (WWDT)
- External interrupt pin/Interrupt-On-Change pins

It is the responsibility of the end user to determine what is acceptable for their application when setting the VREGPM settings in order to ensure correct operation in Sleep.

#### 17.3 Idle Mode

When the IDLEN bit is clear, the SLEEP instruction will put the device into full Sleep mode. When IDLEN is set, the SLEEP instruction will put the device into Idle mode. In Idle mode, the CPU and memory operations are halted, but the peripheral clocks continue to run. This mode is similar to Doze mode, except that in Idle both the CPU and program memory are shut off.



#### Important:

- Peripherals using F<sub>OSC</sub> will continue to operate while in Idle (but not in Sleep). Peripherals using HFINTOSC:LFINTOSC will continue running in both Idle and Sleep.
- When the Clock Out Enable (CLKOUTEN) Configuration bit is cleared, the CLKOUT pin will
  continue operating while in Idle.

#### 17.3.1 Idle and Interrupts

Idle mode ends when an interrupt occurs (even if global interrupts are disabled), but IDLEN is not changed. The device can re-enter Idle by executing the SLEEP instruction. If Recover-on-Interrupt is enabled (ROI = 1), the interrupt that brings the device out of Idle also restores full-speed CPU execution when Doze is also enabled.

#### 17.3.2 Idle and WWDT

When in Idle, the WWDT Reset is blocked and will instead wake the device. The WWDT wake-up is not an interrupt, therefore ROI does not apply.



**Important:** The WWDT can bring the device out of Idle, in the same way it brings the device out of Sleep. The DOZEN bit is not affected.

# 17.4 Peripheral Operation in Power-Saving Modes

All selected clock sources and the peripherals running from them are active in both Idle and Doze modes. Only in Sleep mode, both the F<sub>OSC</sub> and F<sub>OSC</sub>/4 clocks are unavailable. However, all other clock sources enabled specifically or through peripheral clock selection before the part enters Sleep, remain operating in Sleep.

# 17.5 Register Definitions: Power-Savings Control

#### 17.5.1 CPUDOZE

Name: CPUDOZE Offset: 0x4F2

Doze and Idle Register

Bit	7	6	5	4	3	2	1	0
	IDLEN	DOZEN	ROI	DOE			DOZE[2:0]	
Access	R/W	R/W/HC/HS	R/W	R/W/HC/HS		R/W	R/W	R/W
Reset	0	0	0	0		0	0	0

#### Bit 7 - IDLEN Idle Enable

Value	Description
1	A SLEEP instruction places device into Idle mode
0	A SLEEP instruction places the device into Sleep mode

#### Bit 6 - DOZEN Doze Enable<sup>(1)</sup>

Value	Description
1	Places devices into Doze setting
0	Places devices into Normal mode

#### Bit 5 - ROI Recover-on-Interrupt(1)

Value	Description
1	Entering the Interrupt Service Routine (ISR) makes DOZEN = 0
0	Entering the Interrupt Service Routine (ISR) does not change DOZEN

#### Bit 4 - DOE Doze-on-Exit(1)

Value	Description
1	Exiting the ISR makes DOZEN = 1
0	Exiting the ISR does not change DOZEN

#### Bits 2:0 - DOZE[2:0] Ratio of CPU Instruction Cycles to Peripheral Instruction Cycles

Value	Description
111	1:256
110	1:128
101	1:64
100	1:32
011	1:16
010	1:8
001	1:4
000	1:2

#### Note:

1. When ROI = 1 or DOE = 1.

.

#### 17.5.2 **VREGCON**

Name: VREGCON Offset: 0x048

Voltage Regulator Control Register

Bit	7	6	5	4	3	2	1	0
			PMSY	'S[1:0]			VREG	PM[1:0]
Access			R	R			R/W	R/W
Reset			q	q			1	0

Bits 5:4 - PMSYS[1:0] System Power Mode Status

Value	Description
11	Regulator in LP mode for extended temperature range is active
10	Regulator in ULP mode is active
01	Regulator in LP mode is active
00	Regulator in HP mode is active

Bits 1:0 - VREGPM[1:0] Voltage Regulator Power Mode Selection

Value	Description
11	Regulator in Low-Power mode ONLY for extended temperature range
10	Regulator in Ultra-Low-Power mode (lowest current consumption)
01	Regulator in Low-Power mode (faster wake-up from Sleep)
00	Regulator in High-Power mode (fastest wake-up from Sleep)

# 17.6 Register Summary - Power-Savings Control

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x47										
0x48	VREGCON	7:0			PMSY	'S[1:0]			VREGI	PM[1:0]
0x49										
	Reserved									
0x04F1										
0x04F2	CPUDOZE	7:0	IDLEN	DOZEN	ROI	DOE			DOZE[2:0]	

# 18. PMD - Peripheral Module Disable

# 18.1 Overview

This module provides the ability to selectively enable or disable a peripheral. Disabling a peripheral places it in its lowest possible power state. The user can selectively disable unused modules to reduce the overall power consumption.



**Important:** All modules are ON by default following any system Reset.

# 18.2 Disabling a Module

A peripheral can be disabled by setting the corresponding peripheral disable bit in the PMDx register. Disabling a module has the following effects:

- The module is held in Reset and does not function.
- · All the SFRs pertaining to that peripheral become "unimplemented"
  - Writing is disabled
  - Reading returns 0x00
- · Module outputs are disabled

# 18.3 Enabling a Module

Clearing the corresponding module disable bit in the PMDx register, re-enables the module and the SFRs will reflect the Power-on Reset values.



**Important:** There should be no reads/writes to the module SFRs for at least two instruction cycles after it has been re-enabled.

# 18.4 Register Definitions: Peripheral Module Disable

# 18.4.1 PMD0

Name: PMD0 Offset: 0x060

PMD Control Register 0

Bit	7	6	5	4	3	2	1	0
	SYSCMD	FVRMD	HLVDMD	CRCMD	SCANMD		CLKRMD	IOCMD
Access	R/W	R/W	R/W	R/W	R/W		R/W	R/W
Reset	0	0	0	0	0		0	0

# Bit 7 - SYSCMD Disable Peripheral System Clock Network(1)

Value	Description			
1	System clock network disabled (F <sub>OSC</sub> )			
0	System clock network enabled			

#### Bit 6 - FVRMD Disable Fixed Voltage Reference

Disable Fixed Voltage Reference

Value	Description
1	FVR module disabled
0	FVR module enabled

# Bit 5 - HLVDMD Disable High/Low-Voltage Detect

	Value	Description					
ſ	1	HLVD module disabled					
	0	HLVD module enabled					

# Bit 4 - CRCMD Disable CRC Module

_	
Value	Description
1	CRC module disabled
0	CRC module enabled

# Bit 3 - SCANMD Disable NVM Memory Scanner

Value	Description
1	NVM memory scanner module disabled
0	NVM memory scanner module enabled

# Bit 1 - CLKRMD Disable Clock Reference

Value	Description			
1	Clock reference module disabled			
0	Clock reference module enabled			

#### Bit 0 - IOCMD Disable Interrupt-on-Change

Value	Description
1	Interrupt-on-change module is disabled
0	Interrupt-on-change module is enabled

#### Note:

 Clearing the SYSCMD bit disables the system clock (F<sub>OSC</sub>) to peripherals, however peripherals clocked by F<sub>OSC</sub>/4 are not affected.

# **PMD - Peripheral Module Disable**

# 18.4.2 PMD1

Name: PMD1 Offset: 0x061

PMD Control Register 1

Bit	7	6	5	4	3	2	1	0
	SMT1MD	TMR6MD	TMR5MD	TMR4MD	TMR3MD	TMR2MD	TMR1MD	TMR0MD
Access	R/W							
Reset	0	0	0	0	0	0	0	0

# Bit 7 - SMT1MD Disable SMT1 Module

Value	Description
1	SMT1 module disabled
0	SMT1 module enabled

# Bits 0, 1, 2, 3, 4, 5, 6 - TMRnMD Disable Timer TMRn

Value	Description
1	TMRn module disabled
0	TMRn module enabled

# **PMD - Peripheral Module Disable**

# 18.4.3 PMD2

Name: PMD2 Offset: 0x062

PMD Control Register 2

Bit	7	6	5	4	3	2	1	0
	CANMD						TU16BMD	TU16AMD
Access	R/W						R/W	R/W
Reset	0						0	0

# Bit 7 - CANMD Disable CAN Module

Value	Description
1	CAN module disabled
0	CAN module enabled

#### Bit 1 - TU16BMD Disable Universal Timer UT16B

Value	Description
1	UT16B module disabled
0	UT16B module enabled

# Bit 0 - TU16AMD Disable Universal Timer UT16A

Value	Description
1	UT16A module disabled
0	UT16A module enabled

# 18.4.4 PMD3

Name: PMD3 Offset: 0x063

PMD Control Register 3

Bit	7	6	5	4	3	2	1	0
	ACTMD	DAC1MD	ADCMD			C2MD	C1MD	ZCDMD
Access	R/W	R/W	R/W			R/W	R/W	R/W
Reset	0	0	0			0	0	0

# Bit 7 - ACTMD Disable Active Clock Tuning

Value	Description
1	Active Clock Tuning disabled
0	Active Clock Tuning enabled

# Bit 6 - DAC1MD Disable Digital to Analog Converter

Value	Description
1	DAC module disabled
0	DAC module enabled

#### Bit 5 - ADCMD Disable Analog to Digital Converter

	<u> </u>
Value	Description
1	ADC module disabled
0	ADC module enabled

# Bit 2 - C2MD Disable Comparator 2

Value	Description
1	CM2 module disabled
0	CM2 module enabled

### Bit 1 - C1MD Disable Comparator 1

Value	Description
1	CM1 module disabled
0	CM1 module enabled

# Bit 0 - ZCDMD Disable Zero Cross Detect<sup>(1)</sup>

	<b>V</b> alue	Description
	1	ZCD module disabled
(	)	ZCD module enabled

# Note:

1. Subject to the value of ZCD Configuration bit.

# 18.4.5 PMD4

Name: PMD4 Offset: 0x064

PMD Control Register 4

Bit	7	6	5	4	3	2	1	0
		CWG3MD	CWG2MD	CWG1MD	DSM1MD	NCO3MD	NCO2MD	NCO1MD
Access		R/W						
Reset		0	0	0	0	0	0	0

#### Bit 6 - CWG3MD Disable Complimentary Waveform Generator 3

Die Citating Bloadic Complimentary Travelerin Constraint		Bloadic Complimentary Travelenti Concrater C
	Value	Description
	1	CWG3 module disabled
	0	CWG3 module enabled

### Bit 5 - CWG2MD Disable Complimentary Waveform Generator 2

Value	Description
1	CWG2 module disabled
0	CWG2 module enabled

#### Bit 4 - CWG1MD Disable Complimentary Waveform Generator 1

V	alue	Description
1		CWG1 module disabled
0		CWG1 module enabled

# Bit 3 – DSM1MD Disable Digital Signal Modulator

Value	Description
1	DSM module disabled
0	DSM module enabled

### Bit 2 - NCO3MD Disable Numerically Controlled Oscillator 3

Value Description	
1	NCO3 module disabled
0	NCO3 module enabled

# Bit 1 - NCO2MD Disable Numerically Controlled Oscillator 2

V	alue	Description
1		NCO2 module disabled
0		NCO2 module enabled

#### Bit 0 - NCO1MD Disable Numerically Controlled Oscillator 1

Val	lue	Description
1		NCO1 module disabled
0		NCO1 module enabled

# 18.4.6 PMD5

Name: PMD5 Offset: 0x065

PMD Control Register 5

Bit	7	6	5	4	3	2	1	0
	PWM4MD	PWM3MD	PWM2MD	PWM1MD		CCP3MD	CCP2MD	CCP1MD
Access	R/W	R/W	R/W	R/W		R/W	R/W	R/W
Reset	0	0	0	0		0	0	0

# Bit 7 - PWM4MD Disable Pulse Width Modulator 4

Value	Description
1	PWM4 module disabled
0	PWM4 module enabled

#### Bit 6 - PWM3MD Disable Pulse Width Modulator 3

Value	Description
1	PWM3 module disabled
0	PWM3 module enabled

#### Bit 5 - PWM2MD Disable Pulse Width Modulator 2

Value	Description
1	PWM2 module disabled
0	PWM2 module enabled

# Bit 4 - PWM1MD Disable Pulse Width Modulator 1

ı	Value	Description
	1	PWM1 module disabled
	0	PWM1 module enabled

### Bit 2 - CCP3MD Disable Capture Compare 3

Value	Description				
1	CCP3 module disabled				
0	CCP3 module enabled				

# Bit 1 - CCP2MD Disable Capture Compare 2

V	alue	Description			
1		CCP2 module disabled			
0		CCP2 module enabled			

#### Bit 0 - CCP1MD Disable Capture Compare 1

Vá	alue	Description
1		CCP1 module disabled
0		CCP1 module enabled

# **PMD - Peripheral Module Disable**

# 18.4.7 PMD6

Name: PMD6 Offset: 0x066

PMD Control Register 6

Bit	7	6	5	4	3	2	1	0
	U5MD	U4MD	U3MD	U2MD	U1MD	SPI2MD	SPI1MD	I2C1MD
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

# Bits 3, 4, 5, 6, 7 - UnMD Disable UART Un

	<b>V</b> alue	Description				
	1	UARTn module disabled				
(	)	UARTn module enabled				

# Bit 2 - SPI2MD Disable Serial Peripheral Interface 2

Value	Description			
1	SPI2 module disabled			
0	SPI2 module enabled			

#### Bit 1 - SPI1MD Disable Serial Peripheral Interface 1

Value	Description
1	SPI1 module disabled
0	SPI1 module enabled

# Bit 0 - I2C1MD Disable I2C

Value	Description
1	I <sup>2</sup> C1 module disabled
0	I <sup>2</sup> C1 module enabled

# **PMD - Peripheral Module Disable**

# 18.4.8 PMD7

Name: PMD7 Offset: 0x067

PMD Control Register 7

Bit	7	6	5	4	3	2	1	0
	CLC8MD	CLC7MD	CLC6MD	CLC5MD	CLC4MD	CLC3MD	CLC2MD	CLC1MD
Access	R/W							
Reset	0	0	0	0	0	0	0	0

# Bits 0, 1, 2, 3, 4, 5, 6, 7 - CLCnMD Disable CLCn

Value	Description			
1	CLCn module disabled			
0	CLCn module enabled			

# **PMD - Peripheral Module Disable**

# 18.4.9 PMD8

Name: PMD8 Offset: 0x068

PMD Control Register 8

Bit	7	6	5	4	3	2	1	0
	DMA8MD	DMA7MD	DMA6MD	DMA5MD	DMA4MD	DMA3MD	DMA2MD	DMA1MD
Access	R/W							
Reset	0	0	0	0	0	0	0	0

# Bits 0, 1, 2, 3, 4, 5, 6, 7 - DMAnMD Disable DMAn

Value	Description			
1	DMAn module disabled			
0	DMAn module enabled			

# 18.5 Register Summary - PMD

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x5F										
0x60	PMD0	7:0	SYSCMD	FVRMD	HLVDMD	CRCMD	SCANMD		CLKRMD	IOCMD
0x61	PMD1	7:0	SMT1MD	TMR6MD	TMR5MD	TMR4MD	TMR3MD	TMR2MD	TMR1MD	TMR0MD
0x62	PMD2	7:0	CANMD						TU16BMD	TU16AMD
0x63	PMD3	7:0	ACTMD	DAC1MD	ADCMD			C2MD	C1MD	ZCDMD
0x64	PMD4	7:0		CWG3MD	CWG2MD	CWG1MD	DSM1MD	NCO3MD	NCO2MD	NCO1MD
0x65	PMD5	7:0	PWM4MD	PWM3MD	PWM2MD	PWM1MD		CCP3MD	CCP2MD	CCP1MD
0x66	PMD6	7:0	U5MD	U4MD	U3MD	U2MD	U1MD	SPI2MD	SPI1MD	I2C1MD
0x67	PMD7	7:0	CLC8MD	CLC7MD	CLC6MD	CLC5MD	CLC4MD	CLC3MD	CLC2MD	CLC1MD
0x68	PMD8	7:0	DM88MD	DMA7MD	DMA6MD	DMA5MD	DMA4MD	DMA3MD	DMA2MD	DMA1MD

# 19. I/O Ports

# 19.1 Overview

Table 19-1. Port Availability per Device

Device	PORTA	PORTB	PORTC	PORTD	PORTE	PORTF
28-pin devices	•	•	•		<b>●</b> (1)	
40/44-pin devices	•	•	•	•	●(2)	
48-pin devices	•	•	•	•	●(2)	•

#### Notes:

- 1. Pin RE3 only.
- 2. Pins RE0, RE1, RE2 and RE3 only.


Each port has eight registers to control the operation. These registers are:

- PORTx registers (reads the levels on the pins of the device)
- LATx registers (output latch)
- TRISx registers (data direction)
- ANSELx registers (analog select)
- WPUx registers (weak pull-up)
- INLVLx (input level control)
- SLRCONx registers (slew rate control)
- · ODCONx registers (open-drain control)

In this chapter the generic names such as PORTx, LATx, TRISx, etc. can be associated with PORTA, PORTB, PORTC, etc., depending on availability per device.

A simplified model of a generic I/O port, without the interfaces to other peripherals, is shown in the following figure:

Figure 19-1. Generic I/O Port Operation



# 19.2 PORTx - Data Register

PORTx is a bidirectional port, and its corresponding data direction register is TRISx.

Reading the PORTx register reads the status of the pins, whereas writing to it will write to the PORT latch. All write operations are read-modify-write operations. Therefore, a write to a port implies that the PORT pins are read, and this value is modified, then written to the PORT data latch (LATx). The PORT data latch LATx holds the output port data and contains the latest value of a LATx or PORTx write. The example below shows how to initialize PORTA.

#### Example 19-1. Initializing PORTA in assembly ; This code example illustrates initializing the PORTA register. ; The other ports are initialized in the same manner. BANKSEL PORTA CLRF PORTA ;Clear PORTA BANKSEL LATA CLRF TATA ;Clear Data Latch BANKSEL ANSELA ; Enable digital drivers CLRF ANSELA BANKSEL TRISA B'00111000' ;Set RA[5:3] as inputs MOVIW MOVWF TRISA ; and set others as outputs



**Important:** Most PORT pins share functions with device peripherals, both analog and digital. In general, when a peripheral is enabled on a PORT pin, that pin cannot be used as a general purpose output; however, the pin can still be read.

# 19.3 LATx - Output Latch

The Data Latch (LATx registers) is useful for read-modify-write operations on the value that the I/O pins are driving.

A write operation to the LATx register has the same effect as a write to the corresponding PORTx register. A read of the LATx register reads of the values held in the I/O PORT latches, while a read of the PORTx register reads the actual I/O pin value.



**Important:** As a general rule, output operations to a port should use the LAT register to avoid read-modify-write issues. For example, a bit set or clear operation reads the port, modifies the bit, and writes the result back to the port. When two bit operations are executed in succession, output loading on the changed bit may delay the change at the output in which case the bit will be misread in the second bit operation and written to an unexpected level. The LAT registers are isolated from the port loading and therefore changes are not delayed.

# 19.4 TRISx - Direction Control

The TRISx register controls the PORTx pin output drivers, even when the pins are being used as analog inputs. The user should ensure the bits in the TRISx register are set when using the pins as analog inputs. I/O pins configured as analog inputs always read '0'.

Setting a TRISx bit (TRISx = 1) will make the corresponding PORTx pin an input (i.e., disable the output driver). Clearing a TRISx bit (TRISx = 0) will make the corresponding PORTx pin an output (i.e., it enables output driver and puts the contents of the output latch on the selected pin).

# 19.5 ANSELx - Analog Control

Ports that support analog inputs have an associated ANSELx register. The ANSELx register is used to configure the input mode of an I/O pin to analog. Setting an ANSELx bit high will disable the digital input buffer associated with that bit and cause the corresponding input value to always read '0', whether the value is read in PORTx register or selected by PPS as a peripheral input.

Disabling the input buffer prevents analog signal levels on the pin between a logic high and low from causing excessive current in the logic input circuitry.

The state of the ANSELx bits has no effect on digital or analog output functions. A pin with TRIS clear and ANSEL set will still operate as a digital output, but the input mode will be analog. This can cause unexpected behavior when executing read-modify-write instructions on the PORTx register.



**Important:** The ANSELx bits default to the Analog mode after Reset. To use any pins as digital general purpose or peripheral inputs, the corresponding ANSEL bits must be changed to '0' by user.

# 19.6 WPUx - Weak Pull-Up Control

The WPUx register controls the individual weak pull-ups for each PORT pin. When a WPUx bit is set (WPUx = 1), the weak pull-up will be enabled for the corresponding pin. When a WPUx bit is cleared (WPUx = 0), the weak pull-up will be disabled for the corresponding pin.

# 19.7 INLVLx - Input Threshold Control

The INLVLx register controls the input voltage threshold for each of the available PORTx input pins. A selection between the Schmitt Trigger CMOS or the TTL compatible thresholds is available. If that feature is enabled, the input threshold is important in determining the value of a read of the PORTx register and also all other peripherals which are connected to the input. Refer to the I/O Ports table in the "Electrical Specifications" chapter for more details on threshold levels.



**Important:** Changing the input threshold selection should be performed while all peripheral modules are disabled. Changing the threshold level during the time a module is active may inadvertently generate a transition associated with an input pin, regardless of the actual voltage level on that pin.

# 19.8 SLRCONx - Slew Rate Control

The SLRCONx register controls the slew rate option for each PORT pin. Slew rate for each PORT pin can be controlled independently. When a SLRCONx bit is set (SLRCONx = 1), the corresponding PORT pin drive is slew

rate limited. When a SLRCONx bit is cleared (SLRCONx = 0), The corresponding PORT pin drive slews at the maximum rate possible.

# 19.9 ODCONx - Open-Drain Control

The ODCONx register controls the open-drain feature of the port. Open-drain operation is independently selected for each pin. When a ODCONx bit is set (ODCONx = 1), the corresponding port output becomes an open-drain driver capable of sinking current only. When a ODCONx bit is cleared (ODCONx = 0), the corresponding port output pin is the standard push-pull drive capable of sourcing and sinking current.



**Important:** It is necessary to set open-drain control when using the pin for I<sup>2</sup>C.

# 19.10 Edge Selectable Interrupt-on-Change

An interrupt can be generated by detecting a signal at the PORT pin that has either a rising edge or a falling edge. Individual pins can be independently configured to generate an interrupt. Refer to the "IOC - Interrupt-on-Change" chapter for more details.

# 19.11 I<sup>2</sup>C Pad Control

For this family of devices, the  $I^2C$  specific pads are available on RB1, RB2, RC3 and RC4 pins. The  $I^2C$  characteristics of each of these pins is controlled by the RxyI2C registers. These characteristics include enabling  $I^2C$  specific slew rate (over standard GPIO slew rate), selecting internal pull-ups for  $I^2C$  pins, and selecting appropriate input threshold as per SMBus specifications.



**Important:** Any peripheral using the I<sup>2</sup>C pins reads the I<sup>2</sup>C input levels when enabled via RxyI2C.

# 19.12 I/O Priorities

Each pin defaults to the data latch after Reset. Other functions are selected with the peripheral pin select logic. Refer to the "PPS - Peripheral Pin Select Module" chapter for more details.

Analog input functions, such as ADC and comparator inputs, are not shown in the peripheral pin select lists. These inputs are active when the I/O pin is set for Analog mode using the ANSELx register. Digital output functions may continue to control the pin when it is in Analog mode.

Analog outputs, when enabled, take priority over digital outputs and force the digital output driver into a high-impedance state.

The pin function priorities are as follows:

- 1. Port functions determined by the Configuration bits
- 2. Analog outputs (input buffers should be disabled)
- 3. Analog inputs
- Port inputs and outputs from PPS

# 19.13 MCLR/V<sub>PP</sub>/RE3 Pin

The  $\overline{\text{MCLR}}/V_{PP}$  pin is an input-only pin. Its operation is controlled by the MCLRE Configuration bit. When selected as a PORT pin (MCLRE = 0), it functions as a digital input-only pin; as such, it does not have TRISx and LATx bits associated with its operation. Otherwise, it functions as the device's Master Clear input. In either configuration, the  $\overline{\text{MCLR}}/V_{PP}$  pin also functions as the programming voltage input pin during high voltage programming.

The  $\overline{\text{MCLR}/V_{PP}}$  pin is a read-only bit and will read '1' when MCLRE = 1 (i.e., Master Clear enabled).



**Important:** On a Power-on Reset, the  $\overline{MCLR}/V_{PP}$  pin is enabled as a digital input-only if Master Clear functionality is disabled.

The  $\overline{MCLR}/V_{PP}$  pin has an individually controlled internal weak pull-up. When set, the corresponding WPU bit enables the pull-up. When the  $\overline{MCLR}/V_{PP}$  pin is configured as  $\overline{MCLR}$ , (MCLRE = 1 and, LVP = 0), or configured for Low-Voltage Programming, (MCLRE = x and LVP = 1), the pull-up is always enabled and the WPU bit has no effect.

# 19.14 Register Definitions: Port Control

# 19.14.1 PORTx

Name: PORTx

**PORTx Register** 

Bit	7	6	5	4	3	2	1	0
	Rx7	Rx6	Rx5	Rx4	Rx3	Rx2	Rx1	Rx0
Access	R/W							
Reset	X	X	X	X	X	X	X	X

# Bits 0, 1, 2, 3, 4, 5, 6, 7 - Rxn Port I/O Value

Reset States: POR/BOR = xxxxxxxx

All Other Resets = uuuuuuuu

Value	Description
1	PORT pin is ≥ V <sub>IH</sub>
0	PORT pin is ≤ V <sub>IL</sub>



- Writes to PORTx are actually written to the corresponding LATx register. Reads from PORTx register return actual I/O pin values.
- The PORT bit associated with the  $\overline{MCLR}$  pin is Read-Only and will read '1' when  $\overline{MCLR}$  function is enabled (LVP = 1 or (LVP = 0 and MCLRE = 1)).
- Refer to the "Pin Allocation Table" for details about MCLR pin and pin availability per port.

# 19.14.2 LATx

Name: LATx

Output Latch Register

Bit	7	6	5	4	3	2	1	0
	LATx7	LATx6	LATx5	LATx4	LATx3	LATx2	LATx1	LATx0
Access	R/W							
Reset	X	X	X	X	X	X	X	X

Bits 0, 1, 2, 3, 4, 5, 6, 7 - LATxn Output Latch Value

Reset States: POR/BOR = xxxxxxxx

All Other Resets = uuuuuuuu



- Writes to LATx are equivalent with writes to the corresponding PORTx register. Reads from LATx register return register values, not I/O pin values.
- Refer to the "Pin Allocation Table" for details about pin availability per port.

# 19.14.3 TRISx

Name: TRISx

Tri-State Control Register

Bit	7	6	5	4	3	2	1	0
	TRISx7	TRISx6	TRISx5	TRISx4	TRISx3	TRISx2	TRISx1	TRISx0
Access	R/W							
Reset	1	1	1	1	1	1	1	1

# Bits 0, 1, 2, 3, 4, 5, 6, 7 - TRISxn Port I/O Tri-state Control

Value	Description
1	PORTx output driver is disabled. PORTx pin configured as an input (tri-stated)
0	PORTx output driver is enabled. PORTx pin configured as an output



- The TRIS bit associated with the  $\overline{\text{MCLR}}$  pin is Read-Only and the value is 1.
- Refer to the "Pin Allocation Table" for details about MCLR pin and pin availability per port.

# 19.14.4 ANSELx

Name: ANSELx

Analog Select Register

Bit	7	6	5	4	3	2	1	0
	ANSELx7	ANSELx6	ANSELx5	ANSELx4	ANSELx3	ANSELx2	ANSELx1	ANSELx0
Access	R/W							
Reset	1	1	1	1	1	1	1	1

# Bits 0, 1, 2, 3, 4, 5, 6, 7 - ANSELxn Analog Select on Rx Pin

Value	Description
1	Analog input. Pin is assigned as analog input. Digital input buffer disabled.
0	Digital I/O. Pin is assigned to port or digital special function.



- When setting a pin as an analog input, the corresponding TRIS bit must be set to Input mode in order to allow external control of the voltage on the pin.
- Refer to the "Pin Allocation Table" for details about pin availability per port.

# 19.14.5 WPUx

Name: WPUx

Weak pull-up Register

Bit	7	6	5	4	3	2	1	0
	WPUx7	WPUx6	WPUx5	WPUx4	WPUx3	WPUx2	WPUx1	WPUx0
Access	R/W							
Reset	0	0	0	0	0	0	0	0

# Bits 0, 1, 2, 3, 4, 5, 6, 7 - WPUxn Weak Pull-up PORTx Control

Value	Description
1	Weak pull-up enabled
0	Weak pull-up disabled



- The weak pull-up device is automatically disabled if the pin is configured as an output but this register remains unchanged.
- If MCLRE = 1, the weak pull-up on MCLR pin is always enabled and the corresponding WPU bit is not affected.
- · Refer to the "Pin Allocation Table" for details about pin availability per port.

# 19.14.6 INLVLx

Name: INLVLx

Input Level Control Register

Bit	7	6	5	4	3	2	1	0
	INLVLx7	INLVLx6	INLVLx5	INLVLx4	INLVLx3	INLVLx2	INLVLx1	INLVLx0
Access	R/W							
Reset	1	1	1	1	1	1	1	1

Bits 0, 1, 2, 3, 4, 5, 6, 7 - INLVLxn Input Level Select on Rx Pin

Value	Description
1	ST input used for port reads and interrupt-on-change
0	TTL input used for port reads and interrupt-on-change



Important: Refer to the "Pin Allocation Table" for details about pin availability per port.

# 19.14.7 SLRCONx

Name: SLRCONx

Slew Rate Control Register

Bit	7	6	5	4	3	2	1	0
	SLRx7	SLRx6	SLRx5	SLRx4	SLRx3	SLRx2	SLRx1	SLRx0
Access	R/W							
Reset	1	1	1	1	1	1	1	1

# Bits 0, 1, 2, 3, 4, 5, 6, 7 - SLRxn Slew Rate Control on Rx Pin

Value	Description
1	PORT pin slew rate is limited
0	PORT pin slews at maximum rate



Important: Refer to the "Pin Allocation Table" for details about pin availability per port.

# 19.14.8 ODCONx

Name: ODCONx

Open-Drain Control Register

Bit	7	6	5	4	3	2	1	0
	ODCx7	ODCx6	ODCx5	ODCx4	ODCx3	ODCx2	ODCx1	ODCx0
Access	R/W							
Reset	0	0	0	0	0	0	0	0

Bits 0, 1, 2, 3, 4, 5, 6, 7 - ODCxn Open-Drain Configuration on Rx Pin

Value	Description
1	PORT pin operates as open-drain drive (sink current only)
0	PORT pin operates as standard push-pull drive (source and sink current)



Important: Refer to the "Pin Allocation Table" for details about pin availability per port.

# 19.14.9 Rxyl2C

Name: Rxyl2C

I<sup>2</sup>C Pad Rxy Control Register

Bit	7	6	5	4	3	2	1	0
	SLEV	V[1:0]	PU[1:0]				TH[1:0]	
Access	R/W	R/W	R/W	R/W			R/W	R/W
Reset	0	0	0	0			0	0

Bits 7:6 – SLEW[1:0] I<sup>2</sup>C Specific Slew Rate Limiting Control

Value	Description
11	I <sup>2</sup> C fast-mode-plus (1 MHz) slew rate enabled. The SLRxy bit is ignored.
10	Reserved
01	I <sup>2</sup> C fast-mode (400 kHz) slew rate enabled. The SLRxy bit is ignored.
00	Standard GPIO Slew Rate; enabled/disabled via SLRxy bit

Bits 5:4 – PU[1:0] I<sup>2</sup>C Pull-up Selection

Value	Description
11	Reserved
10	10x current of standard weak pull-up
01	2x current of standard weak pull-up
00	Standard GPIO weak pull-up, enabled via WPUxy bit

Bits 1:0 - TH[1:0] I<sup>2</sup>C Input Threshold Selection

	THE THE THE WHOLE THE CONTROL CONTROL
Value	Description
11	SMBus 3.0 (1.35V) input threshold
10	SMBus 2.0 (2.1 V) input threshold
01	I <sup>2</sup> C-specific input thresholds
00	Standard GPIO Input pull-up, enabled via INLVLxy registers



**Important:** Refer to the "Pin Allocation Table" for details about I<sup>2</sup>C compatible pins.

# 19.15 Register Summary - IO Ports

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x0285										
0x0286	RC4I2C	7:0		V[1:0]		PU[1:0]			THI	1:0]
0x0287	RC3I2C	7:0	SLEV	V[1:0]	PU	[1:0]			TH[1:0]	
0x0288	RB2I2C	7:0		V[1:0]	PU	[1:0]			THI	1:0]
0x0289	RB1I2C	7:0	SLEV	V[1:0]	PU	[1:0]			THI	1:0]
0x028A										
	Reserved									
0x03FF										
0x0400	ANSELA	7:0	ANSELA7	ANSELA6	ANSELA5	ANSELA4	ANSELA3	ANSELA2	ANSELA1	ANSELA0
0x0401	WPUA	7:0	WPUA7	WPUA6	WPUA5	WPUA4	WPUA3	WPUA2	WPUA1	WPUA0
0x0402	ODCONA	7:0	ODCA7	ODCA6	ODCA5	ODCA4	ODCA3	ODCA2	ODCA1	ODCA0
0x0403	SLRCONA	7:0	SLRA7	SLRA6	SLRA5	SLRA4	SLRA3	SLRA2	SLRA1	SLRA0
0x0404	INLVLA	7:0	INLVLA7	INLVLA6	INLVLA5	INLVLA4	INLVLA3	INLVLA2	INLVLA1	INLVLA0
0x0405										
	Reserved									
0x0407	ANIOEI D		441051.55	441051.00	ANIOE! DE	441051.54	411051.00	4410EL DO	411051 D4	411051.50
0x0408	ANSELB	7:0	ANSELB7	ANSELB6	ANSELB5	ANSELB4	ANSELB3	ANSELB2	ANSELB1	ANSELB0
0x0409	WPUB	7:0	WPUB7	WPUB6	WPUB5	WPUB4	WPUB3	WPUB2	WPUB1	WPUB0
0x040A	ODCONB	7:0	ODCB7	ODCB6	ODCB5	ODCB4	ODCB3	ODCB2	ODCB1	ODCB0
0x040B	SLRCONB	7:0	SLRB7	SLRB6	SLRB5	SLRB4	SLRB3	SLRB2	SLRB1	SLRB0
0x040C	INLVLB	7:0	INLVLB7	INLVLB6	INLVLB5	INLVLB4	INLVLB3	INLVLB2	INLVLB1	INLVLB0
0x040D	Decembed									
 0v040E	Reserved									
0x040F 0x0410	ANSELC	7:0	ANSELC7	ANSELC6	ANSELC5	ANSELC4	ANSELC3	ANSELC2	ANSELC1	ANSELC0
0x0410	WPUC	7:0	WPUC7	WPUC6	WPUC5	WPUC4	WPUC3	WPUC2	WPUC1	WPUC0
0x0411	ODCONC	7:0	ODCC7	ODCC6	ODCC5	ODCC4	ODCC3	ODCC2	ODCC1	ODCC0
0x0412	SLRCONC	7:0	SLRC7	SLRC6	SLRC5	SLRC4	SLRC3	SLRC2	SLRC1	SLRC0
0x0414	INLVLC	7:0	INLVLC7	INLVLC6	INLVLC5	INLVLC4	INLVLC3	INLVLC2	INLVLC1	INLVLC0
0x0415	IIILVEO	7.0		11127200	11127200	II TEVEO I		INCVESE	II VEVEO I	11424200
	Reserved									
0x0417										
0x0418	ANSELD	7:0	ANSELD7	ANSELD6	ANSELD5	ANSELD4	ANSELD3	ANSELD2	ANSELD1	ANSELD0
0x0419	WPUD	7:0	WPUD7	WPUD6	WPUD5	WPUD4	WPUD3	WPUD2	WPUD1	WPUD0
0x041A	ODCOND	7:0	ODCD7	ODCD6	ODCD5	ODCD4	ODCD3	ODCD2	ODCD1	ODCD0
0x041B	SLRCOND	7:0	SLRD7	SLRD6	SLRD5	SLRD4	SLRD3	SLRD2	SLRD1	SLRD0
0x041C	INLVLD	7:0	INLVLD7	INLVLD6	INLVLD5	INLVLD4	INLVLD3	INLVLD2	INLVLD1	INLVLD0
0x041D										
	Reserved									
0x041F										
0x0420	ANSELE	7:0						ANSELE2	ANSELE1	ANSELE0
0x0421	WPUE	7:0					WPUE3	WPUE2	WPUE1	WPUE0
0x0422	ODCONE	7:0						ODCE2	ODCE1	ODCE0
0x0423	SLRCONE	7:0						SLRE2	SLRE1	SLRE0
0x0424	INLVLE	7:0					INLVLE3	INLVLE2	INLVLE1	INLVLE0
0x0425										
	Reserved									
0x0427										
0x0428	ANSELF	7:0	ANSELF7	ANSELF6	ANSELF5	ANSELF4	ANSELF3	ANSELF2	ANSELF1	ANSELF0
0x0429	WPUF	7:0	WPUF7	WPUF6	WPUF5	WPUF4	WPUF3	WPUF2	WPUF1	WPUF0
0x042A	ODCONF	7:0	ODCF7	ODCF6	ODCF5	ODCF4	ODCF3	ODCF2	ODCF1	ODCF0
0x042B	SLRCONF	7:0	SLRF7	SLRF6	SLRF5	SLRF4	SLRF3	SLRF2	SLRF1	SLRF0
0x042C	INLVLF	7:0	INLVLF7	INLVLF6	INLVLF5	INLVLF4	INLVLF3	INLVLF2	INLVLF1	INLVLF0

# I/O Ports

continued										
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x042D										
	Reserved									
0x04BD										
0x04BE	LATA	7:0	LATA7	LATA6	LATA5	LATA4	LATA3	LATA2	LATA1	LATA0
0x04BF	LATB	7:0	LATB7	LATB6	LATB5	LATB4	LATB3	LATB2	LATB1	LATB0
0x04C0	LATC	7:0	LATC7	LATC6	LATC5	LATC4	LATC3	LATC2	LATC1	LATC0
0x04C1	LATD	7:0	LATD7	LATD6	LATD5	LATD4	LATD3	LATD2	LATD1	LATD0
0x04C2	LATE	7:0						LATE2	LATE1	LATE0
0x04C3	LATF	7:0	LATF7	LATF6	LATF5	LATF4	LATF3	LATF2	LATF1	LATF0
0x04C4										
	Reserved									
0x04C5										
0x04C6	TRISA	7:0	TRISA7	TRISA6	TRISA5	TRISA4	TRISA3	TRISA2	TRISA1	TRISA0
0x04C7	TRISB	7:0	TRISB7	TRISB6	TRISB5	TRISB4	TRISB3	TRISB2	TRISB1	TRISB0
0x04C8	TRISC	7:0	TRISC7	TRISC6	TRISC5	TRISC4	TRISC3	TRISC2	TRISC1	TRISC0
0x04C9	TRISD	7:0	TRISD7	TRISD6	TRISD5	TRISD4	TRISD3	TRISD2	TRISD1	TRISD0
0x04CA	TRISE	7:0					Reserved	TRISE2	TRISE1	TRISE0
0x04CB	TRISF	7:0	TRISF7	TRISF6	TRISF5	TRISF4	TRISF3	TRISF2	TRISF1	TRISF0
0x04CC										
	Reserved									
0x04CD										
0x04CE	PORTA	7:0	RA7	RA6	RA5	RA4	RA3	RA2	RA1	RA0
0x04CF	PORTB	7:0	RB7	RB6	RB5	RB4	RB3	RB2	RB1	RB0
0x04D0	PORTC	7:0	RC7	RC6	RC5	RC4	RC3	RC2	RC1	RC0
0x04D1	PORTD	7:0	RD7	RD6	RD5	RD4	RD3	RD2	RD1	RD0
0x04D2	PORTE	7:0					RE3	RE2	RE1	RE0
0x04D3	PORTF	7:0	RF7	RF6	RF5	RF4	RF3	RF2	RF1	RF0

# 20. IOC - Interrupt-on-Change

# 20.1 Overview

The pins denoted in the table below can be configured to operate as Interrupt-on-Change (IOC) pins for this device. An interrupt can be generated by detecting a signal that has either a rising edge or a falling edge. Any individual PORT pin, or combination of PORT pins, can be configured to generate an interrupt.

Table 20-1. IOC Pin Availability per Device

Device	PORTA	PORTB	PORTC	PORTD	PORTE	PORTF
28-pin devices	•	•	•		●(1)	
40/44-pin devices	•	•	•		●(2)	
48-pin devices	•	•	•		<b>●</b> (2)	

#### Notes:

- 1. Pin RE3 only.
- 2. Pins RE0, RE1, RE2 and RE3 only.




**Important:** If MCLRE = 1 or LVP = 1, the  $\overline{\text{MCLR}}$  pin port functionality is disabled and IOC on that pin is not available

The Interrupt-on-Change module has the following features:

- · Interrupt-on-Change enable (Master Switch)
- Individual pin configuration
- · Rising and falling edge detection
- · Individual pin interrupt flags

The following figure is a block diagram of the IOC module.

Figure 20-1. Interrupt-on-Change Block Diagram (PORTA Example)



# 20.2 Enabling the Module

In order for individual PORT pins to generate an interrupt, the IOC Interrupt Enable bit (IOCIE) of the Peripheral Interrupt Enable register (PIEx) must be set. If the IOC Interrupt Enable bit is disabled, the edge detection on the pin will still occur, but an interrupt will not be generated.

# 20.3 Individual Pin Configuration

A rising edge detector and a falling edge detector are present for each PORT pin. To enable a pin to detect a rising edge, the associated bit of the IOCxP register must be set. To enable a pin to detect a falling edge, the associated bit of the IOCxN register must be set. A PORT pin can be configured to detect rising and falling edges simultaneously by setting both associated bits of the IOCxP and IOCxN registers, respectively.

# 20.4 Interrupt Flags

The bits located in the IOCxF registers are status flags that correspond to the interrupt-on-change pins of each port. If an expected edge is detected on an appropriately enabled pin, then the status flag for that pin will be set, and an interrupt will be generated if the IOCIE bit is set. The IOCIF bit located in the corresponding Peripheral Interrupt Request register (PIRx), is all the IOCxF bits ORd together. The IOCIF bit is read-only. All of the IOCxF Status bits must be cleared to clear the IOCIF bit.

# 20.5 Clearing Interrupt Flags

The individual status flags, (IOCxF register bits), will be cleared by resetting them to zero. If another edge is detected during this clearing operation, the associated status flag will be set at the end of the sequence, regardless of the value actually being written.

In order to ensure that no detected edge is lost while clearing flags, only AND operations masking out known changed bits should be performed. The following sequence is an example of clearing an IOC interrupt flag using this method.

```
Example 20-1. Clearing Interrupt Flags
(PORTA Example)

MOVLW 0xff
XORWF IOCAF, W
ANDWF IOCAF, F
```

# 20.6 Operation in Sleep

An interrupt-on-change interrupt event will wake the device from Sleep mode, if the IOCIE bit is set. If an edge is detected while in Sleep mode, the IOCxF register will be updated prior to the first instruction executed out of Sleep.

# 20.7 Register Definitions: Interrupt-on-Change Control

# 20.7.1 IOCxF

Name: IOCxF

Interrupt-on-Change Flag Register

Bit	7	6	5	4	3	2	1	0
	IOCxF7	IOCxF6	IOCxF5	IOCxF4	IOCxF3	IOCxF2	IOCxF1	IOCxF0
Access	R/W/HS							
Reset	0	0	0	0	0	0	0	0

Bits 0, 1, 2, 3, 4, 5, 6, 7 - IOCxFn Interrupt-on-Change Flag

Value	Condition	Description
1	IOCxP[n] = 1	A positive edge was detected on the Rx[n] pin
1	IOCxN[n] = 1	A negative edge was detected on the Rx[n] pin
0	IOCxP[n] = x and $IOCxN[n] = x$	No change was detected, or the user cleared the detected change



- If MCLRE = 1 or LVP = 1, the MCLR pin port functionality is disabled and IOC on that pin is not available.
- Refer to the "Pin Allocation Table" for details about pins with configurable IOC per port.

# 20.7.2 IOCxN

Name: IOCxN

Interrupt-on-Change Negative Edge Register Example

Bit	7	6	5 4		3	2	1	0
	IOCxN7	IOCxN6	IOCxN5	IOCxN4	IOCxN3	IOCxN2	IOCxN1	IOCxN0
Access	R/W							
Reset	0	0	0	0	0	0	0	0

Bits 0, 1, 2, 3, 4, 5, 6, 7 - IOCxNn Interrupt-on-Change Negative Edge Enable

, , ,	-, , -, -, -				3					
Value	Description									
1	Interrupt-on-Change enable	d on the	OCx	pin for a neg	ative-going edge. Associated Status bit and					
	interrupt flag will be set upon detecting an edge.									
0	Falling edge Interrupt-on-Ch	ange d	isabled	for the asso	ciated pin					



- If MCLRE = 1 or LVP = 1, the MCLR pin port functionality is disabled and IOC on that pin is not available.
- Refer to the "Pin Allocation Table" for details about pins with configurable IOC per port.

# 20.7.3 IOCxP

Name: IOCxP

Interrupt-on-Change Positive Edge Register

Bit	7	6	5	4	3	2	1	0
	IOCxP7	IOCxP6	IOCxP5	IOCxP4	IOCxP3	IOCxP2	IOCxP1	IOCxP0
Access	R/W							
Reset	0	0	0	0	0	0	0	0

Bits 0, 1, 2, 3, 4, 5, 6, 7 – IOCxPn Interrupt-on-Change Positive Edge Enable

, , ,	, , , ,
Value	Description
1	nterrupt-on-Change enabled on the IOCx pin for a positive-going edge. Associated Status bit and
	nterrupt flag will be set upon detecting an edge.
0	Rising edge Interrupt-on-Change disabled for the associated pin.



- If MCLRE = 1 or LVP = 1, the MCLR pin port functionality is disabled and IOC on that pin is not available.
- Refer to the "Pin Allocation Table" for details about pins with configurable IOC per port.

# 20.8 Register Summary: Interrupt-on-Change Control

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x0404										
0x0405	IOCAP	7:0	IOCAP7	IOCAP6	IOCAP5	IOCAP4	IOCAP3	IOCAP2	IOCAP1	IOCAP0
0x0406	IOCAN	7:0	IOCAN7	IOCAN6	IOCAN5	IOCAN4	IOCAN3	IOCAN2	IOCAN1	IOCAN0
0x0407	IOCAF	7:0	IOCAF7	IOCAF6	IOCAF5	IOCAF4	IOCAF3	IOCAF2	IOCAF1	IOCAF0
0x0408										
	Reserved									
0x040C										
0x040D	IOCBP	7:0	IOCBP7	IOCBP6	IOCBP5	IOCBP4	IOCBP3	IOCBP2	IOCBP1	IOCBP0
0x040E	IOCBN	7:0	IOCBN7	IOCBN6	IOCBN5	IOCBN4	IOCBN3	IOCBN2	IOCBN1	IOCBN0
0x040F	IOCBF	7:0	IOCBF7	IOCBF6	IOCBF5	IOCBF4	IOCBF3	IOCBF2	IOCBF1	IOCBF0
0x0410										
	Reserved									
0x0414										
0x0415	IOCCP	7:0	IOCCP7	IOCCP6	IOCCP5	IOCCP4	IOCCP3	IOCCP2	IOCCP1	IOCCP0
0x0416	IOCCN	7:0	IOCCN7	IOCCN6	IOCCN5	IOCCN4	IOCCN3	IOCCN2	IOCCN1	IOCCN0
0x0417	IOCCF	7:0	IOCCF7	IOCCF6	IOCCF5	IOCCF4	IOCCF3	IOCCF2	IOCCF1	IOCCF0
0x0418										
	Reserved									
0x0424										
0x0425	IOCEP	7:0					IOCEP3			
0x0426	IOCEN	7:0					IOCEN3			
0x0427	IOCEF	7:0					IOCEF3			

# 21. PPS - Peripheral Pin Select Module

# 21.1 Overview


The Peripheral Pin Select (PPS) module connects peripheral inputs and outputs to the device I/O pins. Only digital signals are included in the selections.



**Important:** All analog inputs and outputs remain fixed to their assigned pins and cannot be changed through PPS.

Input and output selections are independent as shown in the figure below.

Figure 21-1. PPS Block Diagram



# 21.2 PPS Inputs

Each digital peripheral has a dedicated PPS Peripheral Input Selection (xxxPPS) register with which the input pin to the peripheral is selected. Devices that have 20 leads or less (8/14/16/20) allow PPS routing to any I/O pin, while devices with 28 leads or more allow PPS routing to I/Os contained within two ports (see the PPS Input Selection Table below).



**Important:** The notation "xxx" in the generic register name is a place holder for the peripheral identifier. For example, xxx = T0CKI for the T0CKIPPS register.

Multiple peripherals can operate from the same source simultaneously. Port reads always return the pin level regardless of peripheral PPS selection. If a pin also has analog functions associated, the ANSEL bit for that pin must be cleared to enable the digital input buffer.

**Table 21-1. PPS Input Selection Table** 

		Default Pin	Register Reset	Available Input Port												
Peripheral	PPS Input Register	Selection at POR	Value at POR	28-P	in De	vices	40	-Pir	n De	vic	es	48-	Pin	De	vic	es
Interrupt 0	INT0PPS	RB0	'b001 000	Α	В	_	Α	В		=	_	AE	3 —			_
Interrupt 1	INT1PPS	RB1	'b001 001	Α	В	_	Α	В	-	_	_	— E	3 —	D		_
Interrupt 2	INT2PPS	RB2	'b001 010	Α	В	_	Α	В	-	-	_	— E	3 —			F
Timer0 Clock	T0CKIPPS	RA4	'b000 100	Α	В	_	Α	В	_	_	_	<b>A</b> –				F
Timer1 Clock	T1CKIPPS	RC0	'b010 000	Α	_	С	Α	_	С	_	_		- C		Е	_
Timer1 Gate	T1GPPS	RB5	'b001 101	_	В	С	_	В	С	_	_	— E	ВС			_
Timer3 Clock	T3CKIPPS	RC0	'b010 000	_	В	С	<u> </u>	В	С	-	_		- C		Е	_
Timer3 Gate	T3GPPS	RC0	'b010 000	Α	_	С	Α	_	С	_	_	<b>A</b> –	- C			_
Timer5 Clock	T5CKIPPS	RC2	'b010 010	Α	_	С	Α	_	С	-	_		- C		Е	_
Timer5 Gate	T5GPPS	RB4	'b001 100	_	В	С	_	В	-	D	_	— E	3 —	D		_
Timer2 Input	T2INPPS	RC3	'b010 011	Α	_	С	Α	_	С	-	_	Α –	- C			_
Timer4 Input	T4INPPS	RC5	'b010 101	_	В	С	_	В	С	_	_	— E	C			_
Timer6 Input	T6INPPS	RB7	'b001 111	_	В	С	<u> </u>	В	-	D	_	— E	3 —	D		_
Universal Timer Input 0	TUIN0PPS	RC0	'b010 000	Α	_	С	_	_	С	_	Е		- C		Е	_
Universal Timer Input 1	TUIN1PPS	RB5	'b001 101	<b>—</b>	В	С	-	В	С	_	_	— E	3 —	_		F—
CCP1	CCP1PPS	RC2	'b010 010	_	В	С	_	В	С	_	_		- C			F
CCP2	CCP2PPS	RC1	'b010 001	<b>—</b>	В	С	-	В	С	_	_		- C			F
CCP3	CCP3PPS	RB5	'b001 101	_	В	С	_	В	_	D	_	— E	3 —	D		_
SMT1 Window	SMT1WINPPS	RC0	'b010 000	<u> </u>	В	С	_	В	С	_	_		- C			F
SMT1 Signal	SMT1SIGPPS	RC1	'b010 001	_	В	С	_	В	С	_	_		- C		_	F
PWM Input 0	PWMIN0PPS	RC2	'b010 010	<u> </u>	В	С	_	В	С	_	_		- C			F
PWM Input 1	PWMIN1PPS	RC6	'b010 110	Α	_	С	Α	_	_	_	Е	<b>A</b> –	-		Е	_
PWM1 External Reset Source	PWM1ERSPPS	RC3	'b010 011	Α	-	С	Α	-	С	-	-	<b>A</b> –	- C			-
PWM2 External Reset Source	PWM2ERSPPS	RC5	'b010 101	A	_	С	A	_	С	-	_		- C		Е	_
PWM3 External Reset Source	PWM3ERSPPS	RB7	'b001 111	_	В	С	_	В		D	-	_ E	3 —	D		_
PWM4 External Reset Source	PWM4ERSPPS	RC3	'b010 011	A	_	С	Α	_	С	_	-		- C		Ε	_
CWG1	CWG1PPS	RB0	'b001 000	_	В	С		В	-	D	-	— E	3 —	D	-	_
CWG2	CWG2PPS	RB1	'b001 001		В	С		В		D	-	— E	3 —	D		_
CWG3	CWG3PPS	RB2	'b001 010	_	В	С	<u> </u>	В		D	_	— E	3 —	D		_
DSM1 Carrier Low	MD1CARLPPS	RA3	'b000 011	Α	_	С	Α	_		D	-	<b>A</b> –	-	D		_
DSM1 Carrier High	MD1CARHPPS	RA4	'b000 100	Α	_	С	Α	_		D	_	<b>A</b> –	-	D		_
DSM1 Source	MD1SRCPPS	RA5	'b000 101	Α	_	С	Α	_	-	D	_	<b>A</b> –	-	D	-	_
CLCx Input 1	CLCIN0PPS	RA0	'b000 000	Α	_	С	Α	_	С	_	_	Α –	- C			_
CLCx Input 2	CLCIN1PPS	RA1	'b000 001	Α	_	С	Α	_	С	-	_	<b>A</b> –	- C		_	_
CLCx Input 3	CLCIN2PPS	RB6	'b001 110	T —	В	С	_	В		D	_	— E	3 —	D		_
CLCx Input 4	CLCIN3PPS	RB7	'b001 111	<b>—</b>	В	С	_	В		D	_	— E	3 —	D		_
CLCx Input 5	CLCIN4PPS	RA0	'b000 000	Α	_	С	Α	_	С		-	Α –	- C			_
CLCx Input 6	CLCIN5PPS	RA1	'b000 001	A	_	С	Α	_	С	_	_	<b>A</b> –	- C			_

continued														
		Default Pin	Register Reset			-	۱vai	ilab	le l	npu	t Por	t		
Peripheral	PPS Input Register	Selection at POR	Value at POR	28-P	in De	vices	40	-Pin	ı De	vic	es 4	8-Pi	n Dev	/ices
CLCx Input 7	CLCIN6PPS	RB6	'b001 110	—	В	С		В	-	D		В-	_ D -	_   _
CLCx Input 8	CLCIN7PPS	RB7	'b001 111	—	В	С		В		D	_ _	В-	_ D -	- -
ADC Conversion Trigger	ADACTPPS	RB4	'b001 100	_	В	С	_	В	_	D		В-	_ D -	
SPI1 Clock	SPI1SCKPPS	RC3	'b010 011	—	В	С		В	С			В	C   -	
SPI1 Data	SPI1SDIPPS	RC4	'b010 100	—	В	С		В	С			В	C   -	
SPI1 Slave Select	SPI1SSPPS	RA5	'b000 101	Α	_	С	Α			D	_ A		_ D -	
SPI2 Clock	SPI2SCKPPS	RB3	'b001 011	—	В	С		В	-	D		В-	_ D -	
SPI2 Data	SPI2SDIPPS	RB2	'b001 010	<b>—</b>	В	С		В		D		В-	_ D -	- -
SPI2 Slave Select	SPI2SSPPS	RA4	'b000 100	Α	_	С	Α	_	-	D	— A		_ D -	
I2C1 Clock	I2C1SCLPPS <sup>(1)</sup>	RC3	'b010 011	<b>—</b>	В	С	<u> </u>	В	С	-	_ _	В	c   -	
I2C1 Data	I2C1SDAPPS(1)	RC4	'b010 100	<b>—</b>	В	С		В	С	-		В	c  _ -	
UART1 Receive	U1RXPPS	RC7	'b010 111	<b>—</b>	В	С	<u> </u>	В	С	-	_ _	_ (	c   -	_ F
UART1 Clear to Send	U1CTSPPS	RC6	'b010 110	<b>—</b>	В	С		В	С	-		_ (	c  _ -	_ F
UART2 Receive	U2RXPPS	RB7	'b001 111	<b>—</b>	В	С	<u> </u>	В		D	_ _	В-	_ D -	
UART2 Clear to Send	U2CTSPPS	RB6	'b001 110	<b>—</b>	В	С		В	-	D		В-	_ D -	
UART3 Receive	U3RXPPS	RA7	'b000 111	Α	В	_	Α	В		-	— A			_ F
UART3 Clear to Send	U3CTSPPS	RA6	'b000 110	Α	В	_	Α	В	_	_	— A		_ _ -	_ F
UART4 Receive	U4RXPPS	RB5	'b001 101	_	В	С	_	В	_	D	_ _	В-	_ D -	
UART4 Clear to Send	U4CTSPPS	RB4	'b001 100	_	В	С	_	В	_	D		В-	– D -	
UART5 Receive	U5RXPPS	RA5	'b000 101	Α	_	С	Α	_	С		_ A	-	-  -	_ F
UART5 Clear to Send	U5CTSPPS	RA4	'b000 100	Α	_	С	Α	_	С	-	— A		_ _ -	_ F
CAN Receive	CANRXPPS	RB3	'b001 011	—	В	С	-	В	-	D	_ _	В-	_ D -	_ _

#### Note:

1. Bidirectional pin. The corresponding output must select the same pin.

## 21.3 PPS Outputs

Each digital peripheral has a dedicated Pin Rxy Output Source Selection (RxyPPS) register with which the pin output source is selected. With few exceptions, the port TRIS control associated with that pin retains control over the pin output driver. Peripherals that control the pin output driver as part of the peripheral operation will override the TRIS control as needed. The I<sup>2</sup>C module is an example of such a peripheral.



**Important:** The notation 'Rxy' is a place holder for the pin identifier. The 'x' holds the place of the PORT letter and the 'y' holds the place of the bit number. For example, Rxy = RA0 for the RA0PPS register.

The PPS Output Selection Table below shows the output codes for each peripheral, as well as the available Port selections.

Table 21-2. PPS Output Selection Table

RxyPPS	Output Source	Available Output Ports													
КХУГГО	Output Source	28-F	Pin Dev	ices	4	ŀ0-Pi	n De	vice	s		48-l	Pin I	Devi	ices	
0x46	CANTX	_	В	С	-	В	_	D	—	_	В	_	D	_	_
0x45	ADGRDB	Α	_	С	Α	_	С	_	_	Α	_	_	_	_	F

continued															
					Avai	lable	e Out	tput	Port	s					
RxyPPS	Output Source	28-F	in Dev	ices	4	₽0-Pi	n De	vice	s		48-	Pin l	Devi	ces	
0x44	ADGRDA	Α	_	С	Α	_	С	_	_	Α	<del>-</del>	_	_	_	F
0x43	DSM1	Α	_	С	Α	_	_	D	_	Α	-	_	D	_	
0x42	CLKR	_	В	С	_	В	С	_	_	_	В	_	_	Е	_
0x41	NCO3	_	В	С	-	В	_	_	Е	_	В	_	_	Ε	
0x40	NCO2	_	В	С	_	В	_	D	_	_	В	_	D	_	_
0x3F	NCO1	Α	_	С	Α	_	_	D	_	Α	-	_	D	_	
0x3E - 0x3C	Reserved	_	_	_	_	_	_	_	_	_	-	_	_	_	_
0x3B	TU16B	_	В	С	-	В	_	D	_	_	В	_	D	_	
0x3A	TU16A	_	В	С	_	В	С	_	_	_	-	С	_	_	F
0x39	TMR0	_	В	С	_	В	С	_	_	_	_	С	_	_	F
0x38	I2C1 SDA <sup>(1)</sup>	_	В	С	_	В	С	_	_	_	В	С	_	_	_
0x37	I2C1 SCL <sup>(1)</sup>	_	В	С	-	В	С	_	_	_	В	С	_	_	
0x36	SPI2 SS	Α	_	С	Α	_	_	D	_	Α	-	_	D	_	_
0x35	SPI2 SDO	_	В	С	_	В	_	D	_	_	В	_	D	_	_
0x34	SPI2 SCK	_	В	С	_	В	_	D	_	_	В	_	D	_	_
0x33	SPI1 SS	Α	_	С	Α	_	_	D	_	Α	_	_	D	_	_
0x32	SPI1 SDO	_	В	С	_	В	С	_	_	_	В	С	_	_	_
0x31	SPI1 SCK	_	В	С	-	В	С	_	_	_	В	С	_	_	
0x30	C2OUT	Α	_	С	Α	_	_	_	Е	Α	<b>—</b>	_	_	Ε	_
0x2F	C1OUT	Α	_	С	Α	_	_	D	_	Α	_	_	D	_	_
0x2E	UART5 RTS	_	В	С	_	В	С	_	_	_	<b>—</b>	С	_	_	F
0x2D	UART5 TXDE	_	В	С	_	В	С	_	_	_	_	С	_	_	F
0x2C	UART5 TX	_	В	С	_	В	С	_	_	_	_	С	_	_	F
0x2B	UART4 RTS	Α	В	_	Α	_	_	D	_	Α	_	_	D	_	_
0x2A	UART4 TXDE	Α	В	_	Α	_	_	D	_	Α	<b>—</b>	_	D	_	_
0x29	UART4 TX	Α	В	_	Α	_	_	D	_	Α	_	_	D	_	_
0x28	UART3 RTS	Α	В	_	Α	В	_	_	_	Α	-	_	_	_	F
0x27	UART3 TXDE	Α	В	_	Α	В	_	_	_	Α	-	_	_	_	F
0x26	UART3 TX	Α	В	_	Α	В	_	_	_	Α	-	_	_	_	F
0x25	UART2 RTS	_	В	С	-	В	_	D	_	_	В	_	D	_	
0x24	UART2 TXDE	_	В	С	_	В	_	D	_	_	В	_	D	_	_
0x23	UART2 TX	_	В	С	_	В	_	D	_	_	В	_	D	_	
0x22	UART1 RTS	_	В	С	_	В	С	_	_	_		С	_	_	F
0x21	UART1 TXDE	_	В	С	_	В	С	_	_	_	-	С	_	_	F
0x20	UART1 TX	_	В	С	_	В	С	_	_	_		С	_	_	F
0x1F	PWM4S1P2_OUT	Α	_	С	Α	_	_	D	_	Α	-	_	D	_	
0x1E	PWM4S1P1_OUT	Α	_	С	Α	_	С	_	_	_	-	С	_	_	F
0x1D	PWM3S1P2_OUT	_	В	С	_	В	_	D	_	_	В	_	D	_	
0x1C	PWM3S1P1_OUT		В	С	_	В	_	D	_	_	В	_	D	_	_
0x1B	PWM2S1P2_OUT	_	В	С	_	В	_	D	_	_	В	_	D	_	_
0x1A	PWM2S1P1_OUT	_	В	С	_	В	_	D	_	_	В	_	D	_	_
0x19	PWM1S1P2_OUT	_	В	С	_	В	С	_	_	_	_	С	_	_	F
0x18	PWM1S1P1_OUT	_	В	С	_	В	С	_	_	_	-	С	_	_	F
0x17	CCP3	_	В	С	_	В	_	D	_	_	В	_	D	_	_
0x16	CCP2	_	В	С	_	В	С	_	_	_	_	С	_	_	F

continued															
RxyPPS	Output Source				Ava	ilable	e Out	tput	Port	s					
Кхуггэ	Output Source	28-F	Pin Dev	ices	4	10-Pi	n De	vice	s		48-I	Pin I	Devi	ices	
0x15	CCP1	_	В	С	-	В	С	_	_	_	_	С	_		F
0x14	CWG3D	Α	_	С	Α	_	_	D	_	Α	_	_	D	_	_
0x13	CWG3C	Α	<u> </u>	С	Α	_	_	D	_	Α	_	_	D		
0x12	CWG3B	Α	_	С	Α	_	_	_	Е	Α	_	_	_	Е	_
0x11	CWG3A	_	В	С	-	В	С	_	_	_	В	С	_		
0x10	CWG2D	_	В	С	<b>—</b>	В	_	D	_	_	В	_	D	_	_
0x0F	CWG2C	_	В	С	-	В	_	D	_	_	В	_	D		_
0x0E	CWG2B	_	В	С	<b>—</b>	В	_	D	_	_	В	_	D	_	_
0x0D	CWG2A	_	В	С	-	В	С	_	_	_	В	С	_		_
0x0C	CWG1D	_	В	С	-	В	_	D	_	_	В	_	D	_	_
0x0B	CWG1C	_	В	С	-	В	_	D	_	_	В	_	D		_
0x0A	CWG1B	_	В	С	-	В	_	D	_	_	В	_	D	_	_
0x09	CWG1A	_	В	С	-	В	С	_	_	_	В	С	_		_
0x08	CLC8OUT	_	В	С	-	В	_	D	_	_	В	_	D	_	_
0x07	CLC7OUT	_	В	С	-	В	_	D	_	_	В	_	D	_	_
0x06	CLC6OUT	Α	_	С	Α	_	С	_	_	Α	_	_	_	_	F
0x05	CLC5OUT	Α	<u> </u>	С	Α	_	С	_	_	Α	_	_	_		F
0x04	CLC4OUT	_	В	С	-	В	_	D	_	_	В	_	D	_	_
0x03	CLC3OUT	_	В	С	-	В	_	D	_	_	В	_	D	_	_
0x02	CLC2OUT	Α	_	С	Α	_	С	_	_	Α	_	_	_		F
0x01	CLC10UT	Α	_	С	Α	_	С	_	_	Α	_	_	_	_	F
0x00	LATxy	Α	В	С	Α	В	С	D	E	Α	В	С	D	Е	F

#### Note:

1. Bidirectional pin. The corresponding input must select the same pin.

## 21.4 Bidirectional Pins

PPS selections for peripherals with bidirectional signals on a single pin must be made so that the PPS input and PPS output select the same pin. The I<sup>2</sup>C Serial Clock (SCL) and Serial Data (SDA) are examples of such pins.



**Important:** The I<sup>2</sup>C default pins, and a limited number of other alternate pins, are I<sup>2</sup>C and SMBus compatible. SDA and SCL signals can be routed to any pin; however, pins without I<sup>2</sup>C compatibility will operate at standard TTL/ST logic levels as selected by the port's INLVL register.

#### 21.5 PPS Lock

The PPS module provides an extra layer of protection to prevent inadvertent changes to the PPS selection registers. The PPSLOCKED bit is used in combination with specific code execution blocks to lock/unlock the PPS selection registers.



**Important:** The PPSLOCKED bit is clear by default (PPSLOCKED = 0), which allows the PPS selection registers to be modified without an unlock sequence.

## **PPS - Peripheral Pin Select Module**

PPS selection registers are locked when the PPSLOCKED bit is set (PPSLOCKED = 1). Setting the PPSLOCKED bit requires a specific lock sequence as shown in the examples below in both C and assembly languages.

PPS selection registers are unlocked when the PPSLOCKED bit is clear (PPSLOCKED = 0). Clearing the PPSLOCKED bit requires a specific unlock sequence as shown in the examples below in both C and assembly languages.



**Important:** All interrupts should be disabled before starting the lock/unlock sequence to ensure proper execution.

## Example 21-1. PPS Lock Sequence (Assembly language)

```
; suspend interrupts
BCF INTCONO,GIE
BANKSEL PPSLOCK
; required sequence, next 5 instructions
MOVLW 0x55
MOVWF PPSLOCK
MOVLW 0xAA
MOVWF PPSLOCK
; Set PPSLOCKED bit
BSF PPSLOCK,PPSLOCKED
; restore interrupts
BSF INTCONO,GIE
```

#### Example 21-2. PPS Lock Sequence (C language)

#### Example 21-3. PPS Unlock Sequence (Assembly language)

```
; suspend interrupts
BCF INTCON0,GIE
BANKSEL PPSLOCK
; required sequence, next 5 instructions
MOVLW 0x55
MOVWF PPSLOCK
MOVLW 0xAA
MOVWF PPSLOCK
; Clear PPSLOCKED bit
BCF PPSLOCK,PPSLOCKED
; restore interrupts
BSF INTCON0,GIE
```

### Example 21-4. PPS Unlock Sequence (C language)

## 21.5.1 PPS One-Way Lock

The PPS1WAY Configuration bit can also be used to prevent inadvertent modification to the PPS selection registers.

When the PPS1WAY bit is set (PPS1WAY = 1), the PPSLOCKED bit can only be set one time after a device Reset. Once the PPSLOCKED bit has been set, it cannot be cleared again unless a device Reset is executed.

When the PPS1WAY bit is clear (PPS1WAY = 0), the PPSLOCKED bit can be set or cleared as needed; however, the PPS lock/unlock sequences must be executed.

## 21.6 Operation During Sleep

PPS input and output selections are unaffected by Sleep.

#### 21.7 Effects of a Reset

A device Power-on Reset (POR) or Brown-out Reset (BOR) returns all PPS input selection registers to their default values, and clears all PPS output selection registers. All other Resets leave the selections unchanged. Default input selections are shown in the PPS input register details table. The PPSLOCKED bit is cleared in all Reset conditions.

## 21.8 Register Definitions: Peripheral Pin Select (PPS)

#### 21.8.1 xxxPPS

Name: xxxPPS

Peripheral Input Selection Register

Bit	7	6	5	4	3	2	1	0
				PORT[2:0]			PIN[2:0]	
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			m	m	m	m	m	m

Bits 5:3 - PORT[2:0] Peripheral Input PORT Selection<sup>(1)</sup>

See the PPS Input Selection Table for the list of available Ports and default pin locations.

Reset States: POR = mmm

All other Resets = uuu

Value	Description
101	PORTF
100	PORTE
011	PORTD
010	PORTC
001	PORTB
000	PORTA

#### Bits 2:0 – PIN[2:0] Peripheral Input PORT Pin Selection<sup>(2)</sup>

Reset States: POR = mmm

All other Resets = uuu

Value	Description
111	Peripheral input is from PORTx Pin 7 (Rx7)
110	Peripheral input is from PORTx Pin 6 (Rx6)
101	Peripheral input is from PORTx Pin 5 (Rx5)
100	Peripheral input is from PORTx Pin 4 (Rx4)
011	Peripheral input is from PORTx Pin 3 (Rx3)
010	Peripheral input is from PORTx Pin 2 (Rx2)
001	Peripheral input is from PORTx Pin 1 (Rx1)
000	Peripheral input is from PORTx Pin 0 (Rx0)

#### Notes:

- 1. The Reset value 'm' is determined by device default locations for that input.
- 2. Refer to the Pin Allocation Table for details about available pins per port.

## **PPS - Peripheral Pin Select Module**

#### **RxyPPS** 21.8.2

Name: **RxyPPS** 

Pin Rxy Output Source Selection Register

Bit	7	6	5	4	3	2	1	0
					RxyPF	PS[5:0]		
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			0	0	0	0	0	0

Bits 5:0 - RxyPPS[5:0] Pin Rxy Output Source Selection

See the PPS Output Selection Table for the list of RxyPPS Output Source codes

Reset States: POR = 0000000


All other Resets = uuuuuuu

## **PPS - Peripheral Pin Select Module**

## 21.8.3 PPSLOCK

Name: PPSLOCK

PPS Lock Register



## Bit 0 - PPSLOCKED PPS Locked

Reset States: POR = 0

All other Resets = 0

V	'alue	Description
1		PPS is locked. PPS selections cannot be changed. Writes to any PPS register are ignored.
0		PPS is not locked. PPS selections can be changed, but may require the PPS lock/unlock sequence.

# 21.9 Register Summary: Peripheral Pin Select Module

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x01FF										
0x0200	PPSLOCK	7:0								PPSLOCKED
0x0201	RA0PPS	7:0					RA0PPS[6:0]			
0x0202	RA1PPS	7:0					RA1PPS[6:0]			
0x0203	RA2PPS	7:0					RA2PPS[6:0]			
0x0204	RA3PPS	7:0					RA3PPS[6:0]			
0x0205	RA4PPS	7:0					RA4PPS[6:0]			
0x0206	RA5PPS	7:0					RA5PPS[6:0]			
0x0207	RA6PPS	7:0					RA6PPS[6:0]			
0x0208 0x0209	RA7PPS RB0PPS	7:0 7:0					RA7PPS[6:0]			
0x0209 0x020A	RB1PPS	7:0					RB0PPS[6:0] RB1PPS[6:0]			
0x020A 0x020B	RB2PPS	7:0					RB2PPS[6:0]			
0x020B	RB3PPS	7:0					RB3PPS[6:0]			
0x020C	RB4PPS	7:0					RB4PPS[6:0]			
0x020E	RB5PPS	7:0					RB5PPS[6:0]			
0x020E	RB6PPS	7:0					RB6PPS[6:0]			
0x0210	RB7PPS	7:0					RB7PPS[6:0]			
0x0211	RC0PPS	7:0					RC0PPS[6:0]			
0x0212	RC1PPS	7:0					RC1PPS[6:0]			
0x0213	RC2PPS	7:0					RC2PPS[6:0]			
0x0214	RC3PPS	7:0					RC3PPS[6:0]			
0x0215	RC4PPS	7:0					RC4PPS[6:0]			
0x0216	RC5PPS	7:0					RC5PPS[6:0]			
0x0217	RC6PPS	7:0					RC6PPS[6:0]			
0x0218	RC7PPS	7:0					RC7PPS[6:0]			
0x0219	RD0PPS	7:0					RD0PPS[6:0]			
0x021A	RD1PPS	7:0					RD1PPS[6:0]			
0x021B	RD2PPS	7:0					RD2PPS[6:0]			
0x021C	RD3PPS	7:0					RD3PPS[6:0]			
0x021D	RD4PPS	7:0					RD4PPS[6:0]			
0x021E	RD5PPS	7:0					RD5PPS[6:0]			
0x021F	RD6PPS	7:0					RD6PPS[6:0]			
0x0220	RD7PPS	7:0					RD7PPS[6:0]			
0x0221	RE0PPS	7:0					RE0PPS[6:0]			
0x0222	RE1PPS	7:0					RE1PPS[6:0]			
0x0223	RE2PPS	7:0					RE2PPS[6:0]			
0x0224										
	Reserved									
0x0228							DESCRIPTION OF			
0x0229	RF0PPS	7:0					RF0PPS[6:0]			
0x022A	RF1PPS	7:0					RF1PPS[6:0]			
0x022B	RF2PPS RF3PPS	7:0					RF2PPS[6:0]			
0x022C	RF3PPS RF4PPS	7:0 7:0					RF3PPS[6:0]			
0x022D 0x022E	RF5PPS						RF4PPS[6:0]			
0x022E 0x022F	RF6PPS	7:0 7:0					RF5PPS[6:0] RF6PPS[6:0]			
0x022F 0x0230	RF7PPS	7:0					RF7PPS[6:0]			
0x0230	MITTO	7.0					111 /FF3[0.0]			
	Reserved									
0x023C	r Cool veu									
0x023D	CANRXPPS	7:0				PORT[2:0]			PIN[2:0]	
0x023E	INTOPPS	7:0				[2.0]	PORT		PIN[2:0]	
0x023F	INT1PPS	7:0				POR	T[1:0]		PIN[2:0]	
00201						. 510			[2.0]	

# **PPS - Peripheral Pin Select Module**

cont	continued									
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
				Ů						
0x0240 0x0241	INT2PPS T0CKIPPS	7:0 7:0				PORT[2:0] PORT[2:0]			PIN[2:0]	
0x0241	T1CKIPPS	7:0				PORT[2:0]			PIN[2:0] PIN[2:0]	
0x0242	T1GPPS	7:0					T[1:0]		PIN[2:0]	
0x0244	T3CKIPPS	7:0				PORT[2:0]	1[1.0]		PIN[2:0]	
0x0245	T3GPPS	7:0					T[1:0]		PIN[2:0]	
0x0246	T5CKIPPS	7:0				PORT[2:0]			PIN[2:0]	
0x0247	T5GPPS	7:0					T[1:0]		PIN[2:0]	
0x0248	T2INPPS	7:0					T[1:0]		PIN[2:0]	
0x0249	T4INPPS	7:0					T[1:0]		PIN[2:0]	
0x024A	T6INPPS	7:0				POR'	T[1:0]		PIN[2:0]	
0x024B										
	Reserved									
0x024C										
0x024D	TUIN0PPS	7:0				PORT[2:0]			PIN[2:0]	
0x024E	TUIN1PPS	7:0				PORT[2:0]			PIN[2:0]	
0x024F	CCP1PPS	7:0				PORT[2:0]			PIN[2:0]	
0x0250	CCP2PPS	7:0				PORT[2:0]			PIN[2:0]	
0x0251	CCP3PPS	7:0				POR	T[1:0]		PIN[2:0]	
0x0252	Reserved									
0x0253	PWM1ERSPPS	7:0					T[1:0]		PIN[2:0]	
0x0254	PWM2ERSPPS	7:0				PORT[2:0]	Tr4 01		PIN[2:0]	
0x0255	PWM3ERSPPS	7:0					T[1:0]		PIN[2:0]	
0x0256	PWM4ERSPPS	7:0				PORT[2:0]			PIN[2:0]	
0x0257	PWMIN0PPS	7:0				PORT[2:0]			PIN[2:0]	
0x0258 0x0259	PWMIN1PPS SMT1WINPPS	7:0 7:0				PORT[2:0]			PIN[2:0]	
0x0259 0x025A	SMT1SIGPPS	7:0				PORT[2:0]			PIN[2:0]	
0x025A 0x025B	CWG1PPS	7:0				PORT[2:0]	T[1:0]		PIN[2:0]	
0x025B	CWG1PPS CWG2PPS	7:0					T[1:0]		PIN[2:0] PIN[2:0]	
0x025D	CWG2PPS CWG3PPS	7:0					T[1:0]		PIN[2:0]	
0x025E	MD1CARLPPS	7:0					T[1:0]		PIN[2:0]	
0x025E	MD1CARHPPS	7:0					T[1:0]		PIN[2:0]	
0x0260	MD1SRCPPS	7:0					T[1:0]		PIN[2:0]	
0x0261	CLCIN0PPS	7:0					T[1:0]		PIN[2:0]	
0x0262	CLCIN1PPS	7:0					T[1:0]		PIN[2:0]	
0x0263	CLCIN2PPS	7:0					T[1:0]		PIN[2:0]	
0x0264	CLCIN3PPS	7:0				POR'	T[1:0]		PIN[2:0]	
0x0265	CLCIN4PPS	7:0				POR	T[1:0]		PIN[2:0]	
0x0266	CLCIN5PPS	7:0				POR'	T[1:0]		PIN[2:0]	
0x0267	CLCIN6PPS	7:0					T[1:0]		PIN[2:0]	
0x0268	CLCIN7PPS	7:0					T[1:0]		PIN[2:0]	
0x0269	ADACTPPS	7:0					T[1:0]		PIN[2:0]	
0x026A	SPI1SCKPPS	7:0					T[1:0]		PIN[2:0]	
0x026B	SPI1SDIPPS	7:0					T[1:0]		PIN[2:0]	
0x026C	SPI1SSPPS	7:0					T[1:0]		PIN[2:0]	
0x026D	SPI2SCKPPS	7:0					T[1:0]		PIN[2:0]	
0x026E	SPI2SDIPPS	7:0					T[1:0]		PIN[2:0]	
0x026F	SPI2SSPPS	7:0					T[1:0]		PIN[2:0]	
0x0270	I2C1SDAPPS	7:0					T[1:0]		PIN[2:0]	
0x0271	I2C1SCLPPS	7:0					T[1:0]		PIN[2:0]	
0x0272	U1RXPPS	7:0				PORT[2:0]			PIN[2:0]	
0x0273	U1CTSPPS	7:0				PORT[2:0]	T[4,0]		PIN[2:0]	
0x0274 0x0275	U2RXPPS U2CTSPPS	7:0 7:0					T[1:0]		PIN[2:0]	
0x0275	U3RXPPS	7:0				PORT[2:0]	T[1:0]		PIN[2:0] PIN[2:0]	
0x0276	U3CTSPPS	7:0				PORT[2:0]			PIN[2:0] PIN[2:0]	
0x0277	U4RXPPS	7:0					T[1:0]		PIN[2:0] PIN[2:0]	
0x0278	U4CTSPPS	7:0					T[1:0]		PIN[2:0]	
UNULIS	04010110	1.0				1 010	. []		1 114[2.0]	


# **PPS - Peripheral Pin Select Module**

cont	inued									
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x027A	U5RXPPS	7:0			PORT[2:0] PIN[2:0]					
0x027B	U5CTSPPS	7:0				PORT[2:0]			PIN[2:0]	

#### **CANRXPPS** 21.9.1

Name: **CANRXPPS** Offset: 0x23D

CAN FD Receive PPS Register



Bits 5:3 - PORT[2:0] CANRX Input PORT Selection bits

Bits 2:0 - PIN[2:0] ADACT Input PORT Pin Selection bits

## 22. CLC - Configurable Logic Cell

The Configurable Logic Cell (CLC) module provides programmable logic that operates outside the speed limitations of software execution. The logic cell takes up to 256 input signals and, through the use of configurable gates, reduces those inputs to four logic lines that drive one of eight selectable single-output logic functions.

Input sources are a combination of the following:


- I/O pins
- · Internal clocks
- Peripherals
- · Register bits

The output can be directed internally to peripherals and to an output pin.

The following figure is a simplified diagram showing signal flow through the CLC. Possible configurations include:

- · Combinatorial Logic
  - AND
  - NAND
  - AND-OR
  - AND-OR-INVERT
  - OR-XOR
  - OR-XNOR
- Latches
  - SR
  - Clocked D with Set and Reset
  - Transparent D with Set and Reset

Figure 22-1. CLC Simplified Block Diagram



#### Notes:

- 1. See Figure 22-2 for input data selection and gating.
- 2. See Figure 22-3 for programmable logic functions.

## 22.1 CLC Setup

Programming the CLC module is performed by configuring the four stages in the logic signal flow. The four stages are:

- · Data selection
- · Data gating
- · Logic function selection
- · Output polarity

Each stage is set up at run time by writing to the corresponding CLC Special Function Registers. This has the added advantage of permitting logic reconfiguration on-the-fly during program execution.

#### 22.1.1 Data Selection

Data inputs are selected with CLCnSEL0 through CLCnSEL3 registers.



**Important:** Data selections are undefined at power-up.

Depending on the number of bits implemented in the CLCnSELy registers, there can be as many as 256 sources available as inputs to the configurable logic. Four multiplexers are used to independently select these inputs to pass on to the next stage as indicated on the left side of the following diagram.

Data inputs in the figure are identified by a generic numbered input name.




Figure 22-2. Input Data Selection and Gating

Note: All controls are undefined at power-up

The CLC Input Selection table correlates the generic input name to the actual signal for each CLC module. The table column labeled 'DyS Value' indicates the MUX selection code for the selected data input. DyS is an abbreviation for the MUX select input codes, D1S through D4S, where 'y' is the gate number.

### 22.1.2 Data Gating

Outputs from the input multiplexers are directed to the desired logic function input through the data gating stage. Each data gate can direct any combination of the four selected inputs.

The gate stage is more than just signal direction. The gate can be configured to direct each input signal as inverted or noninverted data. Directed signals are ANDed together in each gate. The output of each gate can be inverted before going on to the logic function stage.

The gating is in essence a 1-to-4 input AND/NAND/OR/ NOR gate. When every input is inverted and the output is inverted, the gate is an AND of all enabled data inputs. When the inputs and output are not inverted, the gate is an OR or all enabled inputs.

Table 22-1 summarizes the basic logic that can be obtained in gate 1 by using the gate logic select bits. The table shows the logic of four input variables, but each gate can be configured to use less than four. If no inputs are selected, the output will be '0' or '1', depending on the gate output polarity bit.

Table 22-1. Data Gating Logic

CLCnGLSy	GyPOL	Gate Logic
0x55	1	AND
0x55	0	NAND
0xAA	1	NOR
0xAA	0	OR
0x00	0	Logic 0
0x00	1	Logic 1

It is possible (but not recommended) to select both the true and negated values of an input. When this is done, the gate output is '0', regardless of the other inputs, but may emit logic glitches (transient-induced pulses). If the output of the channel must be '0' or '1', the recommended method is to set all gate bits to '0' and use the gate polarity bit to set the desired level.

Data gating is configured with the logic gate select registers as follows:

Gate 1: CLCnGLS0Gate 2: CLCnGLS1Gate 3: CLCnGLS2Gate 4: CLCnGLS3

**Note:** Register number suffixes are different than the gate numbers because other variations of this module have multiple gate selections in the same register.

Data gating is indicated in the right side of Figure 22-2. Only one gate is shown in detail. The remaining three gates are configured identically with the exception that the data enables correspond to the enables for that gate.

#### 22.1.3 Logic Function


There are eight available logic functions including:

- AND-OR
- OR-XOR
- AND
- SR Latch
- · D Flip-Flop with Set and Reset
- · D Flip-Flop with Reset
- · J-K Flip-Flop with Reset
- · Transparent Latch with Set and Reset

Logic functions are shown in the following diagram. Each logic function has four inputs and one output. The four inputs are the four data gate outputs of the previous stage. The output is fed to the inversion stage and from there to other peripherals, an output pin, and back to the CLC itself.

Figure 22-3. Programmable Logic Functions

Rev. 10-000122B 9/13/2016



### 22.1.4 Output Polarity

The last stage in the Configurable Logic Cell is the output polarity. Setting the POL bit inverts the output signal from the logic stage. Changing the polarity while the interrupts are enabled will cause an interrupt for the resulting output transition.

## 22.2 CLC Interrupts

An interrupt will be generated upon a change in the output value of the CLCx when the appropriate interrupt enables are set. A rising edge detector and a falling edge detector are present in each CLC for this purpose.

The CLCxIF bit of the associated PIR register will be set when either edge detector is triggered and its associated enable bit is set. The INTP bit enables rising edge interrupts and the INTN bit enables falling edge interrupts.

To fully enable the interrupt, set the following bits:

- · CLCxIE bit of the respective PIE register
- INTP bit (for a rising edge detection)
- · INTN bit (for a falling edge detection)

#### If priority interrupts are not used:

- 1. Clear the IPEN bit of the INTCON register.
- 2. Set the GIE bit of the INTCON register.
- Set the GIEL bit of the INTCON register.

#### If the CLC is a high priority interrupt:

- 1. Set the IPEN bit of the INTCON register.
- 2. Set the CLCxIP bit of the respective IPR register.
- 3. Set the GIEH bit of the INTCON register.

#### If the CLC is a low priority interrupt:

- 1. Set the IPEN bit of the INTCON register.
- 2. Clear the CLCxIP bit of the respective IPR register.
- Set the GIEL bit of the INTCON register.

The CLCxIF bit of the respective PIR register must be cleared in software as part of the interrupt service. If another edge is detected while this flag is being cleared, the flag will still be set at the end of the sequence.

#### 22.3 Effects of a Reset

The CLCnCON register is cleared to '0' as the result of a Reset. All other selection and gating values remain unchanged.

## 22.4 Output Mirror Copies

Mirror copies of all CLCxOUT bits are contained in the CLCDATA register. Reading this register reads the outputs of all CLCs simultaneously. This prevents any reading skew introduced by testing or reading the OUT bits in the individual CLCnCON registers.

## 22.5 Operation During Sleep

The CLC module operates independently from the system clock and will continue to run during Sleep, provided that the input sources selected remain active.

The HFINTOSC remains active during Sleep when the CLC module is enabled and the HFINTOSC is selected as an input source, regardless of the system clock source selected.

In other words, if the HFINTOSC is simultaneously selected as both the system clock and as a CLC input source then, when the CLC is enabled, the CPU will go idle during Sleep, but the CLC will continue to operate and the HFINTOSC will remain active. This will have a direct effect on the Sleep mode current.

## 22.6 CLC Setup Steps

The following steps should be followed when setting up the CLC:

- 1. Disable CLC by clearing the EN bit.
- 2. Select desired inputs using the CLCnSEL0 through CLCnSEL3 registers.
- 3. Clear any ANSEL bits associated with CLC input pins.
- 4. Set all TRIS bits associated with inputs. However, a CLC input will also operate if the pin is configured as an output, in which case the TRIS bits should be cleared.

## **CLC - Configurable Logic Cell**

- 5. Enable the chosen inputs through the four gates using the CLCnGLS0 through CLCnGLS3 registers.
- 6. Select the gate output polarities with the GyPOL bits.
- 7. Select the desired logic function with the MODE bits.
- 8. Select the desired polarity of the logic output with the POL bit. (This step may be combined with the previous gate output polarity step).
- 9. If driving a device pin, configure the associated pin PPS control register and also clear the TRIS bit corresponding to that output.
- 10. Configure the interrupts (optional). See CLC Interrupts.
- 11. Enable the CLC by setting the EN bit.

## 22.7 Register Overlay

All CLCs in this device share the same set of registers. Only one CLC instance is accessible at a time. The value in the CLCSELECT register is one less than the selected CLC instance. For example, a CLCSELECT value of 0 selects CLC1.

## 22.8 Register Definitions: Configurable Logic Cell

**CLC - Configurable Logic Cell** 

#### 22.8.1 CLCSELECT

Name: CLCSELECT Offset: 0x0D5

**CLC Instance Selection Register** 

Selects which CLC instance is accessed by the CLC registers



Bits 2:0 - SLCT[2:0] CLC instance selection

Value	Description
n	Shared CLC registers of instance n+1 are selected for read and write operations.

#### 22.8.2 CLCnCON

Name: CLCnCON Offset: 0x0D6

Configurable Logic Cell Control Register

Bit	7	6	5	4	3	2	1	0
	EN		OUT	INTP	INTN	MODE[2:0]		
Access	R/W		R	R/W	R/W	R/W	R/W	R/W
Reset	0		0	0	0	0	0	0

#### Bit 7 - EN CLC Enable

Value	Description
1	Configurable logic cell is enabled and mixing signals
0	Configurable logic cell is disabled and has logic zero output

Bit 5 - OUT Logic cell output data, after LCPOL. Sampled from CLCxOUT

## Bit 4 - INTP Configurable Logic Cell Positive Edge Going Interrupt Enable

Value	Description
1	CLCxIF will be set when a rising edge occurs on CLCxOUT
0	Rising edges on CLCxOUT have no effect on CLCxIF

## Bit 3 – INTN Configurable Logic Cell Negative Edge Going Interrupt Enable

Value	Description
1	CLCxIF will be set when a falling edge occurs on CLCxOUT
0	Falling edges on CLCxOUT have no effect on CLCxIF

#### Bits 2:0 - MODE[2:0] Configurable Logic Cell Functional Mode Selection

Value	Description
111	Cell is 1-input transparent latch with Set and Reset
110	Cell is J-K flip-flop with Reset
101	Cell is 2-input D flip-flop with Reset
100	Cell is 1-input D flip-flop with Set and Reset
011	Cell is SR latch
010	Cell is 4-input AND
001	Cell is OR-XOR
000	Cell is AND-OR

## 22.8.3 CLCnPOL

Name: CLCnPOL Offset: 0x0D7

Signal Polarity Control Register

Bit	7	6	5	4	3	2	1	0
	POL				G4POL	G3POL	G2POL	G1POL
Access	R/W				R/W	R/W	R/W	R/W
Reset	0				X	X	X	X

Bit 7 - POL CLCxOUT Output Polarity Control

Value	Description
1	The output of the logic cell is inverted
0	The output of the logic cell is not inverted

Bits 0, 1, 2, 3 - GyPOL Gate Output Polarity Control

Reset States: POR/BOR = xxxx

Value	Description
1	The gate output is inverted when applied to the logic cell
0	The output of the gate is not inverted

#### 22.8.4 CLCnSEL0

Name: CLCnSEL0 Offset: 0x0D8

Generic CLCn Data 1 Select Register



Bits 7:0 - D1S[7:0] CLCn Data1 Input Selection

## Table 22-2. CLC Input Selection

DyS	Input Source	DyS (cont.)	Input Source (cont.)	DyS (cont.)	Input Source (cont.)
<b>[0]</b> 0000 0000	CLCIN0PPS	<b>[32]</b> 0010 0000	CCP2	<b>[64]</b> 0100 0000	SPI1_SDO
[1] 0000 0001	CLCIN1PPS	[33] 0010 0001	CCP3	<b>[65]</b> 0100 0001	SPI1_SCK
[2] 0000 0010	CLCIN2PPS	[34] 0010 0010	PWM1S1P1_OUT	<b>[66]</b> 0100 0010	SPI1_SS
[3] 0000 0011	CLCIN3PPS	<b>[35]</b> 0010 0011	PWM1S1P2_OUT	[67] 0100 0011	SPI2_SDO
[4] 0000 0100	CLCIN4PPS	[36] 0010 0100	PWM2S1P1_OUT	<b>[68]</b> 0100 0100	SPI2_SCK
<b>[5]</b> 0000 0101	CLCIN5PPS	[37] 0010 0101	PWM2S1P2_OUT	<b>[69]</b> 0100 0101	SPI2_SS
<b>[6]</b> 0000 0110	CLCIN6PPS	[38] 0010 0110	PWM3S1P1_OUT	<b>[70]</b> 0100 0110	I <sup>2</sup> C_SCL
[7] 0000 0111	CLCIN7PPS	<b>[39]</b> 0010 0111	PWM3S1P2_OUT	<b>[71]</b> 0100 0111	I <sup>2</sup> C_SDA
[8] 0000 1000	Fosc	<b>[40]</b> 0010 1000	PWM4S1P1_OUT	<b>[72]</b> 0100 1000	CWG1A
[9] 0000 1001	HFINTOSC(1)	<b>[41]</b> 0010 1001	PWM4S1P2_OUT	<b>[73]</b> 0100 1001	CWG1B
[10] 0000 1010	LFINTOSC(1)	<b>[42]</b> 0010 1010	NCO1	<b>[74]</b> 0100 1010	CWG2A
[11] 0000 1011	MFINTOSC(1)	<b>[43]</b> 0010 1011	NCO2	<b>[75]</b> 0100 1011	CWG2B
<b>[12]</b> 0000 1100	MFINTOSC (32 kHz)(1)	<b>[44]</b> 0010 1100	NCO3	<b>[76]</b> 0100 1100	CWG3A
<b>[13]</b> 0000 1101	SFINTOSC (1 MHz)(1)	<b>[45]</b> 0010 1101	CMP1_OUT	[77] 0100 1101	CWG3B
<b>[14]</b> 0000 1110	SOSC(1)	<b>[46]</b> 0010 1110	CMP2_OUT		_
<b>[15]</b> 0000 1111	EXTOSC(1)	<b>[47]</b> 0010 1111	ZCD		_
<b>[16]</b> 0001 0000	ADCRC(1)	<b>[48]</b> 0011 0000	IOC		_
[17] 0001 0001	CLKR	<b>[49]</b> 0011 0001	DSM1		_
[18] 0001 0010	TMR0	<b>[50]</b> 0011 0010	HLVD_OUT		_
<b>[19]</b> 0001 0011	TMR1	<b>[51]</b> 0011 0011	CLC1		_
[20] 0001 0100	TMR2	<b>[52]</b> 0011 0100	CLC2		_
<b>[21]</b> 0001 0101	TMR3	<b>[53]</b> 0011 0101	CLC3		_
<b>[22]</b> 0001 0110	TMR4	<b>[54]</b> 0011 0110	CLC4		_
<b>[23]</b> 0001 0111	TMR5	<b>[55]</b> 0011 0111	CLC5		_
<b>[24]</b> 0001 1000	TMR6	<b>[56]</b> 0011 1000	CLC6		_
<b>[25]</b> 0001 1001	TU16A	<b>[57]</b> 0011 1001	CLC7		_
<b>[26]</b> 0001 1010	TU16B	<b>[58]</b> 0011 1010	CLC8		_
[27] 0001 1011	_	<b>[59]</b> 0011 1011	U1TX		_
[28] 0001 1100	_	<b>[60]</b> 0011 1100	U2TX		_
[29] 0001 1101	_	<b>[61]</b> 0011 1101	U3TX		_
[30] 0001 1110	SMT1	<b>[62]</b> 0011 1110	U4TX		_
<b>[31]</b> 0001 1111	CCP1	<b>[63]</b> 0011 1111	U5TX	<b>[127]</b> 0111 1111	_
Note:					

Requests clock.

**CLC - Configurable Logic Cell** 

Reset States: POR/BOR = xxxxxxxx

**CLC - Configurable Logic Cell** 

## 22.8.5 CLCnSEL1

Name: CLCnSEL1 Offset: 0x0D9

Generic CLCn Data 1 Select Register

Bit	7	6	5	4	3	2	1	0
	D2S[7:0]							
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	X	X	X	X	X	X	X	X

Bits 7:0 - D2S[7:0] CLCn Data2 Input Selection

Reset States: POR/BOR = xxxxxxxx

	7 III 9 II 10 I 10 I 10 I 10 I 10 I 10 I
Value	Description
n	Refer to the CLC Input Selection table for input selections.

**CLC - Configurable Logic Cell** 

## 22.8.6 CLCnSEL2

Name: CLCnSEL2 Offset: 0x0DA

Generic CLCn Data 1 Select Register

Bit	7	6	5	4	3	2	1	0		
	D3S[7:0]									
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	X	X	X	X	X	X	X	X		

Bits 7:0 - D3S[7:0] CLCn Data3 Input Selection

Reset States: POR/BOR = xxxxxxxx

All Other Resets = uuuuuuuu

	· · · · · · · · · · · · · · · · · · ·
Value	Description
n	Refer to the CLC Input Selection table for input selections.

**CLC - Configurable Logic Cell** 

#### 22.8.7 CLCnSEL3

Name: CLCnSEL3 Offset: 0x0DB

Generic CLCn Data 4 Select Register

Bit	7	6	5	4	3	2	1	0		
	D4S[7:0]									
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	X	X	X	X	X	X	X	X		

Bits 7:0 - D4S[7:0] CLCn Data4 Input Selection

Reset States: POR/BOR = xxxxxxxx

All Other Resets = uuuuuuuu

	· · · · · · · · · · · · · · · · · · ·
Value	Description
n	Refer to the CLC Input Selection table for input selections.

#### 22.8.8 CLCnGLS0

Name: CLCnGLS0 Offset: 0x0DC

CLCn Gate1 Logic Select Register

Bit	7	6	5	4	3	2	1	0
	G1D4T	G1D4N	G1D3T	G1D3N	G1D2T	G1D2N	G1D1T	G1D1N
Access	R/W							
Reset	X	X	X	X	X	X	X	X

## Bits 1, 3, 5, 7 – G1DyT dyT: Gate1 Data 'y' True (noninverted)

Reset States: POR/BOR = xxxx

All Other Resets = uuuu

Value	Description
1	dyT is gated into g1
0	dyT is not gated into g1

## Bits 0, 2, 4, 6 - G1DyN dyN: Gate1 Data 'y' Negated (inverted)

Reset States: POR/BOR = xxxx

Value	Description
1	dyN is gated into g1
0	dyN is not gated into g1

#### 22.8.9 CLCnGLS1

Name: CLCnGLS1 Offset: 0x0DD

CLCn Gate2 Logic Select Register

Bit	7	6	5	4	3	2	1	0
	G2D4T	G2D4N	G2D3T	G2D3N	G2D2T	G2D2N	G2D1T	G2D1N
Access	R/W							
Reset	X	X	X	X	X	X	X	X

## Bits 1, 3, 5, 7 – G2DyT dyT: Gate2 Data 'y' True (noninverted)

Reset States: POR/BOR = xxxx

All Other Resets = uuuu

Value	Description
1	dyT is gated into g2
0	dyT is not gated into g2

## Bits 0, 2, 4, 6 - G2DyN dyN: Gate2 Data 'y' Negated (inverted)

Reset States: POR/BOR = xxxx

Value	Description
1	dyN is gated into g2
0	dyN is not gated into g2

#### 22.8.10 CLCnGLS2

Name: CLCnGLS2 Offset: 0x0DE

CLCn Gate3 Logic Select Register

Bit	7	6	5	4	3	2	1	0
	G3D4T	G3D4N	G3D3T	G3D3N	G3D2T	G3D2N	G3D1T	G3D1N
Access	R/W							
Reset	X	X	X	X	X	X	x	x

## Bits 1, 3, 5, 7 – G3DyT dyT: Gate3 Data 'y' True (noninverted)

Reset States: POR/BOR = xxxx

All Other Resets = uuuu

Value	Description
1	dyT is gated into g3
0	dyT is not gated into g3

## Bits 0, 2, 4, 6 - G3DyN dyN: Gate3 Data 'y' Negated (inverted)

Reset States: POR/BOR = xxxx

Value	Description
1	dyN is gated into g3
0	dyN is not gated into g3

#### 22.8.11 CLCnGLS3

Name: CLCnGLS3 Offset: 0x0DF

CLCn Gate4 Logic Select Register

Bit	7	6	5	4	3	2	1	0
	G4D4T	G4D4N	G4D3T	G4D3N	G4D2T	G4D2N	G4D1T	G4D1N
Access	R/W							
Reset	X	X	X	X	X	X	X	X

## Bits 1, 3, 5, 7 - G4DyT dyT: Gate4 Data 'y' True (noninverted)

Reset States: POR/BOR = xxxx

All Other Resets = uuuu

Value	Description
1	dyT is gated into g4
0	dyT is not gated into g4

## Bits 0, 2, 4, 6 - G4DyN dyN: Gate4 Data 'y' Negated (inverted)

Reset States: POR/BOR = xxxx

Value	Description
1	dyN is gated into g4
0	dyN is not gated into g4

## 22.8.12 CLCDATA

Name: CLCDATA Offset: 0x0D4

**CLC Data Output Register** 

Mirror copy of CLC outputs

Bit	7	6	5	4	3	2	1	0
	CLC8OUT	CLC7OUT	CLC6OUT	CLC5OUT	CLC4OUT	CLC3OUT	CLC2OUT	CLC1OUT
Access	R/W							
Reset	0	0	0	0	0	0	0	0

Bits 0, 1, 2, 3, 4, 5, 6, 7 - CLCxOUT Mirror copy of CLCx\_out

V	/alue	Description
1		CLCx_out is 1
C		CLCx_out is 0

# 22.9 Register Summary - CLC Control

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00  0xD3	Reserved									
0xD4	CLCDATA	7:0	CLC8OUT	CLC7OUT	CLC6OUT	CLC5OUT	CLC4OUT	CLC3OUT	CLC2OUT	CLC10UT
0xD5	CLCSELECT	7:0							SLCT[2:0]	
0xD6	CLCnCON	7:0	EN		OUT	INTP	INTN		MODE[2:0]	
0xD7	CLCnPOL	7:0	POL				G4POL	G3POL	G2POL	G1POL
0xD8	CLCnSEL0	7:0			•	D1S	[7:0]			
0xD9	CLCnSEL1	7:0				D2S	[7:0]			
0xDA	CLCnSEL2	7:0				D3S	[7:0]			
0xDB	CLCnSEL3	7:0				D4S	[7:0]			
0xDC	CLCnGLS0	7:0	G1D4T	G1D4N	G1D3T	G1D3N	G1D2T	G1D2N	G1D1T	G1D1N
0xDD	CLCnGLS1	7:0	G2D4T	G2D4N	G2D3T	G2D3N	G2D2T	G2D2N	G2D1T	G2D1N
0xDE	CLCnGLS2	7:0	G3D4T	G3D4N	G3D3T	G3D3N	G3D2T	G3D2N	G3D1T	G3D1N
0xDF	CLCnGLS3	7:0	G4D4T	G4D4N	G4D3T	G4D3N	G4D2T	G4D2N	G4D1T	G4D1N

## 23. CLKREF - Reference Clock Output Module

The reference clock output module provides the ability to send a clock signal to the clock reference output pin (CLKR). The reference clock output can be routed internally as an input signal for other peripherals, such as the timers and CLCs.

The reference clock output module has the following features:

- · Selectable clock source using the CLKRCLK register
- · Programmable clock divider
- · Selectable duty cycle

The figure below shows the simplified block diagram of the clock reference module.

Figure 23-1. Clock Reference Block Diagram





Figure 23-2. Clock Reference Timing



## 23.1 Clock Source

The clock source of the reference clock peripheral is selected with the CLK bits.

## 23.1.1 Clock Synchronization

The CLKR output signal is ensured to be glitch-free when the EN bit is set to start the module and enable the CLKR output. When the reference clock output is disabled, the output signal will be disabled immediately.

## 23.2 Programmable Clock Divider

The module takes the clock input and divides it based on the value of the DIV bits.

The following configurations are available:

- · Base clock frequency value
- · Base clock frequency divided by 2
- · Base clock frequency divided by 4
- · Base clock frequency divided by 8
- · Base clock frequency divided by 16
- · Base clock frequency divided by 32
- · Base clock frequency divided by 64
- · Base clock frequency divided by 128

## 23.3 Selectable Duty Cycle

The DC bits are used to modify the duty cycle of the output clock. A duty cycle of 0%, 25%, 50%, or 75% can be selected for all clock rates when the DIV value is not 0b000. When DIV = 0b000 the duty cycle defaults to 50% for all values of DC except 0b00, in which case the duty cycle is 0% (constant low output).



**Important:** The DC value at Reset is 10. This makes the default duty cycle 50% and not 0%.



**Important:** Clock dividers and clock duty cycles can be changed while the module is enabled but doing so may cause glitches to occur on the output. To avoid possible glitches, clock dividers and clock duty cycles should be changed only when the EN bit is clear.

## 23.4 Operation in Sleep Mode

The reference clock module continues to operate and provide a signal output in Sleep for all clock source selections except  $F_{OSC}$  (CLK = 0).

## 23.5 Register Definitions: Reference Clock

Long bit name prefixes for the Reference Clock peripherals are shown in the following table. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 23-1.

Peripheral	Bit Name Prefix
CLKR	CLKR

#### 23.5.1 CLKRCON

Name: CLKRCON Offset: 0x039

Reference Clock Control Register

Bit	7	6	5	4	3	2	1	0
	EN			DC[	1:0]		DIV[2:0]	
Access	R/W			R/W	R/W	R/W	R/W	R/W
Reset	0			1	0	0	0	0

#### Bit 7 - EN Reference Clock Module Enable

Value	Description
1	Reference clock module enabled
0	Reference clock module is disabled

## Bits 4:3 - DC[1:0] Reference Clock Duty Cycle<sup>(1)</sup>

Value	Description
11	Clock outputs duty cycle of 75%
10	Clock outputs duty cycle of 50%
01	Clock outputs duty cycle of 25%
00	Clock outputs duty cycle of 0%

## Bits 2:0 - DIV[2:0] Reference Clock Divider

Value	Description
111	Base clock value divided by 128
110	Base clock value divided by 64
101	Base clock value divided by 32
100	Base clock value divided by 16
011	Base clock value divided by 8
010	Base clock value divided by 4
001	Base clock value divided by 2
000	Base clock value


#### Note:

1. Bits are valid for DIV  $\ge$  001. For DIV = 000, duty cycle is fixed at 50%.

# 23.5.2 CLKRCLK

Name: CLKRCLK Offset: 0x03A

Clock Reference Clock Selection Register



Bits 4:0 - CLK[4:0] CLKR Clock Selection

#### Table 23-2. Clock Reference Module Clock Sources

CLK	Clock Source
11111-10010	Reserved
10001	CLC8_OUT
10000	CLC7_OUT
01111	CLC6_OUT
01110	CLC5_OUT
01101	CLC4_OUT
01100	CLC3_OUT
01011	CLC2_OUT
01010	CLC1_OUT
01001	NCO3_OUT
01000	NCO2_OUT
00111	NCO1_OUT
00110	EXTOSC
00101	SOSC
00100	MFINTOSC (32 kHz)
00011	MFINTOSC (500 kHz)
00010	LFINTOSC
00001	HFINTOSC
00000	Fosc

# 23.6 Register Summary: Reference CLK


Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x38										
0x39	CLKRCON	7:0	EN			DC	1:0]		DIV[2:0]	
0x3A	CLKRCLK	7:0				CLK[4:0]				


#### 24. TMR0 - Timer0 Module


The Timer0 module has the following features:

- 8-bit timer with programmable period
- 16-bit timer
- Selectable clock sources
- Synchronous and asynchronous operation
- Programmable prescaler (Independent of Watchdog Timer)
- Programmable postscaler
- Interrupt on match or overflow
- Output on I/O pin (via PPS) or to other peripherals
- Operation during Sleep

Figure 24-1. Timer0 Block Diagram







#### 24.1 **Timer0 Operation**

Timer0 can operate as either an 8-bit or 16-bit timer. The mode is selected with the MD16 bit.

#### 24.1.1 8-Bit Mode

In this mode Timer0 increments on the rising edge of the selected clock source. A prescaler on the clock input gives several prescale options (see prescaler control bits, CKPS). In this mode, as shown in Figure 24-1, a buffered version of TMR0H is maintained.

This is compared with the value of TMR0L on each cycle of the selected clock source. When the two values match, the following events occur:

- · TMR0L is reset
- The contents of TMR0H are copied to the TMR0H buffer for next comparison

#### 24.1.2 16-Bit Mode

In this mode Timer0 increments on the rising edge of the selected clock source. A prescaler on the clock input gives several prescale options (see prescaler control bits, CKPS). In this mode TMR0H:TMR0L form the 16-bit timer value. As shown in Figure 24-1, reads and writes of the TMR0H register are buffered. The TMR0H register is updated with the contents of the high byte of Timer0 when the TMR0L register is read. Similarly, writing the TMR0L register causes a transfer of the TMR0H register value to the Timer0 high byte.

This buffering allows all 16 bits of Timer0 to be read and written at the same time. Timer0 rolls over to 0x0000 on incrementing past 0xFFFF. This makes the timer free-running. While actively operating in 16-bit mode, the Timer0 value can be read but not written.

#### 24.2 Clock Selection

Timer0 has several options for clock source selections, the option to operate synchronously/asynchronously and an available programmable prescaler. The CS bits are used to select the clock source for Timer0.

# 24.2.1 Synchronous Mode

When the ASYNC bit is clear, Timer0 clock is synchronized to the system clock ( $F_{OSC}/4$ ). When operating in Synchronous mode, Timer0 clock frequency cannot exceed  $F_{OSC}/4$ . During Sleep mode the system clock is not available and Timer0 cannot operate.

#### 24.2.2 Asynchronous Mode

When the ASYNC bit is set, Timer0 increments with each rising edge of the input source (or output of the prescaler, if used). Asynchronous mode allows Timer0 to continue operation during Sleep mode provided the selected clock source operates during Sleep.

#### 24.2.3 Programmable Prescaler

Timer0 has 16 programmable input prescaler options ranging from 1:1 to 1:32768. The prescaler values are selected using the CKPS bits. The prescaler counter is not directly readable or writable. The prescaler counter is cleared on the following events:

- · A write to the TMR0L register
- A write to either the T0CON0 or T0CON1 registers
- · Any device Reset

# 24.2.4 Programmable Postscaler

Timer0 has 16 programmable output postscaler options ranging from 1:1 to 1:16. The postscaler values are selected using the OUTPS bits. The postscaler divides the output of Timer0 by the selected ratio. The postscaler counter is not directly readable or writable. The postscaler counter is cleared on the following events:

- A write to the TMR0L register
- A write to either the T0CON0 or T0CON1 registers
- Any device Reset

# 24.3 Timer0 Output and Interrupt

# 24.3.1 Timer0 Output

TMR0\_out toggles on every match between TMR0L and TMR0H in 8-bit mode, or when TMR0H:TMR0L rolls over in 16-bit mode. If the output postscaler is used, the output is scaled by the ratio selected. The Timer0 output can be routed to an I/O pin via the RxyPPS output selection register, or internally to a number of Core Independent Peripherals. The Timer0 output can be monitored through software via the OUT output bit.

#### 24.3.2 Timer0 Interrupt

The Timer0 Interrupt Flag bit (TMR0IF) is set when the TMR0\_out toggles. If the Timer0 interrupt is enabled (TMR0IE), the CPU will be interrupted when the TMR0IF bit is set. When the postscaler bits (T0OUTPS) are set to 1:1 operation (no division), the T0IF flag bit will be set with every TMR0 match or rollover. In general, the TMR0IF flag bit will be set every T0OUTPS +1 matches or rollovers.

#### 24.3.3 Timer0 Example

Timer0 Configuration:

- Timer0 mode = 16-bit
- Clock Source = F<sub>OSC</sub>/4 (250 kHz)
- · Synchronous operation
- Prescaler = 1:1
- Postscaler = 1:2 (T0OUTPS = 1)

In this case the TMR0\_out toggles every two rollovers of TMR0H:TMR0L. i.e.,  $(0xFFFF)^2^*(1/250kHz) = 524.28 \text{ ms}$ 

# 24.4 Operation During Sleep

When operating synchronously, Timer0 will halt when the device enters Sleep mode. When operating asynchronously and the selected clock source is active, Timer0 will continue to increment and wake the device from Sleep mode if the Timer0 interrupt is enabled.

# 24.5 Register Definitions: Timer0 Control

#### 24.5.1 T0CON0

Name: T0CON0 Offset: 0x31A

Timer0 Control Register 0

Bit	7	6	5	4	3	2	1	0
	EN		OUT	MD16		OUTP	S[3:0]	
Access	R/W		R	R/W	R/W	R/W	R/W	R/W
Reset	0		0	0	0	0	0	0

# Bit 7 - EN TMR0 Enable

Value	Description
1	The module is enabled and operating
0	The module is disabled

#### Bit 5 - OUT TMR0 Output

#### Bit 4 - MD16 16-Bit Timer Operation Select

	in 1 in 10 to 10 th time. Operation colors					
Value	Description					
1	TMR0 is a 16-bit timer					
0	TMR0 is an 8-bit timer					

Bits 3:0 - OUTPS[3:0] TMR0 Output Postscaler (Divider) Select

Value	Description
1111	1:16 Postscaler
1110	1:15 Postscaler
1101	1:14 Postscaler
1100	1:13 Postscaler
1011	1:12 Postscaler
1010	1:11 Postscaler
1001	1:10 Postscaler
1000	1:9 Postscaler
0111	1:8 Postscaler
0110	1:7 Postscaler
0101	1:6 Postscaler
0100	1:5 Postscaler
0011	1:4 Postscaler
0010	1:3 Postscaler
0001	1:2 Postscaler
0000	1:1 Postscaler

#### 24.5.2 T0CON1

Name: T0CON1 Offset: 0x31B

Timer0 Control Register 1

Bit	7	6	5	4	3	2	1	0
		CS[2:0]		ASYNC		CKPS	S[3:0]	
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:5 - CS[2:0] Timer0 Clock Source Select

Value	Description
111	CLC1_OUT
110	SOSC
101	MFINTOSC (500 kHz)
100	LFINTOSC
011	HFINTOSC
010	F <sub>OSC</sub> /4
001	Pin selected by T0CKIPPS (Inverted)
000	Pin selected by T0CKIPPS (Non-inverted)

Bit 4 - ASYNC TMR0 Input Asynchronization Enable

Value	Description
1	The input to the TMR0 counter is not synchronized to system clocks
0	The input to the TMR0 counter is synchronized to Fosc/4

Bits 3:0 - CKPS[3:0] Prescaler Rate Select

Value	Description
1111	1:32768
1110	1:16384
1101	1:8192
1100	1:4096
1011	1:2048
1010	1:1024
1001	1:512
1000	1:256
0111	1:128
0110	1:64
0101	1:32
0100	1:16
0011	1:8
0010	1:4
0001	1:2
0000	1:1

# PIC18F26/46/56Q84

TMR0 - Timer0 Module

# 24.5.3 TMR0H

Name: TMR0H Offset: 0x319

Timer0 Period/Count High Register

Bit	7	6	5	4	3	2	1	0
				TMR0	H[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

Bits 7:0 - TMR0H[7:0] TMR0 Most Significant Counter

	Valu	е	Condition	Description
ĺ	0 to	255	<b>MD16</b> = 0	8-bit Timer0 Period Value. TMR0L continues counting from 0 when this value is reached.
	0 to	255	MD16 = 1	16-bit Timer0 Most Significant Byte

# PIC18F26/46/56Q84

TMR0 - Timer0 Module

# 24.5.4 TMR0L

Name: TMR0L Offset: 0x318

Timer0 Period/Count Low Register

Bit	7	6	5	4	3	2	1	0	
	TMR0L[7:0]								
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	0	0	0	0	0	0	0	0	

Bits 7:0 - TMR0L[7:0] TMR0 Least Significant Counter

Value	Condition	Description
0 to 255	<b>MD16 =</b> 0	8-bit Timer0 Counter bits
0 to 255	MD16 = 1	16-bit Timer0 Least Significant Byte

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 405

# 24.6 Register Summary: Timer0

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x0317										
0x0318	TMR0L	7:0				TMR	)L[7:0]			
0x0319	TMR0H	7:0		TMR0H[7:0]						
0x031A	T0CON0	7:0	EN OUT MD16 OUTPS[3:0]							
0x031B	T0CON1	7:0	CS[2:0] ASYNC CKPS[3:0]							

# 25. TMR1 - Timer1 Module with Gate Control

The Timer1 module is a 16-bit timer/counter with the following features:


- 16-bit timer/counter register pair (TMRxH:TMRxL)
- · Programmable internal or external clock source
- · 2-bit prescaler
- Clock source for optional comparator synchronization
- · Multiple Timer1 gate (count enable) sources
- Interrupt-on-overflow
- Wake-up on overflow (external clock, Asynchronous mode only)
- · 16-bit read/write operation
- Time base for the capture/compare function with the CCP modules
- Special event trigger (with CCP)
- Selectable gate source polarity
- · Gate Toggle mode
- Gate Single-Pulse mode
- · Gate value status
- · Gate event interrupt



Important: References to the module Timer1 apply to all the odd numbered timers on this device.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 407

Figure 25-1. Timer1 Block Diagram



#### Notes:

- 1. This signal comes from the pin selected by Timer1 PPS register.
- TMRx register increments on rising edge.
- 3. Synchronize does not operate while in Sleep.
- 4. See TxCLK for clock source selections.
- 5. See TxGATE for gate source selections.
- 6. Synchronized comparator output should not be used in conjunction with synchronized input clock.

# 25.1 Timer1 Operation

The Timer1 module is a 16-bit incrementing counter that is accessed through the TMRx register. Writes to TMRx directly update the counter. When used with an internal clock source, the module is a timer that increments on every instruction cycle. When used with an external clock source, the module can be used as either a timer or counter and increments on every selected edge of the external source.

Timer1 is enabled by configuring the ON and GE bits. Table 25-1 displays the possible Timer1 enable selections.

Table 25-1. Timer1 Enable Selections

ON	GE	Timer1 Operation
1	1	Count Enabled
1	0	Always On
0	1	Off
0	0	Off

#### 25.2 Clock Source Selection

The CS bits select the clock source for Timer1. These bits allow the selection of several possible synchronous and asynchronous clock sources.

#### 25.2.1 Internal Clock Source

When the internal clock source is selected the TMRx register will increment on multiples of F<sub>OSC</sub> as determined by the Timer1 prescaler.


When the F<sub>OSC</sub> internal clock source is selected, the TMRx register value will increment by four counts every instruction clock cycle. Due to this condition, a 2 LSB error in resolution will occur when reading the TMRx value. To utilize the full resolution of Timer1, an asynchronous input signal must be used to gate the Timer1 clock input.



**Important:** In Counter mode, a falling edge must be registered by the counter prior to the first incrementing rising edge after any one or more of the following conditions:

- Timer1 enabled after POR
- Write to TMRxH or TMRxL
- · Timer1 is disabled
- Timer1 is disabled (ON = 0) when TxCKI is high then Timer1 is enabled (ON = 1) when TxCKI is low.
   Refer to the figure below.

Figure 25-2. Timer1 Incrementing Edge



#### Notes:

- 1. Arrows indicate counter increments.
- 2. In Counter mode, a falling edge must be registered by the counter prior to the first incrementing rising edge of the clock.

#### 25.2.2 External Clock Source

When the external clock source is selected, the TMRx module may work as a timer or a counter. When enabled to count, Timer1 is incremented on the rising edge of the external clock input of the TxCKIPPS pin. This external clock source can be synchronized to the system clock or it can run asynchronously.

#### 25.3 Timer1 Prescaler

Timer1 has four prescaler options allowing 1, 2, 4 or 8 divisions of the clock input. The CKPS bits control the prescale counter. The prescale counter is not directly readable or writable; however, the prescaler counter is cleared upon a write to TMRx.

# 25.4 Secondary Oscillator

A secondary low-power 32.768 kHz oscillator circuit is built-in between pins SOSCI (input) and SOSCO (amplifier output). This internal circuit is to be used in conjunction with an external 32.768 kHz crystal. The secondary oscillator is not dedicated only to Timer1; it can also be used by other modules.

The oscillator circuit is enabled by setting the SOSCEN bit of the OSCEN register. This can be used as one of the Timer1 clock sources selected with the CS bits. The oscillator will continue to run during Sleep.



**Important:** The oscillator requires a start-up and stabilization time before use. Thus, the SOSCEN bit of the OSCEN register should be set and a suitable delay observed prior to enabling Timer1. A software check can be performed to confirm if the secondary oscillator is enabled and ready to use. This is done by polling the secondary oscillator ready Status bit. Refer to "OSC - Oscillator Module (with Fail-Safe Clock Monitor)" for more details.

# 25.5 Timer1 Operation in Asynchronous Counter Mode

When the SYNC control bit is set, the external clock input is not synchronized. The timer increments asynchronously to the internal phase clocks. If the external clock source is selected then the timer will continue to run during Sleep and can generate an interrupt on overflow, which will wake-up the processor. However, special precautions in software are needed to read/write the timer.



**Important:** When switching from synchronous to asynchronous operation, it is possible to skip an increment. When switching from asynchronous to synchronous operation, it is possible to produce an additional increment.

#### 25.5.1 Reading and Writing TMRx in Asynchronous Counter Mode

Reading TMRxH or TMRxL while the timer is running from an external asynchronous clock will ensure a valid read (taken care of in hardware). However, the user should keep in mind that reading the 16-bit timer in two 8-bit values itself, poses certain problems, since there may be a carry out of TMRxL to TMRxH between the reads.

For writes, it is recommended that the user simply stop the timer and write the desired values. A write contention may occur by writing to the timer registers, while the register is incrementing. This may produce an unpredictable value in the TMRxH:TMRxL register pair.

#### 25.6 Timer1 16-Bit Read/Write Mode


Timer1 can be configured to read and write all 16 bits of data to and from the 8-bit TMRxL and TMRxH registers, simultaneously. The 16-bit read and write operations are enabled by setting the RD16 bit. To accomplish this function, the TMRxH register value is mapped to a buffer register called the TMRxH buffer register. While in 16-Bit mode, the TMRxH register is not directly readable or writable and all read and write operations take place through the use of this TMRxH buffer register.

When a read from the TMRxL register is requested, the value of the TMRxH register is simultaneously loaded into the TMRxH buffer register. When a read from the TMRxH register is requested, the value is provided from the TMRxH buffer register instead. This provides the user with the ability to accurately read all 16 bits of the Timer1 value from a

single instance in time. Refer to the figure below for more details. In contrast, when not in 16-Bit mode, the user must read each register separately and determine if the values have become invalid due to a rollover that may have occurred between the read operations.

When a write request of the TMRxL register is requested, the TMRxH buffer register is simultaneously updated with the contents of the TMRxH register. The value of TMRxH must be preloaded into the TMRxH buffer register prior to the write request for the TMRxL register. This provides the user with the ability to write all 16 bits to the TMRx register at the same time. Any requests to write to TMRxH directly does not clear the Timer1 prescaler value. The prescaler value is only cleared through write requests to the TMRxL register.

Figure 25-3. Timer1 16-Bit Read/Write Mode Block Diagram



#### 25.7 Timer1 Gate

Timer1 can be configured to count freely or the count can be enabled and disabled using Timer1 gate circuitry. This is also referred to as Timer1 gate enable. Timer1 gate can also be driven by multiple selectable sources.


#### 25.7.1 Timer1 Gate Enable


The Timer1 Gate Enable mode is enabled by setting the GE bit. The polarity of the Timer1 Gate Enable mode is configured using the GPOL bit.

When Timer1 Gate Enable mode is enabled, Timer1 will increment on the rising edge of the Timer1 clock source. When Timer1 Gate signal is inactive, the timer will not increment and hold the current count. Enable mode is disabled, no incrementing will occur and Timer1 will hold the current count. See figure below for timing details.

Table 25-2. Timer1 Gate Enable Selections

TMRxCLK	GPOL	TxG	Timer1 Operation
<b>↑</b>	1	1	Counts
<b>↑</b>	1 0		Holds Count
<b>↑</b>	0	1	Holds Count
<b>↑</b>	0	0	Counts





#### 25.7.2 Timer1 Gate Source Selection

The gate source for Timer1 is selected using the GSS bits. The polarity selection for the gate source is controlled by the GPOL bit.

Any of the above mentioned signals can be used to trigger the gate. The output of the CMPx can be synchronized to the Timer1 clock or left asynchronous. For more information refer to the "Comparator Output Synchronization" section.

#### 25.7.3 Timer1 Gate Toggle Mode


When Timer1 Gate Toggle mode is enabled, it is possible to measure the full-cycle length of a Timer1 Gate signal, as opposed to the duration of a single level pulse. The Timer1 gate source is routed through a flip-flop that changes state on every incrementing edge of the signal. See figure below for timing details.

Timer1 Gate Toggle mode is enabled by setting the GTM bit. When the GTM bit is cleared, the flip-flop is cleared and held clear. This is necessary in order to control which edge is measured.



**Important:** Enabling Toggle mode at the same time as changing the gate polarity may result in indeterminate operation.


© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 412



#### 25.7.4 Timer1 Gate Single Pulse Mode


When Timer1 Gate Single Pulse mode is enabled, it is possible to capture a single pulse gate event. Timer1 Gate Single Pulse mode is first enabled by setting the GSPM bit. Next, the GGO/DONE must be set. The Timer1 will be fully enabled on the next incrementing edge. On the next trailing edge of the pulse, the GGO/DONE bit will automatically be cleared. No other gate events will be allowed to increment Timer1 until the GGO/DONE bit is once again set in software.

Figure 25-6. Timer1 Gate Single Pulse Mode



Clearing the GSPM bit will also clear the GGO/DONE bit. See the figure below for timing details. Enabling the Toggle mode and the Single Pulse mode simultaneously will permit both sections to work together. This allows the cycle times on the Timer1 gate source to be measured. See figure below for timing details.

Figure 25-7. Timer1 Gate Single Pulse and Toggle Combined Mode



### 25.7.5 Timer1 Gate Value Status

When Timer1 gate value status is utilized, it is possible to read the most current level of the gate control value. The value is stored in the GVAL bit in the TxGCON register. The GVAL bit is valid even when the Timer1 gate is not enabled (GE bit is cleared).

#### 25.7.6 Timer1 Gate Event Interrupt

When Timer1 gate event interrupt is enabled, it is possible to generate an interrupt upon the completion of a gate event. When the falling edge of GVAL occurs, the TMRxGIF flag bit in one of the PIR registers will be set. If the TMRxGIE bit in the corresponding PIE register is set, then an interrupt will be recognized.

The TMRxGIF flag bit operates even when the Timer1 gate is not enabled (GE bit is cleared). For more information on selecting high or low priority status for the Timer1 gate event interrupt see the "VIC - Vectored Interrupt Controller Module" chapter.

# 25.8 Timer1 Interrupt

The TMRx register increments to FFFFh and rolls over to 0000h. When TMRx rolls over, the Timer1 interrupt flag bit of the PIRx register is set. To enable the interrupt-on-rollover, the following bits must be set:

- ON bit of the TxCON register
- TMRxIE bits of the PIEx register
- Global interrupts must be enabled

The interrupt is cleared by clearing the TMRxIF bit as a task in the Interrupt Service Routine. For more information on selecting high or low priority status for the Timer1 overflow interrupt, see the "VIC - Vectored Interrupt Controller Module" chapter.



**Important:** The TMRx register and the TMRxIF bit should be cleared before enabling interrupts.

# 25.9 Timer1 Operation During Sleep

Timer1 can only operate during Sleep when configured as an asynchronous counter. In this mode, many clock sources can be used to increment the counter. To set up the timer to wake the device:

- . ON bit must be set
- · TMRxIE bit of the PIEx register must be set
- · Global interrupts must be enabled
- · SYNC bit must be set
- Configure the TxCLK register for using any clock source other than F<sub>OSC</sub> and F<sub>OSC</sub>/4

The device will wake-up on an overflow and execute the next instruction. If global interrupts are enabled, the device will call the Interrupt Service Routine. The secondary oscillator will continue to operate in Sleep regardless of the SYNC bit setting.

# 25.10 CCP Capture/Compare Time Base

The CCP modules use TMRx as the time base when operating in Capture or Compare mode. In Capture mode, the value in TMRx is copied into the CCPRx register on a capture event. In Compare mode, an event is triggered when the value in the CCPRx register matches the value in TMRx. This event can be a Special Event Trigger.

# 25.11 CCP Special Event Trigger

When any of the CCPs are configured to trigger a special event, the trigger will clear the TMRx register. This special event does not cause a Timer1 interrupt. The CCP module may still be configured to generate a CCP interrupt. In this mode of operation, the CCPRx register becomes the period register for Timer1. Timer1 should be synchronized and  $F_{OSC}/4$  should be selected as the clock source in order to utilize the Special Event Trigger. Asynchronous operation of Timer1 can cause a Special Event Trigger to be missed. In the event that a write to TMRxH or TMRxL coincides with a Special Event Trigger from the CCP, the write will take precedence.

#### 25.12 Peripheral Module Disable

When a peripheral is not used or inactive, the module can be disabled by setting the Module Disable bit in the PMD registers. This will reduce power consumption to an absolute minimum. Setting the PMD bits holds the module in Reset and disconnects the module's clock source. The Module Disable bits for Timer1 (TMR1MD) are in the PMDx register. See the "PMD - Peripheral Module Disable" chapter for more information.

#### 25.13 Register Definitions: Timer1 Control

Long bit name prefixes for the System Arbiter Priority Registers are shown in the table below where "x" refers to the Priority Register instance number. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 415

# PIC18F26/46/56Q84

# **TMR1 - Timer1 Module with Gate Control**

# Table 25-3. Timer1 Register Bit Name Prefixes

Peripheral	Bit Name Prefix
Timer1	T1
Timer3	Т3
Timer 5	T5

#### 25.13.1 TxCON

Name: TxCON

**Offset:** 0x31E,0x32A,0x336

Timer Control Register

Bit	7	6	5	4	3	2	1	0	
			CKPS[1:0]			SYNC	RD16	ON	
Access			R/W	R/W		R/W	R/W	R/W	
Reset			0	0		0	0	0	

# Bits 5:4 - CKPS[1:0] Timer Input Clock Prescaler Select

Reset States: POR/BOR = 00

All Other Resets = uu

Value	Description
11	1:8 Prescaler value
10	1:4 Prescaler value
01	1:2 Prescaler value
00	1:1 Prescaler value

#### Bit 2 - SYNC Timer External Clock Input Synchronization Control

Reset States: POR/BOR = 0

All Other Resets = u

Value	Condition	Description
X	$CS = F_{OSC}/4$ or $F_{OSC}$	This bit is ignored. Timer uses the incoming clock as is.
1	All other clock sources	Do not synchronize external clock input
0	All other clock sources	Synchronize external clock input with system clock

# Bit 1 - RD16 16-Bit Read/Write Mode Enable

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	Enables register read/write of Timer in one 16-bit operation
0	Enables register read/write of Timer in two 8-bit operations

#### Bit 0 - ON Timer On

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	Enables Timer
0	Disables Timer

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 417

#### 25.13.2 TxGCON

Name: TxGCON

Offset: 0x31F,0x32B,0x337

Timer Gate Control Register

Bit	7	6	5	4	3	2	1	0
	GE	GPOL	GTM	GSPM	GGO/DONE	GVAL		
Access	R/W	R/W	R/W	R/W	R/W	R		
Reset	0	0	0	0	0	Х		

# **Bit 7 – GE** Timer Gate Enable Reset States: POR/BOR = 0

All Other Resets = u

	, O	-0.0
Value	Condition	Description
1	<b>ON</b> = 1	Timer counting is controlled by the Timer gate function
0	ON = 1	Timer is always counting
X	<b>ON</b> = 0	This bit is ignored

# **Bit 6 – GPOL** Timer Gate Polarity Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	Timer gate is active-high (Timer counts when gate is high)
0	Timer gate is active-low (Timer counts when gate is low)

#### Bit 5 - GTM Timer Gate Toggle Mode

Timer Gate Flip-Flop Toggles on every rising edge when Toggle mode is enabled.

Reset States: POR/BOR = 0

All Other Resets = u

	7.11 1101 1 100010
Value	Description
1	Timer Gate Toggle mode is enabled
0	Timer Gate Toggle mode is disabled and Toggle flip-flop is cleared

#### Bit 4 - GSPM Timer Gate Single Pulse Mode

Reset States: POR/BOR = 0

All Other Resets = u

Va	lue	Description
1		Timer Gate Single Pulse mode is enabled and is controlling Timer gate
0		Timer Gate Single Pulse mode is disabled

# Bit 3 – GGO/DONE Timer Gate Single Pulse Acquisition Status

This bit is automatically cleared when TxGSPM is cleared.

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	Timer Gate Single Pulse Acquisition is ready, waiting for an edge
0	Timer Gate Single Pulse Acquisition has completed or has not been started

#### Bit 2 - GVAL Timer Gate Current State

Indicates the current state of the timer gate that could be provided to TMRxH:TMRxL


Unaffected by Timer Gate Enable (GE bit)

#### 25.13.3 TxCLK

Name: TxCLK

**Offset:** 0x321,0x32D,0x339

Timer Clock Source Selection Register



Bits 4:0 - CS[4:0] Timer Clock Source Selection

#### Table 25-4. Timer Clock Sources

CS	Clock Source								
	Timer1	Timer3	Timer5						
11111-10110		Reserved							
10101	CLC8_OUT								
10100		CLC7_OUT							
10011		CLC6_OUT							
10010		CLC5_OUT							
10001		CLC4_OUT							
10000		CLC3_OUT							
01111		CLC2_OUT							
01110		CLC1_OUT							
01101	TMR5_OUT	TMR5_OUT	Reserved						
01100	TMR3_OUT	Reserved	TMR3_OUT						
01011	Reserved	TMR1_OUT	TMR1_OUT						
01010		TMR0_OUT							
01001		CLKREF_OUT							
01000		EXTOSC							
00111		SOSC							
00110		MFINTOSC (32 kHz)							
00101		MFINTOSC (500 kHz)							
00100		LFINTOSC							
00011		HFINTOSC							
00010		F <sub>OSC</sub>							
00001		F <sub>OSC</sub> /4							
00000	Pin selected by T1CKIPPS	Pin selected by T3CKIPPS	Pin selected by T5CKIPPS						

Reset States: POR/BOR = 00000


All Other Resets = uuuuu

#### 25.13.4 TxGATE

Name: TxGATE

**Offset:** 0x320,0x32C,0x338

Timer Gate Source Selection Register



Bits 5:0 - GSS[5:0] Timer Gate Source Selection

#### Table 25-5. Timer Gate Sources

GSS		Gate Source						
	Timer1	Timer3	Timer5					
111111-100010		Reserved						
100001	CLC8_OUT							
100000		CLC7_OUT						
011111		CLC6_OUT						
011110		CLC5_OUT						
011101		CLC4_OUT						
011100		CLC3_OUT						
011011		CLC2_OUT						
011010		CLC1_OUT						
011001		ZCD_OUT						
011000		CMP2_OUT						
010111		CMP1_OUT						
010110		NCO3_OUT						
010101		NCO2_OUT						
010100		NCO1_OUT						
010011		PWM4S1P2_OUT						
010010		PWM4S1P1_OUT						
010001		PWM3S1P2_OUT						
010000		PWM3S1P1_OUT						
001111		PWM2S1P2_OUT						
001110		PWM2S1P1_OUT						
001101		PWM1S1P2_OUT						
001100		PWM1S1P1_OUT						
001011		CCP3_OUT						
001010		CCP2_OUT						
001001		CCP1_OUT						
001000		SMT1_OUT						
000111		TMR6_Postscaler_OUT						
000110	TMR5_OUT	TMR5_OUT	Reserved					
000101		TMR4_Postscaler_OUT						
000100	TMR3_OUT	Reserved	TMR3_OUT					
000011		TMR2_Postscaler_OUT						
000010	Reserved	TMR1_OUT	TMR1_OUT					

# PIC18F26/46/56Q84

# **TMR1 - Timer1 Module with Gate Control**

continued									
GSS	Gate Source								
	Timer1	Timer3	Timer5						
000001		TMR0_OUT							
000000	Pin selected by T1GPPS	Pin selected by T3GPPS	Pin selected by T5GPPS						

# PIC18F26/46/56Q84

# TMR1 - Timer1 Module with Gate Control

#### 25.13.5 TMRx

Name: TMRx

Offset: 0x31C,0x328,0x334

Timer Register

Bit	15	14	13	12	11	10	9	8					
		TMRx[15:8]											
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W					
Reset	0	0	0	0	0	0	0	0					
Bit	7	6	5	4	3	2	1	0					
	TMRx[7:0]												
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W					
Reset	0	0	0	0	0	0	0	0					

Bits 15:0 – TMRx[15:0] Timer Register Value
Reset States: POR/BOR = 0000000000000000
All Other Resets = uuuuuuuuuuuuuuuuu

Notes: The individual bytes in this multi-byte register can be accessed with the following register names:

- TMRxH: Accesses the high byte TMRx[15:8]
- TMRxL: Accesses the low byte TMRx[7:0]

# 25.14 Register Summary Timer 1

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x031B										
0x031C	TMR1	7:0					1[7:0]			
0,0010		15:8				TMR <sup>2</sup>	[15:8]			
0x031E	T1CON	7:0			CKPS	S[1:0]		SYNC	RD16	ON
0x031F	T1GCON	7:0	GE	GPOL	GTM	GSPM	GGO/DONE	GVAL		
0x0320	T1GATE	7:0					GSS	[5:0]		
0x0321	T1CLK	7:0						CS[4:0]		
0x0322										
	Reserved									
0x0327										
0x0328	TMR3	7:0	TMR3[7:0]							
0.0020	0328 TMR3	15:8	TMR3[15:8]							
0x032A	T3CON	7:0			CKPS	S[1:0]		SYNC	RD16	ON
0x032B	T3GCON	7:0	GE	GPOL	GTM	GSPM	GGO/DONE	GVAL		
0x032C	T3GATE	7:0					GSS	[5:0]		
0x032D	T3CLK	7:0						CS[4:0]		
0x032E										
	Reserved									
0x0333										
0x0334	TMR5	7:0				TMR	5[7:0]			
0x0334	TIVING	15:8				TMR	5[15:8]			
0x0336	T5CON	7:0			CKP	S[1:0]		SYNC	RD16	ON
0x0337	T5GCON	7:0	GE	GPOL	GTM	GSPM	GGO/DONE	GVAL		
0x0338	T5GATE	7:0				GSS[5:0]				
0x0339	T5CLK	7:0						CS[4:0]		

# 26. TMR2 - Timer2 Module

The Timer2 module is a 8-bit timer that incorporates the following features:


- 8-bit timer and period registers
- · Readable and writable
- Software programmable prescaler (1:1 to 1:128)
- Software programmable postscaler (1:1 to 1:16)
- · Interrupt on T2TMR match with T2PR
- · One-shot operation
- · Full asynchronous operation
- Includes Hardware Limit Timer (HLT)
- · Alternate clock sources
- · External timer Reset signal sources
- · Configurable timer Reset operation

See Figure 26-1 for a block diagram of Timer2.



**Important:** References to module Timer2 apply to all the even numbered timers on this device. (Timer2, Timer4, etc.)

Figure 26-1. Timer2 with Hardware Limit Timer (HLT) Block Diagram



#### Notes:

- 1. Signal to the CCP peripheral for PWM pulse trigger in PWM mode.
- 2. See RSEL for external Reset sources.
- 3. See CS for clock source selections.

## 26.1 Timer2 Operation

Timer2 operates in three major modes:

- Free-Running Period
- One-shot
- Monostable

Within each operating mode there are several options for starting, stopping, and Reset. Table 26-1 lists the options.

In all modes, the T2TMR count register increments on the rising edge of the clock signal from the programmable prescaler. When T2TMR equals T2PR, a high level output to the postscaler counter is generated. T2TMR is cleared on the next clock input.

An external signal from hardware can also be configured to gate the timer operation or force a T2TMR count Reset. In Gate modes the counter stops when the gate is disabled and resumes when the gate is enabled. In Reset modes the T2TMR count is reset on either the level or edge from the external source.

The T2TMR and T2PR registers are both directly readable and writable. The T2TMR register is cleared and the T2PR register initializes to 0xFF on any device Reset. Both the prescaler and postscaler counters are cleared on the following events:

- · A write to the T2TMR register
- A write to the T2CON register
- · Any device Reset
- External Reset source event that resets the timer.



**Important:** T2TMR is not cleared when T2CON is written.

#### 26.1.1 Free-Running Period Mode

The value of T2TMR is compared to that of the Period register, T2PR, on each clock cycle. When the two values match, the comparator resets the value of T2TMR to 0x00 on the next cycle and increments the output postscaler counter. When the postscaler count equals the value in the OUTPS bits of the T2CON register then a one clock period wide pulse occurs on the TMR2 postscaled output, and the postscaler count is cleared.

#### 26.1.2 One-Shot Mode

The One-Shot mode is identical to the Free-Running Period mode except that the ON bit is cleared and the timer is stopped when T2TMR matches T2PR and will not restart until the ON bit is cycled off and on. Postscaler (OUTPS) values other than zero are ignored in this mode because the timer is stopped at the first period event and the postscaler is reset when the timer is restarted.

#### 26.1.3 Monostable Mode

Monostable modes are similar to One-Shot modes except that the ON bit is not cleared and the timer can be restarted by an external Reset event.

# 26.2 Timer2 Output

The Timer2 module's primary output is TMR2\_postscaled, which pulses for a single TMR2\_clk period upon each match of the postscaler counter and the OUTPS bits of the T2CON register. The postscaler is incremented each time the T2TMR value matches the T2PR value. This signal can also be selected as an input to other Core Independent Peripherals:

In addition, the Timer2 is also used by the CCP module for pulse generation in PWM mode. See "PWM Overview" and "PWM Period" sections for more details on setting up Timer2 for use with the CCP and PWM modules.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 425


## 26.3 External Reset Sources

In addition to the clock source, the Timer2 can also be driven by an external Reset source input. This external Reset input is selected for each timer with the corresponding TxRST register. The external Reset input can control starting and stopping of the timer, as well as resetting the timer, depending on the mode used.

# 26.4 Timer2 Interrupt

Timer2 can also generate a device interrupt. The interrupt is generated when the postscaler counter matches the selected postscaler value (OUTPS bits of T2CON register). The interrupt is enabled by setting the TMR2IE interrupt enable bit. Interrupt timing is illustrated in the figure below.

Figure 26-2. Timer2 Prescaler, Postscaler, and Interrupt Timing Diagram



Note 1: Setting the interrupt flag is synchronized with the instruction clock.

Synchronization may take as many as 2 instruction cycles

2: Cleared by software.

# 26.5 PSYNC bit

Setting the PSYNC bit synchronizes the prescaler output to  $F_{OSC}/4$ . Setting this bit is required for reading the Timer2 counter register while the selected Timer clock is asynchronous to  $F_{OSC}/4$ .

**Note:** Setting PSYNC requires that the output of the prescaler is slower than  $F_{OSC}/4$ . Setting PSYNC when the output of the prescaler is greater than or equal to  $F_{OSC}/4$  may cause unexpected results.

#### 26.6 CSYNC bit

All bits in the Timer2 SFRs are synchronized to  $F_{OSC}/4$  by default, not the Timer2 input clock. As such, if the Timer2 input clock is not synchronized to  $F_{OSC}/4$ , it is possible for the Timer2 input clock to transition at the same time as the ON bit is set in software, which may cause undesirable behavior and glitches in the counter. Setting the CSYNC bit remedies this problem by synchronizing the ON bit to the Timer2 input clock instead of  $F_{OSC}/4$ . However, as this synchronization uses an edge of the TMR2 input clock, up to one input clock cycle will be consumed and not counted by the Timer2 when CSYNC is set. Conversely, clearing the CSYNC bit synchronizes the ON bit to  $F_{OSC}/4$ , which does not consume any clock edges, but has the previously stated risk of glitches.

# 26.7 Operating Modes

The mode of the timer is controlled by the MODE bits. Edge-Triggered modes require six Timer clock periods between external triggers. Level-Triggered modes require the triggering level to be at least three Timer clock periods long. External triggers are ignored while in Debug mode.

Table 26-1. Operating Modes Table

	MC	DE	Output	2 11		Timer Control			
Mode	[4:3]	[2:0]	Operation	Operation	Start	Reset	Stop		
		000		Software gate (Figure 26-3)	ON = 1	_	<b>ON</b> = 0		
		001	Period Pulse	Hardware gate, active-high (Figure 26-4)	ON = 1 and TMRx_ers = 1	_	ON = 0 or TMRx_ers = 0		
		010		Hardware gate, active-low	ON = 1 and TMRx_ers = 0	_	ON = 0 or TMRx_ers = 1		
Free-	00	011		Rising or falling edge Reset		TMRx_ers			
Running Period	00	100	Period	Rising edge Reset (Figure 26-5)	-	TMRx_ers ↑	<b>ON</b> = 0		
		101	Pulse	Falling edge Reset	-	TMRx_ers ↓			
		110	with Hardware	Low level Reset	ON = 1	TMRx_ers = 0	ON = 0 or TMRx_ers = 0		
		111	Reset	High level Reset (Figure 26-6)		TMRx_ers = 1	ON = 0 or TMRx_ers = 1		
		000	One-shot	Software start (Figure 26-7)	ON = 1	_			
		001	Edge- Triggered Start (Note 1)  Edge- Triggered Start and Hardware Reset	Rising edge start (Figure 26-8)	ON = 1 and TMRx_ers ↑	_			
		010		Falling edge start	ON = 1 and TMRx_ers ↓	_			
		011		Any edge start	ON = 1 and TMRx_ers ‡	_	ON = 0 or		
One-shot	01	100		Rising edge start and Rising edge Reset (Figure 26-9)	ON = 1 and TMRx_ers ↑	TMRx_ers ↑	Next clock after TxTMR = TxPR		
		101		Falling edge start and Falling edge Reset	ON = 1 and TMRx_ers ↓	TMRx_ers ↓	(Note 2)		
		110		Rising edge start and Low level Reset (Figure 26-10)	ON = 1 and TMRx_ers ↑	TMRx_ers = 0			
		111	(Note 1)	Falling edge start and High level Reset	ON = 1 and TMRx_ers ↓	TMRx_ers = 1			

continued										
Mada	MODE		Output			Timer Control				
Mode	[4:3]	[2:0]	Operation	Operation	Start	Reset	Stop			
		000		Reser	ved					
		001	Edge-	Rising edge start (Figure 26-11)	ON = 1 and TMRx_ers ↑	_	ON = 0 or			
Monostable			010	Triggered Start	Falling edge start	ON = 1 and TMRx_ers↓	_	Next clock after		
		011	(Note 1)	Any edge start	ON = 1 and TMRx_ers ‡		(Note 3)			
Reserved	10	100		Reser	ved					
Reserved		101		Reser	ved					
	t			110	Level Triggered	High level start and Low level Reset (Figure 26-12)	ON = 1 and TMRx_ers = 1	TMRx_ers = 0	ON = 0 or	
One-shot		111	Start and Hardware Reset	Low level start and High level Reset	ON = 1 and TMRx_ers = 0	TMRx_ers = 1	Held in Reset (Note 2)			
Reserved	11	XXX		Reserved						

#### Notes:

- 1. If ON = 0 then an edge is required to restart the timer after ON = 1.
- 2. When T2TMR = T2PR then the next clock clears ON and stops T2TMR at 00h.
- 3. When T2TMR = T2PR then the next clock stops T2TMR at 00h but does not clear ON.

# 26.8 Operation Examples


Unless otherwise specified, the following notes apply to the following timing diagrams:

- Both the prescaler and postscaler are set to 1:1 (both the CKPS and OUTPS bits.)
- The diagrams illustrate any clock except F<sub>OSC</sub>/4 and show clock-sync delays of at least two full cycles for both
  ON and TMRx\_ers. When using F<sub>OSC</sub>/4, the clock-sync delay is at least one instruction period for TMRx\_ers;
  ON applies in the next instruction period.
- ON and TMRx\_ers are somewhat generalized, and clock-sync delays may produce results that are slightly different than illustrated.
- The PWM Duty Cycle and PWM output are illustrated assuming that the timer is used for the PWM function of the CCP module as described in the "PWM Overview" section. The signals are not a part of the Timer2 module.

#### 26.8.1 Software Gate Mode

This mode corresponds to legacy Timer2 operation. The timer increments with each clock input when ON = 1 and does not increment when ON = 0. When the TxTMR count equals the TxPR period count the timer resets on the next clock and continues counting from 0. Operation with the ON bit software controlled is illustrated in Figure 26-3. With TxPR = 5, the counter advances until TxTMR = 5, and goes to zero with the next clock.

Figure 26-3. Software Gate Mode Timing Diagram (MODE = 'b00000)



Note 1: BSF and BCF represent Bit-Set File and Bit-Clear File instructions executed by the CPU to set or clear the ON bit of TxCON. CPU execution is asynchronous to the timer clock input.


#### 26.8.2 Hardware Gate Mode

The Hardware Gate modes operate the same as the Software Gate mode except the TMRx\_ers external signal can also gate the timer. When used with the CCP, the gating extends the PWM period. If the timer is stopped when the PWM output is high, then the duty cycle is also extended.

When MODE = b00001 then the timer is stopped when the external signal is high. When MODE = b00010, then the timer is stopped when the external signal is low.

Figure 26-4 illustrates the Hardware Gating mode for MODE = \b000001 in which a high input level starts the counter.

Figure 26-4. Hardware Gate Mode Timing Diagram (MODE = 'b00001)




# 26.8.3 Edge-Triggered Hardware Limit Mode

In Hardware Limit mode, the timer can be reset by the TMRx\_ers external signal before the timer reaches the period count. Three types of Resets are possible:

- Reset on rising or falling edge (MODE= 'b00011)
- Reset on rising edge (MODE = 'b00100)
- Reset on falling edge (MODE = 'b00101)

When the timer is used in conjunction with the CCP in PWM mode then an early Reset shortens the period and restarts the PWM pulse after a two clock delay. Refer to Figure 26-5.

Figure 26-5. Edge-Triggered Hardware Limit Mode Timing Diagram (MODE = 'b00100)



Note 1: BSF and BCF represent Bit-Set File and Bit-Clear File instructions executed by the CPU to set or clear the ON bit of TxCON. CPU execution is asynchronous to the timer clock input.


# 26.8.4 Level-Triggered Hardware Limit Mode

In the Level-Triggered Hardware Limit Timer modes the counter is reset by high or low levels of the external signal TMRx\_ers, as shown in Figure 26-6. Selecting MODE = b00110 will cause the timer to reset on a low level external signal. Selecting MODE = b00111 will cause the timer to reset on a high level external signal. In the example, the counter is reset while TMRx\_ers = 1. ON is controlled by BSF and BCF instructions. When ON = 0 the external signal is ignored.

When the CCP uses the timer as the PWM time base then the PWM output will be set high when the timer starts counting and then set low only when the timer count matches the CCPRx value. The timer is reset when either the timer count matches the TxPR value or two clock periods after the external Reset signal goes true and stays true.

The timer starts counting, and the PWM output is set high, on either the clock following the TxPR match or two clocks after the external Reset signal relinquishes the Reset. The PWM output will remain high until the timer counts up to match the CCPRx pulse width value. If the external Reset signal goes true while the PWM output is high then the PWM output will remain high until the Reset signal is released allowing the timer to count up to match the CCPRx value.

Figure 26-6. Level-Triggered Hardware Limit Mode Timing Diagram (MODE = 'b00111)




#### 26.8.5 Software Start One-Shot Mode

In One-Shot mode the timer resets and the ON bit is cleared when the timer value matches the TxPR period value. The ON bit must be set by software to start another timer cycle. Setting MODE = \bulletbolon 01000 selects One-Shot mode which is illustrated in Figure 26-7. In the example, ON is controlled by BSF and BCF instructions. In the first case, a BSF instruction sets ON and the counter runs to completion and clears ON. In the second case, a BSF instruction starts the cycle, BCF/BSF instructions turn the counter off and on during the cycle, and then it runs to completion.

When One-Shot mode is used in conjunction with the CCP PWM operation the PWM pulse drive starts concurrent with setting the ON bit. Clearing the ON bit while the PWM drive is active will extend the PWM drive. The PWM drive will terminate when the timer value matches the CCPRx pulse width value. The PWM drive will remain off until software sets the ON bit to start another cycle. If software clears the ON bit after the CCPRx match but before the TxPR match then the PWM drive will be extended by the length of time the ON bit remains cleared. Another timing cycle can only be initiated by setting the ON bit after it has been cleared by a TxPR period count match.

Figure 26-7. Software Start One-Shot Mode Timing Diagram (MODE = 'b01000)



Note 1: BSF and BCF represent Bit-Set File and Bit-Clear File instructions executed by the CPU to set or clear the ON bit of TxCON. CPU execution is asynchronous to the timer clock input.

#### 26.8.6 **Edge-Triggered One-Shot Mode**


The Edge-Triggered One-Shot modes start the timer on an edge from the external signal input, after the ON bit is set, and clear the ON bit when the timer matches the TxPR period value. The following edges will start the timer:

- Rising edge (MODE = 'b01001)
- Falling edge (MODE = 'b01010)
- Rising or Falling edge (MODE = 'b01011)

If the timer is halted by clearing the ON bit then another TMRx ers edge is required after the ON bit is set to resume counting. Figure 26-8 illustrates operation in the rising edge One-Shot mode.

When Edge-Triggered One-Shot mode is used in conjunction with the CCP then the edge-trigger will activate the PWM drive and the PWM drive will deactivate when the timer matches the CCPRx pulse width value and stay deactivated when the timer halts at the TxPR period count match.

Figure 26-8. Edge-Triggered One-Shot Mode Timing Diagram (MODE = 'b01001)



set or clear the ON bit of TxCON. CPU execution is asynchronous to the timer clock input.

#### 26.8.7 Edge-Triggered Hardware Limit One-Shot Mode


In Edge-Triggered Hardware Limit One-Shot modes the timer starts on the first external signal edge after the ON bit is set and resets on all subsequent edges. Only the first edge after the ON bit is set is needed to start the timer. The counter will resume counting automatically two clocks after all subsequent external Reset edges. Edge triggers are as follows:

- Rising edge start and Reset (MODE = 'b01100)
- Falling edge start and Reset (MODE = 'b01101)

The timer resets and clears the ON bit when the timer value matches the TxPR period value. External signal edges will have no effect until after software sets the ON bit. Figure 26-9 illustrates the rising edge hardware limit one-shot operation.

When this mode is used in conjunction with the CCP then the first starting edge trigger, and all subsequent Reset edges, will activate the PWM drive. The PWM drive will deactivate when the timer matches the CCPRx pulse width value and stay deactivated until the timer halts at the TxPR period match unless an external signal edge resets the timer before the match occurs.

Figure 26-9. Edge-Triggered Hardware Limit One-Shot Mode Timing Diagram (MODE = `b01100)



Note 1: BSF and BCF represent Bit-Set File and Bit-Clear File instructions executed by the CPU to set or clear the ON bit of TxCON. CPU execution is asynchronous to the timer clock input.

## 26.8.8 Level Reset, Edge-Triggered Hardware Limit One-Shot Modes


In Level-Triggered One-Shot mode the timer count is reset on the external signal level and starts counting on the rising/falling edge of the transition from Reset level to the active level while the ON bit is set. Reset levels are selected as follows:

- Low Reset level (MODE = 'b01110)
- High Reset level (MODE = 'b01111)

When the timer count matches the TxPR period count, the timer is reset and the ON bit is cleared. When the ON bit is cleared by either a TxPR match or by software control, a new external signal edge is required after the ON bit is set to start the counter.

When Level-Triggered Reset One-Shot mode is used in conjunction with the CCP PWM operation, the PWM drive goes active with the external signal edge that starts the timer. The PWM drive goes inactive when the timer count equals the CCPRx pulse width count. The PWM drive does not go active when the timer count clears at the TxPR period count match.

Figure 26-10. Low Level Reset, Edge-Triggered Hardware Limit One-Shot Mode Timing Diagram (MODE = \b01110)



Note 1: BSF and BCF represent Bit-Set File and Bit-Clear File instructions executed by the CPU to set or clear the ON bit of TxCON. CPU execution is asynchronous to the timer clock input.


# 26.8.9 Edge-Triggered Monostable Modes

The Edge-Triggered Monostable modes start the timer on an edge from the external Reset signal input, after the ON bit is set, and stop incrementing the timer when the timer matches the TxPR period value. The following edges will start the timer:

- Rising edge (MODE = 'b10001)
- Falling edge (MODE = 'b10010)
- Rising or Falling edge (MODE = `b10011)

When an Edge-Triggered Monostable mode is used in conjunction with the CCP PWM operation, the PWM drive goes active with the external Reset signal edge that starts the timer, but will not go active when the timer matches the TxPR value. While the timer is incrementing, additional edges on the external Reset signal will not affect the CCP PWM.

Figure 26-11. Rising Edge-Triggered Monostable Mode Timing Diagram (MODE = 'b10001)



te 1: BSF and BCF represent Bit-Set File and Bit-Clear File instructions executed by the CPU to set or clear the ON bit of TxCON. CPU execution is asynchronous to the timer clock input.

#### 26.8.10 Level-Triggered Hardware Limit One-Shot Modes


The Level-Triggered Hardware Limit One-Shot modes hold the timer in Reset on an external Reset level and start counting when both the ON bit is set and the external signal is not at the Reset level. If one of either the external signal is not in Reset or the ON bit is set, then the other signal being set/made active will start the timer. Reset levels are selected as follows:

- Low Reset level (MODE = 'b10110)
- High Reset level (MODE = 'b10111)

When the timer count matches the TxPR period count, the timer is reset and the ON bit is cleared. When the ON bit is cleared by either a TxPR match or by software control, the timer will stay in Reset until both the ON bit is set and the external signal is not at the Reset level.

When Level-Triggered Hardware Limit One-Shot modes are used in conjunction with the CCP PWM operation, the PWM drive goes active with either the external signal edge or the setting of the ON bit, whichever of the two starts the timer.

Figure 26-12. Level-Triggered hardware Limit One-Shot Mode Timing Diagram (MODE = 'b10110)



## 26.9 Timer2 Operation During Sleep

When PSYNC = 1, Timer2 cannot be operated while the processor is in Sleep mode. The contents of the T2TMR and T2PR registers will remain unchanged while processor is in Sleep mode.

When PSYNC = 0, Timer2 will operate in Sleep as long as the clock source selected is also still running. If any internal oscillator is selected as the clock source, it will stay active during Sleep mode.

# 26.10 Register Definitions: Timer2 Control

Long bit name prefixes for the Timer2 peripherals are shown in table below. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 26-2. Timer2 long bit name prefixes

Peripheral	Bit Name Prefix
Timer2	T2
Timer4	T4
Timer6	Т6

TMR2 - Timer2 Module



**Notice:** References to module Timer2 apply to all the even numbered timers on this device. (Timer2, Timer4, etc.)

TMR2 - Timer2 Module

# 26.10.1 TxTMR

Name: TxTMR

**Offset:** 0x322,0x32E,0x33A

Timer Counter Register

Bit	7	6	5	4	3	2	1	0
				TxTM	R[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - TxTMR[7:0] Timerx Counter

TMR2 - Timer2 Module

# 26.10.2 TxPR

Name: TxPR

**Offset:** 0x323,0x32F,0x33B

Timer Period Register

Bit	7	6	5	4	3	2	1	0
				TxPF	R[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

Bits 7:0 - TxPR[7:0] Timer Period Register

Value	Description
0 - 255	The timer restarts at '0' when TxTMR reaches TxPR value

### 26.10.3 TxCON

Name: **TxCON** 

Offset: 0x324,0x330,0x33C

Timerx Control Register

Bit	7	6	5	4	3	2	1	0
	ON		CKPS[2:0]			OUTP	S[3:0]	
Access	R/W/HC	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

## Bit 7 - ON Timer On(1)

Value	Description
1	Timer is on
0	Timer is off: all counters and state machines are reset

#### Bits 6:4 - CKPS[2:0] Timer Clock Prescale Select

Value	Description
111	1:128 Prescaler
110	1:64 Prescaler
101	1:32 Prescaler
100	1:16 Prescaler
011	1:8 Prescaler
010	1:4 Prescaler
001	1:2 Prescaler
000	1:1 Prescaler

# Bits 3:0 - OUTPS[3:0] Timer Output Postscaler Select

Value	Description
1111	1:16 Postscaler
1110	1:15 Postscaler
1101	1:14 Postscaler
1100	1:13 Postscaler
1011	1:12 Postscaler
1010	1:11 Postscaler
1001	1:10 Postscaler
1000	1:9 Postscaler
0111	1:8 Postscaler
0110	1:7 Postscaler
0101	1:6 Postscaler
0100	1:5 Postscaler
0011	1:4 Postscaler
0010	1:3 Postscaler
0001	1:2 Postscaler
0000	1:1 Postscaler

### Note:

1. In certain modes, the ON bit will be auto-cleared by hardware. See Table 26-1.

### 26.10.4 TxHLT

Name: TxHLT

**Offset:** 0x325,0x331,0x33D

Timer Hardware Limit Control Register

Bit	7	6	5	4	3	2	1	0
	PSYNC	CPOL	CSYNC			MODE[4:0]		
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

### Bit 7 - PSYNC Timer Prescaler Synchronization Enable (1, 2)

Value	Description
1	Timer Prescaler Output is synchronized to F <sub>OSC</sub> /4
0	Timer Prescaler Output is not synchronized to F <sub>OSC</sub> /4

#### Bit 6 - CPOL Timer Clock Polarity Selection(3)

Value	Description
1	Falling edge of input clock clocks timer/prescaler
0	Rising edge of input clock clocks timer/prescaler

## Bit 5 - CSYNC Timer Clock Synchronization Enable (4, 5)

Value	Description
1	ON bit is synchronized to timer clock input
0	ON bit is not synchronized to timer clock input

#### Bits 4:0 - MODE[4:0] Timer Control Mode Selection<sup>(6, 7)</sup>

Value	Description
00000 to	See Table 26-1
11111	

#### Notes:


- 1. Setting this bit ensures that reading TxTMR will return a valid data value.
- 2. When this bit is '1', Timer cannot operate in Sleep mode.
- 3. CKPOL should not be changed while ON = 1.
- 4. Setting this bit ensures glitch-free operation when the ON is enabled or disabled.
- 5. When this bit is set then the timer operation will be delayed by two input clocks after the ON bit is set.
- 6. Unless otherwise indicated, all modes start upon ON = 1 and stop upon ON = 0 (stops occur without affecting the value of TxTMR).
- 7. When TxTMR = TxPR, the next clock clears TxTMR, regardless of the operating mode.

# 26.10.5 TxCLKCON

 Name:
 TxCLKCON

 Offset:
 0x326,0x332,0x33E

Timer Clock Source Selection Register



Bits 4:0 - CS[4:0] Timer Clock Source Selection

### Table 26-3. Clock Source Selection


cs		Clock Source			
CS	Timer2	Timer4	Timer6		
11111-10110		Reserved			
10101		CLC8_OUT			
10100		CLC7_OUT			
10011		CLC6_OUT			
10010		CLC5_OUT			
10001		CLC4_OUT			
10000		CLC3_OUT			
01111		CLC2_OUT			
01110		CLC1_OUT			
01101		ZCD_OUT			
01100		NCO3_OUT			
01011	NCO2_OUT				
01010	NCO1_OUT				
01001	CLKREF_OUT				
01000		EXTOSC			
00111		SOSC			
00110		MFINTOSC (32 kHz)			
00101		MFINTOSC (500 kHz)			
00100	LFINTOSC				
00011	HFINTOSC				
00010	Fosc				
00001	F <sub>OSC</sub> /4				
00000	Pin selected by T2INPPS	Pin selected by T4INPPS	Pin selected by T6INPPS		

# 26.10.6 TxRST

Name: TxRST

**Offset:** 0x327,0x333,0x33F

Timer External Reset Signal Selection Register



Bits 5:0 - RSEL[5:0] External Reset Source Selection

### Table 26-4. External Reset Sources

RSEL		Reset Source		
11022	TMR2	TMR4	TMR6	
111111-100100		Reserved		
100011		U5TX_Edge (Positive/Negative)		
100010		U5RX_Edge (Positive/Negative)		
100001		U4TX_Edge (Positive/Negative)		
100000		U4RX_Edge (Positive/Negative)		
011111		U3TX_Edge (Positive/Negative)		
011110		U3RX_Edge (Positive/Negative)		
011101		U2TX_Edge (Positive/Negative)		
011100		U2RX_Edge (Positive/Negative)		
011011		U1TX_Edge (Positive/Negative)		
011010		U1RX_Edge (Positive/Negative)		
011001		CLC8_OUT		
011000		CLC7_OUT		
010111		CLC6_OUT		
010110		CLC5_OUT		
010101		CLC4_OUT		
010100		CLC3_OUT		
010011		CLC2_OUT		
010010		CLC1_OUT		
010001		ZCD_OUT		
010000		CMP2_OUT		
001111		CMP1_OUT		
001110		PWM4S1P2_OUT		
001101		PWM4S1P1_OUT		
001100		PWM3S1P2_OUT		
001011		PWM3S1P1_OUT		
001010	PWM2S1P2_OUT			
001001		PWM2S1P1_OUT		
001000		PWM1S1P2_OUT		
000111		PWM1S1P1_OUT		
000110		CCP3_OUT		
000101		CCP2_OUT		
000100		CCP1_OUT		

# TMR2 - Timer2 Module

continued								
RSEL	Reset Source							
NOEL	TMR2	TMR4	TMR6					
000011	TMR6_Postscaler_OUT	TMR6_Postscaler_OUT	Reserved					
000010	TMR4_Postscaler_OUT	Reserved	TMR4_Postscaler_OUT					
000001	Reserved	TMR2_Postscaler_OUT	TMR2_Postscaler_OUT					
000000	Pin selected by T2INPPS	Pin selected by T4INPPS	Pin selected by T6INPPS					

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 446

# 26.11 Register Summary - Timer2

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x0321										
0x0322	T2TMR	7:0				T2TM	IR[7:0]			
0x0323	T2PR	7:0				T2PI	R[7:0]			
0x0324	T2CON	7:0	ON		CKPS[2:0]			OUTF	PS[3:0]	
0x0325	T2HLT	7:0	PSYNC	CPOL	CSYNC			MODE[4:0]		
0x0326	T2CLKCON	7:0						CS[4:0]		
0x0327	T2RST	7:0					RSE	L[5:0]		
0x0328										
	Reserved									
0x032D										
0x032E	T4TMR	7:0				T4TM	IR[7:0]			
0x032F	T4PR	7:0				T4PI	R[7:0]			
0x0330	T4CON	7:0	ON		CKPS[2:0]			OUTF	PS[3:0]	
0x0331	T4HLT	7:0	PSYNC	CPOL	CSYNC			MODE[4:0]		
0x0332	T4CLKCON	7:0						CS[4:0]		
0x0333	T4RST	7:0					RSE	L[5:0]		
0x0334										
	Reserved									
0x0339										
0x033A	T6TMR	7:0				T6TM	IR[7:0]			
0x033B	T6PR	7:0	T6PR[7:0]							
0x033C	T6CON	7:0	ON		CKPS[2:0]			OUTF	PS[3:0]	
0x033D	T6HLT	7:0	PSYNC	CPOL	CSYNC			MODE[4:0]		
0x033E	T6CLKCON	7:0						CS[4:0]		
0x033F	T6RST	7:0					RSE	L[5:0]		

#### **27**. **SMT - Signal Measurement Timer**


The Signal Measurement Timer (SMT) is a 24-bit counter with advanced clock and gating logic, which can be configured for measuring a variety of digital signal parameters such as pulse width, frequency and duty cycle, and the time difference between edges on two signals.

Features of the SMT include:

- 24-Bit Timer/Counter
- Two 24-Bit Measurement Capture Registers
- One 24-Bit Period Match Register
- Multi-Mode Operation, Including Relative Timing Measurement
- Interrupt-on-Period Match and Acquisition Complete
- Multiple Clock, Signal and Window Sources

Below is the block diagram for the SMT module.

Figure 27-1. Signal Measurement Timer Block Diagram



#### 27.1 **SMT Operation**

#### 27.1.1 **Clock Source Selection**

The SMT clock source is selected by configuring the CSEL bits. The clock source is prescaled by using the PS bits. The prescaled clock source is used to clock both the counter and any synchronization logic used by the module.


The polarity of the clock source is selected by using the CPOL bit.

#### 27.1.2 Signal and Window Source Selection

The SMT signal and window sources are selected by configuring the SSEL bits and the WSEL bits (refer to the figure below).

The polarity of the signal and window sources is selected by using the SPOL and WPOL bits, respectively.

Figure 27-2. SMT Signal and SMT Window Source Selections



#### 27.1.3 Time Base

The SMTxTMR register is the 24-bit counter/timer used for measurement in each of the modes of the SMT. Setting the RST bit clears the SMTxTMR register to 0x000000. It can be written to and read by software. It is not guarded for atomic access, therefore reads and writes to the SMTxTMR register should be made only when GO = 0.

The counter can be prevented from resetting at the end of the timer period by using the STP bit. When STP = 1, the SMTxTMR will stop and remain equal to the SMTxPR register. When STP = 0, the SMTxTMR register resets to 0x0000000 at the end of the period.

### 27.1.4 Pulse Width and Period Captures

The SMTxCPW and SMTxCPR registers are used to latch in the value of the SMTxTMR register, based on the SMT mode of operation. These registers can also be updated with the current value of the SMTxTMR value by setting the CPWUP and CPRUP bits, respectively.

#### 27.1.5 Status Information

The SMT provides input status information for the user without requiring the need to monitor the raw incoming signals.

Go Status: Timer run status is indicated by the TS bit. The TS bit is delayed in time by synchronizer delays in non-counter modes

**Signal Status:** Signal status is indicated by the AS bit. This bit is used in all modes, except Window Measure, Time-of-Flight, and Capture modes, and is only valid when TS = 1. The signal status is delayed in time by synchronizer delays in non-counter modes.

**Window Status:** Window status is indicated by the WS bit. This bit is only used in Windowed Measure, Gated Counter, and Gated Window Measure modes, and is only valid when TS = 1. Window status is delayed in time by synchronizer delays in non-counter modes.

#### 27.1.6 Modes of Operation

The modes of operation are summarized in the table below. The sections following the table provide descriptions and examples of how each mode can be used. Note that all waveforms assume WPOL/SPOL/CPOL = 0.

For all modes, the REPEAT bit controls whether the acquisition happens only once or is repeated. When REPEAT = 0 (Single Acquisition mode), the timer will stop incrementing and the GO bit will be cleared upon the completion of an acquisition. Otherwise, the timer will continue and allow for continued acquisitions to overwrite the previous ones, until the timer is stopped by software.

Table 27-1. Modes of Operation


<u>MODE</u>	Mode of operation	Synchronous operation
1111-1011	Reserved	-

continued						
<u>MODE</u>	Mode of operation	Synchronous operation				
1010	Windowed Counter	No				
1001	Gated Counter	No				
1000	Counter	No				
0111	Capture	Yes				
0110	Time of Flight Measurement	Yes				
0101	Gated Windowed Measurement	Yes				
0100	Windowed Measurement	Yes				
0011	High and low time Measurement	Yes				
0010	Period and Duty Cycle Measurement	Yes				
0001	Gated Timer	Yes				
0000	Timer	Yes				

#### 27.1.6.1 Timer Mode

Timer mode is the basic mode of operation where the SMTxTMR register is used as a 24-bit timer. No data acquisition takes place in this mode. The timer increments as long as the GO bit has been set by software. No SMT window or SMT signal events affect the GO bit. Everything is synchronized to the SMT clock source. When the timer experiences a period match (SMTxTMR = SMTxPR), the SMTxTMR register is reset and the period match interrupt is set. Refer to the figure below.

Figure 27-3. Timer Mode Timing Diagram



#### 27.1.6.2 Gated Timer Mode

Gated Timer mode uses the SMT\_signal input, selected with the SSEL bits, to control whether or not the SMTxTMR register will increment. Upon a falling edge of the signal, the SMTxCPW register will update to the current value of the SMTxTMR register. Example waveforms for both repeated and single acquisitions are provided in the figures below.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 450

Figure 27-4. Gated Timer Mode, Repeat Acquisition Timing Diagram





Figure 27-5. Gated Timer Mode, Single Acquisition Timing Diagram



#### 27.1.6.3 Period and Duty Cycle Measurement Mode

In this mode, either the duty cycle or period of the input signal can be acquired relative to the SMT clock. The SMTxCPW register is updated on a falling edge of the signal, and the SMTxCPR register is updated on a rising edge of the signal. The rising edge also resets the SMTxTMR register to 0x000001. The GO bit is reset on a rising edge when the SMT is in Single Acquisition mode. Refer to the figures below.

Figure 27-6. Period and Duty Cycle, Repeat Acquisition Mode Timing Diagram





Figure 27-7. Period and Duty Cycle, Single Acquisition Mode Timing Diagram



#### 27.1.6.4 High and Low Measurement Mode

This mode measures the high and low pulse time of the SMT\_signal, relative to the SMT clock. The SMTxTMR register starts incrementing on a rising edge of the input signal. On the falling edge, the SMTxTMR register value is written to the SMTxCPW register. The SMTxTMR register is then reset and continues to increment. On the next rising edge, the SMTxTMR register value is written to the SMTxCPR register. The SMTxTMR register is then reset and continues to increment. Refer to the figures below.

Figure 27-8. High and Low Measurement Mode, Repeat Acquisition Timing Diagram





Figure 27-9. High and Low Measurement Mode, Single Acquisition Timing Diagram



### 27.1.6.5 Windowed Measurement Mode

This mode measures the period of the SMT\_window input, selected with the WSEL bits, relative to the SMT clock. On the rising edge of the window input, the SMTxTMR register value is written to the SMTxCPR register. In Repeat mode, the SMTxTMR register is reset and continues to increment. The capture and reset process repeats on the next rising edge. Refer to the figures below.

Figure 27-10. Windowed Measurement Mode, Repeat Acquisition Timing Diagram





Figure 27-11. Windowed Measurement Mode, Single Acquisition Timing Diagram



### 27.1.6.6 Gated Window Measurement Mode

This mode measures the duty cycle of the SMT\_signal input over a known input window. It does so by incrementing the SMTxTMR register on each rising edge of the SMTx clock signal when the SMT\_signal input is high. The accumulated SMTxTMR register value is written to the SMTxCPR register, and the SMTxTMR register is reset on every rising edge of the window input after the first. Refer to the figures below.

Figure 27-12. Gated Windowed Measurement Mode, Repeat Acquisition Timing Diagram





Figure 27-13. Gated Windowed Measurement Mode, Single Acquisition Timing Diagram



#### 27.1.6.7 Time-of-Flight Measurement Mode

This mode measures the time interval between a rising edge on the SMT\_window input and a rising edge on the SMT\_signal input. The SMTxTMR register starts incrementing on the rising edge of the window input. The SMTxTMR register value is written to the SMTxCPR register and the SMTxTMR register is reset on a rising edge of the signal input. In the event of two rising edges of the window signal without a signal rising edge, the SMTxCPW register will be written with the current value of the SMTxTMR register, which will then be reset. Refer to the figures below.

Figure 27-14. Time-of-Flight Mode, Repeat Acquisition Timing Diagram





Figure 27-15. Time-of-Flight Mode, Single Acquisition Timing Diagram



### 27.1.6.8 Capture Mode

This mode captures the SMTxTMR register value based on a rising or falling edge of the SMT\_window input and triggers an interrupt. This mimics the capture feature of a CCP module. The timer begins incrementing upon the GO bit being set. The SMTxTMR register value is written to the SMTxCPR register on each rising edge of the SMT\_window input. The SMTxTMR register value is written to the SMTxCPW register on each falling edge of the SMT\_window input. The timer is not reset by any hardware conditions in this mode and must be reset by software, if desired. Refer to the figures below.

Figure 27-16. Capture Mode, Repeat Acquisition Timing Diagram






Figure 27-17. Capture Mode, Single Acquisition Timing Diagram



### 27.1.6.9 Counter Mode

This mode increments the SMTxTMR register on each rising edge of the SMT\_signal input. This mode is asynchronous to the SMT clock and uses the SMT\_signal input as a time source. The SMTxCPW register will be updated with the current SMTxTMR register value on the falling edge of the SMT\_window input. Refer to the figure below.

Figure 27-18. Counter Mode Timing Diagram



#### 27.1.6.10 Gated Counter Mode

This mode counts rising edges on the SMT\_signal input, gated by the SMT\_window input. It increments the SMTxTMR register for each rising edge of the SMT\_signal input while the SMT\_window input is high. The SMTxTMR register value is written to the SMTxCPW register upon a falling edge of the SMT\_window input. Refer to the figures below.

Figure 27-19. Gated Counter Mode, Repeat Acquisition Timing Diagram





Figure 27-20. Gated Counter Mode, Single Acquisition Timing Diagram



#### 27.1.6.11 Windowed Counter Mode

This mode counts rising edges of the SMT\_signal between rising edges of the SMT\_window input. Beginning with the rising edge of the SMT\_window input, the SMTxTMR register is incremented for every rising edge of the SMT\_signal input. The SMTxTMR register value is written to the SMTxCPW register on the falling edge of the SMT\_window input and the SMTxTMR register continues to increment. The SMTxTMR register value is written to the SMTxCPR register, then reset on each rising edge of the SMT\_window input after the first. Refer to the figures below.

Figure 27-21. Windowed Counter Mode, Repeat Acquisition Timing Diagram





Figure 27-22. Windowed Counter Mode, Single Acquisition Timing Diagram



## 27.1.7 Interrupts

The SMT has three interrupts located in one of the PIR registers:

- Pulse Width Acquisition Interrupt (SMTxPWAIF): Interrupt triggers when the SMTxCPW register is updated with the SMTxTMR register value.
- **Period Acquisition Interrupt (SMTxPRAIF):** Interrupt triggers when the SMTxCPR register is updated with the SMTxTMR register value.
- Counter Period Match Interrupt (SMTxIF): Interrupt triggers when the SMTxTMR register equals the SMTxPR register.

Each of the above interrupts can be enabled/disabled using the corresponding bits in the PIE register.

#### 27.1.8 Operation During Sleep

The SMT can operate during Sleep mode, provided that the clock and signal sources continue to function. In general, internal clock sources, such as HFINTOSC, continue to operate in Sleep mode when selected as the clock source, whereas external oscillators, such as  $F_{OSC}$  and  $F_{OSC}/4$  cease to operate in Sleep.

# 27.2 Register Definitions: SMT Control

Long bit name prefixes for the SMT peripherals are shown in the table below. Replace the x in SMTx with the SMT peripheral instance number. Refer to the "Long Bit Names" section in the "Register and Nit Naming Conventions" chapter for more information.

Table 27-2. SMT Long Bit Name Prefixes

Peripheral	Bit Name Prefix
SMT1	SMT1

### 27.2.1 SMTxCON0

Name: SMTxCON0 Offset: 0x030C

SMT Control Register 0

Bit	7	6	5	4	3	2	1	0
	EN		STP	WPOL	SPOL	CPOL	PS	[1:0]
Access	R/W		R/W	R/W	R/W	R/W	R/W	R/W
Reset	0		0	0	0	0	0	0

### Bit 7 - EN SMT Enable

	Value	Description
ſ	1	SMT is enabled
	0	SMT is disabled; internal states are reset, clock requests are disabled

#### Bit 5 - STP SMT Counter Halt Enable

1	<b>V</b> alue	Condition	Description
-	1	When SMTxTMR = SMTxPR	Counter remains at SMTxPR; period match interrupt occurs when clocked
(	)	When SMTxTMR = SMTxPR	Counter resets to 0x000000; period match interrupt occurs when clocked

#### Bit 4 - WPOL SMT\_window Input Polarity Control

	/alue	Description
-	L	SMT_window input is active-low/falling edge enabled
(	)	SMT_window input is active-high/rising edge enabled

## Bit 3 - SPOL SMT\_signal Input Polarity Control

Value	Description
1	SMT_signal input is active-low/falling edge enabled
0	SMT_signal input is active-high/rising edge enabled

#### Bit 2 - CPOL SMT Clock Input Polarity Control

	zit z zi z zi				
Value	/alue Description				
1	SMTxTMR increments on the falling edge of the selected clock signal				
0	SMTxTMR increments on the rising edge of the selected clock signal				

# Bits 1:0 - PS[1:0] SMT Prescale Select

	1.101
Value	Description
11	Prescaler = 1:8
10	Prescaler = 1:4
01	Prescaler = 1:2
00	Prescaler = 1:1

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 461

# 27.2.2 SMTxCON1

Name: SMTxCON1 Offset: 0x030D

SMT Control Register 1

Bit	7	6	5	4	3	2	1	0
	GO	REPEAT				MOD	E[3:0]	
Access	R/W	R/W			R/W	R/W	R/W	R/W
Reset	0	0			0	0	0	0

### Bit 7 - GO SMT GO Data Acquisition

Value	Description
1	Incrementing, acquiring data is enabled
0	Incrementing, acquiring data is disabled

## Bit 6 - REPEAT SMT Repeat Acquisition Enable

Va	alue	Description			
1 Repeat Data Acquisition mode is enabled					
0 Single Acquisition mode is enabled		Single Acquisition mode is enabled			

### Bits 3:0 - MODE[3:0] SMT Operation Mode Select

	Bits 3:0 - MODE[3:0] SMT Operation Mode Select			
Value	Description			
1111	Reserved			
1110	Reserved			
1101	Reserved			
1100	Reserved			
1011	Reserved			
1010	Windowed Counter			
1001	Gated Counter			
1000	Counter			
0111	Capture			
0110	Time-of-Flight			
0101	Gated Windowed Measurement			
0100	Windowed Measurement			
0011	High and Low Time Measurement			
0010	Period and Duty-Cycle Acquisition			
0001	Gated Timer			
0000	Timer			

### 27.2.3 **SMTxSTAT**

Name: SMTxSTAT Offset: 0x030E

SMT Status Register

Bit	7	6	5	4	3	2	1	0
	CPRUP	CPWUP		RST		TS	WS	AS
Access	R/W/HC	R/W/HC		R/W		R	R	R
Reset	0	0		0		0	0	0

### Bit 7 - CPRUP SMT Manual Period Buffer Update

Value Description				
1 Request write of SMTxTMR value to SMTxCPR registers				
0	SMTxCPR registers update is complete			

# Bit 6 - CPWUP SMT Manual Pulse Width Buffer Update

	Value	Description			
1 Request write of SMTxTMR value to SMTxCPW registers					
	0	SMTxCPW registers update is complete			

### Bit 4 - RST SMT Manual Timer Reset

Value	Description
1	Request Reset to SMTxTMR registers
0	SMTxTMR registers update is complete

### Bit 2 - TS SMT GO Value Status

Value	Description
1	SMTxTMR is incrementing
0	SMTxTMR is not incrementing

### Bit 1 - WS SMT Window Status

ı	Value	Description
	1	SMT window is open
	0	SMT window is closed

# Bit 0 - AS SMT Signal Value Status


١	/alue	Description
1	=	SMT acquisition is in progress
(	)	SMT acquisition is not in progress

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 463

# 27.2.4 SMTxCLK

Name: SMTxCLK Offset: 0x030F

SMT Clock Selection Register




Bits 3:0 - CSEL[3:0] SMT Clock Selection

CSEL Value	SOURCE	Active in Sleep
1111-1001	Reserved	No
1000	CLKR	No
0111	EXTOSC	Yes
0110	SOSC	Yes
0101	MFINTOSC (32 kHz)	Yes
0100	MFINTOSC (500 kHz)	Yes
0011	LFINTOSC	Yes
0010	HFINTOSC	Yes
0001	FOSC	No
0000	FOSC/4	No

## 27.2.5 SMTxWIN

Name: SMTxWIN Offset: 0x0311

SMT Window Input Select Register



Bits 5:0 - WSEL[5:0] SMT Window Signal Selection

WSEL Value	Window Source	Active in Sleep
111111-101000	Reserved	No
100111	CLC8_OUT	No
100110	CLC7_OUT	No
100101	CLC6_OUT	No
100100	CLC5_OUT	No
100011	CLC4_OUT	No
100010	CLC3_OUT	No
100001	CLC2_OUT	No
100000	CLC1_OUT	No
011111	ZCD_OUT	No
011110	CMP2_OUT	No
011101	CMP1_OUT	No
011100	NCO3_OUT	No
011011	NCO2_OUT	No
011010	NCO1_OUT	No
011001	PWM4S1P2_OUT	No
011000	PWM4S1P1_OUT	No
010111	PWM3S1P2_OUT	No
010110	PWM3S1P1_OUT	No
010101	PWM2S1P2_OUT	No
010100	PWM2S1P1_OUT	No
010011	PWM1S1P2_OUT	No
010010	PWM1S1P1_OUT	No
010001	CCP3_OUT	No
010000	CCP2_OUT	No
001111	CCP1_OUT	No
001110-001100	Reserved	No
001011	TU16B_OUT	No
001010	TU16A_OUT	
001001	TMR6_Postscaler_OUT	No
001000	TMR4_Postscaler_OUT	No
000111	TMR2_Postscaler_OUT	No
000110	TMR0_OUT	No
000101	CLKREF	No
000100	EXTOSC	Yes


# **SMT - Signal Measurement Timer**

continued			
WSEL Value	Window Source	Active in Sleep	
000011	SOSC	Yes	
000010	MFINTOSC (32 kHz)	Yes	
000001	LFINTOSC	Yes	
000000	SMT1WINPPS	No	

# 27.2.6 SMTxSIG

Name: SMTxSIG Offset: 0x0310

SMT Signal Selection Register



Bits 5:0 - SSEL[5:0] SMT Signal Selection

SSEL Value	Source
111111-100110	Reserved
100101	CLC8_OUT
100100	CLC7_OUT
100011	CLC6_OUT
100010	CLC5_OUT
100001	CLC4_OUT
100000	CLC3_OUT
011111	CLC2_OUT
011110	CLC1_OUT
011101	ZCD_OUT
011100	CMP2_OUT
011011	CMP1_OUT
011010	NCO3_OUT
011001	NCO2_OUT
011000	NCO1_OUT
010111	PWM4S1P2_OUT
010110	PWM4S1P1_OUT
010101	PWM3S1P2_OUT
010100	PWM3S1P1_OUT
010011	PWM2S1P2_OUT
010010	PWM2S1P1_OUT
010001	PWM1S1P2_OUT
010000	PWM1S1P1_OUT
001111	CCP3_OUT
001110	CCP2_OUT
001101	CCP1_OUT
001100-001010	Reserved
001001	TU16B_OUT
001000	TU16A_OUT
000111	TMR6_Postscaler_OUT
000110	TMR5_OUT
000101	TMR4_Postscaler_OUT
000100	TMR3_OUT
000011	TMR2_Postscaler_OUT
000010	TMR1_OUT

# **SMT - Signal Measurement Timer**

continued		
SSEL Value	Source	
000001	TMR0_OUT	
000000	SMT1SIGPPS	

#### 27.2.7 SMTxTMR

Name: SMTxTMR Offset: 0x0300

SMT Timer Register

Bit	23	22	21	20	19	18	17	16
				TMR[	23:16]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	15	14	13	12	11	10	9	8
				TMR	[15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
				TMR	[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 23:0 - TMR[23:0] SMT Timer Value

- SMTxTMRU: Accesses the upper byte TMR[23:16]
- SMTxTMRH: Accesses the high byte TMR[15:8]
- SMTxTMRL: Accesses the low byte TMR[7:0]

#### 27.2.8 SMTxCPR

Name: SMTxCPR Offset: 0x0303

SMT Captured Period Register

Bit	23	22	21	20	19	18	17	16
				CPR[	23:16]			
Access	R	R	R	R	R	R	R	R
Reset	x	x	x	x	x	x	x	x
Bit	15	14	13	12	11	10	9	8
				CPR	[15:8]			
Access	R	R	R	R	R	R	R	R
Reset	x	x	x	x	x	x	x	x
Bit	7	6	5	4	3	2	1	0
				CPR	R[7:0]			
Access	R	R	R	R	R	R	R	R
Reset	x	x	x	x	x	x	x	x

Bits 23:0 - CPR[23:0] SMTxTMR Value at Time of Period Capture Event

All Other Resets = uuuuuuuuuuuuuuuuuuuuu

- SMTxCPRU: Accesses the upper byte CPR[23:16]
- SMTxCPRH: Accesses the high byte CPR[15:8]
- SMTxCPRL: Accesses the low byte CPR[7:0]

#### 27.2.9 SMTxCPW

Name: SMTxCPW Offset: 0x0306

SMT Captured Pulse Width Register

Bit	23	22	21	20	19	18	17	16
				CPW[	23:16]			
Access	R	R	R	R	R	R	R	R
Reset	x	x	x	x	x	x	x	x
Bit	15	14	13	12	11	10	9	8
				CPW	[15:8]			
Access	R	R	R	R	R	R	R	R
Reset	x	X	X	X	X	X	X	X
Bit	7	6	5	4	3	2	1	0
				CPW	/[7:0]			
Access	R	R	R	R	R	R	R	R
Reset	x	x	x	x	x	x	x	x

Bits 23:0 - CPW[23:0] SMTxTMR Value at Time of Capture Event

All Other Resets = uuuuuuuuuuuuuuuuuuuuu

- SMTxCPWU: Accesses the upper byte CPW[23:16]
- SMTxCPWH: Accesses the high byte CPW[15:8]
- SMTxCPWL: Accesses the low byte CPW[7:0]

### 27.2.10 SMTxPR

Name: SMTxPR Offset: 0x0309

SMT Period Register

Bit	23	22	21	20	19	18	17	16
				PR[2	3:16]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1
Bit	15	14	13	12	11	10	9	8
				PR[	15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1
Bit	7	6	5	4	3	2	1	0
				PR[	[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

Bits 23:0 - PR[23:0] The SMTxTMR Value at Which the SMTxTMR Resets to Zero

- SMTxPRU: Accesses the upper byte PR[23:16]
- SMTxPRH: Accesses the high byte PR[15:8]
- SMTxPRL: Accesses the low byte PR[7:0]

# 27.3 Register Summary - SMT Control

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x02FF										
		7:0		-	:	TMF	R[7:0]		-	:
0x0300	SMT1TMR	15:8				TMR	[15:8]			
		23:16				TMR[	23:16]			
		7:0				CPF	R[7:0]			
0x0303	SMT1CPR	15:8				CPR	[15:8]			
		23:16				CPR[	23:16]			
		7:0	CPW[7:0]							
0x0306	SMT1CPW	15:8		CPW[15:8]						
		23:16				CPW	23:16]			
		7:0				PR	[7:0]			
0x0309	SMT1PR	15:8				PR[	15:8]			
		23:16				PR[2	3:16]			
0x030C	SMT1CON0	7:0	EN		STP	WPOL	SPOL	CPOL	PS	[1:0]
0x030D	SMT1CON1	7:0	GO REPEAT MODE[3:0]				E[3:0]	-		
0x030E	SMT1STAT	7:0	CPRUP	CPWUP		RST		TS	WS	AS
0x030F	SMT1CLK	7:0						CSE	L[3:0]	
0x0310	SMT1SIG	7:0					SSE	L[5:0]		
0x0311	SMT1WIN	7:0		WSEL[5:0]						

### 28. UTMR - Universal Timer Module


The UTMR Universal Timer module is a 16-bit timer/counter with a combination of signal measurement and hardware limit timer functions. It is designed to provide all timer/counter related functions in a single peripheral and includes the following list of features:

- Master/Slave chaining, which allows two timer/counters to be combined into a single larger timer/counter with a single set of control registers
- · Software independent operation, including both signal measurement and hardware limit features
  - External Reset (ERS) inputs
  - Individual control of Start, Stop and Reset
  - Hardware Limit mode
  - One-Shot mode
- · Full asynchronous clocking
  - Multiple clock selections
  - Synchronization circuitry for control bit and ERS inputs
  - Integrated fully programmable prescaler
- Dual Output modes
  - Pulse output
  - Level output
  - Output polarity control
- · Double-buffered Period register
  - Compatible with DMA control
  - Interrupt, Stop or Reset On Match
- · Interrupt on Start, Stop and Reset

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 474

PIC18F26/46/56Q84
UTMR - Universal Timer Module

Figure 28-1. Universal Timer Block Diagram



### 28.1 Module Nomenclature

The following nomenclature is used for this module on this device:

Table 28-1. Module Nomenclature

Timer Size (x)	Instance (y)	Module (TUxy)
16 bits	A	TU16A
16 bits	В	TU16B

#### 28.2 Clock Source Selection

The TUxyCLK register bits select the clock source for the UTMR module. These bits allow the selection of several possible synchronous and asynchronous clock sources. Because the selected clock source also controls the optional synchronization of all external signals for the UTMR module, delays between the selection of a function and its action may vary according to the frequency of the selected clock source relative to the microcontroller's clock frequency. See Synchronous vs. Synchronous Operation for more details.

When an internal clock source is selected (clock derived from system oscillator), the choice of clock source will affect the increment rate of the TUxyTMR register, relative to the system instruction rate. When an external clock source is selected (a clock not derived from the system oscillator), the UTMR module will work as either a timer or a counter. When enabled to count and the CPOL bit is set, the TUxyTMR counter register is incremented on the rising edge of the selected external source. For increment on the falling edge of the selected external clock source, the CPOL bit must be cleared. When operating from an external clock source, the CSYNC bit should also be set to synchronize the controls and ERS signals to the clock domain of the selected external clock.



**Important:** Due to the inherent uncertainty of reading or writing a 16-bit timer with an 8-bit bus and operating from an asynchronous clock source, it is recommended that read/write of the timer registers use the CAPT and the CLR commands. Refer to Timer Counter and Capture Registers for more information.

#### 28.3 UTMR Prescaler

The UTMR module has a fully programmable 8-bit prescaler, allowing division of the clock input by 1 to 256. The prescaler register TUxyPS is programmed with the desired prescaler value minus one. For example, for a 10:1 prescaler value, the TUxyPS register would be loaded with 0x09. The internal prescaler counter is not directly readable or writable; however, the prescaler counter is cleared upon a Reset of the TUxyTMR counter register. See Figure 28-4 and Figure 28-5 for examples of how the counter timing works with respect to a prescaler.

### 28.4 UTMR Operation

The basic UTMR module has a counter/timer, a double-buffered period register, and a hardwired compare function. Together with an External Reset Selector (ERS), Clock Selection Mux, and programmable Start/Stop/Reset logic, the module can be configured for a variety of hardware limit and signal measurement functions. See Figure 28-1 for the UTMR module block diagram.

Available options include:

- 1. Synchronous or asynchronous operation
- 2. Software control via the ON bit
- 3. Asynchronous read and reset of the counter/timer using the CAPT and CLR bits
- 4. Selection of a variety of hardware ERS inputs
- 5. A variety of both software and hardware triggers for start, stop and reset events
- 6. A Limit mode that stops the counter/timer on a period register match

#### 7. A One-Shot/Monostable mode option

Together, the various combination of options implements all the functions for both a signal measurement and hardware limit timer.


### 28.4.1 Synchronous vs. Asynchronous Operation

A new feature of the UTMR module is the isolation of the counter/timer and its control logic to a separate timer clock domain. This can simplify and accelerate the operation of the timer when running on an external clock source. Unfortunately, it also makes the control bits in the timer control registers asynchronous to the timer clock domain. It is, therefore, necessary to synchronize the timer control register bits to the timer clock domain by setting the CSYNC bit in the TUxyHLT register. This will cause the synchronization of both the ERS inputs and control register bits to the selected counter/timer clock, and allow the module to operate completely asynchronous from the system clock.

The synchronization logic produces a delay between the assertion of a signal and its effect in operation. Any signal that goes from the processor domain to the timer domain (like assertion/de-assertion of ON or ERS controls) requires three counter/timer clocks to synchronize. Any signal that goes from the timer domain to the processor domain (like assertion/de-assertion of ON bit, RUN bit, ERS controls, output and interrupt signals) requires three system clocks to synchronize. This delay is generally acceptable in synchronous applications because the start, reset and stop events are delayed equally, and there is no net change to the counter sequence.

Figure 28-2 shows clock synchronization with the ON bit (Start) and ERS Reset (Stop), whereas Figure 28-3 shows clock synchronization with setting/clearing of the ON bit (Start/Stop). If an external clock source is selected, then the UTMR will also continue to run during Sleep and can generate interrupts on Start, Stop or Reset, which will wake-up the processor.

Figure 28-2. Clock Synchronization with ON bit and Stop Condition



### Note:

1. Not to scale; clocks are not shown.




Figure 28-3. Clock Synchronization with ON bit and Off Condition

#### Note:

1. Not to scale; clocks are not shown.

Clearing the CSYNC bit will disable the synchronization logic. When CSYNC = 0, ERS asynchronously gates the clock and/or resets the timer, according to Start, Reset and Stop options. It is possible that the timer clock may transition at the same time that the ON bit is set by the user or an ERS event occurs or a CLR or CAPT command is passed (a clock collision), which may cause unpredictable results to the counter value. Setting CSYNC = 1 removes this uncertainty.



**Important:** Using an external clock synchronizer, like the CLC or the comparator sync logic, can allow synchronous applications with CSYNC = 0, but clock rate limitations may apply at the device level.

set CIF

ON bit must be set for all counting operations. With START = \b00 (no ERS Start), setting ON will start the timer as though a Start condition occurred. With START > \b00 (ERS edge/level-triggers Start), setting ON prepares the timer for an ERS Start condition and enables the ERS detection logic.

ON will return to '0' when a hardware Stop condition occurs or when written by software, except as noted in One-Shot Mode. Figure 28-4 and Figure 28-5 below show timing examples for One-Shot mode with CSYNC = 1 and CSYNC = 0, respectively.




Figure 28-4. Synchronization and Prescaler Timing (CSYNC = 1)

PR = 4 (Period of 5) PS = 2 (Prescaler of 3)

- 1. The ON bit is set in the software and cleared by hardware upon Stop (one-shot mode).
- 2. The RUN trace illustrates the actual RUN SFR bit and not the internal Timer Clock domain run/ stop signal.
- 3. Ensure that TUxyTMR counter is reset to zero by setting CLR command.
- 4. Cleared by software.




Figure 28-5. Synchronization and Prescaler Timing (CSYNC = 0)

START = None (ON = 1) RESET = At PR Match S
CSYNC = Async OSEN = Enabled
PR = 4 (Period of 5) PS = 2 (Prescaler of 3)

#### Note:

- 1. The ON bit is set in the software and cleared by hardware upon Stop (one-shot mode).
- 2. The RUN trace illustrates the actual RUN SFR bit and not the internal Timer Clock domain run/stop signal.
- 3. Ensure that TUxyTMR counter is reset to zero by setting CLR command.
- 4. Cleared by software.

#### 28.4.2 Timer Counter and Capture Registers

The UTMR module has two registers to access the timer/counter value – TUxyTMR counter register and TUxyCR capture register. The size of these registers is the same as the size of the timer. Both registers share the same memory location and are addressed based on the RDSEL bit in the TUxyCON0 register. Setting the RDSEL bit addresses the TUxyTMR counter register, whereas clearing the RDSEL bit addresses the TUxyCR capture register.

To read the raw counter value using the TUxyTMR counter register, the RDSEL bit must be set. When the timer is running in either Synchronous or Asynchronous mode, directly reading the TUxyTMR counter register can produce


erroneous values. This can occur when the counter/timer is operating from an asynchronous clock source or when the read happens coincidentally with the rollover of the bottom 8-bits of the TUxyTMR counter register.

Clearing the RDSEL bit directs all counter/timer reads through the TUxyCR capture register. The TUxyCR capture register is functionally a read-only register and is loaded directly from the counter/timer in response to either of the following three conditions:

- 1. Setting the CAPT command bit.
- 2. When a stop event is generated.
- 3. In the event of an ERS rising edge (or falling edge based on EPOL bit selection) if the Stop condition is set to none. See Stop Event for more details on Stop condition.

It is generally recommended that any read of the timer, when it is running, should utilize the CAPT command bit with the RDSEL bit clear. Asserting the CAPT bit will cause synchronous transfer of the timer value to the TUxyCR capture register. The CAPT bit remains set until the capture is complete. The TUxyCR capture register can then be read by the processor without any data corruption. See Figure 28-6 for an example of the CAPT bit operation.

Figure 28-6. CAPT Bit Operation



#### Timer Setup:

START = None (ON = 1) RESET = At PR Match STOP = None CSYNC = Sync

#### Note:

- 1. Cross-domain clock synchronization applies as required but is not highlighted.
- The RUN trace illustrates the internal Timer Clock domain run/stop signal. Clock sync delays apply before the value appears in the RUN SFR bit.
- 3. The uncertainty of the output is due to the prescaler setting.
- 4. Cleared by software.

In the event of an ERS rising capture, the TUxyCR capture register must be read before the event of a second ERS rising or the data captured will be overwritten by the second rising event.

The TUxyTMR counter register can be written when the RDSEL bit is set, provided that the ON bit is clear. Attempting to write to the TUxyTMR counter register with the ON bit set can result in corrupted data. If the intention is to clear the counter, the CLR command bit should be used instead of writing zeros. Asserting the CLR bit clears the TUxyTMR counter register, even if the ON bit is set. The CLR bit remains set until the counter is reset.

The CAPT and CLR command bits are subject to synchronization delays which is dependent on the settings of CSYNC and ON bits as shown in Table 28-2 below.

Table 28-2. Behavior of CAPT and CLR Commands with respect to ON and CSYNC Bits

ON Bit	CSYNC Bit	Behavior of CAPT and CLR Commands
1 (Timer Running)	1	Synchronization delay of three timer clock cycles applies before the desired action is performed.
1 (Timer Running)	0	No synchronization delay applies. Desired action is performed immediately.
0 (Timer Stopped)	1	Synchronization delay of three timer clock cycles applies. The desired action is delayed until timer clock resumes.
0 (Timer Stopped)	0	No synchronization delay applies. Desired action is performed immediately.



#### Important:

- Reading and writing the TUxyTMR counter register when the timer is running (ON = 1) is not recommended. TUxyTMR counter register should be read or written to only when the timer is stopped (ON = 0) to prevent data corruption.
- 2. The TUxyTMR register, like many othe registers in the module, remains unchanged after a non-POR/BOR system reset. It is recommended to always clear this register at the start of program execution to avoid counting from an unknown value.
- Setting the CLR bit does not reset the TUxyCR capture register.
- 4. The TUxyTMR register should not be written as a means to change the effective period. If the intention is to change the timer period, the TUxyPR period register should be changed instead. See Timer Period Register for more details on how to change the timer period while the timer is running.
- 5. When software sets a CLR or CAPT command bit, the bit-value of '1' is indicated in the SFR immediately, to indicate that the over-and-back clock synchronization is not complete. However, a sufficiently high timer clock frequency might complete the cross-domain synchronization within one instruction cycle and the bit value would always appear to be '0'.
- 6. Setting CLR or CAPT command bits to '0' has no effect.
- 7. The timer starts counting by incrementing the TUxyTMR value to the next valid counter value. For instance, if the counter is in reset state (TUxyTMR = 0) then the timer starts counting from 1. If the TUxyTMR = PR and RESET = at PR Match, then the timer will start counting by resetting the counter to zero first.

#### 28.4.3 Timer Period Register

The TUxyPR period register establishes the period of the periodic timer operation or the duration of hardware limit timing. The register size is the same as the timer size and is initialized to the maximum value.

The TUxyPR period register is double-buffered to simplify software timing and provide atomic updates. Writing to the higher bytes of TUxyPR always stores data into buffer registers, but does not change the effective PR value. If the timer is not counting (ON = 0), writing to the Least Significant Byte will change the effective PR value immediately to the full buffered value. If the timer is counting (ON = 1), writing to the LSB of TUxyPR is also buffered and is considered armed for an update. When a second qualifying event occurs, which is a Reset event, the effective PR value is changed to the full buffered value.



#### Important:

- 1. Writing to MSBs after arming the load can lead to corrupted operation.
- Reading the TUxyPR period register returns the most-recently written value, not necessarily the current effective PR value.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 482

#### 28.4.4 External Reset Source (ERS)


An External Reset Source (ERS) is an external input to the timer module that can be used to trigger Start, Reset and Stop conditions for the timer. It can be selected by configuring the TUxyERS selection register and goes through edge/level detection and synchronization as shown in Figure 28-7. The polarity of the ERS signal is selected using the EPOL bit in the TUxyHLT register. Setting the EPOL bit will invert the state of the selected ERS source. Also included is a 'Continuous mode' selection for Start/Stop conditions to provide an ERS-independent software controlled start/stop option. See Start, Stop and Reset Events for start, stop and reset events.



#### Important:

- 1. Actions involving ERS require the ON bit to be set and a running clock.
- 2. The EPOL bit should not be changed when ON = 1. Changing EPOL will spontaneously cause an edge event and can cause timer output to flip.

Figure 28-7. ERS Edge/Level Detection, Synchronization and Polarity Control



#### 28.4.5 Start, Stop and Reset Events

To enable the counter/timer, the ON bit of the TUxyCON0 register must be set. When ON = 0, the module is disabled, and the module output is cleared.

When the module is disabled, the following things apply:

- 1. RUN SFR bit is cleared.
- 2. OPOL bit in the TUxyCON0 register will continue to control the output polarity.
- 3. ERS input logic is reset and disabled.
- 4. Interrupts will not trigger.
- 5. Clock requests are not asserted.
- All SFRs can be written.



#### Important:

- The value of the TUxyTMR counter and TUxyCR capture registers are not affected when the ON bit is clear, unless they are changed explicitly by the user.
- Clock synchronization may apply, in which case, actions performed may or may not have immediate effect
- 3. The ON bit, like many other bits in the module, remains unchanged after a non-POR/BOR system reset. It is recommended to clear the ON bit at the start of program execution to avoid starting the system with a running timer.

#### 28.4.5.1 Start Event

The start event for the counter/timer start is selected using the START bits in the TUxyHLT register. The available options include:

- 1. No hardware Start: The counter/timer starts when the ON bit is set. This is the software-based start option. Any Stop events are ignored, but will still cause a capture.
- Either edge of the ERS signal (edge-triggered): The counter/timer starts at the event of either the rising or falling edge of the ERS signal.
- Rising edge of the ERS signal (edge-triggered): The counter/timer starts at the event of a rising edge of the ERS signal. When the EPOL bit is set, the polarity is inverted and the counter/timer starts at the event of a falling edge of ERS signal. See Figure 28-10 for an example of rising ERS edge Start and either ERS edge Stop condition.
- 4. ERS = 1 (level-triggered): The counter/timer starts at the presence of a logic one of the ERS signal. When the EPOL bit is set, the polarity is inverted and the counter/timer starts at the presence of a logic zero of the ERS signal. Any Stop events that occur when ERS = 1 (or 0, based on EPOL) are ignored, but will still cause a capture. See Figure 28-11 for an example of level-triggered Start.



#### Important:

 In the event of a level-triggered Start/Reset, the active level must be asserted for at least one timer clock period to ensure proper sampling. If the duration of the asserted level is less than one timer clock, there is a possibility of the level trigger being missed and not sampled by the timer module.

#### 28.4.5.2 Reset Event

The Reset event for the counter/timer Reset is selected using the RESET bits in the TUxyHLT register. The Reset function dominates the operation of the counter.

The available options include:


- 1. No hardware Reset: No hardware Reset of the counter/timer. The counter will continue to the full value and roll over to zero.
- 2. ERS = 0 (level-triggered): The counter/timer resets at the presence of a logic zero of the ERS signal and/or when the TUxyTMR counter register is equal to the TUxyPR period register. When the EPOL bit is set, the polarity is inverted and the counter/timer resets at the presence of a logic one of the ERS signal. This prevents any start event from advancing the counter and RUN bit is held at zero. See Figure 28-9 for an example of a level-triggered ERS Reset.<sup>(2)</sup>
- 3. At a start event: The counter/timer resets at the first clock of the counter/timer start and/or when the TUxyTMR counter register is equal to the TUxyPR period register. The number of cycles needed to reach PR match is extended by one. If the Start condition is ERS = 1 (or ERS = 0, based on EPOL selection), the Reset will only apply to the leading ERS edge. See Figure 28-11 for an example of Reset at a Start event.<sup>(2)</sup>
- 4. At period match: The counter/timer resets when TUxyTMR counter register is equal to the TUxyPR period register.



#### Important:

- 1. If the counter is already zero, a Reset event will not trigger ZIF interrupt.
- 2. When prescaler > 0, then any ERS or Start-based Reset event that occurs during a PR match period will reset the timer counter and prescaler counter immediately, and the pulse output will not occur. If the Reset event collides with the pulse output (regardless of prescaler setting), then the pulse output will occur naturally and the counter will reset at the next prescaler counter naturally.
- 3. In the event of a level-triggered Start/Reset, the active level must be asserted for at least one timer clock period to ensure proper sampling. If the duration of the asserted level is less than one timer clock, there is a possibility of the level trigger being missed and not sampled by the timer module.

Figure 28-8. Coincidental Start and Stop




#### **Timer Setup:**

START = Rising ERS Edge RESET = At Start+PR Match STOP = Rising ERS Edge CSYNC = Sync

- 1. Cross-domain clock synchronization applies as required but is not highlighted.
- A coincident Start/Stop condition that starts the counter does not cause either a capture or CIF to be set.
- 3. A synchronous edge-triggered Start/Stop condition is one timer clock cycle wide internally.
- 4. The RUN trace illustrates the internal Timer Clock domain run/stop signal. Clock sync delays apply before the value appears in the RUN SFR bit.
- 5. The uncertainty of the output is due to the prescaler setting.
- 6. Timer Out (Level) rises along with ERS when START = Rising/Either ERS Edge.
- 7. Cleared by software.

Figure 28-9. ERS = 0 Level Reset



#### **Timer Setup:**

START = None (ON = 1)CSYNC = Sync

RESET = ERS Level-0+PR Match OSEN = Enabled

STOP = Either ERS Edge

- 1. Cross-domain clock synchronization applies as required but is not highlighted.
- 2. The ON bit is set in the software and cleared by hardware upon Stop (one-shot mode).
- 3. The RUN trace illustrates the internal Timer Clock domain run/stop signal. Clock sync delays apply before the value appears in the RUN SFR bit.
- 4. The uncertainty of the output is due to the prescaler setting.
- 5. Cleared by software.




Figure 28-10. Rising Edge Start and Either Edge Stop

- 1. Cross-domain clock synchronization applies as required but is not highlighted.
- 2. TOP represents the maximum counter value.
- 3. The RUN trace illustrates the internal Timer Clock domain run/stop signal. Clock sync delays apply before the value appears in the RUN SFR bit.
- 4. The uncertainty of the output is due to the prescaler setting.
- 5. Timer Out (Level) rises along with ERS when START = Rising/Either ERS Edge.
- 6. Timer Out (Level) falls synchronous to the timer clock.
- 7. Cleared by software.




Figure 28-11. Reset at Level Start and Stop at PR Match

#### **Timer Setup:**

START = ERS Level-1 CSYNC = Sync

RESET = At Start+PR Match

STOP = At PR Match

- 1. Cross-domain clock synchronization applies as required but is not highlighted.
- 2. The RUN trace illustrates the internal Timer Clock domain run/stop signal. Clock sync delays apply before the value appears in the RUN SFR bit.
- 3. The uncertainty of the output is due to the prescaler setting.
- 4. Cleared by software.

#### 28.4.5.3 Stop Event

The stop event for the counter/timer stop is selected using the STOP bits in the TUxyHLT register. The available options include:

- No hardware Stop: The counter/timer runs continuously until the ON bit is cleared. Neither the ERS signal nor a PR register match will stop the counter/timer. This is the software-controlled stop option. The current counter value is captured in the TUxyCR capture register at every rising edge of ERS signal, in which case the TUxyCR capture register must be read before the event of a second ERS rising or the captured data will be overwritten by the second rising event. When the EPOL bit is set, the polarity is inverted and the counter value is captured at every falling edge of ERS signal instead.
- Either edge of the ERS signal (edge-triggered): The counter/timer stops at the event of either the rising or falling edge of the ERS signal and the counter value is captured in the TUxyCR capture register. See Figure 28-10 for an example of rising ERS edge Start and either ERS edge Stop condition.
- Rising edge of the ERS signal (edge-triggered): The counter/timer stops at the event of a rising edge of the ERS signal and the counter value is captured in the TUxyCR capture register. When the EPOL bit is set, the polarity is inverted and the counter/timer stops at the falling edge of the ERS signal.
- At period match: The counter/timer stops when the TUxyTMR counter register is equal to the TUxyPR period register and the counter value is captured in the TUxyCR capture register. See Figure 28-11 for an example of Stop at PR match.



#### Important:

- In the event of coincidental start and stop events, and RUN = 0; the start event takes precedence, timer capture and CIF interrupt are blocked, and OSEN is ignored. See Figure 28-8 for a coincidental start and stop event at ERS rising edge. If RUN = 1, then the stop event is ignored, but will still cause a capture.
- If Reset and Stop are coincident, the captured value is the value prior to the Reset and the counter will stop at zero.
- 3. After stopping, the start edge detector needs up to 3 timer clock periods to resume, and any overlapping stop events may be ignored in that interval.
- If the counter is not running (no start has occurred), a stop event will have no side effects, like capturing data.

#### 28.4.6 Hardware Limit Mode

The Limit mode of operation is controlled by the LIMIT bit in the TUxyCON1 register. Setting the LIMIT bit will cause the counter/timer value to not advance when the TUxyTMR counter register value equals the value in the TUxyPR period register (even though the timer is still "running"). If the LIMIT bit is cleared, the counter/timer will continue to count through the PR match and roll over at the maximum value of the TUxyTMR counter register. The LIMIT bit is not synchronized to the counter/timer clock and should not be changed when the ON bit is set.



#### Important:

- 1. This bit is relevant when RESET = `b00 (No hardware reset) and counter equals PR.
- The effect of Limit mode is to prevent the counter from exceeding PR value. Reset and CLR events are not prevented from clearing the counter.

### 28.4.7 One-Shot Mode


The One-Shot mode is enabled by setting the OSEN bit in the TUxyCON1 register. When the OSEN bit is set, the counter/timer will increment until a Stop condition is detected. At that time, the ON bit will be cleared and the counter/timer will stop. See Figure 28-12 for an example of One-Shot mode.



**Important:** In One-Shot mode, a Stop condition clears the ON bit, even if it coincides with another Start event. If a Stop event occurs prior to Start, that Stop condition does not clear ON bit.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 489

Figure 28-12. One-Shot Mode



### **Timer Setup:**

START = None (ON = 1) CSYNC = Sync

RESET = At PR Match OSEN = Enabled STOP = At PR Match

#### Note:

- 1. Cross-domain clock synchronization applies as required but is not highlighted.
- 2. Ensure that TUxyTMR counter is reset to zero by setting CLR command.
- 3. The ON bit is set in the software and cleared by hardware upon Stop (one-shot mode).
- 4. The RUN trace illustrates the internal Timer Clock domain run/stop signal. Clock sync delays apply before the value appears in the RUN SFR bit.
- 5. The uncertainty of the output is due to the prescaler setting.
- 6. Cleared by software.

#### 28.4.8 Run Status Flag

In all modes of operation, the RUN status bit in the TUxyCON1 register is set whenever the counter/timer is active (after a Start event, but before a Stop condition). The RUN bit will remain set through a Reset condition<sup>(1)</sup>. Note that the RUN status bit is synchronous to the counter/timer clock and updates may be delayed. Refer to Synchronous vs. Asynchronous Operation for details about clock synchronization.



#### Important:

- 1. The RUN bit is held at zero if a Start has occurred (the counter is "running"), but ERS is holding the counter at the value zero when RESET = \b01 (level-triggered).
- 2. The RUN status bit lags the internal run/stop state by two to three instruction cycles. If Start and Stop occur rapidly in succession, the RUN bit may not be set at all.

### 28.5 UTMR Output Modes

The UTMR module can generate either a pulsed or level output. When the OM bit in the TUxyCON0 register is set, the output will follow the Run/Stop state of the counter timer (level output), set to indicate that the timer is running,

### **UTMR - Universal Timer Module**

and cleared to indicate the timer has stopped. The output remains set through all Reset conditions, except when ERS is holding the timer/counter in a Reset state (RESET = `b11, level ERS Reset).

When the OM bit is cleared, the timer output is pulsed high at every period match (pulse output). The duration of the pulse is one single primary clock period at the end of the counter match period, regardless of the prescaler. This is demonstrated in Figure 28-4 and Figure 28-5 where the pulse output occurs only during the last timer clock period during the PR match.

The polarity of the output (pulsed or level) is controlled by the OPOL bit in the TUxyCON0 register. When OPOL is set, the output will either pulse low or be held low when timer output is active. When OPOL is cleared, the output will be either pulse high or be held high when timer output is active. The OPOL bit will control the output polarity of the module even when the module is disabled (ON = 0).



#### Important:

- When START = 'b01 or 'b10 (edge-triggered), the level output is asserted as soon as the qualified ERS edge is registered without any synchronization delays (even when CSYNC = 1).
- When LIMIT = 1, the pulse output will assert as indicated and will remain asserted until the counter changes from PR.
- 3. The OPOL bit does not affect the polarity of the RUN SFR bit.

### 28.6 Interrupt and DMA Triggers

The Universal Timer module provides three interrupt sources - Period Register match, Zero and Capture.

- A PR match interrupt occurs and the PRIF interrupt flag in the TUxyCON1 register is set when the TUxyTMR
  counter register increments and becomes equal to the TUxyPR period register. The PRIF interrupt will not
  occur if the user writes the PR value to the TUxyTMR counter register directly.
- 2. A zero interrupt occurs and the ZIF interrupt flag in the TUxyCON1 register is set when the TUxyTMR counter register becomes equal to zero. This occurs when:
  - A Reset condition resets the counter to zero, or
  - Software sets the CLR command bit, or
  - Counter naturally overflows to zero, or
  - User writes zero to the TUxyTMR counter register directly.
- A capture interrupt occurs and the CIF interrupt flag in the TUxyCON1 register is set whenever a capture event
  occurs, and the TUxyCR capture register is updated with the counter value. See Timer Counter and Capture
  Registers for a list of capture event conditions. The CIF interrupt trigger requires a running timer.

Each interrupt has a corresponding enable bit in the TUxyCON0 register (PRIE, ZIE, and CIE). Setting any of the three interrupt enable bits will allow the module to generate a corresponding interrupt. The interrupt flags (PRIF, ZIF and CIF) will set even if the corresponding interrupt is disabled.

All the three interrupt flags are combined together to form one single, top system level TUxyIF interrupt flag in the PIRx register as shown in Figure 28-13. The TUxyIF interrupt flag is a read-only bit in the PIRx register, which is automatically cleared when all the three interrupt flags (PRIF, ZIF and CIF) are cleared.


The Universal Timer module also provides the three interrupt sources to trigger DMA transfers (PRIF, ZIF and CIF conditions). The TUxyPR period register is also double-buffered to facilitate DMA loading of the register in response to a CIF interrupt trigger.



#### Important:

- The interrupts need not be enabled with their associated enable bits to be used as triggers for DMA transfer
- The interrupts must be enabled for the TUxyIF flag to be set in the PIRx register as shown in Figure 28-13.

Figure 28-13. Interrupt and DMA Trigger



### 28.7 Operation During Sleep

When the processor is asleep, the counter will hold the selected clock source active and continue to operate as configured. Because the counter/timer module can generate interrupts, the module is also capable of waking up the processor.

### 28.8 Chaining Counter Timers

A feature of the Universal Timer module is the ability to chain two counter/timers into a single module. Setting the CHxyz bit in the TUCHAIN register will combine two instances of Universal Timers into a single bigger Timer module. When two Universal Timer modules are chained, one of them becomes the primary module (Master), whereas the other becomes the secondary module (Slave). The Master module forms the least significant segment of the combined counter/timer whereas the Slave module forms the most significant segment. Figure 28-14 shows the Master/Slave configuration of the Chained Operational Model.

When operating in this configuration, control of the combined counter/timer is via the TUxyCON0, TUxyCON1, TUxyPS, TUxyCLK, TUxyERS, and TUxyHLT registers of the Master module. The same registers of the Slave module become defunct. The timer output, interrupts and DMA triggers for the combined timer/counter are generated by the Master module.

The TUxyTMR counter, TUxyCR capture, and TUxyPR period registers of both the Master and Slave modules are combined respectively, to provide higher-width register control for the combined counter/timer.

The timer chaining in this device is as follows:


# PIC18F26/46/56Q84

## **UTMR - Universal Timer Module**

### Table 28-3. Timer Chaining

TUxy Instance	Master/Slave	TUCHAIN Control Bit	Chained Timer Size
TU16A (16-bit)	Master (Least Significant Segment)	CH16AB	32-bit
TU16B (16-bit)	Slave (Most Significant Segment)	CITIOAD	32-bit

Figure 28-14. Chained Operational Model



#### Note:

- 1. This is a conceptual diagram only.
- 2. Control registers, state machine, prescaler and input ERS and clock for slave is not used. Rather they are derived from the master segment.

### 28.9 Register Definitions: Universal Timer

Long bit name prefixes for the UTMR peripherals are shown in the following table. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

# PIC18F26/46/56Q84

## **UTMR - Universal Timer Module**

### Table 28-4. Universal Timer Long bit name prefixes

Peripheral	Bit Name Prefix
TU16A	TU16A
TU16B	TU16B

### 28.9.1 TUxyCON0

Name: TUxyCON0

Timer Control Register 0

Bit	7	6	5	4	3	2	1	0
	ON	CPOL	ОМ	OPOL	RDSEL	PRIE	ZIE	CIE
Access	R/W/HC	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bit 7 – ON Timer Enable<sup>(1,2)</sup> Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	The module is enabled
0	The module is disabled and in the lowest-power mode

Bit 6 - CPOL Timer Clock Polarity Select (3,4)

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	The counter advances with the clock rising edge
0	The counter advances with the clock falling edge

Bit 5 - OM Timer Output Mode Select

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	Output is in Level mode
0	Output is in Pulse mode

Bit 4 - OPOL Timer Output Polarity Select(5)

Reset States: POR/BOR = 0

All Other Resets = u

	7 til Ottlor ( toocte – u
Value	Description
1	Output is high when the timer is idle
0	Output is low when the timer is idle

Bit 3 - RDSEL Timer Readout Mode Select(6,7,8)

The RDSEL bit selects the addressing of TUxyTMR and TUxyCR registers. See Timer Counter and Capture Registers for details.

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	TUxyTMR reads/write the value of the raw counter
0	TUxyCR reads the value of the capture register

Bit 2 – PRIE Period Match Interrupt Enable<sup>(9,10)</sup>

Reset States: POR/BOR = 0

All Other Resets = u

Val	lue	Description
1		PRIF interrupt will occur when the counter increments from PR-1 to PR
0		PRIF interrupt is disabled

Bit 1 – ZIE Zero Interrupt Enable<sup>(9)</sup>

Reset States: POR/BOR = 0

### PIC18F26/46/56Q84

### **UTMR - Universal Timer Module**

	All Other Resets = u		
Value	Description		
1	ZIF interrupt will occur when the counter becomes zero from a non-zero value		
0	ZIF interrupt is disabled		

Bit 0 - CIE Capture Interrupt Enable (9,11)

Reset States: POR/BOR = 0
All Other Resets = u

Value	Description		
1	CIF interrupt will occur when a capture event occurs		
0	CIF interrupt is disabled		

- 1. The selected clock will be enabled when this bit is set and a Start condition has occurred.
- 2. When this bit is set and CSYNC = 1, it takes three timer clocks to synchronize. When this bit is cleared and CSYNC = 1, the selected clock source (especially external clock sources) must supply at least three additional clocks to resolve internal states. During this time, if the timer is already running, any stop/reset related ERS events that get processed will continue to affect the run state of the timer. If CSYNC = 0, the ON bit clears immediately and the timer stops immediately.
- 3. This bit is not clock synchronized, and should only be changed while ON = 0.
- 4. The purpose of this control is to select the active edge when using externally-clocked counter mode.
- 5. This bit controls the output even when ON = 0.
- 6. This bit is shadowed when the module is frozen during debugging and restored when the module resumes operation.
- 7. Capture or stop events load the TUxyCR capture register, regardless of this bit's setting.
- 8. The effect of writing to TUxyCR with RDSEL = 0 is not defined.
- The interrupt flags will be set even if the corresponding interrupt is disabled.
- 10. The PRIF interrupt will not occur if the user writes the PR value to the TUxyTMR counter register directly.
- 11. The CIF interrupt trigger requires a running timer.
- 12. This register is not available when the module is chained and operated as a slave.

#### 28.9.2 **TUxyCON1**

Name: TUxyCON1

Timer Control Register 1

Bit	7	6	5	4	3	2	1	0
	RUN	OSEN	CLR	LIMIT	CAPT	PRIF	ZIF	CIF
Access	R	R/W	R/S/HC	R/W	R/S/HC	R/W/HS	R/W/HS	R/W/HS
Reset	0	0	0	0	0	0	0	0

Bit 7 - RUN Timer Run/Stop Status (read-only)(1,2)

Reset States: POR/BOR = 0 All Other Resets = u

Value	Description			
1	Timer is running (counting) and not being held in Reset by ERS (per EPOL bit selection)			
0	Timer is not counting or is held in Reset by ERS			

Bit 6 - OSEN One-Shot Mode Enable (3,4)

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	The counter operates in One-Shot mode; ON will be cleared by a Stop condition
0	The counter can be repeatedly Started by the ERS signal

#### Bit 5 - CLR Timer Counter "Clear" Command (5,6)

Writing this bit with '0' has no effect. Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	Once set, the timer counter and the internal prescaler counter are cleared, then this bit is cleared (the
	captured value of TUxyCR is unchanged)
0	Clearing action is complete (or not started)

#### Bit 4 – LIMIT Limit Mode Enable<sup>(4)</sup>

This bit is relevant when RESET = 'b00 (continuous mode) and counter equals PR.

Reset States: POR/BOR = 0 All Other Resets = u

	7111 0 11101 1 100010 1
Value	Description
1	Counter value remains equal to PR (unchanged); no additional interrupts occur
0	Counter value goes tor PR+1 when clocked

### Bit 3 - CAPT Timer "Capture" Command (5,6,7,8,9)

Writing this bit with '0' has no effect. Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	Once set, the counter value is captured in TUxyCR and this bit is cleared
0	TUxyCR update is complete (or not started)

### Bit 2 – PRIF Period Match Interrupt Flag(10,11,12)

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	The counter has incremented from PR-1 to PR
0	The counter has not incremented from PR-1 to PR since this bit was last cleared

### PIC18F26/46/56Q84

### **UTMR - Universal Timer Module**

**Bit 1 – ZIF** Zero Interrupt Flag<sup>(10,11)</sup> Reset States: POR/BOR = 0

All Other Resets = u

Value	Description				
1	The counter has reset or rolled over to zero				
0	The counter has not reset or rolled over since this bit was last cleared				

Bit 0 - CIF Capture Interrupt Flag(10,11,13)

Reset States: POR/BOR = 0
All Other Resets = u

Value	Description
1	A capture event has occurred
0	A capture event has not occurred since this bit was last cleared

- 1. Clock synchronization delays apply.
- 2. This bit is held at zero if a Start has occurred (the counter is "running"), but ERS is holding the counter at the value zero when RESET = 'b01 (level-triggered).
- 3. The clearing of the ON bit in one-shot mode is subject to clock synchronization delays. Refer to sections Synchronous vs. Asynchronous Operation and One-Shot Mode for details.
- 4. This bit is not clock synchronized, and should only be changed while ON = 0.
- 5. This bit is subject to clock synchronization delays; see also Timer Counter and Capture Registers.
- 6. If the counter is disabled (ON = 0) or if the module is frozen during debugging, then the timer clock has been disabled; the effect of setting CLR or CAPT command bits depends on the clock synchronization setting. If CSYNC = 0, the corresponding action is performed immediately. If CSYNC = 1, the corresponding action is delayed until the clock resumes (even in frozen state while debugging). See also Timer Counter and Capture Registers.
- 7. A capture event can also be triggered by other means. See Timer Counter and Capture Registers for details.
- 8. If CAPT command is near-coincident with a Stop event, the captured value may represent the first event that occurs.
- 9. The captured value is read by setting RDSEL = 0 and reading TUxyCR.
- 10. This bit may be set by software in order to invoke an interrupt or DMA operation.
- 11. The interrupt flags will be set even if the corresponding interrupt is disabled.
- 12. The PRIF interrupt will not occur if the user writes the PR value to the TUxyTMR counter register directly.
- 13. The CIF interrupt trigger requires a running timer.
- 14. This register is not available when the module is chained and operated as a slave.

### 28.9.3 TUxyHLT

Name: TUxyHLT

Hardware Limit Timer Control Register

Bit	7	6	5	4	3	2	1	0
	EPOL	CSYNC	START[1:0]		RESET[1:0]		STOP[1:0]	
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	1	0	0	0	0	0	0

#### Bit 7 - EPOL ERS Polarity Selection

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	The edges and levels for Start, Reset and Stop are inverted
0	The edges and levels for Start, Reset and Stop are the true input levels

#### Bit 6 - CSYNC ERS Clock Synchronization Select<sup>(1,2)</sup>

Reset States: POR/BOR = 1

All Other Resets = u

Value	Description
1	ERS and ON are synchronized with TUxyCLK
0	The counter starts, stops and resets asynchronously

### Bits 5:4 - START[1:0] Counter Start Condition Select(3,4)

Reset States: POR/BOR = 00

All Other Resets = uu

Value	Description
11	Timer counter starts when ERS = 1
10	Timer counter starts at rising edge of ERS
01	Timer counter starts at either edge of ERS
00	No start due to ERS, timer runs when ON = 1

### Bits 3:2 - RESET[1:0] Counter Reset Condition Select<sup>(4,5,6,7,8)</sup>

Reset States: POR/BOR = 00

All Other Resets = uu

Value	Description
11	Timer counter resets at PR match i.e., when counter equals PR; Next clock brings counter to zero
10	Timer counter resets at the first clock when starting and/or also at PR match
01	Timer counter resets when ERS = 0 and/or also at PR match
00	No hardware Reset

### Bits 1:0 - STOP[1:0] Counter Stop Condition Select<sup>(4,8,9,10,11)</sup>

The Stop feature has effect only when the counter is actively running. Once stopped, additional Stop events will not invoke capture or interrupt.

Reset States: POR/BOR = 00

All Other Resets = uu

Value	Description
11	Timer stops counting at PR match i.e., when counter equals PR; current counter value is captured in
	TUxyCR
10	Timer stops counting at rising edge of ERS; current counter value is captured in TUxyCR
01	Timer stops counting at either edge of ERS; current counter value is captured in TUxyCR
00	ERS or PR match do not stop the timer; software must clear ON to stop the timer; current counter
	value is captured in TUxyCR at every rising edge of ERS

### PIC18F26/46/56Q84

### **UTMR - Universal Timer Module**

- 1. This bit is Reset to '1'.
- 2. If CSYNC = 0, the ERS and ON edges must occur sufficiently further away from the clock edge to be registered into the timer domain. If the ERS and/or ON edges occur too close to the clock edge, it may result in a Race condition and the ERS/ON edges may be missed.
- The TUxyCLK clock source is enabled when ON = 1 regardless of the Start event.
- 4. If EPOL = 1, then timer Start/Reset/Stop conditions happen at the alternate level/edge, respectively.
- 5. When the timer is running, any subsequent Start condition is ignored. If RESET = 'b10 (Reset at first clock after starting), the timer resets at every Start condition, even when the actual start event is being ignored.
- 6. If START = 'b11 (level triggered at ERS = 1), RESET = 'b10 (Reset at first clock after starting) applies only at the Off-On transition of the Timer's Run state.
- 7. If RESET = 'b10 (level-triggered), the RUN bit is held at '0'.
- 8. A Reset or Stop event reloads the PR register as described in Timer Period Register.
- 9. Actions involving ERS require ON = 1 and a running clock.
- 10. Software can always set ON = 0 to stop the counter.
- 11. If OSEN = 1, a Stop event will clear ON.
- 12. This register is not clock synchronized and should only be written when ON = 0.
- 13. This register is not available when the module is chained and operated as a slave.

## PIC18F26/46/56Q84

### **UTMR - Universal Timer Module**

### 28.9.4 TUxyPS

Name: TUxyPS

Prescaler Value Register

Bit	7	6	5	4	3	2	1	0
	PS[7:0]							
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

**Bits 7:0 – PS[7:0]** Clock Prescaler register Reset States: POR/BOR = 00000000

All Other Resets = uuuuuuuu

	· · · · · · · · · · · · · · · · · · ·
Value	Description
0xFF-0x0	Divider ratio is (PS+1):1
1	
0x00	The input clock is not divided (1:1 clocking)

#### Notes:

- 1. This register should only be written when ON = 0.
- 2. This register is not available when the module is chained and operated as a slave.
- 3. The internal prescaler counter (not the TUxyPS register) is reset by any Stop or Reset event, and upon any write to the TUxyPS and TUxyTMR registers. This allows the next timer interval to be full-length.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 502

### 28.9.5 TUxyTMR (16-bit)

Name: TU16yTMR Offset: 0x38B,0x397

Timer Counter Register for 16-bit version of UTMR module. This register can only be addressed when RDSEL = 1.

Bit	15	14	13	12	11	10	9	8	
	TMR[15:8]								
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	0	0	0	0	0	0	0	0	
Bit	7	6	5	4	3	2	1	0	
	TMR[7:0]								
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	0	0	0	0	0	0	0	0	

Bits 15:0 - TMR[15:0] Timer value

All Other Resets = uuuuuuuuuuuuuuu

	· · · · · · · · · · · · · · · · · · ·
Condition	Description
RDSEL = 1	The raw counter register is read or written; should only be accessed while clocking is disabled i.e.,
	when $ON = 0$ .
RDSEL = 0	Reserved. Do not use.

- 1. Writing to this register will change the raw counter value directly. The user must handle the operation correctly to avoid data corruption. There is no safeguard for atomic access. Reading or writing a running counter is not recommended. This register should only be accesses while clocking is disabled.
- 2. The individual bytes in this multibyte register can be accessed with the following register names:
  - TUxyTMRH: Accesses the high byte TUxyTMR[15:8]
  - TUxyTMRL: Accesses the low byte TUxyTMR[7:0]

### 28.9.6 TUxyCR (16-bit)

**Name:** TU16yCR **Offset:** 0x38B,0x397

Timer Capture Register for 16-bit version of UTMR module. This register can only be addressed when RDSEL = 0.

Bit	15	14	13	12	11	10	9	8
	CR[15:8]							
Access	R	R	R	R	R	R	R	R
Reset	0	0	0	0	0	0	0	0
5	_		_					
Bit	/	6	5	4	3	2	1	0
			CR[7:0]					
Access	R	R	R	R	R	R	R	R
Reset	0	0	0	0	0	0	0	0

#### Bits 15:0 - CR[15:0] Timer capture value

All Other Resets = uuuuuuuuuuuuuuu

Condition	Description
RDSEL = 1	Reserved. Do not use.
RDSEL = 0	The value captured by the most-recent Stop or Capture event is returned (read-only)

- 1. Writing to this register is not recommended and may result in unexplained behavior.
- 2. The captured value is updated at Stop or when software sets CAPT = 1, regardless of the RDSEL value. Refer to Timer Counter and Capture Registers for details.
- 3. The individual bytes in this multibyte register can be accessed with the following register names:
  - TUxyCRH: Accesses the high byte TUxyCR[15:8]
  - TUxyCRL: Accesses the low byte TUxyCR[7:0]

## 28.9.7 TUxyPR (16-bit)

Name: TU16yPR Offset: 0x38D,0x399

Timer Period Register for 16-bit version of UTMR module.

Bit	15	14	13	12	11	10	9	8				
	PR[15:8]											
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W				
Reset	1	1	1	1	1	1	1	1				
Bit	7	6	5	4	3	2	1	0				
	PR[7:0]											
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W				
Reset	1	1	1	1	1	1	1	1				

## Bits 15:0 - PR[15:0] Period value

The period of the timer.

All Other Resets = uuuuuuuuuuuuuuu


## Notes:

- 1. This register is double-buffered; effective PR value is loaded as defined by Timer Period Register.
- 2. Data written to higher bytes is buffered; data written to LSB is also buffered and arms the effective PR value to be loaded at the next Reset or CLR event.
- 3. Reading this register returns the data most-recently written, not necessarily the current PR setting.
- 4. The individual bytes in this multibyte register can be accessed with the following register names:
  - TUxyPRH: Accesses the high byte TUxyPR[15:8]
  - TUxyPRL: Accesses the low byte TUxyPR[7:0]

# 28.9.8 TUxyCLK

Name: TUxyCLK

Clock Input Selector



Bits 4:0 - CLK[4:0] Clock Input Selector

# Table 28-5. TUxyCLK Clock Input Selections

CLK	Clock Input
11111	CLC8_OUT
11110	CLC7_OUT
11101	CLC6_OUT
11100	CLC5_OUT
11011	CLC4_OUT
11010	CLC3_OUT
11001	CLC2_OUT
11000	CLC1_OUT
10111	NCO3_OUT
10110	NCO2_OUT
10101	NCO1_OUT
10100	PWM4S1P2_OUT
10011	PWM4S1P1_OUT
10010	PWM3S1P2_OUT
10001	PWM3S1P1_OUT
10000	PWM2S1P2_OUT
01111	PWM2S1P1_OUT
01110	PWM1S1P2_OUT
01101	PWM1S1P1_OUT
01100	CCP3_OUT
01011	CCP2_OUT
01010	CCP1_OUT
01001	CLKREF_OUT
01000	EXTOSC
00111	SOSC
00110	MFINTOSC (32 kHz)
00101	MFINTOSC (500 kHz)
00100	LFINTOSC
00011	HFINTOSC
00010	F <sub>OSC</sub>
00001	TUIN1PPS
00000	TUIN0PPS

Reset States: POR/BOR = 00000

All Other Resets = uuuuu

# PIC18F26/46/56Q84

# **UTMR - Universal Timer Module**


N	ΛΤΔ	

1. This register is not available when the module is chained and operated as a slave.

# 28.9.9 TUxyERS

Name: TUxyERS

**External Input Selector** 



Bits 5:0 - ERS[5:0] External Reset Source Selector

# Table 28-6. TUxyERS External Reset Sources

ERS	External Rese	t Source Connection
EKS	TU16A	TU16B
111111	TU16ATMRL_Read or TU16ACRL_Read	TU16BTMRL_Read or TU16BCRL_Read <sup>(1)</sup>
111110	TU16APRL_Write <sup>(1)</sup>	TU16BPRL_Write <sup>(1)</sup>
111101-100111	F	eserved
100110	S	PI2_SCK
100101	S	PI1_SCK
100100	12	C1_SCL
100011	U5TX_Edge	(Positive/Negative)
100010	U5RX_Edge	(Positive/Negative)
100001	U4TX_Edge	(Positive/Negative)
100000	U4RX_Edge	(Positive/Negative)
011111	U3TX_Edge	(Positive/Negative)
011110	U3RX_Edge	(Positive/Negative)
011101	U2TX_Edge	(Positive/Negative)
011100	U2RX_Edge	(Positive/Negative)
011011	U1TX_Edge	(Positive/Negative)
011010	U1RX_Edge	(Positive/Negative)
011001	CI	.C8_OUT
011000	CI	.C7_OUT
010111	CI	.C6_OUT
010110	CI	.C5_OUT
010101	CI	.C4_OUT
010100	CI	.C3_OUT
010011	CI	.C2_OUT
010010	CI	.C1_OUT
010001	Z	CD_OUT
010000	CN	MP2_OUT
001111	CN	MP1_OUT
001110	NO	CO3_OUT
001101	NO	CO2_OUT
001100	NO	CO1_OUT
001011	PWM	4S1P2_OUT
001010	PWM	4S1P1_OUT
001001	PWM	3S1P2_OUT
001000	PWM	3S1P1_OUT

continued									
ERS	External Reset Source Connection								
EKS	TU16A	TU16B							
000111	PWM2S1P2_OUT								
000110	PWM2S <sup>2</sup>	PWM2S1P1_OUT							
000101	PWM1S <sup>2</sup>	PWM1S1P2_OUT							
000100	PWM1S <sup>2</sup>	IP1_OUT							
000011	TU16B_OUT Reserved								
000010	Reserved TU16A_OUT								
000001	TUIN1PPS								
000000	TUIN	0PPS							

## Note:

Reset States: POR/BOR = 000000 All Other Resets = uuuuuu

## Note:

1. This register is not available when the module is chained and operated as a slave.

<sup>1.</sup> TUxyPRL\_Write,TUxyTMRL\_Read and TUxyCRL\_Read are event triggers occurring when the indicated SFR is accessed.

# PIC18F26/46/56Q84

# **UTMR - Universal Timer Module**

## 28.9.10 TUCHAIN

Name: TUCHAIN Offset: 0x3BB

**Timer Chain Control** 



## Bit 0 - CH16AB Timers TU16A and TU16B Chain Enable

Reset States: POR/BOR = x

All Other Resets = u

Value	Description
1	Timers TU16A (Master) and TU16B (Slave) operate as a single 32-bit timer
	TU16ATMR, TU16ACR and TU16APR form the least significant bits of the counter, capture and period values, respectively.
0	Timers TU16A and TU16B operate as independent 16-bit timers

#### Note:

1. When chained, TUxyCON0, TUxyCON1, TUxyHLT, TUxyPS, TUxyCLK and TUxyERS of the slave timer are undefined. Refer to Chaining Counter Timers for details.

# 28.10 Register Summary - Universal Timer

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00  0x0386	Reserved									
0x0387	TU16ACON0	7:0	ON	CPOL	OM	OPOL	RDSEL	PRIE	ZIE	CIE
0x0388	TU16ACON1	7:0	RUN	OSEN	CLR	LIMIT	CAPT	PRIF	ZIF	CIF
0x0389	TU16AHLT	7:0	EPOL	CSYNC	STAR	T[1:0]	RESE	T[1:0]	STO	P[1:0]
0x038A	TU16APS	7:0				PS[	7:0]			
0x038B	TU16ATMR	7:0				TMR	R[7:0]			
UXUSOD	TOTOATIVIK	15:8				TMR	[15:8]			
0x038B	TU16ACR	7:0				CR	[7:0]			
UXUSOD	TOTOACK	15:8				CR[	15:8]			
0x038D	TU16APR	7:0				PR[	[7:0]			
UXUSOD	TOTOAPK	15:8				PR[	15:8]			
0x038F	TU16ACLK	7:0						CLK[4:0]		
0x0390	TU16AERS	7:0				-	ERS	5[5:0]		
0x0391  0x0392	Reserved									
0x0393	TU16BCON0	7:0	ON	CPOL	OM	OPOL	RDSEL	PRIE	ZIE	CIE
0x0394	TU16BCON1	7:0	RUN	OSEN	CLR	LIMIT	CAPT	PRIF	ZIF	CIF
0x0395	TU16BHLT	7:0	EPOL	CSYNC	STAR	RT[1:0]	RESE	T[1:0]	STO	P[1:0]
0x0396	TU16BPS	7:0				PS[	7:0]			
0x0397	TU16BTMR	7:0				TMR	R[7:0]			
0x0397	TUTOBTWIK	15:8				TMR	[15:8]			
0x0397	TU16BCR	7:0				CR	[7:0]			
0x0397	TUTOBUR	15:8				CR[	15:8]			
0x0399	TU16BPR	7:0				PR[	[7:0]			
0x0399	TUTOBPR	15:8				PR[	15:8]			
0x039B	TU16BCLK	7:0						CLK[4:0]		
0x039C	TU16BERS	7:0					ERS	S[5:0]		
0x039D  0x03BA	Reserved									
0x03BB	TUCHAIN	7:0								CH16AB

# 29. CCP - Capture/Compare/PWM Module

The Capture/Compare/PWM module is a peripheral that allows the user to time and control different events, and to generate Pulse-Width Modulation (PWM) signals. In Capture mode, the peripheral allows the timing of the duration of an event. The Compare mode allows the user to trigger an external event when a predetermined amount of time has expired. The PWM mode can generate Pulse-Width Modulated signals of varying frequency and duty cycle.

Each individual CCP module can select the timer source that controls the module. The default timer selection is Timer1 when using Capture/Compare mode and Timer2 when using PWM mode in the CCPx module.

It should be noted that the Capture/Compare mode operation is described with respect to Timer1 and the PWM mode operation is described with respect to Timer2 in the following sections.

The Capture and Compare functions are identical for all CCP modules.



**Important:** In devices with more than one CCP module, it is very important to pay close attention to the register names used. Throughout this section, the prefix "CCPx" is used as a generic replacement for specific numbering. A number placed where the "x" is in the prefix is used to distinguish between separate modules. For example, CCP1CON and CCP2CON control the same operational aspects of two completely different CCP modules.

# 29.1 CCP Module Configuration

Each Capture/Compare/PWM module is associated with a control register (CCPxCON), a capture input selection register (CCPxCAP) and a data register (CCPRx). The data register, in turn, is comprised of two 8-bit registers: CCPRxL (low byte) and CCPRxH (high byte).

## 29.1.1 CCP Modules and Timer Resources

The CCP modules utilize Timers 1 through 6 that vary with the selected mode. Various timers are available to the CCP modules in Capture, Compare or PWM modes, as shown in the table below.

Table 29-1. CCP Mode - Timer Resources

CCP Mode	Timer Resource			
Capture	Timer1, Timer3 or Timer5  Timer2, Timer4 or Timer6			
Compare				
PWM				

The assignment of a particular timer to a module is selected as shown in the "Capture, Compare, and PWM Timers Selection" chapter. All of the modules may be active at once and may share the same timer resource if they are configured to operate in the same mode (Capture/Compare or PWM) at the same time.

## 29.1.2 Open-Drain Output Option

When operating in Output mode (the Compare or PWM modes), the drivers for the CCPx pins can be optionally configured as open-drain outputs. This feature allows the voltage level on the pin to be pulled to a higher level through an external pull-up resistor and allows the output to communicate with external circuits without the need for additional level shifters.

# 29.2 Capture Mode

Capture mode makes use of the 16-bit odd numbered timer resources (Timer1, Timer3, etc.) . When an event occurs on the capture source, the 16-bit CCPRx register captures and stores the 16-bit value of the TMRx register. An event is defined as one of the following and is configured by the MODE bits:


- · Every falling edge of CCPx input
- · Every rising edge of CCPx input
- Every 4<sup>th</sup> rising edge of CCPx input
- Every 16<sup>th</sup> rising edge of CCPx input
- Every edge of CCPx input (rising or falling)

When a capture is made, the Interrupt Request Flag bit CCPxIF of the PIRx register is set. The interrupt flag must be cleared in software. If another capture occurs before the value in the CCPRx register is read, the old captured value is overwritten by the new captured value. The following figure shows a simplified diagram of the capture operation.



**Important:** If an event occurs during a 2-byte read, the high and low-byte data will be from different events. It is recommended while reading the CCPRx register pair to either disable the module or read the register pair twice for data integrity.

Figure 29-1. Capture Mode Operation Block Diagram



## 29.2.1 Capture Sources

The capture source is selected with the CTS bits.

In Capture mode, the CCPx pin should be configured as an input by setting the associated TRIS control bit.



Important: If the CCPx pin is configured as an output, a write to the port can cause a capture condition.

## 29.2.2 Timer1 Mode for Capture

Timer1 must be running in Timer mode or Synchronized Counter mode for the CCP module to use the capture feature. In Asynchronous Counter mode, the capture operation may not work.

See the "TMR1 - Timer1 Module with Gate Control" Module with Gate Control" chapter for more information on configuring Timer1.

## 29.2.3 Software Interrupt Mode

When the Capture mode is changed, a false capture interrupt may be generated. The user should keep the CCPxIE Interrupt Priority bit of the PIEx register clear to avoid false interrupts. Additionally, the user should clear the CCPxIF Interrupt Flag bit of the PIRx register following any change in Operating mode.



**Important:** Clocking Timer1 from the system clock ( $F_{OSC}$ ) should not be used in Capture mode. In order for Capture mode to recognize the trigger event on the CCPx pin, Timer1 must be clocked from the instruction clock ( $F_{OSC}$ /4) or from an external clock source.

## 29.2.4 CCP Prescaler

There are four prescaler settings specified by the MODE bits. Whenever the CCP module is turned off, or the CCP module is not in Capture mode, the prescaler counter is cleared. Any Reset will clear the prescaler counter.

Switching from one capture prescaler to another does not clear the prescaler and may generate a false interrupt. To avoid this unexpected operation, turn the module off by clearing the CCPxCON register before changing the prescaler. The example below demonstrates the code to perform this function.

#### 

## 29.2.5 Capture During Sleep

Capture mode depends upon the Timer1 module for proper operation. There are two options for driving the Timer1 module in Capture mode. It can be driven by the instruction clock (F<sub>OSC</sub>/4), or by an external clock source.

When Timer1 is clocked by F<sub>OSC</sub>/4, Timer1 will not increment during Sleep. When the device wakes from Sleep, Timer1 will continue from its previous state.

Capture mode will operate during Sleep when Timer1 is clocked by an external clock source.

## 29.3 Compare Mode

The Compare mode function described in this section is available and identical for all CCP modules.

Compare mode makes use of the 16-bit odd numbered Timer resources (Timer1, Timer3, etc.). The 16-bit value of the CCPRx register is constantly compared against the 16-bit value of the TMRx register. When a match occurs, one of the following events can occur:


- Toggle the CCPx output and clear TMRx
- Toggle the CCPx output without clearing TMRx
- · Set the CCPx output
- Clear the CCPx output
- Generate a Pulse output
- Generate a Pulse output and clear TMRx

The action on the pin is based on the value of the MODE control bits.

All Compare modes can generate an interrupt. When MODE = 'b0001 or 'b1011, the CCP resets the TMRx register.

The following figure shows a simplified diagram of the compare operation.

Figure 29-2. Compare Mode Operation Block Diagram



## 29.3.1 CCPx Pin Configuration

The CCPx pin must be configured as an output in software by clearing the associated TRIS bit and defining the appropriate output pin through the RxyPPS registers. See the "PPS - Peripheral Pin Select Module" chapter for more details.

The CCP output can also be used as an input for other peripherals.



**Important:** Clearing the CCPxCON register will force the CCPx compare output latch to the default low level. This is not the PORT I/O data latch.

#### 29.3.2 Timer1 Mode for Compare

In Compare mode, Timer1 must be running in either Timer mode or Synchronized Counter mode. The compare operation may not work in Asynchronous Counter mode.

See the "TMR1 - Timer1 Module with Gate Control" chapter for more information on configuring Timer1.



**Important:** Clocking Timer1 from the system clock  $(F_{OSC})$  should not be used in Compare mode. In order for Compare mode to recognize the trigger event on the CCPx pin, Timer1 must be clocked from the instruction clock  $(F_{OSC}/4)$  or from an external clock source.

## 29.3.3 Compare During Sleep

Since  $F_{OSC}$  is shut down during Sleep mode, the Compare mode will not function properly during Sleep, unless the timer is running. The device will wake on interrupt (if enabled).


## 29.4 PWM Overview

Pulse-Width Modulation (PWM) is a scheme that controls power to a load by switching quickly between fully ON and fully OFF states. The PWM signal resembles a square wave where the high portion of the signal is considered the ON state and the low portion of the signal is considered the OFF state. The high portion, also known as the pulse width, can vary in time and is defined in steps. A larger number of steps applied, which lengthens the pulse width, also supplies more power to the load. Lowering the number of steps applied, which shortens the pulse width, supplies less power. The PWM period is defined as the duration of one complete cycle or the total amount of ON and OFF time combined.

PWM resolution defines the maximum number of steps that can be present in a single PWM period. A higher resolution allows for more precise control of the pulse-width time and in turn the power that is applied to the load.

The term duty cycle describes the proportion of the ON time to the OFF time and is expressed in percentages, where 0% is fully OFF and 100% is fully ON. A lower duty cycle corresponds to less power applied and a higher duty cycle corresponds to more power applied. The figure below shows a typical waveform of the PWM signal.

Figure 29-3. CCP PWM Output Signal




## 29.4.1 Standard PWM Operation

The standard PWM function described in this section is available and identical for all CCP modules. It generates a Pulse-Width Modulation (PWM) signal on the CCPx pin with up to ten bits of resolution. The period, duty cycle, and resolution are controlled by the following registers:

- Even numbered TxPR registers (T2PR, T4PR, etc.)
- Even numbered TxCON registers (T2CON, T4CON, etc.)
- · 16-bit CCPRx registers
- · CCPxCON registers

It is required to have  $F_{OSC}/4$  as the clock input to TxTMR for correct PWM operation. The following figure shows a simplified block diagram of PWM operation.

Figure 29-4. Simplified PWM Block Diagram



Notes:

- 8-bit timer is concatenated with two bits generated by Fosc or two bits of the internal prescaler to create 10-bit time-base.
- 2. The alignment of the 10 bits from the CCPR register is determined by the CCPxFMT bit.



**Important:** The corresponding TRIS bit must be cleared to enable the PWM output on the CCPx pin.

## 29.4.2 Setup for PWM Operation

The following steps illustrate how to configure the CCP module for standard PWM operation:

- Select the desired output pin with the RxyPPS control to select CCPx as the source. Disable the selected pin output driver by setting the associated TRIS bit. The output will be enabled later at the end of the PWM setup.
- 2. Load the selected timer period register TxPR register with the PWM period value.
- 3. Configure the CCP module for the PWM mode by loading the CCPxCON register with the appropriate values.
- 4. Load the CCPRx register with the PWM duty cycle value and configure the FMT bit to set the proper register alignment.
- 5. Configure and start the selected Timer:
  - Clear the TMRxIF Interrupt Flag bit of the PIRx register. See Note below.
  - Select the timer clock source to be as F<sub>OSC</sub>/4. This is required for correct operation of the PWM module.
  - Configure the TxCKPS bits of the TxCON register with the desired Timer prescale value.
  - Enable the Timer by setting the TxON bit.
- 6. Enable the PWM output:
  - Wait until the Timer overflows and the TMRxIF bit of the PIRx register is set. See Note below.
  - Enable the CCPx pin output driver by clearing the associated TRIS bit.



**Important:** In order to send a complete duty cycle and period on the first PWM output, the above steps must be included in the setup sequence. If it is not critical to start with a complete PWM signal on the first output, then step 6 may be ignored.

#### 29.4.3 Timer2 Timer Resource

The PWM standard mode makes use of the 8-bit Timer2 timer resources to specify the PWM period.

#### 29.4.4 PWM Period

The PWM period is specified by the T2PR register of Timer2. The PWM period can be calculated using the formula in the equation below.

#### **Equation 29-1. PWM Period**

 $PWMPeriod = [(T2PR + 1)] \bullet 4 \bullet T_{OSC} \bullet (TMR2PrescaleValue)$ 

where  $T_{OSC} = 1/F_{OSC}$ 

When T2TMR is equal to T2PR, the following three events occur on the next increment event:

- · T2TMR is cleared
- The CCPx pin is set. (Exception: If the PWM duty cycle = 0%, the pin will not be set.)
- The PWM duty cycle is transferred from the CCPRx register into a 10-bit buffer.




**Important:** The Timer postscaler (see "Timer2 Interrupt") is not used in the determination of the PWM frequency.

#### 29.4.5 PWM Duty Cycle

The PWM duty cycle is specified by writing a 10-bit value to the CCPRx register. The alignment of the 10-bit value is determined by the FMT bit (see Figure 29-5). The CCPRx register can be written to at any time. However, the duty cycle value is not latched into the 10-bit buffer until after a match between T2PR and T2TMR.

The equations below are used to calculate the PWM pulse width and the PWM duty cycle ratio.

Figure 29-5. PWM 10-Bit Alignment



## Equation 29-2. Pulse Width

 $Pulse\ Width = (CCPRxH:CCPRxL\ register\ value) \bullet T_{OSC} \bullet (TMR2\ Prescale\ Value)$ 

# Equation 29-3. Duty Cycle

$$DutyCycleRatio = \frac{(CCPRxH:CCPRxL register value)}{4(T2PR+1)}$$

The CCPRx register is used to double buffer the PWM duty cycle. This double buffering is essential for glitchless PWM operation.

The 8-bit timer T2TMR register is concatenated with either the 2-bit internal system clock (F<sub>OSC</sub>), or two bits of the prescaler, to create the 10-bit time base. The system clock is used if the Timer2 prescaler is set to 1:1.

When the 10-bit time base matches the CCPRx register, then the CCPx pin is cleared (see Figure 29-4).

# 29.4.6 PWM Resolution

The resolution determines the number of available duty cycles for a given period. For example, a 10-bit resolution will result in 1024 discrete duty cycles, whereas an 8-bit resolution will result in 256 discrete duty cycles.

The maximum PWM resolution is ten bits when T2PR is 0xFF. The resolution is a function of the T2PR register value, as shown below.

#### Equation 29-4. PWM Resolution

$$\text{Resolution} = \frac{\log[4(T2PR+1)]}{\log(2)}bits$$



**Important:** If the pulse-width value is greater than the period, the assigned PWM pin(s) will remain unchanged.

Table 29-2. Example PWM Frequencies and Resolutions ( $F_{OSC} = 20 \text{ MHz}$ )

PWM Frequency	1.22 kHz	4.88 kHz	19.53 kHz	78.12 kHz	156.3 kHz	208.3 kHz
Timer Prescale	16	4	1	1	1	1
T2PR Value	0xFF	0xFF	0xFF	0x3F	0x1F	0x17
Maximum Resolution (bits)	10	10	10	8	7	6.6

Table 29-3. Example PWM Frequencies and Resolutions (F<sub>OSC</sub> = 8 MHz)

PWM Frequency	1.22 kHz	4.90 kHz	19.61 kHz	76.92 kHz	153.85 kHz	200.0 kHz
Timer Prescale	16	4	1	1	1	1
T2PR Value	0x65	0x65	0x65	0x19	0x0C	0x09
Maximum Resolution (bits)	8	8	8	6	5	5

## 29.4.7 Operation in Sleep Mode

In Sleep mode, the T2TMR register will not increment and the state of the module will not change. If the CCPx pin is driving a value, it will continue to drive that value. When the device wakes up, T2TMR will continue from the previous state.

#### 29.4.8 Changes in System Clock Frequency

The PWM frequency is derived from the system clock frequency. Any changes in the system clock frequency will result in changes to the PWM frequency. See the "OSC - Oscillator Module (with Fail-Safe Clock Monitor)" chapter for additional details.

## 29.4.9 Effects of Reset

Any Reset will force all ports to Input mode and the CCP registers to their Reset states.

## 29.5 Register Definitions: CCP Control

Long bit name prefixes for the CCP peripherals are shown in the following table. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 519

# PIC18F26/46/56Q84

# **CCP - Capture/Compare/PWM Module**

# Table 29-4. CCP Long bit name prefixes

Peripheral	Bit Name Prefix
CCP1	CCP1
CCP2	CCP2
CCP3	CCP3

## 29.5.1 CCPxCON

Name: CCPxCON

**Offset:** 0x342,0x346,0x34A

**CCP Control Register** 

Bit	7	6	5	4	3	2	1	0
	EN		OUT	FMT		MOD	E[3:0]	
Access	R/W		R	R/W	R/W	R/W	R/W	R/W
Reset	0		X	0	0	0	0	0

## Bit 7 - EN CCP Module Enable

Value	Description
1	CCP is enabled
0	CCP is disabled

## Bit 5 - OUT CCP Output Data (read-only)

## Bit 4 - FMT CCPW (pulse-width) Value Alignment

Value	Condition	Description
X	Capture mode	Not used
Х	Compare mode	Not used
1	PWM mode	Left-aligned format
0	PWM mode	Right-aligned format

## Bits 3:0 - MODE[3:0] CCP Mode Select

#### Table 29-5. CCPx Mode Select

MODE Value	Operating Mode	Operation	Set CCPxIF
11xx	PWM	PWM operation	Yes
1011		Pulse output; clear TMR1 <sup>(2)</sup>	Yes
1010	Compare	Pulse output	Yes
1001	Compare	Clear output <sup>(1)</sup>	Yes
1000		Set output <sup>(1)</sup>	Yes
0111		Every 16 <sup>th</sup> rising edge of CCPx input	Yes
0110		Every 4 <sup>th</sup> rising edge of CCPx input	Yes
0101	Capture	Every rising edge of CCPx input	Yes
0100		Every falling edge of CCPx input	Yes
0011		Every edge of CCPx input	Yes
0010	Compare	Toggle output	Yes
0001	Compare	Toggle output; clear TMR1 <sup>(2)</sup>	Yes
0000	Disabled		_

## Notes:

- 1. The set and clear operations of the Compare mode are reset by setting MODE = 'b00000 or EN = 0.
- 2. When MODE = 'b0001 or 'b1011, then the timer associated with the CCP module is cleared. TMR1 is the default selection for the CCP module, so it is used for indication purposes only.

# 29.5.2 CCPxCAP

Name: CCPxCAP

**Offset:** 0x343,0x347,0x34B

Capture Trigger Input Selection Register



Bits 3:0 - CTS[3:0] Capture Trigger Input Selection

# Table 29-6. Capture Trigger Sources

CTS Value	Source		
1100-1111	Reserved		
1011	CLC8_OUT		
1010	CLC7_OUT		
1001	CLC6_OUT		
1000	CLC5_OUT		
0111	CLC4_OUT		
0110	CLC3_OUT		
0101	CLC2_OUT		
0100	CLC1_OUT		
0011	IOC Interrupt		
0010	CMP2_OUT		
0001	CMP1_OUT		
0000	Pin selected by CCPxPPS		

## 29.5.3 CCPRx

Name: CCPRx

**Offset:** 0x340,0x344,0x348

Capture/Compare/Pulse Width Register

Bit	15	14	13	12	11	10	9	8
	CCPR[15:8]							
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	X	X	X	X	x	X	X	X
Bit	7	6	5	4	3	2	1	0
Γ				CCPI	R[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	X	X	X	X	X	X	X	X

Bits 15:0 - CCPR[15:0] Capture/Compare/Pulse Width

All other Resets = uuuuuuuuuuuuuuu

Notes: The individual bytes in this multi-byte register can be accessed with the following register names:

- When MODE = Capture or Compare
  - CCPRxH: Accesses the high byte CCPR[15:8]
  - CCPRxL: Accesses the low byte CCPR[7:0]
- When MODE = PWM and FMT = 0
  - CCPRx[15:10]: Not used
  - CCPRxH[1:0]: Accesses the two Most Significant bits CCPR[9:8]
  - CCPRxL: Accesses the eight Least Significant bits CCPR[7:0]
- When MODE = PWM and FMT = 1
  - CCPRxH: Accesses the eight Most Significant bits CCPR[9:2]
  - CCPRxL[7:6]: Accesses the two Least Significant bits CCPR[1:0]
  - CCPRx[5:0]: Not used

# 29.6 Register Summary - CCP Control

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00  0x033F	Reserved									
0x0340	-0040 CODD4					CCPI	R[7:0]			
0x0340	340 CCPR1	15:8				CCPF	R[15:8]			
0x0342	CCP1CON	7:0	EN		OUT	FMT	MODE[3:0]			
0x0343	CCP1CAP	7:0					CTS[3:0]			
0.0244	0344 CCPR2	7:0		CCPR[7:0]						
0x0344		15:8		CCPR[15:8]						
0x0346	CCP2CON	7:0	EN		OUT	FMT		MOD	E[3:0]	
0x0347	CCP2CAP	7:0					CTS[3:0]			
0x0348	CCPR3	7:0		CCPR[7:0]						
UXU348	CCPR3	15:8		CCPR[15:8]						
0x034A	CCP3CON	7:0	EN		OUT	FMT	MODE[3:0]			
0x034B	CCP3CAP	7:0						CTS	[3:0]	

# 30. Capture, Compare, and PWM Timers Selection


Each of these modules has an independent timer selection which can be accessed using the timer selection register. The default timer selection is Timer1 for capture or compare functions and Timer2 for PWM functions.

30.1 Register Definitions: Capture, Compare, and PWM Timer Selection

# 30.1.1 CCPTMRS0

Name: CCPTMRS0 Offset: 0x34C

**CCP Timers Selection Register** 



Bits 0:1, 2:3, 4:5 - CnTSEL CCPn Timer Selection

CnTSEL Value	Capture/Compare	PWM
11	Timer5	Timer6
10	Timer3	Timer4
01	Timer1	Timer2
00	Reserved	

# 30.2 Register Summary - Capture, Compare, and PWM Timers Selection

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x034B										
0x034C	CCPTMRS0	7:0			C3TSI	EL[1:0]	C2TSI	EL[1:0]	C1TSE	EL[1:0]

# 31. PWM - Pulse-Width Modulator with Compare

This module is a 16-bit Pulse-Width Modulator (PWM) with a compare feature and multiple outputs. The outputs are grouped in slices where each slice has two outputs. There can be up to four slices in each PWM module. The EN bit enables the PWM operation for all slices simultaneously. The prescale counter, postscale counter, and all internal logic is held in Reset while the EN bit is low.

Features of this module include the following:

- · Five main operating modes:
  - Left Aligned
  - Right Aligned
  - Center Aligned
  - Variable Aligned
  - Compare
    - Pulsed
    - Toggled
- Push-pull operation (available in Left and Right Aligned modes only)
- · Independent 16-bit period timer
- · Programmable clock sources
- Programmable trigger sources for synchronous duty cycle and period changes
- · Programmable synchronous/asynchronous Reset sources
- · Programmable Reset source polarity control
- · Programmable PWM output polarity control
- · Up to four 2-output slices per module

Block diagrams of each PWM mode are shown in their respective sections.

# 31.1 Output Slices

A PWM module can have up to four output slices. An output slice consists of two PWM outputs, PWMx\_SaP1\_out and PWMx\_SaP2\_out. Both share the same operating mode. However, other slices may operate in a different mode. PWMx\_SaP1\_out and PWMx\_SaP2\_out have independent duty cycles which are set with the respective P1 and P2 parameter registers.

## 31.1.1 Output Polarity

The polarity for the PWMx\_SaP1\_out and PWMx\_SaP2\_out is controlled with the respective POL1 and POL2 bits. Setting the polarity bit inverts the output Active state to low true. Toggling the polarity bit toggles the output whether or not the PWM module is enabled.

## 31.1.2 Operating Modes

Each output slice can operate in one of six modes selected with the MODE bits. The Left and Right Aligned modes can also be operated in Push-Pull mode by setting the PPEN bit. The following sections provide more details on each mode including block diagrams.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 528

## 31.1.2.1 Left Aligned Mode

In Left Aligned mode the active part of the duty cycle is at the beginning of the period. The outputs start active and stay active for the number of prescaled PWM clock periods specified by the P1 and P2 parameter registers then go inactive for the remainder of the period. Block and timing diagrams follow.

Figure 31-1. Left Aligned Block Diagram





Figure 31-2. Left Aligned Timing Diagram

Note: MODE='b000, PR=5, P1=4, P2=2



## 31.1.2.2 Right Aligned Mode

In Right Aligned mode the active part of the duty cycle is at the end of the period. The outputs start in the Inactive state and then go active the number of prescaled PWM clock periods specified by the P1 and P2 parameter registers before the end of the period. Block and timing diagrams follow.

Figure 31-3. Right Aligned Block Diagram





Figure 31-4. Right Aligned Timing Diagram



Note: MODE='b001, PR=5, P1=4, P2=2

# 31.1.2.3 Center Aligned Mode

In Center Aligned mode the active duty cycle is centered in the period. The period for this mode is twice that of other modes as shown in the following equation.

# **Equation 31-1. Center Aligned Period**

$$Period = \frac{(PR + 1) \times 2}{F_{PWMx\_clk}}$$

The parameter register specifies the number of PWM clock periods that the output goes active before the period center. The output goes inactive the same number of prescaled PWM clock periods after the period center. Block and timing diagrams follow.

Figure 31-5. Center Aligned Block Diagram





Figure 31-6. Center Aligned Timing Diagram



Note: MODE='b010 PR=5, P1=4, P2=2

## 31.1.2.4 Variable Alignment Mode

In Variable Alignment mode the active part of the duty cycle starts when the parameter 1 value (P1) matches the timer and ends when the parameter 2 value (P2) matches the timer. Both outputs are identical because both parameter values are used for the same duty cycle. Block and timing diagrams follow.

Figure 31-7. Variable Alignment Block Diagram





Figure 31-8. Variable Alignment Timing Diagram



Note: MODE='b011 PR=5, P1=4, P2=2

## 31.1.2.5 Compare Modes

In the Compare modes, the PWM timer is compared to the P1 and P2 parameter values. When a match occurs the output is either pulsed or toggled. In Pulsed Compare mode, the duty cycle is always one prescaled PWM clock period. In Toggle Compare mode the duty cycle is always one full PWM period. Refer to the following sections for more details.

#### 31.1.2.5.1 Pulsed Compare Mode

In Pulsed Compare mode the duty cycle is one prescaled PWM clock period that starts when the timer matches the parameter value and ends one prescaled PWM clock period later. The outputs start in the Inactive state and then go active during the duty cycle. Block and timing diagrams follow.

Figure 31-9. Pulsed Compare Block Diagram





Figure 31-10. Pulsed Compare Timing Diagram



Note: MODE=' b100 PR=5, P1=4, P2=2

# 31.1.2.5.2 Toggled Compare

In Toggled Compare mode the duty cycle is alternating full PWM periods. The output goes active when the PWM timer matches the P1 or P2 parameter value and goes inactive in the next period at the same match point. Block and timing diagrams follow.

Figure 31-11. Toggled Compare Block Diagram





Figure 31-12. Toggled Compare Timing Diagram



Note: MODE=' b101 PR=5, P1=4, P2=2

## 31.1.3 Push-Pull Mode

The Push-Pull mode is enabled by setting the PPEN bit. Push-Pull operates only in the Left Aligned and Right Aligned modes. In the Push-Pull mode the outputs are active every other PWM period. PWMx\_SaP1\_out is active when the PWMx\_SaP2\_out is not and the PWMx\_SaP2\_out is active when the PWMx\_SaP1\_out is not. When the parameter value (P1 or P2) is greater than the period value (PR) then the corresponding output is active for one full PWM period. The following figures illustrate timing examples of Left and Right Aligned Push-Pull modes.

Figure 31-13. Left Aligned Push-Pull Mode Timing Diagram





Figure 31-14. Right Aligned Push-Pull Mode Timing Diagram



Note: MODE='b001, PR=5, P1=6, P2=2, PPEN=1

## 31.2 Period Timer

All slices in a PWM instance operate with the same period. The value written to the PWMxPR register is one less than the number of prescaled PWM clock periods (PWM\_clk) in the PWM period.

The PWMxPR register is double buffered. When the PWM is operating, writes to the PWMxPR register are transferred to the period buffer only after the LD bit is set or an external load event occurs. The transfer occurs at the next period Reset event. If the LD bit is set less than 3 PWM clock periods before the end of the period then the transfer may be one full period later.

Loading the buffers of multiple PWM instances can be coordinated using the PWMLOAD register. See the Buffered Period and Parameter Registers section for more details.

## 31.3 Clock Sources

The time base for the PWM period prescaler is selected with the CLK bits. Changes take effect immediately when written. Clearing the EN bit before making clock source changes is recommended to avoid unexpected behavior.

## 31.3.1 Clock Prescaler

The PWM clock frequency can be reduced with the clock prescaler. There are 256 prescale selections from 1:1 to 1:256.

The CPRE bits select the prescale value. Changes to the prescale value take effect immediately. Clearing the EN bit before making prescaler changes is recommended to avoid unexpected behavior. The prescale counter is reset when the EN bit is cleared.

## 31.4 External Period Resets

The period timer can be reset and held at zero by a logic level from one of various sources. The Reset event also resets the postscaler counter. The resetting source is selected with the ERS bits.

The Reset can be configured with the ERSNOW bit to occur on either the next PWM clock or the next PWM period Reset event. When the ERSNOW bit is set then the Reset will occur on the next PWM clock. When the ERSNOW bit is cleared then the Reset will be held off until the period normally resets at the end of the period. The difference between a normal period Reset and an ERS Reset is that once the timer is reset it is held at zero until the ERS signal goes false. The following timing diagrams illustrate the two types of external Reset.

Figure 31-15. Right Aligned Mode with ERSNOW = 1





Figure 31-16. Left Aligned Mode with ERSNOW = 0



Note: PR=5, P1=4, P2=2

# 31.5 Buffered Period and Parameter Registers

The PWMxPR, PWMxSaP1 and PWMxSaP2 registers are double buffered. The PWM module operates on the buffered copies. The values in all these registers are copied to the buffer registers when the PWM module is enabled.

Changes to the PWMxPR, PWMxSaP1 and PWMxSaP2 registers do not affect the buffer registers while the PWM is operating until either software sets the LD bit or an external load event occurs. For all operating modes except Center Aligned, the values are copied to the buffer registers when the PWM timer is reloaded at the end of the period in which the load request occurred. In the Center Aligned mode the buffer update occurs on every other period Reset event because one full center aligned period uses two period cycles. Load requests that occur three or less clocks before the end of the period may not be serviced until the following period.

A list of external load trigger sources is shown in the PWMxLDS register. Software can set the LD bits of multiple PWM instances simultaneously with the PWMLOAD register.



**Important:** No changes are allowed after the LD bit is set until after the LD bit is cleared by hardware. Unexpected behavior may result if the LD bit is cleared by software.

# 31.6 Synchronizing Multiple PWMs

To synchronize multiple PWMs the PWMEN register is used to enable selected PWMs simultaneously. The bits in the PWMEN register are mirror copies of the EN bit of every PWM in the device. Setting or clearing the EN bits in the PWMEN register enables or disables all the corresponding PWMs simultaneously.

# 31.7 Interrupts

Each PWM instance has a period interrupt and interrupts associated with the mode and parameter settings.

## 31.7.1 Period Interrupt

The period interrupt occurs when the PWMx timer value matches the PR value, thereby also resetting the PWMx timer. Refer to Figure 31-2 for a timing example. The period interrupt is indicated with the PWMxPIF flag bit in one of the PIR registers and is set whether or not the interrupt is enabled. This flag must be reset by software. The PWMxPIF interrupt is enabled with the PWMxPIE bit in the corresponding PIE register.

#### 31.7.1.1 Period Interrupt Postscaler

The frequency of the period interrupt events can be reduced with the period interrupt postscaler. A postscaler counter suppresses period interrupts until the postscale count is reached. Only one PWM period interrupt is generated for every postscale counts. There are 256 postscale selections from 1:1 to 1:256.

The PIPOS bits select the postscale value. Changes to the postscale value take effect immediately. Clearing the EN bit before making postscaler changes is recommended to avoid unexpected behavior. The postscale counter is reset when the EN bit is cleared.

## 31.7.2 Parameter Interrupts

The P1 and P2 parameters in each slice have interrupts that occur depending on the selected mode. The individual parameter interrupts are indicated in the PWMxGIR register and enabled by the corresponding bits in the PWMxGIE register.

A timing example is shown in Figure 31-2. Refer to the timing diagrams of each of the other modes for more details.

All the enabled PWMxGIR interrupts of one PMW instance are OR'd together into the PWMxIF bit in one of the PIR registers. The PWMxIF bit is read-only. When any of the PWMxGIR bits are set then the PWMxIF bit is true. All PWMxGIF flags must be reset to clear the PWMxIF bit. The PWMxIF interrupt is enabled with the PWMxIE bit in the corresponding PIE register.

# 31.8 Operation During Sleep

The PWM module operates in Sleep only if the PWM clock is active. Some internal clock sources are automatically enabled to operate in Sleep when a peripheral using them is enabled. Those clock sources are identified in the clock source table shown in the PWMxCLK clock source selection register.

# 31.9 Register Definitions: PWM Control

Long bit name prefixes for the PWM peripherals are shown in the table below. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 31-1. PWM Bit Name Prefixes


Peripheral	Bit Name Prefix
PWM1	PWM1
PWM2	PWM2
PWM3	PWM3
PWM4	PWM4

## 31.9.1 **PWMxERS**

Name: PWMxERS

**Offset:** 0x460,0x46F,0x47E,0x48D

PWMx External Reset Source



Bits 4:0 - ERS[4:0] External Reset Source Select


ERS	Reset Source						
EKS	PWM1	PWM2	PWM3	PWM4			
11111-10010		Reserved (El	RS Disabled)				
10001		CLC8	_OUT				
10000		CLC7	_OUT				
01111		CLC6	_OUT				
01110		CLC5	_OUT				
01101		CLC4	_OUT				
01100		CLC3	_OUT				
01011	CLC2_OUT						
01010		CLC1	_OUT				
01001	PWM4S1P2_OUT	PWM4S1P2_OUT	PWM4S1P2_OUT	Reserved			
01000	PWM4S1P1_OUT	PWM4S1P1_OUT	PWM4S1P1_OUT	Reserved			
00111	PWM3S1P2_OUT	PWM3S1P2_OUT	Reserved	PWM3S1P2_OUT			
00110	PWM3S1P1_OUT	PWM3S1P1_OUT	Reserved	PWM3S1P1_OUT			
00101	PWM2S1P2_OUT	Reserved	PWM2S1P2_OUT	PWM2S1P2_OUT			
00100	PWM2S1P1_OUT	Reserved	PWM2S1P1_OUT	PWM2S1P1_OUT			
00011	Reserved	PWM1S1P2_OUT	PWM1S1P2_OUT	PWM1S1P2_OUT			
00010	Reserved	PWM1S1P1_OUT	PWM1S1P1_OUT	PWM1S1P1_OUT			
00001	PWM1ERSPPS	PWM2ERSPPS	PWM3ERSPPS	PWM4ERSPPS			
00000		ERS D	isabled				

## 31.9.2 **PWMxCLK**

Name: PWMxCLK

**Offset:** 0x461,0x470,0x47F,0x48E

PWMx Clock Source



Bits 4:0 - CLK[4:0] PWM Clock Source Select


CLK	Source	Operates in sleep			
11111-10110	Reserved	N/A			
10100	CLC8_OUT	Yes <sup>(1)</sup>			
10011	CLC7_OUT	Yes <sup>(1)</sup>			
10010	CLC6_OUT	Yes <sup>(1)</sup>			
10001	CLC5_OUT	Yes <sup>(1)</sup>			
10000	CLC4_OUT	Yes <sup>(1)</sup>			
01111	CLC3_OUT	Yes <sup>(1)</sup>			
01110	CLC2_OUT	Yes <sup>(1)</sup>			
01101	CLC1_OUT	Yes <sup>(1)</sup>			
01100	NCO3_OUT	Yes <sup>(1)</sup>			
01011	NCO2_OUT	Yes <sup>(1)</sup>			
01010	NCO1_OUT	Yes <sup>(1)</sup>			
01001	CLKREF	Yes <sup>(1)</sup>			
01000	EXTOSC	Yes			
00111	SOSC	Yes			
00110	MFINTOSC (32 kHz)	Yes			
00101	MFINTOSC (500 kHz)	Yes			
00100	LFINTOSC	Yes			
00011	HFINTOSC	Yes			
00010	F <sub>osc</sub>	No			
00001	PWMIN1PPS	Yes <sup>(1)</sup>			
00000	PWMIN0PPS	Yes <sup>(1)</sup>			
Note: Operation during Sleep is possible if the clock supplying the source peripheral operates in Sleep.					

#### 31.9.3 **PWMxLDS**

Name: PWMxLDS

**Offset:** 0x462,0x471,0x480,0x48F

PWMx Auto-load Trigger Source Select Register



Bits 4:0 - LDS[4:0] Auto-load Trigger Source Select

LDS	Source
11111-10011	Auto-load Disabled
10010	DMA8_Destination_Count_Done
10001	DMA7_Destination_Count_Done
10000	DMA6_Destination_Count_Done
01111	DMA5_Destination_Count_Done
01110	DMA4_Destination_Count_Done
01101	DMA3_Destination_Count_Done
01100	DMA2_Destination_Count_Done
01011	DMA1_Destination_Count_Done
01010	CLC8_OUT
01001	CLC7_OUT
01000	CLC6_OUT
00111	CLC5_OUT
00110	CLC4_OUT
00101	CLC3_OUT
00100	CLC2_OUT
00011	CLC1_OUT
00010	PWMIN1PPS
00001	PWMIN0PPS
00000	Auto-load Disabled

#### 31.9.4 PWMxPR

Name: PWMxPR

**Offset:** 0x463,0x472,0x481,0x490

PWMx Period Register

Determines the PWMx period

Bit	15	14	13	12	11	10	9	8
				PR[	15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
				PR[	7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

### Bits 15:0 - PR[15:0] PWM Period

Number of PWM clocks periods in the PWM period

Notes: The individual bytes in this multi-byte register can be accessed with the following register names:

- PWMxPRH: Accesses the high byte PR[15:8]
- PWMxPRL: Accesses the low byte PR[7:0]

# PIC18F26/46/56Q84

# **PWM - Pulse-Width Modulator with Compare**

#### 31.9.5 PWMxCPRE

Name: PWMxCPRE

**Offset:** 0x465,0x474,0x483,0x492

PWMx Clock Prescaler Register

Bit	7	6	5	4	3	2	1	0
				CPRI	E[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - CPRE[7:0] PWM Clock Prescale Value

Value	Description
n	PWM clock is prescaled by n+1

# **PWM - Pulse-Width Modulator with Compare**

#### 31.9.6 PWMxPIPOS

Name: PWMxPIPOS

**Offset:** 0x466,0x475,0x484,0x493
PWMx Period Interrupt Postscaler Register

Bit	7	6	5	4	3	2	1	0
				PIPO	S[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - PIPOS[7:0] Period Interrupt Postscale Value


Value	Description
n	Period interrupt occurs after n+1 period events

#### 31.9.7 PWMxGIR

Name: PWMxGIR

**Offset:** 0x467,0x476,0x485,0x494

PWMx Interrupt Register



#### Bit 1 - SaP2 Slice "a" Parameter 2 Interrupt Flag

Value	MODE	Description
1	Variable aligned or Compare	Compare match between P2 and PWM counter has occurred
1	Center aligned	PWMx_SaP2_out has changed
1	Right aligned	Left edge of PWMx_SaP2_out pulse has occurred
1	Left aligned	Right edge of PWMx_SaP2_out pulse has occurred
0	All	Interrupt event has not occurred

#### Bit 0 - SaP1 Slice "a" Parameter 1 Interrupt Flag


Value	MODE	Description
1	Variable aligned or Compare	Compare match between P1 and PWM counter has occurred
1	Center aligned	PWMx_SaP1_out has changed
1	Right aligned	Left edge of PWMx_SaP1_out pulse has occurred
1	Left aligned	Right edge of PWMx_SaP1_out pulse has occurred
0	All	Interrupt event has not occurred

#### 31.9.8 **PWMxGIE**

Name: PWMxGIE

**Offset:** 0x468,0x477,0x486,0x495

PWMx Interrupt Enable Register



Bit 1 - SaP2 Slice "a" Parameter 2 Interrupt Enable

	Value	Description
ſ	1	Slice "a" Parameter 2 match interrupt is enabled
	0	Slice "a" Parameter 2 match interrupt is not enabled

# Bit 0 - SaP1 Slice "a" Parameter 1 Interrupt Enable

Va	alue	Description
1		Slice "a" Parameter 1 match interrupt is enabled
0		Slice "a" Parameter 1 match interrupt is not enabled

#### 31.9.9 **PWMxCON**

Name: PWMxCON

**Offset:** 0x469,0x478,0x487,0x496

**PWM Control Register** 

Bit	7	6	5	4	3	2	1	0
	EN					LD	ERSPOL	ERSNOW
Access	R/W					R/W/HC	R/W	R/W
Reset	0					0	0	0

#### Bit 7 - EN PWM Module Enable

Value	Description
1	PWM module is enabled
0	PWM module is disabled. The prescaler, postscaler, and all internal logic is reset. Outputs go to their
	default states. Register values remain unchanged.

#### Bit 2 – LD Reload Registers

Reload the period and duty cycle registers on the next period event

Value	Description
value	Description
1	Reload PR/P1/P2 registers
0	Reload not enabled or reload complete

#### Bit 1 - ERSPOL External Reset Polarity Select

Value	Description
1	External Reset input is active-low
0	External Reset input is active-high

## Bit 0 - ERSNOW External Reset Mode Select

Determines when an external Reset event takes effect.

Value	Description
1	Stop counter on the next PWM clock. Output goes to the Inactive state.
0	Stop counter at the end of the period. Output goes to the Inactive state.

#### 31.9.10 PWMxSaCFG

Name: PWMxSaCFG

PWM Slice "a" Configuration Register(1)

Bit	7	6	5	4	3	2	1	0
	POL2	POL1			PPEN		MODE[2:0]	
Access	R/W	R/W			R/W	R/W	R/W	R/W
Reset	0	0			0	0	0	0

#### Bit 7 - POL2 PWM Slice "a" Parameter 2 Output Polarity

Valu	ıe	Description
1		PWMx_SaP2_out is low true
0		PWMx_SaP2_out is high true

#### Bit 6 - POL1 PWM Slice "a" Parameter 1 Output Polarity

Valu	e Description	
1	PWMx_SaP1_out is low true	
0	PWMx_SaP1_out is high true	

#### Bit 3 - PPEN Push-Pull Mode Enable

Each period the output alternates between PWMx\_SaP1\_out and PWMx\_SaP2\_out. Only Left and Right Aligned modes are supported. Other modes may exhibit unexpected results.

Value	Description
1	PWMx Slice "a" Push-Pull mode is enabled
0	PWMx Slice "a" Push-Pull mode is not enabled

# **Bits 2:0 – MODE[2:0]** PWM Module Slice "a" Operating Mode Select Selects operating mode for both PWMx\_SaP1\_out and PWMx\_SaP2\_out

Value	Description
11x	Reserved. Outputs go to Reset state.
101	Compare mode: Toggle PWMx_SaP1_out and PWMx_SaP2_out on PWM timer match with corresponding parameter register
100	Compare mode: Set PWMx_SaP1_out and PWMx_SaP2_out high on PWM timer match with corresponding parameter register
011	Variable Aligned mode
010	Center Aligned mode
001	Right Aligned mode
000	Left Aligned mode

#### Note:

1. Changes to this register must be done only when the EN bit is cleared.

#### 31.9.11 PWMxSaP1

Name: PWMxSaP1

PWM Slice "a" Parameter 1 Register

Determines the active period of slice "a", parameter 1 output

Bit	15	14	13	12	11	10	9	8
				P1[1	15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
				P1[	7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

#### Bits 15:0 - P1[15:0] Parameter 1 Value

Value	MODE	Description
n	Compare	Compare match event occurs when PWMx timer = n (Refer to MODE selections)
n	Variable aligned	PWMx_SaP1_out and PWMx_SaP2 both go high when PWMx timer = n
n	Center aligned	PWMx_SaP1_out is high 2*n PWMx clock periods centered around PWMx period event
n	Right aligned	PWMx_SaP1_out is high n PWMx clock periods at end of PWMx period
n	Left aligned	PWMx_SaP1_out is high n PWMx clock periods at beginning of PWMx period

**Notes:** The individual bytes in this multi-byte register can be accessed with the following register names:

- PWMxSaP1H: Accesses the high byte P1[15:8]
- PWMxSaP1L: Accesses the low byte P1[7:0]

#### 31.9.12 PWMxSaP2

Name: PWMxSaP2

PWM Slice "a" Parameter 2 Register

Determines the active period of slice "a", parameter 2 output

Bit	15	14	13	12	11	10	9	8
				P2[1	15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
				P2[	7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

#### Bits 15:0 - P2[15:0] Parameter 2 Value

Value	MODE	Description
n	Compare	Compare match event occurs when PWMx timer = n (Refer to MODE selections)
n	Variable aligned	PWMx_SaP1_out and PWMx_SaP2 both go low when PWMx timer = n
n	Center aligned	PWMx_SaP2_out is high 2*n PWMx clock periods centered around PWMx period event
n	Right aligned	PWMx_SaP2_out is high n PWMx clock periods at end of PWMx period
n	Left aligned	PWMx_SaP2_out is high n PWMx clock periods at beginning of PWMx period


**Notes:** The individual bytes in this multi-byte register can be accessed with the following register names:

- PWMxSaP2H: Accesses the high byte P2[15:8]
- PWMxSaP2L: Accesses the low byte P2[7:0]

#### 31.9.13 PWMLOAD

Name: PWMLOAD Offset: 0x49C

Mirror copies of all PWMxLD bits



Bits 0, 1, 2, 3 - MPWMxLD Mirror copy of PWMxLD bit

Mirror copies of all PWMxLD bits can be set simultaneously to synchronize the load event across all PWMs

Value	Description
1	PWMx parameter and period values will be transferred to their buffer registers at the next period Reset
	event
0	There are no PWMx period and parameter value transfers pending

#### 31.9.14 PWMEN

Name: PWMEN Offset: 0x49D

Mirror copies of all PWMxEN bits



Bits 0, 1, 2, 3 - MPWMxEN Mirror copy of PWMxEN bit

Mirror copies of all PWMxEN bits can be set simultaneously to synchronize the enable event across all PWMs

Value	Description
1	PWMx is enabled
0	PWMx is not enabled

# 31.10 Register Summary - PWM

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x045F										
0x0460	PWM1ERS	7:0						ERS[4:0]		
0x0461	PWM1CLK	7:0						CLK[4:0]		
0x0462	PWM1LDS	7:0						LDS[4:0]		
0x0463	PWM1PR	7:0					[7:0]			
0,0100		15:8					15:8]			
0x0465	PWM1CPRE	7:0					E[7:0]			
0x0466	PWM1PIPOS	7:0				PIPO	S[7:0]			
0x0467	PWM1GIR	7:0							S1P2	S1P1
0x0468	PWM1GIE	7:0							S1P2	S1P1
0x0469	PWM1CON	7:0	EN					LD	ERSPOL	ERSNOW
0x046A	PWM1S1CFG	7:0	POL2	POL1			PPEN		MODE[2:0]	
0x046B	PWM1S1P1	7:0				P1	[7:0]			
070400	1 WWITOTI 1	15:8				P1[ <sup>-</sup>	15:8]			
0x046D	PWM1S1P2	7:0		P2[7:0]						
0.00+0.0		15:8		P2[15:8]						
0x046F	PWM2ERS	7:0						ERS[4:0]		
0x0470	PWM2CLK	7:0						CLK[4:0]		
0x0471	PWM2LDS	7:0						LDS[4:0]		
0x0472	PWM2PR	7:0	PR[7:0]							
UXU472	PWWZPR	15:8	PR[15:8]							
0x0474	PWM2CPRE	7:0		CPRE[7:0]						
0x0475	PWM2PIPOS	7:0				PIPO	S[7:0]			
0x0476	PWM2GIR	7:0							S1P2	S1P1
0x0477	PWM2GIE	7:0							S1P2	S1P1
0x0478	PWM2CON	7:0	EN					LD	ERSPOL	ERSNOW
0x0479	PWM2S1CFG	7:0	POL2	POL1			PPEN		MODE[2:0]	
	DIVINO 4D4	7:0				P1	7:0]			
0x047A	PWM2S1P1	15:8				P1[	15:8]			
	DIAMAGO 4 DO	7:0				P2	7:0]			
0x047C	PWM2S1P2	15:8					15:8]			
0x047E	PWM3ERS	7:0					-	ERS[4:0]		
0x047F	PWM3CLK	7:0						CLK[4:0]		
0x0480	PWM3LDS	7:0						LDS[4:0]		
		7:0				PR	[7:0]			
0x0481	PWM3PR	15:8					15:8]			
0x0483	PWM3CPRE	7:0					E[7:0]			
0x0484	PWM3PIPOS	7:0					S[7:0]			
0x0485	PWM3GIR	7:0							S1P2	S1P1
0x0486	PWM3GIE	7:0							S1P2	S1P1
0x0487	PWM3CON	7:0	EN					LD	ERSPOL	ERSNOW
0x0488	PWM3S1CFG	7:0	POL2	POL1			PPEN		MODE[2:0]	
		7:0	P1[7:0]							
0x0489	PWM3S1P1	15:8					15:8]			
		7:0				<u>.</u>				
0x048B	PWM3S1P2	15:8	P2[7:0] P2[15:8]							
0x048D	PWM4ERS	7:0				[		ERS[4:0]		
0x048E	PWM4CLK	7:0	CLK[4:0]							
0x048F	PWM4LDS	7:0	LDS[4:0]							
		7:0	PR[7:0]							
0x0490	PWM4PR	15:8					15:8]			
0x0492	PWM4CPRE	7:0					E[7:0]			
0x0492 0x0493	PWM4PIPOS	7:0					S[7:0]			
0x0493	PWM4GIR	7:0				FIPU	رر		S1P2	S1P1
030494	FVVIVI4GIR	7.0							3172	3171

# PIC18F26/46/56Q84

# **PWM - Pulse-Width Modulator with Compare**

cont	continued									
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x0495	PWM4GIE	7:0							S1P2	S1P1
0x0496	PWM4CON	7:0	EN					LD	ERSPOL	ERSNOW
0x0497	PWM4S1CFG	7:0	POL2	POL1			PPEN		MODE[2:0]	
0x0498	PWM4S1P1	7:0		•		P1[	7:0]			
0X0496		15:8		P1[15:8]						
0x049A	PWM4S1P2	7:0				P2[	7:0]			
0X049A	FWW451F2	15:8		P2[15:8]						
0x049C	PWMLOAD	7:0					MPWM4LD	MPWM3LD	MPWM2LD	MPWM1LD
0x049D	PWMEN	7:0					MPWM4EN	MPWM3EN	MPWM2EN	MPWM1EN

# 32. CWG - Complementary Waveform Generator Module

The Complementary Waveform Generator (CWG) produces half-bridge, full-bridge, and steering of PWM waveforms. It is backwards compatible with previous CCP functions.

The CWG has the following features:

- · Six Operating modes:
  - Synchronous Steering mode
  - Asynchronous Steering mode
  - Full-Bridge mode, Forward
  - Full-Bridge mode, Reverse
  - Half-Bridge mode
  - Push-Pull mode
- Output Polarity Control
- · Output Steering
- Independent 6-bit Rising and Falling Event Dead-Band Timers:
  - Clocked dead band
  - Independent rising and falling dead-band enables
- Auto-Shutdown Control With:
  - Selectable shutdown sources
  - Auto-restart option
  - Auto-shutdown pin override control

# 32.1 Fundamental Operation

The CWG generates two output waveforms from the selected input source.

The off-to-on transition of each output can be delayed from the on-to-off transition of the other output, thereby creating a time delay immediately where neither output is driven. This is referred to as dead time and is covered in Dead-Band Control section.

It may be necessary to guard against the possibility of circuit faults or a feedback event arriving too late or not at all. In this case, the active drive must be terminated before the Fault condition causes damage. This is referred to as auto-shutdown and is covered in the Auto-Shutdown section.

## 32.2 Operating Modes

The CWG module can operate in six different modes, as specified by the MODE bits:

- · Half-Bridge mode
- Push-Pull mode
- Asynchronous Steering mode
- · Synchronous Steering mode
- · Full-Bridge mode, Forward
- Full-Bridge mode, Reverse

All modes accept a single pulse input, and provide up to four outputs as described in the following sections.

All modes include auto-shutdown control as described in Auto-Shutdown section.



Important: Except as noted for Full-Bridge mode, mode changes should only be performed while EN = 0.

# 32.2.1 Half-Bridge Mode

In Half-Bridge mode, two output signals are generated as true and inverted versions of the input as illustrated in Figure 32-1. A non-overlap (dead-band) time is inserted between the two outputs to prevent shoot-through current in various power supply applications. Dead-band control is described in Dead-Band Control section. The output steering feature cannot be used in this mode. A basic block diagram of this mode is shown in Figure 32-2.

The unused outputs CWGxC and CWGxD drive similar signals as CWGxA and CWGxB, with polarity independently controlled by the POLC and POLD bits, respectively.

Figure 32-1. CWG Half-Bridge Mode Operation





Figure 32-2. Simplified CWG Block Diagram (Half-Bridge Mode, MODE = 'b100)



#### 32.2.2 Push-Pull Mode

In Push-Pull mode, two output signals are generated, alternating copies of the input as illustrated in Figure 32-3. This alternation creates the Push-Pull effect required for driving some transformer-based power supply designs. Steering modes are not used in Push-Pull mode. A basic block diagram for the Push-Pull mode is shown in Figure 32-4.

The Push-Pull sequencer is reset whenever EN = 0 or if an auto-shutdown event occurs. The sequencer is clocked by the first input pulse, and the first output appears on CWGxA.

The unused outputs CWGxC and CWGxD drive copies of CWGxA and CWGxB, respectively, but with polarity controlled by the POLC and POLD bits, respectively.

Figure 32-3. CWG Push-Pull Mode Operation






Figure 32-4. Simplified CWG Block Diagram (Push-Pull Mode, MODE = 'b101)



## 32.2.3 Full-Bridge Mode

In Forward and Reverse Full-Bridge modes, three outputs drive static values while the fourth is modulated by the input data signal. The mode selection may be toggled between forward and reverse by toggling the MODE[0] bit of the CWGxCON0 while keeping the MODE[2:1] bits static, without disabling the CWG module. When connected, as shown in Figure 32-5, the outputs are appropriate for a full-bridge motor driver. Each CWG output signal has independent polarity control, so the circuit can be adapted to high-active and low-active drivers. A simplified block diagram for the Full-Bridge modes is shown in Figure 32-6.

Figure 32-5. Example of Full-Bridge Application







Figure 32-6. Simplified CWG Block Diagram (Forward and Reverse Full-Bridge Modes)

In Forward Full-Bridge mode (MODE = 'b010), CWGxA is driven to its Active state, CWGxB and CWGxC are driven to their Inactive state, and CWGxD is modulated by the input signal, as shown in Figure 32-7.

In Reverse Full-Bridge mode (MODE = 'b011), CWGxC is driven to its Active state, CWGxA and CWGxD are driven to their Inactive states, and CWGxB is modulated by the input signal, as shown in Figure 32-7.

In Full-Bridge mode, the dead-band period is used when there is a switch from forward to reverse or vice versa. This dead-band control is described in the Dead-Band Control section, with additional details in the Rising Edge and Reverse Dead Band and Falling Edge and Forward Dead Band sections. Steering modes are not used with either of the Full-Bridge modes.

Figure 32-7. Example of Full-Bridge Output



### Notes:

- 1. A rising CWG data input creates a rising event on the modulated output.
- 2. Output signals shown as active-high; all POLy bits are clear.

#### 32.2.3.1 Direction Change in Full-Bridge Mode


In Full-Bridge mode, changing the MODE[0] bit controls the forward/reverse direction. Direction changes occur on the next rising edge of the modulated input.

The sequence, described as follows, is illustrated in Figure 32-8.

- The associated active output CWGxA and the inactive output CWGxC are switched to drive in the opposite direction.
- 2. The previously modulated output CWGxD is switched to the Inactive state, and the previously inactive output CWGxB begins to modulate.

3. CWG modulation resumes after the direction-switch dead band has elapsed.

Figure 32-8. Example of PWM Direction Change at Near 100% Duty Cycle



#### 32.2.3.2 Dead-Band Delay in Full-Bridge Mode

Dead-band delay is important when either of the following conditions is true:

- The direction of the CWG output changes when the duty cycle of the data input is at or near 100%.
- The turn-off time of the power switch, including the power device and driver circuit, is greater than the turn-on time.

The dead-band delay is inserted only when changing directions, and only the modulated output is affected. The statically-configured outputs (CWGxA and CWGxC) are not afforded dead-band, and switch essentially simultaneously.

Figure 32-8 shows an example of the CWG outputs changing directions from forward to reverse, at near 100% duty cycle. In this example, at time t1, the output of CWGxA and CWGxD become inactive, while output CWGxC becomes active. Since the turn-off time of the power devices is longer than the turn-on time, a shoot-through current will flow through power devices QC and QD for the duration of 'T'. The same phenomenon will occur to power devices QA and QB for the CWG direction change from reverse to forward.

When changing the CWG direction at high duty cycle is required for an application, two possible solutions for eliminating the shoot-through current are:

- 1. Reduce the CWG duty cycle for one period before changing directions.
- 2. Use switch drivers that can drive the switches off faster than they can drive them on.

#### 32.2.4 Steering Modes

In both Synchronous and Asynchronous Steering modes, the CWG Data can be steered to any combination of four CWG outputs. A fixed-value will be presented on all the outputs not used for the PWM output. Each output has independent polarity, steering, and shutdown options. Dead-band control is not used in either Steering mode.


For example, when STRA = 0 then the corresponding pin is held at the level defined by OVRA. When STRA = 1, then the pin is driven by the CWG Data signal.

# PIC18F26/46/56Q84

# **CWG - Complementary Waveform Generator Mod...**

The POLy bits control the signal polarity only when STRy = 1.

The CWG auto-shutdown operation also applies in Steering modes as described in Auto-Shutdown. An auto-shutdown event will only affect pins that have STRy = 1.



**CWG** Data

STRD

Q

SHUTDOWN

FREEZE


#### 32.2.4.1 Synchronous Steering Mode

In Synchronous Steering mode (MODE = 'b001), the changes to steering selection registers take effect on the next rising edge of CWG Data (see figure below). In Synchronous Steering mode, the output will always produce a complete waveform.



Important: Only the STRx bits are synchronized; the OVRx bits are not synchronized.


Figure 32-10. Example of Synchronous Steering (MODE = 'b001)



#### 32.2.4.2 Asynchronous Steering Mode

In Asynchronous mode (MODE = 'b000), steering takes effect at the end of the instruction cycle that writes to STRx. In Asynchronous Steering mode, the output signal may be an incomplete waveform (see figure below). This operation may be useful when the user firmware needs to immediately remove a signal from the output pin.

Figure 32-11. Example of Asynchronous Steering (MODE = 'b000)



#### 32.2.4.3 Start-up Considerations

The application hardware must use the proper external pull-up and/or pull-down resistors on the CWG output pins. This is required because all I/O pins are forced to high-impedance at Reset.

The Polarity Control bits (POLy) allow the user to choose whether the output signals are active-high or active-low.

#### 32.3 Clock Source

The clock source is used to drive the dead-band timing circuits. The CWG module allows the following clock sources to be selected:

- F<sub>OSC</sub> (system clock)
- HFINTOSC

When the HFINTOSC is selected, the HFINTOSC will be kept running during Sleep. Therefore, CWG modes requiring dead-band can operate in Sleep, provided that the CWG data input is also active during Sleep. The clock sources are selected using the CS bit. The system clock F<sub>OSC</sub>, is disabled in Sleep and thus dead-band control cannot be used.

## 32.4 Selectable Input Sources

The CWG generates the output waveforms from the input sources which are selected with the ISM bits. Refer to the CWGxISM register for more details.

# 32.5 Output Control

#### 32.5.1 CWG Output

Each CWG output can be routed to a Peripheral Pin Select (PPS) output via the RxyPPS register. Refer to the "PPS - Peripheral Pin Select Module" chapter for more details.

## 32.5.2 Polarity Control

The polarity of each CWG output can be selected independently. When the output polarity bit is set, the corresponding output is active-high. Clearing the output polarity bit configures the corresponding output as active-low. However, polarity does not affect the override levels. Output polarity is selected with the POLy bits. Auto-shutdown and steering options are unaffected by polarity.

#### 32.6 Dead-Band Control

The dead-band control provides non-overlapping complementary outputs to prevent shoot-through current when the outputs switch. Dead-band operation is employed for Half-Bridge and Full-Bridge modes. The CWG contains two 6-bit dead-band counters. One is used for the rising edge of the input source control in Half-Bridge mode or for reverse direction change dead-band in Full-Bridge mode. The other is used for the falling edge of the input source control in Half-Bridge mode or for forward direction change dead-band in Full-Bridge mode.

Dead-band is timed by counting CWG clock periods from zero up to the value in the rising or falling dead-band counter registers.

#### 32.6.1 Dead-Band Functionality In Half-Bridge Mode

In Half-Bridge mode, the dead-band counters dictate the delay between the falling edge of the normal output and the rising edge of the inverted output. This can be seen in Figure 32-1.

#### 32.6.2 Dead-Band Functionality In Full-Bridge Mode


In Full-Bridge mode, the dead-band counters are used when undergoing a direction change. The MODE[0] bit can be set or cleared while the CWG is running, allowing for changes from Forward to Reverse mode. The CWGxA and CWGxC signals will change immediately upon the first rising input edge following a direction change, but the modulated signals (CWGxB or CWGxD, depending on the direction of the change) will experience a delay dictated by the dead-band counters.

## 32.7 Rising Edge and Reverse Dead-Band

In Half-Bridge mode, the rising edge dead-band delays the turn-on of the CWGxA output after the rising edge of the CWG data input. In Full-Bridge mode, the reverse dead-band delay is only inserted when changing directions from Forward mode to Reverse mode, and only the modulated output, CWGxB, is affected.

The CWGxDBR register determines the duration of the dead-band interval on the rising edge of the input source signal. This duration is from 0 to 64 periods of the CWG clock. The following figure illustrates different dead-band delays for rising and falling CWG Data events.

Figure 32-12. Dead-Band Operation, CWGxDBR = 0x01, CWGxDBF = 0x02



Dead-band is always initiated on the edge of the input source signal. A count of zero indicates that no dead-band is present.

If the input source signal reverses polarity before the dead-band count is completed, then no signal will be seen on the respective output.

The CWGxDBR register value is double-buffered. When EN = 0, the buffer is loaded when CWGxDBR is written. When EN = 1, then the buffer will be loaded at the rising edge following the first falling edge of the CWG Data, after the LD bit is set.

# 32.8 Falling Edge and Forward Dead Band


In Half-Bridge mode, the falling edge dead band delays the turn-on of the CWGxB output at the falling edge of the CWG data input. In Full-Bridge mode, the forward dead-band delay is only inserted when changing directions from Reverse mode to Forward mode, and only the modulated output CWGxD is affected.

The CWGxDBF register determines the duration of the dead-band interval on the falling edge of the input source signal. This duration is from zero to 64 periods of CWG clock.

Dead-band delay is always initiated on the edge of the input source signal. A count of zero indicates that no dead band is present.

If the input source signal reverses polarity before the dead-band count is completed, then no signal will be seen on the respective output.

Figure 32-13. Dead-Band Operation, CWGxDBR = 0x03, CWGxDBF = 0x06, Source Shorter Than Dead Band



The CWGxDBF register value is double-buffered. When EN = 0, the buffer is loaded when CWGxDBF is written. When EN = 1, then the buffer will be loaded at the rising edge following the first falling edge of the data input after the LD is set.

#### 32.9 Dead-Band Jitter

When the rising and falling edges of the input source are asynchronous to the CWG clock, it creates jitter in the deadband time delay. The maximum jitter is equal to one CWG clock period. Refer to the equations below for more details.

**Equation 32-1. Dead-Band Delay Time Calculation** 

$$T_{DEAD-BAND\_MIN} = \frac{1}{F_{CWG\ CLOCK}} \bullet DBx$$

$$T_{DEAD\,-\,BAND\_MAX} = \frac{1}{F_{CWG\_CLOCK}} \bullet (DBx + 1)$$

$$T_{IITTER} = T_{DEAD - BAND\_MAX} - T_{DEAD - BAND\_MIN}$$

$$T_{JITTER} = \frac{1}{F_{CWG\ CLOCK}}$$

$$T_{DEAD-BAND\ MAX} = T_{DEAD-BAND\ MIN} + T_{IITTER}$$

#### **Dead-Band Delay Example Calculation**

$$DBx = 0x0A = 10$$

$$F_{CWG\ CLOCK} = 8\ MHz$$

$$T_{JITTER} = \frac{1}{8 MHz} = 125 ns$$


$$T_{DEAD-BAND\ MIN} = 125ns \bullet 10 = 1.25\mu s$$

$$T_{DEAD-BAND\ MAX} = 1.25\mu s + 0.125\ \mu s = 1.37\mu s$$

#### 32.10 Auto-Shutdown

Auto-shutdown is a method to immediately override the CWG output levels with specific overrides that allow for safe shutdown of the circuit. The Shutdown state can be either cleared automatically or held until cleared by software. The auto-shutdown circuit is illustrated in the following figure.

#### Figure 32-14. CWG Shutdown Block Diagram



#### 32.10.1 Shutdown

The Shutdown state can be entered by either of the following two methods:

- · Software Generated
- External Input

#### 32.10.2 Software Generated Shutdown

Setting the SHUTDOWN bit will force the CWG into the Shutdown state.

When the auto-restart is disabled, the Shutdown state will persist as long as the SHUTDOWN bit is set.

When auto-restart is enabled, the SHUTDOWN bit will clear automatically and resume operation on the next rising edge event. The SHUTDOWN bit indicates when a shutdown condition exists. The bit may be set or cleared in software or by hardware.

#### 32.10.3 External Input Source

External shutdown inputs provide the fastest way to safely suspend CWG operation in the event of a Fault condition. When any of the selected shutdown inputs goes active, the CWG outputs will immediately go to the selected override levels without software delay. The override levels are selected by the LSBD and LSAC bits. Several input sources can be selected to cause a shutdown condition. All input sources are active-low. The shutdown input sources are individually enabled by the ASyE bits.



**Important:** Shutdown inputs are level sensitive, not edge sensitive. The Shutdown state cannot be cleared, except by disabling auto-shutdown, as long as the shutdown input level persists.

#### 32.10.4 Pin Override Levels

The levels driven to the CWG outputs during an auto-shutdown event are controlled by the LSBD and LSAC bits. The LSBD bits control CWGxB/D output levels, while the LSAC bits control the CWGxA/C output levels.

#### 32.10.5 Auto-Shutdown Interrupts

When an auto-shutdown event occurs, either by software or hardware setting SHUTDOWN, the CWGxIF flag bit of the PIRx register is set.

### 32.11 Auto-Shutdown Restart

After an auto-shutdown event has occurred, there are two ways to resume operation:

- Software controlled
- Auto-restart

In either case, the shutdown source must be cleared before the restart can take place. That is, either the shutdown condition must be removed, or the corresponding ASYE bit must be cleared.

#### 32.11.1 Software-Controlled Restart


When the REN bit is clear (REN = 0), the CWG module must be restarted after an auto-shutdown event through software.

Once all auto-shutdown sources are removed, the software must clear the SHUTDOWN bit. Once SHUTDOWN is cleared, the CWG module will resume operation upon the first rising edge of the CWG data input.



**Important:** The SHUTDOWN bit cannot be cleared in software if the auto-shutdown condition is still present.

Figure 32-15. Shutdown Functionality, Auto-Restart Disabled (REN = 0, LSAC = 'b01, LSBD = 'b01)



#### 32.11.2 Auto-Restart

When the REN bit is set (REN = 1), the CWG module will restart from the Shutdown state automatically.


# CWG - Complementary Waveform Generator Mod...

Once all auto-shutdown conditions are removed, the hardware will automatically clear the SHUTDOWN bit. Once SHUTDOWN is cleared, the CWG module will resume operation upon the first rising edge of the CWG data input.



**Important:** The SHUTDOWN bit cannot be cleared in software if the auto-shutdown condition is still present.

Figure 32-16. Shutdown Functionality, Auto-Restart Enabled (REN = 1, LSAC = 'b01, LSBD = 'b01)



# 32.12 Operation During Sleep

The CWG module operates independently from the system clock and will continue to run during Sleep, provided that the clock and input sources selected remain active.

The HFINTOSC remains active during Sleep when all the following conditions are met:

- · CWG module is enabled
- · Input source is active
- · HFINTOSC is selected as the clock source, regardless of the system clock source selected.

In other words, if the HFINTOSC is simultaneously selected as the system clock and the CWG clock source, when the CWG is enabled and the input source is active, then the CPU will go idle during Sleep, but the HFINTOSC will remain active and the CWG will continue to operate. This will have a direct effect on the Sleep mode current.

# 32.13 Configuring the CWG

- 1. Ensure that the TRIS control bits corresponding to CWG outputs are set so that all are configured as inputs, ensuring that the outputs are inactive during setup. External hardware must ensure that pin levels are held to safe levels.
- 2. Clear the EN bit, if not already cleared.
- 3. Configure the MODE bits to set the output operating mode.
- 4. Configure the POLy bits to set the output polarities.
- 5. Configure the ISM bits to select the data input source.
- 6. If a steering mode is selected, configure the STRy bits to select the desired output on the CWG outputs.
- 7. Configure the LSBD and LSAC bits to select the auto-shutdown output override states (this is necessary even if not using auto-shutdown because start-up will be from a Shutdown state).
- 8. If auto-restart is desired, set the REN bit.
- 9. If auto-shutdown is desired, configure the ASyE bits to select the shutdown source.
- Set the desired rising and falling dead-band times with the CWGxDBR and CWGxDBF registers.
- 11. Select the clock source with the CS bit.

- 12. Set the EN bit to enable the module.
- 13. Clear the TRIS bits that correspond to the CWG outputs to set them as outputs.

If auto-restart is to be used, set the REN bit and the SHUTDOWN bit will be cleared automatically. Otherwise, clear the SHUTDOWN bit in software to start the CWG.

# 32.14 Register Definitions: CWG Control

Long bit name prefixes for the CWG peripherals are shown in the table below. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 32-1. CWG Long bit name prefixes

Peripheral	Bit Name Prefix
CWG1	CWG1
CWG2	CWG2
CWG3	CWG3

#### 32.14.1 CWGxCON0

Name: CWGxCON0

**Offset:** 0x3C0,0x3C9,0x3D2

CWG Control Register 0

Bit	7	6	5	4	3	2	1	0
	EN	LD					MODE[2:0]	
Access	R/W	R/W/HC				R/W	R/W	R/W
Reset	0	0				0	0	0

#### Bit 7 - EN CWG Enable

Value	Description
1	Module is enabled
0	Module is disabled

# Bit 6 - LD CWG1 Load Buffers(1)

Value	Description
1	Dead-band count buffers to be loaded on CWG data rising edge, following first falling edge after this bit
	is set
0	Buffers remain unchanged

### Bits 2:0 - MODE[2:0] CWG Mode

Value	Description
111	Reserved
110	Reserved
101	CWG outputs operate in Push-Pull mode
100	CWG outputs operate in Half-Bridge mode
011	CWG outputs operate in Reverse Full-Bridge mode
010	CWG outputs operate in Forward Full-Bridge mode
001	CWG outputs operate in Synchronous Steering mode
000	CWG outputs operate in Asynchronous Steering mode

#### Note:

1. This bit can only be set after EN = 1; it cannot be set in the same cycle when EN is set.

#### 32.14.2 CWGxCON1

Name: CWGxCON1

**Offset:** 0x3C1,0x3CA,0x3D3

CWG Control Register 1

Bit	7	6	5	4	3	2	1	0
			IN		POLD	POLC	POLB	POLA
Access			R		R/W	R/W	R/W	R/W
Reset			X		0	0	0	0

#### Bit 5 - IN CWG Input Value (read-only)

Value	Description
1	CWG data input is a logic 1
0	CWG data input is a logic 0

# Bits 0, 1, 2, 3 - POLy CWG Output 'y' Polarity

Value	Description
1	Signal output is inverted polarity
0	Signal output is normal polarity

## 32.14.3 CWGxCLK

Name: CWGxCLK

Offset: 0x3BC,0x3C5,0x3CE

CWG Clock Input Selection Register



Bit 0 - CS CWG Clock Source Selection Select


Value	Description
1	HFINTOSC (remains operating during Sleep)
0	Fosc

## 32.14.4 CWGxISM

Name: CWGxISM

Offset: 0x3BD,0x3C6,0x3CF

CWGx Input Selection Register



Bits 4:0 - ISM[4:0] CWG Data Input Source Select

ISM	Input Selection			
ISIVI	CWG1	CWG2	CWG3	
11111-11010		Reserved		
11001	CLC8_OUT			
11000	CLC7_OUT			
10111		CLC6_OUT		
10110	CLC5_OUT			
10101		CLC4_OUT		
10100		CLC3_OUT		
10011	CLC2_OUT			
10010		CLC1_OUT		
10001	DSM1_OUT			
10000	CMP2_OUT			
01111	CMP1_OUT			
01110	NCO3_OUT			
01101				
01100		NCO1_OUT		
01011	PWM4S1P2_OUT			
01010	PWM4S1P1_OUT			
01001	PWM3S1P2_OUT			
01000	PWM3S1P1_OUT			
00111	PWM2S1P2_OUT			
00110	PWM2S1P1_OUT			
00101	PWM1S1P2_OUT			
00100	PWM1S1P1_OUT			
00011	CCP3_OUT			
00010	CCP2_OUT			
00001	CCP1_OUT			
00000	Pin selected by CWG1PPS	Pin selected by CWG2PPS	Pin selected by CWG3PPS	

#### 32.14.5 CWGxSTR

Name: CWGxSTR

**Offset:** 0x3C4,0x3CD,0x3D6

CWG Steering Control Register(1)

Bit	7	6	5	4	3	2	1	0
	OVRD	OVRC	OVRB	OVRA	STRD	STRC	STRB	STRA
Access	R/W							
Reset	0	0	0	0	0	0	0	0

#### Bits 4, 5, 6, 7 - OVRy Steering Data OVR'y'

, -, -							
Value	Condition	Description					
X	STRy = 1	CWGx'y' output has the CWG data input waveform with polarity control from					
		POLy bit					
1	STRy = $0$ and POLy = $x$	CWGx'y' output is high					
0	STRy = $0$ and POLy = $\times$	CWGx'y' output is low					

# Bits 0, 1, 2, 3 - STRy STR'y' Steering Enable<sup>(2)</sup>

			,	<u> </u>
Value	Descrip	tion		
1	CWGx'y	' outpu	t has the	CWG data input waveform with polarity control from POLy bit
0	CWGx'y	' outpu	t is assig	ned to value of OVRy bit

#### Notes:

- 1. The bits in this register apply only when MODE = 'b00x (CWGxCON0, Steering modes).
- 2. This bit is double-buffered when MODE = 'b001.

#### 32.14.6 CWGxAS0

Name: CWGxAS0

**Offset:** 0x3C2,0x3CB,0x3D4

CWG Auto-Shutdown Control Register 0

Bit	7	6	5	4	3	2	1	0
	SHUTDOWN	REN	LSBD[1:0]		LSAC[1:0]			
Access	R/W/HS/HC	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	1	0	1		

# Bit 7 - SHUTDOWN Auto-Shutdown Event Status(1,2)

Value	Description
1	An auto-shutdown state is in effect
0	No auto-shutdown event has occurred

#### Bit 6 - REN Auto-Restart Enable

Value	Description
1	Auto-restart is enabled
0	Auto-restart is disabled

#### Bits 5:4 - LSBD[1:0] CWGxB and CWGxD Auto-Shutdown State Control

Value	Description
11	A logic '1' is placed on CWGxB/D when an auto-shutdown event occurs.
10	A logic '0' is placed on CWGxB/D when an auto-shutdown event occurs.
01	Pin is tri-stated on CWGxB/D when an auto-shutdown event occurs.
00	The Inactive state of the pin, including polarity, is placed on CWGxB/D after the required dead-band
	interval when an auto-shutdown event occurs.

#### Bits 3:2 - LSAC[1:0] CWGxA and CWGxC Auto-Shutdown State Control

Value	Description
11	A logic '1' is placed on CWGxA/C when an auto-shutdown event occurs.
10	A logic '0' is placed on CWGxA/C when an auto-shutdown event occurs.
01	Pin is tri-stated on CWGxA/C when an auto-shutdown event occurs.
00	The Inactive state of the pin, including polarity, is placed on CWGxA/C after the required dead-band
	interval when an auto-shutdown event occurs.

#### Notes:


- 1. This bit may be written while EN = 0, to place the outputs into the shutdown configuration.
- The outputs will remain in Auto-Shutdown state until the next rising edge of the CWG data input after this bit is cleared.

#### 32.14.7 CWGxAS1

Name: CWGxAS1

**Offset:** 0x3C3,0x3CC,0x3D5

CWG Auto-Shutdown Control Register 1



Bits 0, 1, 2, 3, 4, 5, 6, 7 – ASyE CWG Auto-shutdown Source Enable<sup>(1,2)</sup>

ASyE	Auto-Shutdown Source							
ASYL	CWG1	CWG2	CWG3					
AS7E		CLC6_OUT						
AS6E	CLC2_OUT	CLC3_OUT	CLC4_OUT					
AS5E	CMP2_OUT							
AS4E	CMP1_OUT							
AS3E	TMR6_Postscaler_OUT							
AS2E	TMR4_Postscaler_OUT							
AS1E	TMR2_Postscaler_OUT							
AS0E	Pin selected by CWG1PPS	Pin selected by CWG2PPS	Pin selected by CWG3PPS					

#### Notes:

- 1. This bit may be written while EN = 0, to place the outputs into the shutdown configuration.
- The outputs will remain in Auto-Shutdown state until the next rising edge of the CWG data input after this bit is cleared.

# **CWG - Complementary Waveform Generator Mod...**

#### 32.14.8 CWGxDBR

Name: CWGxDBR

**Offset:** 0x3BE,0x3C7,0x3D0

CWG Rising Dead-Band Count Register

Bit	7	6	5	4	3	2	1	0
					DBR	[5:0]		
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			X	X	X	X	X	X

Bits 5:0 - DBR[5:0] CWG Rising Edge-Triggered Dead-Band Count

Reset States: POR/BOR = xxxxxx

All Other Resets = uuuuuu

1	Value	Description
	n	Dead-band is active no less than n, and no more than n+1, CWG clock periods after the rising edge
	0	0 CWG clock periods. Dead-band generation is bypassed

# **CWG - Complementary Waveform Generator Mod...**

#### 32.14.9 CWGxDBF

Name: CWGxDBF

**Offset:** 0x3BF,0x3C8,0x3D1

CWG Falling Dead-Band Count Register

Bit	7	6	5	4	3	2	1	0
					DBF	[5:0]		
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			X	X	X	X	X	X

Bits 5:0 - DBF[5:0] CWG Falling Edge-Triggered Dead-Band Count

Reset States: POR/BOR = xxxxxx

All Other Resets = uuuuuu

Value	Description
n	Dead-band is active no less than n, and no more than n+1, CWG clock periods after the falling edge
0	0 CWG clock periods. Dead-band generation is bypassed

# 32.15 Register Summary - CWG

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x03BB										
0x03BC	CWG1CLK	7:0								CS
0x03BD	CWG1ISM	7:0						ISM[4:0]		
0x03BE	CWG1DBR	7:0				-	DBR	R[5:0]		
0x03BF	CWG1DBF	7:0					DBF	[5:0]		
0x03C0	CWG1CON0	7:0	EN	LD					MODE[2:0]	
0x03C1	CWG1CON1	7:0			IN		POLD	POLC	POLB	POLA
0x03C2	CWG1AS0	7:0	SHUTDOWN	REN	LSBI	D[1:0]	LSA	C[1:0]		
0x03C3	CWG1AS1	7:0	AS7E	AS6E	AS5E	AS4E	AS3E	AS2E	AS1E	AS0E
0x03C4	CWG1STR	7:0	OVRD	OVRC	OVRB	OVRA	STRD	STRC	STRB	STRA
0x03C5	CWG2CLK	7:0								CS
0x03C6	CWG2ISM	7:0					!	ISM[4:0]		
0x03C7	CWG2DBR	7:0					DBR	R[5:0]		
0x03C8	CWG2DBF	7:0					DBF	[5:0]		
0x03C9	CWG2CON0	7:0	EN	LD					MODE[2:0]	
0x03CA	CWG2CON1	7:0			IN		POLD	POLC	POLB	POLA
0x03CB	CWG2AS0	7:0	SHUTDOWN	REN	LSBI	D[1:0]	LSA	C[1:0]		
0x03CC	CWG2AS1	7:0	AS7E	AS6E	AS5E	AS4E	AS3E	AS2E	AS1E	AS0E
0x03CD	CWG2STR	7:0	OVRD	OVRC	OVRB	OVRA	STRD	STRC	STRB	STRA
0x03CE	CWG3CLK	7:0								CS
0x03CF	CWG3ISM	7:0					!	ISM[4:0]		
0x03D0	CWG3DBR	7:0					DBR	R[5:0]		
0x03D1	CWG3DBF	7:0					DBF	[5:0]		
0x03D2	CWG3CON0	7:0	EN	LD					MODE[2:0]	
0x03D3	CWG3CON1	7:0			IN		POLD	POLC	POLB	POLA
0x03D4	CWG3AS0	7:0	SHUTDOWN	REN	LSBI	D[1:0]	LSA	C[1:0]		
0x03D5	CWG3AS1	7:0	AS7E	AS6E	AS5E	AS4E	AS3E	AS2E	AS1E	AS0E
0x03D6	CWG3STR	7:0	OVRD	OVRC	OVRB	OVRA	STRD	STRC	STRB	STRA

# 33. NCO - Numerically Controlled Oscillator Module


The Numerically Controlled Oscillator (NCO) module is a timer that uses overflow from the addition of an increment value to divide the input frequency. The advantage of the addition method over a simple counter driven timer is that the output frequency resolution does not vary with the divider value. The NCO is most useful for applications that require frequency accuracy and fine resolution at a fixed duty cycle.

Features of the NCO include:

- · 20-Bit Increment Function
- · Fixed Duty Cycle (FDC) mode
- · Pulse Frequency (PF) mode
- · Output Pulse Width Control
- · Multiple Clock Input Sources
- · Output Polarity Control
- Interrupt Capability

The following figure is a simplified block diagram of the NCO module.

Figure 33-1. Numerically Controlled Oscillator Module Simplified Block Diagram



**Note 1:** The increment registers are double-buffered to allow for value changes to be made without first disabling the NCO module. The full increment value is loaded into the buffer registers on the second rising edge of the NCOx\_clk signal that occurs immediately after a write to the NCOxINCL register. The buffers are not user-accessible and are shown here for reference.

# 33.1 NCO Operation

The NCO operates by repeatedly adding a fixed value to an accumulator. Additions occur at the input clock rate. The accumulator will overflow with a carry periodically, which is the raw NCO output (NCO\_overflow). This effectively reduces the input clock by the ratio of the addition value to the maximum accumulator value. See the following equation.

#### **Equation 33-1. NCO Overflow Frequency**

$$F_{OVERFLOW} = \frac{NCO\ Clock\ Frequency\ imes\ Increment\ Value}{2^{20}}$$

It should be apparent from the equation that there is a linear relationship between the increment value and the overflow frequency. This linear advantage over divide-by-n timers comes at the cost of output jitter. However, the jitter is always plus or minus one NCO clock period that occurs periodically, depending on the division remainder. For example, when there is no division remainder then there is no jitter, whereas a division remainder of 0.5 will result in a jitter frequency one half of the overflow frequency.

#### 33.1.1 NCO Clock Sources

The NCO can be clocked from a variety of sources including the system clock, internal timers, and other peripherals. The NCO clock source is selected by configuring the CKS bits.

#### 33.1.2 Accumulator

The accumulator is a 20-bit register. Read and write access to the accumulator is available through three registers:

- NCOxACCL
- NCOxACCH
- NCOxACCU

#### 33.1.3 Adder

The NCO adder is a full adder, which operates synchronously from the source clock. The addition of the previous result and the increment value replaces the accumulator value on the rising edge of each input clock.

#### 33.1.4 Increment Registers

The increment value is stored in three registers making up a 20-bit word. In order of LSB to MSB they are:

- NCOxINCL
- NCOxINCH
- NCOxINCU

The increment registers are readable and writable and are double-buffered to allow value changes to be made without first disabling the NCO module.

When the NCO module is enabled, the NCOxINCU and NCOxINCH registers should be written first, then the NCOxINCL register. Writing to the NCOxINCL register initiates the increment buffer registers to be loaded simultaneously on the second rising edge of the NCO\_clk signal.

When the NCO module is disabled, the increment buffers are loaded immediately after a write to the increment registers.




**Important:** The increment buffer registers are not user-accessible.

# 33.2 Fixed Duty Cycle Mode

In Fixed Duty Cycle (FDC) mode, every time the accumulator overflows, the output is toggled. This provides a 50% duty cycle at half the F<sub>OVERFLOW</sub> frequency, provided that the increment value remains constant. For more information, see the figure below.

The FDC mode is selected by clearing the PFM bit.

Figure 33-2. FDC Output Mode Timing Diagram



# 33.3 Pulse Frequency Mode

In Pulse Frequency (PF) mode, the output becomes active on the rising clock edge immediately following the overflow event, and goes inactive 1 to 128 clock periods later, determined by the  $\frac{PWS}{PWS}$  bits. This provides a pulsed output at the  $\frac{PWS}{PWS}$  frequency. For more information, refer to the figure above.



**Important:** When the selected pulse width is greater than the accumulator overflow time frame, then the NCO output does not toggle.

The level of the active and inactive states is determined by the POL bit.

PF mode is selected by setting the PFM bit.

# 33.4 Output Polarity Control

The last stage in the NCO module is the output polarity. The POL bit selects the output polarity. The active level of the Pulse Frequency mode is high true when the POL bit is cleared.

Changing the polarity while the interrupts are enabled will cause an interrupt for the resulting output transition.

The NCO output signal (NCOx out) is available by internal routing to several other peripherals.

# 33.5 Interrupts

When the accumulator overflows, the NCO Interrupt Flag bit, NCOxIF, in the associated PIR register is set. To enable interrupt service on this event, the following bits must be set:

- EN bit
- · NCOxIE bit in the associated PIE register
- Peripheral and Global Interrupt Enable bits

The interrupt must be cleared by software by clearing the NCOxIF bit in the Interrupt Service Routine.

#### 33.6 Effects of a Reset

All of the NCO registers are cleared to zero as the result of any Reset.

# 33.7 Operation in Sleep

The NCO module operates independently from the system clock and will continue to run during Sleep, provided that the clock source selected remains active.

The HFINTOSC remains active during Sleep when the NCO module is enabled and the HFINTOSC is selected as the clock source, regardless of the system clock source selected.

In other words, if the HFINTOSC is simultaneously selected as the system clock and the NCO clock source, when the NCO is enabled, the CPU will go Idle during Sleep, but the NCO will continue to operate and the HFINTOSC will remain active.

With a clock running, it will have a direct effect on the Sleep mode current.

# 33.8 Register Definitions: NCO

Long bit name prefixes for the NCO peripherals are shown in the table below. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 33-1. NCO Long Bit Name Prefixes

Peripheral	Bit Name Prefix
NCO1	NCO1
NCO2	NCO2
NCO3	NCO3

# 33.8.1 NCOxCON

Name: NCOxCON

**Offset:** 0x446,0x44E,0x456

NCO Control Register

Bit	7	6	5	4	3	2	1	0
	EN		OUT	POL				PFM
Access	R/W		R	R/W				R/W
Reset	0		0	0				0

#### Bit 7 - EN NCO Enable

Value	Description
1	NCO module is enabled
0	NCO module is disabled

#### Bit 5 – OUT NCO Output

Displays the current logic level of the NCO module output.

#### Bit 4 - POL NCO Polarity

Value	Description
1	NCO output signal is inverted
0	NCO output signal is not inverted


# Bit 0 - PFM NCO Pulse Frequency Mode

Value	Description
1	NCO operates in Pulse Frequency mode. Output frequency is F <sub>OVERFLOW</sub> .
0	NCO operates in Fixed Duty Cycle mode. Output frequency is F <sub>OVERFLOW</sub> divided by 2.

#### 33.8.2 NCOxCLK

Name: NCOxCLK

**Offset:** 0x447,0x44F,0x457 NCO Input Clock Control Register



Bits 7:5 - PWS[2:0] NCO Output Pulse Width Select(1)

Value	Description
111	NCO output is active for 128 input clock periods
110	NCO output is active for 64 input clock periods
101	NCO output is active for 32 input clock periods
100	NCO output is active for 16 input clock periods
011	NCO output is active for 8 input clock periods
010	NCO output is active for 4 input clock periods
001	NCO output is active for 2 input clock periods
000	NCO output is active for 1 input clock periods

# Bits 4:0 - CKS[4:0] NCO Clock Source Select

CKS		Clock Source		A stive in clean
Value	NCO1	NCO2	NC03	Active in sleep
11111-11011		Reserved		-
11010		CLC8_OUT		No
11001		CLC7_out		No
11000		CLC6_out		No
10111		CLC5_OUT		No
10110		CLC4_OUT		No
10101		CLC3_out		No
10100		CLC2_OUT		No
10011		CLC1_OUT		No
10010	NCO3_OUT	NCO3_OUT	Reserved	No
10001	NCO2_OUT	Reserved	NCO2_OUT	No
10000	Reserved	NCO1_OUT	NCO1_OUT	No
01111-01101		Reserved		-
01100		TU16B_OUT		No
01011		TU16A_OUT		No
01010		TMR6_OUT		No
01001		TMR4_OUT		No
01000		TMR2_OUT		No
00111		CLKREF		No
00110		EXTOSC		Yes
00101		SOSC		Yes
00100		MFINTOSC		Yes
00011		MFINTOSC		Yes
00010		LFINTOSC		Yes
00001		HFINTOSC		Yes

# PIC18F26/46/56Q84

# NCO - Numerically Controlled Oscillator Mo...

continued									
CKS		Clock Source		Active in sleep					
Value	NCO1	NCO2	NC03	Active in Sieep					
00000		Fosc		No					

#### Note:

1. PWS applies only when operating in Pulse Frequency mode.

#### 33.8.3 NCOxACC

Name: NCOxACC

**Offset:** 0x440,0x448,0x450

NCO Accumulator Register

Bit	23	22	21	20	19	18	17	16		
	ACC[19:16]									
Access					R/W	R/W	R/W	R/W		
Reset					0	0	0	0		
Bit	15	14	13	12	11	10	9	8		
				ACC	[15:8]					
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		
Bit	7	6	5	4	3	2	1	0		
	ACC[7:0]									
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		

Bits 19:0 - ACC[19:0] Accumulated sum of NCO additions

#### Notes:

- 1. The individual bytes in this multi-byte register can be accessed with the following register names:
  - NCOxACCU: Accesses the upper byte ACC[23:16]
  - NCOxACCH: Accesses the high byte ACC[15:8]
  - NCOxACCL: Accesses the low byte ACC[7:0]
- 2. The accumulator spans registers NCOxACCU:NCOxACCH:NCOxACCL. The 24 bits are reserved but not all are used. This register updates in real-time, asynchronously to the CPU; there is no provision to ensure atomic access to this 24-bit space using an 8-bit bus. Writing to this register while the module is operating will produce undefined results.

#### 33.8.4 NCOxINC

Name: NCOxINC

**Offset:** 0x443,0x44B,0x453

NCO Increment Register

23	22	21	20	19	18	17	16	
					INC[1	9:16]		
				R/W	R/W	R/W	R/W	
				0	0	0	0	
15	14	13	12	11	10	9	8	
			INC[	15:8]				
R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
0	0	0	0	0	0	0	0	
7	6	5	4	3	2	1	0	
INC[7:0]								
R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
0	0	0	0	0	0	0	1	
	15 R/W 0 7	15 14  R/W R/W 0 0  7 6  R/W R/W	15 14 13  R/W R/W R/W 0 0 0 7 6 5  R/W R/W R/W	15 14 13 12  R/W R/W R/W R/W R/W 0 0 0 0 0 7 6 5 4  INC  R/W R/W R/W R/W	R/W 0  15 14 13 12 11  INC[15:8]  R/W R/W R/W R/W R/W R/W 0 0 0 0 0 0  7 6 5 4 3  INC[7:0]  R/W R/W R/W R/W R/W	R/W   R/W   0   0   0	R/W   R/W   R/W   R/W   R/W   0   0   0   0   0   0   0   0   0	

Bits 19:0 - INC[19:0] Value by which the NCOxACC is increased by each NCO clock

#### Notes:

- 1. The individual bytes in this multi-byte register can be accessed with the following register names:
  - NCOxINCU: Accesses the upper byte INC[19:16]
  - NCOxINCH: Accesses the high byte INC[15:8]
  - NCOxINCL: Accesses the low byte INC[7:0]
- 2. The logical increment spans NCOxINCU:NCOxINCH:NCOxINCL.
- 3. NCOxINC is double-buffered as INCBUF:
  - INCBUF is updated on the next falling edge of NCOxCLK after writing to NCOxINCL
  - NCOxINCU and NCOxINCH should be written prior to writing NCOxINCL

# 33.9 Register Summary - NCO

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x043F		7:0				100	217.01			
0x0440	NOOAAOO	15:8		ACC[7:0]						
UXU44U	NCO1ACC			ACC[15:8] ACC[19:16]						
		23:16				1110		ACC	[19:16]	
		7:0					[7:0]			
0x0443	NCO1INC	15:8				INC	[15:8]			
		23:16						INC[	19:16]	
0x0446	NCO1CON	7:0	EN		OUT	POL				PFM
0x0447	NCO1CLK	7:0		PWS[2:0]				CKS[4:0]		
	NCO2ACC	7:0	ACC[7:0]							
0x0448		15:8	ACC[15:8]							
		23:16						ACC	[19:16]	
		7:0 INC[7:0]								
0x044B	NCO2INC	NCO2INC 15:8				INC	15:8]			
		23:16						INC[	19:16]	
0x044E	NCO2CON	7:0	EN		OUT	POL				PFM
0x044F	NCO2CLK	7:0		PWS[2:0]				CKS[4:0]		
		7:0				ACC	[7:0]			
0x0450	NCO3ACC	15:8				ACC	[15:8]			
		23:16						ACCI	19:16]	
		7:0	INC[7:0]							
0x0453	NCO3INC	15:8					15:8]			
		23:16					,	INCI	19:16]	
0x0456	NCO3CON	7:0	EN		OUT	POL				PFM
0x0457	NCO3CLK	7:0		PWS[2:0]		. 02		CKS[4:0]		
070-101	HOODOLK	7.0		1 110[2.0]				01(0[4.0]		

# 34. DSM - Data Signal Modulator Module

The Data Signal Modulator (DSM) is a peripheral that allows the user to mix a data stream, also known as a modulator signal, with a carrier signal to produce a modulated output. Both the carrier and the modulator signals are supplied to the DSM module either internally, from the output of a peripheral, or externally through an input pin. The modulated output signal is generated by performing a logical "AND" operation of both the carrier and modulator signals, and then provided to the DSM out pin.

The carrier signal is comprised of two distinct and separate signals. A Carrier High (CARH) signal and a Carrier Low (CARL) signal. During the time in which the modulator (MOD) signal is in a Logic High state, the DSM mixes the CARH signal with the modulator signal. When the modulator signal is in a Logic Low state, the DSM mixes the CARL signal with the modulator signal.

Using this method, the DSM can generate the following types of key modulation schemes:

- Frequency Shift Keying (FSK)
- Phase-Shift Keying (PSK)
- ON-OFF Keying (OOK)

Additionally, the following features are provided within the DSM module:

- · Carrier Synchronization
- · Carrier Source Polarity Select
- · Programmable Modulator Data
- Modulated Output Polarity Select
- Peripheral Module Disable, which provides the ability to place the DSM module in the lowest power consumption mode

The figure below shows a simplified block diagram of the data signal modulator peripheral.




Figure 34-1. Simplified Block Diagram of the Data Signal Modulator

# 34.1 DSM Operation

The DSM module is enabled by setting the EN bit. Clearing the EN bit disables the output of the module, but retains the carrier and source signal selections. The module will resume operation when the EN bit is set again. The output of the DSM module can be rerouted to several pins using the PPS output source selection register. When the EN bit is cleared the output pin is held low.

# 34.1.1 Modulator Signal Sources

The modulator signal can be supplied from several different sources, and is selected by configuring the MS bits.

# 34.1.2 Carrier Signal Sources

The carrier high signal and carrier low signal can be supplied from several different sources, and is selected by the CH bits and CL bits, respectively.

# 34.2 Carrier Synchronization

During the time when the DSM switches between carrier high and carrier low signal sources, the carrier data in the modulated output signal can become truncated. To prevent this, the carrier signal can be synchronized to the modulator signal. When synchronization is enabled, the carrier pulse that is being mixed at the time of the transition is allowed to transition low before the DSM switches over to the next carrier source.

Synchronization is enabled separately for the carrier high and carrier low signal sources. Synchronization for the carrier high signal is enabled by setting the CHSYNC bit. Synchronization for the carrier low signal is enabled by setting the CLSYNC bit. The figures below show the timing diagrams of using various synchronization methods.

Figure 34-2. On-Off Keying (OOK) Synchronization




Figure 34-3. No Synchronization (CHSYNC = 0, CLSYNC = 0)




Figure 34-4. Carrier High Synchronization (CHSYNC = 1, CLSYNC = 0)




Figure 34-5. Carrier Low Synchronization (CHSYNC = 0, CLSYNC = 1)





Figure 34-6. Full Synchronization (CHSYNC = 1, CLSYNC = 1)



# 34.3 Carrier Source Polarity Select

The signal provided from any selected input source for the carrier high and carrier low signals can be inverted. Inverting the signal for the carrier high and low source is enabled by setting the CHPOL bit and the CLPOL bit, respectively.

# 34.4 Programmable Modulator Data

The BIT control bit can used to generate the modulation signal. This gives the user the ability to provide software driven modulation.

# 34.5 Modulated Output Polarity

The modulated output signal provided on the DSM\_out pin can also be inverted. Inverting the modulated output signal is enabled by setting the OPOL bit.

# 34.6 Operation in Sleep Mode

The DSM can operate during Sleep, if the carrier and modulator input sources are also operable during Sleep. Refer to "Power-Saving Modes" chapter for more details.

#### 34.7 Effects of a Reset

Upon any device Reset, the DSM module is disabled. The user's firmware is responsible for initializing the module before enabling the output. All the registers are reset to their default values.

# 34.8 Peripheral Module Disable

The DSM module can be completely disabled using the PMD module to achieve maximum power saving. When the DSMMD bit of the PMD registers is set, the DSM module is completely disabled. This puts the module in its lowest power consumption state. When enabled again all the registers of the DSM module default to POR status.

# 34.9 Register Definitions: Modulation Control

Long bit name prefixes for the modulation control peripherals are shown in the table below. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 34-1. Modulation Control Long Bit Name Prefixes

Peripheral	Bit Name Prefix
DSM1	MD1

#### 34.9.1 MDxCON0

Name: MDxCON0 Offset: 0x6A

Modulation Control Register 0

Bit	7	6	5	4	3	2	1	0
	EN		OUT	OPOL				BIT
Access	R/W		R/W	R/W				R/W
Reset	0		0	0				0

#### Bit 7 - EN Modulator Module Enable

Value	Description	
1	DSM is enabled and mixing input signals	
0	DSM is disabled and has no output	

Bit 5 – OUT Modulator Output<sup>(1)</sup>
Displays the current DSM\_out value

#### Bit 4 - OPOL Modulator Output Polarity Select

Va	lue	Description
1		DSM output signal is inverted; idle high output
0		DSM output signal is not inverted; idle low output

# Bit 0 - BIT Modulation Source Signal<sup>(2)</sup>

Allows direct software control of the modulation signal


#### Notes:

- 1. The modulated output frequency can be greater and asynchronous from the clock that updates this register bit. The bit value may not be valid for higher speed modulator or carrier signals.
- 2. MDBIT must be selected as the modulation source in the MDxSRC register for this operation.

#### 34.9.2 MDxCON1

Name: MDxCON1 Offset: 0x6B

Modulation Control Register 1



#### Bit 5 - CHPOL Modulator High Carrier Polarity Select

Value	Description
1	Selected high carrier signal is inverted
0	Selected high carrier signal is not inverted

#### Bit 4 - CHSYNC Modulator High Carrier Synchronization Enable

Value	Description	
1	Modulator waits for a falling edge on the high time carrier signal before allowing a switch to the low	
	time carrier	
0	Modulator output is not synchronized to the high time carrier signal <sup>(1)</sup>	

#### Bit 1 - CLPOL Modulator Low Carrier Polarity Select

	The modulator Low Currier Folding Coloct		
Value	Description		
1	Selected low carrier signal is inverted		
0	Selected low carrier signal is not inverted		

#### Bit 0 - CLSYNC Modulator Low Carrier Synchronization Enable

Value	Description	
1	Modulator waits for a falling edge on the low time carrier signal before allowing a switch to the high	
	time carrier	
0	Modulator output is not synchronized to the low time carrier signal <sup>(1)</sup>	


#### Note:

1. Narrowed carrier pulse widths or spurs may occur in the signal stream if the carrier is not synchronized.

# 34.9.3 MDxCARH

Name: MDxCARH Offset: 0x6E

Modulation High Carrier Control Register




Bits 4:0 - CH[4:0] Modulator Carrier High Selection

СН	Connection
11111-10111	Reserved
10110	CLC8_OUT
10101	CLC7_OUT
10100	CLC6_OUT
10011	CLC5_OUT
10010	CLC4_OUT
10001	CLC3_OUT
10000	CLC2_OUT
01111	CLC1_OUT
01110	NCO3_OUT
01101	NCO2_OUT
01100	NCO1_OUT
01011	PWM4S1P1_OUT
01010	PWM3S1P1_OUT
01001	PWM2S1P1_OUT
01000	PWM1S1P1_OUT
00111	CCP3_OUT
00110	CCP2_OUT
00101	CCP1_OUT
00100	CLKREF_OUT
00011	EXTOSC
00010	HFINTOSC
00001	F <sub>OSC</sub> (System Clock)
00000	Pin selected by MDCARHPPS

# 34.9.4 MDxCARL

Name: MDxCARL Offset: 0x6D

Modulation Low Carrier Control Register




Bits 4:0 - CL[4:0] Modulator Carrier Low Input Selection

CL	Connection
11111-10111	Reserved
10110	CLC8_OUT
10101	CLC7_OUT
10100	CLC6_OUT
10011	CLC5_OUT
10010	CLC4_OUT
10001	CLC3_OUT
10000	CLC2_OUT
01111	CLC1_OUT
01110	NCO3_OUT
01101	NCO2_OUT
01100	NCO1_OUT
01011	PWM4S1P2_OUT
01010	PWM3S1P2_OUT
01001	PWM2S1P2_OUT
01000	PWM1S1P2_OUT
00111	CCP3_OUT
00110	CCP2_OUT
00101	CCP1_OUT
00100	CLKREF_OUT
00011	EXTOSC
00010	HFINTOSC
00001	F <sub>OSC</sub> (System Clock)
00000	Pin selected by MDCARLPPS

# 34.9.5 MDxSRC

Name: MDxSRC Offset: 0x6C

Modulation Source Control Register



Bits 5:0 - MS[5:0] Modulator Source Selection

мѕ	Connection
111111-100000	Reserved
100000	SPI2_SDO
011111	SPI1_SDO
011110	UART5_TX
011101	UART4_TX
011100	UART3_TX
011011	UART2_TX
011010	UART1_TX
011001	CLC8_OUT
011000	CLC7_OUT
010111	CLC6_OUT
010110	CLC5_OUT
010101	CLC4_OUT
010100	CLC3_OUT
010011	CLC2_OUT
010010	CLC1_OUT
010001	CMP2_OUT
010000	CMP1_OUT
001111	NCO3_OUT
001110	NCO2_OUT
001101	NCO1_OUT
001100	PWM4S1P2_OUT
001011	PWM4S1P1_OUT
001010	PWM3S1P2_OUT
001001	PWM3S1P1_OUT
001000	PWM2S1P2_OUT
000111	PWM2S1P1_OUT
000110	PWM1S1P2_OUT
000101	PWM1S1P1_OUT
000100	CCP3_OUT
000011	CCP2_OUT
000010	CCP1_OUT
000001	MDBIT
000000	Pin selected by MDSRCPPS

# 34.10 Register Summary - DSM

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x69										
0x6A	MD1CON0	7:0	EN		OUT	OPOL				BIT
0x6B	MD1CON1	7:0			CHPOL	CHSYNC			CLPOL	CLSYNC
0x6C	MD1SRC	7:0				MS[5:0]				
0x6D	MD1CARL	7:0				CL[4:0]				
0x6E	MD1CARH	7:0				CH[4:0]				

# 35. UART - Universal Asynchronous Receiver Transmitter with Protocol Support

The Universal Asynchronous Receiver Transmitter (UART) module is a serial I/O communications peripheral. It contains all the clock generators, shift registers and data buffers necessary to perform an input or output serial data transfer, independent of device program execution. The UART, also known as a Serial Communications Interface (SCI), can be configured as a full-duplex asynchronous system or one of several automated protocols. The Full-Duplex mode is useful for communications with peripheral systems, such as wireless modems and USB to serial interface modules.

Supported protocols include:

- LIN Master and Slave
- DMX Controller and Receiver
- · DALI Control Gear and Control Device

The UART module includes the following capabilities:

- · Half and Full-duplex asynchronous transmit and receive
- · Two-byte input buffer
- · One-byte output buffer
- Programmable 7-bit or 8-bit byte width
- · 9th bit address detection
- · 9th bit even or odd parity
- · Input buffer overrun error detection
- · Receive framing error detection
- Hardware and software flow control
- Automatic checksum calculation and verification
- Programmable 1, 1.5, and 2 Stop bits
- · Programmable data polarity
- · Manchester encoder/decoder
- · Operation in Sleep
- · Automatic detection and calibration of the baud rate
- Wake-up on Break reception
- · Automatic and user timed Break period generation
- RX and TX inactivity time-outs (with Timer2)

The operation of the UART module is controlled through nineteen 8-bit registers:

- Three control registers (UxCON0-UxCON2)
- Error enable and status (UxERRIE, UxERRIR, UxUIR)
- UART buffer status and control (UxFIFO)
- Three 9-bit protocol parameters (UxP1-UxP3)
- 16-bit Baud Rate Generator (UxBRG)
- Transmit buffer write (UxTXB)
- Receive buffer read (UxRXB)
- Receive checksum (UxRXCHK)
- Transmit checksum (UxTXCHK)

The UART transmit output (TX\_out) is available to the TX pin and internally to various peripherals.

Block diagrams of the UART transmitter and receiver are shown in the following figures.

Figure 35-1. UART Transmitter Block Diagram





Figure 35-2. UART Receiver Block Diagram



# 35.1 UART I/O Pin Configuration

The RX input pin is selected with the UxRPPS register. The TX output pin is selected with each pin's RxyPPS register. When the TRIS control for the pin corresponding to the TX output is cleared, the UART will control the logic level on the TX pin. Changing the TXPOL bit in UxCON2 will immediately change the TX pin logic level, regardless of the value of EN or TXEN.

# 35.2 UART Asynchronous Modes

The UART has five asynchronous modes:

- 7-bit
- 8-bit
- · 8-bit with even parity in the 9th bit
- · 8-bit with odd parity in the 9th bit
- · 8-bit with address indicator in the 9th bit

The UART transmits and receives data using the standard Non-Return-to-Zero (NRZ) format. NRZ is implemented with two levels: a VOH Mark state, which represents a '1' data bit, and a VOL Space state, which represents a '0' data bit. NRZ implies that consecutively transmitted data bits of the same value stay at the output level of that bit without returning to a neutral level between each bit transmission. An NRZ transmission port idles in the Mark state. Each character transmission consists of one Start bit followed by seven or eight data bits, one optional parity or address bit, and is always terminated by one or more Stop bits. The Start bit is always a space and the Stop bits are always marks. The most common data format is eight bits with no parity. Each transmitted bit persists for a period of 1/ (Baud Rate). An on-chip dedicated 16-bit Baud Rate Generator is used to derive standard baud rate frequencies from the system oscillator. See UART Baud Rate Generator for more information.

In all asynchronous modes, the UART transmits and receives the LSb first. The UART's transmitter and receiver are functionally independent, but share the same data format and baud rate. Parity is supported by the hardware with even and odd parity modes.

## 35.2.1 UART Asynchronous Transmitter

The UART transmitter block diagram is shown in Figure 35-1. The heart of the transmitter is the serial Transmit Shift Register (TSR), which is not directly accessible by software. The TSR obtains its data from the transmit buffer, which is the UxTXB register.

#### 35.2.1.1 Enabling the Transmitter

The UART transmitter is enabled for asynchronous operations by configuring the following control bits:

- TXEN = 1
- MODE = 0000 through 0011
- UxBRG = desired baud rate
- BRGS = desired baud rate multiplier
- RxyPPS = code for desired output pin
- ON = 1

All other UART control bits are assumed to be in their default state.

Setting the TXEN bit enables the transmitter circuitry of the UART. The MODE bits select the desired mode. Setting the ON bit enables the UART. When TXEN is set and the transmitter is not Idle, the TX pin is automatically configured as an output. When the transmitter is Idle, the TX pin drive is relinquished to the port TRIS control. If the TX pin is shared with an analog peripheral, the analog I/O function should be disabled by clearing the corresponding ANSEL bit.



**Important:** The UxTXIF Transmitter Interrupt flag is set when the TXEN Enable bit is set and the UxTXB register can accept data.

#### 35.2.1.2 Transmitting Data

A transmission is initiated by writing a character to the UxTXB register. If this is the first character, or the previous character has been completely transmitted from the TSR, the data in the UxTXB is immediately transferred to the TSR register. If the TSR still contains all or part of a previous character, the new character data is held in the UxTXB until the previous character transmission is complete. The pending character in the UxTXB is then transferred to the

# **UART - Universal Asynchronous Receiver Tra...**

TSR at the beginning of the previous character Stop bit transmission. The transmission of the Start bit, data bits and Stop bit sequence commences immediately following the completion of all of the previous character's Stop bits.

#### 35.2.1.3 Transmit Data Polarity

The polarity of the transmit data is controlled with the TXPOL bit. The default state of this bit is '0' which selects high true transmit idle and data bits. Setting the TXPOL bit to '1' will invert the transmit data, resulting in low true idle and data bits. The TXPOL bit controls transmit data polarity in all modes.

#### 35.2.1.4 Transmit Interrupt Flag

The UxTXIF Interrupt Flag bit in the PIR register is set whenever the UART transmitter is enabled and no character is being held for transmission in the UxTXB register. In other words, the UxTXIF bit is clear only when the TSR is busy with a character and a new character has been queued for transmission in the UxTXB register.

The UxTXIF interrupt is enabled by setting the UxTXIE Interrupt Enable bit in the PIE register. However, the UxTXIF Flag bit will be set whenever the UxTXB register is empty, regardless of the state of the UxTXIE Enable bit. The UxTXIF bit is read-only and cannot be set or cleared by software.

To use interrupts when transmitting data, set the UxTXIE bit only when there is more data to send. Clear the UxTXIE Interrupt Enable bit upon writing the UxTXB register with the last character of the transmission.

#### 35.2.1.5 TSR Status

The TXMTIF bit indicates the status of the TSR. This is a read-only bit. The TXMTIF bit is set when the TSR is empty and idle. The TXMTIF bit is cleared when a character is transferred to the TSR from the UxTXB. The TXMTIF bit remains clear until all bits, including the Stop bits, have been shifted out of the TSR and a byte is not waiting in the UxTXB register.

The TXMTIF will generate a summary UxEIF interrupt when the TXMTIE bit is set.



**Important:** The TSR is not mapped in data memory, so it is not available to the user.

#### 35.2.1.6 Transmitter 7-bit Mode

The 7-Bit mode is selected when the MODE bits are set to `0001'. In 7-bit mode, only the seven Least Significant bits of the data written to UxTXB are transmitted. The Most Significant bit is ignored.

#### 35.2.1.7 Transmitter Parity Modes

When odd or even parity mode is selected, all data is sent as nine bits. The first eight bits are data and the 9th bit is parity. Even and odd parity is selected when the MODE bits are set to `0011' and `0010', respectively. Parity is automatically determined by the module and inserted in the serial data stream.

#### 35.2.1.8 Asynchronous Transmission Setup

Use the following steps as a guide for configuring the UART for asynchronous transmissions.

- 1. Initialize the UxBRG register pair and the BRGS bit to achieve the desired baud rate.
- 2. Set the MODE bits to the desired asynchronous mode.
- 3. Set the TXPOL bit if inverted TX output is desired.
- 4. Enable the asynchronous serial port by setting the ON bit.
- 5. Enable the transmitter by setting the TXEN Control bit. This will cause the UxTXIF Interrupt flag to be set.
- 6. If the device has PPS, configure the desired I/O pin RxyPPS register with the code for the TX output.
- 7. If interrupts are desired, set the UxTXIE Interrupt Enable bit in the respective PIE register. An interrupt will occur immediately provided that global interrupts are also enabled.
- 8. Write one byte of data into the UxTXB register. This will start the transmission.
- Subsequent bytes may be written when the UxTXIF bit is '1'.

Figure 35-3. UART Asynchronous Transmission





Figure 35-4. UART Asynchronous Transmission (back-to-back)



#### 35.2.2 UART Asynchronous Receiver

The Asynchronous mode is typically used in RS-232 systems. The receiver block diagram is shown in Figure 35-2. The data is received on the RX pin and drives the data recovery block. The data recovery block is actually a high-speed shifter operating at 4 or 16 times the baud rate, whereas the serial Receive Shift Register (RSR) operates at the bit rate. When all bits of the character have been shifted in, they are immediately transferred to a two-character First-In First-Out (FIFO) memory. The FIFO buffering allows reception of two complete characters and the start of a third character before software must begin servicing the UART receiver. The FIFO registers and RSR are not directly accessible by software. Access to the received data is made via the UxRXB register.

## 35.2.2.1 Enabling the Receiver

The UART receiver is enabled for asynchronous operation by configuring the following control bits:

- RXEN = 1
- MODE = 0000 through 0011
- UxBRG = desired baud rate
- BRGS = desired baud rate multiplier
- RXPPS = code for desired input pin
- Input pin ANSEL bit = 0
- ON = 1

All other UART control bits are assumed to be in their default state.

# **UART - Universal Asynchronous Receiver Tra...**

Setting the RXEN bit enables the receiver circuitry of the UART. Setting the MODE bits configures the UART for the desired Asynchronous mode. Setting the ON bit enables the UART. The TRIS bit corresponding to the selected RX I/O pin must be set to configure the pin as an input.



**Important:** If the RX function is on an analog pin, the corresponding ANSEL bit must be cleared for the receiver to function.

#### 35.2.2.2 Receiving Data

Data is recovered from the bit stream by timing to the center of the bits and sampling the input level. In High-Speed mode, there are four BRG clocks per bit and only one sample is taken per bit. In Normal-Speed mode, there are 16 BRG clocks per bit and three samples are taken per bit.

The receiver data recovery circuit initiates character reception on the falling edge of the Start bit. The Start bit is always a '0'. The Start bit is qualified in the middle of the bit. In Normal-Speed mode only, the Start bit is also qualified at the leading edge of the bit. The following paragraphs describe the majority-detect sampling of the Normal-Speed mode without inverted polarity.

The falling edge starts the Baud Rate Generator (BRG) clock. The input is sampled at the first and second BRG clocks.

If both samples are high, then the falling edge is deemed a glitch and the UART returns to the Start bit detection state without generating an error.

If either sample is low, the data recovery circuit continues counting BRG clocks and takes samples at clock counts: 7, 8, and 9. When less than two samples are low, the Start bit is deemed invalid and the data recovery circuit aborts character reception, without generating an error, and resumes looking for the falling edge of the Start bit.

When two or more samples are low, the Start bit is deemed valid and the data recovery continues. After a valid Start bit is detected, the BRG clock counter continues and resets at count 16. This is the beginning of the first data bit.

The data recovery circuit counts the BRG clocks from the beginning of the bit and takes samples at clocks 7, 8, and 9. The bit value is determined from the majority of the samples. The resulting '0' or '1' is shifted into the RSR. The BRG clock counter continues and resets at count 16. This sequence repeats until all data bits have been sampled and shifted into the RSR.

After all data bits have been shifted in, the first Stop bit is sampled. Stop bits are always a '1'. If the bit sampling determines that a '0' is in the Stop bit position, the framing error is set for this character. Otherwise, the framing error is cleared for this character. See Receive Framing Error for more information on framing errors.

#### 35.2.2.3 Receive Data Polarity

The polarity of the receive data is controlled with the RXPOL bit. The default state of this bit is '0' which selects high true receive idle and data bits. Setting the RXPOL bit to '1' will invert the receive data, resulting in low true idle and data bits. The RXPOL bit controls receive data polarity in all modes.

#### 35.2.2.4 Receive Interrupts

Immediately after all data bits and the Stop bit have been received, the character in the RSR is transferred to the UART receive FIFO. The UxRXIF Interrupt flag in the respective PIR register is set at this time, provided it is not being suppressed.

The UxRXIF is suppressed by any of the following:

- · FERIF when FERIE is set
- PERIF when PERIE is set

When the UART uses DMA for reception, suppressing the UxRXIF suspends the DMA transfer of data until software processes the error and reads UxRXB to advance the FIFO beyond the error.

The UxRXIF interrupts are enabled by setting all of the following bits:

- UxRXIE, Interrupt Enable bit in the PIE register
- · Global Interrupt Enable bits

# **UART - Universal Asynchronous Receiver Tra...**

The UxRXIF Interrupt Flag bit will be set when it is not suppressed and there is an unread character in the FIFO, regardless of the state of interrupt enable bits. Reading the UxRXB register will transfer the top character out of the FIFO and reduce the FIFO contents by one. The UxRXIF Interrupt Flag bit is read-only and therefore cannot be set or cleared by software.

#### 35.2.2.5 Receive Framing Error

Each character in the receive FIFO buffer has a corresponding framing error flag bit. A framing error indicates that the Stop bit was not seen at the expected time. For example, a Break condition will be received as a 0x00 byte with the framing error bit set.

The framing error flag is accessed via the FERIF bit. The FERIF bit represents the frame status of the top unread character of the receive FIFO. Therefore, the FERIF bit must be read before reading UxRXB.

The FERIF bit is read-only and only applies to the top unread character of the receive FIFO. A framing error (FERIF = 1) does not preclude reception of additional characters. It is neither necessary nor possible to clear the FERIF bit directly. Reading the next character from the FIFO buffer will advance the FIFO to the next character and the next corresponding framing error, if any.

The FERIF bit is cleared when the character at the top of the FIFO does not have a framing error or when all bytes in the receive FIFO have been read. Clearing the ON bit resets the receive FIFO, thereby also clearing the FERIF bit.

A framing error will generate a summary UxEIF interrupt when the FERIE bit is set. The summary error is reset when the FERIF bit of the top of the FIFO is '0' or when all FIFO characters have been retrieved.



**Important:** When FERIE is set, UxRXIF interrupts are suppressed by FERIF = 1.

#### 35.2.2.6 Receiver Parity Modes

Even or odd parity is automatically detected when the MODE bits are set to `0011' or `0010', respectively. The parity modes receive eight data bits and one parity bit for a total of nine bits for each character. The PERIF bit represents the parity error of the top unread character of the receive FIFO rather than the parity bit itself. The parity error must be read before the UxRXB register is read because reading the UxRXB register will advance the FIFO pointer to the next byte with its associated PERIF flag.

A parity error will generate a summary UxEIF interrupt when the PERIE bit is set. The summary error is reset when the PERIF bit of the top of the FIFO is '0' or when all FIFO characters have been retrieved.



**Important:** When PERIE is set, the UxRXIF interrupts are suppressed by PERIF = 1.

#### 35.2.2.7 Receive FIFO Overflow

When more characters are received than the receive FIFO can hold, the RXFOIF bit is set. The character causing the Overflow condition is discarded. The RUNOVF bit determines how the receive circuit responds to characters while the Overflow condition persists. When RUNOVF is set, the receive shifter stays synchronized to the incoming data stream by responding to Start, data, and Stop bits. However, all received bytes not already in the FIFO are discarded. When RUNOVF is cleared, the receive shifter ceases operation and Start, data, and Stop bits are ignored. The Receive Overflow condition is cleared by reading the UxRXB register and clearing the RXFOIF bit. If the UxRXB register is not read, thereby opening a space in the FIFO, the next character received will be discarded and cause another Overflow condition.

A receive overflow error will generate a summary UxEIF interrupt when the RXFOIE bit is set.


#### 35.2.2.8 Asynchronous Reception Setup

Use the following steps as a guide for configuring the UART for asynchronous reception:

1. Initialize the UxBRG register pair and the BRGS bit to achieve the desired baud rate.

- 2. Configure the RXPPS register for the desired RX pin.
- 3. Clear the ANSEL bit for the RX pin (if applicable).
- 4. Set the MODE bits to the desired Asynchronous mode.
- 5. Set the RXPOL bit if the data stream is inverted.
- 6. Enable the serial port by setting the ON bit.
- 7. If interrupts are desired, set the UxRXIE bit in the PIEx register and enable global interrupts.
- 8. Enable reception by setting the RXEN bit.
- Read the UxERRIR register to get the error flags.
- 10. The UxRXIF Interrupt Flag bit will be set when a character is transferred from the RSR to the receive buffer. An interrupt will be generated if the UxRXIE interrupt enable bit is also set.
- 11. Read the UxRXB register to get the received byte.
- 12. If an overrun occurred, clear the RXFOIF bit.

Figure 35-5. UART Asynchronous Reception



Note: This timing diagram shows three bytes appearing on the RX input. The UxRXB is not read before the third word is received, causing the RXFOIF (FIFO overrun) bit to be set. STPMD = 0, STP=00.

#### 35.2.3 Asynchronous Address Mode

A special Address Detection mode is available for use when multiple receivers share the same transmission line, as seen in RS-485 systems.

When Asynchronous Address mode is enabled, all data is transmitted and received as 9-bit characters. The 9th bit determines whether the character is address or data. When the 9th bit is set, the eight Least Significant bits are the address. When the 9th bit is clear, the Least Significant bits are data. In either case, the 9th bit is stored in PERIF when the byte is written to the receive FIFO. When PERIE is also set, the RXIF will be suppressed, thereby suspending DMA transfers allowing software to process the received address.

An address character will enable all receivers that match the address and disable all other receivers. Once a receiver is enabled, all non-address characters will be received until an address character that does not match is received.

#### 35,2,3,1 Address Mode Transmit

The UART transmitter is enabled for asynchronous address operation by configuring the following control bits:

- TXEN = 1
- MODE = 0100
- UxBRG = desired baud rate

- BRGS = desired baud rate multiplier
- RxyPPS = code for desired output pin
- ON = 1

Addresses are sent by writing to the UxP1L register. This transmits the written byte with the 9th bit set, which indicates that the byte is an address.

Data is sent by writing to the UxTXB register. This transmits the written byte with the 9th bit cleared, which indicates that the byte is data.

To send data to a particular device on the transmission bus, first transmit the address of the intended device. All subsequent data will be accepted only by that device until an address of another device is transmitted.

Writes to UxP1L take precedence over writes to UxTXB. When both the UxP1L and UxTXB registers are written while the TSR is busy, the next byte to be transmitted will be from UxP1L.

To ensure all data intended for one device are sent before the address is changed, wait until the TXMTIF bit is high before writing UxP1L with the new address.

#### 35.2.3.2 Address Mode Receive

The UART receiver is enabled for asynchronous address operation by configuring the following control bits:

- RXEN = 1
- MODE = 0100
- UxBRG = desired baud rate
- BRGS = desired baud rate multiplier
- RXPPS = code for desired input pin
- Input pin ANSEL bit = 0
- UxP2L = receiver address
- UxP3L = address mask
- **ON** = 1

In Address mode, no data will be transferred to the input FIFO until a valid address is received. This is the default state. Any of the following conditions will cause the UART to revert to the default state:

- ON = 0
- RXEN = 0
- · Received address does not match

When a character with the 9th bit set is received, the Least Significant eight bits of that character will be qualified by the values in the UxP2L and UxP3L registers.

The byte is XORed with UxP2L then ANDed with UxP3L. A match occurs when the result is 0h, in which case, the unaltered received character is stored in the receive FIFO, thereby setting the UxRXIF Interrupt bit. The 9th bit is stored in the corresponding PERIF bit, identifying this byte as an address.

An address match also enables the receiver for all data such that all subsequent characters without the 9th bit set will be stored in the receive FIFO.

When the 9th bit is set and a match does not occur, the character is not stored in the receive FIFO and all subsequent data is ignored.

The UxP3L register mask allows a range of addresses to be accepted. Software can then determine the sub-address of the range by processing the received address character.

# 35.3 DMX Mode (Full-featured UARTs only)

DMX is a protocol used in stage and show equipment. This includes lighting, fog machines, motors, etc. The protocol consists of a Controller that sends out commands, and receiver such as theater lights that receive these commands. The DMX protocol is usually unidirectional, but can be a bidirectional protocol in either Half or Full-Duplex modes. An example of a Half-Duplex mode is the RDM (Remote Device Management) protocol that sits on DMX512A. The

Controller transmits commands and the receiver receives them. There are no error conditions or re-transmit mechanisms.

DMX, or DMX512A as it is known, consists of a "Universe" of 512 channels. This means that one Controller can output up to 512 bytes on a single DMX link. Each piece of equipment on the line is programmed to listen to a consecutive sequence of one or more of these bytes.

For example, a fog machine connected to one of the universes may be programmed to receive one byte, starting at byte number 10, and a lighting unit may be programmed to receive four bytes starting at byte number 22.


#### 35.3.1 DMX Controller

The DMX Controller mode is configured with the following settings:

- MODE = 1010
- TXEN = 1
- RXEN = 0
- TXPOL = 0
- UxP1 = One less than the number of bytes to transmit (excluding the Start code)
- UxBRG = Value to achieve 250K baud rate
- STP = 10 for two Stop bits
- RxyPPS = TX pin output code
- ON = 1

Each DMX transmission begins with a Break followed by a byte called the "Start Code". The width of the Break is fixed at 25 bit times. The Break is followed by a "Mark After Break" (MAB) Idle period. After this Idle period, the 1st through 'n'th byte is transmitted, where 'n-1' is the value in UxP1. See the following figure.

Figure 35-6. DMX Transmit Sequence



Note 1: The MAB period is fixed at 3 bit times

Software sends the Start Code and the 'n' data bytes by writing the UxTXB register with each byte to be sent in the desired order. A UxTXIF value of '1' indicates when the UxTXB is ready to accept the next byte.

The internal byte counter is not accessible to software. Software needs to keep track of the number of bytes written to UxTXB to ensure that no more and no less than 'n' bytes are sent because the DMX state machine will automatically insert a Break and reset its internal counter after 'n' bytes are written. One way to ensure synchronization between hardware and software is to toggle TXEN after the last byte of the universe is completely free of the transmit shift register, as indicated by the TXMTIF bit.

#### 35.3.2 DMX Receiver

The DMX Receiver mode is configured with the following settings:

MODE = 1010

- TXEN = 0
- RXEN = 1
- RXPOL = 0
- UxP2 = number of first byte to receive
- UxP3 = number of last byte to receive
- UxBRG = Value to achieve 250K baud rate
- STP = 10 for two Stop bits
- ON = 1
- UxRXPPS = code for desired input pin
- Input pin ANSEL bit = 0

When configured as a DMX Receiver, the UART listens for a Break character that is at least 23 bit periods wide. If the Break is shorter than 23 bit times, the Break is ignored and the DMX state machine remains in Idle mode. Upon receiving the Break, the DMX counters will be reset to align with the incoming data stream. Immediately after the Break, the UART will see the "Mark after Break" (MAB). This space is ignored by the UART. The Start Code follows the MAB and will always be stored in the receive FIFO.

After the Start Code, the 1st through 512th byte will be received, but not all of them are stored in the receive FIFO. The UART ignores all received bytes until the ones of interest are received. This is done using the UxP2 and UxP3 registers. The UxP2 register holds the value of the byte number to start the receive process. The byte counter starts at '0' for the first byte after the Start Code. For example, to receive four bytes starting at the 10th byte after the Start Code, write 009h (9 decimal) to UxP2H:L and 00Ch (12 decimal) to UxP3H:L. The receive FIFO depth is limited, therefore the bytes must be retrieved by reading UxRXB as they come in to avoid a receive FIFO Overrun condition.

Typically, two Stop bits are inserted between bytes. If either Stop bit is detected as a '0' then the framing error for that byte will be set.

Since the DMX sequence always starts with a Break, the software can verify that it is in sync with the sequence by monitoring the RXBKIF flag to ensure that the next byte received after the RXBKIF is processed as the Start Code and subsequent bytes are processed as the expected data.

## 35.4 LIN Modes (Full-featured UARTs only)

LIN is a protocol used primarily in automotive applications. The LIN network consists of two kinds of software processes: a Master process and a Slave process. Each network has only one Master process and one or more Slave processes.

From a physical layer point of view, the UART on one processor may be driven by both a Master and a Slave process, as long as only one Master process exists on the network.

A LIN transaction consists of a Master process followed by a Slave process. The Slave process may involve more than one slave where one is transmitting and the other(s) are receiving. The transaction begins by the following Master process transmission sequence:

- 1. Break
- 2. Delimiter bit
- 3. Sync Field
- 4. PID byte

The PID determines which Slave processes are expected to respond to the master. When the PID byte is complete, the TX output remains in the Idle state. One or more of the Slave processes may respond to the Master process. If no one responds within the inter-byte period, the master is free to start another transmission. The inter-byte period is timed by software using a means other than the UART.

The Slave process follows the Master process. When the slave software recognizes the PID then that Slave process responds by either transmitting the required response or by receiving the transmitted data. Only Slave processes send data. Therefore, Slave processes receiving data are receiving that of another Slave process.

When a slave sends data, the slave UART automatically calculates the checksum for the transmitted bytes as they are sent and appends the inverted checksum byte to the slave response.

When a slave receives data, the checksum is accumulated on each byte as it is received using the same algorithm as the sending process. The last byte, which is the inverted checksum value calculated by the sending process, is added to the locally calculated checksum by the UART. The check passes when the result is all '1's, otherwise the check fails and the CERIF bit is set.

Two methods for computing the checksum are available: legacy and enhanced. The legacy checksum includes only the data bytes. The enhanced checksum includes the PID and the data. The COEN control bit determines the checksum method. Setting C0EN to '1' selects the enhanced method. Software must select the appropriate method before the Start bit of the checksum byte is received.

#### 35.4.1 LIN Master/Slave Mode

The LIN Master mode includes capabilities to generate Slave processes. The Master process stops at the PID transmission. Any data that is transmitted in Master/Slave mode is done as a Slave process. LIN Master/Slave mode is configured by the following settings:

- **MODE** = 1100
- **TXEN** = 1
- RXEN = 1
- UxBRG = Value to achieve desired baud rate
- TXPOL = 0 (for high Idle state)
- STP = desired Stop bits selection
- COEN = desired Checksum mode
- RxyPPS = TX pin selection code
- TX pin TRIS control = 0
- ON = 1



Important: The TXEN bit must be set before the Master process is received and remain set while in LIN mode whether or not the Slave process is a transmitter.

The Master process is started by writing the PID to the UxP1L register when UxP2 is '0' and the UART is Idle. The UxTXIF will not be set in this case. Only the six Least Significant bits of UxP1L are used in the PID transmission.

The two Most Significant bits of the transmitted PID are PID parity bits. PID[6] is the exclusive-or of PID bits 0, 1, 2, and 4. PID[7] is the inverse of the exclusive-or of PID bits 1, 3, 4, and 5.

The UART hardware calculates and inserts these bits in the serial stream.

Writing UxP1L automatically clears the UxTXCHK and UxRXCHK registers and generates the Break, the delimiter bit, the Sync character (55h), and the PID transmission portion of the transaction. The data portion of the transaction that follows, if there is one, is a Slave process. See LIN Slave Mode for more details of that process. The master receives its own PID if RXEN is set. Software performs the Slave process corresponding to the PID that was sent and received. Attempting to write UxP1L before an active Master process is complete will not succeed. Instead, the TXWRE bit will be set.

#### 35.4.2 **LIN Slave Mode**

The LIN Slave mode is configured by the following settings:

- MODE = 1011
- TXEN = 1
- RXEN = 1
- UxP2 = Number of data bytes to transmit
- UxP3 = Number of data bytes to receive
- UxBRG = Value to achieve default baud rate
- TXPOL = 0 (for high Idle state)
- STP = desired Stop bits selection

- C0EN = desired checksum mode
- RxyPPS = TX pin selection code
- TX pin TRIS control = 0
- ON = 1

The Slave process starts upon detecting a Break on the RX pin. The Break clears the UxTXCHK, UxRXCHK, UxP2, and UxP3 registers. At the end of the Break, the auto-baud circuity is activated and the baud rate is automatically set using the Sync character following the Break. The character following the Sync character is received as the PID code and is saved in the receive FIFO. The UART computes the two PID parity bits from the six Least Significant bits of the PID. If either parity bit does not match the corresponding bit of the received PID code, the PERIF flag is set and saved at the same FIFO location as the PID code. The UxRXIF bit is set indicating that the PID is available.

Software retrieves the PID by reading the UxRXB register and determines the Slave process to execute from that. The checksum method, number of data bytes, and whether to send or receive data, is defined by software according to the PID code.

#### 35.4.2.1 LIN Slave Receiver

When the Slave process is a Receiver, the software performs the following tasks:

- The UxP3 register is written with a value equal to the number of data bytes to receive.
- The C0EN bit is set or cleared to select the appropriate checksum. This must be completed before the Start bit
  of the checksum byte is received.
- · Each byte of the process response is read from UxRXB when UxRXIF is set.

The UART updates the checksum on each received byte. When the last data byte is received, the computed checksum total is stored in the UxRXCHK register. The next received byte is saved in the receive FIFO and added with the value in UxRXCHK. The result of this addition is not accessible. However, if the result is not all '1's, the CERIF bit is set. The CERIF flag persists until cleared by software. Software needs to read UxRXB to remove the checksum byte from the FIFO, but the byte can be discarded if not needed for any other purpose.

After the checksum is received, the UART ignores all activity on the RX pin until a Break starts the next transaction.

#### 35.4.2.2 LIN Slave Transmitter

When the Slave process is a transmitter, software performs the following tasks in the order shown:

- The UxP2 register is written with a value equal to the number of bytes to transmit. This will enable the UxTXIF flag which is disabled when UxP2 is '0'
- · The C0EN bit is set or cleared to select the appropriate checksum
- · Each byte of the process response is written to UxTXB when UxTXIF is set

The UART accumulates the checksum as each byte is written to UxTXB. After the last byte is written, the UART stores the calculated checksum in the UxTXCHK register and transmits the inverted result as the last byte in the response.

The UxTXIF flag is disabled when the number of bytes specified by the value in the UxP2 register have been written. Any writes to UxTXB that exceed the UxP2 count will be ignored and set the TXWRE flag.

## 35.5 DALI Mode (Full-featured UARTs only)


DALI is a protocol used for intelligent lighting control for building automation. The protocol consists of Control Devices and Control Gear. A Control Device is an application controller that sends out commands to the light fixtures. The light fixture itself is termed as a Control Gear. The communication is done using Manchester encoding, which is performed by the UART hardware.

Manchester encoding consists of the clock and data in a single bit stream (refer to Figure 35-9). A high-to-low or a low-to-high transition always occurs in the middle of the bit period and may or may not occur at the bit period boundaries. When the consecutive bits in the bit stream are of the same value (i.e., consecutive '1's or consecutive '0's) a transition occurs at the bit boundary. However, when the bit value changes, there is no transition at the bit boundary. According to the standard, a half-bit time is typically 416.7 µs long. A double half-bit time or a single bit is typically 833.3 µs.

The protocol is inherently half-duplex. Communication over the bus occurs in the form of forward and backward frames. Wait times between the frames are defined in the standard to prevent collision between the frames.

A Control Device transmission is termed as the forward frame. In the DALI 2.0 standard, a forward frame can be two or three bytes in length. The two-byte forward frame is used for communication between Control Device and Control Gear whereas the three-byte forward frame is used for communication between Control Devices on the bus. The first byte in the forward frame is the control byte and is followed by either one or two data bytes. The transaction begins when the Control Device starts a transmission. Unlike other protocols, each byte in the frame is transmitted MSb first. Typical frame timing is shown below.


Figure 35-7. DALI Frame Timing



During the communication between two Control Devices, three bytes are required to be transmitted. In this case, the software must write the third byte to UxTXB as soon as UxTXIF goes true and before the output shifter becomes empty. This ensures that the three bytes of the forward frame are transmitted back-to-back without any interruption.


All Control Gear on the bus receive the forward frame. If the forward frame requires a reply to be sent, one of the Control Gear may respond with a single byte, called the backward frame. The 2.0 standard requires the Control Gear to begin transmission of the backward frame between 5.5 ms to 10.5 ms (~14 to 22 half-bit times) after reception of the forward frame. Once the backward frame is received by the Control Device, it is required to wait a minimum of 2.4 ms (~6 half-bit times). After this wait time, the Control Device is free to transmit another forward frame. Refer to the figure below.

Figure 35-8. DALI Forward/Backward Frame Timing



A Start bit is used to indicate the start of the forward and backward frames. When ABDEN = 0, the receiver bit rate is determined by the BRG register. When ABDEN = 1, the first bit synchronizes the receiver with the transmitter and sets the receiver bit rate. The low period of the Start bit is measured and is used as the timing reference for all data bits in the forward and backward frames. The ABDOVF bit is set if the Start bit low period causes the measurement counter to overflow. All the bits following the Start bit are data bits. The bit stream terminates when no transition is detected in the middle of a bit period. Refer to the figure below.

Figure 35-9. Manchester Timing



The forward and backward frames are terminated by two Idle bit periods or Stop bits. Normally, these start in the first bit period of a byte. If both Stop bits are valid, the byte reception is terminated.

If either of the Stop bits is invalid, the frame is tagged as invalid by saving it as a null byte and setting the framing error in the receive FIFO.

A framing error also occurs when no transition is detected on the bus in the middle of a bit period when the byte reception is not complete. In such a scenario, the byte will be saved with the FERIF bit set.

#### 35.5.1 Control Device

The Control Device mode is configured with the following settings:

- MODE = 'b1000
- TXEN = 1
- RXEN = 1
- UxP1 = Forward frames are held for transmission with this number of half-bit periods after the completion of a forward or backward frame.
- UxP2 = Forward/backward frame threshold delimiter. Any reception that starts this number of half-bit periods
  after the completion of a forward or backward frame is detected as forward frame and sets the PERIF flag of the
  corresponding received byte.
- UxBRG = Value to achieve 1200 baud rate
- TXPOL = appropriate polarity for interface circuit
- STP = 'b10 for two Stop bits
- RxyPPS = TX pin selection code
- TX pin TRIS control = 0
- ON = 1

A forward frame is initiated by writing the control byte to the UxTXB register. After sending the control byte, each data byte must be written to the UxTXB register as soon as UxTXIF goes true. It is necessary to perform every write after UxTXIF goes true, to ensure that the transmit buffer is ready to accept the byte. Each write must also occur before the TXMTIF bit goes true, to ensure that the bit stream of the forward frame is generated without interruption.

When TXMTIF goes true, indicating the transmit shift register has completed sending the last byte in the frame, the TX output is held in Idle state for the number of half-bit periods selected by the STP bits.

After the last Stop bit, the TX output is held in the Idle state for an additional wait time determined by the half-bit period count in the UxP1 register. For example, a 2450  $\mu$ s delay (~6 half-bit times) requires a value of 6 in UxP1L.

Any writes to the UxTXB register that occur after TXMTIF goes true, but before the UxP1 wait time expires, are held and then transmitted immediately following the wait time. If a backward frame is received during the wait time, any bytes that may have been written to UxTXB will be transmitted after completion of the backward frame reception plus the UxP1 wait time.

The wait timer is reset by the backward frame and starts over immediately following the reception of the Stop bits of the backward frame. Data pending in the transmit shift register will be sent when the wait time elapses.

To replace or delete any pending forward frame data, the TXBE bit needs to be set to flush the shift register and transmit buffer. A new control byte can then be written to the UxTXB register. The control byte will be held in the buffer and sent at the beginning of the next forward frame following the UxP1 wait time.

In Control Device mode, PERIF is set when a forward frame is received. This helps the software to determine whether the received byte is part of a forward frame from a Control Device (either from the Control Device under consideration or from another Control Device on the bus) or a backward frame from a Control Gear.

#### 35.5.2 Control Gear

The Control Gear mode is configured with the following settings:

- MODE = 'b1001
- TXEN = 1
- RXEN = 1
- UxP1 = Back Frames are held for transmission this number of half-bit periods after the completion of a Forward Frame.
- UxP2 = Forward/Back Frame threshold delimiter. Idle periods longer than this number of half-bit periods are detected as Forward Frames.
- UxBRG = Value to achieve 1200 baud rate
- TXPOL = Appropriate polarity for interface circuit
- RXPOL = Same as TXPOL
- STP = 'b10 for two Stop bits
- RxyPPS = TX pin output code
- TX pin TRIS control = 0
- RXPPS = RX pin selection code
- RX pin TRIS control = 1
- Input pin ANSEL bit = 0
- **ON** = 1

The UART starts listening for a forward frame when the Control Gear mode is entered. Only the frames that follow an Idle period longer than UxP2 half-bit periods are detected as forward frames. Backward frames from other Control Gear are ignored. Only forward frames will be stored in UxRXB. This is necessary because a backward frame can be sent only as a response to a forward frame.

The forward frame is received one byte at a time in the receive FIFO and retrieved by reading the UxRXB register. The end of the forward frame starts a timer to delay the backward frame response by a wait time equal to the number of half-bit periods stored in UxP1.

The data received in the forward frame is processed by the application software. If the application decides to send a backward frame in response to the forward frame, the value of the backward frame is written to UxTXB. This value is held for transmission in the transmit shift register until the wait time expires, being transmitted afterwards.

If the backward frame data is written to UxTXB after the wait time has expired, it is held in the UxTXB register until the end of the wait time following the next forward frame. The TXMTIF bit is false when the backward frame data is held in the transmit shift register. Receiving a UxRXIF interrupt before the TXMTIF goes true indicates that the backward frame write was too late and another forward frame was received before sending the backward frame. The pending backward frame is flushed by setting the TXBE bit to prevent it from being sent after the next forward frame.

## 35.6 General Purpose Manchester (Full-featured UARTs only)

General purpose Manchester is a subset of the DALI mode. When the UxP1L register is cleared, there is no minimum wait time between frames. This allows full and half-duplex operation because writes to the UxTXB register are not held waiting for a receive operation to complete.

General purpose Manchester operation maintains all other aspects of DALI mode as shown in Figure 35-9 such as:

- · Single-pulse Start bit
- · Most Significant bit first

· No stop periods between back-to-back bytes

The general purpose Manchester mode is configured with the following settings:

- MODE = 'b1000
- TXEN = 1
- RXEN = 1
- UxP1 = 0h
- UxBRG = Desired baud rate
- TXPOL and RXPOL = Desired Idle state
- STP = Desired number of stop periods
- RxyPPS = TX pin selection code
- TX pin TRIS control = 0
- RXPPS = RX pin selection code
- RX pin TRIS control = 1
- Input pin ANSEL bit = 0
- ON = 1

The Manchester bit stream timing is shown in Figure 35-9.

## 35.7 Polarity

Receive and transmit polarity is user selectable and affects all modes of operation.

The idle level is programmable with the TXPOL and RXPOL polarity control bits. Both control bits default to '0', which selects a high idle level for transmit and receive. The low level Idle state is selected by setting the control bit to '1'. TXPOL controls the TX idle level. RXPOL controls the RX idle level.

## 35.8 Stop Bits

The number of Stop bits is user selectable with the STP bits. The STP bits affect all modes of operation.

Stop bits selections are shown in the table below:

Table 35-1.

Transmitter Stop bits	Receiver verification
1	Verify Stop bit
1.5	Verify first Stop bit
2	Verify both Stop bits
2	Verify only first Stop bit

In all modes, except DALI, the transmitter is Idle for the number of Stop bit periods between each consecutively transmitted word. In DALI, the Stop bits are generated after the last bit in the transmitted data stream.

The input is checked for the idle level in the middle of the first Stop bit, when receive verify on first is selected, as well as in the middle of the second Stop bit, when verify on both is selected. If any Stop bit verification indicates a non-idle level, the framing error FERIF bit is set for the received word.

#### 35.8.1 Delayed Receive Interrupt

When operating in Half-Duplex mode, where the microcontroller needs to reverse the transceiver direction after a reception, it may be more convenient to hold off the UxRXIF interrupt until the end of the Stop bits to avoid line contention. The user selects when the UxRXIF interrupt occurs with the STPMD bit. When STPMD is '1', the UxRXIF interrupt occurs at the end of the last Stop bit. When STPMD is '0', the UxRXIF interrupt occurs when the received

byte is stored in the receive FIFO. When STP = 10, the store operation is performed in the middle of the second Stop bit, otherwise, it is performed in the middle of the first Stop bit.

The FERIF and PERIF interrupts are not delayed with STPMD. When STPMD is set, the preferred indicator for reversing transceiver direction is the UxRXIF interrupt because it is delayed whereas the others are not.

## 35.9 Operation After FIFO Overflow

The Receive Shift Register (RSR) can be configured to stop or continue running during a receive FIFO Overflow condition. Stopped operation is the Legacy mode.

When the RSR continues to run during an Overflow condition, the first word received after clearing the overflow will always be valid.

When the RSR is stopped during an Overflow condition, the synchronization with the Start bits is lost. Therefore, the first word received after the overflow is cleared may start in the middle of a word.

Operation during overflow is selected with the RUNOVF bit. When the RUNOVF bit is set, the receiver maintains synchronization with the Start bits throughout the Overflow condition.

#### 35.10 Receive and Transmit Buffers

The UART uses small buffer areas to transmit and receive data. These are sometimes referred to as FIFOs.

The receiver has a Receive Shift Register (RSR) and two or more buffer registers. The buffer at the top of the FIFO (earliest byte to enter the FIFO) is by retrieved by reading the UxRXB register.

The transmitter has one or more Transmit Shift Register (TSR) and one buffer register. Writes to UxTXB go to the transmit buffer then immediately to the TSR, if it is empty. When the TSR is not empty, writes to UxTXB are held then transferred to the TSR when it becomes available.

#### 35.10.1 FIFO Status

The UxFIFO register contains several Status bits for determining the state of the receive and transmit buffers.

The RXBE bit indicates that the receive FIFO is empty. This bit is essentially the inverse of UxRXIF. The RXBF bit indicates that the receive FIFO is full.

The TXBE bit indicates that the transmit buffer is empty (same as UxTXIF) and the TXBF bit indicates that the buffer is full. A third transmitter Status bit, TXWRE (transmit write error), is set whenever a UxTXB write is performed when the TXBF bit is set. This indicates that the write was unsuccessful.

### 35.10.2 FIFO Reset

All modes support resetting the receive and transmit buffers.

The receive buffer is flushed and all unread data discarded when the RXBE bit is written to '1'. Instead of using a BSF instruction to set RXBE, the MOVWF instruction with the TXBE bit cleared should be used to avoid inadvertently clearing a byte pending in the TSR when UxTXB is empty.

Data written to UxTXB when TXEN is low will be held in the Transmit Shift Register (TSR) then sent when TXEN is set. The transmit buffer and inactive TSR are flushed by setting the TXBE bit. Setting TXBE while a character is actively transmitting from the TSR will complete the transmission without being flushed.

Clearing the ON bit will discard all received data and transmit data pending in the TSR and UxTXB.

### 35.11 Flow Control

This section does not apply to the LIN, DALI, or DMX modes.

Flow control is the means by which a sending UART data stream can be suspended by a receiving UART. Flow control prevents input buffers from overflowing without software intervention. The UART supports both hardware and XON/XOFF methods of flow control.

The flow control method is selected with the FLO bits. Flow control is disabled when both bits are cleared.


#### 35.11.1 Hardware Flow Control

The hardware flow control is selected by setting the FLO bits to '10'.

The hardware flow control consists of three lines. The RS-232 signal names for two of these are RTS, and CTS. Both are low true. The third line is called TXDE for transmit drive enable which may be used to control an RS-485 transceiver. This output is high when the TX output is actively sending a character and low at all other times. The UART is configured as DTE (computer) equipment which means RTS is an output and CTS is an input.

The RTS and CTS signals work as a pair to control the transmission flow. A DTE-to-DTE configuration connects the RTS output of the receiving UART to the CTS input of the sending UART. Refer to the following figure.

Figure 35-10. Hardware Flow Control Connections




The UART receiving data asserts the  $\overline{\text{RTS}}$  output low when the input FIFO is empty. When a character is received, the  $\overline{\text{RTS}}$  output goes high until the UxRXB is read to free up both FIFO locations.

When the CTS input goes high after a byte has started to transmit, the transmission will complete normally. The receiver accommodates this by accepting the character in the second FIFO location even when the CTS input is high.

### 35.11.2 RS-485 Transceiver Control

The hardware flow control can be used to control the direction of an RS-485 transceiver as shown in the following figure. The  $\overline{\text{CTS}}$  input will be configured to be always enabled by setting the UxCTSPPS selection to an unimplemented PORT pin, such as RD0. When the signal and control lines are configured as shown in the figure below, the UART will not receive its own transmissions. To verify that there are no collisions on the RS-485 lines, the transceiver RE control can be disconnected from TXDE and tied low, thereby enabling loopback reception of all transmissions. See Collision Detection for more information.

#### Figure 35-11. RS-485 Configuration



Note 1: Configure UxCTSPPS to an unimplemented input such as RD0. (e.g. UxCTSPPS = 0x18)

#### 35.11.3 XON/XOFF Flow Control

XON/XOFF flow control is selected by setting the FLO bits to '01'.

XON/XOFF is a data-based flow control method. The signals to suspend and resume transmission are special characters sent by the receiver to the transmitter. The advantage is that additional hardware lines are not needed.

XON/XOFF flow control requires full-duplex operation because the transmitter must be able to receive the signal to suspend transmitting while the transmission is in progress. Although XON and XOFF are not defined in the ASCII code, the generally accepted values are 13h for XOFF and 11h for XON. The UART uses those codes.

The transmitter defaults to XON, or transmitter enabled. This state is also indicated by the read-only XON bit.

When an XOFF character is received, the transmitter stops transmitting after completing the character actively being transmitted. The transmitter remains disabled until an XON character is received.

XON will be forced on when software toggles the TXEN bit.

When the RUNOVF bit is set, the XON and XOFF characters continue to be received and processed without the need to clear the input FIFO by reading UxRXB. However, if the RUNOVF bit is clear then UxRXB must be read to avoid a receive overflow which will suspend flow control when the receive buffer overflows.

## 35.12 Checksum (Full-featured UARTs only)

This section does not apply to the LIN mode, which handles checksums automatically.

The transmit and receive checksum adders are enabled when the COEN bit is set. When enabled, the adders accumulate every byte that is transmitted or received. The accumulated sum includes the carry of the addition. Software is responsible for clearing the checksum registers before a transaction and performing the check at the end of the transaction.

The following examples illustrate how the checksum registers could be used in the Asynchronous modes.

#### 35.12.1 Transmit Checksum Method

- 1. Clear the UxTXCHK register.
- 2. Set the C0EN bit.
- Send all bytes of the transaction output.
- Invert UxTXCHK and send the result as the last byte of the transaction.

#### 35.12.2 Receive Checksum Method

- 1. Clear the UxRXCHK register.
- 2. Set the C0EN bit.
- 3. Receive all bytes in the transaction including the checksum byte.
- Set MSb of UxRXCHK if 7-bit mode is selected.
- Add '1' to UxRXCHK.
- 6. If the result is '0', the checksum passes, otherwise it fails.

The CERIF Checksum Interrupt flag is not active in any mode other than LIN.

## 35.13 Collision Detection (Full-featured UARTs only)

External forces that interfere with the transmit line are detected in all modes of operation with collision detection. Collision detection is always active when RXEN and TXEN are both set. When the receive input is connected to the transmit output through either the same I/O pin or external circuitry, a character will be received for every character transmitted. The collision detection circuit provides a warning when the word received does not match the word transmitted.

The TXCIF flag is used to signal collisions. This signal is only useful when the TX output is looped back to the RX input and everything that is transmitted is expected to be received. If more than one transmitter is active at the same time, it can be assumed that the TX word will not match the RX word. The TXCIF detects this mismatch and flags an interrupt. The TXCIF bit will also be set in DALI mode transmissions when the received bit is missing the expected mid-bit transition.

Collision detection is always active, regardless of whether or not the RX input is connected to the TX output. It is up to the user to disable the TXCIE bit when collision interrupts are not required. The software overhead of unloading the receive buffer of transmitted data is avoided by setting the RUNOVF bit and ignoring the receive interrupt and letting the receive buffer overflow. When the transmission is complete, prepare for receiving data by flushing the receive buffer (see FIFO Reset) and clearing the RXFOIF overflow flag.

## 35.14 RX/TX Activity Time-out

The UART works in conjunction with the HLT timers to monitor activity on the RX and TX lines. Use this feature to determine when there has been no activity on the receive or transmit lines for a user-specified period of time.

To use this feature, set the HLT to the desired time-out period by a combination of the HLT clock source, timer prescale value, and timer period registers. Configure the HLT to reset on the UART TX or RX line and start the HLT at the same time the UART is started. UART activity will keep resetting the HLT to prevent a full HLT period from elapsing. When there has been no activity on the selected TX or RX line for longer than the HLT period, then an HLT interrupt will occur signaling the time-out event.

For example, the following register settings will configure HLT2 for a 5 ms time-out of no activity on U1RX:

- T2PR = 0x9C (156 prescale periods)
- T2CLKCON = 0x05 (500 kHz internal oscillator)
- T2HLT = 0x04 (free running, reset on rising edge)
- T2RST = 0x15 (reset on U1RX)
- T2CON = 0xC0 (Timer2 on with 1:16 prescale)

## 35.15 Clock Accuracy With Asynchronous Operation

The factory calibrates the internal oscillator block output (INTOSC). However, the INTOSC frequency may drift as  $V_{DD}$  or temperature changes, and this directly affects the asynchronous baud rate. Two methods may be used to adjust the baud rate clock, but both require a reference clock source of some kind.

The first (preferred) method uses the OSCTUNE register to adjust the INTOSC output. Adjusting the value of the OSCTUNE register allows for fine resolution changes to the system clock source. See "**HFINTOSC Frequency Tuning**" for more information.

The other method adjusts the value of the Baud Rate Generator. This can be done automatically with the Auto-Baud Detect feature (see Auto-Baud Detect). There may not be fine enough resolution when adjusting the Baud Rate Generator to compensate for a gradual change of the peripheral clock frequency.

#### 35.16 UART Baud Rate Generator

The Baud Rate Generator (BRG) is a 16-bit timer that is dedicated to the support of the UART operation. The UxBRG register pair determines the period of the free running baud rate timer. The multiplier of the baud rate period is determined by the BRGS bit.

The high baud rate range (BRGS = 1) is intended to extend the baud rate range up to a faster rate when the desired baud rate is not possible otherwise and to improve the baud rate resolution at high baud rates. Using the normal baud rate range (BRGS = 0) is recommended when the desired baud rate is achievable with either range.



**Important:** BRGS = 1 is not supported in the DALI mode.

Writing a new value to UxBRG causes the BRG timer to be reset (or cleared). This ensures that the BRG does not wait for a timer overflow before outputting the new baud rate.

If the system clock is changed during an active receive operation, a receive error or data loss may result. To avoid this problem, check the status of the RXIDL bit to make sure that the receive operation is Idle before changing the system clock. The following table contains formulas for determining the baud rate.

Table 35-2. Baud Rate Formulas

BRGS	BRG/UART Mode	Baud Rate Formula	
1	High Rate	Fosc/[4(UxBRG+1)]	
0	Normal Rate	Fosc/[16(UxBRG+1)]	

The following example provides a sample calculation for determining the baud rate and baud rate error.

#### **Example 35-1. Baud Rate Error Calculation**

For a device with Fosc of 16 MHz, desired baud rate of 9600, asynchronous mode, and BRGS = 0.

$$DesiredBaudrate = \frac{F_{OSC}}{16 \times (UxBRG + 1)}$$

Solving for UxBRG:

$$UxBRG = \frac{F_{OSC}}{16 \times DesiredBaudrate} - 1$$

$$UxBRG = \frac{16000000}{16 \times 9600} - 1$$

$$UxBRG = 103.17 \simeq 103$$

$$CalculatedBaudrate = \frac{16000000}{16 \times (103 + 1)}$$

CalculatedBaudrate = 9615

$$Error = \frac{CalculatedBaudrate - DesiredBaudrate}{DesiredBaudrate}$$

$$Error = \frac{9615 - 9600}{9600}$$

$$Error \simeq 0.16\%$$


#### 35.16.1 Auto-Baud Detect

The UART module supports automatic detection and calibration of the baud rate in the 8-bit asynchronous and LIN modes. However, setting ABDEN to start auto-baud detection is neither necessary, nor possible in LIN mode because that mode supports auto-baud detection automatically at the beginning of every data packet. Enabling auto-baud detect with the ABDEN bit applies to the asynchronous modes only.

When Auto-Baud Detect (ABD) is active, the clock to the BRG is reversed. Rather than the BRG clocking the incoming RX signal, the RX signal is timing the BRG. The Baud Rate Generator is used to time the period of a received 55h (ASCII "U"), which is the Sync character for the LIN bus. The unique feature of this character is that it has five falling edges, including the Start bit edge, and five rising edges, including the Stop bit edge.

In 8-bit Asynchronous mode, setting the ABDEN bit enables the auto-baud calibration sequence. The first falling edge of the RX input after ABDEN is set will start the auto-baud calibration sequence. While the ABD sequence takes place, the UART state machine is held in idle. On the first falling edge of the receive line, the UxBRG begins counting up using the BRG counter clock, as shown in the following figure. The fifth falling edge will occur on the RX pin at the beginning of the bit 7 period. At that time, an accumulated value totaling the proper BRG period is left in the UxBRG register pair, the ABDEN bit is automatically cleared and the ABDIF interrupt flag is set. ABDIF must be cleared by software.

Figure 35-12. Automatic Baud Rate Calibration



RXIDL indicates that the sync input is active. RXIDL will go low on the first falling edge and go high on the fifth rising edge.

The BRG auto-baud clock is determined by the BRGS bit, as shown in the following table.

Table 35-3. BRG Counter Clock Rates

BRGS	BRG Base Clock BRG ABD Clock	
1	Fosc/4	Fosc/32
0	Fosc/16	Fosc/128

During ABD, the internal BRG register is used as a 16-bit counter. However, the UxBRG registers retain the previous BRG value until the auto-baud process is successfully completed. While calibrating the baud rate period, the internal BRG register is clocked at 1/8th the BRG base clock rate. The resulting byte measurement is the average bit time when clocked at full speed and is transferred to the UxBRG registers when complete.



#### Important:

- 1. When both the WUE and ABDEN bits are set, the auto-baud detection will occur on the byte following the Break character (see Auto Wake-on-Break).
- 2. It is up to the user to verify the incoming character baud rate is within the range of the selected BRG clock source. Some combinations of oscillator frequency and UART baud rates are not possible.

#### 35.16.2 Auto-Baud Overflow

During the course of automatic baud detection, the ABDOVF bit will be set if the baud rate counter overflows before the fifth falling edge is detected on the RX pin. The ABDOVF bit indicates that the counter has exceeded the maximum count that can fit in the 16 bits of the UxBRG register pair. After the ABDOVF bit has been set, the state machine continues to search until the fifth falling edge is detected on the RX pin. Upon detecting the fifth falling RX edge, the hardware will set the ABDIF Interrupt flag and clear the ABDEN bit. The UxBRG register values retain their previous value. The ABDIF flag and ABDOVF flag can be cleared by software directly. To generate an interrupt on an Auto-baud Overflow condition, all the following bits must be set:

- ABDOVE bit
- · UxEIE bit in the PIEx register
- Global Interrupt Enable bits

To terminate the auto-baud process before the ABDIF flag is set, clear the ABDEN bit, then clear the ABDOVF bit.


#### 35.16.3 Auto Wake-on-Break

During Sleep mode, all clocks to the UART are suspended. Because of this, the Baud Rate Generator is inactive and a proper character reception cannot be performed. The Auto Wake-on-Break feature allows the controller to wake up due to activity on the RX line.

The Auto Wake-up feature is enabled by setting both the WUE bit and the UxIE bit in the PIEx register. Once set, the normal receive sequence on RX is disabled, and the UART remains in an Idle state, monitoring for a wake-up event independent of the CPU mode. A wake-up event consists of a transition out of the Idle state on the RX line. (This coincides with the start of a Break or a wake-up signal character for the LIN protocol.)


The UART module generates a WUIF interrupt coincident with the wake-up event. The interrupt is generated synchronously to the Q clocks in normal CPU operating modes (Figure 35-13), and asynchronously, if the device is in Sleep mode (Figure 35-14). The interrupt condition is cleared by clearing the WUIF bit.

Figure 35-13. Auto Wake-Up Timing During Normal Operation



Note 1: The UART remains in Idle while the WUE bit is set.

Figure 35-14. Auto Wake-Up Timing During Sleep



Note 1: The UART remains in idle while the WUE bit is set.

To generate an interrupt on a wake-up event, all the following bits must be set:

- · UxIE bit in the PIEx register
- · Global interrupt enables

The WUE bit is automatically cleared by the transition to the Idle state on the RX line at the end of the Break. This signals to the user that the Break event is over. At this point, the UART module is in Idle mode, waiting to receive the next character.

#### 35.16.3.1 Auto Wake-Up Special Considerations

#### **Break Character**

To avoid character errors or character fragments during a wake-up event, all bits in the character causing the Wake event must be zero.

When the wake-up is enabled, the function works independent of the low time on the data stream. If the WUE bit is set and a valid non-zero character is received, the low time from the Start bit to the first rising edge will be interpreted as the wake-up event. The remaining bits of the character will be received as a fragmented character and subsequent characters can result in framing or overrun errors.

Therefore, the initial character of the transmission must be all zeros. This must be eleven or more bit times, 13 bit times recommended for LIN bus, or any number of bit times for standard RS-232 devices.

#### **Oscillator Start-up Time**

The oscillator start-up time must be considered, especially in applications using oscillators with longer start-up intervals (i.e., LP, XT or HS/PLL modes). The Sync Break (or wake-up signal) character must be of sufficient length, and be followed by a sufficient interval, to allow enough time for the selected oscillator to start and provide proper initialization of the UART.

#### The WUE Bit

To ensure that no actual data is lost, check the RXIDL bit to verify that a receive operation is not in process before setting the WUE bit. If a receive operation is not occurring, the WUE bit may then be set just prior to entering the Sleep mode.

## 35.17 Transmitting a Break

The UART module has the capability of sending either a fixed length Break period or a software-timed Break period. The fixed length Break consists of a Start bit, followed by 12 '0' bits and a Stop bit. The software-timed Break is generated by setting and clearing the BRKOVR bit.


To send the fixed length Break, set the SENDB and TXEN bits. The Break sequence is then initiated by a write to UxTXB. The timed Break will occur first, followed by the character written to UxTXB that initiated the Break. The initiating character is typically the Sync character of the LIN specification.

SENDB is disabled in the LIN and DMX modes because those modes generate the Break sequence automatically.

The SENDB bit is automatically reset by hardware after the Break Stop bit is complete.

The TXMTIF bit indicates when the transmit operation is Active or Idle, just as it does during normal transmission. The following figure illustrates the Break sequence.

Figure 35-15. Send-Break Sequence



## 35.18 Receiving a Break

The UART has counters to detect when the RX input remains in the Space state for an extended period of time. When this happens, the RXBKIF bit is set.

A Break is detected when the RX input remains in the Space state for 11 bit periods for asynchronous and LIN modes, and 23 bit periods for DMX mode.

The user can select to receive the Break interrupt as soon as the Break is detected or at the end of the Break, when the RX input returns to the Idle state. When the RXBIMD bit is '1', then RXBKIF is set immediately upon Break detection. When RXBIMD is '0', then RXBKIF is set when the RX input returns to the Idle state.

## 35.19 UART Operation During Sleep

The UART ceases to operate during Sleep. The safe way to wake the device from Sleep by a serial operation is to use the Wake-on-Break feature of the UART. See Auto Wake-on-Break.

## 35.20 Register Definitions: UART

Long bit name prefixes for the UART peripherals are shown in the following table. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 35-4. UART Long bit name prefixes

Peripheral	Bit Name Prefix
UART1 (full featured)	U1
UART2 (full featured)	U2

# PIC18F26/46/56Q84

# **UART - Universal Asynchronous Receiver Tra...**

continued		
Peripheral	Bit Name Prefix	
UART3 (limited features)	U3	
UART4 (limited features)	U4	
UART5 (limited features)	U5	

### 35.20.1 UxCON0

Name: UxCON0

**Offset:** 0x2AB,0x2BE,0x2D1,0x2E4,0x2F7

**UART Control Register 0** 

Bit	7	6	5	4	3	2	1	0
	BRGS	ABDEN	TXEN	RXEN		MOD	E[3:0]	
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

#### Bit 7 - BRGS Baud Rate Generator Speed Select

Value	Description
1	Baud Rate Generator is high speed with 4 baud clocks per bit
0	Baud Rate Generator is normal speed with 16 baud clocks per bit

### Bit 6 - ABDEN Auto-baud Detect Enable(3)

Valu	e Description
1	Auto-baud is enabled. Receiver is waiting for Sync character (0x55)
0	Auto-baud is not enabled or auto-baud is complete

## Bit 5 - TXEN Transmit Enable Control<sup>(2)</sup>

Value	Description
1	Transmit is enabled. TX output pin drive is forced on when transmission is active, and controlled by
	PORT TRIS control when transmission is idle.
0	Transmit is disabled. TX output pin drive is controlled by PORT TRIS control

### Bit 4 - RXEN Receive Enable Control(2)

Value	Description
1	Receiver is enabled
0	Receiver is disabled

#### Bits 3:0 - MODEI3:01 UART Mode Select(1)

Value	Description
1111-110	Reserved
1	
1100	LIN Master/Slave mode <sup>(4)</sup>
1011	LIN Slave-Only mode <sup>(4)</sup>
1010	DMX mode <sup>(4)</sup>
1001	DALI Control Gear mode <sup>(4)</sup>
1000	DALI Control Device mode <sup>(4)</sup>
0111-010	Reserved
1	
0100	Asynchronous 9-bit UART Address mode. 9th bit: 1 = address, 0 = data
0011	Asynchronous 8-bit UART mode with 9th bit even parity
0010	Asynchronous 8-bit UART mode with 9th bit odd parity
0001	Asynchronous 7-bit UART mode
0000	Asynchronous 8-bit UART mode

#### Notes:


- 1. Changing the UART MODE while ON = 1 may cause unexpected results.
- 2. Clearing TXEN or RXEN will not clear the corresponding buffers. Use TXBE or RXBE to clear the buffers.
- 3. ABDEN is read-only when MODE > 'b0111.
- 4. Full-featured UARTs only.

### 35.20.2 UxCON1

Name: UxCON1

**Offset:** 0x2AC,0x2BF,0x2D2,0x2E5,0x2F8

**UART Control Register 1** 



### Bit 7 - ON Serial Port Enable

Value	Description
1	Serial port enabled
0	Serial port disabled (held in Reset)

#### Bit 4 - WUE Wake-up Enable

Value	Description					
1	Receiver is waiting for falling RX input edge which will set the UxIF bit. Cleared by hardware on wake					
	event. Also requires UxIE bit of PIEx to enable wake					
0	Receiver operates normally					

#### Bit 3 - RXBIMD Receive Break Interrupt Mode Select

Value	Description
1	Set RXBKIF immediately when RX in has been low for the minimum Break time
0	Set RXBKIF on rising RX input after RX in has been low for the minimum Break time

### Bit 1 - BRKOVR Send Break Software Override

Valu	ue Description	
1	TX output is forced to non-idle s	tate
0	TX output is driven by transmit s	hift register

#### Bit 0 - SENDB Send Break Control(1)

Value	Description
1	Output Break upon UxTXB write. Written byte follows Break. Bit is cleared by hardware.
0	Break transmission completed or disabled

#### Note:

1. This bit is read-only in LIN, DMX, and DALI modes.

### 35.20.3 UxCON2

Name: UxCON2

**UART Control Register 2** 

Bit	7	6	5	4	3	2	1	0
	RUNOVF	RXPOL	STP[1:0]		C0EN	TXPOL	FLO[1:0]	
Access	R/W	R/W/HC	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

#### Bit 7 - RUNOVF Run During Overflow Control

Value	Description
1	RX input shifter continues to synchronize with Start bits after overflow condition
0	RX input shifter stops all activity on receiver overflow condition

### Bit 6 - RXPOL Receive Polarity Control

Valu	e Descriptio	1
1	Invert RX p	olarity, Idle state is low
0	RX polarity	is not inverted, Idle state is high

### Bits 5:4 - STP[1:0] Stop Bit Mode Control<sup>(1)</sup>

Value	Description
11	Transmit 2 Stop bits, receiver verifies first Stop bit
10	Transmit 2 Stop bits, receiver verifies first and second Stop bits
01	Transmit 1.5 Stop bits, receiver verifies first Stop bit
00	Transmit 1 Stop bit, receiver verifies first Stop bit

### Bit 3 - C0EN Checksum Mode Select(2)

Value	Condition	Description
1	MODE = LIN	Enhanced LIN checksum includes PID in sum
0	MODE = LIN	Legacy LIN checksum does not include PID in sum
1	MODE = not LIN	Checksum is the sum of all TX and RX characters
0	MODE = not LIN	Checksum is disabled

## Bit 2 – TXPOL Transmit Control Polarity<sup>(1)</sup>

Value	Description
1	Output data is inverted, TX output is low in Idle state
0	Output data is not inverted, TX output is high in Idle state

## Bits 1:0 - FLO[1:0] Handshake Flow Control

Value	Description
11	Reserved
10	RTS/CTS and TXDE Hardware flow control
01	XON/XOFF Software flow control
00	Flow control is off

#### Notes:

- 1. All modes transmit selected number of Stop bits.
- 2. Full-featured UARTs only.

### 35.20.4 UxERRIR

Name: UxERRIR

**UART Error Interrupt Flag Register** 

Bit	7	6	5	4	3	2	1	0
	TXMTIF	PERIF	ABDOVF	CERIF	FERIF	RXBKIF	RXFOIF	TXCIF
Access	R/S/C	R/W/HC	R/W/S	R/W/S	R/S/C	R/W/S	R/W/S	R/W/S
Reset	1	0	0	0	0	0	0	0

#### Bit 7 - TXMTIF Transmit Shift Register Empty Interrupt Flag

Value	Description
1	Transmit shift register is empty (Set at end of Stop bits)
0	Transmit shift register is actively shifting data

### Bit 6 - PERIF Parity Error Interrupt Flag

Value	Condition	Description
1	MODE = LIN or Parity	Unread byte at top of input FIFO has parity error
0	MODE = LIN or Parity	Unread byte at top of input FIFO does not have parity error
1	MODE = DALI Device	Unread byte at top of input FIFO received as Forward Frame
0	MODE = DALI Device	Unread byte at top of input FIFO received as Back Frame
1	MODE = Address	Unread byte at top of input FIFO received as address
0	MODE = Address	Unread byte at top of input FIFO received as data
X	MODE = All others	Not used

### Bit 5 - ABDOVF Auto-baud Detect Overflow Interrupt Flag

Value	Condition	Description
1	MODE = DALI	Start bit measurement overflowed counter
0	MODE = DALI	No overflow during Start bit measurement
1	MODE = All others	Baud Rate Generator overflowed during the auto-detection sequence
0	MODE = All others	Baud Rate Generator has not overflowed

#### Bit 4 - CERIF Checksum Error Interrupt Flag

Value	Condition	Description
1	MODE = LIN	Checksum error
0	MODE = LIN	No checksum error
Х	MODE = not LIN	Not used

#### Bit 3 - FERIF Framing Error Interrupt Flag

	<u> </u>
Value	Description
1	Unread byte at top of input FIFO has framing error
0	Unread byte at top of input FIFO does not have framing error

## Bit 2 - RXBKIF Break Reception Interrupt Flag

Value	Description
1	Break detected
0	No break detected

#### Bit 1 - RXFOIF Receive FIFO Overflow Interrupt Flag

_	<u> </u>
Value	Description
1	Receive FIFO has overflowed
0	Receive FIFO has not overflowed

## Bit 0 - TXCIF Transmit Collision Interrupt Flag<sup>(1)</sup>

# PIC18F26/46/56Q84

# **UART - Universal Asynchronous Receiver Tra...**

Value	Description
1	Transmitted word is not equal to the word received during transmission
0	Transmitted word equals the word received during transmission

#### Note:

1. Full-featured UARTs only.

### 35.20.5 UxERRIE

Name: UxERRIE

**UART Error Interrupt Enable Register** 

Bit	7	6	5	4	3	2	1	0
	TXMTIE	PERIE	ABDOVE	CERIE	FERIE	RXBKIE	RXFOIE	TXCIE
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

#### Bit 7 - TXMTIE Transmit Shift Register Empty Interrupt Enable

Value	Description
1	Interrupt enabled
0	Interrupt not enabled

#### Bit 6 - PERIE Parity Error Interrupt Enable

Value	Description
1	Interrupt enabled
0	Interrupt not enabled

#### Bit 5 - ABDOVE Auto-baud Detect Overflow Interrupt Enable

	The state of the s
Value	Description
1	Interrupt enabled
0	Interrupt not enabled

#### Bit 4 - CERIE Checksum Error Interrupt Enable

Value	Description
1	Interrupt enabled
0	Interrupt not enabled

#### Bit 3 - FERIE Framing Frror Interrupt Fnable

	Bit 6 - 1 Eitile 1 familing Enter Interrupt Enable		
Value	Description		
1	Interrupt enabled		
0	Interrupt not enabled		

#### Bit 2 - RXBKIE Break Reception Interrupt Enable

Value	Description
1	Interrupt enabled
0	Interrupt not enabled

## Bit 1 - RXFOIE Receive FIFO Overflow Interrupt Enable

Value	Description		
1	Interrupt enabled		
0	Interrupt not enabled		

## Bit 0 - TXCIE Transmit Collision Interrupt Enable<sup>(1)</sup>

Val	lue	Description
1		Interrupt enabled
0		Interrupt not enabled

## Note:

1. Full-featured UARTs only.

### 35.20.6 UxUIR

Name: UxUIR

**Offset:** 0x2B1,0x2C4,0x2D7,0x2EA,0x2FD

**UART General Interrupt Flag Register** 



## Bit 7 - WUIF Wake-up Interrupt

Value	Description			
1	Idle to non-idle transition on RX line detected when WUE is set. Also sets UxIF. (WUIF must be cleared			
	by software to clear UxIF)			
0	WUE not enabled by software or no transition detected			

## Bit 6 - ABDIF Auto-baud Detect Interrupt

Value	е	Description
1		Auto-baud detection complete. Status shown in UxIF when ABDIE is set. (Must be cleared by software)
0		Auto-baud not enabled or auto-baud enabled and auto-baud detection not complete

## Bit 2 - ABDIE Auto-baud Detect Interrupt Enable

Value	Description
1	ABDIF will set UxIF bit in PIRx register
0	ABDIF will not set UxIF

### 35.20.7 UxFIFO

Name: UxFIFO

**Offset:** 0x2B0,0x2C3,0x2D6,0x2E9,0x2FC

**UART FIFO Status Register** 

Bit	7	6	5	4	3	2	1	0
	TXWRE	STPMD	TXBE	TXBF	RXIDL	XON	RXBE	RXBF
Access	R/W/S	R/W	R/W/S/C	R/S/C	R/S/C	S/C	R/W/S/C	R/S/C
Reset	0	0	1	0	1	1	1	0

#### Bit 7 - TXWRE Transmit Write Error Status (must be cleared by software)

TATTLE Transmit White Error Status (mast be distinct by software)				
Value	Condition	Description		
1	MODE = LIN Master	UxP1L was written when a master process was active		
1	MODE = LIN Slave	UxTXB was written when UxP2 = 0 or more than UxP2 bytes have been		
		written to UxTXB since last Break		
1	MODE = Address detect	UxP1L was written before the previous data in UxP1L was transferred to TX shifter		
1	MODE = All	A new byte was written to UxTXB when the output FIFO was full		
0	MODE = All	No error		

#### Bit 6 - STPMD Stop Bit Detection Mode

Value	Condition	Description
1	STP = 11	Assert UxRXIF at end of first Stop bit
1	STP≠ 11	Assert UxRXIF at end of last Stop bit
0	STP = xx	Assert UxRXIF in middle of first Stop bit

### Bit 5 - TXBE Transmit Buffer Empty Status

Value	Description
1	Transmit buffer is empty. Setting this bit will clear the transmit buffer and output shift register.
0	Transmit buffer is not empty. Software cannot clear this bit.

### Bit 4 - TXBF Transmit Buffer Full Status

Value	Description
1	Transmit buffer is full
0	Transmit buffer is not full

#### Bit 3 - RXIDL Receive Pin Idle Status

Value	Description
1	Receive pin is in Idle state
0	UART is receiving Start, Stop, Data, Auto-baud, or Break

#### Bit 2 - XON Software Flow Control Transmit Enable Status

Value	Description
1	Transmitter is enabled
0	Transmitter is disabled

#### Bit 1 - RXBE Receive Buffer Empty Status

Value	Description
1	Receive buffer is empty. Setting this bit will clear the RX buffer <sup>(1)</sup>
0	Receive buffer is not empty. Software cannot clear this bit.

### Bit 0 - RXBF Receive Buffer Full Status

Value	Description
1	Receive buffer is full

# PIC18F26/46/56Q84

## **UART - Universal Asynchronous Receiver Tra...**

Value	Description
0	Receive buffer is not full

### Note:

1. The BSF instruction should not be used to set RXBE because doing so will clear a byte pending in the transmit shift register when the UxTXB register is empty. Instead, use the MOVWF instruction with a '0' in the TXBE bit location.

### 35.20.8 UxBRG

Name: UxBRG

**Offset:** 0x2AE,0x2C1,0x2D4,0x2E7,0x2FA

**UART Baud Rate Generator** 

Bit	15	14	13	12	11	10	9	8			
	BRG[15:8]										
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W			
Reset	0	0	0	0	0	0	0	0			
Bit	7	6	5	4	3	2	1	0			
	BRG[7:0]										
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W			
Reset	0	0	0	0	0	0	0	0			

#### Bits 15:0 - BRG[15:0] Baud Rate Generator Value

The UART Baud Rate equals [Fosc\*(1+(BRGS\*3)]/[(16\*(BRG-1))]

#### Notes:

- 1. The individual bytes in this multi-byte register can be accessed with the following register names:
  - UxBRGH: Accesses the high byte BRG[15:8]
  - UxBRGL: Accesses the low byte BRG[7:0]
- 2. The UxBRG registers should only be written when ON = 0.
- 3. Maximum BRG value when MODE = 100x and BRGS = 1 is 0x7FFE.
- 4. Maximum BRG value when MODE = '100x and BRGS = 0 is 0x1FFE.

### 35.20.9 UxRXB

Name: **UxRXB** 

Offset: 0x2A1,0x2B4,0x2C7,0x2DA,0x2ED

**UART** Receive Register

Bit	7	6	5	4	3	2	1	0
				RXB	[7:0]			
Access	R	R	R	R	R	R	R	R
Reset	X	X	X	X	X	X	X	X

Bits 7:0 - RXB[7:0] Top of Receive FIFO

DS40002259A-page 642

## 35.20.10 UxTXB

Name: UxTXB

**Offset:** 0x2A3,0x2B6,0x2C9,0x2DC,0x2EF

**UART Transmit Register** 


Bit	7	6	5	4	3	2	1	0
				TXB	[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - TXB[7:0] Bottom of Transmit FIFO

## 35.20.11 UxP1

Name: UxP1

**UART Parameter 1** 



## Bit 8 - P1[8] Parameter 1 Most Significant bit

UART mode operating parameter values

Value	Condition	Description
n	MODE = DMX	Most Significant bit of number of bytes to transmit between Start Code and automatic Break generation
n	MODE = DALI Control Device	Most Significant bit of idle time delay after which a Forward Frame is sent. Measured in half-bit periods
n	MODE = DALI Control Gear	Most Significant bit of delay between the end of a Forward Frame and the start of the Back Frame Measured in half-bit periods
X	All other modes/Limited featured UART	Not used

## Bits 7:0 - P1[7:0] Parameter 1 Least Significant bits

UART mode operating parameter values

Value	Condition	Description
n	MODE = DMX	Least Significant bits of number of bytes to transmit between Start Code and automatic Break generation
n	MODE = DALI Control Device	Least Significant bits of idle time delay after which a Forward Frame is sent. Measured in half-bit periods
n	MODE = DALI Control Gear	Least Significant bits of delay between the end of a Forward Frame and the start of the Back Frame Measured in half-bit periods
n	MODE = LIN	PID to transmit (Only Least Significant 6 bits used)
n	MODE = Asynchronous Address	Address to transmit (9th transmit bit automatically set to '1')
X	All other modes	Not used

Notes: The individual bytes in this multi-byte register can be accessed with the following register names:

- UxP1H: Accesses the high byte P1[8]
- UxP1L: Accesses the low byte P1[7:0]

## 35.20.12 UxP2

Name: UxP2

**UART Parameter 2** 

Bit	15	14	13	12	11	10	9	8
								P2[8]
Access								R/W
Reset								0
Bit	7	6	5	4	3	2	1	0
				P2[	7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

## Bit 8 - P2[8] Parameter 2 Most Significant bit

UART mode operating parameter values

Value	Condition	Description
n	MODE = DMX	Most Significant bit of first address of receive block
n	MODE = DALI	Most Significant bit of number of half-bit periods of idle time in Forward Frame detection threshold
Х	All other modes/Limited featured UART	Not used

## Bits 7:0 - P2[7:0] Parameter 2 Least Significant bits

UART mode operating parameter values

Value	Condition	Description
n	MODE = DMX	Least Significant bits of first address of receive block
n	MODE = DALI	Least Significant bits of number of half-bit periods of idle time in Forward Frame detection threshold
n	MODE = LIN	Number of data bytes to transmit
n	MODE = Asynchronous Address	Receiver address
Х	All other modes	Not used

**Notes:** The individual bytes in this multi-byte register can be accessed with the following register names:

- UxP2H: Accesses the high byte P2[8]
- UxP2L: Accesses the low byte P2[7:0]

## 35.20.13 UxP3

Name: UxP3

**UART Parameter 3** 

Bit	15	14	13	12	11	10	9	8
								P3[8]
Access			•					R/W
Reset								0
Bit	7	6	5	4	3	2	1	0
				P3	[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

## Bit 8 - P3[8] Parameter 3 Most Significant bit

UART mode operating parameter values

Value	Condition	Description
n	MODE = DMX	Most Significant bit of last address of receive block
Х	All other modes/Limited featured UART	Not used

### Bits 7:0 - P3[7:0] Parameter 3 Least Significant bits

UART mode operating parameter values

Value	Condition	Description
n	MODE = DMX	Least Significant bits of last address of receive block
n	MODE = LIN Slave	Number of data bytes to receive
n	MODE = Asynchronous Address	Receiver address mask. Received address is XOR'd with UxP2L
		then AND'd with UxP3L Match occurs when result is zero
Х	All other modes	Not used

Notes: The individual bytes in this multi-byte register can be accessed with the following register names:

- UxP3H: Accesses the high byte P3[8]
- UxP3L: Accesses the low byte P3[7:0]

# PIC18F26/46/56Q84

## **UART - Universal Asynchronous Receiver Tra...**

## 35.20.14 UxTXCHK

Name: UxTXCHK Offset: 0x2A4,0x2B7

UART Transmit Checksum Result Register

Bit	7	6	5	4	3	2	1	0
				TXCH	K[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - TXCHK[7:0] Transmit Checksum Value

Value	Condition	Description
n	MODE = LIN and C0EN = 1	Sum of all transmitted bytes including PID
n	MODE = LIN and C0EN = 0	Sum of all transmitted bytes except PID
n	MODE = All others and C0EN = 1	Sum of all transmitted bytes since last clear
X	MODE = All others and C0EN = 0	Not used

# PIC18F26/46/56Q84

## **UART - Universal Asynchronous Receiver Tra...**

## 35.20.15 UxRXCHK

Name: UxRXCHK Offset: 0x2A2, 0x2B5

UART Receive Checksum Result Register

Bit	7	6	5	4	3	2	1	0
				RXCH	IK[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - RXCHK[7:0] Receive Checksum Value

Value	Condition	Description
n	MODE = LIN and C0EN = 1	Sum of all received bytes including PID
n	MODE = LIN and C0EN = 0	Sum of all received bytes except PID
n	MODE = All others and C0EN = 1	Sum of all received bytes since last clear
Х	MODE = All others and C0EN = 0	Not used

# 35.21 Register Summary - UART

00         U2ERRIE         7:0         TXMTIE         PERIE         ABDOVE         CERIE         FERIE         RXBKIE           0x01          Reserved         0x02A0         RXB[7:0]         RXB[7:0]         0x02A1         U1RXB         7:0         RXCHK[7:0]         RXCHK[7:0]         0x02A3         U1TXB         7:0         TXB[7:0]         TXCHK[7:0]         TXCHK[7:0]         0x02A4         U1TXCHK         7:0         P1[7:0]         P1[7:0]         P2[7:0]         P2[7:0]         TXCHX[7:0]         P3[7:0]         P3[7:0]         P3[7:0]         P3[7:0]         P3[7:0]         P3[7:0]         PXPIMD         PXPIMD <t< th=""><th>P1[8] P2[8] P3[8]</th></t<>	P1[8] P2[8] P3[8]				
Nove	P2[8]				
0x02A0         0x02A1         U1RXB         7:0         RXB[7:0]           0x02A2         U1RXCHK         7:0         RXCHK[7:0]           0x02A3         U1TXB         7:0         TXB[7:0]           0x02A4         U1TXCHK         7:0         TXCHK[7:0]           0x02A5         U1P1         7:0         P1[7:0]           0x02A7         U1P2         7:0         P2[7:0]           0x02A9         U1P3         7:0         P3[7:0]           0x02AB         U1CON0         7:0         BRGS         ABDEN         TXEN         MOD	P2[8]				
0x02A1         U1RXB         7:0         RXB[7:0]           0x02A2         U1RXCHK         7:0         RXCHK[7:0]           0x02A3         U1TXB         7:0         TXB[7:0]           0x02A4         U1TXCHK         7:0         TXCHK[7:0]           0x02A5         U1P1         7:0         P1[7:0]           0x02A7         U1P2         7:0         P2[7:0]           0x02A9         U1P3         7:0         P3[7:0]           0x02AB         U1CON0         7:0         BRGS         ABDEN         TXEN         MOD	P2[8]				
0x02A2         U1RXCHK         7:0         RXCHK[7:0]           0x02A3         U1TXB         7:0         TXB[7:0]           0x02A4         U1TXCHK         7:0         TXCHK[7:0]           0x02A5         U1P1         7:0         P1[7:0]           0x02A7         U1P2         7:0         P2[7:0]           0x02A9         U1P3         7:0         P3[7:0]           0x02AB         U1CON0         7:0         BRGS         ABDEN         TXEN         RXEN         MOI	P2[8]				
0x02A3         U1TXB         7:0         TXB[7:0]           0x02A4         U1TXCHK         7:0         TXCHK[7:0]           0x02A5         U1P1         7:0         P1[7:0]           0x02A7         U1P2         7:0         P2[7:0]           0x02A9         U1P3         7:0         P3[7:0]           0x02AB         U1CON0         7:0         BRGS         ABDEN         TXEN         RXEN         MOD	P2[8]				
0x02A4         U1TXCHK         7:0         TXCHK[7:0]           0x02A5         U1P1         7:0         P1[7:0]           0x02A7         U1P2         7:0         P2[7:0]           0x02A9         U1P3         7:0         P3[7:0]           0x02AB         U1CON0         7:0         BRGS         ABDEN         TXEN         RXEN         MOI	P2[8]				
0x02A5         U1P1         7:0         P1[7:0]           15:8                               0x02A7         U1P2                   7:0                   P2[7:0]           0x02A9         U1P3                   7:0                   P3[7:0]           0x02AB         U1CON0         7:0         BRGS         ABDEN         TXEN         RXEN         MOI	P2[8]				
0x02A5	P2[8]				
15:8  0x02A7  U1P2  7:0  15:8  0x02A9  U1P3  7:0  P2[7:0]  15:8  0x02AB  U1CON0  7:0  BRGS  ABDEN  TXEN  RXEN  MOD	P2[8]				
0x02A7 U1P2 15:8 P3[7:0]  0x02A9 U1P3 7:0 P3[7:0]  0x02AB U1CON0 7:0 BRGS ABDEN TXEN RXEN MODE					
15:8  0x02A9					
0x02A9	P3[8]				
0x02AB         U1CON0         7:0         BRGS         ABDEN         TXEN         RXEN         MOI	P3[8]				
0x02AC U1CON1 7:0 ON WUE RXBIMD	BRKOVR SENDB				
0x02AD U1CON2 7:0 RUNOVF RXPOL STP[1:0] C0EN TXPOL	FLO[1:0]				
0x02AE					
15:8 BRG[15:8]	D)/D5 D)/D5				
0x02B0 U1FIFO 7:0 TXWRE STPMD TXBE TXBF RXIDL XON	RXBE RXBF				
0x02B1 U1UIR 7:0 WUIF ABDIF ABDIE	DVEOIE TYOIS				
0x02B2 U1ERRIR 7:0 TXMTIF PERIF ABDOVF CERIF FERIF RXBKIF	RXFOIF TXCIF				
0x02B3 U1ERRIE 7:0 TXMTIE PERIE ABDOVE CERIE FERIE RXBKIE	RXFOIE TXCIE				
0x02B4         U2RXB         7:0         RXB[7:0]           0x02B5         U2RXCHK         7:0         RXCHK[7:0]					
0x02B6         U2TXB         7:0         TXB[7:0]           0x02B7         U2TXCHK         7:0         TXCHK[7:0]					
0x02B7	<u> </u>				
0x02B8 U2P1 7.0 P1[7.0]	D4[0]				
7:0 P2[7:0]	P1[8]				
0x02BA U2P2 7.0 F2[7.0]	P2[8]				
7:0 P3[7:0]	FZ[0]				
0x02BC U2P3 15:8	P3[8]				
	DE[3:0]				
0x02BF	BRKOVR SENDB				
0x02C0	FLO[1:0]				
7:0 BRG[7:0]	1 20[1.0]				
0x02C1 U2BRG 15:8 BRG[15:8]					
0x02C3 U2FIFO 7:0 TXWRE STPMD TXBE TXBF RXIDL XON	RXBE RXBF				
0x02C4	10.02				
0x02C5 U2ERRIR 7:0 TXMTIF PERIF ABDOVF CERIF FERIF RXBKIF	RXFOIF TXCIF				
0x02C6 U2ERRIE 7:0 TXMTIE PERIE ABDOVE CERIE FERIE RXBKIE	RXFOIE TXCIE				
0x02C7					
0x02C8 Reserved					
0x02C9					
0x02CA Reserved					
7·0 P1[7·0]					
0x02CB U3P1 15:8					
7:0 P2[7:0]					
0x02CD U3P2 15:8					
7:0 P3(7:0)					
0x02CF U3P3 15:8					
	DE[3:0]				
0x02D2 U3CON1 7:0 ON WUE RXBIMD	BRKOVR SENDB				
0x02D3 U3CON2 7:0 RUNOVF RXPOL STP[1:0] TXPOL	FLO[1:0]				

# PIC18F26/46/56Q84

# **UART - Universal Asynchronous Receiver Tra...**

contin	nued									
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
		7:0				BRO	G[7:0]			
0x02D4	U3BRG	15:8					i[15:8]			
0x02D6	U3FIFO	7:0	TXWRE	STPMD	TXBE	TXBF	RXIDL	XON	RXBE	RXBF
0x02D7	U3UIR	7:0	WUIF	ABDIF				ABDIE		
0x02D8	U3ERRIR	7:0	TXMTIF	PERIF	ABDOVF	CERIF	FERIF	RXBKIF	RXFOIF	
0x02D9	U3ERRIE	7:0	TXMTIE	PERIE	ABDOVE	CERIE	FERIE	RXBKIE	RXFOIE	
0x02DA	U4RXB	7:0				RXE	3[7:0]			
0x02DB	Reserved									
0x02DC	U4TXB	7:0				TXE	3[7:0]			
0x02DD	Reserved									
0.0005	LUDA	7:0				P1	[7:0]			
0x02DE	U4P1	15:8								
0.0050	LUDO	7:0				P2	[7:0]			
0x02E0	U4P2	15:8								
0.0050	LUDO	7:0				P3	[7:0]			
0x02E2	U4P3	15:8					-			
0x02E4	U4CON0	7:0	BRGS	ABDEN	TXEN	RXEN		MOD	E[3:0]	
0x02E5	U4CON1	7:0	ON			WUE	RXBIMD		BRKOVR	SENDB
0x02E6	U4CON2	7:0	RUNOVF	RXPOL	STP	[1:0]		TXPOL	FLO	[1:0]
		7:0								
0x02E7	U4BRG	15:8					[15:8]			
0x02E9	U4FIFO	7:0	TXWRE	STPMD	TXBE	TXBF	RXIDL	XON	RXBE	RXBF
0x02EA	U4UIR	7:0	WUIF	ABDIF				ABDIE		
0x02EB	U4ERRIR	7:0	TXMTIF	PERIF	ABDOVF	CERIF	FERIF	RXBKIF	RXFOIF	
0x02EC	U4ERRIE	7:0	TXMTIE	PERIE	ABDOVE	CERIE	FERIE	RXBKIE	RXFOIE	
0x02ED	U5RXB	7:0		l .		RXE	3[7:0]			
0x02EE	Reserved									
0x02EF	U5TXB	7:0				TXE	3[7:0]			
0x02F0	Reserved									
		7:0				P1	[7:0]			
0x02F1	U5P1	15:8								
		7:0				P2	[7:0]			
0x02F3	U5P2	15:8								
		7:0				P3	[7:0]			
0x02F5	U5P3	15:8								
0x02F7	U5CON0	7:0	BRGS	ABDEN	TXEN	RXEN		MOD	E[3:0]	
0x02F8	U5CON1	7:0	ON			WUE	RXBIMD		BRKOVR	SENDB
0x02F9	U5CON2	7:0	RUNOVF	RXPOL	STP			TXPOL	FLO	
		7:0		1	1		G[7:0]		1	
0x02FA	U5BRG	15:8					[15:8]			
0x02FC	U5FIFO	7:0	TXWRE	STPMD	TXBE	TXBF	RXIDL	XON	RXBE	RXBF
0x02FD	U5UIR	7:0	WUIF	ABDIF				ABDIE		
0x02FE	U5ERRIR	7:0	TXMTIF	PERIF	ABDOVF	CERIF	FERIF	RXBKIF	RXFOIF	
			TXMTIE	PERIE	ABDOVE	CERIE	1	RXBKIE	RXFOIE	

# 36. SPI - Serial Peripheral Interface Module


The Serial Peripheral Interface (SPI) module is a synchronous serial data communication bus that operates in Full-Duplex mode. Devices communicate in a master/slave environment where the master device initiates the communication. A slave device is typically controlled through a chip select known as Slave Select. Some examples of slave devices include serial EEPROMs, shift registers, display drivers, A/D converters, and other PIC® devices with SPI capabilities.

The SPI bus specifies four signal connections:

- · Serial Clock (SCK)
- · Serial Data Out (SDO)
- · Serial Data In (SDI)
- · Slave Select (SS)

The following figure shows the block diagram of the SPI module.

Figure 36-1. SPI Module Simplified Block Diagram



Note 1: If the transmit FIFO is empty and TXR=1, the previous value of the receive shift register will be sent to the transmit serializer.

The SPI transmit output (SDO\_out) is available to the remappable PPS SDO pin and internally to the select peripherals.


The SPI bus typically operates with a single master device and one or more slave devices. When multiple slave devices are used, an independent Slave Select connection is required from the master device to each slave device.

The master selects only one slave at a time. Most slave devices have tri-state outputs so their output signal appears disconnected from the bus when they are not selected.

Transmissions typically involve Shift registers, eight bits in size, one in the master and one in the slave. With either the master or the slave device, data is always shifted out one bit at a time, with the Most Significant bit (MSb) shifted out first. At the same time, a new bit is shifted into the device. Unlike older Microchip devices, the SPI module on this device contains one register for incoming data and another register for outgoing data. Both registers also have multibyte FIFO buffers and allow for DMA bus connections.

The figure below shows a typical connection between two devices configured as master and slave devices.

Figure 36-2. SPI Master/Slave Connection with FIFOs



Note 1: In some modes, if the Transmit FIFO is empty, the most recently received byte of data will be transmitted.

2: This diagram assumes that the LSBF bit is cleared (communications are MSb-first). When LSBF is set, the communications will be LSb-first.

Data is shifted out of the transmit FIFO on the programmed clock edge and into the receive Shift register on the opposite edge of the clock.

The master device transmits information on its SDO output pin which is connected to, and received by, the slave's SDI input pin. The slave device transmits information on its SDO output pin, which is connected to, and received by, the master's SDI input pin.

The master device sends out the clock signal. Both the master and the slave devices should be configured for the same clock phase and clock polarity.

During each SPI clock cycle, a full-duplex data transmission occurs. This means that while the master device is sending out the MSb from its output register (on its SDO pin) and the slave device is reading this bit and saving it as the LSb of its input register. The slave device is also sending out the MSb from its Shift register (on its SDO pin) and the master device is reading this bit and saving it as the LSb of its input register.

After eight bits have been shifted out, the master and slave have exchanged register values and stored the incoming data into the receiver FIFOs.

If there is more data to exchange, the registers are loaded with new data and the process repeats.

Whether the data is meaningful or not (dummy data) depends on the application software. This leads to three scenarios for data transmission:

- Master sends useful data and slave sends dummy data
- Master sends useful data and slave sends useful data

· Master sends dummy data and slave sends useful data

In this SPI module, dummy data may be sent without software involvement. Dummy transmit data is automatically handled by clearing the TXR bit and receive data is ignored by clearing the RXR bit. See Table 36-1 as well as Master Mode and Slave Mode for further TXR/RXR setting details.

This SPI module can send transmissions of any number of bits, and can send information in segments of varying size (from 1-8 bits in width). As such, transmissions may involve any number of clock cycles, depending on the amount of data to be transmitted.

When there is no more data to be transmitted, the master stops sending the clock signal and deselects the slave. Every slave device connected to the bus that has not been selected through its Slave Select line disregards the clock and transmission signals and does not transmit out any data of its own.

# 36.1 SPI Controls

The following registers control the SPI operation:

- · SPI Interrupt Flag Register (SPIxINTF)
- SPI Interrupt Enable Register (SPIxINTE)
- SPI Byte Count High and Low Registers (SPIxTCNTH/L)
- SPI Bit Count Register (SPIxTWIDTH)
- SPI Baud Rate Register (SPIxBAUD)
- SPI Control Register 0 (SPIxCON0)
- SPI Control Register 1 (SPIxCON1)
- · SPI Control Register 2 (SPIxCON2)
- SPI FIFO Status Register (SPIxSTATUS)
- SPI Receiver Buffer Register (SPIxRXB)
- SPI Transmit Buffer Register (SPIxTXB)
- SPI Clock Select Register (SPIxCLK)

SPIxCON0, SPIxCON1, and SPIxCON2 are control registers for the SPI module.

SPIxSTATUS reflects the status of both the SPI module and the receive and transmit FIFOs.

SPIxBAUD and SPIxCLK control the Baud Rate Generator (BRG) of the SPI module when in Master mode. The SPIxCLK selects the clock source that is used by the BRG. The SPIxBAUD configures the clock divider used on that clock source. More information on the BRG is available in Master Mode SPI Clock Configuration.

SPIxTxB and SPIxRxB are the Transmit and Receive Buffer registers used to send and receive data on the SPI bus. The Transmit and Receive Buffer registers offer indirect access to Shift registers that are used for shifting the data in and out. Both registers access the multi-byte FIFOs, allowing for multiple transmissions or receptions to be stored between software transfers of the data.

The SPIxTCNTH:L register pair either count or control the number of bits or bytes in a data transfer. When BMODE = 1, the SPIxTCNT value signifies bytes and the SPIxTWIDTH value signifies the number of bits in a byte. When BMODE = 0, the SPIxTCNT value is concatenated with the SPIxTWIDTH register to signify bits. In Master Receive Only mode (TXR = 0 and RXR = 1), the data transfer is initiated by writing SPIxTCNT with the desired bit or byte value to transfer. In Master Transmit mode (TXR = 1), the data transfer is initiated by writing the SPIxTxB register, in which case the SPIxTCNT is a down counter for the bits or bytes transferred.

The SPIxINTF and SPIxINTE are the flags and enables, respectively, for SPI specific interrupts. They are tied to the SPIxIF flag and SPIxIE enable bit in the PIR and PIE registers, which is triggered when any interrupt contained in the SPIxINTF/SPIxINTE registers is triggered. The PIR/PIE registers also contain SPIxTXIF/SPIxTXIE bits, which are the interrupt flag and enable for the SPI Transmit Interrupt, as well as the SPIxRXIF/SPIxRXIE bits, which are the interrupt flag and enable bit for the SPI receive interrupt.

# 36.2 SPI Operation

When initializing the SPI, several options need to be specified. This is done by programming the appropriate control bits of the SPIxCON0, SPIxCON1, and SPIxCON2 registers. These control bits allow the following to be configured:

- · Master mode (SCK is the clock output)
- · Slave mode (SCK is the clock input)
- Clock Polarity (Idle state of SCK)
- · Input, Output, and Slave Select Polarity
- · Data Input Sample Phase (middle or end of data output time)
- Clock Edge (output data on first/second edge of SCK)
- · Clock Rate (Master mode only)
- · Slave Select mode (Master or Slave mode)
- MSB-First or LSB-First
- Receive/Transmit modes:
  - Full-Duplex
  - Receive Only (receive without transmit)
  - Transmit Only (transmit without receive)
- Transfer Counter mode (only available in Transmit Only mode)

### 36.2.1 Enabling and Disabling the SPI Module

Setting the EN bit enables the SPI peripheral. However, to reset or reconfigure the SPI mode the EN bit must be cleared.

Setting the EN bit enables the SPI inputs and outputs: SDI, SDO, SCK\_out, SCK\_in, SS\_out, and SS\_in. The pins for all of these inputs and outputs are selected by the PPS controls, and thus must have their functions mapped properly to the device pins to function. Refer to the "PPS - Peripheral Pin Select Module" chapter for more details.

SS\_out and SCK\_out must have the pins to which they are assigned set as outputs (TRIS bits must be '0') in order to properly output. Clearing the TRIS bit of the SDO pin will cause the SPI module to always control that pin, but is not necessary for SDO functionality. (see Input and Output Polarity Control)

Configurations selected by the following registers should not be changed while the EN bit is set:

- SPIxBAUD
- SPIxCON1
- SPIxCON0 (with the exception of clearing the EN bit)

Clearing the EN bit aborts any transmissions in progress, disables the setting of interrupt flags by hardware, and resets the FIFO occupancy. (see Transmit and Receive FIFOs)

#### 36.2.2 BUSY Bit

While a data transfer is in progress, the SPI hardware sets the BUSY bit. This bit can be polled by the user to determine the current status of the SPI module, and to know when a communication is complete. The following registers and bits should not be changed by software while the BUSY bit is set:

- SPIxTCNT
- SPIxTWIDTH
- SPIxCON2
- The CLB bit



#### Important:

- The BUSY bit is subject to synchronization delay of up to two instruction cycles. The user must wait
  for it to set after loading the transmit buffer (SPIxTXB register) before using it to determine the
  status of the SPI module.
- It is also not recommended to read SPIxTCNT while the BUSY bit is set, as the value in the
  registers may not be a reliable indicator of the transfer counter. Use the TCZIF bit to accurately
  determine that the transfer counter has reached zero.

#### 36.2.3 Transmit and Receive FIFOs

The transmission and reception of data from the SPI module is handled by two FIFOs, one for reception and one for transmission. These are addressed by the SFRs, SPIxRXB and SPIxTXB, respectively.

The transmit FIFO is written to by software and is read by the SPI module to shift the data onto the SDO pin. The receive FIFO is written to by the SPI module as it shifts in the data from the SDI pin and is read by software. Setting the CLB bit resets the occupancy for both FIFOs, emptying both buffers. The FIFOs are also reset by clearing the EN bit, thus disabling the SPI module.



**Important:** The transmit and receive FIFO occupancy refer to the number of bytes that are currently being stored in each FIFO. These values are used in this chapter to illustrate the function of these FIFOs and are not directly accessible through software.

The SPIxRXB register addresses the receive FIFO and is read-only. Reading from this register will read from the first FIFO location that was written to by hardware and decrease the receive FIFO occupancy. If the FIFO is empty, reading from this register will instead return a value of zero and set the RXRE (Receive Buffer Read Error) bit. The RXRE bit must then be cleared in software in order to properly reflect the status of the read error. When the receive FIFO is full, the RXBF bit will be set.

The SPIxTXB register addresses the transmit FIFO and is write-only. Writing to the register will write to the first empty FIFO location and increase the occupancy. If the FIFO is full, writing to this register will not affect the data and will set the TXWE bit. When the transmit FIFO is empty, the TXBE bit will be set.

More details on enabling and disabling the receive and transmit functions is summarized in Table 36-1 and Slave Mode Transmit Options.

# 36.2.4 LSb vs. MSb-First Operation

Typically, the SPI communication outputs the Most Significant bit first, but some devices or buses may not conform to this standard. In this case, the LSBF bit may be used to alter the order in which bits are shifted out during the data exchange. In both Master and Slave mode, the LSBF bit controls whether data is shifted MSb or LSb first. Clearing the bit (default) configures the data to transfer MSb first, which conforms to traditional SPI operation, while setting the bit configures the data to transfer LSb first.

# 36.2.5 Input and Output Polarity Control

SPIxCON1 has three bits that control the polarity of the SPI inputs and outputs:

- · The SDIP bit controls the polarity of the SDI input
- · The SDOP bit controls the polarity of the SDO output
- · The SSP bit controls the polarity of both the slave SS input and the master SS output

For all three bits, when the bit is clear, the input or output is active-high, and when the bit is set, the input or output is active-low. When the EN bit is cleared, SS\_out and SCK\_out both revert to the Inactive state dictated by their polarity bits. The SDO output state, when the EN bit is cleared, is determined by several factors as follows:

- When the associated TRIS bit for the SDO pin is cleared, and the SPI goes idle after a transmission, the SDO output will remain at the last bit level.
- When the associated TRIS bit for the SDO pin is set, its behavior varies in Slave and Master mode:
  - In Slave mode, the SDO pin tri-states when any of the following are true:

- · Slave Select is inactive
- EN = 0
- TXR = 0
- In Master mode:
  - The SDO pin tri-states when TXR = 0
  - When TXR = 1 and the SPI goes idle after a transmission, the SDO output will remain at the last bit level. The SDO pin will revert to the Idle state when EN is cleared.

#### 36.2.6 Transfer Counter

In all Master modes, the transfer counter can be used to determine how many data transfers the SPI will send/receive. The transfer counter is comprised of the SPIxTCNT registers, and is also partially controlled by the SPIxTWIDTH register.

The transfer counter has two primary modes, determined by the BMODE bit. Each mode uses the SPIxTCNT and SPIxTWIDTH registers to determine the number and size of the transfers. In both modes, when the transfer counter reaches zero, the TCZIF interrupt flag is set.



#### Important:

In all Slave modes and when BMODE = 1 in Master modes, the transfer counter will still decrement as transfers occur and can be used to count the number of messages sent/received, control SS\_out, and trigger TCZIF. Also, when BMODE = 1, the SPIxTWIDTH register can be used in Master and Slave modes to determine the size of messages sent and received by the SPI, even if the transfer counter is not being actively used to control the number of messages being sent/received by the SPI module.

#### 36.2.6.1 Total Bit Count Mode (BMODE = 0)

In this mode, SPIxTCNT and SPIxTWIDTH are concatenated to determine the total number of bits to be transferred. These bits will be loaded from/into the transmit/receive FIFOs in 8-bit increments and the transfer counter will be decremented by eight until the total number of remaining bits is less than eight. If there are any remaining bits (SPIxTWIDTH  $\neq 0$ ), the transmit FIFO will send out one final message with any extra bits greater than the remainder ignored.

The SPIxTWIDTH is the remaining bit count but the value does not change as it does for the SPIxTCNT value. The receiver will load a final byte into the receiver FIFO, and pad the extra bits with zeros. The LSBF bit determines whether the Most Significant or Least Significant bits of this final byte are ignored or padded. For example, when LSBF = 0 and the final transfer contains only two bits, then if the last byte sent was 0x5F, the RXB of the receiver will contain 0x40 which are the two MSbs of the final byte padded with zeros in the LSbs.

In this mode, the SPI master will only transmit messages when the SPIxTCNT value is greater than zero, regardless of the TXR and RXR settings.

In Master Transmit mode, the transfer starts with the data write to the SPIxTXB register or the count value written to the SPIxTCNTL register, whichever occurs last.

In Master Receive Only mode, the transfer clocks start when the SPIxTCNTL value is written. Transfer clocks are suspended when the receive FIFO is full and resume as the FIFO is read.

#### 36.2.6.2 Variable Transfer Size Mode (BMODE = 1)

In this mode, SPIxTWIDTH specifies the width of every individual piece of the data transfer in bits. SPIxTCNT specifies the number of transfers of this bit length. If SPIxTWIDTH = 0, each piece is a full byte of data. If SPIxTWIDTH  $\neq 0$ , then only that specified number of bits from the transmit FIFO are shifted out, with the unused bits ignored.

Received data is padded with zeros in the unused bit areas when transferred into the receive FIFO. The LSBF bit determines whether the Most Significant or Least Significant bits of the transfers are ignored or padded.

In this mode, the transfer counter being zero only stops messages from being sent or received when in Receive Only mode.



#### Important:

With BMODE = 1, it is possible for the transfer counter (SPIxTCNT) to decrement below zero, although when in 'Receive Only' Master mode, transfer clocks will cease when the transfer counter reaches zero.

#### 36.2.6.3 Transfer Counter in Slave Mode

In Slave mode, the transfer counter will still decrement as data is shifted in and out of the SPI module, but it will not control data transfers. The BMODE bit along with the transfer counter is used to determine when the device should look for Slave Select faults.

When BMODE = 0, the SSFLT bit will be set if Slave Select transitions from its Active to Inactive state during bytes of data, or if it transitions before the last bit sent during the final byte (if SPIxTWIDTH  $\neq$  0).

When BMODE = 1, the SSFLT bit will be set if Slave Select transitions from its Active to Inactive state before the final bit of each individual transfer is completed.

**Note:** SSFLT does not have an associated interrupt, so it should be checked in software. An ideal time to do this is when the End of Slave Select Interrupt (EOSIF) is triggered (see Start of Slave Select and End of Slave Select Interrupts).

#### 36.3 Master Mode

In Master mode, the device controls the SCK line, and as such, initiates data transfers and determines when any slaves broadcast data onto the SPI bus.

Master mode can be configured in four different modes, configured by the TXR and RXR bits:

- · Full-Duplex mode
- · Receive Only mode
- · Transmit Only mode
- · Transfer Off mode

The modes are illustrated in the following table:

Table 36-1. Master Mode TXR/RXR Settings

	TXR = 1	<b>TXR</b> = 0
RXR = 1	Full Duplex mode  BMODE = 1: Transfer when RxFIFO is not full and TxFIFO is not empty  BMODE = 0: Transfer when RXFIFO is not full, TXFIFO is not empty, and the Transfer Counter is non-zero	Receive Only mode Transfer when RxFIFO is not full and the Transfer Counter is non-zero Transmitted data is either the top of the FIFO or the most recently received data
<b>RXR</b> = 0	Transmit Only mode  BMODE = 1: Transfer when TxFIFO is not empty  BMODE = 0: Transfer when TXFIFO is not empty and the  Transfer Counter is non-zero  Received data is not stored	No Transfers


#### 36.3.1 Full-Duplex Mode

When both TXR and RXR are set, the SPI master is in Full-Duplex mode. In this mode, data transfer triggering is affected by the BMODE bit.

When BMODE = 1, data transfers will occur whenever both the receive FIFO is not full and there is data present in the transmit FIFO. In practice, as long as the receive FIFO is not full, data will be transmitted/received as soon as the SPIxTXB register is written to, matching the functionality of SPI (MSSP) modules on older 8-bit Microchip devices. The SPIxTCNT will decrement with each transfer. However, when SPIxTCNT is zero the next transfer is not inhibited

and the corresponding SPIxTCNT decrement will cause the count to roll over to the maximum value. The following figure shows an example of a communication using this mode.

Figure 36-3. SPI Master Operation - Data Exchange RXR = 1, TXR = 1



Note: 1. SS(out) is not shown on this diagram

- SPIXTCNT write is optional when TXR/RXR = 1/1 and BMODE=1. If BMODE=0, a write to SPIXTCNT is required to start transmission; TCZIF signals the transition of SPIXTCNT from 1 to 0
- 3. Transmission gap occurs while waiting for transmitter data.

When BMODE = 0, the transfer counter (SPIxTCNT) must also be written to before transfers will occur. Transfers will cease when the transfer counter reaches '0'. For example, if SPIxTXB is written twice and then SPIxTCNTL is written with '3' then the transfer will start with the SPIxTCNTL write. The two bytes in the TXFIFO will be sent after which the transfer will suspend until the third and last byte is written to SPIxTXB.

#### 36.3.2 Transmit Only Mode

When TXR is set and RXR is clear, the SPI master is in Transmit Only mode. In this mode, data transfer triggering is affected by the BMODE bit.

When BMODE = 1, data transfers will occur whenever the transmit FIFO is not empty. Data will be transmitted as soon as the SPIxTXB register is written to, matching the functionality of the SPI (MSSP) modules on previous 8-bit devices. The SPIxTCNT will decrement with each transfer. However, when SPIxTCNT is zero the next transfer is not inhibited and the corresponding SPIxTCNT decrement will cause the count to roll over to the maximum value. Any data received in this mode is not stored in the receive FIFO. The following figure shows an example of sending a command and then sending a byte of data, using this mode.




Figure 36-4. SPI Master Operation - Command+Write Data TXR = 1, RXR = 0

Note: 1. SS out is not shown

- 2. The byte counter is optional when TXR/RXR = 1/0;
- 3. After the command bytes, wait for SRMTIF before loading SPIxTXB otherwise the command data would decrement SPIxTXCNT. Alternatively, load SPIxTXCNT= 5 and count the command bytes also; TCZIF signals the end of the transmission.
- 4. Transmit data interrupt handler (or DMA) must write only the bytes necessary; the byte counter is not available as an indicator.
- 5. Reading the SPIxRXB is not required because RXR = 0.

When BMODE = 0, the transfer counter (SPIxTCNT) must also be written to before transfers will occur, and transfers will cease when the transfer counter reaches '0'.

For example, if SPIxTXB is written twice and then SPIxTCNTL is written with '3', the transfer will start with the SPIxTCNTL write. The two bytes in the TXFIFO will be sent after which the transfer will suspend until the third and last byte is written to SPIxTXB.

#### 36.3.3 Receive Only Mode

When RXR is set and TXR is clear, the SPI master is in Receive Only mode. In this mode, data transfers when the receive FIFO is not full and the transfer counter is non-zero. In this mode, writing a value to SPIxTCNTL will start the clocks for transfer. The clocks will suspend while the receive FIFO is full and cease when the SPIxTCNT reaches zero (see Transfer Counter). If there is any data in the transmit FIFO, the first data written to SPIxTXB will be transmitted on each data exchange, although the transmit FIFO occupancy will not change, meaning that the same message will be sent on each transmission. If there is no data in the transmit FIFO, the most recently received data will be transmitted. The following figure shows an example of sending a command using the Transmit Only mode and then receiving a byte of data using the Receive Only mode.



**Important:** When operating in Receive only mode and the size of every SPI transaction is less than 8 bits, it is recommended to operate in BMODE = 1 mode. The size of the packet can be configured using the SPIxTWIDTH register.




Figure 36-5. SPI Master Operation, Command+Read Data, TXR = 0, RXR = 1

This is not considered an imposition in this case, because the slave probably needs time to load output data

#### 36.3.4 **Transfer Off Mode**

When both TXR and RXR are cleared, the SPI master is in Transfer Off mode. In this mode, SCK will not toggle and no data is exchanged. However, writes to SPIxTXB will be transferred to the transmit FIFO which will then be transmitted when the TXR bit is set.


#### 36.3.5 **Master Mode Slave Select Control**

#### 36.3.5.1 **Hardware Slave Select Control**

The SPI module allows for direct hardware control of a Slave Select output. The Slave Select output (SS out) is controlled both directly, through the SSET bit, and indirectly by the hardware while the transfer counter is non-zero (see Transfer Counter). The SS out pin is selected with the PPS controls. The SS out polarity is controlled by the

Setting the SSET bit will assert SS\_out. Clearing the SSET bit will leave SS\_out to be controlled by the transfer counter. When the transfer counter is loaded, the SPI module will automatically assert SS\_out. When the transfer counter decrements to zero, the SPI module will deassert SS out either one baud period after the final SCK pulse of the final transfer (when CKE/SMP = 0/1) or one half baud period otherwise, as shown in the following figure.

Figure 36-6. SPI Master SS Operation - CKE = 0, BMODE = 1, TWIDTH = 0, SSP= 0



Note: 1. SDO bit number illustrates the transmitted bit number, and is not intended to imply SDO\_out tristate operation.

2. Assumes SPIxTXB holds data when SPIxTCNTL is written.

#### 36.3.5.2 Software Slave Select Control

Slave Select can be controlled through software via a general purpose I/O pin. In this case, ensure that the desired pin is configured as a general purpose output with the PPS and TRIS controls. In this case, SSET will not affect the Slave Select, the Transfer Counter will not automatically control the Slave Select output, and all setting and clearing of the Slave Select output line must be directly controlled by software.

#### 36.3.6 Master Mode SPI Clock Configuration

#### 36.3.6.1 SPI Clock Selection

The clock source for SPI Master modes is selected by the SPIxCLK register.

The SPIxBAUD register allows for dividing this clock. The frequency of the SCK output is defined by the following equation:

#### **Equation 36-1. SCK Output Frequency**

$$F_{BAUD} = \frac{F_{CSEL}}{2 \times (BAUD + 1)}$$

where  $F_{BAUD}$  is the baud rate frequency output on the SCK pin,  $F_{CSEL}$  is the frequency of the input clock selected by the SPIxCLK register, and BAUD is the value contained in the SPIxBAUD register.

### 36.3.6.2 Clock and Data Change Alignment

The CKP, CKE, and SMP bits control the relationship between the SCK clock output, SDO output data changes, and SDI input data sampling. The bit functions are as follows:

- · CKP controls SCK output polarity
- · CKE controls SDO output change relative to the SCK clock
- · SMP controls SDI input sampling relative to the clock edges

The CKE bit, when set, inverts the low Idle state of the SCK output to a high Idle state.

The following figures illustrate the eight possible combinations of the CKP, CKE, and SMP bit selections.



**Important:** All timing diagrams assume the LSBF bit is cleared.

Figure 36-7. Clocking Detail - Master Mode, CKE = 0, SMP = 0





Figure 36-8. Clocking Detail - Master Mode, CKE = 1, SMP = 1









Figure 36-10. Clocking Detail - Master Mode, CKE = 1, SMP = 0



#### 36.3.6.3 SCK Start-up Delay

When starting an SPI data exchange, the master device asserts the SS output, by either setting the SSET bit or loading the TCNT value, and then triggers the module to send data by writing SPIxTXB. These data triggers are synchronized to the clock selected by the SPIxCLK register before the first SCK pulse appears, usually requiring one or two clock periods of the selected SPI source clock.

The SPI module includes additional synchronization delays on SCK generation specifically designed to ensure that the Slave Select output timing is correct, without requiring precision software timing loops. By default this synchronization delay is ½ baud period.

When the value of the SPIxBAUD register is a small number (indicating higher SCK frequencies), the code execution delay between asserting SS and writing SPIxTXB is relatively long compared to the added synchronization delay before the first SCK edge. With larger values of SPIxBAUD (indicating lower SCK frequencies), the code execution delay is much smaller relative to the synchronization delay. Therefore, the first SCK edge after SS is asserted will be closer to the synchronization delay.

Setting the FST bit removes the synchronization delay, allowing systems with low SPIxBAUD values (and thus, long synchronization delays) to forgo this extra delay in which case the time between the SS assertion and the first SCK edge depends entirely on the code execution delay.

# 36.4 Slave Mode

# 36.4.1 Slave Mode Transmit Options

The SDO output of the SPI module in Slave mode is controlled by the following:

- TXR bit
- · TRIS bit associated with the SDO pin
- · Slave Select input
- · Current state of the transmit FIFO

This control is summarized in the following table where TRISxn refers to the bit in the TRIS register corresponding to the pin that SDO has been assigned with PPS, TXR is the Transmit Data Required Control bit, SS is the state of the Slave Select input, and TXBE is the transmit FIFO Buffer Empty bit.

Table 36-2. Slave Mode Transmit

TRISxn <sup>(1)</sup>	TXR	SS	TXBE	SDO State
0	0	FALSE	0	Drives state determined by LATxn <sup>(2)</sup>
0	0	FALSE	1	Drives state determined by LATxn <sup>(2)</sup>
0	0	TRUE	0	Outputs the oldest byte in the transmit FIFO Does not remove data from the transmit FIFO
0	0	TRUE	1	Outputs the most recently received byte
0	1	FALSE	0	Drives state determined by LATxn <sup>(2)</sup>
0	1	FALSE	1	Drives state determined by LATxn <sup>(2)</sup>
0	1	TRUE	0	Outputs the oldest byte in the transmit FIFO Removes transmitted byte from the transmit FIFO Decrements occupancy of transmit FIFO
0	1	TRUE	1	Outputs the most recently received byte Sets the TXUIF bit
1	0	FALSE	0	Tri-stated
1	0	FALSE	1	Tri-stated
1	0	TRUE	0	Tri-stated
1	0	TRUE	1	Tri-stated
1	1	FALSE	0	Tri-stated
1	1	FALSE	1	Tri-stated
1	1	TRUE	0	Outputs the oldest byte in the transmit FIFO Removes transmitted byte from the transmit FIFO Decrements the FIFO occupancy
1	1	TRUE	1	Outputs the most recently received byte Sets the TXUIF bit

#### Notes:

- 1. TRISxn is the bit in the TRISx register corresponding to the pin to which SDO has been assigned with PPS.
- 2. LATxn is the bit in the LATx register corresponding to the pin to which SDO has been assigned with PPS.

#### 36.4.1.1 SDO Drive/Tri-state

The TRIS bit associated with the SDO pin controls whether the SDO pin will tri-state. When this TRIS bit is cleared, the pin will always be driving to a level, even when the SPI module is inactive. When the SPI module is inactive

(either due to the master not clocking the SCK line or the SS being false), the SDO pin will be driven to the value of the LAT bit associated with the SDO pin. When the SPI module is active, its output is determined by both TXR and whether there is data in the transmit FIFO.

When the TRIS bit associated with the SDO pin is set, the pin will only have an output level driven to it when TXR = 1 and the Slave Select input is true. In all other cases, the pin will be tri-stated.

Table 36-3. Slave Mode Transmit

TRISxn <sup>(1)</sup>	TXR	SS	TXBE	SDO State
0	0	FALSE	0	Output level determined by LATxn <sup>(2)</sup>
0	0	FALSE	1	Output level determined by LATxn <sup>(2)</sup>
0	0	TRUE	0	Outputs the oldest byte in the TXFIFO Does not remove data from the TXFIFO
0	0	TRUE	1	Outputs the most recently received byte
0	1	FALSE	0	Output level determined by LATxn <sup>(2)</sup>
0	1	FALSE	1	Output level determined by LATxn <sup>(2)</sup>
0	1	TRUE	0	Outputs the oldest byte in the TXFIFO Removes transmitted byte from the TXFIFO Decrements occupancy of TXFIFO
0	1	TRUE	1	Outputs the most recently received byte Sets the TXUIF bit
1	0	FALSE	0	Tri-stated
1	0	FALSE	1	Tri-stated
1	0	TRUE	0	Tri-stated
1	0	TRUE	1	Tri-stated
1	1	FALSE	0	Tri-stated
1	1	FALSE	1	Tri-stated
1	1	TRUE	0	Outputs the oldest byte in the TXFIFO Removes transmitted byte from the TXFIFO Decrements occupancy of TXFIFO
1	1	TRUE	1	Outputs the most recently received byte Sets the TXUIF bit

#### Notes:

- 1. TRISxn is the bit in the TRISx register corresponding to the pin that SDO has been assigned with PPS.
- 2. LATxn is the bit in the LATx register corresponding to the pin that SDO has been assigned with PPS.

#### 36.4.1.2 SDO Output Data

The TXR bit controls the nature of the data that is transmitted in Slave mode. When TXR is set, transmitted data is taken from the transmit FIFO. If the FIFO is empty, the most recently received data will be transmitted and the TXUIF flag will be set to indicate that a transmit FIFO underflow has occurred.

When TXR is cleared, the data will be taken from the transmit FIFO, and the FIFO occupancy will not decrease. If the transmit FIFO is empty, the most recently received data will be transmitted, and the TXUIF bit will not be set. However, if the TRIS bit associated with the SDO pin is set, clearing the TXR bit will cause the SPI module to not output any data to the SDO pin.

#### 36.4.2 Slave Mode Receive Options

The RXR bit controls the nature of receptions in Slave mode. When RXR is set, the SDI input data will be stored in the receive FIFO if it is not full. If the receive FIFO is full, the RXOIF bit will be set to indicate a receive FIFO overflow error and the data is discarded. When RXR is cleared, all received data will be ignored and not stored in the receive FIFO (although it may still be used for transmission if the transmit FIFO is empty). The following figure shows a typical Slave mode communication, showing a case where the master writes two then three bytes, showing interrupts as well as the behavior of the transfer counter in Slave mode (see Transfer Counter in Slave Mode for more details on the transfer counter in Slave mode as well as SPI Interrupts for more information on interrupts).

SS in SCK in Output data SOSIF Transfer Counter Software Write to SPIXTCNTL **TCZIF** Software Write TXR Software Write to RXR Receiver process SPIxRIF Software

Figure 36-11. SPI Slave Mode Operation - Interrupt-Driven, Master Writes 2+3 Bytes

Note: 1. This delay is exaggerated for illustration, and can be as short as 1/2 bit period.

- 2. If the device is sleeping, SOSIF will wake it up for interrupt service.
- 3. Setting SPIxTCNTL is optional in this example, otherwise it will count -3, -4, -5, and TCZIF will not occur

#### 36.4.3 Slave Mode Slave Select

Read from SPIxRXB

In Slave mode, an external Slave Select signal can be used to synchronize communication with the master device. The Slave Select line is held in its Inactive state (high by default) until the master device is ready to communicate. When the Slave Select transitions to its Active state, the slave knows that a new transmission is starting.

When the Slave Select goes false at the end of the transmission, the receive function of the selected SPI slave device returns to the Inactive state. The slave is then ready to receive a new transmission when the Slave Select goes true again.

The Slave Select signal is received on the SS input pin. This pin is selected with the SPIxSSPPS register (refer to the "PPS Inputs" section). When the input on this pin is true, transmission and reception are enabled, and the SDO pin is driven. When the input on this pin is false, the SDO pin is either tri-stated (if the TRIS bit associated with the SDO pin is set) or driven to the value of the LAT bit associated with the SDO pin (if the TRIS bit associated with the SDO pin is cleared). The SCK input is ignored when the SS input is false.

If the SS input goes false, while a data transfer is still in progress, it is considered a Slave Select fault. The SSFLT bit indicates whether such an event has occurred. The transfer counter value determines the number of bits in a valid data transfer (see Transfer Counter for more details).

The Slave Select polarity is controlled by the SSP bit. When SSP is set (its default state), the Slave Select input is active-low, and when it is cleared, the Slave Select input is active-high.

The Slave Select for the SPI module is controlled by the SSET bit. When SSET is cleared (its default state), the Slave Select will act as described above. When the bit is set, the SPI module will behave as if the SS input is always in its Active state.



#### Important:

When SSET is set, the effective SS\_in signal is always active. Hence, the SSFLT bit may be disregarded.

#### 36.4.4 Slave Mode Clock Configuration


In Slave mode, SCK is an input, and must be configured to the same polarity and clock edge as the master device. As in Master mode, the polarity of the clock input is controlled by the CKP bit and the clock edge used for transmitting data is controlled by the CKE bit.

#### 36.4.5 Daisy-Chain Configuration

The SPI bus can be connected in a daisy-chain configuration. The first slave output is connected to the second slave input, the second slave output is connected to the third slave input, and so on. The final slave output is connected to the master input. Each slave sends out, during a second group of clock pulses, an exact copy of what was received during the first group of clock pulses. The whole chain acts as one large communication shift register. The daisy-chain feature only requires a single Slave Select line from the master device connected to all slave devices (alternately, the slave devices can be configured to ignore the Slave Select line by setting the SSET bit). In a typical daisy-chain configuration, the SCK signal from the master is connected to each of the slave device SCK inputs. However, the SCK input and output are separate signals selected by the PPS control. When the PPS selection is made to configure the SCK input and SCK output on separate pins then, the SCK output will follow the SCK input, allowing for SCK signals to be daisy-chained like the SDO/SDI signals.

The following two figures show block diagrams of a typical daisy-chain connection, and a daisy-chain connection with daisy-chained SPI clocks, respectively.

Figure 36-12. Traditional SPI Daisy-Chain Connection






Figure 36-13. SPI Daisy-Chain Connection With Chained SCK

# 36.5 SPI Operation In Sleep Mode

The SPI Master mode will operate in Sleep, provided the clock source selected by SPIxCLK is active in Sleep mode. FIFOs will operate as they would when the part is awake. When TXR = 1, the transmit FIFO will need to contain data in order for transfers to take place in Sleep. All interrupts will still set the interrupt flags in Sleep but only enabled interrupts will wake the device from Sleep.

The SPI Slave mode will operate in Sleep, because the clock is provided by an external master device. FIFOs will still operate and interrupts will set interrupt flags, and enabled interrupts will wake the device from Sleep.

# 36.6 SPI Interrupts

There are three top level SPI interrupts in the PIRx register:

- · SPI Transmit (SPIxTXIF)
- SPI Receive (SPIxRXIF)
- SPI Module status (SPIxIF)

The SPI Module status interrupts are enabled at the module level in the SPIxINTE register. Only enabled status interrupts will cause the single top level SPIxIF flag to be set.

# 36.6.1 SPI Receive Interrupt

The SPI receive interrupt is set when the receive FIFO contains data, and is cleared when the receive FIFO is empty. The interrupt flag, SPIxRXIF, is located in one of the PIR registers. The interrupt enable, SPIxRXIE, is located in the corresponding PIE register. The SPIxRXIF interrupt flag is read-only.

# 36.6.2 SPI Transmit Interrupt

The SPI Transmit interrupt is set when the transmit FIFO is not full and can accept a character, and is cleared when the transmit FIFO is full and cannot accept a character. The interrupt flag, SPIxTXIF, is located in one of the PIR registers. The interrupt enable, SPIxTXIE, is located in the corresponding PIE register. The SPIxTXIF interrupt flag is read-only.

# 36.6.3 SPI Status Interrupts

The SPIxIF flag is located in one of the PIR registers. This flag is set when any of the individual status flags in SPIxINTF and their respective SPIxINTE bits are set. In order for any specific interrupt flag to interrupt normal program flow both the SPIxIE bit, in the PIE register corresponding to the PIR register, and the specific bit in SPIxINTE associated with that interrupt must be set.


The Status Interrupts include the following:

- · Shift Register Empty (SRMTIF)
- Transfer Counter is Zero (TCZIF)
- · Start of Slave Select (SOSIF)
- End of Slave Select (EOSIF)
- Receiver Overflow (RXOIF)
- Transmitter Underflow (TXUIF)

#### 36.6.3.1 Shift Register Empty Interrupt

The Shift Register Empty interrupt flag and enable are the SRMTIF and SRMTIE bits respectively. This interrupt is only available in Master mode and triggers when a data transfer completes and conditions are not present to start a new transfer, as dictated by the TXR and RXR bits (see Table 36-1 for conditions for starting a new Master mode data transfer with different TXR/ RXR settings). This interrupt will be triggered at the end of the last full bit period, after SCK has been low for one ½-baud period. See the figure below for more details of the timing of this interrupt as well as other interrupts. This bit will not clear itself when the conditions for starting a new transfer occur, and must be cleared in software.

Figure 36-14. Transfer And Slave Select Interrupt Timing



Note

- 1: SRMTIF available only in Master mode
- 2: Clearing of interrupt flags is shown for illustration; actual interrupt flags must be cleared in software
- 3: SOSIF and EOSIF are set according to SS\_in, even in Master mode.

#### 36.6.3.2 Transfer Counter is Zero Interrupt

The Transfer Counter is Zero Interrupt flag and enable are the TCZIF and TCZIE bits, respectively. This interrupt will trigger when the transfer counter (defined by BMODE, SPIxTCNT and SPIxTWIDTH) decrements from one to zero. See Figure 36-14 for more details on the timing of this interrupt as well as other interrupts. This bit must be cleared in software.



#### Important:

The TCZIF flag only indicates that the transfer counter has decremented from one to zero, and may not indicate that the entire data transfer process is complete. Either poll the BUSY bit and wait for it to be cleared or use the Shift Register Empty Interrupt (SRMTIF) to determine when a data transfer is fully complete.

#### 36.6.3.3 Start of Slave Select and End of Slave Select Interrupts

The start of Slave Select Interrupt flag and enable are the SOSIF and SOSIE bits, respectively. The end of Slave Select Interrupt flag and enable are the EOSIF and EOSIE bits, respectively. These interrupts trigger at the leading and trailing edges of the Slave Select input.

The interrupts are active in both Master and Slave mode, and will trigger on transitions of the Slave Select input regardless of which mode the SPI is in. In Master mode, the PPS controls should be used to assign the Slave Select input to the same pin as the Slave Select output, allowing these interrupts to trigger on changes to the Slave Select output.

In Slave mode, changing the SSET bit can trigger these interrupts, as it changes the effective input value of Slave Select.

Both SOSIF and EOSIF must be cleared in software.

#### 36.6.3.4 Receiver Overflow and Transmitter Underflow Interrupts

The receiver overflow interrupt triggers if data is received when the receive FIFO is already full and RXR = 1. In this case, the data will be discarded and the RXOIF bit will be set. The Receiver Overflow Interrupt Enable bit is RXOIE.

The Transmitter Underflow Interrupt flag triggers if a data transfer begins when the transmit FIFO is empty and TXR = 1. In this case, the most recently received data will be transmitted and the TXUIF bit will be set. The Transmitter Underflow Interrupt Enable bit is TXUIE.

Both these interrupts will only occur in Slave mode, as Master mode will not allow the receive FIFO to overflow or the transmit FIFO to underflow.

# 36.7 Register Definitions: Serial Peripheral Interface

Long bit name prefixes for the SPI peripherals are shown in the table below where "x" refers to the SPI instance number. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 36-4. SPI Bit Name Prefixes

Peripheral	Bit Name Prefix
SPI1	SPI1
SPI2	SPI2

# 36.7.1 SPIxCON0

Name: SPIxCON0 Offset: 0x084,0x091

SPI Control Register 0

Bit	7	6	5	4	3	2	1	0
	EN					LSBF	MST	BMODE
Access	R/W					R/W	R/W	R/W
Reset	0					0	0	0

# Bit 7 - EN SPI Enable

Value	Description
1	SPI is enabled
0	SPI is disabled

# Bit 2 – LSBF LSb-First Data Exchange Select<sup>(1)</sup>

Value	Description
1	Data is exchanged LSb first
0	Data is exchanged MSb first (traditional SPI operation)

#### Bit 1 - MST SPI Master Operating Mode Select(1)

	1
Value	Description
1	SPI module operates as the bus master
0	SPI module operates as a bus slave

# Bit 0 - BMODE Bit-Length Mode Select<sup>(1)</sup>

Value	Description
1	SPIxTWIDTH setting applies to every byte: total bits sent is SPIxTWIDTH*SPIxTCNT, end-of-packet
	occurs when SPIxTCNT = 0
0	SPIxTWIDTH setting applies only to the last byte exchanged; total bits sent is SPIxTWIDTH +
	(SPIxTCNT*8)

#### Note:

1. Do not change this bit when EN = 1.

# 36.7.2 SPIxCON1

Name: SPIxCON1 Offset: 0x085,0x092

SPI Control Register 1

Bit	7	6	5	4	3	2	1	0
	SMP	CKE	CKP	FST		SSP	SDIP	SDOP
Access	R/W	R/W	R/W	R/W		R/W	R/W	R/W
Reset	0	0	0	0		1	0	0

# Bit 7 - SMP SPI Input Sample Phase Control

Value	Mode	Description
1	Slave	Reserved
1	Master	SDI input is sampled at the end of data output time
0	Slave or Master	SDI input is sampled in the middle of data output time

#### Bit 6 - CKE Clock Edge Select

Value	Description
1	Output data changes on transition from Active to Idle clock state
0	Output data changes on transition from Idle to Active clock state

#### Bit 5 - CKP Clock Polarity Select

	olosic claim, colosi
Value	Description
1	Idle state for SCK is high level
0	Idle state for SCK is low level

# Bit 4 - FST Fast Start Enable

Value	MODE	Description
X	Slave	This bit is ignored
1	Master	Delay to first SCK may be less than ½ baud period
0	Master	Delay to first SCK will be at least ½ baud period

#### Bit 2 - SSP Slave Select Input/Output Polarity Control

Dit 2 001	Clave Coloct Input Culput Folding Control
Value	Description
1	SS is active-low
0	SS is active-high

### Bit 1 - SDIP SPI Input Polarity Control

Value	Description
1	SDI input is active-low
0	SDI input is active-high

# Bit 0 - SDOP SPI Output Polarity Control

D.C 0 02	or output i dianty control		
Value	Description		
1	SDO output is active-low		
0	SDO output is active-high		

#### 36.7.3 SPIxCON2

Name: SPIxCON2
Offset: 0x086,0x093
SPI Control Register 2<sup>(3)</sup>

Bit	7	6	5	4	3	2	1	0
	BUSY	SSFLT				SSET	TXR	RXR
Access	R	R				R/W	R/W	R/W
Reset	0	0				0	0	0

# Bit 7 - BUSY SPI Module Busy Status(1)

Value	Description
1	Data exchange is busy
0	Data exchange is not taking place

#### Bit 6 - SSFLT SS in Fault Status

Value	Condition	Description
X	SSET = 1	This bit is unchanged
1	SSET = 0	SS_in ended the transaction unexpectedly, and the data byte being received was lost
0	SSET = 0	SS in ended normally

#### Bit 2 - SSET Slave Select Enable

Value	MODE	Description
1	Master	SS_out is driven to the Active state continuously
0	Master	SS_out is driven to the Active state while the transmit counter is not zero
1	Slave	SS_in is ignored and data is clocked on all SCK_in (as though SS = TRUE at all times)
0	Slave	SS_in enables/disables data input and tri-states SDO if the TRIS bit associated with the SDO
		pin is set (see Slave Mode Transmit table for details)

#### Bit 1 - TXR Transmit Data-Required Control(2)

	Transmit Bata Hoganica Control
Value	Description
1	TxFIFO data is required for a transfer
0	TxFIFO data is not required for a transfer

# Bit 0 - RXR Receive FIFO Space-Required Control(2)

Value	Description
1	Data transfers are suspended when the RxFIFO is full
0	Received data is not stored in the FIFO


### Notes:

- 1. The BUSY bit is subject to synchronization delay of up to two instruction cycles. The user must wait after loading the transmit buffer (SPIxTXB register) before using it to determine the status of the SPI module.
- See Master Mode TXR/RXR Settings table as well as section Master Mode and section Slave Mode for more details pertaining to TXR and RXR function.
- 3. This register should not be written to while a transfer is in progress (BUSY bit is set).

# 36.7.4 SPIxCLK

Name: SPIxCLK Offset: 0x08C,0x099

SPI Clock Selection Register



Bits 4:0 - CLKSEL[4:0] SPI Clock Source Selection

# Table 36-5. SPI CLK Source Selections

CLK	Selection
10111-11111	Reserved
10110	CLC8_OUT
10101	CLC7_OUT
10100	CLC6_OUT
10011	CLC5_OUT
10010	CLC4_OUT
10001	CLC3_OUT
10000	CLC2_OUT
01111	CLC1_OUT
01110	SMT1_OUT
01001-01111	Reserved
01110	TU16B_OUT
01101	TU16A_OUT
01000	TMR6_Postscaler_OUT
00111	TMR4_Postscaler_OUT
00110	TMR2_Postscaler_OUT
00101	TMR0_OUT
00100	Clock Reference Output
00011	EXTOSC
00010	MFINTOSC (500 kHz)
00001	HFINTOSC
00000	F <sub>OSC</sub> (System Clock)

# PIC18F26/46/56Q84

# **SPI - Serial Peripheral Interface Module**

# 36.7.5 SPIxBAUD

Name: SPIxBAUD Offset: 0x089,0x096

SPI Baud Rate Register

Bit	7	6	5	4	3	2	1	0
				BAUI	D[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - BAUD[7:0] Baud Clock Prescaler Select

Value	Description
n	SCK high or low time: TSC = SPI Clock Period*(n+1)
	SCK toggle frequency: FSCK = FBAUD = SPI Clock Frequency/(2*(n+1))

# **36.7.6 SPIXTCNT**

Name: SPIxTCNT Offset: 0x082,0x08F

SPI Transfer Counter Register

Bit	15	14	13	12	11	10	9	8
							TCNTH[2:0]	
Access						R/W	R/W	R/W
Reset						0	0	0
Bit	7	6	5	4	3	2	1	0
				TCN	ΓL[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 10:8 - TCNTH[2:0] SPI Transfer Counter Most Significant Byte

Value	Condition	Description
n	BMODE = 0	Bits 13-11 of the transfer bit count
n	BMODE = 1	Bits 10-8 of the transfer byte count

#### Bits 7:0 - TCNTLI7:01 SPI Transfer Counter Least Significant Byte

	TOTAL DE CETT TIGING	or Counter Loads digitimount Byto
Value	Condition	Description
n	BMODE = 0	Bits 10-3 of the transfer bit count
n	BMODF = 1	Bits 7-0 of the transfer byte count


# PIC18F26/46/56Q84

# **SPI - Serial Peripheral Interface Module**

# 36.7.7 SPIxTWIDTH

Name: SPIxTWIDTH Offset: 0x088,0x095

SPI Transfer Width Register



Bits 2:0 - TWIDTH[2:0] SPI Transfer Count Byte Width or 3 LSbs of the Transfer Bit Count

Value	Condition	Description
n	BMODE = 0	Bits 2-0 of the transfer bit count
n	BMODE = 1	Number of bits in each transfer byte count. Bits = $n$ (when $n > 0$ ) or 8 (when $n = 0$ ).

# 36.7.8 SPIxSTATUS

Name: SPIxSTATUS Offset: 0x087,0x094

SPI Status Register

Bit	7	6	5	4	3	2	1	0
	TXWE		TXBE		RXRE	CLB		RXBF
Access	R/C/HS		R		R/C/HS	S		R
Reset	0		1		0	0		0

# Bit 7 - TXWE Transmit Buffer Write Error

Value	Description
1	SPIxTXB was written while TxFIFO was full
0	No error has occurred

# Bit 5 - TXBE Transmit Buffer Empty

Value	Description
1	Transmit buffer TxFIFO is empty
0	Transmit buffer is not empty

# Bit 3 - RXRE Receive Buffer Read Error

Value	Description
1	SPIxRXB was read while RxFIFO was empty
0	No error has occurred

# Bit 2 - CLB Clear Buffer Control

Value	Description
1	Reset the receive and transmit buffers, making both buffers empty
0	Take no action

# Bit 0 - RXBF Receive Buffer Full

Value	Description
1	Receive buffer is full
0	Receive buffer is not full

# PIC18F26/46/56Q84

# **SPI - Serial Peripheral Interface Module**

# 36.7.9 SPIxRXB

Name: SPIxRXB Offset: 0x080,0x08D

SPI Receive Buffer

Bit	7	6	5	4	3	2	1	0
				RXE	3[7:0]			
Access	R	R	R	R	R	R	R	R
Reset	X	X	X	X	X	X	X	X

# Bits 7:0 - RXB[7:0] Receive Buffer

Value	Condition	Description
n	Receive buffer is not empty	Contains the top-most byte of the RXFIFO. Reading this register will remove the RXFIFO top-most byte and decrease the occupancy of the RXFIFO by 1.
0	Receive buffer is empty	Reading this register will return '0', leave the occupancy unchanged, and set the RXRE Status bit

# PIC18F26/46/56Q84

# **SPI - Serial Peripheral Interface Module**

# 36.7.10 SPIxTXB

Name: SPIxTXB Offset: 0x081,0x08E

SPI Transmit Buffer

Bit	7	6	5	4	3	2	1	0
				TXB	3[7:0]			
Access	W	W	W	W	W	W	W	W
Reset	X	X	X	X	X	X	X	X

# Bits 7:0 - TXB[7:0] Transmit Buffer

Value	Condition	Description
n	Transmit buffer is not	Writing to this register adds the data to the top of the TXFIFO and increases
	full	the occupancy of the TXFIFO by 1.
Х	Transmit buffer is full	Writing to this register does not affect the data in the TXFIFO or the
		occupancy count. The TXWE Status bit will be set.

# **36.7.11 SPIXINTE**

Name: SPIxINTE Offset: 0x08B,0x098

SPI Interrupt Enable Register

Bit	7	6	5	4	3	2	1	0
	SRMTIE	TCZIE	SOSIE	EOSIE		RXOIE	TXUIE	
Access	R/W	R/W	R/W	R/W		R/W	R/W	
Reset	0	0	0	0		0	0	

# Bit 7 - SRMTIE Shift Register Empty Interrupt Enable

1	Value	Description
	1	Interrupt is enabled
	0	Interrupt is not enabled

#### Bit 6 - TCZIE Transfer Counter is Zero Interrupt Enable

Va	lue	Description
1		Interrupt is enabled
0		Interrupt is not enabled

#### Bit 5 - SOSIE Start of Slave Select Interrupt Enable

Value	Description
1	Interrupt is enabled
0	Interrupt is not enabled

# Bit 4 - EOSIE End of Slave Select Interrupt Enable

Value	Description
1	Interrupt is enabled
0	Interrupt is not enabled

#### Bit 2 - RXOIE Receiver Overflow Interrupt Enable

Value	Description			
1	Interrupt is enabled			
0	Interrupt is not enabled			

# Bit 1 - TXUIE Transmitter Underflow Interrupt Enable

٧	alue	Description
1		Interrupt is enabled
0		Interrupt is not enabled

# **36.7.12 SPIXINTF**

Name: SPIxINTF Offset: 0x08A,0x097

SPI Interrupt Flag Register

Bit	7	6	5	4	3	2	1	0
	SRMTIF	TCZIF	SOSIF	EOSIF		RXOIF	TXUIF	
Access	R/W/HS	R/W/HS	R/W/HS	R/W/HS		R/W/HS	R/W/HS	
Reset	0	0	0	0		0	0	

Bit 7 - SRMTIF Shift Register Empty Interrupt Flag

Value	MODE	Description					
X	Slave	This bit is ignored					
1	Master	The data transfer is complete					
0	Master	Either no data transfers have occurred or a data transfer is in progress					

Bit 6 - TCZIF Transfer Counter is Zero Interrupt Flag

Value	Description
1	The transfer counter has decremented to zero
0	No interrupt pending

Bit 5 - SOSIF Start of Slave Select Interrupt Flag

Value	Description
1	SS_in transitioned from false to true
0	No interrupt pending

# Bit 4 - EOSIF End of Slave Select Interrupt Flag

Value	Description			
1	SS_in transitioned from true to false			
0	No interrupt pending			

# Bit 2 - RXOIF Receiver Overflow Interrupt Flag

Value	Description
1	Data transfer completed when RXBF = 1 (edge-triggered) and RXR = 1
0	No interrupt pending

# Bit 1 - TXUIF Transmitter Underflow Interrupt Flag

Value	Description			
1	Slave Data transfer started when TXBE = 1 and TXR = 1			
0	No interrupt pending			

# 36.8 Register Summary - SPI Control


Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x7F										
0x80	SPI1RXB	7:0					3[7:0]			
0x81	SPI1TXB	7:0					8[7:0]			
0x82	SPI1TCNT	7:0	TCNTL[7:0]							
UNUZ	OFFICE	15:8							TCNTH[2:0]	
0x84	SPI1CON0	7:0	EN					LSBF	MST	BMODE
0x85	SPI1CON1	7:0	SMP	CKE	CKP	FST		SSP	SDIP	SDOP
0x86	SPI1CON2	7:0	BUSY	SSFLT				SSET	TXR	RXR
0x87	SPI1STATUS	7:0	TXWE		TXBE		RXRE	CLB		RXBF
0x88	SPI1TWIDTH	7:0							TWIDTH[2:0]	-
0x89	SPI1BAUD	7:0	BAUD[7:0]							
0x8A	SPI1INTF	7:0	SRMTIF	TCZIF	SOSIF	EOSIF		RXOIF	TXUIF	
0x8B	SPI1INTE	7:0	SRMTIE	TCZIE	SOSIE	EOSIE		RXOIE	TXUIE	
0x8C	SPI1CLK	7:0						CLKSEL[4:0]		
0x8D	SPI2RXB	7:0	RXB[7:0]							
0x8E	SPI2TXB	7:0	TXB[7:0]							
0.05	ODIOTONIT	7:0	TCNTL[7:0]							
0x8F	SPI2TCNT	15:8							TCNTH[2:0]	
0x91	SPI2CON0	7:0	EN					LSBF	MST	BMODE
0x92	SPI2CON1	7:0	SMP	CKE	CKP	FST		SSP	SDIP	SDOP
0x93	SPI2CON2	7:0	BUSY	SSFLT				SSET	TXR	RXR
0x94	SPI2STATUS	7:0	TXWE		TXBE		RXRE	CLB		RXBF
0x95	SPI2TWIDTH	7:0							TWIDTH[2:0]	
0x96	SPI2BAUD	7:0				BAU	D[7:0]			
0x97	SPI2INTF	7:0	SRMTIF	TCZIF	SOSIF	EOSIF	-	RXOIF	TXUIF	
0x98	SPI2INTE	7:0	SRMTIE	TCZIE	SOSIE	EOSIE		RXOIE	TXUIE	
0x99	SPI2CLK	7:0						CLKSEL[4:0]		

# 37. I<sup>2</sup>C - Inter-Integrated Circuit Module

The Inter-Integrated Circuit (I<sup>2</sup>C) bus is a multi-master serial data communication bus. Devices communicate in a master/slave environment where the master devices initiate the communication. A slave device is controlled through addressing.

The following figure shows a block diagram of the I<sup>2</sup>C interface module, and shows both Master and Slave modes together.

Figure 37-1. I<sup>2</sup>C Block Diagram



# 37.1 I<sup>2</sup>C Features

The I<sup>2</sup>C supports the following modes and features:

- Modes
  - Master mode
  - Slave mode
  - Multi-Master mode
- Features
  - Supports Standard-mode (100 kHz), Fast-mode (400 kHz) and Fast-mode plus (1 MHz) modes of operation
  - Dedicated Address, Receive, and Transmit buffers
  - Up to four unique Slave addresses
  - General Call addressing
  - 7-bit and 10-bit addressing with optional masking
  - Interrupts for:

- Start condition
- · Restart condition
- Stop condition
- · Address match
- · Data Write
- · Acknowledge Status
- NACK detection
- · Data Byte Count
- · Bus Collision
- · Bus Time-out
- Clock Stretching for:
  - RX buffer full
  - · TX buffer empty
  - · Incoming address match
  - · Data Write
  - · Acknowledge Status
- Bus Collision Detection with Arbitration
- Bus Time-out Detection
  - · Selectable clock sources
  - Clock prescaler
- Selectable Serial Data (SDA) Hold Time
- Dedicated I<sup>2</sup>C Pad (I/O) Control
  - Standard GPIO or I<sup>2</sup>C-specific slew rate control
  - Selectable I<sup>2</sup>C pull-up levels
  - I<sup>2</sup>C-specific, SMBus 2.0/3.0, or standard GPIO input threshold level selections
- Integrated Direct Memory Access (DMA) support
- Remappable pin locations using Peripheral Pin Select (PPS)

# 37.2 I<sup>2</sup>C Terminology

The I<sup>2</sup>C communication protocol terminology used throughout this document have been adapted from the Phillips I<sup>2</sup>C Specification and can be found in the table below.

#### I<sup>2</sup>C Bus Terminology and Definitions

Term	Definition			
Master	The device that initiates a transfer, generates the clock signal and terminates a transfer			
Slave	The device addressed by the master			
Multi-Master	A bus containing more than one master device that can initiate communication			
Transmitter	The device that shifts data out onto the bus			
Receiver	The device that shifts data in from the bus			
Arbitration	Procedure that ensures only one master at a time controls the bus			
Synchronization	Procedure that synchronizes the clock signal between two or more devices on the bus			
Idle	The state in which no activity occurs on the bus and both bus lines are at a high logic level			
Active	The state in which one or more devices are communicating on the bus			
Matching Address	The address byte received by a slave that matches the value that is stored in the I2CxADR0/1/2/3 registers			

Addressed Slave	Slave device that has received a matching address and is actively being clocked by a master device
Write Request	Master transmits an address with the R/W bit clear indicating that it wishes to transmit data to a slave device
Read Request	Master transmits an address with the $R/\overline{W}$ bit set indicating that it wishes to receive data from a slave device
Clock Stretching	The action in which a device holds the SCL line low to stall communication
Bus Collision	Occurs when the module samples the SDA line and returns a low state while expecting a high state
Bus Time-out	Occurs whenever communication stalls for a period longer than acceptable

## 37.3 I<sup>2</sup>C Module Overview

The I<sup>2</sup>C module provides a synchronous serial interface between the microcontroller and other I<sup>2</sup>C-compatible devices using a bidirectional two-wire bus. Devices operate in a master/slave environment that may contain one or more master devices and one or more slave devices. The master device always initiates communication.

The I<sup>2</sup>C bus consists of two signal connections:

- Serial Clock (SCL)
- Serial Data (SDA)

Both the SCL and SDA connections are open-drain lines, each line requiring pull-up resistors to the application's supply voltage. Pulling the line to ground is considered a logic '0', while allowing the line to float is considered a logic '1'. It is important to note that the voltage levels of the logic low and logic high are not fixed and are dependent on the bus supply voltage. According to the I²C Specification, a logic low input level is up to 30% of  $V_{DD}$  ( $V_{IL} \le 0.3 V_{DD}$ ), while the logic high input level is 70% to 100% of  $V_{DD}$  ( $V_{IH} \ge 0.7 V_{DD}$ ). Both signal connections are considered bidirectional, although the SCL signal can only be an output in Master mode and an input in Slave mode.


All transactions on the bus are initiated and terminated by the master device. Depending on the direction of the data being transferred, there are four main operations performed by the  $I^2C$  module:

- Master Transmit: master is transmitting data to a slave
- · Master Receive: master is receiving data from a slave
- Slave Transmit: slave is transmitting data to a master
- · Slave Receive: slave is receiving data from a master

The  $I^2C$  interface allows for a multi-master bus, meaning that there can be several master devices present on the bus. A master can select a slave device by transmitting a unique address on the bus. When the address matches a slave's address, the slave responds with an Acknowledge condition ( $\overline{ACK}$ ), and communication between the master and that slave can commence. All other devices connected to the bus must ignore any transactions not intended for them.

The following figure shows a typical I<sup>2</sup>C bus configuration with one master and two slaves.

Figure 37-2. I<sup>2</sup>C Master-Slave Connections



## 37.3.1 Byte Format

As previously mentioned, all I<sup>2</sup>C communication is performed in 9-bit segments. The transmitting device sends a byte to a receiver, and once the byte is processed by the receiver, the receiver returns an Acknowledge bit. There are no limits to the amount of data bytes in a I<sup>2</sup>C transmission.

After the  $8^{th}$  falling edge of the SCL line, the transmitting device releases control of the SDA line to allow the receiver to respond with either an Acknowledge ( $\overline{ACK}$ ) sequence or a Not Acknowledge (NACK) sequence. At this point, if the receiving device is a slave, it can hold the SCL line low (clock stretch) to allow itself time to process the incoming byte. Once the byte has been processed, the receiving device releases the SCL line, allowing the master device to provide the  $9^{th}$  clock pulse, within which the slave responds with either an  $\overline{ACK}$  or a NACK sequence. If the receiving device is a master, it may also hold the SCL line low until it has processed the received byte. Once the byte has been processed, the master device will generate the  $9^{th}$  clock pulse and transmit the  $\overline{ACK}$  or NACK sequence.

Data is valid to change only while the SCL signal is in a low state, and sampled on the rising edge of SCL. Changes on the SDA line while the SCL line is high indicate either a Start or Stop condition.

#### 37.3.2 SDA and SCL Pins

The SDA and SCL pins must be configured as open-drain outputs. Open-drain configuration is accomplished by setting the appropriate bits in the Open-Drain Control (ODCONx) registers, while output direction configuration is handled by clearing the appropriate bits in the Tri-State Control (TRISx) registers. Input threshold, slew rate, and internal pull-up settings are configured using the Rxyl2C registers. The Rxyl2C registers are used exclusively on the default  $I^2$ C pin locations, and provide the following selections:

- · Input threshold levels:
  - SMBus 3.0 (1.35V) input threshold
  - SMBus 2.0 (2.1V) input threshold
  - I<sup>2</sup>C-specific input thresholds

- Standard GPIO input thresholds (controlled by the Input Level Control (INLVLx) registers)
- · Slew rate limiting:
  - I<sup>2</sup>C-specific slew rate limiting
  - Standard GPIO slew rate (controlled by the Slew Rate Control (SLRCONx) registers)
- I<sup>2</sup>C pull-ups:
  - Programmable ten or two times the current of the standard internal pull-up
  - Standard GPIO pull-up (controlled by the Weak Pull-Up Control (WPUx) registers)




**Important:** The pin locations for SDA and SCL are remappable through the Peripheral Pin Select (PPS) registers. If new pin locations for SDA and SCL are desired, user software must configure the INLVLx, SLRCONx, ODCONx, and TRISx registers for each new pin location. The Rxyl2C registers cannot be used since they are dedicated to the default pin locations. Additionally, the internal pull-ups for non-l<sup>2</sup>C pins are not strong enough to drive the pins; therefore, external pull-up resistors must be used.

#### 37.3.2.1 SDA Hold Time

SDA hold time refers to the amount of time between the low threshold region of the falling edge of SCL ( $V_{IL} \le 0.3 V_{DD}$ ) and either the low threshold region of the rising edge of SDA ( $V_{IL} \le 0.3 V_{DD}$ ) or the high threshold region of the falling edge of SDA ( $V_{IH} \ge 0.7 V_{DD}$ ) (see figure below). If the SCL fall time is long or close to the maximum allowable time set by the I<sup>2</sup>C Specification, data may be sampled in the undefined logic state between the 70% and 30% region of the falling SCL edge, leading to data corruption. The I<sup>2</sup>C module offers selectable SDA hold times, which can be useful to ensure valid data transfers at various bus data rates and capacitance loads.

Figure 37-3. SDA Hold Time



### 37.3.3 Start Condition

All I<sup>2</sup>C transmissions begin with a Start condition. The Start condition is used to synchronize the SCL signals between the master and slave devices. The I<sup>2</sup>C Specification defines a Start condition as a transition of the SDA line from a logic high level (Idle state) to a logic low level (Active state) while the SCL line is at a logic high (see figure below). A Start condition is always generated by the master, and is initiated by either writing to the Start (S) bit or by writing to the I<sup>2</sup>C Transmit Buffer (I2CxTXB) register, depending on the Address Buffer Disable (ABD) bit setting.


When the  $I^2C$  module is configured in Master mode, module hardware waits until the bus is free (Idle state). Module hardware checks the Bus Free Status (BFRE) bit to ensure the bus is idle before initiating a Start condition. When the BFRE bit is set, the bus is considered idle, and indicates that the SCL and SDA lines have been in a logic high state

for the amount of I<sup>2</sup>C clock cycles as selected by the Bus Free Time Selection (BFRET) bits. When a Start condition is detected on the bus, module hardware clears the BFRE bit, indicating an active bus.

In Multi-Master mode, it is possible for two master devices to issue Start conditions at the same time. If two or more masters initiate a Start at the same time, a bus collision will occur; however, the I<sup>2</sup>C Specification states that a bus collision cannot occur on a Start. In this case, the competing master devices must go through bus arbitration during the addressing phase.

The figure below shows a Start condition.

Figure 37-4. Start Condition



### 37.3.4 Acknowledge Sequence

The 9th SCL pulse for any transferred address/data byte is reserved for the Acknowledge ( $\overline{ACK}$ ) sequence. During an Acknowledge sequence, the transmitting device relinquishes control of the SDA line to the receiving device. At this time, the receiving device must decide whether to pull the SDA line low ( $\overline{ACK}$ ) or allow the line to float high (NACK). Since the Acknowledge sequence is an active-low signal, pulling the SDA line low informs the transmitter that the receiver has successfully received the transmitted data.

The Acknowledge Data (ACKDT) bit holds the value to be transmitted during an Acknowledge sequence while the I2CxCNT register is non-zero (I2CxCNT!= 0). When a slave device receives a matching address, or a receiver receives valid data, the ACKDT bit is cleared by user software to indicate an  $\overline{ACK}$ . If the slave does not receive a matching address, user software sets the ACKDT bit, indicating a NACK. In Slave or Multi-Master modes, if the Address Interrupt and Hold Enable (ADRIE) or Write Interrupt and Hold Enable (WRIE) bits are set, the clock is stretched after receiving a matching address or after the 8th falling edge of SCL when a data byte is received. This allows user software time to determine the  $\overline{ACK}/NACK$  response to send back to the transmitter.

The Acknowledge End of Count (ACKCNT) bit holds the value that will be transmitted once the I2CxCNT register reaches a zero value (I2CxCNT = 0). When the I2CxCNT register reaches a zero value, the ACKCNT bit can be cleared (ACKCNT = 0), indicating an  $\overline{ACK}$ , or ACKCNT can be set (ACKCNT = 1), indicating a NACK.



**Important:** The ACKCNT bit is only used when the I2CxCNT register is zero, otherwise the ACKDT bit is used for ACK/NACK sequences.

In Master Write or Slave Read modes, the Acknowledge Status (ACKSTAT) bit holds the result of the Acknowledge sequence transmitted by the receiving device. The ACKSTAT bit is cleared when the receiver sends an  $\overline{ACK}$ , and is set when the receiver does not Acknowledge (NACK).

The Acknowledge Time Status (ACKT) bit indicates whether or not the bus is in an Acknowledge sequence. The ACKT bit is set during an ACK/NACK sequence on the 8th falling edge of SCL, and is cleared on the 9th rising edge of SCL, indicating that the bus is not in an ACK/NACK sequence.

Certain conditions will cause a NACK sequence to be sent automatically. A NACK sequence is generated by module hardware when any of the following bits are set:

- Transmit Write Error Status (TXWE)
- Transmit Underflow Status (TXU)
- Receive Read Error Status (RXRE)
- Receive Overflow Status (RXO)



**Important:** Once a NACK is detected on the bus, all subsequent Acknowledge sequences will consist of a NACK until all error conditions are cleared.

The following figure shows  $\overline{ACK}$  and NACK sequences.

Figure 37-5. ACK/NACK Sequences



### 37.3.5 Restart Condition

A Restart condition is essentially the same as a Start condition – the SDA line transitions from an idle level to an active level while the SCL line is idle – but may be used in place of a Stop condition whenever the master device has completed its current transfer but wishes to keep control of the bus. A Restart condition has the same effect as a Start condition, resetting all slave logic and preparing it to receive an address.


A Restart condition is also used when the master wishes to use a combined data transfer format. A combined data transfer format is used when a master wishes to communicate with a specific register address or memory location. In a combined format, the master issues a Start condition, followed by the slave's address, followed by a data byte which represents the desired slave register or memory address. Once the slave address and data byte have been acknowledged by the slave, the master issues a Restart condition, followed by the slave address. If the master wishes to write data to the slave, the LSb of the slave address, the Read/not Write ( $R/\overline{W}$ ) bit, will be clear. If the master wishes to read data from the slave, the  $R/\overline{W}$  bit will be set. Once the slave has acknowledged the second address byte, the master issues a Restart condition, followed by the upper byte of the slave address with the  $R/\overline{W}$  bit set. Slave logic will then acknowledge the upper byte, and begin to transmit data to the master.



**Important:** In 10-bit Slave mode, a Restart is required for the master to read data out of the slave, regardless of which data transfer format is used – master read-only or combined. For example, if the master wishes to perform a bulk read, it will transmit the slave's 10-bit address with the  $R/\overline{W}$  bit clear.

The figure below shows a Restart condition.

Figure 37-6. Restart Condition




### 37.3.6 Stop Condition

All I<sup>2</sup>C transmissions end with a Stop condition. A Stop condition occurs when the SDA line transitions from a logic low (active) level to a logic high (idle) level while the SCL line is at a logic high level. A Stop condition is always generated by the master device, and is generated by module hardware when a Not Acknowledge (NACK) is detected on the bus, a bus time-out event occurs, or when the I<sup>2</sup>C Byte Count (I2CxCNT) register reaches a zero count. A Stop condition may also be generated through software by setting the Stop (P) bit.

The figure below shows a Stop condition.

Figure 37-7. Stop Condition



### 37.3.7 Bus Timeout

The SMBus protocol requires a bus watchdog to prevent a stalled device from holding the bus indefinitely. The I2C Bus Timeout Clock Source Selection (I2CxBTOC) register provides several clock sources that can be used as the timeout time base. The I2C Bus Timeout (I2CxBTO) register is used to determine the actual bus timeout time period, as well as how the module responds to a timeout.

The bus timeout hardware monitors for the following conditions:

- SCL = 0 (regardless of whether or not the bus is Active)
- SCL = 1 and SDA = 0 while the bus is Active

If either of these conditions are true, an internal timeout counter increments, and continues to increment as long as the condition stays true, or until the timeout period has expired. If these conditions change (e.g. SCL = 1), the internal timeout counter is reset by module hardware.

The Bus Timeout Clock Source Selection (BTOC) bits select the timeout clock source. If an oscillator is selected as the timeout clock source, such as the LFINTOSC, the timeout clock base period is approximately 1 ms. If a timer is selected as the timeout clock source, the timer can be configured to produce a variety of time periods.



**Remember:** The SMBus protocol dictates a 25 ms timeout for slave devices and a 35 ms timeout for master devices.

The Timeout Time Selection (TOTIME) bits and the Timeout Prescaler Extension Enable (TOBY32) bit are used to determine the timeout period. The value written into TOTIME multiplies the base timeout clock period. For example, if a value of '35' is written into the TOTIME bits, and the LFINTOSC is selected as the timeout clock source, the timeout period is approximately 35 ms (35 x 1 ms). If the TOBY32 bit is set (TOBY32 = 1), the timeout period determined by the TOTIME bits is multiplied by 32. If TOBY32 is clear (TOBY32 = 0), the timeout period determined by the TOTIME bits is used as the timeout period.

The examples below illustrate possible timeout configurations.

The Timeout Recovery Selection (TOREC) bit determines how the module will respond to a bus timeout. When a bus timeout occurs and TOREC is set (TOREC = 1), the I2C module is reset and module hardware sets the Bus Timeout Interrupt Flag (BTOIF). If the Bus Timeout Interrupt Enable (BTOIE) is also set, an interrupt will be generated. If a bus timeout occurs and TOREC is clear (TOREC = 0), the BTOIF bit is set, but the module is not reset.

If the module is configured in Slave mode with TOREC set (TOREC = 1), and a bus timeout event occurs (regardless of the state of the Slave Mode Active (SMA) bit), the module is immediately reset, the SMA and Slave Clock Stretching (CSTR) bits are cleared, and the Bus Timeout Interrupt Flag (BTOIF) bit is set.

If the module is configured in Slave mode with TOREC clear (TOREC = 0), and a bus timeout event occurs (regardless of the state of the Slave Mode Active (SMA) bit), the BTOIF bit is set, but user software must reset the module.




**Important:** It is recommended to set TOREC (TOREC = 1) when operating in Slave mode.

If the module is configured in Master mode with TOREC set (TOREC = 1), and the bus timeout event occurs while the Master is active (Master Mode Active (MMA) = 1), the Master Data Ready (MDR) bit is cleared, the module will immediately attempt to transmit a Stop condition, and sets the BTOIF bit. Stop condition generation may be delayed if a slave device is stretching the clock, but will resume once the clock is released, or if the slave holding the bus also has a timeout event occur. The MMA bit is only cleared after the Stop condition has been generated.

If the module is configured in Master mode with TOREC clear (TOREC = 0), and the bus timeout event occurs while the Master is active (Master Mode Active (MMA) = 1), the MDR bit is cleared and the BTOIF bit is set, but user software must initiate the Stop condition by setting the P bit.

The figure below shows an example of a Bus Timeout event when the module is operating in Master mode.

Figure 37-8. Master Mode Bus Timeout Example



### 37.3.8 Address Buffers

The I<sup>2</sup>C module has two address buffer registers, I2CxADB0 and I2CxADB1, which can be used as address receive buffers in Slave mode, address transmit buffers in Master mode, or both address transmit and address receive buffers in 7-bit Multi-Master mode (see table below). The address buffers are enabled/disabled via the Address Buffer Disable (ABD) bit.

When the ABD bit is clear (ABD = 0), the buffers are enabled, which means:

- In 7-bit Master mode, the desired slave address with the R/W value is transmitted from the I2CxADB1 register, bypassing the I2C Transmit Buffer (I2CxTXB). I2CxADB0 is unused.
- In 10-bit Master mode, I2CxADB1 holds the upper bits and R/W value of the desired slave address, while I2CxADB0 holds the lower eight bits of the desired slave address. Master hardware copies the contents of I2CxADB1 to the transmit shift register, and waits for an ACK from the slave. Once the ACK is received, master hardware copies the contents of I2CxADB0 to the transmit shift register.
- In 7-bit Slave mode, a matching received address is loaded into I2CxADB0, bypassing the I2C Receive Buffer (I2CxRXB). I2CxADB1 is unused.
- In 10-bit Slave mode, I2CxADB0 is loaded with the lower eight bits of the matching received address, while I2CxADB1 is loaded with the upper bits and R/W value of the matching received address.
- In 7-bit Multi-Master mode, the device can be both a master and a slave depending on the sequence of events
  on the bus. When being addressed as a slave, the matching received address with R/W value is stored into
  I2CxADB0. When being used as a master, the desired slave address and R/W value are loaded into the
  I2CxADB1 register.

When the ABD bit is set (ABD = 1), the buffers are disabled, which means:

- In Master mode, the desired slave address is transmitted from the I2CxTXB register.
- In Slave mode, a matching received address is loaded into the I2CxRXB register.

#### Table 37-1. Address Buffer Direction

Mode	I2CxADB0	I2CxADB1	
Slave (7-bit)	RX	Unused	
Slave (10-bit)	RX (address low byte)	RX (address high byte)	
Master (7-bit)	Unused	TX	
Master (10-bit)	TX (address low byte)	TX (address high byte)	
Multi-Master (7-bit)	RX	TX	

#### 37.3.9 Transmit Buffer

The I<sup>2</sup>C module has a dedicated transmit buffer, I2CxTXB, which is independent from the receive buffer.

The transmit buffer is loaded with an address byte (when ABD = 1), or a data byte, that is copied into the transmit shift register and transmitted onto the bus. When the I2CxTXB register does not contain any transmit data, the Transmit Buffer Empty Status (TXBE) bit is set (TXBE = 1), allowing user software or the DMA to load a new byte into the buffer. When the TXBE bit is set and the I2CxCNT register is non-zero (I2CxCNT != 0), the I2C Transmit Interrupt Flag (I2CxTXIF) bit of the PIR registers is set, and can be used as a DMA trigger. A write to I2CxTXB will clear both the TXBE and I2CxTXIF bits. Setting the Clear Buffer (CLRBF) bit clears I2CxTXIF, the I2Cx Receive Buffer (I2CxRXB) and I2CxTXB.

If user software attempts to load I2CXTXB while it is full, the Transmit Write Error Status (TXWE) bit is set, a NACK is generated, and the new data is ignored. If TXWE is set, user software must clear the bit before attempting to load the buffer again.

When module hardware attempts to transfer the contents of I2CxTXB to the transmit shift register while I2CxTXB is empty (TXBE = 1), the Transmit Underflow Status (TXU) bit is set, I2CxTXB is loaded with 0xFF, and a NACK is generated.



**Important:** A transmit underflow can only occur when clock stretching is disabled (Clock Stretching Disable (CSD) bit = 1). Clock stretching prevents transmit underflows because the clock is stretched after the 8th falling SCL edge, and is only released upon the write of new data into I2CxTXB.

### 37.3.10 Receive Buffer

The I<sup>2</sup>C module has a dedicated receive buffer, I2CxRXB, which is independent from the transmit buffer.

Data received through the shift register is transferred to I2CxRXB when the byte is complete. User software or the DMA can access the byte by reading the I2CxRXB register. When new data is loaded into I2CxRXB, the Receive Buffer Full Status (RXBF) bit is set, allowing user software or the DMA to read the new data. When the RXBF bit is set, the I<sup>2</sup>C Receive Interrupt Flag (I2CxRXIF) bit of the PIR registers is set, and can be used to trigger the DMA. A read of the I2CxRXB register will clear both RXBF and I2CxRXIF bits. Setting the CLRBF bit clears the I2CxRXIF bit, I2CxRXB, and I2CxTXB.

If the buffer is read while empty (RXBF = 0), the Receive Read Error Status (RXRE) bit is set, and the module generates a NACK. User software must clear RXRE to resume normal operation.

When the module attempts to transfer the contents of the receive shift register to I2CxRXB while I2CxRXB is full (RXBF = 1), the Receive Overflow Status (RXO) bit is set, and a NACK is generated. The data currently stored in I2CxRXB remains unchanged, but the data in the receive shift register is lost.



**Important:** A receive overflow can only occur when clock stretching is disabled. Clock stretching prevents receive overflows because the receive shift register cannot receive any more data until user software or the DMA reads I2CxRXB and the SCL line is released.

## 37.3.11 Clock Stretching

Clock stretching occurs when a slave device holds the SCL line low to pause bus communication. A slave device may stretch the clock to allow more time to process incoming data, prepare a response for the master device, or to prevent receive overflow or transmit underflow conditions. Clock stretching is enabled by clearing the Clock Stretch Disable (CSD) bit, and is only available in Slave and Multi-Master modes.


When clock stretching is enabled (CSD = 0), the Slave Clock Stretching (CSTR) bit can be used to determine if the clock is currently being stretched. While the slave is actively stretching the clock, CSTR is set by hardware (CSTR = 1). Once the slave has completed its current transaction and clock stretching is no longer required, either module hardware or user software must clear CSTR to release the clock and resume communication.

### 37.3.11.1 Clock Stretching for Buffer Operations

When enabled (CSD = 0), clock stretching is forced during buffer read/write operations. This allows the slave device time to either load I2CxTXB with transmit data, or read data from I2CxRXB to clear the buffer.


In Slave Receive mode, clock stretching prevents receive data overflows. When the first seven bits of a new byte are received into the receive shift register while I2CxRXB is full (RXBF = 1), slave hardware automatically stretches the clock and sets CSTR. When the slave has read the data in I2CxRXB, slave hardware automatically clears CSTR to release the SCL line and continue communication (see figure below).

Figure 37-9. Receive Buffer Clock Stretching



In Slave Transmit mode, clock stretching prevents transmit underflows. When I2CxTXB is empty (TXBE = 1) and the I2CxCNT register is non-zero (I2CxCNT != 0), slave hardware stretches the clock and sets CSTR upon the 8th falling SCL edge. Once the slave has loaded new data into I2CxTXB, slave hardware automatically clears CSTR to release the SCL line and allow further communication (see figure below).

Figure 37-10. Transmit Buffer Clock Stretching



### 37.3.11.2 Clock Stretching for Other Slave Operations

The I<sup>2</sup>C module provides three Interrupt and Hold Enable features:

- · Address Interrupt and Hold Enable
- · Data Write Interrupt and Hold Enable
- Acknowledge Status Time Interrupt and Hold Enable

When clock stretching is enabled (CSD = 0), the Interrupt and Hold Enable features provide an interrupt response, and stretches the clock to allow time for address recognition, data processing, or an ACK/NACK response.

The Address Interrupt and Hold Enable feature will generate an interrupt event and stretch the SCL line when a matching address is received. This feature is enabled by setting the Address Interrupt and Hold Enable (ADRIE) bit. When enabled (ADRIE = 1), the CSTR bit and the Address Interrupt Flag (ADRIF) bit are set by module hardware, and the SCL line is stretched following the 8th falling SCL edge of a received matching address. Once the slave has completed processing the address, software determines whether to send an  $\overline{ACK}$  or a NACK back to the master device. Slave software must clear both the ADRIF and CSTR bits to resume communication.



**Important:** In 10-bit Slave Addressing mode, clock stretching occurs only after the slave receives a matching low address byte, or a matching high address byte with the R/ $\overline{W}$  bit = 1 (Master read) while the Slave Mode Active (SMA) bit is set (SMA = 1). Clock stretching does not occur after the slave receives a matching high address byte with the R/ $\overline{W}$  bit = 0 (Master write).

The Data Write Interrupt and Hold Enable feature provides an interrupt event and stretches the SCL signal after the slave receives a data byte. This feature is enabled by setting the Data Write Interrupt and Hold Enable (WRIE) bit. When enabled (WRIE = 1), module hardware sets both the CSTR bit and the Data Write Interrupt Flag (WRIF) bit and stretches the SCL line after the 8th falling edge of SCL. Once the slave has read the new data, software determines whether to send an  $\overline{ACK}$  or a NACK back to the master device. Slave software must clear both the CSTR and WRIF bits to resume communication.

The Acknowledge Status Time Interrupt and Hold Enable feature generates an interrupt event and stretches the SCL line after the acknowledgement phase of a transaction. This feature is enabled by setting the Acknowledge Status Time Interrupt and Hold Enable (ACKTIE) bit. When enabled (ACKTIE = 1), module hardware sets the CSTR bit and the Acknowledge Status Time Interrupt Flag (ACKTIF) bit and stretches the clock after the 9th falling edge of SCL for

all address, read, or write operations. Slave software must clear both the ACKTIF and CSTR bits to resume communication.

## 37.3.12 Data Byte Count

The data byte count refers to the number of data bytes in a complete I<sup>2</sup>C packet. The data byte count does not include address bytes. The I2C Byte Count (I2CxCNT) register is used to specify the length, in bytes, of the complete transaction. The value loaded into I2CxCNT will be decremented by module hardware each time a data byte is transmitted or received by the module.



**Important:** The I2CxCNT register will not decrement past a zero value.

When a byte transfer causes the I2CxCNT register to decrement to '0', the Byte Count Interrupt Flag (CNTIF) bit is set, and if the Byte Count Interrupt Enable (CNTIE) is set, the general purpose I2C Interrupt Flag (I2CxIF) bit of the Peripheral Interrupt Registers (PIR) is also set. If the I2C Interrupt Enable (I2CxIE) bit of the Peripheral Interrupt Enable (PIE) registers is set, module hardware will generate an interrupt event.



**Important:** The I2CxIF bit is read-only and can only be cleared by clearing all the interrupt flag bits of the I2CxPIR register.

The I2CxCNT register can be read at any time, but it is recommended that a double read is performed to ensure a valid count value.

The I2CxCNT register can be written to; however, care is required to prevent register corruption. If the I2CxCNT register is written to during the 8th falling SCL edge of a reception, or during the 9th falling SCL edge of a transmission, the register value may be corrupted. In Slave mode, I2CxCNT can be safely written to any time the clock is not being stretched (CSTR = 0), or after a Stop condition has been received (Stop Condition Interrupt Flag (PCIF) = 1). In Master mode, I2CxCNT can be safely written to any time the Master Data Ready (MDR) or Bus Free (BFRE) bits are set. If the I<sup>2</sup>C packet is longer than 65,536 bytes, the I2CxCNT register can be updated mid-message to prevent the count from reaching zero; however, the preventative measures listed above must be followed.

When in either Slave Read or Master Write mode and the I2CxCNT value is non-zero (I2CxCNT != 0), the value of the ACKDT bit is used as the acknowledgement response. When I2CxCNT reaches zero (I2CxCNT = 0), the value of the Acknowledge End of Count (ACKCNT) bit is used for the acknowledgement response.

In Master read or write operations, when the I2CxCNT register is clear (I2CxCNT = 0) and the Restart Enable (RSEN) bit is clear, master hardware automatically generates a Stop condition upon the 9th falling edge of SCL. When I2CxCNT is clear (I2CxCNT = 0) and RSEN is set (RSEN = 1), master hardware will stretch the clock while it waits for the Start (S) bit to be set (S = 1). When the Start bit has been set, module hardware transmits a Restart condition followed by the address of the slave it wishes to communicate with.

### 37.3.12.1 Auto-Load I2CxCNT

The I2CxCNT register can be automatically loaded. Auto-loading of the I2CxCNT register is enabled when the Auto-Load I2C Count Register Enable (ACNT) bit is set (ACNT = 1).

In master transmit mode, the first two bytes following either the 7-bit or 10-bit slave address are transferred from I2CxTXB into both I2CxCNT and the transmit shift register.



**Important:** When using the auto-load feature in any transmit mode (Slave, Master, Multi-Master), the first of the two bytes following the address is the I2CxCNT register's high byte, followed by the I2CxCNT register's low byte. If the order of these two bytes is switched, the value loaded into the I2CxCNT register will not be correct.

In master reception mode, the first two bytes received from the slave are loaded into both I2CxCNT and I2CxRXB. The value of the Acknowledge Data (ACKDT) bit is used as the master's acknowledgement response to prevent a false NACK from being generated before the I2CxCNT register is updated with the new count value.

In slave reception mode, the first two bytes received after a receiving a matching 7-bit or 10-bit address are loaded into both I2CxCNT and I2CxRXB, and the value of the ACKDT bit is used as the slave's acknowledgement response.

In slave transmit mode, the first two bytes loaded into I2CxTXB following the reception of a matching 7-bit or 10-bit address are transferred into both I2CxCNT and the transmit shift register.



**Important:** It is not necessary to preload the I2CxCNT register when using the auto-load feature. If no value is loaded by the 9th falling SCL edge following an address transmission or reception, the Byte Count Interrupt Flag (CNTIF) will be set by module hardware, and must be cleared by software to prevent an interrupt event before I2CxCNT is updated. Alternatively, I2CxCNT can be preloaded with a non-zero value to prevent the CNTIF from being set. In this case, the preloaded value will be overwritten once the new count value has been loaded into I2CxCNT.

## 37.3.13 DMA Integration

The I<sup>2</sup>C module can be used with the DMA for data transfers. The DMA can be triggered through software via the DMA Transaction (DGO) bit, or through the use of the following hardware triggers:

- I<sup>2</sup>C Transmit Interrupt Flag (I2CxTXIF)
- I<sup>2</sup>C Receive Interrupt Flag (I2CxRXIF)
- I<sup>2</sup>C Interrupt Flag (I2CxIF)
- I<sup>2</sup>C Error Interrupt Flag (I2CxEIF)

For I<sup>2</sup>C communication, the I2CxTXIF is commonly used as the hardware trigger source for master or slave transmission, and I2CxRXIF is commonly used as the hardware trigger source for master or slave reception.

### 37.3.13.1 7-Bit Master Transmission

When address buffers are enabled (ABD = 0), I2CxADB1 is loaded with the slave address, and I2CxCNT is loaded with a count value. At this point, I2CxTXB does not contain data, and the Transmit Buffer Empty (TXBE) bit is set (TXBE= 1). The I2CxTXIF bit is not set since it can only be set when the Master Mode Active (MMA) and TXBE bits are set. Once software sets the Start (S) bit, the MMA bit is set, and hardware transmits the slave address. Upon the 8th falling SCL edge, since TXBE = 1, the Master Data Request (MDR) and I2CxTXIF bits are set, and hardware stretches the clock while the DMA loads I2CxTXB with data. Once the DMA loads I2CxTXB, the TXBE, MDR, and I2CxTXIF bits are cleared by hardware, and the DMA waits for the next occurrence of I2CxTXIF being set.

When address buffers are disabled (ABD = 1), software must load I2CxTXB with the slave address to begin transmission. This is because I2CxTXIF can only be set when MMA = 1, and since a Start has not occurred, MMA = 0. Once the address has been transmitted, I2CxTXIF will be set, triggering the DMA to load I2CxTXB with data.

### 37.3.13.2 10-Bit Master Transmission

When address buffers are enabled (ABD = 0), I2CxADB1 is loaded with the slave high address, I2CxADB0 is loaded with the slave low address, and I2CxCNT is loaded with a count value. Once software sets the Start (S) bit, the MMA bit is set, and hardware transmits the 10-bit slave address. Upon the 8th falling SCL edge of the transmitted address low byte, since TXBE = 1, the MDR and I2CxTXIF bits are set, and hardware stretches the clock while the DMA loads I2CxTXB with data. Once the DMA loads I2CxTXB, the TXBE, MDR, and I2CxTXIF bits are cleared by hardware, and the DMA waits for the next occurrence of I2CxTXIF being set.

When address buffers are disabled (ABD = 1), software must load I2CxTXB with the slave high address to begin transmission. Once the slave high address has been transmitted, I2CxTXIF will be set, triggering the DMA to load I2CxTXB with slave low address. Once the DMA loads I2CxTXB with the slave low address, the TXBE, MDR, and I2CxTXIF bits are cleared by hardware, and the DMA waits for the next occurrence of I2CxTXIF being set.

## 37.3.13.3 7/10-Bit Master Reception

In both 7-bit and 10-bit master receive modes, the state of the ABD bit is ignored. Once the complete 7-bit or 10-bit address has been received by the slave, the slave will transmit a data byte. Once the byte has been received by the

master, hardware sets the I2CxRXIF bit, which triggers the DMA to read I2CxRXB. Once the DMA has read I2CxRXB, I2CxRXIF is cleared by hardware and the DMA waits for the next occurrence of I2CxRXIF being set.

## 37.3.13.4 7-Bit Slave Transmission

In 7-bit slave transmission mode, the state of ABD is ignored. If the slave receives the matching 7-bit address and TXBE is set, I2CxTXIF is set by hardware, triggering the DMA to load data into I2CxTXB. Once the data is transmitted from I2CxTXB, I2CxTXIF is set by hardware, triggering the DMA to once again load I2CxTXB with data. The DMA will continue to load data into I2CxTXB until I2CxCNT reaches a zero value. Once I2CxCNT reaches zero and the data is transmitted from I2CxTXB, I2CxTXIF will not be set, and the DMA will stop loading data.

#### 37.3.13.5 10-Bit Slave Transmission

In 10-bit slave transmission mode, the state of ABD is ignored. If there is no data in I2CxTXB after the slave has received the address high byte with the R/W bit set, hardware sets I2CxTXIF, triggering the DMA to load I2CxTXB. The DMA will continue to load data into I2CxTXB until I2CxCNT reaches a zero value. Once I2CxCNT reaches zero and the data is transmitted from I2CxTXB, I2CxTXIF will not be set, and the DMA will stop loading data.

## 37.3.13.6 7/10-Bit Slave Reception

When address buffers are enabled (ABD = 0), slave hardware loads I2CxADB0/1 with the matching address, while all data is received by I2CxRXB. Once the slave loads I2CxRXB with a received data byte, hardware sets I2CxRXIF, which triggers the DMA to read I2CxRXB. The DMA will continue to read I2CxRXB whenever I2CxRXIF is set.

When address buffers are disabled (ABD = 1), the slave loads I2CxRXB with the matching address byte(s) as they are received. Each received address byte sets I2CxRXIF, which triggers the DMA to read I2CxRXB. The DMA will continue to read I2CxRXB whenever I2CxRXIF is set.

#### 37.3.14 Interrupts

The I<sup>2</sup>C module offers several interrupt features designed to assist with communication functions. The interrupt hardware contains four high-level interrupts and several condition-specific interrupts.

#### 37.3.14.1 High-Level Interrupts

Module hardware provides four high-level interrupts:

- Transmit
- Receive
- General Purpose
- Error

These flag bits are read-only bits, and cannot be cleared by software.

The I2C Transmit Interrupt Flag (I2CxTXIF) bit is set when the I2CxCNT register is non-zero (I2CxCNT != 0), and the transmit buffer, I2CxTXB, is empty as indicated by the Transmit Buffer Empty Status (TXBE) bit (TXBE = 1). If the I2C Transmit Interrupt Enable (I2CxTXIE) bit is set, an interrupt event will occur when the I2CxTXIF bit becomes set. Writing new data to I2CxTXB, or setting the Clear Buffer (CLRBF) bit, will clear the interrupt condition. The I2CxTXIF bit is also used by the DMA as a trigger source.



**Important:** I2CxTXIF can only be set when either the Slave Mode Active (SMA) or Master Mode Active (MMA) bits are set, and the I2CxCNT register is non-zero (I2CxCNT != 0). The SMA bit is only set after an address has been successfully acknowledged by a slave device, which prevents false interrupts from being triggered on address reception. The MMA bit is set once the master completes the transmission of a Start condition.

The I2C Receive Interrupt Flag (I2CxRXIF) bit is set when the receive shift register has loaded new data into the receive buffer, I2CxRXB. When new data is loaded into I2CxRXB, the Receive Buffer Full Status (RXBF) bit is set (RXBF = 1), which also sets I2CxRXIF. If the I2C Receive Interrupt Enable (I2CxRXIE) bit is set, an interrupt event will occur when the I2CxRXIF bit becomes set. Reading data from I2CxRXB, or setting the CLRBF bit, will clear the interrupt condition. The I2CxRXIF bit is also used by the DMA as a trigger source.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 698

# **I2C - Inter-Integrated Circuit Module**



**Important:** I2CxRXIF can only be set when either the Slave Mode Active (SMA) or Master Mode Active (MMA) bits are set.

The I2C Interrupt Flag (I2CxIF) is the general purpose interrupt. I2CxIF is set whenever any of the interrupt flag bits contained in the I2C Peripheral Interrupt Register (I2CxPIR) and the associated interrupt enable bits contained in the I2C Peripheral Interrupt Enable Register (I2CxPIE) are set. If I2CxIF becomes set while the I2C Interrupt Enable (I2CxIE) bit is set, an interrupt event will occur. I2CxIF is cleared by module hardware when all enabled interrupt flag bits in I2CxPIR are clear.

The I2C Error Interrupt Flag (I2CxEIF) is set whenever any of the interrupt flag bits contained in the I2C Error Register (I2CxERR) and their associated interrupt enable bits are set. If I2CxEIF becomes set while the I2C Error Interrupt Enable (I2CxEIE) bit is set, an interrupt event will occur. I2CxEIF is cleared by hardware when all enabled error interrupt flag bits in the I2CxERR register are clear.

### 37.3.14.2 Condition-Specific Interrupts

In addition to the high-level interrupts, module hardware provides several condition-specific interrupts.

The I2C Peripheral Interrupt Register (I2CxPIR) contains the following interrupt flag bits:

- CNTIF: Byte Count Interrupt Flag
- ACKTIF: Acknowledge Status Time Interrupt Flag
- · WRIF: Data Write Interrupt Flag
- ADRIF: Address Interrupt Flag
- · PCIF: Stop Condition Interrupt Flag
- · RSCIF: Restart Condition Interrupt Flag
- SCIF: Start Condition Interrupt Flag

When any of the flag bits in I2CxPIR become set and the associated interrupt enable bits in I2CxPIE are set, the generic I2CxIF is also set. If the generic I2CxIE bit is set, an interrupt event is generated whenever one of the I2CxPIR flag bits becomes set. If the I2CxIE bit is clear, the I2CxPIR flag bit will still be set by hardware; however, no interrupt event will be triggered.

CNTIF becomes set (CNTIF = 1) when the I2CxCNT register value reaches zero, indicating that all data bytes in the  $I^2C$  packet have been transmitted or received. CNTIF is set after the 9th falling SCL edge when I2CxCNT reaches zero (I2CxCNT = 0).

ACKTIF is set (ACKTIF = 1) by the 9th falling edge of SCL for any byte when the device is addressed as a slave in any Slave or Multi-Master mode. If the Acknowledge Interrupt and Hold Enable (ACKTIE) bit is set and ACKTIF becomes set:

- If an ACK is detected, clock stretching is also enabled (CSTR = 1).
- If a NACK is detected, no clock stretching occurs (CSTR = 0).

WRIF is set (WRIF = 1) after the 8th falling edge of SCL when the module receives a data byte in Slave or Multi-Master modes. Once the data byte is received, WRIF is set, as is the Receive Buffer Full Status (RXBF) bit, the I2CxRXIF bit, and if the Data Write Interrupt and Hold Enable (WRIE) bit is set, the generic I2CxIF bit is also set. WRIF is a read/write bit and must be cleared in software, while the RXBF, I2CxRXIF, and I2CxIF bits are read-only and are cleared by reading I2CxRXB or by setting the Clear Buffer bit (CLRBF = 1).

ADRIF is set on the 8th falling edge of SCL after the module has received a matching 7-bit address, after receiving a matching 10-bit upper address byte, and after receiving a matching 10-bit lower address byte in Slave or Multi-Master modes. Upon receiving a matching 7-bit address or 10-bit upper address, the address is copied to I2CxADB0, the R/W bit setting is copied to the Read Information (R) bit, the Data (D) bit is cleared, and the ADRIF bit is set. If the Address Interrupt and Hold Enable (ADRIE) bit is set, I2CxIF is set, and the clock will be stretched while the module determines whether to ACK or NACK the transmitter. Upon receiving the matching 10-bit lower address, the address is copied to I2CxADB1, and the ADRIF bit is set. If ADRIE is also set, the clock is stretched while the module determines the ACK/NACK response to return to the transmitter.

PCIF is set whenever a Stop condition is detected on the bus.

# **I2C - Inter-Integrated Circuit Module**

RSCIF is set upon the detection of a Restart condition.

SCIF is set upon the detection of a Start condition.

In addition to the I2CxPIR register, the I2C Error (I2CxERR) register contains three interrupt flag bits that are used to detect bus errors. These read/write bits are set by module hardware, but must be cleared by user software. The I2CxERR register also includes the interrupt enable bits for these three error conditions, and when set, will cause an interrupt event whenever the associated interrupt flag bit becomes set.

I2CxERR contains the following interrupt flag bits:

BTOIF: Bus Time-out Interrupt Flag
 BCLIF: Bus Collision Interrupt Flag
 NACKIF: NACK Detect Interrupt Flag

BTOIF is set when a bus timeout occurs. The bus timeout period is configured using one of the timeout sources selected by the I2C Bus Timeout Clock Source Selection (I2CxBTOC) register.

If the module is configured in Slave mode with TOREC set (TOREC = 1), and a bus timeout event occurs (regardless of the state of the Slave Mode Active (SMA) bit), the module is immediately reset, the SMA and Slave Clock Stretching (CSTR) bits are cleared, and the BTOIF bit is set. If the Bus Timeout Interrupt Enable (BTOIE) bit is set, the generic I2C Error Interrupt Flag (I2CxEIF) bit is set.

If the module is configured in Slave mode with TOREC clear (TOREC = 0), and a bus timeout event occurs (regardless of the state of the Slave Mode Active (SMA) bit), the BTOIF bit is set, but user software must reset the module. If the Bus Timeout Interrupt Enable (BTOIE) bit is set, the generic I2C Error Interrupt Flag (I2CxEIF) bit is set

If the module is configured in Master mode with TOREC set (TOREC = 1), and the bus timeout event occurs while the Master is active (Master Mode Active (MMA) = 1), the Master Data Ready (MDR) bit is cleared, the module will immediately attempt to transmit a Stop condition, and sets the BTOIF bit. Stop condition generation may be delayed if a slave device is stretching the clock, but will resume once the clock is released, or if the slave holding the bus also has a timeout event occur. The MMA bit is only cleared after the Stop condition has been generated. If the Bus Timeout Interrupt Enable (BTOIE) bit is set, the generic I2C Error Interrupt Flag (I2CxEIF) bit is set.

If the module is configured in Master mode with TOREC clear (TOREC = 0), and the bus timeout event occurs while the Master is active (Master Mode Active (MMA) = 1), the MDR bit is cleared and the BTOIF bit is set, but user software must initiate the Stop condition by setting the P bit. If the Bus Timeout Interrupt Enable (BTOIE) bit is set, the generic I2C Error Interrupt Flag (I2CxEIF) bit is set.

BCLIF is set upon the detection of a bus collision. A bus collision occurs any time the SDA line is sampled at a logic low while the module expects both SCL and SDA lines to be at a high logic level. When a bus collision occurs, BCLIF is set, and if the Bus Collision Detect Interrupt Enable (BCLIE) bit is set, I2CxEIF is also set, and the module is reset.

NACKIF is set when either the master or slave is active (SMA = 1 | MMA = 1) and a NACK response is detected on the bus. A NACK response occurs during the 9th SCL pulse in which the SDA line is released to a logic high. In Master mode, a NACK can be issued when the master has finished receiving data from a slave, or when the master receives incorrect data. In Slave mode, a NACK is issued when the slave does not receive a matching address, or when it receives incorrect data. A NACK can also be automatically issued when any of the following bits become set, which will also set NACKIF and I2CxEIF:

- TXWE: Transmit Write Error Status
- RXRE: Receive Read Error Status
- TXU: Transmit Underflow Status
- RXO: Receive Overflow Status



**Important:** The I2CxEIF bit is read-only, and is only cleared by hardware after all enabled I2CxERR error flags have been cleared.

### 37.3.15 Operation in Sleep

The I<sup>2</sup>C module can operate while in Sleep mode.

In Slave mode, the module can transmit and receive data as long as the system clock source operates in Sleep. If the generic I2C Interrupt Enable (I2CxIE) bit is set and the slave receives or transmits a complete byte, I2CxIF is set and the device wakes up from Sleep.

In Master mode, both the system clock and the selected I2CxCLK source must be able to operate in Sleep. If the I2CxIE bit is set and the I2CxIF bit becomes set, the device wakes from Sleep.

# 37.4 I<sup>2</sup>C Operation

All I<sup>2</sup>C communication is performed in 9-bit segments consisting of an 8-bit address/data segment followed by a 1-bit acknowledgement segment. Address and data bytes are transmitted with the Most Significant bit (MSb) first. Interaction between the I<sup>2</sup>C module and other devices on the bus is controlled and monitored through several I<sup>2</sup>C Control, Status, and Interrupt registers.

To begin any  $I^2C$  communication, mater hardware checks to ensure that the bus is in an Idle state as indicated by the Bus Free Status (BFRE) bit. When BFRE = 1, both SDA and SCL lines are floating to a logic high and the bus is considered 'Idle'. When the master detects an Idle bus, it transmits a Start condition, followed by the address of the slave it intends to communicate with. The slave address can be either 7-bit or 10-bit, depending on the application design.

In 7-bit Addressing mode, the Least Significant bit (LSb) of the 7-bit slave address is reserved for the Read/not Write  $(R/\overline{W})$  bit, while in 10-bit Addressing mode, the LSb of the high address byte is reserved as the  $R/\overline{W}$  bit. If the  $R/\overline{W}$  bit is clear  $(R/\overline{W}=0)$ , the master intends to read information from the slave. If  $R/\overline{W}$  is set  $(R/\overline{W}=1)$ , the master intends to write information to the slave. If the addressed slave exists on the bus, it must respond with an Acknowledgement  $(\overline{ACK})$  sequence.

Once a slave has been successfully addressed, the master will continue to receive data from the slave, write data to the slave, or a combination of both. Data is always transmitted Most Significant bit (MSb) first. When the master has completed its transactions, it can either issue a Stop condition, signaling to the slave that communication is to be terminated, or a Restart condition, informing the bus that the current master wishes to hold the bus to communicate with the same or other slave devices.

### 37.4.1 I<sup>2</sup>C Slave Mode Operation

The I<sup>2</sup>C module provides four slave operation modes as selected by the I<sup>2</sup>C Mode Select (MODE) bits:

- I<sup>2</sup>C Slave mode with recognition of up to four 7-bit addresses
- I<sup>2</sup>C Slave mode with recognition of up to two masked 7-bit addresses
- I<sup>2</sup>C Slave mode with recognition of up to two 10-bit addresses
- I<sup>2</sup>C Slave mode with recognition of one masked 10-bit address

During operation, the slave device waits until module hardware detects a Start condition on the bus. Once the Start condition is detected, the slave waits for the incoming address information to be received by the receive shift register. The address is then compared to the addresses stored in the I2C Address 0/1/2/3 registers (I2CxADR0, I2CxADR1, I2CxADR2, I2CxADR3), and if an address match is detected, slave hardware transfers the matching address into either the I2CxADB0/I2CxADB1 registers or the I2CxRXB register, depending on the state of the Address Buffer Disable (ABD) bit. If there are no address matches, there is no response from the slave.

### 37.4.1.1 Slave Addressing Modes

The I2CxADR0, I2CxADR1, I2CxADR2, and I2CxADR3 registers contain the slave's addresses. The first byte (7-bit mode) or first and second bytes (10-bit mode) following a Start or Restart condition are compared to the values stored in the I2CxADR registers (see figure below). If an address match occurs, the valid address is transferred to the I2CxADB0/I2CxADB1 registers or I2CxRXB register, depending on the addressing mode and the state of the ABD bit.

Table 37-2. I<sup>2</sup>C Address Registers


Mode	I2CxADR0	I2CxADR1	I2CxADR2	I2CxADR3
7-bit	7-bit address	7-bit address	7-bit address	7-bit address

7-bit w/ masking	7-bit address	7-bit mask for I2CxADR0	7-bit address	7-bit mask for I2CxADR2
10-bit	Address low byte	Address high byte	Address low byte	Address high byte
10-bit w/ masking	Address low byte	Address high byte	Address low byte mask	Address high byte mask

In 7-bit Address mode, the received address byte is compared to all four I2CxADR registers independently to determine a match. The R/ $\overline{W}$  bit is ignored during address comparison. If a match occurs, the matching received address is transferred from the receive shift register to either the I2CxADB0 register (when ABD = 0) or to the I2CxRXB register (when ABD = 1), and the value of the R/ $\overline{W}$  bit is loaded into the Read Information (R) bit.

In 7-bit Address with Masking mode, I2CxADR0 holds one slave address and I2CxADR1 holds the mask value for I2CxADR0, while I2CxADR2 holds a second slave address and I2CxADR3 holds the mask value for I2CxADR2. A zero bit in a mask register means that the associated bit in the address register is a 'don't care', which means that the particular address bit is not used in the address comparison between the received address in the shift register and the address stored in either I2CxADR0 or I2CxADR2 (see figure below).

Figure 37-11. 7-Bit Address with Masking Example



In 10-bit Address mode, I2CxADR0 and I2CxADR1, and I2CxADR2 and I2CxADR3, are combined to create two 10-bit addresses. I2CxADR0 and I2CxADR2 hold the lower eight bits of the address, while I2CxADR1 and I2CxADR3 hold the upper two bits of the address, the R/W bit, and the five-digit '11110' code assigned to the five Most Significant bits of the high address byte.



**Important:** The '11110' code is specified by the I<sup>2</sup>C Specification, but is not supported by Microchip. It is up to the user to ensure the correct bit values are loaded into the address high byte. If a master device has included the five-digit code in the address it intends to transmit, the slave must also include those bits in slave address.

The upper received address byte is compared to the values in I2CxADR1 and I2CxADR3, and if a match occurs, the address is stored in either I2CxADB1 (when ABD = 0) or in I2CxRXB (when ABD = 1), and the value of the R/W bit is transferred into the R bit. The lower received address byte is compared to the values in I2CxADR0 and I2CxADR2, and if a match occurs, the address is stored in either I2CxADB0 (when ABD = 0) or in I2CxRXB (when ABD = 1).

In 10-bit Address with Masking mode, I2CxADR0 and I2CxADR1 are combined to form the 10-bit address, while I2CxADR2 and I2CxADR3 are combined to form the 10-bit mask. The upper received address byte is compared to the masked value in I2CxADR1, and if a match occurs, the address is stored in either I2CxADB1 (when ABD = 0) or in I2CxRXB (when ABD = 1), and the value of the  $R/\overline{W}$  bit is transferred into the R bit. The lower received address byte is compared to the value in I2CxADR0, and if a match occurs, the address is stored in either I2CxADB0 (when ABD = 0) or in I2CxRXB (when ABD = 1).

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 702

## 37.4.1.2 General Call Addressing Support


The I $^2$ C Specification reserves the address  $0 \times 00$  as the General Call address. The General Call address is used to address all slave modules connected to the bus at the same time. When a master issues a General Call, all slave devices should, in theory, respond with an  $\overline{ACK}$ . The General Call Enable (GCEN) bit determines whether slave hardware will respond to a General Call address. When GCEN is set (GCEN = 1), slave hardware will respond to a General Call with an  $\overline{ACK}$ , and when GCEN is clear (GCEN = 0), the General Call is ignored, and the slave responds with a NACK.

When the module receives a General Call, the ADRIF bit is set and the address is stored in I2CxADB0. If the ADRIE bit is set, the module will generate an interrupt and stretch the clock after the 8th falling edge of SCL. This allows the slave to determine the acknowledgement response to return to the master (see figure below).



**Important:** When using the General Call addressing feature, loading the I2CxADR0/1/2/3 registers with the  $0 \times 00$  address is not recommended. Additionally, slave hardware only supports General Call addressing in 7-bit Addressing modes.

Figure 37-12. General Call Addressing



### 37.4.1.3 Slave Operation in 7-Bit Addressing Modes

The upper seven bits of an address byte are used to determine a slave's address, while the LSb of the address byte is reserved as the Read/not Write  $(R/\overline{W})$  bit. When  $R/\overline{W}$  is set  $(R/\overline{W} = 1)$ , the master device intends to read data from the slave. When  $R/\overline{W}$  is clear  $(R/\overline{W} = 0)$ , the master device intends to write data to the slave. When an address match occurs, the  $R/\overline{W}$  bit is copied to the Read Information (R) bit, and the 7-bit address is copied to I2CxADB0.

#### 37.4.1.3.1 Slave Transmission (7-bit Addressing Mode)

The following section describes the sequence of events that occur when the module is transmitting data in 7-bit Addressing mode:

- The master device issues a Start condition. Once the Start condition has been detected, slave hardware sets
  the Start Condition Interrupt Flag (SCIF) bit. If the Start Condition Interrupt Enable (SCIE) bit is also set, the
  generic I2CxIF is also set.
- 2. Master hardware transmits the 7-bit slave address with the R/W bit set, indicating that it intends to read data from the slave.
- The received address is compared to the values in the I2CxADR registers. If the slave is configured in 7-bit Addressing mode (no masking), the received address is independently compared to each of the I2CxADR0/1/2/3 registers. In 7-bit Addressing with Masking mode, the received address is compared to the masked value of I2CxADR0 and I2CxADR2.
  - If an address match occurs:
    - The Slave Mode Active (SMA) bit is set by module hardware.
    - The R/W bit value is copied to the Read Information (R) bit by module hardware.
    - The Data (D) bit is cleared by hardware, indicating the last received byte was an address.

# **I2C - Inter-Integrated Circuit Module**

- The Address Interrupt Flag (ADRIF) bit is set. If the Address Interrupt and Hold Enable (ADRIE) bit is set, and the Clock Stretching Disable (CSD) bit is clear, hardware sets the Slave Clock Stretching (CSTR) bit and the generic I2CxIF bit. This allows time for the slave to read either I2CxADB0 or I2CxRXB and selectively ACK/NACK based on the received address. When the slave has finished processing the address, software must clear CSTR to resume operation.
- The matching received address is loaded into either the I2CxADB0 register or into the I2CxRXB register as determined by the Address Buffer Disable (ABD) bit. When ABD is clear (ABD = 0), the matching address is copied to I2CxADB0. When ABD is set (ABD = 1), the matching address is copied to I2CxRXB, which also sets the Receive Buffer Full Status (RXBF) bit and the I2C Receive Interrupt Flag (I2CxRXIF) bit. I2CxRXIF is a read-only bit, and must be cleared by either reading I2CxRXB or by setting the Clear Buffer (CLRBF) bit (CLRBF = 1).

If no address match occurs, the module remains idle.

- 4. If the Transmit Buffer Empty Status (TXBE) bit is set (TXBE = 1), I2CxCNT has a non-zero value (I2CxCNT!= 0), and the I2C Transmit Interrupt Flag (I2CxTXIF) is set (I2CxTXIF = 1), slave hardware sets CSTR, stretches the clock (when CSD = 0), and waits for software to load I2CxTXB with data. I2CxTXB must be loaded to clear I2CxTXIF. Once data is loaded into I2CxTXB, hardware automatically clears CSTR to resume communication.
- 5. The master device transmits the 9th clock pulse, and slave hardware transfers the value of the ACKDT bit onto the SDA line. If there are pending errors, such as a receive overflow (RXO = 1), slave hardware automatically generates a NACK condition. NACKIF is set, and the module goes idle.
- 6. Upon the 9th falling SCL edge, the data byte in I2CxTXB is transferred to the transmit shift register, and I2CxCNT is decremented by one. Additionally, the Acknowledge Status Time Interrupt Flag (ACKTIF) bit is set. If the Acknowledge Status Time Interrupt and Hold Enable (ACKTIE) bit is also set, the generic I2CxIF is set, and if slave hardware generated an ACK, the CSTR bit is also set and the clock is stretched (when CSD = 0). If a NACK was generated, the CSTR bit remains unchanged. Once complete, software must clear CSTR and ACKTIF to release the clock and continue operation.
- 7. If the slave generated an ACK and I2CxCNT is non-zero, master hardware transmits eight clock pulses, and slave hardware begins to shift the data byte out of the shift register starting with the Most Significant bit (MSb).
- 8. After the 8th falling edge of SCL, slave hardware checks the status of TXBE and I2CxCNT. If TXBE is set and I2CxCNT has a non-zero count value, hardware sets CSTR and the clock is stretched (when CSD = 0) until software loads I2CxTXB with new data. Once I2CxTXB has been loaded, hardware clears TXBE, I2CxTXIF, and CSTR to resume communication.
- 9. Once the master hardware clocks in all eight data bits, it transmits the 9th clock pulse along with the ACK/ NACK response back to the slave. Slave hardware copies the ACK/NACK value to the Acknowledge Status (ACKSTAT) bit and sets ACKTIF. If ACKTIE is also set, slave hardware sets the generic I2CxIF bit and CSTR, and stretches the clock (when CSD = 0). Software must clear CSTR to resume operation.
- 10. After the 9th falling edge of SCL, data currently loaded in I2CxTXB is transferred to the transmit shift register, setting both TXBE and I2CxTXIF. I2CxCNT is decremented by one. If I2CxCNT is zero (I2CxCNT = 0), CNTIF is set.
- 11. If I2CxCNT is non-zero and the master issued an  $\overline{ACK}$  on the last byte (ACKSTAT = 0), the master transmits eight clock pulses, and slave hardware begins to shift data out of the shift register.
- 12. Repeat steps 8 11 until the master has received all the requested data (I2CxCNT = 0). Once all data has been received, the master issues a NACK, followed by either a Stop or Restart condition. Once the NACK has been received by the slave, hardware sets NACKIF and clears SMA. If the NACK Detect Interrupt Enable (NACKIE) bit is also set, the generic I2C Error Interrupt Flag (I2CxEIF) is set. If the master issued a Stop condition, slave hardware sets the Stop Condition Interrupt Flag (PCIF). If the master issued a Restart condition, slave hardware sets the Restart Condition Interrupt Flag (RSCIF). If the associated interrupt enable bits are also set, the generic I2CxIF is also set.



**Important:** I2CxEIF is read-only, and is cleared by hardware when all enable interrupt flag bits in I2CxERR are cleared.

Figure 37-13. 7-Bit Slave Mode Transmission (No Clock Stretching)




Figure 37-14. 7-Bit Slave Mode Transmission (ADRIE = 1)







Figure 37-15. 7-Bit Slave Mode Transmission (ACKTIE = 1)



### 37.4.1.3.2 Slave Reception (7-Bit Addressing Mode)

The following section describes the sequence of events that occur when the module is receiving data in 7-bit Addressing mode:

- The master issues a Start condition. Once the Start is detected, slave hardware sets the Start Condition Interrupt Flag (SCIF) bit. If the Start Condition Interrupt Enable (SCIE) bit is also set, the generic I2CxIF bit is also set.
- 2. The master transmits the 7-bit slave address with the R/W bit clear, indicating that it intends to write data to the slave.
- 3. The received address is compared to the values in the I2CxADR registers. If the slave is configured in 7-bit Addressing mode (no masking), the received address is independently compared to each of the I2CxADR0/1/2/3 registers. In 7-bit Addressing with Masking mode, the received address is compared to the masked value of I2CxADR0 and I2CxADR2.
  If an address match occurs:
  - The Slave Mode Active (SMA) bit is set by module hardware.
  - The R/W bit value is copied to the Read Information (R) bit by module hardware.
  - The Data (D) bit is cleared (D = 0) by hardware, indicating the last received byte was an address.
  - The Address Interrupt Flag (ADRIF) bit is set (ADRIF = 1). If the Address Interrupt and Hold Enable (ADRIE) bit is set (ADRIE = 1), and the Clock Stretching Disable (CSD) bit is clear (CSD = 0), hardware sets the Slave Clock Stretching (CSTR) bit and the generic I2CxIF bit. This allows time for the slave to read either I2CxADB0 or I2CxRXB and selectively ACK/NACK based on the received address. When the slave has finished processing the address, software must clear CSTR to resume operation.
  - The matching received address is loaded into either the I2CxADB0 register or into the I2CxRXB register as determined by the Address Buffer Disable (ABD) bit. When ABD is clear (ABD = 0), the matching address is copied to I2CxADB0. When ABD is set (ABD = 1), the matching address is copied to I2CxRXB, which also sets the Receive Buffer Full Status (RXBF) bit and the I2C Receive Interrupt Flag (I2CxRXIF) bit. I2CxRXIF is a read-only bit, and must be cleared by either reading I2CxRXB or by setting the Clear Buffer (CLRBF) bit (CLRBF = 1).

If no address match occurs, the module remains idle.

- 4. The master device transmits the 9th clock pulse, and slave hardware transfers the value of the ACKDT bit onto the SDA line. If there are pending errors, such as a receive overflow (RXO = 1), slave hardware automatically generates a NACK condition. NACKIF is set, and the module goes idle.
- 5. Upon the 9th falling SCL edge, the Acknowledge Status Time Interrupt Flag (ACKTIF) bit is set. If the Acknowledge Interrupt and Hold Enable (ACKTIE) bit is also set, the generic I2CxIF is set, and if slave hardware generated an ACK, the CSTR bit is also set and the clock is stretched (when CSD = 0). If a NACK was generated, the CSTR bit remains unchanged. Once complete, software must clear CSTR and ACKTIF to release the clock and continue operation.
- 6. If slave hardware generated a NACK, master hardware generates a Stop condition, the Stop Condition Interrupt Flag (PCIF) bit is set when slave hardware detects the Stop condition, and the slave goes idle. If an ACK was generated, master hardware transmits the first seven bits of the 8-bit data byte.
- 7. If data remains in I2CxRXB (RXBF = 1 and I2CxRXIF = 1) when the first seven bits of the new byte are received by the shift register, CSTR is set, and if CSD is clear, the clock is stretched after the 7th falling edge of SCL. This allows time for the slave to read I2CxRXB, which clears RXBF and I2CxRXIF, and prevents a receive buffer overflow. Once RXBF and I2CxRXIF are cleared, hardware releases SCL.
- 8. Master hardware transmits the 8th bit of the current data byte into the slave receive shift register. Slave hardware then transfers the complete byte into I2CxRXB on the 8th falling edge of SCL, and sets the following bits:
  - I2CxRXIF
  - I2CxIF
  - Data Write Interrupt Flag (WRIF)
  - Data (D)
  - RXBF

I2CxCNT is decremented by one. If the Data Write Interrupt and Hold Enable (WRIE) is set (WRIE = 1), hardware sets CSTR (when CSD = 0) and stretches the clock, allowing time for slave software to read

# **I2C - Inter-Integrated Circuit Module**

- I2CxRXB and determine the state of the ACKDT bit that is transmitted back to the master. Once the slave determines the Acknowledgement response, software clears CSTR to allow further communication.
- 9. Master hardware transmits the 9th clock pulse. If there are pending errors, such as receive buffer overflow, slave hardware automatically generates a NACK condition, sets NACKIF, and the module goes idle. If I2CxCNT is non-zero (I2CxCNT!= 0), slave hardware transmits the value of ACKDT as the acknowledgement response to the master. It is up to software to configure ACKDT appropriately. In most cases, the ACKDT bit should be clear (ACKDT = 0) so that the master receives an ACK response (logic low level on SDA during the 9th clock pulse).
  - If I2CxCNT is zero (I2CxCNT = 0), slave hardware transmits the value of the Acknowledge End of Count (ACKCNT) bit as the Acknowledgement response, rather than the value of ACKDT. It is up to software to configure ACKCNT appropriately. In most cases, ACKCNT should be set (ACKCNT = 1), which represents a NACK condition. When master hardware detects a NACK on the bus, it will generate a Stop condition. If ACKCNT is clear (ACKCNT = 0), an ACK will be issued, and master hardware will not issue a Stop condition.
- 10. Upon the 9th falling edge of SCL, the ACKTIF bit is set. If ACKTIE is also set, the generic I2CxIF is set, and if CSD is clear, slave hardware sets CSTR and stretches the clock. This allows time for software to read I2CxRXB. Once complete, software must clear both CSTR and ACKTIF to release the clock and continue communication.
- 11. Repeat steps 6 -10 until the master has transmitted all the data (I2CxCNT = 0), or until the master issues a Stop or Restart condition.

Figure 37-16. 7-Bit Slave Mode Reception (No Clock Stretching)





Figure 37-17. 7-Bit Slave Mode Reception (ADRIE = 1)



PIC18F26/46/56Q84

Figure 37-18. 7-Bit Slave Mode Reception (ACKTIE = 1)





Figure 37-19. 7-Bit Slave Mode Reception (WRIE = 1)




## 37.4.1.4 Slave Operation in 10-Bit Addressing Modes

In 10-bit Addressing modes, the first two bytes following a Start condition form the 10-bit address (see figure below). The first byte (address high byte) holds the upper two address bits, the  $R/\overline{W}$  bit, and a five digit code (11110) as defined by the  $I^2C$  Specification. The second byte (address low byte) holds the lower eight address bits. In all 10-bit Addressing modes, the  $R/\overline{W}$  value contained in the first byte must always be zero ( $R/\overline{W} = 0$ ). If the master intends to read data from the slave, it must issue a Restart condition, followed by the address high byte with  $R/\overline{W}$  set ( $R/\overline{W} = 1$ ).

The first byte is compared to the values in the I2CxADR1 and I2CxADR3 registers in 10-bit Addressing mode, or to the masked value of I2CxADR1 in 10-bit Addressing with Masking mode. The second byte is compared to the values in the I2CxADR0 and I2CxADR2 registers in 10-bit Addressing mode, or to the masked value of I2CxADR0 in 10-bit Addressing with Masking mode. If an address high byte match occurs, the high address byte is copied to I2CxADB1 and the I2CxADB1 and the I2CxADB1 bit value is copied to the Read Information (R) bit, and if an address low byte match occurs, the low address byte is copied to I2CxADB0.

Figure 37-20. Upper and Lower 10-Bit Address Bytes



#### 37.4.1.4.1 Slave Transmission (10-Bit Addressing Mode)

The following section describes the sequence of events that occur when the module is transmitting data in 10-bit Addressing mode:

- The master device issues a Start condition. Once the Start condition has been detected, slave hardware sets
  the Start Condition Interrupt Flag (SCIF) bit. If the Start Condition Interrupt Enable (SCIE) bit is also set, the
  generic I2CxIF is also set.
- 2. Master hardware transmits the 10-bit high address byte with the  $R/\overline{W}$  bit clear ( $R/\overline{W} = 0$ ).
- Slave hardware compares the received address to the values in the I2CxADR registers. If the slave is
  configured in 10-bit Addressing mode (no masking), the received high address byte is compared to the values
  in I2CxADR1 and I2CxADR3. In 10-bit Addressing with Masking mode, the received high address byte is
  compared to the masked value of I2CxADR1.

If an address match occurs:

- The R/W value is copied to the Read Information (R) bit by module hardware.
- The Data (D) bit is cleared by hardware.
- The Address Interrupt Flag (ADRIF) bit is set (ADRIF = 1).
- The matching address is loaded into either the I2CxADB1 register or into the I2CxRXB register as determined by the Address Buffer Disable (ABD) bit. When ABD is clear (ABD = 0), the matching address is copied to I2CxADB1. When ABD is set (ABD = 1), the matching address is copied to I2CxRXB, which also sets the Receive Buffer Full Status (RXBF) bit and the I2C Receive Interrupt Flag (I2CxRXIF) bit.



**Important:** Regardless of whether the Address Interrupt and Hold Enable (ADRIE) bit is set, clock stretching does not occur when the  $R/\overline{W}$  bit is clear in 10-bit Addressing modes.

If no address match occurs, the module remains idle.

- 4. The master device transmits the 9th clock pulse, and slave hardware transfers the value of the ACKDT bit onto the SDA line. If there are pending errors, such as a receive buffer overflow (RXO = 1), slave hardware generates a NACK and the module goes idle.
- The master device transmits the low address byte. If the slave is configured in 10-bit Addressing mode (no masking), the received low address byte is compared to the values in I2CxADR0 and I2CxADR2. In 10-bit Addressing with Masking mode, the received low address byte is compared to the masked value of I2CxADR0.

If a match occurs:

- The Slave Mode Active (SMA) bit is set by module hardware.
- ADRIF is set. If ADRIE is set, and the Clock Stretching Disable (CSD) bit is clear, hardware sets the
  Slave Clock Stretching (CSTR) bit and the generic I2CxIF bit. This allows time for the slave to read either
  I2CxADB0 or I2CxRXB and selectively ACK/NACK based on the received address. When the slave has
  finished processing the address, software must clear CSTR to resume operation.
- The matching received address is loaded into either the I2CxADB0 register or into the I2CxRXB register as determined by the ABD bit. When ABD is clear (ABD = 0), the matching address is copied to I2CxADB0. When ABD is set (ABD = 1), the matching address is copied to I2CxRXB, which also sets RXBF and I2CxRXIF. I2CxRXIF is a read-only bit, and must be cleared by either reading I2CxRXB or by setting the Clear Buffer (CLRBF) bit (CLRBF = 1).

If no match occurs, the module goes idle.

- 6. The master device transmits the 9th clock pulse, and slave hardware transfers the value of the ACKDT bit onto the SDA line. If there are pending errors, such as a receive buffer overflow (RXO = 1), slave hardware generates a NACK and the module goes idle.
- 7. After the 9th falling edge of SCL, the Acknowledge Status Time Interrupt Flag (ACKTIF) bit is set. If the Acknowledge Time Interrupt and Hold Enable (ACKTIE) bit is also set, the generic I2CxIF is set, and if slave hardware generated an ACK, the CSTR bit is also set and the clock is stretched (when CSD = 0). If a NACK was generated, the CSTR bit remains unchanged. Once completed, software must clear CSTR and ACKTIF to release the clock and resume operation.
- 8. Master hardware issues a Restart condition (cannot be a Start condition), and once the slave detects the Restart, hardware sets the Restart Condition Interrupt Flag (RSCIF). If the Restart Condition Interrupt Enable (RSCIE) bit is also set, the generic I2CxIF is also set.
- 9. Master hardware transmits the slave's high address byte with R/W set. If the received high address byte matches:
  - The R/W bit value is copied to the R bit.
  - The SMA bit is set.
  - The D bit is cleared, indicating the last byte as an address.
  - ADRIF is set. If ADRIE is set, and the CSD bit is clear, hardware sets CSTR and the generic I2CxIF bit.
    This allows time for the slave to read either I2CxADB1 or I2CxRXB and selectively ACK/NACK based on
    the received address. When the slave has finished processing the address, software must clear CSTR to
    resume operation.
  - The matching received address is loaded into either the I2CxADB1 register or into the I2CxRXB register as determined by the ABD bit. When ABD is clear (ABD = 0), the matching address is copied to I2CxADB1. When ABD is set (ABD = 1), the matching address is copied to I2CxRXB, which also sets RXBF and I2CxRXIF. I2CxRXIF is a read-only bit, and must be cleared by either reading I2CxRXB or by setting CLRBF (CLRBF = 1).

If the address does not match, the module goes idle.


- 10. If the Transmit Buffer Empty Status (TXBE) bit is set (TXBE = 1), I2CxCNT has a non-zero value (I2CxCNT != 0), and the I2C Transmit Interrupt Flag (I2CxTXIF) is set (I2CxTXIF = 1), slave hardware sets CSTR, stretches the clock (when CSD = 0), and waits for software to load I2CxTXB with data. I2CxTXB must be loaded to clear I2CxTXIF. Once data is loaded into I2CxTXB, hardware automatically clears CSTR to resume communication.
- 11. The master device transmits the 9th clock pulse, and slave hardware transfers the value of the ACKDT bit onto the SDA line. If there are pending errors, such as a receive overflow (RXO = 1), slave hardware automatically generates a NACK condition. NACKIF is set, and the module goes idle.

# **I2C - Inter-Integrated Circuit Module**

- 12. Upon the 9th falling SCL edge, the data byte in I2CxTXB is transferred to the transmit shift register, and I2CxCNT is decremented by one. Additionally, the ACKTIF bit is set. If the ACKTIE bit is also set, the generic I2CxIF is set, and if slave hardware generated an ACK, the CSTR bit is also set and the clock is stretched (when CSD = 0). If a NACK was generated, the CSTR bit remains unchanged. Once complete, software must clear CSTR and ACKTIF to release the clock and continue operation.
- 13. If the slave generated an ACK and I2CxCNT is non-zero, master hardware transmits eight clock pulses, and slave hardware begins to shift the data byte out of the shift register starting with the Most Significant bit (MSb).
- 14. After the 8th falling edge of SCL, slave hardware checks the status of TXBE and I2CxCNT. If TXBE is set and I2CxCNT has a non-zero count value, hardware sets CSTR and the clock is stretched (when CSD = 0) until software loads I2CxTXB with new data. Once I2CxTXB has been loaded, hardware clears CSTR to resume communication.
- 15. Once the master hardware clocks in all eight data bits, it transmits the 9th clock pulse along with the ACK/ NACK response back to the slave. Slave hardware copies the ACK/NACK value to the Acknowledge Status (ACKSTAT) bit and sets ACKTIF. If ACKTIE is also set, slave hardware sets the generic I2CxIF bit and CSTR, and stretches the clock (when CSD = 0). Software must clear CSTR to resume operation.
- 16. After the 9th falling edge of SCL, data currently loaded in I2CxTXB is transferred to the transmit shift register, setting both TXBE and I2CxTXIF. I2CxCNT is decremented by one. If I2CxCNT is zero (I2CxCNT = 0), CNTIF is set.
- 17. If I2CxCNT is non-zero and the master issued an  $\overline{ACK}$  on the last byte (ACKSTAT = 0), the master transmits eight clock pulses, and slave hardware begins to shift data out of the shift register.
- 18. Repeat Steps 13-17 until the master has received all the requested data (I2CxCNT = 0). Once all data is received, master hardware transmits a NACK condition, followed by either a Stop or Restart condition. Once the NACK has been received by the slave, hardware sets NACKIF and clears SMA. If the NACK Detect Interrupt Enable (NACKIE) bit is also set, the generic I2C Error Interrupt Flag (I2CxEIF) is set. If the master issued a Stop condition, slave hardware sets the Stop Condition Interrupt Flag (PCIF). If the master issued a Restart condition, slave hardware sets the Restart Condition Interrupt Flag (RSCIF) bit. If the associated interrupt enable bits are also set, the generic I2CxIF is also set.

PIC18F26/46/56Q84
I2C - Inter-Integrated Circuit Module

Figure 37-21. 10-Bit Slave Mode Transmission



### 37.4.1.4.2 Slave Reception (10-Bit Addressing Mode)

The following section describes the sequence of events that occur when the module is receiving data in 7-bit Addressing mode:

- The master issues a Start condition. Once the Start is detected, slave hardware sets the Start Condition Interrupt Flag (SCIF) bit. If the Start Condition Interrupt Enable (SCIE) bit is also set, the generic I2CxIF bit is also set.
- 2. Master hardware transmits the address high byte with the R/ $\overline{W}$  bit clear (R/ $\overline{W}$  = 0).
- 3. The received high address byte is compared to the values in the I2CxADR registers. If the slave is configured in 10-bit Addressing mode (no masking), the received high address byte is compared to the values in the I2CxADR1 and I2CxADR3 registers. If the slave is configured in 10-bit Addressing with Masking mode, the received high address byte is compared to the masked value in the I2CxADR1 register. If a high address match occurs:
  - The  $R/\overline{W}$  bit value is copied to the Read Information (R) bit by module hardware.
  - The Data (D) bit is cleared (D = 0) by hardware, indicating the last received byte was an address.
  - The Address Interrupt Flag (ADRIF) bit is set (ADRIF = 1). It is important to note that regardless of
    whether the Address Interrupt and Hold Enable (ADRIE) bit is set, clock stretching does not occur when
    the R/W bit is clear in 10-bit Addressing modes.
  - The matching address is loaded into either the I2CxADB1 register or into the I2CxRXB register as determined by the Address Buffer Disable (ABD) bit. When ABD is clear (ABD = 0), the matching address is copied to I2CxADB1. When ABD is set (ABD = 1), the matching address is copied to I2CxRXB, which also sets the Receive Buffer Full Status (RXBF) bit and the I2C Receive Interrupt Flag (I2CxRXIF) bit.

If no address match occurs, the module remains idle.

- 4. The master device transmits the 9th clock pulse, and slave hardware transfers the value of the ACKDT bit onto the SDA line. If there are pending errors, such as a receive buffer overflow (RXO = 1), slave hardware generates a NACK and the module goes idle.
- The master device transmits the low address byte. If the slave is configured in 10-bit Addressing mode (no masking), the received low address byte is compared to the values in I2CxADR0 and I2CxADR2. In 10-bit Addressing with Masking mode, the received low address byte is compared to the masked value of I2CxADR0.

If a match occurs:

- The Slave Mode Active (SMA) bit is set by module hardware.
- ADRIF is set. If ADRIE is set, and the Clock Stretching Disable (CSD) bit is clear, hardware sets the
  Slave Clock Stretching (CSTR) bit and the generic I2CxIF bit. This allows time for the slave to read either
  I2CxADB0 or I2CxRXB and selectively ACK/NACK based on the received address. When the slave has
  finished processing the address, software must clear CSTR to resume operation.
- The matching received address is loaded into either the I2CxADB0 register or into the I2CxRXB register as determined by the ABD bit. When ABD is clear (ABD = 0), the matching address is copied to I2CxADB0. When ABD is set (ABD = 1), the matching address is copied to I2CxRXB, which also sets the RXBF and the I2CxRXIF bits. I2CxRXIF is a read-only bit, and must be cleared by either reading I2CxRXB or by setting the Clear Buffer (CLRBF) bit (CLRBF = 1).

If no match occurs, the module goes idle.

- 6. The master device transmits the 9th clock pulse, and slave hardware transfers the value of the ACKDT bit onto the SDA line. If there are pending errors, such as a receive buffer overflow (RXO = 1), slave hardware generates a NACK and the module goes idle.
- 7. After the 9th falling edge of SCL, the Acknowledge Status Time Interrupt Flag (ACKTIF) bit is set. If the Acknowledge Time Interrupt and Hold Enable (ACKTIE) bit is also set, the generic I2CxIF is set, and if slave hardware generated an ACK, the CSTR bit is also set and the clock is stretched (when CSD = 0). If a NACK was generated, the CSTR bit remains unchanged. Once completed, software must clear CSTR and ACKTIF to release the clock and resume operation.
- 8. If slave hardware generated a NACK, master hardware generates a Stop condition, the Stop Condition Interrupt Flag (PCIF) is set when slave hardware detects the Stop condition, and the slave goes idle. If an ACK was generated, master hardware transmits the first seven bits of the 8-bit data byte.


# **I2C - Inter-Integrated Circuit Module**

- 9. If data remains in I2CxRXB (RXBF = 1 and I2CxRXIF = 1) when the first seven bits of the new byte are received by the shift register, CSTR is set, and if CSD is clear, the clock is stretched after the 7th falling edge of SCL. This allows time for the slave to read I2CxRXB, which clears RXBF and I2CxRXIF, and prevents a receive buffer overflow. Once I2CxRXB has been read, RXBF and I2CxRXIF are cleared, and hardware releases SCL.
- 10. Master hardware transmits the 8th bit of the current data byte into the slave receive shift register. Slave hardware then transfers the complete byte into I2CxRXB on the 8th falling edge of SCL, and sets the following bits:
  - I2CxRXIF
  - I2CxIF
  - Data Write Interrupt Flag (WRIF)
  - Data (D)
  - RXBF

I2CxCNT is decremented by one. If the Data Write Interrupt and Hold Enable (WRIE) bit is set (WRIE = 1), hardware sets CSTR (when CSD = 0) and stretches the clock, allowing time for slave software to read I2CxRXB and determine the state of the ACKDT bit that is transmitted back to the master. Once the slave determines the Acknowledgement response, software clears CSTR to allow further communication.

- 11. Upon the 9th falling edge of SCL, the ACKTIF bit is set. If ACKTIE is also set, the generic I2CxIF is set, and if CSD is clear, slave hardware sets CSTR and stretches the clock. This allows time for software to read I2CxRXB. Once complete, software must clear both CSTR and ACKTIF to release the clock and continue communication.
- 12. Repeat Steps 8 11 until the master has transmitted all the data (I2CxCNT = 0), or until the master issues a Stop or Restart condition.

PIC18F26/46/56Q84



### 37.4.2 I<sup>2</sup>C Master Mode Operation

The I<sup>2</sup>C module provides two master operation modes as selected by the I<sup>2</sup>C Mode Select (MODE) bits:

- I<sup>2</sup>C Master mode with 7-bit addressing
- I<sup>2</sup>C Master mode with 10-bit addressing

To begin any I<sup>2</sup>C communication, master hardware checks to ensure that the bus is in an Idle state, which means both the SCL and SDA lines are floating in a high logic state as indicated by the Bus Free Status (BFRE) bit.

Once Master hardware has determined that the bus is free (BFRE = 1), it examines the state of the Address Buffer Disable (ABD) bit. The ABD bit determines whether the I2CxADB registers are used.

When ABD is clear (ABD = 0), address buffers I2CxADB0 and I2CxADB1 are active. In 7-bit Addressing mode, software loads I2CxADB1 with the 7-bit slave address and R/W bit setting, and also loads I2CxTXB with the first byte of data . In 10-bit Addressing mode, software loads I2CxADB1 with the address high byte and I2CxADB0 with the address low byte, and also loads I2CxTXB with the first data byte. Software must issue a Start condition to initiate communication with the slave.

When ABD is set (ABD = 1), the address buffers are inactive. In this case, communication begins as soon as software loads the slave address into I2CxTXB. Writes to the Start bit (S) are ignored.

In 7-bit Addressing mode, the Least Significant bit (LSb) of the 7-bit address byte acts as the Read/not Write (R/ $\overline{W}$ ) information bit, while in 10-bit Addressing mode, the LSb of the address high byte is reserved as the R/ $\overline{W}$  bit. When R/ $\overline{W}$  is set, the master intends to read data from the slave (see figure below). When R/ $\overline{W}$  is clear, the master intends to write data to the slave (see figure below). The master may also wish to read or write data to a specific location, such as writing to a specific EEPROM location. In this case, the master issues a Start condition, followed by the slave's address with the R/ $\overline{W}$  bit clear. Once the slave acknowledges the address, the first data byte following the 7-bit or 10-bit address is used as the slave's specific register location. If the master intends to read data from the specific location, it must issue a Restart condition, followed by the slave address with the R/ $\overline{W}$  bit set (see figure below). If the addressed slave device exists on the bus, it must respond with an Acknowledge ( $\overline{ACK}$ ) sequence.

Once a slave has acknowledged its address, the master begins to receive data from the slave or transmits data to the slave. Data is always transmitted Most Significant bit (MSb) first. When the master wishes to halt further communication, it transmits either a Stop condition, signaling to the slave that communication is to be terminated, or a Restart condition, informing the bus that the current master wishes to hold the bus to communicate with the same or other slave devices.

Figure 37-23. 7-Bit Master Read Diagram




Figure 37-24. 7-Bit Master Read Diagram (from a specific memory/register location)




Figure 37-25. 10-Bit Master Read Diagram




Figure 37-26. 7-Bit Master Write Diagram




Figure 37-27. 7-Bit Master Write Diagram (to a specific memory/register location)





Figure 37-28. 10-Bit Master Write Diagram



#### 37.4.2.1 Bus Free Time

The Bus Free Status (BFRE) bit indicates the activity status of the bus. When BFRE is set (BFRE = 1), the bus is in an Idle state (both SDA and SCL are floating high), and any master device residing on the bus can compete for control of the bus. When BFRE is clear (BFRE = 0), the bus is in an Active state, and any attempts by a master to control the bus will cause a collision.


The Bus Free Time (BFRET) bits determine the length of time, in terms of I<sup>2</sup>C clock pulses, before the bus is considered idle. Once module hardware detects logic high levels on both SDA and SCL, it monitors the I<sup>2</sup>C clock signal, and when the desired number of pulses have occurred, module hardware sets BFRE. The BFRET bits are also used to ensure that the module meets the minimum Stop hold time as defined by the I<sup>2</sup>C Specification.

#### 37.4.2.2 Master Clock Timing

The Serial Clock (SCL) signal is generated by module hardware via the I2C Clock Selection Register (I2CxCLK), the I2C Baud Rate Prescaler Register (I2CxBAUD), and the Fast Mode Enable (FME) bit.

The figure below illustrates the SCL clock generation.

Figure 37-29. SCL Clock Generation



I2CxCLK contains several clock source selections. The clock source selections typically include variants of the system clock and timer resources.



**Important:** When using a timer as the clock source, the timer must also be configured. Additionally, when using the HFINTOSC as a clock source it is important to understand that the HFINTOSC frequency selected by the OSCFRQ register is used as the clock source. The clock divider selected by the NDIV bits is not used. For example, if OSCFRQ selects 4 MHz as the HFINTOSC clock frequency, and the NDIV bits select a divide by four scaling factor, the I2C Clock Frequency will be 4 MHz and not 1 MHz since the divider is ignored.

I2CxBAUD is used to determine the prescaler (clock divider) for the I2CxCLK source.

The FME bit acts as a secondary divider to the prescaled clock source.

When FME is clear (FME = 0), one SCL period ( $T_{SCL}$ ) is equal to five clock periods of the prescaled I2CxCLK source. In other words, the prescaled I2CxCLK source is divided by five. For example, if the HFINTOSC (set to 4 MHz) clock source is selected, I2CxBAUD is loaded with a value of '7', and the FME bit is clear, the actual SCL frequency is 100 kHz (see Equation below).

## Equation 37-1. SCL Frequency (FME = 0)

#### Example:


I2CxCLK: HFINTOSC (4 MHz)

I2CxBAUD: 7FME: FME = 0

$$f_{SCL} = \frac{\frac{f_{12CxCLK}}{(BAUD + 1)}}{FME} = \frac{\frac{4MHz}{8}}{5} = 100 \, \text{kHz}$$

When FME is clear, master hardware uses the first prescaled I2CxCLK source period to drive SCL low (see figure below). During the second period, hardware verifies that SCL is in fact low. During the third period, hardware releases SCL, allowing it to float high. Master hardware then uses the fourth and fifth periods to sample SCL to verify that SCL is high. If a slave is holding SCL low (clock stretch) during the fourth and/or fifth period, master hardware samples each successive prescaled I2CxCLK period until a high level is detected on SCL. Once the high level is detected, master hardware samples SCL during the next two I2CxCLK periods to verify that SCL is high.

Figure 37-30. SCL Timing (FME = 0)



When FME is set (FME = 1), one SCL period ( $T_{SCL}$ ) is equal to four clock periods of the prescaled I2CxCLK source. In other words, the prescaled I2CxCLK source is divided by four. Using the example from above, if the HFINTOSC (4 MHz) clock source is selected, I2CxBAUD is loaded with a value of '7' and the FME bit is set, the actual SCL frequency is 125 kHz (see Equation below).

#### Equation 37-2. SCL Frequency (FME = 1)

Example:


I2CxCLK: HFINTOSC (4 MHz)

I2CxBAUD: 7FME: FME = 1

$$f_{SCL} = \frac{\frac{f_{12CxCLK}}{(BAUD + 1)}}{\frac{EME}{EME}} = \frac{\frac{4MHz}{8}}{\frac{4}{4}} = 125kHz$$

When FME is set, master hardware uses the first prescaled I2CxCLK source period to drive SCL low (see figure below). During the second prescaled period, hardware verifies that SCL is in fact low. During the third period, hardware releases SCL, allowing it to float high. Master hardware then uses the fourth period to sample SCL to verify that SCL is high. If a slave is holding SCL low (clock stretch) during the fourth period, master hardware samples each successive prescaled I2CxCLK period until a high level is detected on SCL. Once the high level is detected, master hardware samples SCL during the next period to verify that SCL is high.

Figure 37-31. SCL Timing (FME = 1)




### 37.4.2.3 Start Condition Timing

A Start condition is initiated by either writing to the Start (S) bit (when ABD = 0), or by writing to I2CxTXB (when ABD = 1). When the Start condition is initiated, master hardware verifies that the bus is idle, then begins to count the number of I2CxCLK periods as determined by the Bus Free Time Status (BFRET) bits. Once the Bus Free Time period has been reached, hardware sets BFRE (BFRE = 1), the Start condition is asserted on the bus, which pulls the SDA line low, and the Start Condition Interrupt Flag (SCIF) bit is set (SCIF = 1). Master hardware then waits one full SCL period (T<sub>SCL</sub>) before pulling the SCL line low, signaling the end of the Start condition. At this point, hardware loads the transmit shift register from either I2CxADB0/I2CxADB1 (ABD = 0) or I2CxTXB (ABD = 1).

The figure below shows an example of a Start condition.

Figure 37-32. Start Condition Timing





### Important:

- 1. See device data sheet for Start condition hold time parameters.
- 2. SDA hold times are configured via the SDAHT bits.

#### 37.4.2.4 Acknowledge Sequence Timing

As previously mentioned, the 9th SCL pulse for any transferred address/data byte is reserved for the Acknowledge  $(\overline{ACK})$  sequence. During an Acknowledge sequence, the transmitting device relinquishes control of the SDA line to the receiving device. At this time, the receiving device must decide whether to pull the SDA line low  $(\overline{ACK})$  or allow the line to float high (NACK).

An Acknowledge sequence is enabled automatically by module hardware following an address/data byte reception. On the 8th falling edge of SCL, the value of either the ACKDT or ACKCNT bits are copied to the SDA output, depending on the state of I2CxCNT. When I2CxCNT holds a non-zero value (I2CxCNT != 0), the value of ACKDT is copied to SDA (see figure below). When I2CxCNT reaches a zero count (I2CxCNT = 0), the value of ACKCNT is copied to SDA (see figure below). In most applications, the value of ACKDT should be zero (ACKDT = 0), which represents an  $\overline{ACK}$ , while the value of ACKCNT should be one (ACKCNT = 1), which represents a NACK.

Figure 37-33. Acknowledge (ACK) Sequence Timing





Figure 37-34. Not Acknowledge (NACK) Sequence Timing




#### 37.4.2.5 Restart Condition Timing

A Restart condition is identical to a Start condition. A master device may issue a Restart instead of a Stop condition if it intends to hold the bus after completing the current data transfer. A Restart condition occurs when the Restart Enable (RSEN) bit is set (RSEN = 1), either I2CxCNT is zero (I2CxCNT = 0) or ACKSTAT is set (ACKSTAT = 1), and either master hardware (ABD = 1) or user software (ABD = 0) sets the Start (S) bit.

When the Start bit is set, master hardware releases SDA (SDA floats high) for half of an SCL clock period ( $T_{SCL}/2$ ), and then releases SCL for another half of an SCL period, then samples SDA (see figure below). If SDA is sampled low while SCL is sampled high, a bus collision has occurred. In this case, the Bus Collision Detect Interrupt Flag (BCLIF) is set, and if the Bus Collision Detect Interrupt Enable (BCLIE) bit is also set, the generic I2CxEIF is set, and the module goes idle. If SDA is sampled high while SCL is also sampled high, master hardware issues a Start

condition. Once the Restart condition is detected on the bus, the Restart Condition Interrupt Flag (RSCIF) is set by hardware, and if the Restart Condition Interrupt Enable (RSCIE) bit is set, the generic I2CxIF is also set.

Figure 37-35. Restart Condition Timing





### Important:

1. See device data sheet for Restart condition setup times.

#### 37.4.2.6 Stop Condition Timing

A Stop condition occurs when SDA transitions from an Active state to an Idle state while SCL is Idle. Master hardware will issue a Stop condition when it has completed its current transmission and is ready to release control of the bus. A Stop condition is also issued after an error condition occurs, such as a bus time-out, or when a NACK condition is detected on the bus. User software may also generate a Stop condition by setting the Stop (P) bit.


After the  $\overline{\text{ACK}}/\text{NACK}$  sequence of the final byte of the transmitted/received packet, hardware pulls SCL low for half of an SCL period ( $T_{\text{SCL}}/2$ ) (see figure below). After the half SCL period, hardware releases SCL, then samples SCL to ensure it is in an Idle state (SCL = 1). Master hardware then waits the duration of the Stop condition setup time ( $T_{\text{SU:STO}}$ ) and releases SDA, setting the Stop Condition Interrupt Flag (PCIF). If the Stop Condition Interrupt Enable (PCIE) bit is also set, the generic I2CxIF is also set.



**Important:** At least one SCL low period must appear before a Stop condition is valid. If the SDA line transitions low, then high again, while SCL is high, the Stop condition is ignored, and a Start condition will be detected by the receiver.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 728

Figure 37-36. Stop Condition Timing





#### Important:

- At least one SCL low period must appear before a Stop is valid.
- 2. See the device data sheet electrical specifications for Stop condition setup and hold times.

#### 37.4.2.7 Master Operation in 7-Bit Addressing Modes

In Master 7-bit Addressing modes, the slave's 7-bit address and  $R/\overline{W}$  bit value are loaded into either I2CxADB1 or I2CxTXB, depending on the Address Buffer Disable (ABD) bit setting. When the master wishes to read data from the slave, software must set the  $R/\overline{W}$  bit ( $R/\overline{W} = 1$ ). When the master wishes to write data to the slave, software must clear the  $R/\overline{W}$  bit ( $R/\overline{W} = 0$ ).

#### 37.4.2.7.1 Master Transmission (7-Bit Addressing Mode)

The following section describes the sequence of events that occur when the module is transmitting data in 7-bit Addressing mode:

- 1. Depending on the configuration of the Address Buffer Disable (ABD) bit, one of two methods may be used to begin communication:
  - 1.1. When ABD is clear (ABD = 0), the address buffer, I2CxADB1, is enabled. In this case, the 7-bit slave address and R/W bit are loaded into I2CxADB1, with the R/W bit clear (R/W = 0). The number of data bytes are loaded into I2CxCNT, and the first data byte is loaded into I2CxTXB. After these registers are loaded, software must set the Start (S) bit to begin communication. Once the S bit is set, master hardware waits for the Bus Free (BFRE) bit to be set before transmitting the Start condition to avoid bus collisions.
  - 1.2. When ABD is set (ABD = 1), the address buffer is disabled. In this case, the number of data bytes are loaded into I2CxCNT, and the slave's 7-bit address and R/W bit are loaded into I2CxTXB. A write to I2CxTXB will cause master hardware to automatically issue a Start condition once the bus is idle (BFRE = 1). Software writes to the Start bit are ignored.
- 2. Master hardware waits for BFRE to be set, then shifts out the Start condition. Module hardware sets the Master Mode Active (MMA) bit and the Start Condition Interrupt Flag (SCIF). If the Start Condition Interrupt Enable (SCIE) bit is set, the generic I2CxIF is also set.

## PIC18F26/46/56Q84


## **I2C - Inter-Integrated Circuit Module**

- 3. Master hardware transmits the 7-bit slave address and R/W bit.
- 4. If upon the 8th falling edge of SCL, I2CxTXB is empty (Transmit Buffer Empty Status (TXBE) = 1), I2CxCNT is non-zero (I2CxCNT!= 0), and the Clock Stretching Disable (CSD) bit is clear (CSD = 0):
  - The I2C Transmit Interrupt Flag (I2CxTXIF) is set. If the I2C Transmit Interrupt Enable (I2CxTXIE) bit is also set, the generic I2CxIF is also set.
  - The Master Data Request (MDR) bit is set, and the clock is stretched, allowing time for software to load I2CxTXB with new data. Once I2CxTXB has been written, hardware releases SCL and clears MDR.
- 5. Hardware transmits the 9th clock pulse and waits for an ACK/NACK response from the slave. If the master receives an ACK, module hardware transfers the data from I2CxTXB into the transmit shift register, and I2CxCNT is decremented by one. If the master receives a NACK, hardware will attempt to issue a Stop condition. If the clock is currently being stretched by a slave, the master must wait until the bus is free before issuing the Stop.
- 6. Master hardware checks I2CxCNT for a zero value. If I2CxCNT is zero:
  - 6.1. If ABD is clear (ABD = 0), master hardware issues a Stop condition, or sets MDR if the Restart Enable (RSEN) bit is set and waits for software to set the Start bit to issue a Restart condition. CNTIF is set.
  - 6.2. If ABD is set (ABD = 1), master hardware issues a Stop condition, or sets MDR if RSEN is set and waits for software to load I2CxTXB with a new slave address. CNTIF is set.
- 7. Master hardware transmits the data byte.
- 8. If upon the 8th falling edge of SCL I2CxTXB is empty (TXBE = 1), I2CxCNT is non-zero (I2CxCNT != 0), and CSD is clear (CSD = 0):
  - I2CxTXIF is set. If the I2CxTXIE bit is also set, the generic I2CxIF is also set.
  - The MDR bit is set, and the clock is stretched, allowing time for software to load I2CxTXB with new data.
     Once I2CxTXB has been written, hardware releases SCL and clears MDR.

If TXBE is set (TXBE = 1) and I2CxCNT is zero (I2CxCNT = 0):

- I2CxTXIF is NOT set.
- CNTIF is set.
- Master hardware issues a Stop condition, setting PCIF.
- 9. Repeat Steps 5 8 until all data has been transmitted.

Figure 37-37. 7-Bit Master Mode Transmission



12C - Inter-Integrated Circuit Module

PIC18F26/46/56Q84

#### 37.4.2.7.2 Master Reception (7-Bit Addressing Mode)

The following section describes the sequence of events that occur when the module is receiving data in 7-bit Addressing mode:

- 1. Depending on the configuration of the Address Buffer Disable (ABD) bit, one of two methods may be used to begin communication:
  - 1.1. When ABD is clear (ABD = 0), the address buffer, I2CxADB1, is enabled. In this case, the 7-bit slave address and R/W bit are loaded into I2CxADB1, with the R/W bit set (R/W = 1). The number of expected received data bytes are loaded into I2CxCNT. After these registers are loaded, software must set the Start (S) bit to begin communication. Once the S bit is set, master hardware waits for the Bus Free (BFRE) bit to be set before transmitting the Start condition to avoid bus collisions.
  - 1.2. When ABD is set (ABD = 1), the address buffer is disabled. In this case, the number of expected received data bytes are loaded into I2CxCNT, and the slave's 7-bit address and R/W bit are loaded into I2CxTXB. A write to I2CxTXB will cause master hardware to automatically issue a Start condition once the bus is idle (BFRE = 1). Software writes to the Start bit are ignored.
- 2. Master hardware waits for BFRE to be set, then shifts out the Start condition. Module hardware sets the Master Mode Active (MMA) bit and the Start Condition Interrupt Flag (SCIF). If the Start Condition Interrupt Enable (SCIE) bit is set, the generic I2CxIF is also set.
- 3. Master hardware transmits the 7-bit slave address and R/W bit.
- 4. Master hardware samples SCL to determine if the slave is stretching the clock, and continues to sample SCL until the line is sampled high.
- Master hardware transmits the 9th clock pulse, and receives the ACK/NACK response from the slave.
   If an ACK is received, master hardware receives the first seven bits of the data byte into the receive shift register.

If a NACK is received, hardware sets the NACK Detect Interrupt Flag (NACKIF), and:


- 5.1. ABD = 0: Master generates a Stop condition, or sets the MDR bit (if RSEN is also set) and waits for software to set the Start bit to generate a Restart condition.
- 5.2. ABD = 1: Master generates a Stop condition, or sets the MDR bit (if RSEN is also set) and waits for software to load a new address into I2CxTXB. Software writes to the Start bit are ignored.

If the NACK Detect Interrupt Enable (NACKIE) is also set, hardware sets the generic I2CxEIF bit.

- 6. If previous data remains in the I2C Receive Buffer (I2CxRXB) when the first seven bits of the new byte are received into the receive shift register (RXBF = 1), the MDR bit is set (MDR = 1), and the clock is stretched after the 7th falling edge of SCL. This allows the master time to read I2CxRXB, which clears the RXBF bit, and prevents receive buffer overflows. Once RXBF is clear, hardware releases SCL.
- 7. The master clocks in the 8th bit of the data byte into the receive shift register, then transfers the full byte into I2CxRXB. Master hardware sets the I2C Receive Interrupt Flag (I2CxRXIF) and RXBF, and if the I2C Receive Interrupt Enable (I2CxRXIE) is set, the generic I2CxIF is also set. Finally, I2CxCNT is decremented by one.
- 8. Master hardware checks I2CxCNT for a zero value.

  If I2CxCNT is non-zero (I2CxCNT!= 0), hardware transmits the value of the Acknowledge Data (ACKDT) bit as the acknowledgement response to the slave. It is up to user software to properly configure ACKDT. In most cases, ACKDT should be clear (ACKDT = 0), which indicates an ACK response.
  - If I2CxCNT is zero (I2CxCNT = 0), hardware transmits the value of the Acknowledge End of Count (ACKCNT) bit as the acknowledgement response to the slave. CNTIF is set, and master hardware either issues a Stop condition or a Restart condition. It is up to user software to properly configure ACKCNT. In most cases, ACKCNT should be set (ACKCNT = 1), which indicates a NACK response. When hardware detects a NACK on the bus, it automatically issues a Stop condition. If a NACK is not detected, the Stop will not be generated, which may lead to a stalled bus condition.
- 9. Master hardware receives the first seven bits of the next data byte into the receive shift register.
- 10. Repeat Steps 6 9 until all expected bytes have been received.

Figure 37-38. 7-Bit Master Mode Reception



12C - Inter-Integrated Circuit Module

PIC18F26/46/56Q84

### 37.4.2.8 Master Operation in 10-Bit Addressing Modes

In Master 10-bit Addressing modes, the slave's 10-bit address and R/ $\overline{W}$  bit value are loaded into either the I2CxADB0 and I2CxADB1 registers (when ABD = 0), or I2CxTXB (when ABD = 1). When the master intends to read data from the slave, it must first transmit the full 10-bit address with the R/ $\overline{W}$  bit clear (R/ $\overline{W}$  = 0), issue a Restart condition, then transmit the address high byte with the R/ $\overline{W}$  bit set (R/ $\overline{W}$  = 1). When the master intends to write data to the slave, it must transmit the full 10-bit address with the R/ $\overline{W}$  bit clear (R/ $\overline{W}$  = 0).

#### 37.4.2.8.1 Master Transmission (10-Bit)

The following section describes the sequence of events that occur when the module is transmitting data in 10-bit Addressing mode:

- 1. Depending on the configuration of the Address Buffer Disable (ABD) bit, one of two methods may be used to begin communication:
  - 1.1. When ABD is clear (ABD = 0), the address buffers, I2CxADB0 and I2CxADB1, are enabled. In this case, the address high byte is loaded into I2CxADB1 with the R/W bit clear, while the address low byte is loaded into I2CxADB0. I2CxCNT is loaded with the total number of data bytes to transmit, and the first data byte is loaded into I2CxTXB. After these registers are loaded, software must set the Start bit to begin communication.
  - 1.2. When ABD is set (ABD = 1), the address buffers are disabled. In this case, I2CxCNT must be loaded with the total number of bytes to transmit prior to loading I2CxTXB with the address high byte and R/W bit. A write to I2CxTXB forces module hardware to issue a Start condition automatically; software writes to the S bit are ignored.
- 2. Master hardware waits for BFRE to be set, then shifts out the Start condition. Module hardware sets the Master Mode Active (MMA) bit and the Start Condition Interrupt Flag (SCIF). If the Start Condition Interrupt Enable (SCIE) bit is also set, the generic I2CxIF is also set.
- 3. Master hardware transmits the address high byte and R/W bit from I2CxADB1.
- 4. Master hardware transmits the 9th clock pulse and shifts in the ACK/NACK response from the slave. If the master receives a NACK, it issues a Stop condition.

If the master receives and ACK and:

- 4.1. ABD = 0: Hardware transmits the address low byte from I2CxADB0.
- 4.2. ABD = 1: Hardware sets I2CxTXIF and the Master Data Request (MDR) bit and waits for software to load I2CxTXB with the address low byte. Software must load I2CxTXB to resume communication.
- 5. If upon the 8th falling edge of SCL I2CxTXB is empty (TXBE = 1), I2CxCNT is non-zero (I2CxCNT != 0), and the Clock Stretching Disable (CSD) bit is clear (CSD = 0):
  - I2CxTXIF is set. If the I2C Transmit Interrupt Enable (I2CxTXIE) bit is also set, the generic I2CxIF is also set.
  - MDR bit is set, and the clock is stretched, allowing time for software to load I2CxTXB with the address low byte. Once I2CxTXB has been written, hardware releases SCL and clears MDR.
- 6. Hardware transmits the 9th clock pulse and waits for an ACK/NACK response from the slave. If the master receives an ACK, module hardware transfers the data from I2CxTXB into the transmit shift register, and I2CxCNT is decremented by one. If the master receives a NACK, hardware will attempt to issue a Stop condition. If the clock is currently being stretched by a slave, the master must wait until the bus is free before issuing the Stop.
- 7. Master hardware checks I2CxCNT for a zero value. If I2CxCNT is zero:
  - 7.1. If ABD is clear (ABD = 0), master hardware issues a Stop condition, or sets MDR if the Restart Enable (RSEN) bit is set and waits for software to set the Start bit to issue a Restart condition. CNTIF is set.
  - 7.2. If ABD is set (ABD = 1), master hardware issues a Stop condition, or sets MDR if RSEN is set and waits for software to load I2CxTXB with a new slave address. CNTIF is set.
- 8. Master hardware transmits the data byte.
- 9. If upon the 8th falling edge of SCL I2CxTXB is empty (TXBE = 1), I2CxCNT is non-zero (I2CxCNT != 0), and CSD is clear (CSD = 0):
  - The I2CxTXIF bit is set. If the I2CxTXIE bit is also set, the generic I2CxIF is also set.

## PIC18F26/46/56Q84


## **I2C - Inter-Integrated Circuit Module**

The MDR bit is set, and the clock is stretched, allowing time for software to load I2CxTXB with new data.
 Once I2CxTXB has been written, hardware releases SCL and clears MDR.

If TXBE is set (TXBE = 1) and I2CxCNT is zero (I2CxCNT = 0):

- I2CxTXIF is NOT set.
- CNTIF is set.
- Master hardware issues a Stop condition, setting PCIF.
- 10. Repeat Steps 6 9 until all data has been transmitted.

Figure 37-39. 10-Bit Master Mode Transmission



12C - Inter-Integrated Circuit Module

PIC18F26/46/56Q84

#### 37.4.2.8.2 Master Reception (10-Bit Addressing Mode)

The following section describes the sequence of events that occur when the module is receiving data in 10-bit addressing mode:

- Depending on the configuration of the Address Buffer Disable (ABD) bit, one of two methods may be used to begin communication:
  - 1.1. When ABD is clear (ABD = 0), the address buffers, I2CxADB0 and I2CxADB1, are enabled. In this case, the address high byte and R/W bit are loaded into I2CxADB1, with R/W clear (R/W = 0). The address low byte is loaded into I2CxADB0, and the Restart Enable (RSEN) bit is set by software. After these registers are loaded, software must set the Start (S) bit to begin communication. Once the S bit is set, master hardware waits for the Bus Free (BFRE) bit to be set before transmitting the Start condition to avoid bus collisions.
  - 1.2. When ABD is set (ABD = 1), the address buffers are disabled. In this case, the number of expected received bytes are loaded into I2CxCNT, the address high byte and R/W bit are loaded into I2CxTXB, with R/W clear (R/W = 0). A write to I2CxTXB will cause master hardware to automatically issue a Start condition once the bus is idle (BFRE = 1). Software writes to the Start bit are ignored.
- 2. Master hardware waits for BFRE to be set, then shifts out the Start condition. Module hardware sets the Master Mode Active (MMA) bit and the Start Condition Interrupt Flag (SCIF). If the Start Condition Interrupt Enable (SCIE) bit is set, the generic I2CxIF is also set.
- 3. Master hardware transmits the address high byte and  $R/\overline{W}$  bit.
- 4. Master hardware samples SCL to determine if the slave is stretching the clock, and continues to sample SCL until the line is sampled high.
- Master hardware transmits the 9th clock pulse, and receives the ACK/NACK response from the slave.
   If a NACK was received, the NACK Detect Interrupt Flag (NACKIF) is set and the master immediately issues a Stop condition.
  - If an  $\overline{\mathsf{ACK}}$  was received, module hardware transmits the address low byte.
- 6. Master hardware samples SCL to determine if the slave is stretching the clock, and continues to sample SCL until the line is sampled high.
- 7. Master hardware transmits the 9th clock pulse, and receives the ACK/NACK response from the slave. If an ACK was received, hardware sets MDR, and waits for hardware or software to set the Start bit.
  - If a NACK is received, hardware sets NACKIF, and:
  - 7.1. ABD = 0: Master generates a Stop condition, or sets the MDR bit (if RSEN is also set) and waits for software to set the Start bit to generate a Restart condition.
  - 7.2. ABD = 1: Master generates a Stop condition, or sets the MDR bit (if RSEN is also set) and waits for software to load a new address into I2CxTXB. Software writes to the Start bit are ignored.

If the NACK Detect Interrupt Enable (NACKIE) is also set, hardware sets the generic I2CxEIF bit.

- 8. Software loads I2CxCNT with the expected number of received bytes.
- 9. If ABD is clear (ABD = 0), software sets the Start bit. If ABD is set (ABD = 1), software writes the address high byte with R/W bit into I2CxTXB, with R/W set (R/W = 1).
- 10. Master hardware transmits the Restart condition, which sets the Restart Condition Interrupt Flag (RSCIF) bit. If the Restart Condition Interrupt Enable (RSCIE) bit is set, the generic I2CxIF is set by hardware.
- 11. Master hardware transmits the high address byte and  $R/\overline{W}$  bit.
- 12. Master hardware samples SCL to determine if the slave is stretching the clock, and continues to sample SCL until the line is sampled high.
- 13. Master hardware transmits the 9th clock pulse, and receives the ACK/NACK response from the slave. If an ACK is received, master hardware receives the first seven bits of the data byte into the receive shift register.

If a NACK is received, and:

- 13.1. ABD = 0: Master generates a Stop condition, or sets the MDR bit (if RSEN is also set) and waits for software to set the Start bit to generate a Restart condition.
- 13.2. ABD = 1: Master generates a Stop condition, or sets the MDR bit (if RSEN is also set) and waits for software to load a new address into I2CxTXB. Software writes to the Start bit are ignored.

## PIC18F26/46/56Q84


## **I2C - Inter-Integrated Circuit Module**

- 14. If previous data is currently in I2CxRXB (RXBF = 1) when the first seven bits are received by the receive shift register, hardware sets MDR, and the clock is stretched after the 7th falling edge of SCL. This allows software to read I2CxRXB, which clears the RXBF bit, and prevents a receive buffer overflow. Once the RXBF bit is cleared, hardware releases SCL.
- 15. Master hardware clocks in the 8th bit of the data byte into the receive shift register, then transfers the complete byte into I2CxRXB, which sets the I2CxRXIF and RXBF bits. If I2CxRXIE is also set, hardware sets the generic I2CxIF bit. I2CxCNT is decremented by one.
- 16. Hardware checks I2CxCNT for a zero value.

  If I2CxCNT is non-zero (I2CxCNT!= 0), hardware transmits the value of the Acknowledge Data (ACKDT) bit as the acknowledgement response to the slave. It is up to user software to properly configure ACKDT. In most cases, ACKDT should be clear (ACKDT = 0), which indicates an ACK response.
  - If I2CxCNT is zero (I2CxCNT = 0), hardware transmits the value of the Acknowledge End of Count (ACKCNT) bit as the acknowledgement response to the slave. CNTIF is set, and master hardware either issues a Stop condition or a Restart condition. It is up to user software to properly configure ACKCNT. In most cases, ACKCNT should be set (ACKCNT = 1), which indicates a NACK response. When hardware detects a NACK on the bus, it automatically issues a Stop condition. If a NACK is not detected, the Stop will not be generated, which may lead to a stalled bus condition.
- 17. Master hardware receives the first seven bits of the next data byte into the receive shift register.
- 18. Repeat Steps 14 17 until all expected bytes have been received.

PIC18F26/46/56Q84

Figure 37-40. 10-Bit Master Mode Reception



### 37.4.3 I<sup>2</sup>C Multi-Master Mode Operation

In Multi-Master mode, multiple master devices reside on the same bus. A single device, or all devices, may act as both a master and a slave. Control of the bus is achieved through clock synchronization and bus arbitration.

The Bus Free (BFRE) bit is used to determine if the bus is free. When BFRE is set (BFRE = 1), the bus is in an Idle state, allowing a master device to take control of the bus.

In Multi-Master mode, the Address Interrupt and Hold Enable (ADRIE) bit must be set (ADRIE = 1), and the Clock Stretching Disable (CSD) bit must be clear (CSD = 0), in order for a master device to be addressed as a slave.

When a matching address is received into the receive shift register, the SMA bit is set, and the Address Interrupt Flag (ADRIF) bit is set. Since ADRIE is also set, hardware sets the Slave Clock Stretching (CSTR) bit, and hardware stretches the clock to allow time for software to respond to the master device being addressed as a slave. Once the address has been processed, software must clear CSTR to resume communication.



**Important:** Slave hardware has priority over master hardware in Multi-Master mode. Master mode communication can only be initiated when SMA = 0.

#### 37.4.3.1 Multi-Master Mode Clock Synchronization

In a multi-master system, each master may begin to generate a clock signal as soon as the bus is idle. Clock synchronization allows all devices on the bus to use a single SCL signal.

When a high-to-low transition on SCL occurs, all active master devices begin SCL low period timing, with their clocks held low until their low hold time expires and the high state is reached. If one master's clock signal is still low, SCL will be held low until that master reaches its high state. During this time, all other master devices are held in a Wait state (see figure below).

Once all masters have counted off their low period times, SCL is released high, and all master devices begin counting their high periods. The first master to complete its high period pulls the SCL line low again.


This means that when the clocks are synchronized, the SCL low period is determined by the master with the longest SCL low period, while the SCL high period is determined by the master device with the shortest SCL high period.



**Important:** The I<sup>2</sup>C Specification does not require the SCL signal to have a 50% duty cycle. In other words, one master's clock signal may have a low time that is 60% of the SCL period and a high time that is 40% of the SCL period, while another master may be 50/50. This creates a timing difference between the two clock signals, which may result in data loss.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 740

Figure 37-41. Clock Synchronization during Arbitration



#### 37.4.3.2 Multi-Master Mode Bus Arbitration

When the bus is idle, any master device may attempt to take control of the bus. Two or more master devices may issue a Start condition within the minimum hold time (T<sub>HD:STA</sub>), which triggers a valid Start on the bus. The master devices must then compete using bus arbitration to determine who takes control of the bus and completes their transaction.

Bus arbitration takes place bit by bit, and it may be possible for two masters who have identical messages to complete the entire transaction without either device losing arbitration.

During every bit period, while SCL is high each master device compares the actual signal level of SDA to the signal level the master actually transmitted. SDA sampling is performed during the SCL high period because the SDA data must be stable during this period; therefore, the first master to detect a low signal level on SDA while it expects a high signal level loses arbitration. In this case, the 'losing' master device detects a bus collision and sets the Bus Collision Detect Interrupt Flag (BCLIF), and if the Bus Collision Detect Interrupt Enable (BCLIE) bit is set, the generic I2CxEIF is also set.

Arbitration can be lost in any of the following states:

- · Address transfer
- Data transfer
- Start condition
- Restart condition
- · Acknowledge sequence
- Stop condition

If a collision occurs during the data transfer phase, the transmission is halted and both SCL and SDA are released by hardware. If a collision occurs during a Start, Restart, Acknowledge, or Stop, the operation is aborted and hardware releases SCL and SDA. If a collision occurs during the addressing phase, the master that 'wins' arbitration may be

# **I2C - Inter-Integrated Circuit Module**


attempting to address the 'losing' master as a slave. In this case, the master that lost arbitration must switch to its Slave mode and check to see if an address matches.



**Important:** The I<sup>2</sup>C Specification states that a bus collision cannot occur during a Start condition. If a collision occurs during a Start, BCLIF will be set during the addressing phase.


User software must clear **BCLIF** to resume operation.

Figure 37-42. Bus Collision



PIC18F26/46/56Q84

Figure 37-43. Multi-Master Mode Transmission



# 37.5 Register Definitions: I<sup>2</sup>C Control

Long bit name prefixes for the  $I^2C$  peripherals are shown in the following table. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 37-3. I<sup>2</sup>C Long Bit Name Prefixes

Peripheral	Bit Name Prefix	
I2C1	I2C1	

## 37.5.1 I2CxCON0

Name: I2CxCON0 Offset: 0x0294

I2C Control Register 0

Bit	7	6	5	4	3	2	1	0
	EN	RSEN	S	CSTR	MDR		MODE[2:0]	
Access	R/W	R/W	R/W/HS/HC	R/C/HS/HC	R	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

#### Bit 7 - EN I2C Module Enable<sup>(1,2)</sup>

		To Modale Eliable		
Value Description		Description		
ſ	1	The I <sup>2</sup> C module is enabled		
	0	The I <sup>2</sup> C module is disabled		

## **Bit 6 – RSEN** Restart Enable (used only when MODE = 1xx)

Value	Description				
1	Hardware sets MDR on 9th falling SCL edge (when I2CxCNT = 0 or ACKSTAT = 1)				
0	Hardware issues Stop condition on 9th falling SCL edge (when I2CxCNT = 0 or ACKSTAT = 1)				

## Bit 5 – S Master Start (used only when MODE = 1xx)

Value	Condition	Description
1	MMA = 0:	Set by write to I2CxTXB or S bit, hardware issues Start condition
0	MMA = 0:	Cleared by hardware after sending Start condition
1	MMA = 1 and MDR = 1:	Set by write to I2CxTXB or S bit, communication resumes with a Restart condition
0	MMA = 1 and MDR = 1:	Cleared by hardware after sending Restart condition

## Bit 4 - CSTR Slave Clock Stretching(3)

Value	Condition	Description
1		Clock is held low (clock stretching)
0		Enable clocking, SCL control is released
	SMA = 1 and RXBF = 1 <sup>(6)</sup> :	Set by hardware on 7th falling SCL edge User must read I2CxRXB and clear CSTR to release SCL
	SMA = 1 and TXBE = 1 and I2CxCNT!= 0:	Set by hardware on 8th falling SCL edge User must write to I2CxTXB and clear CSTR to release SCL
	when ADRIE = 1 <sup>(4)</sup> :	Set by hardware on 8th falling edge of matching received address User must clear CSTR to release SCL
	SMA = 1 and WRIE = 1:	Set by hardware on 8th falling SCL edge of received data byte User must clear CSTR to release SCL
	SMA = 1 and ACKTIE = 1:	Set by hardware on 9th falling SCL edge User must clear CSTR to release SCL

#### Bit 3 – MDR Master Data Request (*Master pause*)

Value	Condition	Description		
1		Master state machine pauses until data is read/written		
		(SCL is held low)		
0		Master clocking of data is enabled		
	MMA = 1 and $RXBF = 1$ (pause for $RX$ ):	Set by hardware on 7th falling SCL edge		
		User must read I2CxRXB to release SCL		
	MMA = 1 and TXBE = 1 and I2CxCNT != 0	Set by hardware on the 8th falling SCL edge		
	(pause for TX):	User must write to I2CxTXB to release SCL		

## PIC18F26/46/56Q84

## **I2C - Inter-Integrated Circuit Module**

Value	Condition	Description
	RSEN = 1 and MMA = 1 and (I2CxCNT = 0 or ACKSTAT = 1) (pause for Restart):	Set by hardware on 9th falling SCL edge User must set S bit or write to I2CxTXB to release SCL and issue a Restart condition

#### Bits 2:0 - MODE[2:0] I2C Mode Select

Value	Description	
111	I <sup>2</sup> C Multi-Master mode (SMBus 2.0 Host) <sup>(5)</sup>	
110	I <sup>2</sup> C Multi-Master mode (SMBus 2.0 Host) <sup>(5)</sup>	
101	I <sup>2</sup> C Master mode, 10-bit address	
100	I <sup>2</sup> C Master mode, 7-bit address	
011	I <sup>2</sup> C Slave mode, one 10-bit address with masking	
010	I <sup>2</sup> C Slave mode, two 10-bit addresses	
001	I <sup>2</sup> C Slave mode, two 7-bit addresses with masking	
000	I <sup>2</sup> C Slave mode, four 7-bit addresses	

#### Notes:

- 1. SDA and SCL pins must be configured as open-drain I/Os and use either internal or external pull-up resistors.
- 2. SDA and SCL signals must configure both the input and output PPS registers for each signal.
- 3. CSTR can be set by multiple hardware sources; all sources must be addressed by user software before the SCL line can be released.
- 4. SMA is set on the same SCL edge as CSTR for a matching received address.
- 5. In this mode, ADRIE should be set, allowing an interrupt to clear the BCLIF condition and the ACK of a matching address.
- 6. In 10-bit Slave mode (when ABD = 1), CSTR will be set when the high address has not been read from I2CxRXB before the low address is shifted in.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 746

#### 37.5.2 I2CxCON1

Name: I2CxCON1 Offset: 0x0295

**I2C Control Register 1** 

Bit	7	6	5	4	3	2	1	0
	ACKCNT	ACKDT	ACKSTAT	ACKT	Р	RXO	TXU	CSD
Access	R/W	R/W	R	R	R/S/HC	R/W/HS	R/W/HS	R/W
Reset	0	0	0	0	0	0	0	0

## Bit 7 - ACKCNT Acknowledge End of Count<sup>(2)</sup>

Value	Condition	Description
1	I2CxCNT = 0	Not Acknowledge (NACK) copied to SDA output
0	I2CxCNT = 0	Acknowledge (ACK) copied to SDA output

## Bit 6 - ACKDT Acknowledge Data<sup>(1,2)</sup>

Value	Condition	Description
1	Matching received address	Not Acknowledge (NACK) copied to SDA output
0	Matching received address	Acknowledge (ACK) copied to SDA output
1	<b>I2CxCNT</b> != 0	Not Acknowledge (NACK) copied to SDA output
0	I2CxCNT != 0	Acknowledge (ACK) copied to SDA output

## Bit 5 - ACKSTAT Acknowledge Status (Transmission only)

Value	Description
1	Acknowledge was not received for the most recent transaction
0	Acknowledge was received for the most recent transaction

#### Bit 4 - ACKT Acknowledge Time Status

Value	Description
1	Indicates that the bus is in an Acknowledge sequence, set on the 8th falling SCL edge
0	Not in an Acknowledge sequence, cleared on the 9th rising SCL edge

## Bit 3 - P Master Stop<sup>(4)</sup>

Value	Condition	Description
1	MMA = 1	Initiate a Stop condition
0	MMA = 1	Cleared by hardware after sending Stop

## Bit 2 - RXO Receive Overflow Status (used only when MODE = 0xx or MODE = 11x)(3)

Value	Description
1	Set when SMA = 1 and a master receives data when RXBF = 1
0	No slave receive overflow condition

## **Bit 1 – TXU** Transmit Underflow Status (used only when MODE = 0xx or MODE = 11x)(3)

Value	Description
1	Set when SMA = 1 and a master transmits data when TXBE = 1
0	No slave transmit underflow condition

## Bit 0 – CSD Clock Stretching Disable (used only when MODE = 0xx or MODE = 11x)

Value	Description
1	When SMA = 1, the CSTR bit will not be set
0	Slave clock stretching proceeds normally

## PIC18F26/46/56Q84

## **I2C - Inter-Integrated Circuit Module**

#### Notes:

- 1. Software writes to ACKDT must be followed by a minimum SDA setup time before clearing CSTR.
- 2. A NACK may still be generated by hardware when bus errors are present as indicated by the I2CxSTAT1 or I2CxERR registers.
- 3. This bit can only be set when CSD = 1.
- 4. If SCL is high (SCL = 1) when this bit is set, the current clock pulse will complete (SCL = 0) with the proper SCL/SDA timing required for a valid Stop condition; any data in the transmit or receive shift registers will be lost

## 37.5.3 I2CxCON2

Name: I2CxCON2 Offset: 0x0296

I2C Control Register 2

Bit	7	6	5	4	3	2	1	0
	ACNT	GCEN	FME	ABD	SDAH	IT[1:0]	BFRE	ET[1:0]
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

## Bit 7 - ACNT Auto-Load I2C Count Register Enable

Value	Description
1	The first transmitted/received byte after the address is automatically loaded into the I2CxCNT register
0	Auto-load of I2CxCNT is disabled

#### Bit 6 – GCEN General Call Address Enable (used when MODE = 00x or MODE = 11x)

Value	Description
1	General Call Address (0x00) causes an address match event
0	General Call Addressing is disabled

#### Bit 5 - FME Fast Mode Enable

Value	Description
1	SCL frequency (F <sub>SCL</sub> ) = F <sub>I2CxCLK</sub> / <b>4</b>
0	SCL frequency (F <sub>SCL</sub> ) = F <sub>I2CxCLK</sub> / <b>5</b>

## Bit 4 - ABD Address Buffer Disable

Value	Description
1	Address buffers are disabled;
	Received address is loaded into I2CxRXB, address to transmit is loaded into I2CxTXB
0	Address buffers are enabled;
	Received address is loaded into I2CxADB0/I2CxADB1, address to transmit is loaded into I2CxADB0/
	I2CxADB1

## Bits 3:2 - SDAHT[1:0] SDA Hold Time Selection

Value	Description
11	Reserved
10	Minimum of 30 ns hold time on SDA after the falling SCL edge
01	Minimum of 100 ns hold time on SDA after the falling SCL edge
00	Minimum of 300 ns hold time on SDA after the falling SCL edge

## Bits 1:0 - BFRET[1:0] Bus Free Time Selection

Value	Description
11	64 I2CxCLK pulses
10	32 I2CxCLK pulses
01	16 I2CxCLK pulses
00	8 I2CxCLK pulses

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 749

## 37.5.4 I2CxSTAT0

Name: I2CxSTAT0 Offset: 0x0298

## I2C Status Register 0

Bit	7	6	5	4	3	2	1	0
	BFRE	SMA	MMA	R	D			
Access	R	R	R	R	R			
Reset	0	0	0	0	0			

## Bit 7 - BFRE Bus Free Status<sup>(2)</sup>

Value	Description
1	Indicates an Idle bus; both SCL and SDA have been high for the time selected by the BFRET bits
0	Bus is not Idle

#### Bit 6 - SMA Slave Mode Active Status

Value	Description
1	Slave mode is active
	Set after the 8th falling SCL edge of a received matching 7-bit slave address
	Set after the 8th falling SCL edge of a matching received 10-bit slave <b>low</b> address
	Set after the 8th falling SCL edge of a received matching 10-bit slave high w/read address, only after a
	previous received matching high and low w/write address
0	Slave mode is not active
	Cleared when any Restart/Stop condition is detected on the bus
	Cleared by BTOIF and BCLIF conditions

## Bit 5 - MMA Master Mode Active Status

Value	Description
1	Master mode is active
	Set when master state machine asserts a Start condition
0	Master mode is not active
	Cleared when BCLIF is set
	Cleared when Stop condition is issued
	Cleared for BTOIF condition after the master successfully shifts out a Stop condition

## Bit 4 - R Read Information(1)

Value	Description
1	Indicates that the last matching received address was a Read request
0	Indicates that the last matching received address was a Write request

#### Bit 3 - D Data

Value	Description
1	Indicates that the last byte received or transmitted was data
0	Indicates that the last byte received or transmitted was an address

#### Notes:

- This bit holds the R/W bit information following the last received address match. Addresses transmitted by the
  master do not affect the master's R bit, and addresses appearing on the bus without a match do not affect the
  R bit.
- 2. I2CxCLK must have a valid clock source selected for this bit to function.

## 37.5.5 I2CxSTAT1

Name: I2CxSTAT1 Offset: 0x0299

I2C Status Register 1

Bit	7	6	5	4	3	2	1	0
	TXWE		TXBE		RXRE	CLRBF		RXBF
Access	R/W/HS		R		R/W/HS	R/S		R
Reset	0		1		0	0		0

## Bit 7 - TXWE Transmit Write Error Status<sup>(1)</sup>

	Value	Description
ſ	1	A new byte of data was written into I2CxTXB when it was full (must be cleared by software)
	0	No transmit write error occurred

## Bit 5 - TXBE Transmit Buffer Empty Status<sup>(2)</sup>

Value	Description
1	I2CxTXB is empty (cleared by writing to the I2CxTXB register)
0	I2CxTXB is full

#### Bit 3 - RXRE Receive Read Error Status<sup>(1)</sup>

V	'alue	Description
1		A byte of data was read from I2CxRXB when it was empty (must be cleared by software)
0		No receive overflow occurred

## Bit 2 - CLRBF Clear Buffer(3)

Value	Description
1	Setting this bit clears/empties the receive and transmit buffers, causing a Reset of RXBF and TXBE
	Setting this bit clears the I2CxRXIF and I2CxTXIF interrupt flags

## Bit 0 - RXBF Receive Buffer Full Status<sup>(2)</sup>

Value	Description
1	I2CxRXB is full (cleared by reading the I2CxRXB register)
0	I2CxRXB is empty

#### Notes:

- 1. This bit, when set, will cause a NACK to be issued.
- 2. Used as a trigger source for DMA operations.
- 3. This bit is special function; it can only be set by user software and always reads '0'.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 751

#### 37.5.6 I2CxPIR

Name: I2CxPIR Offset: 0x029A

**I2C Interrupt Flag Register** 

Bit	7	6	5	4	3	2	1	0
	CNTIF	ACKTIF		WRIF	ADRIF	PCIF	RSCIF	SCIF
Access	R/W/HS	R/W/HS		R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS
Reset	0	0		0	0	0	0	0

## Bit 7 - CNTIF Byte Count Interrupt Flag<sup>(1)</sup>

	Value	Description
	1	Set on the 9th falling SCL edge when I2CxCNT = 0
(	0	I2CxCNT value is not zero

## Bit 6 - ACKTIF Acknowledge Status Time Interrupt Flag (used only when MODE = 0xx or MODE = 11x)(1,2)

Value	Description
1	Acknowledge sequence detected, set on the 9th falling SCL edge for any byte when addressed as a
	slave
0	Acknowledge sequence not detected

## Bit 4 – WRIF Data Write Interrupt Flag (used only when MODE = 0xx or MODE = 11x)(1)

Value	e Description
1	Data byte detected, set on the 8th falling SCL edge for a received data byte
0	Data byte not detected

### Bit 3 – ADRIF Address Interrupt Flag (used only when MODE = 0xx or MODE = 11x)(1)

Value	Description
1	Address detected, set on the 8th falling SCL edge for a matching received address byte
0	Address not detected

#### Bit 2 - PCIF Stop Condition Interrupt Flag(1)

	en etop condition menuper lag
Value	Description
1	Stop condition detected
0	Stop condition not detected

## Bit 1 - RSCIF Restart Condition Interrupt Flag<sup>(1)</sup>

Value	Description
1	Restart condition detected
0	Restart condition not detected

#### Bit 0 - SCIF Start Condition Interrupt Flag(1)

	311 0 0011	Ctart Condition intorrupt riag
	Value	Description
ſ	1	Start condition detected
	0	Start condition not detected

#### Notes:

- 1. Enabled interrupt flags are OR'ed to produce the PIRx[I2CxIF] bit.
- 2. ACKTIF is not set by a matching 10-bit high address byte with the R/W bit clear. It is only set after the matching low address byte is shifted in.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 752

#### 37.5.7 I2CxPIE

Name: I2CxPIE Offset: 0x029B

I2C Interrupt and Hold Enable Register

Bit	7	6	5	4	3	2	1	0
	CNTIE	ACKTIE		WRIE	ADRIE	PCIE	RSCIE	SCIE
Access	R/W	R/W		R/W	R/W	R/W	R/W	R/W
Reset	0	0		0	0	0	0	0

#### Bit 7 - CNTIE Byte Count Interrupt Enable(1)

Value	Description
1	Enables Byte Count interrupts
0	Disables Byte Count interrupts

## Bit 6 – ACKTIE Acknowledge Status Time Interrupt and Hold Enable<sup>(1,2)</sup>

1	Value	Description
	1	Enables Acknowledge Status Time Interrupt and Hold condition
	0	Disables Acknowledge Status Time Interrupt and Hold condition

#### Bit 4 - WRIE Data Write Interrupt and Hold Enable<sup>(1,3)</sup>

Value	Description
1	Enables Data Write Interrupt and Hold condition
0	Disables Data Write Interrupt and Hold condition

## Bit 3 - ADRIE Address Interrupt and Hold Enable(1,4)

Value	Description
1	Enables Address Interrupt and Hold condition
0	Disables Address Interrupt and Hold condition

### Bit 2 - PCIE Stop Condition Interrupt Enable(1)

١	Value	Description	
	1	Enables interrupt on the detection of a Stop condition	
	0	Disables interrupt on the detection of a Stop condition	

## Bit 1 - RSCIE Restart Condition Interrupt Enable(1)

Value	Description
1	Enables interrupt on the detection of a Restart condition
0	Disables interrupt on the detection of a Restart condition

## Bit 0 - SCIE Stop Condition Interrupt Enable(1)

Value	Description
1	Enables interrupt on the detection of a Start condition
0	Disables interrupt on the detection of a Start condition

#### Notes:

- 1. Enabled interrupt flags are OR'ed to produce the PIRx[I2CxIF] bit.
- When ACKTIE is set (ACKTIE = 1) and ACKTIF becomes set (ACKTIF = 1), if an ACK is generated, CSTR is also set. If a NACK is generated, CSTR remains unchanged.
- 3. When WRIE is set (WRIE = 1) and WRIF becomes set (WRIF = 1), CSTR is also set.
- 4. When ADRIE is set (ADRIE = 1) and ADRIF becomes set (ADRIF = 1), CSTR is also set.

#### 37.5.8 I2CxERR

Name: I2CxERR Offset: 0x0297

**I2C Error Register** 

Bit	7	6	5	4	3	2	1	0
		BTOIF	BCLIF	NACKIF		BTOIE	BLCIE	NACKIE
Access		R/W/HS	R/W/HS	R/W/HS		R/W	R/W	R/W
Reset		0	0	0		0	0	0

#### Bit 6 - BTOIF Bus Timeout Interrupt Flag(1,2)

2.00 2.00 2ao milionapi ing	
Value	Description
1	Bus timeout event occurred
0	No bus timeout event occurred

#### Bit 5 - BCLIF Bus Collision Detect Interrupt Flag<sup>(1)</sup>

Value	Description
1	Bus collision detected
0	No bus collision occurred

## Bit 4 - NACKIF NACK Detect Interrupt Flag<sup>(1,3,4)</sup>

Value	Description
1	NACK detected on the bus (when SMA = 1 or MMA = 1)
0	No NACK detected on the bus

## Bit 2 - BTOIE Bus Timeout Interrupt Enable

Value	Description
1	Enable Bus Timeout interrupts
0	Disable Bus Timeout interrupts

#### Bit 1 - BLCIE Bus Collision Detect Interrupt Enable

Bit i Bedie Bad Comoion Botoot intorrapt Emasic	
Value	Description
1	Enable Bus Collision interrupts
0	Disable Bus Collision interrupts

## Bit 0 - NACKIE NACK Detect Interrupt Enable

Value	Description
1	Enable NACK detect interrupts
0	Disable NACK detect interrupts


## Notes:

- 1. Enabled error interrupt flags are OR'ed to produce the PIRx[I2CxEIF] bit.
- 2. User software must select the Bus Timeout source in the I2CxBTOC register.
- 3. NACKIF is also set when any of the TXWE, RXRE, TXU, or RXO bits are set.
- 4. NACKIF is not set for the NACK response to a non-matching slave address.

## 37.5.9 I2CxCLK

Name: I2CxCLK Offset: 0x029E

I2C Clock Selection Register



Bits 4:0 – CLK[4:0] I2C Clock Selection Table 37-4.

CLK	Selection
11000-11111	Reserved
10111	CLC8_out
10110	CLC7_out
10101	CLC6_out
10100	CLC5_out
10011	CLC4_out
10010	CLC3_out
10001	CLC2_out
10000	CLC1_out
01111	SMT1 overflow
01100-01110	Reserved
01011	TU16B_out
01010	TU16A_out
01001	TMR6 post scaled output
01000	TMR4 post scaled output
00111	TMR2 post scaled output
00110	TMR0 overflow
00101	EXTOSC
00100	Clock Reference output
00011	MFINTOSC (500 kHz)
00010	HFINTOSC
00001	F <sub>OSC</sub>
00000	F <sub>OSC</sub> /4


## PIC18F26/46/56Q84

## **I2C - Inter-Integrated Circuit Module**

## 37.5.10 I2CxBAUD

Name: I2CxBAUD Offset: 0x029D

I2C Baud Rate Prescaler



Bits 7:0 - BAUD[7:0] Baud Rate Prescaler Selection

Valu	ıe	Description
n		Prescaled I2C Clock Frequency ( $F_{PRECLK}$ ) = $\frac{I2CxCLK}{(BAUD + 1)}$

**Note:** It is recommended to write this register only when the module is Idle (MMA = 0 or SMA = 0), or when the module is clock stretching (CSTR = 1 or MDR = 1).

# 37.5.11 I2CxCNT

Name: I2CxCNT Offset: 0x028C

I2C Byte Count Register<sup>(1,2)</sup>

Bit	15	14	13	12	11	10	9	8			
	CNT[15:8]										
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W			
Reset	0	0	0	0	0	0	0	0			
Bit	7	6	5	4	3	2	1	0			
	CNT[7:0]										
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W			
Reset	0	0	0	0	0	0	0	0			

# Bits 15:0 - CNT[15:0] Byte Count

Condition	Description
If receiving data:	Count value decremented on 8th falling SCL edge when a new byte is loaded into I2CxRXB
If transmitting data:	Count value is decremented on the 9th falling SCL edge when a new byte is moved from
	I2CxTXB

#### Notes:

- 1. It is recommended to write this register only when the module is idle (MMA = 0 or SMA = 0), or when the module is clock stretching (CSTR =1 or MDR = 1).
- 2. CNTIF is set on the 9th falling SCL edge when I2CxCNT = 0.

# 37.5.12 I2CxBTO

Name: I2CxBTO Offset: 0x029C

I2C Bus Timeout Register(1)

Bit	7	6	5	4	3	2	1	0
	TOREC	TOBY32			TOTIN	1E[5:0]		
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

### Bit 7 - TOREC Timeout Recovery Selection

Value	Description
1	A BTO event will reset the I2C module and set BTOIF.
0	A BTO event will set BTOIF, but will not reset the I2C module.

### Bit 6 - TOBY32 Timeout Prescaler Extension Enable<sup>(2)</sup>

Value	Description
1	BTO time = TOTIME * T <sub>BTOCLK</sub>
0	BTO time = TOTIME * T <sub>BTOCLK</sub> * 32

# Bits 5:0 - TOTIME[5:0] Timeout Time Selection

Value	Condition	Description
n	TOBY32 = 1	Timeout is TOTIME periods of the prescaled BTO clock (TOTIME = n * T <sub>BTOCLK</sub> )
n	TOBY32 = 0	Timeout is TOTIME periods of the prescaled BTO clock multiplied by 32 (TOTIME = n *
		T <sub>BTOCLK</sub> * <b>32</b> )

### Notes:


- 1. It is recommended to write this register only when the module is Idle (MMA = 0 or SMA = 0), or when the module is clock stretching (CSTR = 1 or MDR = 1).
- 2. When TOBY32 is set (TOBY32 = 1) and the LFINTOSC, MFINTOSC, or SOSC is selected as the BTO clock source, the timeout time (TOTIME) will be approximately in milliseconds.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 758

# 37.5.13 I2CxBTOC

Name: I2CxBTOC Offset: 0x029F

**I2C Bus Timeout Clock Source Selection** 



Bits 3:0 – BTOC[3:0] Bus Timeout Clock Source Selection Table 37-5.

втос	Selection
1111 - 1001	Reserved
1000	SOSC
0111	MFINTOSC (32 kHz)
0110	LFINTOSC
0101	TU16B_out
0100	TU16A_out
0011	TMR6_postscaled
0010	TMR4_postscaled
0001	TMR2_postscaled
0000	Reserved

# 37.5.14 [I2CxADB0]

Name: I2CxADB0 Offset: 0x028E

I2C Address Buffer 0 Register<sup>(1)</sup>

Bit	7	6	5	4	3	2	1	0	
	ADB[7:0]								
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	0	0	0	0	0	0	0	0	

Bits 7:0 - ADB[7:0] I2C Address Buffer 0

Condition	Description
7-bit Slave/Multi-Master modes (MODE = 00x or	ADB[7:1]: Received matching 7-bit slave address
11x <b>)</b> :	ADB[0]: Received R/W value from 7-bit address
10-bit Slave modes (MODE = 01x):	ADB[7:0]: Received matching lower eight bits of 10-bit
	slave address
7-bit Master mode (MODE = 100):	Unused in this mode
10-bit Master mode (MODE = 101):	ADB[7:0]: Eight Least Significant bits of the 10-bit slave
	address

# Note:

1. This register is read-only except in Master 10-bit Address mode (MODE = 101).

# 37.5.15 I2CxADB1

Name: I2CxADB1 Offset: 0x028F

I2C Address Buffer 1 Register<sup>(1)</sup>

Bit	7	6	5	4	3	2	1	0
				ADB	3[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - ADB[7:0] I2C Address Buffer 1

7.0 - ADD[7.0] 120 / Idd 1635 Daller 1					
Condition	Description				
7-bit Slave modes (MODE = 00x):	Unused in this mode				
10-bit Slave modes (MODE = 01x):	ADB[7:1]: Received matching 10-bit slave address high byte ADB[0]: Received R/W value from 10-bit high address byte				
7-bit Master mode (MODE = 100):	ADB[7:1]: 7-bit slave address ADB[0]: R/W value				
10-bit Master mode (MODE = 101):	ADB[7:1]: 10-bit slave high address byte ADB[0]: R/W value				
7-bit Multi-Master modes (MODE = 11x):	ADB[7:1]: 7-bit slave address ADB[0]: R/W value				

# Note:

1. This register is read-only in 7-bit Slave Address modes (MODE = 0xx).

# PIC18F26/46/56Q84

# **I2C - Inter-Integrated Circuit Module**

# 37.5.16 I2CxADR0

Name: I2CxADR0 Offset: 0x0290

I2C Address 0 Register

Bit	7	6	5	4	3	2	1	0	
	ADR[7:0]								
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	1	1	1	1	1	1	1	1	

Bits 7:0 - ADR[7:0] 12C Slave Address 0

Condition	Description
7-bit Slave/Multi-Master modes (MODE = 00x or 11x):	ADR[7:1]: 7-bit slave address
	ADR[0]: Unused; bit state is 'don't care'
10-bit Slave modes (MODE = 01x):	ADR[7:0]: Eight Least Significant bits of first 10-bit address

# 37.5.17 I2CxADR1

Name: I2CxADR1 Offset: 0x0291

I2C Address 1 Register



Bits 7:1 - ADR[6:0] I2C Slave Address 1

Condition	Description
7-bit Slave/Multi-Master modes (MODE = 000 or	7-bit slave address 1
110 <b>)</b> :	
7-bit Slave/Multi-Master modes with Masking (MODE	7-bit slave address mask for I2CxADR0
= 011 <b>or</b> 111 <b>)</b> :	
10-bit Slave mode (MODE = 010):	ADR[7:3]: Bit pattern (11110) as defined by the I <sup>2</sup> C
	Specification <sup>(1)</sup>
	ADR[2:1]: Two Most Significant bits of first 10-bit address
10-bit Slave mode with Masking (MODE = 011):	ADR[7:3]: Bit pattern (11110) as defined by the I <sup>2</sup> C
	Specification <sup>(1)</sup>
	ADR[2:1]: Two Most Significant bits of 10-bit address

# Note:

1. The '11110' bit pattern used in the 10-bit address high byte is defined by the I<sup>2</sup>C Specification. It is up to the user to define these bits. These bit values are compared to the received address by hardware to determine a match. The bit pattern transmitted by the master must be the same as the slave address's bit pattern used for comparison or a match will not occur.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 763

# PIC18F26/46/56Q84

# **I2C - Inter-Integrated Circuit Module**

# 37.5.18 I2CxADR2

Name: I2CxADR2 Offset: 0x0292

I2C Address 2 Register

Bit	7	6	5	4	3	2	1	0
	ADR[7:0]							
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

Bits 7:0 - ADR[7:0] I2C Slave Address 2

bits 1.0 - Abit[1.0] 120 Glave Addiess 2						
Description						
ADR[7:1]: 7-bit slave address 2						
ADR[0]: Unused; bit state is 'don't care'						
ADR[7:1]: 7-bit slave address						
ADR[0]: Unused; bit state is 'don't care'						
ADR[7:0]: Eight Least Significant bits of the second 10-						
bit address						
ADR[7:0]: Eight Least Significant bits of 10-bit address						
mask						

# 37.5.19 I2CxADR3

Name: I2CxADR3 Offset: 0x0293

I2C Address 3 Register<sup>(1)</sup>



### Bits 7:1 - ADRI6:01 I2C Slave Address 3

DILS 7.1 - ADIN[0.0] 120 Slave Address 5	
Name	Description
7-bit Slave/Multi-Master modes (MODE = 000 or	7-bit slave address 3
110 <b>)</b> :	
7-bit Slave/Multi-Master modes with Masking	7-bit slave address mask for I2CxADR2
(MODE = 001 or 111):	
10-bit Slave mode (MODE = 010):	ADR[7:3]: Bit pattern (11110) as defined by the I <sup>2</sup> C
	Specification <sup>(1)</sup>
	ADR[2:1]: Two Most Significant bits of second 10-bit address
10-bit Slave mode with Masking (MODE = 011):	ADR[7:3]: Bit pattern (11110) as defined by the I <sup>2</sup> C
	Specification <sup>(1)</sup>
	ADR[2:1]: Two Most Significant bits of 10-bit address mask

# Note:

1. The '11110' bit pattern used in the 10-bit address high byte is defined by the I<sup>2</sup>C Specification. It is up to the user to define these bits. These bit values are compared to the received address by hardware to determine a match. The bit pattern transmitted by the master must be the same as the slave address's bit pattern used for comparison or a match will not occur.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 765

# 37.5.20 I2CxTXB

Name: I2CxTXB Offset: 0x028B

I2C Transmit Buffer Register(1)

Bit	7	6	5	4	3	2	1	0
				TXB	[7:0]			
Access	W	W	W	W	W	W	W	W
Reset	x	X	X	x	X	X	x	x

Bits 7:0 - TXB[7:0] I2C Transmit Buffer

**Note:** This register is write-only. Reading this register will return a value of  $0 \times 0 = 0$ .

# 37.5.21 I2CxRXB

Name: I2CxRXB Offset: 0x028A

I2C Receive Buffer<sup>(1)</sup>

Bit	7	6	5	4	3	2	1	0
				RXB	[7:0]			
Access	R	R	R	R	R	R	R	R
Reset	X	X	X	X	X	X	X	X

Bits 7:0 - RXB[7:0] I2C Receive Buffer

**Note:** This register is read-only. Writes to this register are ignored.

# 37.6 Register Summary - I2C

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x0289										
0x028A	I2C1RXB	7:0				RXE	B[7:0]	•		
0x028B	I2C1TXB	7:0				TXE	8[7:0]			
0x028C	I2C1CNT	7:0				CNT	[7:0]			
0x026C	IZCTCINT	15:8				CNT	[15:8]			
0x028E	I2C1ADB0	7:0				ADE	3[7:0]			
0x028F	I2C1ADB1	7:0				ADE	3[7:0]			
0x0290	I2C1ADR0	7:0		ADR[7:0]						
0x0291	I2C1ADR1	7:0		ADR[6:0]						
0x0292	I2C1ADR2	7:0				ADF	R[7:0]			
0x0293	I2C1ADR3	7:0				ADR[6:0]				
0x0294	I2C1CON0	7:0	EN	RSEN	S	CSTR	MDR		MODE[2:0]	
0x0295	I2C1CON1	7:0	ACKCNT	ACKDT	ACKSTAT	ACKT	Р	RXO	TXU	CSD
0x0296	I2C1CON2	7:0	ACNT	GCEN	FME	ABD	SDAH	IT[1:0]	BFRE	ET[1:0]
0x0297	I2C1ERR	7:0		BTOIF	BCLIF	NACKIF		BTOIE	BLCIE	NACKIE
0x0298	I2C1STAT0	7:0	BFRE	SMA	MMA	R	D			
0x0299	I2C1STAT1	7:0	TXWE		TXBE		RXRE	CLRBF		RXBF
0x029A	I2C1PIR	7:0	CNTIF	ACKTIF		WRIF	ADRIF	PCIF	RSCIF	SCIF
0x029B	I2C1PIE	7:0	CNTIE	ACKTIE		WRIE	ADRIE	PCIE	RSCIE	SCIE
0x029C	I2C1BTO	7:0	TOREC	TOBY32			TOTIN	/IE[5:0]		
0x029D	I2C1BAUD	7:0				BAU	D[7:0]			
0x029E	I2C1CLK	7:0						CLK[4:0]		
0x029F	I2C1BTOC	7:0						ВТО	C[3:0]	

# 38. CAN FD - Controller Area Network, Flexible Data-Rate

This family of devices contain a Controller Area Network Flexible Data-Rate (CAN FD) module. CAN FD is a serial interface which is useful for communicating with other peripherals or microcontroller devices. This interface, or protocol, was designed to allow communications within noisy environments.

The CAN FD module is a communication controller, implementing the CAN FD protocol as defined in the BOSCH specification. This module supports CAN 1.2, CAN 2.0A, CAN 2.0B Passive, CAN 2.0B Active and CAN FD versions of the protocol. The module implementation is a full CAN FD system; however, the CAN specification is not covered within this data sheet. Refer to the BOSCH CAN specification for further details.

CAN FD has two primary enhancements over CAN 2.0:

- The maximum data field size is increased from 8 bytes to 64 bytes.
- · The data rate can optionally be switched to a faster bit rate after the arbitration field.

The CAN FD controller is capable of sending and receiving CAN 2.0 messages, and both CAN FD messages and CAN 2.0 messages can exist on the same bus. However, this does not mean that CAN FD and CAN 2.0 controllers should be mixed on the same bus, as CAN 2.0 controllers will generate error frames upon receiving a CAN FD message.

Features of the CAN FD module include:

#### General

- · Nominal (arbitration) bit rate up to 1 Mbps
- · Data bit rate up to 4 Mbps (dependent on oscillator selection)
- · CAN FD Controller modes:
  - Mixed CAN 2.0B and CAN FD mode
  - CAN 2.0B mode
- Conforms to ISO11898-1:2015

# Message FIFOs

- · 3 FIFOs configurable as transmit or receive FIFOs
- One Transmit Queue (TXQ)
- · Transmit Event FIFO (TEF) with 32-bit timestamp

### **Message Transmission**

- Message transmission prioritization:
  - Based on priority bit field and/or
  - Message with lowest ID gets transmitted first using the TXQ
- · Programmable automatic retransmission attempts: unlimited, three attempts or disabled

#### **Message Reception**

- 12 flexible filter and mask objects
- · Each object can be configured to filter either:
  - Standard ID and first 18 data bits or
  - Extended ID
- · 32-Bit timestamp

# 38.1 Module Overview

The CAN FD module implements several aspects of the CAN FD protocol:

The Bit Stream Processor (BSP) is an implementation of the Medium Access Control (MAC) of the CAN FD
protocol described in ISO 11898-1:2015. It serializes and describing the bit stream, encodes and decodes
the CAN FD frames, manages the medium access, acknowledges frames, and detects and signals errors.

- 2. The TX handler prioritizes the messages that are requested for transmission by the transmit FIFOs. It uses the RAM interface to fetch the transmit data from RAM and provides it to the BSP for transmission.
- The BSP provides received messages to the RX handler. The RX handler uses an acceptance filter, which
  filters the messages that are to be stored in the receive FIFOs. It uses the RAM interface to store received
  data into the RAM.
- 4. Each FIFO can be configured either as a transmit or receive FIFO. The FIFO control keeps track of the FIFO head and tail and calculates the user address. In a TX FIFO, the user address points to the address in RAM where the data for the next transmit message is stored. In an RX FIFO, the user address points to the address in RAM where the data of the next receive message will be read. The user notifies the FIFO that a message is written to or read from RAM by incrementing the head/tail of the FIFO.
- 5. The TXQ is a special transmit FIFO that transmits the messages, based on the ID of the messages stored in the gueue.
- 6. The TEF stores the message IDs of the transmitted messages.
- 7. A free-running Time Base Counter (TBC) is used to timestamp received messages. Messages in the TEF can also be timestamped.
- The CAN FD controller module generates interrupts when new messages are received or when messages are transmitted successfully.

The CANRX input pin is selected with the CANRXPPS register. The CANTX output pin is selected with each pin's RxyPPS register.

**Note:** The CANRX pin defaults to pin RB3, but the CANTX has no default location and must be assigned to a pin before CAN transmissions can occur.

In modes that enable the CANRX pin, the user must ensure that the appropriate TRIS bit for CANRX is set to configure the pin as an input, and the associated ANSEL bit for that pin is cleared to enable the digital input buffer. In addition, in modes that enable the CANTX pin, the appropriate TRIS bit for the associated pin must be cleared to enable pin output.


### 38.1.1 Module Functionality

The CAN FD module consists of the CAN message/protocol handler and the device RAM devoted to CAN FIFOs. The protocol handler performs the needed CAN protocol actions, transferring data in and out of the FIFOs as defined by the firmware (see Figure 38-1).

The following sequence illustrates the necessary initialization steps before the CAN module can be used to transmit or receive a message. Steps can be added or removed depending on the requirements of the application.

- Use the CANRXPPS and appropriate RxyPPS registers to map the CANRX and CANTX functions to the desired pins of the device.
- 2. Initialize LAT, TRIS and ANSEL bits for the selected CANRX and CANTX pins.
- 3. Ensure that the CAN module is in Configuration mode.
- 4. Set up Baud Rate registers.
- 5. Ensure FIFOs are properly configured as transmit/receive.
- 6. Set up Filter and Mask registers.
- 7. If desired, populate transmit FIFOs with data to transmit.
- 8. Set the CAN module to Normal/Normal CAN FD or any other mode required by the application logic.

Figure 38-1. CAN FD Module Simplified Block Diagram



# 38.2 Modes of Operation

The CAN FD Protocol Module has eight modes of operation:

- · Configuration mode
- · Normal CAN FD mode: Supports mixing of CAN FD and CAN 2.0 messages.
- Normal CAN 2.0 mode: Will generate error frames when receiving CAN FD messages. The FDF bit is forced to zero and only CAN 2.0 frames are sent, even if the FDF bit is set in the transmit message object.
- Disable mode
- · Listen Only mode
- · Restricted Operation mode

- · Internal Loopback mode
- · External Loopback mode

The modes of operations can be grouped into four main groups: Configuration, Normal, Sleep and Debug (see Figure 38-2).

### 38.2.1 Mode Change

Figure 38-2 illustrates the possible mode transitions. New modes of operation are requested by writing to the REQOP[2:0] (C1CON[26:24]) bits. The modes of operations do not change immediately. The modes will only change when the bus is Idle.

The current operating mode is indicated by the OPMOD[2:0] (C1CON[23:21]) bits. The application can enable an interrupt on an OPMODx change or poll the OPMODx bits.

### 38.2.1.1 Changing Between Normal Modes

Directly changing between Normal modes is not allowed. The Configuration mode must be selected before a new Normal mode can be selected.

### 38.2.1.2 Changing Between Debug Modes

Directly changing between Debug modes is not allowed. The Configuration mode must be selected before a new Debug mode can be selected.

### 38.2.1.3 Exiting Normal Mode

The device will transition to Configuration or Sleep mode only after the current message is transmitted.

### 38.2.1.4 Entering and Exiting Disable Mode

The CAN FD Protocol Module enters Disable mode after a Disable mode request. The device exits Disable mode after a mode request.


If WAKIE is set, a dominant edge on CxRX will generate an interrupt. The CPU has to enable the CAN module by requesting a Normal mode.

#### 38.2.1.5 Bus Integrating Mode

The CAN FD Protocol module integrates to the bus according to the ISO11898-1:2015 specifications (eleven consecutive recessive bits), under the following conditions:

- · Change from Configuration mode to one of the Normal modes or Debug modes
- · Change from Disable mode to one of the Normal modes

Figure 38-2. Modes of Operation



# 38.2.2 Configuration Mode

After Reset, the CAN FD Protocol Module is in Configuration mode. The error counters are cleared and all registers contain the Reset values.

The CAN FD Protocol Module must be initialized before activation. This is only possible when the module is in Configuration mode, OPMOD[2:0] = 100. The Configuration mode is requested by setting REQOP[2:0] = 100.

The CAN FD Protocol module will protect the user from accidentally violating the CAN protocol through programming errors. The following registers and bit fields can only be programmed during Configuration mode:

- CxCON: WAKFIL, CLKSEL, PXEDIS, ISOCRECEN, TXQEN, STEF, SERRLOM, ESIGM, RTXAT
- CxNBTCFG, C1DBTCFG and C1TDC

# CAN FD - Controller Area Network, Flexible ...

- CxTXQCON: PLSIZE[2:0], FSIZE[4:0]
- CxFIFOCON: TXEN, RXTSEN, PLSIZE[2:0], FSIZE[4:0]
- CxTEFCON: TEFTSEN, FSIZE[4:0]
- CxFIFOBA

The CAN FD Protocol module is not allowed to enter Configuration mode during transmission or reception to prevent the module from causing errors on the CAN bus. The following registers are Reset when exiting Configuration mode:

- CxTREC
- CxBDIAG0
- CxBDIAG1

In Configuration mode, FRESET is set in the CxFIFOCON, CxTXQCON, and CxTEFCON registers, and all FIFOs and the TXQ are Reset.

#### 38.2.3 Normal Modes

#### 38.2.3.1 Normal CAN FD Mode

Once the device is configured, Normal Operation mode can be requested by setting REQOP[2:0] = 000. In this mode, the device will be on the CAN bus. It can transmit and receive messages in CAN FD mode, Bit Rate Switching can be enabled and up to 64 data bytes can be transmitted and received.

#### 38.2.3.2 Normal CAN 2.0 Mode

The Normal CAN 2.0 Operation mode can be requested by setting REQOP[2:0] = 110. In this mode, the device will be on the CAN bus. This is a the Classic CAN 2.0 mode. The module will not receive CAN FD frames. It might send error frames if CAN FD frames are detected on the bus. The FDF, BRS and ESI bits in the TX objects will be ignored and transmitted as '0'.

#### 38.2.4 Disable Mode

Disable mode is similar to Configuration mode, except the error counters are not Reset. Disable mode is requested by setting REQOP[2:0] = 001. The CAN module will not be allowed to enter Disable mode while a transmission or reception is taking place to prevent causing errors on the CAN bus. The module will enter Disable mode when the current message completes.

The OPMODx bits indicate whether the module successfully entered Disable mode. The application software should use this bit field as a handshake indication for the Disable mode request. The CxTX pin will stay in the recessive state while the module is in Disable mode to prevent inadvertent CAN bus errors.

### 38.2.5 Debug Modes

### 38.2.5.1 Listen Only Mode

Listen Only mode is a variant of Normal CAN FD Operation mode. If the Listen Only mode is activated, the module on the CAN bus is passive. It will receive messages, but it will not transmit any bits. TXREQx bits will be ignored. No error flags or Acknowledge signals are sent. The error counters are deactivated in this state. The Listen Only mode can be used for detecting the baud rate on the CAN bus. It is necessary that there are at least two further nodes that communicate with each other. The baud rate can be detected empirically by testing different values until a message is received successfully. This mode is also useful for monitoring the CAN bus without influencing it.

# 38.2.5.2 Restricted Operation Mode

In Restricted Operation mode, the node is able to receive data and remote frames, and to Acknowledge valid frames, but it does not send data frames, remote frames, error frames or overload frames. In case of an error or overload condition, it does not send dominant bits; instead, it waits for the bus to enter the Idle condition to resynchronize itself to the CAN communication. The error counters are not incremented.

#### 38.2.5.3 Loopback Mode

Loopback mode is a variant of Normal CAN FD Operation mode. This mode will allow internal transmission of messages from the transmit FIFOs to the receive FIFOs. The module does not require an external Acknowledge from the bus. No messages can be received from the bus, because the CxRX pin is disconnected.

#### 38.2.5.3.1 Internal Loopback Mode

The transmit signal is internally connected to receive and the CxTX pin is driven high.

#### 38.2.5.3.2 External Loopback Mode

The transmit signal is internally connected to receive and transmit messages and can be monitored on the CxTX pin.

#### 38.2.6 Low-Power Modes

#### 38.2.6.1 Sleep Mode

In the CAN module, special conditions need to be met for Sleep mode. The module must first be switched to Disable mode by setting REQOPx = 001. When OPMODx = 001, indicating Disable mode has been achieved, the CAN FD Protocol Module enters Sleep mode after a Sleep mode request.

In Sleep mode, the register content does not change, so the OPMODx bits do not change. At the end of Sleep, the module will continue in the mode specified by the OPMODx bits previous to Sleep mode (which should be Disable mode, OPMODx = 001). If the user executes a SLEEP instruction without switching to Disable mode, the module assumes a clock is available to read/write from RAM. Since the system clock input is not available in Sleep mode, the CAN module cannot run as it requires a system clock to transmit or receive. Also, the FIFO is in system RAM, which has no clock in Sleep mode.

Recommended steps:

- 1. Write the REQOP[2:0] bits to '001'; the module will enter Disable mode.
- 2. Poll the OPMOD[2:0] bits to verify whether they are '001', which indicates that the module has successfully entered Disable mode.
- 3. Execute the SLEEP instruction.

#### 38.2.6.2 Idle Mode

The system can be set to run in a low-power mode, called Idle mode. When the device is in Idle mode, the CPU is disabled and only select peripherals are active. Based on the configuration of the CAN SIDL bit, the module can either be in or out of Idle mode:

- If SIDL = 0, the module continues operation in Idle mode. If the module generates an interrupt while in Idle mode, the interrupt may generate a wake-up event.
- If SIDL = 1, the module stops when the device is in Idle mode. The module performs the same procedures when stopped in Idle mode as it does in Disable mode and the same requirements apply.

The user should ensure that the module is not active when the CPU transitions to Idle mode with SIDL = 1. To protect the CAN bus system from fatal consequences due to violation of this rule, the module will drive the TX pin into the Recessive state while stopped in Idle mode. If the CAN SIDL bit is set, the recommended procedure is to bring the module into Disable mode before the device is placed in Idle mode.

### 38.2.6.3 Wake-Up From Sleep

Upon a wake-up from Sleep mode, the WAKIF flag is set.

The module will monitor the CAN receive line for activity while the module is Sleeping. The device will generate a wake-up interrupt on the falling edges of CxRX if WAKIE is enabled.

The device will exit Sleep mode after a new mode request or a negative edge on CxRX.

The module will be in Sleep mode if either of the following is true:

- The system is in Sleep mode following Disable mode.
- The system is in Idle mode with SIDL = 1.

#### Notes:

- If the module is in Sleep mode, the module generates an interrupt if the WAKIE bit (C1INT[30]) is set and bus
  activity is detected. Due to delays in starting up the oscillator and CPU, the message activity that caused the
  wake-up will be lost.
- The module can be programmed to apply a low-pass filter function to the CAN receive input line while in Disable, Sleep or Idle mode. This feature can be used to protect the module from wake-up due to short glitches on the CAN bus lines. The WAKFIL bit (C1CON[8]) enables or disables the filter while the module is asleep.

# 38.3 Configuration

# 38.3.1 Clock Configuration

The sample point of all nodes in a CAN FD network should be at the same position. Hence, it is recommended to use the same clock frequency and bit time settings for all nodes. Therefore, a CAN Clock of 40 MHz or 20 MHz is recommended.

The CLKSEL bit allows the selection of the clock source to the CAN FD module.

- If CLKSEL = 1, then the external clock (EXTCLK) will be selected.
- If CLKSEL = 0, then the system clock ( $F_{OSC}$ ) will be selected.

### 38.3.2 CAN Configuration

The C1CON register contain several bits that can only be configured in Configuration mode.

### 38.3.2.1 ISO CRC Enable

The module supports ISO CRC (according to ISO11898-1:2015) and non-ISO CRC (see 38.4.1 ISO vs. Non-ISO CRC). ISO CRC is enabled by setting the ISOCRCEN bit.

### 38.3.2.2 Protocol Exception Disable

The negative edge between the FDF bit and the "reserved bit" in CAN FD frames is important for the calculation of the transceiver delay and for hard synchronization. Therefore, if the "reserved bit" following the FDF bit is detected recessive, the CAN FD Protocol Module will treat this as a form error. This is called, "Protocol Exception Event Detection Disabled" and is configured by setting the PXEDIS bit. The Protocol Exception Event Detection Disabled can be enabled by clearing the PXEDIS bit. As a reaction to the protocol exception event, the error counters are not changed, hard synchronization is enabled, the module sends recessive bits and enters the bus integration state.

### 38.3.2.3 Wake-up Filter

The WAKFIL bit is used to enable/disable the low-pass filter on the CxRX pin. The filter is only active during Sleep mode. The WFTx bits allow the configuration of different filter times.

#### 38.3.2.4 Restriction of Transmission Attempts

ISO11898-1:2015 requires that frames that lost arbitration and are not Acknowledged, or are destroyed by errors, are automatically retransmitted. Optionally, the number of retransmission attempts can be limited. When the RTXAT bit is set, retransmission attempts can be limited using the TXAT[1:0] bits in the FIFO Control registers. If the RTXAT bit is clear, then the TXATx bits in the FIFO Control register are ignored and the retransmission attempts are unlimited.

# 38.3.2.5 Error State Indicator (ESI) in Gateway Mode

Normally, the ESI bit in a transmitted message reflects the error status of the CAN FD Protocol module. ESI is transmitted recessive when the module is error passive. In case the module is used in a gateway application, there will be situations where the ESI bit in the message should be transmitted recessive, even though the gateway module is error active. This can be configured by setting the ESIGM bit.

# 38.3.2.6 Mode Selection In Case of System Error

The SERRLOM bit selects which mode the module will transition to in case of a system error. The module can either transition to Restricted Operation mode or Listen Only mode.

### 38.3.2.7 Reserving Message Memory for TXQ and TEF

Setting the TXQEN bit will reserve RAM for the TXQ. If the TXQEN bit is cleared, then the TXQ cannot be used. Setting the STEF bit will reserve RAM for the TEF and all transmitted messages will be stored in the TEF.

### 38.3.3 CAN FD Bit Time Configuration

In order to achieve higher bandwidth, bits in a CAN FD frame are transmitted with two different bit rates:

- Nominal Bit Rate (NBR): Used during arbitration until the sample point of the BRS bit and the sample point of the CRC delimiter reach the EOF
- · Data Bit Rate (DBR): Used during the data and CRC field

NBR is limited by the propagation delay of the CAN network (see 38.3.3.2 Propagation Delay). In the data phase, only one transmitter remains; therefore, the bit rate can be increased. The transmitting node always compares the intended transmitted bits with the actual bits on the CAN bus. The propagation delay in the data phase can be longer than the bit time. In this case, the data bits are sampled at a Secondary Sample Point (SSP) (see 38.3.3.3 Transmitter Delay Compensation (TDC)).

NBR is the number of bits per second during the arbitration phase. It is the inverse of the Nominal Bit Time (NBT) (see Equation 38-1).

# Equation 38-1. Nominal Bit Rate/Time

$$NBR = \frac{1}{NBT}$$

DBR is the number of bits per second during the data phase. It is the inverse of the Data Bit Time (DBT) (see Equation 38-2).

#### Equation 38-2. Data Bit Rate/Time

$$DBR = \frac{1}{DBT}$$

The Baud Rate Prescaler (BRP) is used to divide the SYSCLK. The divided SYSCLK is used to generate the bit times. There are two prescalers: NBRP for the Nominal Bit Rate Prescaler and DBRP for the Data Bit Rate Prescaler. The Time Quanta (NTQ and DTQ) are selected as shown in Equation 38-3 and Equation 38-4.

### **Equation 38-3. Nominal Time Quanta**

$$NTQ = NBRP \times T_{SYSCLK} = \frac{NBRP}{F_{SYSCLK}}$$

#### Equation 38-4. Data Time Quanta

$$DTQ = DBRP \times T_{SYSCLK} = \frac{DBRP}{F_{SYSCLK}}$$

CAN bit times have four segments, as specified in ISO11898-1:2015 (see Figure 38-3).

**Synchronization Segment (SYNC)** – Synchronizes the different nodes connected on the CAN bus. A bit edge is expected to be within this segment. The Synchronization Segment is always one TQ.


**Propagation Segment (PRSEG)** – Compensates for the propagation delay on the bus. PRSEG has to be longer than the maximum propagation delay.

**Phase Segment 1 (PHSEG1)** – Compensates for errors that may occur due to phase shifts in the edges. The time segment may be automatically lengthened during resynchronization to compensate for the phase shift.

**Phase Segment 2 (PHSEG2)** – Compensates for errors that may occur due to phase shifts in the edges. The time segment may be automatically shortened during resynchronization to compensate for the phase shift.

In the Bit Time registers, PRSEG and PHSEG1 are combined to create TSEG1. PHSEG2 is called TSEG2. Each segment has multiple Time Quanta (TQ). The sample point lies between TSEG1 and TSEG2. Table 38-1 and Table 38-2 show the ranges for the bit time configuration parameters.

Figure 38-3. Partition of Bit Time



The total number of TQ in a bit time is programmable and can be calculated using Equation 38-5 and Equation 38-6.

# Equation 38-5. Number of NTQ in a NBT

$$\frac{NBT}{NTQ} = NSYNC + NTSEG1 + NTSEG2$$

# Equation 38-6. Number of DTQ in a DBT

$$\frac{DBT}{DTQ} = DSYNC + DTSEG1 + DTSEG2$$

Table 38-1. Nominal Bit Rate Configuration Ranges

Segment	Minimum	Maximum
NSYNC	1	1
NTSEG1	2	256
NTSEG2	1	128
NSJW	1	128
NTQ per Bit	4	385

Table 38-2. Data Bit Rate Configuration Ranges

Segment	Minimum	Maximum
DSYNC	1	1
DTSEG1	1	32
DTSEG2	1	16
DSJW	1	16
DTQ per Bit	3	49

# 38.3.3.1 Sample Point

The sample point is the point in the bit time at which the logic level of the bit is read and interpreted. The sample point in percent can be calculated using Equation 38-7 and Equation 38-8.

# Equation 38-7. Nominal Sample Point (%)

$$NSP = \frac{1 + NTSEG1}{\frac{NBT}{NTQ}} \times 100$$

### Equation 38-8. Data Sample Point (%)

$$DSP = \frac{1 + DTSEG1}{\frac{DBT}{DTQ}} \times 100$$

### 38.3.3.2 Propagation Delay


Figure 38-4 illustrates the propagation delay between two CAN nodes on the bus, assuming Node A is transmitting a CAN message. The transmitted bit will propagate from the transmitting CAN Node A through the transmitting CAN transceiver, over the CAN bus, through the receiving CAN transceiver and into the receiving CAN Node B. During the arbitration phase of a CAN message, the transmitter samples the CAN bus and checks if the transmitted bit matches the received bit. The transmitting node has to place the sample point after the maximum propagation delay.

Equation 38-9 describes the maximum propagation delay; where  $t_{TXD-RXD}$  is the propagation = delay of the transceiver, a maximum of 255 ns according to ISO11898-1:2015.  $T_{BUS}$  is the delay on the CAN bus, which is approximately 5 ns/m. The factor 2 comes from the worst-case when Node B starts transmitting exactly when the bit from Node A arrives.

# **Equation 38-9. Maximum Propagation Delay**

$$T_{PROP} = 2 \times (t_{TXD} - RXD + T_{BUS})$$

Figure 38-4. Propagation Delay



Delay: Node B to A (TPROPBA)

#### 38.3.3.3 Transmitter Delay Compensation (TDC)

During the data phase of a CAN FD transmission, only one node is transmitting; the others are receiving. Therefore, the propagation delay does not limit the maximum data rate. When transmitting via pin CxTX, the CAN FD Protocol Module receives the transmitted data from its local CAN transceiver via pin CxRX. The received data are delayed by the CAN transceiver's loop delay. In case this delay is greater than 1 + DTSEG1, a bit error would be detected.

In order to enable a data phase bit time that is shorter than the transceiver loop delay, the Transmitter Delay Compensation (TDC) is implemented. Instead of sampling after DTSEG1, a Secondary Sample Point (SSP) is calculated and used for sampling during the data phase of a CAN FD message.

Figure 38-5 illustrates how the transceiver loop delay is measured and Equation 1-10 shows how the SSP is calculated.

### **Equation 38-10. Secondary Sample Point**

SSP = TDCV[5:0] + TDCO[6:0]




Figure 38-5. Measurement of Transceiver Delay (TDCV)

### 38.3.3.4 Synchronization

To compensate for phase shifts between the oscillator frequencies of the nodes on the CAN bus, each CAN controller must be able to synchronize to the relevant edge of the incoming signal. The CAN controller expects an edge in the received signal to occur within the SYNC segment. Only recessive-to-dominant edges are used for synchronization.

There are two mechanisms used for synchronization:

- Hard Synchronization Forces the edge that has occurred to lie within the SYNC segment. The bit time counter is restarted with SYNC.
- Resynchronization If the edge falls outside the SYNC segment, PHSEG1 or PHSEG2 will be adjusted.

For a more detailed description of the CAN synchronization, please refer to ISO11898-1:2015.

#### 38.3.3.5 Synchronization Jump Width

The Synchronization Jump Width (SJW) is the maximum amount that PHSEG1 and PHSEG2 can be adjusted during resynchronization. SJW is programmable (see Table 38-1 and Table 38-2).

### 38.3.3.6 Oscillator Tolerance

The oscillator tolerance, df, around the nominal frequency of the oscillator, fnom, is defined in Equation 38-11.

Equation 38-12 through Equation 38-16 describe the conditions for the maximum tolerance of the oscillator.

# **Equation 38-11. Oscillator Tolerance**

$$(1 - df) \times fnom \le F_{SYSCLK} \le (1 + df) \times fnom$$

# Equation 38-12. Condition 1

$$df \leq \frac{NSJW}{2 \times 10 \times \frac{NBT}{NTO}}$$

# Equation 38-13. Condition 2

$$df \leq \frac{\min(NPHSEG1, NPHSEG2)}{2 \times \left(13 \times \frac{NBT}{NTQ} - NPHSEG2\right)}$$

### Equation 38-14. Condition 3

$$df \leq \frac{DSJW}{2 \times 10 \times \frac{DBT}{DTO}}$$

# Equation 38-15. Condition 4

$$df \leq \frac{\min(NPHSEG1, \, NPHSEG2)}{2 \times \left(\left(6 \times \frac{DBT}{DTQ} - DPHSEG2\right) \times \frac{DBRP}{NBRP} + 7 \times \frac{NBT}{NTQ}\right)}$$

# Equation 38-16. Condition 5

$$df \leq \frac{DSJW - \max\Bigl(0, \Bigl(\frac{NBRP}{DBRP} - 1\Bigr)\Bigr)}{2 \times \Bigl(\Bigl(2 \times \frac{NBT}{NTQ} \times HNSEGP2\Bigr) \times \frac{NBRP}{DBRP} + DPHSEG2 + 4 \times \frac{DBT}{DTQ}\Bigr)}$$

### 38.3.3.7 Recommendations for Bit Time Configuration

The following recommendations should be considered when configuring the bit time:

- · Select the highest available CAN clock frequency:
  - Short TQ leads to high resolution to select the sample point.
  - Use 20 MHz or 40 MHz for SYSCLK.
- · Select the lowest NBRP and DBRP:
  - Low BRP leads to short TQ.
  - NSYNC and DSYNC will be short and reduce the quantization error.
  - The receiving node can synchronize more accurately to the transmitting node.
- · Set NBRP equal to DBRP:
  - Identical TQ in both phases prevents quantization errors during Bit Rate Switching.
- Use the same Nominal Sample Point (NSP) and Data Sample Point (DSP) in all nodes on the CAN FD network:
  - Different sample points in the different nodes lead to different lengths of the BRS and CRC delimiter bits and introduce phase errors when switching the bit rate.
  - NSP need not be equal to the DSP.
  - The SSP can be different in differing CAN FD nodes.
- · Select the largest possible NSJW and DSJW:
  - Maximizes the oscillator tolerance.
  - Allows the receiving nodes to quickly resynchronize to the transmitting nodes.
- Enable automatic TDC for DBR of 1 Mbps and higher:
  - Automatic TDC measurement compensates for transmitter delay variations.

### 38.3.3.8 Bit Time Configuration Example

The following tables illustrate the configuration of the CAN FD Bit Time registers, assuming there is a CAN FD network in an automobile with the following parameters:

- 500 kbps NBR sample point at 80%
- 2 Mbps DBR sample point at 80%
- 40 Meters minimum bus length

Table 38-3 and Table 38-4 illustrate how the bit time parameters are calculated. Since the parameters depend on multiple constraints and equations, and are calculated using an iterative process, it is recommended to enter the equations in a spreadsheet.

Table 38-5 translates the calculated values into register values. It is recommended to let the CAN FD Protocol module measure the Transmitter Delay Compensation Value (TDCV). This is accomplished by setting TDCMOD[1:0] (C1TDCH[1:0]) = 10 (Automatic mode). In order to set the SSP to 80%, TDCO[6:0] are set to 1 + DTSEG1.

Table 38-3. Step-by-Step Nominal Bit Rate Configuration

Parameter	Constraint	Value	Unit	Equations and Comments
NBT	NBT ≥ μs	2	us	Equation 38-1
F <sub>SYSCLK</sub>	F <sub>SYSCLK</sub> ≤ 40 MHz	40	MHz	CAN clock frequency = 40 MHz
NBRP	1 to 256	1	-	Select smallest possible BRP value to maximize resolution.
NTQ	NBT, F <sub>SYSCLK</sub>	12.5	ns	Equation 38-3
NBT/NTQ	4 to 385	160	-	Equation 38-5
NSYNC	Fixed	1	NTQ	Defined in ISO11898-1:2015
NPRSEG	NPRSEG > T <sub>PROP</sub>	95	NTQ	Equation 38-9;T <sub>PROP</sub> = 910 ns, minimum NPRSEG = T <sub>PROP</sub> /NTQ = 72.8 NTQ. Selecting 95 will allow up to a 60m bus length
NTSEG1	2 to 256 NTQ	127	NTQ	Equation 38-7. Select NTSEG1 to achieve 80% NSP.
NTSEG2	1 to 128 NTQ	32	NTQ	There are 32 NTQ left to reach NBT/NTQ = 160
NSJW	1 to 128 NTQ; SJW ≤ min(NPHSEG1, NPHSEG2)	32	NTQ	Maximizing NSJW lessens the requirement for the oscillator tolerance.

Table 38-4. Step-by-Step Data Bit Rate Configuration

Parameter	Constraint	Value	Unit	Equations and Comments
DBT	DBT ≥ 125 ns	500	ns	Equation 38-2
DBRP	1 to 256	1	-	Selecting the same prescaler as for NBT ensures that to the T <sub>Q</sub> resolution does not change during the Bit Rate Switching
DTQ	DBT, F <sub>SYSCLK</sub>	12.5	ns	Equation 38-4
DBT/DTQ	3 to 49	40	-	Equation 38-6

continued					
Parameter	Constraint	Value	Unit	Equations and Comments	
DSYNC	Fixed	1	DTQ	Defined in ISO11898-1:2015.	
DTSEG1	1 to 32 DTQ	31	DTQ	Equation 38-8	
DTSEG2	1 to 16 DTQ	8	DTQ	There are 8 DTQ left to reach DBT/DTQ = 40	
DSJW	1 to 16 DTQ; SJW≤ min (DPHSEG1, DPHSEG2)	8	DTQ	Maximizing DSJW lessens the requirement for the oscillator tolerance	
Oscillator Tolerance Conditions 1-5	Minimum of Conditions 1-5	.78	%	Equation 38-11through Equation 38-16	

Table 38-5. Bit Time Register Initialization (500k/2M)

CxNBTCFG	Value	CxDBTCFG	Value	CxTDC	Value
BRP[7:0]	0	BRP[7:0]	0	TDCMOD[1:0]	2
TSEG[7:0]	126	TSEG[7:0]	30	TDCO[6:0]	31
TSEG2[6:0]	31	TSEG2[6:0]	7	TDCV[5:0]	0
SJW[6:0]	31	SJW[6:0]	7	-	-

# 38.3.4 Message Memory Configuration

The message objects of the TEF, TXQ and transmit/receive FIFOs are located in RAM (see Figure 38-6). The application must configure the number of message objects in a FIFO between Message Object 0 and Message Object 31. Additionally, the application must configure the payload size of the message objects in each FIFO. This configuration determines where message objects are located in RAM. The RAM allocation can only be configured in Configuration mode.

In order to optimize RAM usage, the application should start configuring the RAM with the TEF, followed by the TXQ, and continue with FIFO 1, FIFO 2 and FIFO 3.

Figure 38-6. Message Memory Organization

TEF
TXQ
FIFO 1
FIFO 2: Message Object 0
FIFO 2: Message Object 1
FIFO 2: Message Object n
FIFO 3

# 38.3.4.1 Transmit Event FIFO Configuration

In order to reserve space in RAM for the TEF, the STEF bit (C1CON[19]) has to be set. The number of message objects in the TEF is configured using the FSIZE[4:0] bits (C1TEFCON[27:23]). Transmitted messages can be timestamped by setting the TEFTSEN bit (C1TEFCON[5]).

### 38.3.4.2 Transmit Queue Configuration

In order to reserve space in RAM for the TXQ, the TXQEN bit (C1CON[19]) has to be set. The number of message objects in the TXQ is configured using the FSIZE[4:0] bits (C1TXQCON[27:23]). All objects in the TXQ use the same payload size (number of data bytes), which is configured using the PLSIZE[2:0] bits (C1TXQCON[30:28]).

### 38.3.4.3 Transmit FIFO Configuration

FIFO 1 through FIFO 3 can be configured as transmit FIFOs by setting TXEN in the CxFIFOCONy register. The number of message objects in each transmit FIFO is configured using the FSIZE[4:0] bits (CxFIFOCONy[27:23]). All objects in one transmit FIFO use the same payload size (number of data bytes), which is determined by the PLSIZE[2:0] bits (CxFIFOCONy[30:28]).

### 38.3.4.4 Receive FIFO Configuration

FIFO 1 through FIFO 3 can be configured as receive FIFOs by clearing TXEN in the CxFIFOCONy register. The number of message objects in each receive FIFO is configured using the FSIZE[4:0] bits (CxFIFOCONy[27:23]). All objects in one receive FIFO use the same payload size (number of data bytes), which is determined by the PLSIZE[2:0] bits (CxFIFOCONy[30:28]). Received messages can be timestamped by setting the RXTSEN bit (CxFIFOCONy[5]).

### 38.3.4.5 Calculation of Required Message Memory

The size of required RAM depends on the configuration of each FIFO. Equation 38-17 through Equation 38-19 specify the sizes of the TEF, TXQ and the FIFOs in bytes. The TEF or TXQ is not used if their size is zero.

Since the size of the integrated RAM is limited, the user must check that the memory configuration fits into RAM. Equation 38-20 can be used to calculate the total RAM usage in bytes.

The size of the TEF objects depends on the enabling of timestamping. If TEFTSEN is set, then tefts = 4, else tefts = 0.

The PayLoad(i) is defined in data bytes.

The size of a message object of an RX FIFO varies dependent on the enabling of timestamping. If RXTSEN = 1 and TXEN = 0 for FIFO(i), then rxts(i) = 4, else rxts(i) = 0.

N is defined as the number of FIFOs used in addition to the TEF and the TXQ.

### Equation 38-17. Size of TEF

$$S_{TEF} = N_{ELEMENTS}(TEF) \times (tefts + 8)$$

# Equation 38-18. Size of TXQ

$$S_{TXQ} = N_{ELEMENTS}(TXQ) \times (8 + PayLoad(TXQ))$$

# Equation 38-19. Size of FIFOs

$$S_{FIFO}(i) = N_{ELEMENTS}(i) \times (rxts(i) + 8 + PayLoad(i))$$

# Equation 38-20. Total RAM Usage

$$S_{RAM} = \left(S_{TEF} + S_{TXQ} + \sum_{i=1}^{N} S_{FIFO}(i)\right)$$

For example:

- If TEF is 4 messages deep (N<sub>Elements</sub> (TEF) = 4) and TEFTSEN is clear, then the size of TEF = S<sub>TEF</sub> = 4 x (0 + 8) = 32 bytes
- If N<sub>Elements</sub> (TXQ) = 1, PayLoad (TXQ) = 12, then the size of TXQ = S<sub>TXO</sub> = 1 x (8 + 12) = 20 bytes
- If  $N_{\text{Flements}}$  (FIFO) = 3, PayLoad (FIFO) = 8, then the size of FIFO =  $S_{\text{FIFO}}$  = 3 x (8 + 8) = 48 bytes

Therefore,  $S_{RAM} = S_{TEF} + S_{TXQ} + S_{FIFO} = 32 + 20 + 48 = 100$  bytes.

# 38.4 CAN FD Message Frames

The ISO11898-1:2015 describes the different CAN message frames in detail. Figure 38-7 through Figure 38-12 explain and summarize the construction of the messages and fields.

There are four different CAN data/remote frames (see Figure 38-8):

- CAN Base Frame: Classic CAN 2.0 frame using Standard ID
- · CAN FD Base Frame: CAN FD frame using Standard ID
- CAN Extended Frame: Classic CAN 2.0 frame using Extended ID
- CAN FD Extended Frame: CAN FD frame using Extended ID

There are no remote frames in CAN FD frames; therefore, the RTR bit is replaced with the RRS bit (see Figure 38-8). The RRS bit in the CAN FD base frame can be used to extend the SID to 12 bits. When enabled, it is referred to as SID11; it is the Least Significant bit (LSb) of SID[11:0].

Figure 38-9 specifies the control field of the different CAN messages. Before CAN FD was added to the ISO11898-1:2015, the FDF bit was a reserved bit. Now the FDF bit selects between Classic and CAN FD formats.

The BRS bit selects if the bit rate should be switched in the data phase of CAN FD frames. Figure 38-12 illustrates the error and overload frames. These special frames do not change.

**Note:** If an error is detected during the data phase of a CAN FD frame, the bit rate will be switched back to the Nominal Bit Rate (NBR). Error frames are always transmitted at the arbitration bit rate.

#### 38.4.1 ISO vs. Non-ISO CRC

To support the system validation of non-ISO CRC ECUs, the CAN FD Controller module supports both ISO CRC (according to ISO11898-1:2015) and non-ISO CRC (see Figure 38-10 and Figure 38-11). The CRC field is selectable using the ISOCRCEN bit (C1CON[5]). The ISO CRC field contains the stuff count. This count was not included in the original CAN FD specification; it was added to fix a minor issue in the error detection of the original specification.

CAN FD frames use two different lengths of CRC: 17-bit for up to 16 data bytes and 21-bit for 20 or more data bytes. Technically, there are a total of six different CAN data/remote frames in the CAN FD.

Figure 38-7. General Data Frame

	DATA FRAME							
IFS (3b)	SOF (1b)	1 ARRITRATION(12/32n) (CTRT/6/8/9n) 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1					IFS (3b)	

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 785

Figure 38-8. Arbitration Field




Figure 38-9. Control Field




Figure 38-10. ISO CRC Field




Figure 38-11. NON\_ISO CRC Field




Figure 38-12. Error and Overload Frame

	ERF			
ANYWHERE WITHIN DATA FRAME	ERRFLAG(6b)	ERRDEL(8b)	IFS (3b) or OVL	
	OVER	LOAD		
EOF or ERRDEL or OVLDEL	OVLFLAG(6b)	OVLDEL(8b)	IFS (3b) or OVL	

# 38.4.1.1 DLC Encoding

The Data Length Code (DLC) specifies the number of data bytes a message frame contains. Table 38-6 illustrates the encoding.

Table 38-6. DLC Encoding

Frame	DLC	Number of Data Bytes		
CAN 2.0 and CAN FD	0	0		
	1	1		
	2	2		
	3	3		
	4	4		
	5	5		
	6	6		
	7	7		
	8	8		
CAN 2.0	9-15	8		
CAN FD	9	12		
	10	16		
	11	20		
	12	24		
	13	32		
	14	48		
	15	64		

# 38.5 Message Transmission

The application needs to configure the FIFO or TXQ before it can be used for transmission (see 38.3.4.3 Transmit FIFO Configuration and 38.3.4.2 Transmit Queue Configuration).

### 38.5.1 Transmit Message Object

Table 38-7 specifies the transmit message object used by the TXQ and the transmit FIFOs. The transmit objects contain the message ID, control bits and payload.

- SID: Standard Identifier or Base Identifier.
- EID: Extended Identifier.
- DLC: Data Length Code; specifies the number of data bytes to transmit (see 38.4.1.1 DLC Encoding).
- **IDE**: Identifier Extension; clearing this bit will transmit a base frame, setting this bit will transmit an extended frame.
- RTR: Remote Transmit Request; this bit is only specified in CAN 2.0 frames. Setting this bit will request a transmission of a receiving node.
- **FDF**: FD Format; if this bit is set, a CAN FD frame will be transmitted; otherwise, a CAN 2.0 frame will be transmitted. If Normal CAN 2.0 mode is selected, this bit is ignored and only CAN 2.0 frames are transmitted.
- **BRS**: Bit Rate Switch; the data phase of a CAN FD frame will be transmitted using DBR if this bit is set. If the bit is clear, the whole frame will be transmitted using NBR.
- **ESI**: Error State Indicator; normally, the ESI bit reflects the error status of the transmitting node. A recessive ESI bit in a CAN FD frame indicates that the transmitting node is error passive; a dominant bit shows that the transmitting node is error active. If ESIGM (C1CON[17]) = 0, this bit in the object is ignored. If ESIGM = 1, the ESI bit in the transmitted message will be transmitted recessive if the CAN FD Protocol Module is error passive, or if the ESI bit in the message object is set. A gateway application would use it to signal that the ESI bit of the transmitting node is set.

- **SEQ**: Sequence Number; SEQ is not transmitted on the CAN bus. It is used to keep track of the transmitted messages. SEQ is stored in the TEF message object.
- **Transmit Buffer Data**: Contains the payload of the message. Only the number of data bytes specified by the DLC are transmitted. Byte 0 is transmitted first, followed by 1, 2 and so on.

### 38.5.2 Loading Messages into Transmit FIFO

Before loading a message into the FIFO, the application must ensure that the FIFO is not full. There is space in the FIFO if TFNRFNIF (CxFIFOSTAy[0]) is set. Loading a message into a full FIFO can corrupt a message that is being transmitted.

The FIFO user address (CxFIFOUAy) points to the RAM of the next transmit message object where the application should store the message. To of the transmit message object is loaded first, followed by T1, T2 and so on. The maximum number of data bytes is limited by the configured payload. Only the number of data bytes specified by the DLC have to be loaded.

After the message object is loaded into RAM, the FIFO needs to be incremented by setting the UINC bit (CxFIFOCONy[8]). Doing so will cause the CAN FD Protocol module to increment the head of the FIFO and update CxFIFOUAy.

Now the message is ready for transmission and the next message can be loaded at the new address.

# 38.5.3 Loading Messages Into Transmit Queue

Loading transmit message objects into the TXQ works similarly to loading message objects into a transmit FIFO. The application must check the CxTXQSTA register to see if there is space in the TXQ. The CxTXQUA registers should be used instead of the CxFIFOUAy registers to calculate the address to load the message and set the UINC bit (CxTXQCON[8]) to increment the head of the TXQ.

Table 38-7. Transmit Message Object (TXQ and TX FIFO)

Byte	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0
0	SID[7:0]							
1			EID[4:0]			SID[10:8]		
2				EID[12:	5]			
3	SID11 EII			EID[17:13]	EID[17:13]			
4	FDF	BRS	RTR	IDE		DLC	[3:0]	
5			5	SEQ[6:0]				ESI
6				SEQ[14:	7]			
7		SEQ[22:15]						
8	Transmit Data Byte 0							
9	Transmit Data byte 1							
10	Transmit Data byte 2							
11	Transmit Data byte 3							
12		Transmit Data byte 4						
13	Transmit Data byte 5							
14	Transmit Data byte 6							
15	Transmit Data byte 7							
0					h. 4 0			
m-3	Transmit Data byte n-3							

# CAN FD - Controller Area Network, Flexible ...

m-2	Transmit Data byte n-2
m-1	Transmit Data byte n-1
m	Transmit Data byte n

bit 15:11 **EID[4:0]**: Extended Identifier bits bit 10-0 **SID[10:0]**: Standard Identifier bits bit 15-14 **Unimplemented**: Read as 'x'

bit 13 SID11: In FD mode, the Standard ID can be Extended to 12 bits using r1 bit

bit 12-0 EID[17:5]: Extended Identifier bits

bit 15-9 SEQ[6:0]: Bits 6-0 of sequence to keep track of transmitted messages in transmit event FIFO bits

bit 8 **ESI:** Error Status Indicator bit - In CAN to CAN Gateway mode (ESIGM (C1CONH[1]) = 1), the transmitted ESI flag is a "logical OR" of ESI and the error passive state of the CAN controller.

In Normal mode, ESI indicates the error status:

1 = Transmitting node is error passive

0 = Transmitting node is error active

bit 7 **FDF:** FD Frame bit - distinguishes between CAN and CAN FD formats.

bit 6 BRS: Bit Rate Switch bit - selects if data bit rate is switched

bit 5 RTR: Remote Transmission Request bit (not used in CAN FD)

bit 4 IDE: Identifier Extension bit - distinguishes between base and extended format

bit 3-0 DLC[3:0]: Data Length Code bits

bit 15:0 SEQ[22:7]:Bits 22-7 Sequence to Keep Track of Transmitted Messages in Transmit Event FIFO bits

#### Note:

1. Data Bytes 0-2: Payload size is configured individually in the PLSIZE[2:0] bits (CxFIFOCONy[31:29]).

### 38.5.4 Requesting Transmission of Message in Transmit FIFO

After a message is loaded into a transmit FIFO, the message is ready for transmission. The application initiates the transmission of all messages in a FIFO by setting the TXREQ bit (CxFIFOCONy[9]) or by setting the corresponding bit in the C1TXREQ register. When all messages are transmitted, TXREQ gets cleared. The application can request transmission of multiple FIFOs and the TXQ simultaneously. The FIFO or TXQ with the highest priority will start transmitting first. Messages in a FIFO will be transmitted First-In First-Out.

Messages can be loaded into a FIFO while the FIFO is transmitting messages. Since TXREQ is cleared by the FIFO automatically after the FIFO empties, UINC and TXREQ of the CxFIFOCONy register must be set at the same time after appending a message. This ensures that all messages in the FIFO are transmitted, including the appended messages.

### 38.5.5 Requesting Transmission of Message in Transmit Queue

After a message is loaded into the TXQ, the message is ready for transmission. The application initiates the transmission of all messages in the queue by setting TXREQ (CxTXQCON[9]). When all messages have been transmitted, TXREQ will be cleared. The application can request transmission of the TXQ and multiple FIFOs simultaneously. The TXQ or FIFO of the CxTXQCON register with the highest priority will start transmitting first. Messages in the TXQ will be transmitted based on their ID. The message with the highest priority ID and the lowest ID value will be transmitted first.

Messages can be loaded into the TXQ while the TXQ is transmitting messages. Since TXREQ is cleared by the TXQ automatically after the TXQ empties, UINC and TXREQ of the CxTXQCON register must be set at the same time after appending a message. This ensures that all messages in the TXQ are transmitted, including the appended messages.

# 38.5.6 C1TXREQ Register

The CxTXREQ register contains the TXREQ[31:0] bits of the TXQ and of all the TX FIFOs. They have the following purposes:

- The user application can request transmission of the TXQ and/or one or more TX FIFOs, using only one SPI instruction, by setting the corresponding bits in the CxTXREQ register. Clearing a bit does NOT abort any transmissions.
- Reading the CxTXREQ register gives information about which transmit FIFOs have transmissions pending.

CxTXREQ[0] is mapped to the TXQ, CxTXREQ[1] is mapped to TX FIFO 1, CxTXREQ[2] is mapped to TX FIFO 2 and so on.

# 38.5.7 Transmit Priority

The transmit priority of the FIFOs and TXQ needs to be configured using the TXPRIx bits (CxFIFOCONy[20:16] and CxTXQCON[20:16]).

Before transmitting a message, the priorities of the TXQ and the TX FIFOs queued for transmission are compared. The FIFO/TXQ with the highest priority will be transmitted first. For example, if transmit FIFO 1 has a higher priority setting than FIFO 3, all messages in FIFO 1 will be transmitted first. If multiple FIFOs have the same priority, the FIFO with the highest index is transmitted. For example, if FIFO 1 and FIFO 3 have the same priority setting, all messages in FIFO 3 will be transmitted first. If the TXQ and one or more FIFOs have the same priority, all messages in the TXQ will be transmitted first.

The transmit priority will be recalculated after every successful transmission of a single message.

### 38.5.7.1 Transmit Priority of Messages in FIFO

In this method, the messages in a FIFO are transmitted First-In First-Out.

### 38.5.7.2 Transmit Priority of Messages in TXQ

Messages in the TXQ are transmitted based on the message ID. The message with the lowest message ID (highest priority) is transmitted first.

### 38.5.7.3 Transmit Priority Based on ID

The goal of transmitting CAN messages based on ID is to avoid "Inner Priority Inversion". If a low-priority message is waiting to get transmitted due to bus traffic (arbitration), a higher priority message could be prevented from being transmitted. The TXQ solves this issue by reprioritizing the messages in the queue based on priority (ID).

### 38.5.8 Transmit Bandwidth Sharing

The bandwidth sharing feature works as follows:

- After a successful transmission of a message, the module will remain Idle for n arbitration bit times before the module attempts to transmit the next message; it suspends the next transmission.
- · After the device has received a message, the module can transmit the next message as soon as the bus is Idle.

This allows other nodes on the bus to transmit their messages, even though they are of lower priority.

The number of arbitration bit times between transmissions can be configured using the TXBWS[3:0] bits (C1CON[31:28]).

### 38.5.9 Retransmission Attempts

The number of retransmission attempts can be configured as follows:

- · Retransmission attempts are disabled
- · Three retransmission attempts
- Unlimited retransmissions

The retransmission attempts can be restricted by setting RTXAT (CxCON[16]). The number of retransmission attempts can be configured individually for each transmit FIFO and the TXQ using TXAT[1:0] (CxFIFOCONy[22:21] and CxTXQCON[22:21], respectively).

In case RTXAT = 0, unlimited retransmission attempts will be used for all transmit FIFOs and the TXQ, and TXATx will be ignored.

### 38.5.9.1 Retransmission Attempts Disabled

TXREQ will be cleared after the attempt to transmit the message. If the message is not successfully transmitted due to loss of arbitration or due to an error, TXATIF in the CxFIFOSTAy or CxTXQSTA register will be set.

#### 38.5.9.2 Three Retransmission Attempts

In case an error is detected during transmission, the CAN FD Protocol module will decrement the number of remaining attempts and try to retransmit the message the next time the bus is Idle. In case arbitration is lost, the number of remaining attempts will not change. If all retransmission attempts are exhausted, TXREQ will be cleared and TXATIF in CxFIFOSTAy or CxTXQSTA will be set.

Before retransmitting the message, the transmit priority will be recalculated. The retransmission attempts will be reinitialized if a different TX FIFO or TXQ is selected for transmission, or if a message is received after the last transmission attempt.

#### 38.5.9.3 Unlimited Retransmission

TXREQ will be cleared only after all messages in the TX FIFO or TXQ are successfully transmitted.

### 38.5.10 Aborting Transmission

A pending transmission can only be aborted before the transmission of the message starts, before the Start-of-Frame (SOF).

The transmission of a specific FIFO can be aborted by clearing TXREQ in the CAN Transmit Queue Control register; it cannot be aborted by clearing the bits in the CxTXREQ registers. Writing a '0' to one of the bits in the CxTXREQ registers will be ignored. The TXABT bit in the CAN FIFO Status y register will be set after a successful abortion. TXREQ will remain set until the message either aborts or is successfully transmitted.

Setting ABAT (CxCON[27]) will abort all pending messages of all FIFOs. After all TXREQx bits are cleared, ABAT has to be cleared in order to be able to transmit new messages.

Clearing TXREQ for a transmit FIFO will attempt to abort all transmissions in the FIFO. If a message is successfully transmitted, the FIFO index will be updated as normal. If the message is successfully aborted, the FIFO index will not change.

The user can then use the FIFO Message Index bits, FIFOCI[4:0] (CxFIFOSTAy[12:8]), to identify messages that are transmitted. To reset the transmit FIFO index and erase all pending messages, the user can set the FRESET bit. The FIFO can then be loaded with new messages to be transmitted.

### 38.5.11 Remote Transmit Request (RTR)

The CAN bus system has a method for allowing a master node to request data from another node. The master sends a message with the RTR bit set. The message contains no data, only an address to trigger a filter match.

Remote frames are only specified for CAN 2.0 frames; they are not supported in CAN FD frames.

The filter that is configured to respond to a Remote Transmit Request will point to a FIFO that is configured for transmission and RTREN has to be set.

Automatic remote data requests can be handled without MCU intervention. If a FIFO is properly configured, when a filter matches and points to the FIFO, the FIFO will be queued for transmission.

The FIFO must be configured as follows:

- Set TXEN to '1'.
- · A filter must be enabled and loaded with a matching message identifier.
- The Buffer Pointer for that filter must point to the TX FIFO (normally, a filter points to an RX FIFO).
- RTREN bit must be set to '1' to enable RTR.
- The FIFO must be preloaded with at least one message to be sent.

When an RTR message is received and it matches a filter pointing to a properly configured transmit FIFO, the TXREQ bit is set, queuing the object for transmission according to priorities.

A FIFO will only be transmitted if TXEN and RTREN are set, and if it is NOT empty. When a request for a remote transmission occurs while the FIFO is empty, the event will be treated as an overflow and the RXOVIF bit will be set.

### 38.5.12 Mismatch of DLC and Payload Size During Transmission

The PLSIZEx bits reserve a certain number of bytes in the transmit FIFO. The CAN FD Protocol module handles mismatches between the DLC and payload size as follows:

- If the DLC is smaller than the reserved payload, the number of data bytes specified by the DLC will be transmitted.
- If the DLC is bigger than the reserved payload, the module will not transmit the message. Instead, it will set the IVMIF (CxINT[15]) and DLCMM (CxBDIAG1[31]) flags and clear the TXREQ flag. The application can use the TEF to identify the message that is not transmitted.

#### 38.5.13 Transmit State Diagram

Figure 38-13 describes how messages are queued for transmission. It illustrates how the most important transmit flags are set and cleared:

- 1. Messages are queued for transmission by setting the TXREQ flag.
- 2. The transmit priority will be determined. The FIFO or TXQ with the highest priority TXPRIx flag will be selected. The index of the TX message in the FIFO or TXQ will be calculated.
- 3. The TX message is pending for transmission.
- 4. Transmission can only start when the bus is Idle.
- 5. A pending transmission can only be aborted before SOF is transmitted.
- 6. During the transmission of a message, the CAN FD Protocol module checks for the following:
  - 6.1. Loss of arbitration during the arbitration field.
  - 6.2. Transmit errors.
- 7. In case a message of a TX FIFO or the TXQ is transmitted successfully, the TXREQ will only be cleared after all messages of the FIFO are transmitted. After the transmission of any message, the status flags of the FIFO or TXQ are updated. In case STEF (CxCON[19]) is set, the message will be stored into the TEF and a timestamp will be attached if enabled.
- 8. In case arbitration is lost, TXLARB of the TX FIFO or TXQ will be set and the device will switch over to receiving the message (see 38.8 Message Reception).
- In case an error is detected during the transmission of a message, an error frame will be transmitted and the appropriate error flags will be set. Messages will be retransmitted according to 38.5.9 Retransmission Attempts.




Figure 38-13. Transmit State Diagram

#### 38.5.14 Resetting Transmit FIFO

A Transmit FIFO can be reset by:

- Setting FRESET (CxFIFOCONy[10]) or
- Placing the module in Configuration mode (OPMOD[2:0] = 100).

Resetting the FIFO will reset the head and tail pointers, and the CxFIFOSTAy register. The settings in the CxFIFOCONy register will not change.

Before resetting a TX FIFO using FRESET, ensure no transmissions are pending.

### 38.5.15 Resetting Transmit Queue

The Transmit Queue can be reset by:

- · Setting FRESET (CxTXQCON[10]) or
- Placing the module in Configuration mode (OPMOD[2:0] = 100).

Resetting the TXQ will reset the head and tail pointers, and the CxTXQSTA register. The settings in the CxTXQCON register will not change.

Before resetting the TXQ using FRESET, ensure no transmissions are pending.

## 38.6 Transmit Event FIFO (TEF)

The TEF allows the application to keep track of the order and time in which the messages are transmitted. The TEF works similarly to a receive FIFO. Instead of storing received messages, it stores transmitted messages. Messages

are only saved if STEF (CxCON[19]) is set. The sequence number (SEQ) of the transmitted message is copied into the TEF object. The payload data are not stored. Transmitted messages are timestamped if TEFTSEN is set.

Table 38-8 specifies the TEF object. The first two words of the TEF object are a copy of the transmit message object. Optionally, the TEF object contains the timestamp when the message is transmitted.

#### 38.6.1 Reading a TEF Object

Before reading a TEF object, the application must check that the TEF is not empty by reading the CxTEFSTA register. The TEF is not empty if TEFNEIF is set.

The TEF user address points to the address in RAM of the next TEF object to read. The actual address in RAM is calculated using Equation 1-21. TE0 of the TEF object is read first, followed by TE1 and TE2.

#### Equation 38-21. Start Address of the TEF Object

A = BaseAddress = CxFIFOBA

**Note:** CxFIFOBAH/L needs to be set to a value between 0x3800 and the end of RAM, leaving enough room to allow the TEF and Transmit Queue (if enabled) as well as the FIFOs.

After the TEF object is read from RAM, the TEF needs to be incremented by setting UINC (CxTEFCON[8]). This will cause the CAN FD Protocol module to increment the tail pointer and update CxTEFUA.

Now the next message can be read from the TEF.

#### 38.6.1.1 Resetting the TEF

TEF can be reset by:

- Setting FRESET (CxTEFCON[10]) or
- Placing the module in Configuration mode (OPMOD[2:0] = 100).

Resetting the FIFO will reset the head and tail pointers, and the CxTEFSTA register. The settings in the CxTEFCON register will not change.

Table 38-8. Transmit Event FIFO Object

Byte	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0
0		SID[7:0]						
1			EID[4:0]				SID[10:8]	
2		EID[12:5]						
3	-	-	SID11			EID[17:13]		
4	FDF	BRS	RTR	IDE		DLC	[3:0]	
5	SEQ[6:0] ESI				ESI			
6				SEC	Q[14:7]			
7		SEQ[22:15]						
8		TXMSGTS[7:0]						
9		TXMSGTS[15:8]						
10		TXMSGTS[23:16]						
11				TXMSG	TS[31:24]			

bit 15-11 **EID[4:0]**: Extended Identifier bits bit 10-0 **SID[10:0]**: Standard Identifier bits

bit 15-14 **Unimplemented:** Read as  $\ensuremath{^{\mbox{vx'}}}$ 

bit 13 SID11: In FD mode, the Standard ID can be Extended to 12 Bits using r1 bit

bit 12-0 EID17:5: Extended Identifier bits

bit 15-9 SEQ[6:0]: Bits 6-0 of the sequence to keep track of transmitted messages in Transmit Event FIFO

bit 8 ESI: Error Status Indicator bit

In CAN-to-CAN Gateway mode (ESIGM (CxCON[17]) = 1), the transmitted ESI flag is a "logical OR" of ESI and the error passive state of the CAN controller.

In Normal mode, ESI indicates the error status:

1 = Transmitting node is error passive

0 = Transmitting node is error active

bit 7 FDF: FD Frame bit - distinguishes between CAN and CAN FD formats

bit 6 BRS: Bit Rate Switch bit - selects if Data Bit Rate is switched

bit 5 RTR: Remote Transmission Request bit (not used in CAN FD)

bit 4 IDE: Identifier Extension bit - distinguishes between base and extended format.

bit 3-0 DLC[3:0]: Data Length Code bits

bit 15-0 SEQ[22:7]: Bits 22-7 of the sequence to keep track of transmitted messages in Transmit Event FIFO

bit 15-0 TXMSGTS[15:0] Transmit Message Timestamp bits

bit 15-0 TXMSGTS[31:16]: Transmit Message Timestamp bits

#### Note:

1. TE4 and TE5 (TXMSGTSx) only exist in objects where TEFTSEN (CxTEFCON[5]) is set.

## 38.7 Message Filtering

All messages on a CAN network will be received by all nodes. In order to process only messages of interest, a hardware filtering mechanism is implemented. The CAN FD Protocol module can be configured to receive only messages of interest. The module contains 12 acceptance filters. Each acceptance filter contains a filter object and a mask object. The user application configures the specific filter to receive a message with a given identifier by setting the filter object and mask object to match the identifier of the message to be received.

### 38.7.1 Filter Configuration

The filters are controlled by the CxFLTCONy registers. The filters must be disabled by clearing the FLTEN bit before changing the filter or mask object; the module need not be in Configuration mode. After the filter object is updated, the Buffer Pointer, FnBP, has to be initialized and the filter can be enabled by setting the FLTEN bit. The FnBP points to the FIFO where the matching receive message needs to be stored.

#### 38.7.2 Filtering a Received Message

The CAN FD Protocol module starts acceptance filtering after the arbitration field and when the first three data bytes of a message are received. Figure 38-14 describes the flow of message filtering.

The module loops through all the filters, starting with Filter 0, which is the highest priority filter. The message in the Receive Message Assembly Buffer (RXMAB) is compared to the filter and mask. In case the message matches the filter and it is received without any errors, the message will be stored into the RX FIFO pointed to by the FnBP. Acceptance filtering is stopped and the associated RFIF bit is set.

In case an RTR is received, the TXREQ bit of the TX FIFO pointed to by FnBP will be set. Filtering will continue with the next filter and RXOVIF will be set only when one of the following happens:

- · A filter matches, but the RX FIFO is full.
- When multiple filters match the same message and all matching RX FIFOs are full, only the RXOVIF of the FIFO
  pointed to by the highest priority filter will be set.
- The RXOVIF bit will be set if the TX FIFO is empty during an RTR (TXEN = 1, RTREN = 1).

If none of the filters match, the received message will be discarded.

**Note:** If the module receives a message that matches a filter, but the corresponding FIFO is a TX FIFO (TXEN = 1, RTREN = 0), the module will discard the received message.




Figure 38-14. Message Filtering Flow

### 38.7.2.1 Filtering Standard or Extended Frames

The Filter Match flowchart illustrates the flow of matching a single filter object to the received message in the RXMAB.


The filter object can be configured to accept either standard, extended or both frames. If MIDE is clear, both standard and extended frames will be accepted.

If the filter should only accept standard frames, then MIDE must be set and EXIDE must be cleared. If the filter should only accept extended frames, then both MIDE and EXIDE must be set.

#### 38.7.2.2 Mask Bits

The mask object is used to ignore selected bits of the received identifier. The masked bits (mask bits with a value of '0') of the RXMAB will not be compared with the bits in the filter object. For example, to receive all messages with Identifiers 0, 1, 2 and 3, it is required to mask the lower two bits of the identifier by clearing the corresponding bits of the mask object.

Figure 38-15. Filter Match



### 38.7.2.3 Filtering on Data Bytes

When the filter is configured to receive standard frames, the EID part of the filter and mask object can be selected to filter the data bytes. The DNCNT[4:0] bits in the C1CONL register are used to select how many bits in the data bytes are compared. Table 38-9 explains how many data bits are compared, and which filter bits and data bits are compared.

If DNCNTx is:

- '0', then data byte filtering is disabled.
- Non-zero, the filtering will commence on as many data bits as specified in DNCNTx. A filter hit will require matching of the SIDx bits and a match of n data bits with the filter's EID[0:17] bits. Data Byte 0[7] is always compared to EID[0], Data Byte 0[6] to EID[1], Data Byte 2[6] to EID[17].
- Greater than 18, indicating that the user-selected number of bits is greater than the total number of EIDx bits. The filter comparison will terminate with the 18th bit of the data.
- Greater than 16, and the received message has DLC = 2, indicating a payload of two data bytes. The filter comparison will terminate with the 16th bit of the data.
- Greater than 8, and the received message has DLC = 1, indicating a payload of one data byte. The filter comparison will terminate with the 8th bit of the data.
- Greater than 0, and the received message has DLC = 0, indicating no data payload. The filter comparison will terminate with the identifier.

#### 38.7.2.4 12-Bit Standard ID


Setting SID11EN (CxTDC[8]) allows the use of RRS as bit 12 of the SIDx (LSB). 12-Bit SID mode is only available for CAN FD base frames. The filter is extended by SID11 and MSID11. Data bytes can also be filtered in this mode.

Table 38-9. Data Byte Filter Configuration

DNCNT[4:0]	Received Message Data Bits to be Compared Byte [bits]	EIDx Bits Used for Acceptance Filter
00000	No Comparison	No Comparison
00001	Data Byte 0[7]	EID[0]
00010	Data byte 0[7:6]	EID[0:1]
00011	Data byte 0[7:5]	EID[0:2]
00100	Data byte 0[7:4]	EID[0:3]
00101	Data byte 0[7:3]	EID[0:4]
00110	Data byte 0[7:2]	EID[0:5]
00111	Data byte 0[7:1]	EID[0:6]
01000	Data byte 0[7:0]	EID[0:7]
01001	Data byte 0[7:0] and Data Byte 1[7]	EID[0:8]
01010	Data byte 0[7:0] and Data Byte 1[7:6]	EID[0:9]
01011	Data byte 0[7:0] and Data Byte 1[7:5]	EID[0:10]
01100	Data byte 0[7:0] and Data Byte 1[7:4]	EID[0:11]
01101	Data byte 0[7:0] and Data Byte 1[7:3]	EID[0:12]
01110	Data byte 0[7:0] and Data Byte 1[7:2]	EID[0:13]
01111	Data byte 0[7:0] and Data Byte 1[7:1]	EID[0:14]
10000	Data byte 0[7:0] and Data Byte 1[7:0]	EID[0:15]
10001	Byte 0[7:0] and Byte 1[7:0] and Byte 2[7]	EID[0:16]
10010 to 11111	Byte 0[7:0] and Byte 1[7:0] and Byte 2[7:6]	EID[0:17]

Figure 38-16 illustrates how the first 18 data bits of the received message data payload are compared with the corresponding EIDx bits of the message acceptance filter (EID[17:0] bits in the C1FLTOBJxH/L registers). The IDE bit of the received message must be '0'.

Figure 38-16. CAN Operation with DeviceNet<sup>™</sup> Filtering



Note: The DeviceNet filtering configuration shown for the EIDx bits is DNCNT[4:0] = 10010.

## 38.8 Message Reception

The application has to configure the RX FIFO before it can be used for reception (see 38.3.4.4 Receive FIFO Configuration). In addition, the application has to configure and enable at least one filter (see 38.7.1 Filter Configuration).

The CAN FD Protocol Module continuously monitors the CAN bus. Messages that match a filter are stored in the RX FIFO pointed to by the filter (see 38.7.2 Filtering a Received Message). The message data are stored in the receive message objects.

#### 38.8.1 Receive Message Object

Table 38-10 specifies the receive message object used by the RX FIFOs. The receive objects contain the message ID, control bits, payload and timestamp.

- SID: Standard Identifier (ID) or Base ID.
- · EID: Extended Identifier.
- DLC: Data Length Code; specifies the number of data bytes in the frame (see 38.4.1.1 DLC Encoding).
- IDE: Identifier Extension; IDE = 0 means a Base Identifier frame is received. IDE = 1 means an Extended Identifier frame is received.
- RTR: Remote Transmit Request; this bit is only specified in CAN 2.0 frames. If this bit is set, the module is requested to respond with a frame transmission.
- FDF: FD Frame; if this bit is set, a CAN FD frame is received; otherwise, a CAN 2.0 frame is received.
- BRS: Bit Rate Switch; the data phase of a CAN FD frame is received using DBR if this bit is set. If the bit is clear, the whole frame is received using NBR.
- ESI: Error Status Indicator; the ESI bit reflects the error status of the transmitting node. A recessive ESI bit in a CAN FD frame indicates that the transmitting node is error passive; a dominant bit shows that the transmitting node is error active.
- FILHIT: Indicates the number of the filter that matched the received message.
- RXMSGTS: Timestamp of the received message; timestamping can be enabled for each RX FIFO individually using RXTSEN (C1FIFOCONxL[5]). The receive message object will not contain RXMSGTS if timestamping is disabled.
- Receive Buffer Data: Contains the payload of the message. The maximum payload is configured by the PLSIZEx bits (CxFIFOCON[31:29]).

### 38.8.1.1 Reading a Receive Message Object

Before reading a receive message object, the application must ensure that the RX FIFO is not empty by reading the CxFIFOSTAy register. The RX FIFO is not empty if TFNRFNIF is set.

The RX FIFO user address (CxFIFOUAy) points to the RAM of the next receive message object to read. R0 of the receive message object is read first, followed by R1, R2 and so on.

After the receive message object is read from RAM, the RX FIFO needs to be incremented by setting the UINC bit (CxFIFOCONy[8]). This will make the CAN FD Protocol module increment to the tail of the FIFO and update CxFIFOUAy.

Now the application can read the next message from the RX FIFO.

Table 38-10. Receive Message Object

Byte	Bit 7	Bit 6	Bit 5	Bi	t 4	Bit 3	Bit 2	Bit 1	Bit 0
0	SID[7:0]								
1			EID[4:0]					SID[10:8	]
2				EID[12:	5]				
3	-	-	SID11			EID[1	7:13]		
4			FILHIT[4:0]				-	-	ESI
5	FDF	BRS	RTR	IC	)E		DLC[3	:0]	
6	-	-	-	-	-		-	-	-
7	-	-	-	-	-		-	-	-
8			Red	eive Data	Byte 0				
9	Receive Data Byte 1								
10	Receive Data Byte 2								
11	Receive Data Byte 3								
12	Receive Data Byte 4								
13			Red	eive Data	Byte 5				
14			Red	eive Data	Byte 6				
15	Receive Data Byte 7								
m-3	Receive Data Byte n-3								
m-2									
m-1	Receive Data Byte n-2  Receive Data Byte n-1								
m									
111	Receive Data Byte n								

bit 15-11 **EID[4:0]**: Extended Identifier bits bit 10-0 **SID[10:0]**: Standard Identifier bits bit 15-14 **Unimplemented**: Read as 'x'

bit 13 SID11: In FD mode, the Standard ID can be extended to 12 bits using r1 bit

bit 12-0 **EID[17:5]**: Extended Identifier bits bit 10-9 **Unimplemented**: Read as 'x'

bit 8 **ESI:** Error Status Indicator bit - In CAN-to-CAN Gateway mode (ESIGM = 1), the transmitted ESI flag is a "logical OR" of ESI and the error passive state of the CAN controller.

In Normal mode, ESI indicates the error status:

1 = Transmitting node is error passive

0 = Transmitting node is error active

bit 7 FDF: FD Frame bit - distinguishes between CAN and CAN FD formats

bit 6 BRS: Bit Rate Switch bit - selects if Data Bit Rate is switched

bit 5 RTR: Remote Transmission Request bit (not used in CAN FD)

bit 4 IDE: Identifier Extension bit - distinguishes between base and extended format.

bit 3-0 **DLC[3:0]:** Data Length Code bits

bit 15:0 Unimplemented: Read as 'x'

bit 15:0 **RXMSGTS[15:0]:** Receive Message Timestamp bits bit 15:0 **RXMSGTS[31:16]:** Receive Message Timestamp bits

#### Notes:

- 1. Receive Message Object: Data Bytes 0-n; payload size is configured individually with the PLSIZE[2:0] bits.
- 2. R2 (RXMSGTSx) only exists in objects where RXTSEN is set.

### 38.8.2 Receive State Diagram

Figure 38-17 illustrates how messages are received. It illustrates how the most important receive flags are set and cleared.

- The CAN FD Protocol module remains Idle until a SOF is detected.
- After a SOF is detected, the module will receive the arbitration and control fields.
- Based on the DNCNTx bits and the received DLC, acceptance filtering will start. See Figure 4-14 for more details.
- If none of the filters match, the message will still be received, but it will not be stored.
- · If a filter matches, the device checks whether the receive object the filter points to is full.
- · If the receive object is not full, the rest of the data bytes are received and stored to the receive object.
- If the receive object is full, the RXOVIF bit will be set.
- If a complete message is received, the message will be stored, a timestamp will be attached and the receive flags will be set; the FIFO status flags will be updated and the FIFO head will be incremented.
- In case an error is detected during the reception of a message, an error frame will be transmitted and the appropriate error flags will be set.




Figure 38-17. Receive State Diagram

### 38.8.3 Resetting RX FIFO

A receive FIFO can be reset by:

- Setting FRESET (CxFIFOCONy[10]) or
- Placing the module in Configuration mode (OPMOD[2:0] = 100).

Resetting the FIFO will reset the head and tail pointers, and the CxFIFOSTAy register. The settings in the CxFIFOCONy registers will not change.

Before resetting an RX FIFO using FRESET, ensure that no enabled filter is pointing to the FIFO.

#### 38.8.4 Mismatch of DLC and Payload Size During Reception

The PLSIZEx bits reserve a certain number of bytes in the receive message object. The module handles mismatches between DLC and payload size as follows:

- If the number of bytes specified by the DLC is smaller than the number of bytes specified by the PLSIZEx bits, the received message bytes will be stored in the message object, without any padding.
- If the number of bytes specified by the DLC is bigger than the number of bytes specified by the PLSIZEx bits,
  the data bytes that fit in the receive message object are stored and the other data bytes that do not fit are
  discarded. The module ensures that the next message object in RAM does not get overwritten. The module will
  store the message in the receive object and the RX FIFO status flags will be updated. In addition, the IVMIF
  (CxINT[15]) and DLCMM flags (CxBDIAG1[31]) will be set.

#### 38.9 FIFO Behavior

This section explains the FIFO behavior when TEF and TXQ are enabled. FIFO 1 is configured as a TX FIFO and FIFO 2 as an RX FIFO. The remaining FIFOs are not configured.

#### Notes:

- 1. The start addresses are calculated based on the number of objects in the FIFO and the PLSIZEx bits.
- 2. The start addresses of the FIFOs given in Table 38-11 are calculated when TEF starts at 0x1400.

#### Table 38-11. Example FIFO Configuration

FIFO	Objects in FIFO	Payload per Object	Timestamp	Bytes in Object	Bytes in FIFO	Start Address
TEF	12	N/A	Yes	12	144	0x1400
TXQ	8	32	N/A	40	320	0x1490
FIFO 1	5	64	N/A	72	360	0x15D0
FIFO 2	16	64	Yes	76	1216	0x1738
FIFO 3	N/A	-	-	-	-	0x1BF8

#### 38.9.1 FIFO Status Flags

FIFO 1 through FIFO 3 can be configured as transmit or receive FIFOs. The same status flags in CxFIFOSTAy are used for transmit and receive FIFOs. The status flags behave differently based on the selected configuration.

#### 38.9.1.1 TX FIFO Status Flags

There are three transmit status flags:

- TFEIF (TFERFFIF): Transmit FIFO Empty Interrupt Flag; set when the FIFO is empty.
- TFHIF (TFHRFHIF): Transmit FIFO Half Empty Interrupt Flag; set when FIFO is less than half full.
- TFNIF (TFNRFNIF): Transmit FIFO Not Full Interrupt Flag; set when FIFO is not full.

The status flags of a transmit FIFO are set when there is space to load a new message object into the FIFO. Before the first message object is loaded (after the FIFO is reset), all status flags are set. When the FIFO is fully loaded, all flags are cleared.

#### 38.9.1.2 RX FIFO Status Flags

There are three receive status flags:

- RFFIF (TFERFFIF): Receive FIFO Full Interrupt Flag; set when the FIFO is full.
- RFHIF (TFHRFHIF): Receive FIFO Half Full Interrupt Flag; set when the FIFO is at least half full.
- RFNIF (TFNRFNIF): Receive FIFO Not Empty Interrupt Flag; set when there is at least one message in the FIFO.

The status flags of the receive FIFO are set when there are received messages in the FIFO. Before the first message is received (after the FIFO is reset), all status flags are cleared. When the FIFO is full, all flags are set.

### 38.9.1.3 TXQ Status Flags

There are two TXQ status flags:

- TXQEIF: TXQ Empty Interrupt Flag; set when the TXQ is empty.
- TXQNIF: TXQ Not Full Interrupt Flag; set when TXQ is not full.

The status flags of the TXQ are set when there is space to load a new message object into the TXQ. Before the first message object is loaded (after the TXQ is reset), all status flags are set. When the TXQ is fully loaded, all flags are cleared.

## 38.9.1.4 TEF Status Flags

There are four TEF status flags:

· TEFFIF: TEF Full Interrupt Flag; set when the TEF is full.

- TEFHIF: TEF Half Full Interrupt Flag; set when the TEF is at least half full.
- TEFNEIF: TEF Not Empty Interrupt Flag; set when there is at least one message in the TEF.
- TEFOVIF: TEF Overrun Interrupt Flag; set when an overflow has occurred.

The status flags of the TEF are set when there are transmitted messages in the FIFO. Before the first message is stored (after the TEF is reset), all status flags are cleared. When the TEF is full, all flags are set.

#### 38.9.2 Transmit FIFO Behavior

FIFO 1 is configured as a TX FIFO. CxFIFOCON1 is used to control the FIFO. CxFIFOSTA1 contains the status flags and the FIFO Index bits (FIFOCI[4:0]). CxFIFOUA1 contains the user address of the next transmit message object to be loaded

Figure Figure 38-18 through Figure 38-23 illustrate how the status flags, user address and FIFO index are updated for FIFO 1.

Figure 38-18 shows the status of FIFO 1 after Reset. Message objects, MO0 to MO4, are empty. All status flags are set. The user address and the FIFO index point to MO0.

Figure 38-18. FIFO 1 - Initial State




Figure 38-19 illustrates the status of FIFO 1 after the first message (MSG0) is loaded. MO0 now contains MSG0. The user application sets the UINC bit (CxFIFOCON1[8]), which causes the FIFO head to advance. The user address now points to MO1. TFEIF is cleared since the FIFO is no longer empty. The user application now sets TXREQ to request the transmission of MSG0.

Figure 38-19. FIFO 1 - First Message Loaded




Figure 38-20 illustrates the status of FIFO 1 after MSG0 is transmitted. The FIFO is empty again. TFEIF is set and TXREQ is cleared. FIFOCIx bits now point to MO1 with user address 0x218.

Figure 38-20. FIFO 1 - First Message Transmitted




Figure 38-21 illustrates the status of FIFO 1 after three more messages are loaded: MSG1-MSG3. The user address now points to MO4. TFHIF is cleared because the FIFO is now less than half empty.

Figure 38-21. FIFO 1 - Three More Messages Loaded




Figure 38-22 illustrates the status of FIFO 1 after two more messages are loaded: MSG4 and MSG5. CxFIFOUA1 now points to MO1. All status flags are now cleared because the FIFO is full. The user address and the FIFO index now point to MO1. The user application now sets TXREQ to request the transmission of MSG1-MSG5.

Figure 38-22. FIFO 1- FIFO Fully Loaded





Figure 38-23 illustrates the status of FIFO 1 after MSG1-MSG5 are transmitted. The FIFO is empty again. All status flags are set and TXREQ is cleared. The user address and the FIFO index point to MO1 again.

Figure 38-23. FIFO 1 - FIFO Fully Transmitted



#### 38.9.3 Receive FIFO Behavior

FIFO 2 is configured as an RX FIFO. CxFIFOCON2 is used to control the FIFO. CxFIFOSTA2 contains the status flags and the FIFO index (FIFOCIx). CxFIFOUA2 contains the user address of the next message object to read.

Figure 38-24 through Figure 38-31 illustrate how the status flags, user address and FIFO index are updated.

Figure 38-24 shows the status of FIFO 2 after the Reset. Message objects, MO0 to MO15, are empty. All status flags are cleared. The user address and the FIFO index point to MO0.

Figure 38-24. FIFO 2 - Initial State




Figure 38-25 illustrates the status of FIFO 2 after the first message (MSG0) is received. MO0 now contains MSG0. The FIFO index now points to MO1. RFNIF is set since the FIFO is not empty anymore.

Figure 38-25. FIFO 2 - First Message Received




Figure 38-26 illustrates the status of FIFO 2 after MSG0 is read. The user application reads the message from RAM and sets the UINC bit (CxFIFOCON2[8]). The user address increments and points to MO1. The FIFO index is unchanged. The FIFO is empty again. All flags are cleared.

Figure 38-26. FIFO 2 - First Message Read




Figure 38-27 illustrates the status of FIFO 2 after eight more messages are received: MSG1-MSG8. The user address still points to MO1. RFNIF and RFHIF are set because the FIFO is now half full. The FIFO index points to MO9.

### Figure 38-27. FIFO 2 - Half Full




Figure 38-28 illustrates the status of FIFO 2 after ten more messages are received: MSG5-MSG15. The user address still points to MO1. The FIFO index points to MO0. RFNIF and RFHIF are set.

Figure 38-28. FIFO 2 - FIFO Almost Full




Figure 38-29 illustrates the status of FIFO 2 after one more message is received: MSG16. All status flags are set because the FIFO is full. The user address and the FIFO index point to MO1.

Figure 38-29. FIFO 2 - FIFO Full




Figure 38-30 illustrates the status of FIFO 2 after one more message is received. Since FIFO 2 is already full, an overflow occurs. The message is discarded and RXOVIF is set. The user address and FIFO index has not changed.

Figure 38-30. FIFO 2 - FIFO Overflow





Figure 38-31 illustrates the status of FIFO 2 after the application cleared RXOVIF and read two more messages. RFFIF is clear because the FIFO is not full anymore. The user address points to MO3. The FIFO index has not changed.

Figure 38-31. FIFO 2 - Two More Messages Read



#### 38.9.4 Transmit Queue Behavior

C1TXQCON is used to control the TXQ. C1TXQSTA contains the status flags and the TXQ index (TXQCIx). C1TXQUA contains the user address of the next transmit message object to be loaded.

The TXQCI[4:0] bits are used by the CAN FD Protocol module to calculate the next message to transmit. TXQCIx bits are not incremented linearly. They are recalculated every time a message gets transmitted or TXREQ gets set.

Figure 38-32 through Figure 38-37 illustrate how the status flags and user address are updated. There is no need for the user application to use TXQCIx; therefore, it is not shown in the figures.

Figure 38-32 shows the status of the TXQ after Reset. Message objects, MO0 to MO7, are empty. All status flags are set. The user address points to MO0.

Figure 38-32. TXQ - Initial State




Figure 38-33 illustrates the status of the TXQ after the first message (MSG0) is loaded. MO0 now contains MSG0. The user application sets the UINC bit, which causes the FIFO head to advance. The user address now points to MO1. TXQEIF is cleared, since the queue is not empty anymore. The user application now sets TXREQ to request the transmission of MSG0.

#### Figure 38-33. TXQ - First Message Loaded




Figure 38-34 illustrates the status of the TXQ after MSG0 is transmitted. The TXQ is empty again. TXQEIF is set and TXREQ is cleared. The user address still points to MO1 because UINC is not set.

Figure 38-34. TXQ - First Message Transmitted




Figure 38-35 illustrates the status of the TXQ after MSG1 is loaded and UINC is set. The user address now points to the next free message object: MO0.

Figure 38-35. TXQ - Next Message Loaded




Figure 38-36 illustrates the status of the TXQ after six more messages are loaded: MSG2-MSG7. The user address now points to the last free message object: MO7.

Figure 38-36. TXQ - Next Six Messages Loaded





Figure 38-37 illustrates the status of the TXQ after MSG8 is loaded and UINC is set. The TXQ is now full, all flags are cleared. The user address now points to MO0. The user application now sets TXREQ. The messages will be transmitted based on the priority of their IDs.

Figure 38-37. TXQ - Full



#### 38.9.5 Transmit Event FIFO Behavior

C1TEFCONL and C1TEFCONH are used to control the TEF. C1TEFSTA contains the status flags. C1TEFUAL and C1TEFUAH contain the user address of the next message object to read.

The actual RAM address is calculated using Equation 38-21.

Figure 38-38 through Figure 38-45 illustrate how the status flags and user address are updated. The TEF stores transmitted messages; therefore, the flags behave similarly to an RX FIFO.

Figure 38-38 shows the status of the TEF after Reset. Message objects, MO0 to MO11, are empty. All status flags are cleared. The user address points to MO0.

Figure 38-38. TEF - Initial State




Figure Figure 38-39 shows the status of the TEF after the first transmit message is stored. MO0 contains ID0, the ID of MSG0. TEFNEIF is set since the TEF is not empty. The user address points to MO0.

Figure 38-39. TEF - First Transmit Message is Stored




Figure 38-40 illustrates the status of the TEF after ID0 is read. The user application reads the ID from RAM and sets the UINC bit (C1TEFCONL[8]). The user address increments and points to MO1. The TEF is empty again. All flags are cleared.

#### Figure 38-40. TEF - First ID Read




Figure 38-41 illustrates the status of the TEF after six more messages are transmitted: MSG1-MSG6. The user address points to MO1. TEFNEIF and TEFHIF are set because the TEF is now half full.

Figure 38-41. TEF - Half Full




Figure 38-42 illustrates the status of the TEF after five more messages are transmitted: MSG7-MSG11. The user address still points to MO1. TEFNEIF and TEFHIF are set.

Figure 38-42. TEF- Almost Full




Figure 38-43 illustrates the status of the TEF after one more message is transmitted: MSG12. All status flags are set because the TEF is full. The user address points to MO1.

#### Figure 38-43. TEF - Full




Figure 38-44 illustrates the status of the TEF after one more message is transmitted. Since the TEF is already full, an overflow occurs. The ID is discarded and TEFOVIF is set. The user address remains unchanged.

Figure 38-44. TEF - Overflow





Figure 38-45 illustrates the status of the TEF after the application cleared TEFOVIF and read one more message. TEFFIF is clear because the TEF is not full anymore. The user address points to MO2.

Figure 38-45. TEF - One More ID Read



### 38.10 Timestamping

The CAN FD Protocol module contains a Time Base Counter (TBC). The TBC is a 32-bit free-running counter that increments on multiples of SYSCLK and rolls over to zero when:

- TBCPRE[9:0] bits (CxTSCON[9:0]) are used to configure the prescaler for the TBC.
- Setting TBCEN (CxTSCON[16]) enables the TBC.
- Clearing TBCEN disables, stops and resets the TBC.
- The TBC has to be disabled before writing to C1TBC by clearing TBCEN.
- TEFTSEN (CxTEFCON[5]) has to be set to timestamp messages in the TEF.
- RXTSEN (CxFIFOCONy[5]) has to be set to timestamp messages in the individual RX FIFO.
- The application can read C1TBC at any time. Similar to any multibyte counter, the application has to consider that the counter increments and might roll over while reading different bytes of the counter.

All timestamps are 32 bits, allowing timestamps to be used for system time synchronization with high resolution.

A rollover of the TBC will generate an interrupt if TBCIE is set.

Messages can be timestamped either at the beginning of a frame or at the end, depending on the TSEOF bit (C1TSCON[17]). When TSEOF = 0, TSRES (C1TSCON[18]) specifies if FD frames are timestamped at SOF or the "reserved bit". Table 38-12 specifies the reference points when the timestamping occurs. At the reference point, the value of the TBC (C1TBC) is captured and stored into the message object:

- Receive Message Object: The TBC value is stored in the RXMSGTSx bits (see Table 38-10).
- TEF Object: The TBC value is stored in the TXMSGTSx bits (see Table 38-8).

Table 38-12. Reference Point

Frame	CAN 2.0	CAN FD
Start of TX	Sample point of SOF	Sample point of SOF or the bit after FDF
Start of RX	Sample point of SOF	Sample point of SOF or the bit after FDF
Valid TX	No error till end of EOF	No error till end of EOF
Valid RX	No error till the last, but one bit of EOF	No error till the last, but one bit of EOF

## 38.11 Interrupts


Interrupts can be classified into multiple layers. Lower layer interrupts propagate to higher layers by multiplexing them into single interrupts. Figure 38-46 illustrates the layers of interrupts.

- · FIFO Individual Interrupts
- · FIFO Combined Interrupts
- · Main Interrupts

These interrupts are then funneled into three separate module interrupts:

- Receive Interrupt
- Transmit Interrupt
- · Information Interrupt

All module interrupts are persistent, meaning the condition that caused the interrupt must be cleared within the module for the interrupt request to be removed.



### 38.11.1 FIFO Individual Interrupts

CxFIFOCONy contains the interrupt enable flags and CxFIFOSTAy contains the interrupt flags for the FIFOs. There is a separate register for each FIFO.

### 38.11.1.1 Transmit Queue Interrupts

CxTXQCON contains the interrupt enable flags and CxTXQSTA contains the interrupt flags for the TXQ.

The TXQ interrupt occurs when there is a change in the status of the TXQ. There are two interrupt sources:

- TXQ Not Full Interrupt Flag (TXQNIF)
- TXQ Empty Interrupt Flag (TXQEIF)

Both interrupts can be enabled individually. The interrupts cannot be cleared by the application; they will be cleared when the condition of the FIFO terminates.

Both interrupt sources are OR'd together and reflected in the TFIF0 flag (CxTXIF[0]).

#### 38.11.1.2 Receive FIFO Interrupts (RFIF)

The receive FIFO interrupts occur when there is a change in the status of the receive FIFO. There are three interrupt sources:

- · Receive FIFO Full Interrupt Flag (RFFIF)
- Receive FIFO Half Full Interrupt Flag (RFHIF)
- Receive FIFO Not Empty Interrupt Flag (RFNIF)

All three interrupts can be enabled individually. The interrupts cannot be cleared by the application; they will be cleared when the condition of the FIFO terminates.

The three interrupt sources are OR'd together and reflected in the RFIF[31:16] (CxRXIF[31:16]) and RFIF[15:1] (CxRXIF[15:1]) flags.

### 38.11.1.3 Transmit FIFO Interrupts (TFIF)

The transmit FIFO interrupts occur when there is a change in the status of the transmit FIFO. There are three interrupt sources:

- Transmit FIFO Not Full Interrupt Flag (TFNIF)
- · Transmit FIFO Half Empty Interrupt Flag (TFHIF)
- Transmit FIFO Empty Interrupt Flag (TFEIF)

All three interrupts can be enabled individually. The interrupts cannot be cleared by the application; they will be cleared when the condition of the FIFO terminates.

The three interrupt sources are OR'd together and reflected in the C1TXIF[31:1] flags.

### 38.11.1.4 Receive FIFO Overrun Interrupt (RXOVIF)

When a message is successfully received, but the FIFO is full, the RXOVIF of the individual FIFO is set. The flag must be cleared by the application.

#### 38.11.1.5 Transmit FIFO Attempt Interrupt (TXATIF)

When the retransmission of a message fails due to an error, and all retransmission attempts are exhausted, the TXATIF flag is set. The flag must be cleared by the application.

#### 38.11.1.6 Transmit Event FIFO Interrupts (TEFIF)

The TEF interrupts occur when there is a change in the status of the TEF. There are four interrupt sources:

- TEF Full Interrupt Flag (TEFFIF)
- · TEF Half Full Interrupt Flag (TEFHIF)
- · TEF Not Empty Interrupt Flag (TEFNEIF)
- TEF Overrun Interrupt Flag (TEFOVIF)

The TEF interrupts work similarly to the receive FIFO interrupts. All four interrupts can be enabled individually.

TEFFIF, TEFHIF and TEFNEIF cannot be cleared by the application; they will be cleared when the status of the FIFO terminates.

The TEFOVIF must be cleared by the application.

The four interrupt sources are OR'd together and reflected in the TEFIF flag (C1INT[4]).

### 38.11.2 FIFO Combined Interrupts

The following interrupts are individual FIFO interrupts:

FIFOs/TXQ: RFIFx, TFIFx, RFOVIFx and TFATIFx

They are combined into single Interrupt Status registers:

CxRXIF, CxTXIF, CxRXOVIF and CxTXATIF

The bits in the status registers are mapped to the FIFOs as follows: Bit 0 to TXQ, Bit 1 to FIFO 1, Bit 2 to FIFO 2, up to Bit 3 to FIFO 3. Since Bit 0 corresponds to the TXQ, Bit 0 of CxRXIF and CxRXOVIF is reserved. Hence, by

reading one register, the application can check the status of all FIFOs for a particular interrupt (e.g., any RFIFx pending).

The FIFO interrupts are enabled in CxFIFOCONy.

TXQ interrupts are enabled in CxTXQCON.

Clearing of the FIFO interrupts is explained in FIFO Individual Interrupts.

#### 38.11.3 Main Interrupts

The CxINT register contains all the main interrupts. The following interrupts are a logical 'OR' of all combined FIFO interrupts: RXIF, TXIF, RXOVIF and TXATIF. These flags are read-only and must be cleared in preceding hierarchies.

The TEFIF is generated in the TEF. This flag is read-only and must be cleared in preceding hierarchies.

All interrupts in CxINT can be enabled individually.

#### 38.11.3.1 Invalid Message Interrupt - IVMIF

If a CAN bus error or DLC mismatch is detected during the last message transmitted or received, the IVMIF bit will be set. The CxBDIAG1 register sets a flag for each error. The flag must be cleared by the application.

The following CAN bus errors will trigger the interrupt in case an error frame is transmitted: CRC, stuff bit, form, bit or ACK.

The flag will not be set if the ESI of a received message is set.

#### 38.11.3.2 Wake-Up Interrupt (WAKIF)

This bit is set if bus activity has been detected while the module is in Sleep mode. The flag must be cleared by the application.

#### 38.11.3.3 CAN Bus Error Interrupt (CERRIF)

The CxTREC register will count the errors during transmit and receive according to the ISO11898-1:2015. The CERRIF flag will be set based on the error counter values. The flag must be cleared by the application.

CERRIF will be set each time a threshold in the TEC/REC counter is crossed by the following conditions:

- TEC or REC exceeds the error warning state threshold.
- · The transmitter or receiver transitions to the error passive state.
- · The transmitter transitions to the bus off state.
- The transmitter or receiver transitions from the error passive to error active state.
- The module transitions from the bus off to error active state after the bus off recovery sequence.

When the user clears CERRIF, it will remain clear until a new counter crossing occurs.

#### 38.11.3.4 CAN Mode Change Interrupt (MODIF)

When the OPMOD[2:0] bits change, the MODIF flag will be set. The flag must be cleared by the application.

#### 38.11.3.5 CAN Timer Interrupt (TBCIF)

When the time base counter rolls over, TBCIF will be set. The flag must be cleared by the application.

#### 38.11.3.6 System Error Interrupt (SERRIF)

#### **Bus Bandwidth Error**

Bandwidth errors can happen during receive and transmit.

Receive Message Assembly Buffer (RX MAB) overflow occurs when the module is unable to write a received CAN message to RAM before the next message arrives.

Transmit Message Assembly Buffer (TX MAB) underflow occurs when the module cannot feed the TX MAB fast enough to provide consistent data to the Bit Stream Processor.

The SERRIF flag will be set and the ICODE[6:0] bits (C1VEC[6:0]) will be set to 100 0101.

#### **Handling of RX MAB Overflow Errors**

RX MAB overflows are not acceptable for some applications. To prevent overflows, frame filtering and data saving starts as early as possible; the latest at the beginning of the CRC field of the received message. Updating the FIFO

status has to wait until the beginning of the 7th bit of the EOF field, since the received frame is only valid at this point. The complete message has to be saved and the FIFO has to be updated until the end of the arbitration field of the next message.

In case of an RX MAB overflow, the new message that caused the overflow will be discarded. The module continues to store the message that is completely received and filtered. Afterwards, the module will be able to receive new messages on the bus. The application will be notified using the SERRIF bit.

The SERRIF bit (CxINT[12]) will be cleared by writing a zero to the bit. This will also clear the SERRIF condition from the ICODEx bits.

#### **Handling of TX MAB Underflow Errors**

ISO11898-1:2015 requires MAC data consistency: a transmitted message must contain consistent data. If data errors occur due to ECC errors, or TX MAB underflow, the transmission will not start. If the transmission is in progress, it will stop and the module will transition to either Restricted Operation or Listen Only mode, which is selectable using the SERRLOM bit (CxCON[18]).

The module handles these errors by stopping the transmission and transitioning to Restricted Operation or Listen Only mode. The CxTX pin will be forced high. Additionally, all TXREQs will be ignored. The application will be notified using SERRIF. The module will continue to receive messages.

#### 38.11.4 Interrupt Handling

The CAN FD Protocol module allows the application to handle interrupts efficiently by:

- Implementing a Look-up Table using the C1VEC registers.
- · Using the status registers and deciding which interrupt to service first.

The application can also use a combination of these two methods to handle interrupts.

#### 38.11.4.1 Interrupt Look-up Table

The ICODEx and FILHITx bits in the CxVEC register enable the application to use a Look-up Table to implement the Interrupt Service Routine (ISR).

The following bit fields allow the application to make full use of the three interrupt pins:

- TXCODE[6:0] bits: Reflect which object has a transmit interrupt pending
- RXCODE[6:0] bits: Reflect which object has a receive interrupt pending

A separate Look-up Table can be implemented for transmit and receive interrupts. If more than one object has a pending interrupt, the interrupt or FIFO with the highest number will show up in RXCODEx, TXCODEx and ICODEx. Once the interrupt with the highest priority is cleared, the next highest priority interrupt will show up in C1VECH/L. RXCODEx, TXCODEx and ICODEx are implemented with combinatorial logic using the interrupt flags as inputs.

#### 38.11.4.2 Interrupt Status Register

The CAN FD Protocol module contains three FIFOs and a TXQ. It would be complex to use the ICODEx bits since the interrupt priorities are determined by the module. Therefore, the following measures are taken to ensure efficient servicing of interrupts:

- CXINT contains all main interrupt sources. The application can identify the categories of interrupts that are pending and decide the order in which interrupts are to be serviced (e.g., RXIF).
- · All categories of interrupts for all FIFOs are combined into individual registers: CxRXIF, CxTXIF, CxRXOVIF and CxTXATIF. The application can identify the RFIFx bits that are pending by reading only one register. The same is true for TFIFx, RXOVIF and TXATIF.
- In the register map, the Interrupt Status registers are arranged in a single block: CxVEC, followed by CxINT, CxRXIF, CxTXIF, CxRXOVIF and CxTXATIF. This arrangement allows all status registers to be read with a single read access.

#### 38.11.5 Interrupt Flags

Table 1-13 summarizes all interrupt flags and lists how interrupts are cleared.

### Table 38-13. Interrupt Flags

Flags	Registers	Categories	Cleared by Module <sup>(1)</sup>	Cleared by Application	Read-Only <sup>(2)</sup>	Description
RFFIF, RFHIF, RFNIF	CxFIFOSTAy	FIFO	X	-	-	RX FIFO
TFNIF, TFHIF, TFEIF	CxFIFOSTAy	FIFO	X	-	-	TX FIFO
TXQNIF, TXQEIF	CxTXQSTA	TXQ	X	-	-	Transmit Queue
RXOVIF	CxFIFOSTAy	FIFO	-	X	-	RX Overrun
TXATIF	CxFIFOSTAy, CxTXQSTA	FIFO, TXQ	_	X	-	TX Attempt
TEFFIF, TEFHIF, TEFNEIF	CxTEFSTA	FIFO	X	-	-	TEF
TEFOVIF	CxTEFSTA	FIFO	-	X	-	TEF Overrun
RFIF[3:1]	CxRXIF	Combined	-	-	X	All RX FIFOs
TFIF[3:1]	CxTXIF	Combined	-	-	X	All TX FIFOs
RFOVIF[3:1]	CxRXOVIF	Combined	-	-	X	All RX FIFO Overruns
TFATIF[3:0]	CxTXATIF	Combined	-	-	X	All TX FIFO Attempts
RXIF	CxINT	Main	-	-	Х	RX
TXIF	CxINT	Main	-	-	Х	TX
RXOVIF	CxINT	Main	-	-	X	RX Overrun
TXATIF	CxINT	Main	-	-	Х	TX Attempt
TEFIF	CxINT	Main	-	-	X	TEF
IVMIF	CxINT	Main	-	X	-	Invalid Message
WAKIF	CxINT	Main	-	X	-	Wake-up
CERRIF	CxINT	Main	-	X	-	CAN Bus Error
MODIF	CxINT	Main	-	X	-	Mode Change
TBCIF	CxINT	Main	-	X	-	Time Base Counter
SERRIF	CxINT	Main	-	X	-	System Error

### Notes:

- The flags will be cleared when the condition of the FIFO terminates, initiated by the UINC bit (CxFIFOCONy[8]).
- 2. The flags need to be cleared in the preceding hierarchies.

## 38.12 Error Handling

Every CAN controller checks the messages on the bus for the following errors: bit, stuff, CRC, form and ACK errors. Whenever the controller detects an error, an error frame is transmitted that deletes the message on the bus. Error frames are always signaled using the nominal bit rate.


Error detection and fault confinement are described in the ISO11898-1:2015. CxTREC contains the error counters TEC and REC (TERRCNTx, RERRCNTx). CxTREC contains the error warning and error state bits. TEC and REC increment and decrement according to ISO11898-1:2015 specifications.

Figure 38-47 illustrates the different error states of the CAN FD Protocol module. The module starts in the error Active state. If the TEC or REC exceeds 127, the module transitions to the error passive state. If the TEC exceeds 255, the module will transition to the bus Off state.

The module transmits active error frames when in an error Active state. It will transmit passive error frames while in an error Passive state. When the module is in bus Off, the CxTX pin is always driven high and no dominant bits are transmitted

To avoid the module from transitioning to the error Passive state, the module will alert the application when the TEC or REC reaches 96, using the CERRIF interrupt flag (see CAN Bus Error Interrupt (CERRIF)). This allows the application to take action before it enters the error Passive state.

Figure 38-47. Error States



The error-free message counter, together with the error counters and error flags, can be used to determine the quality of the bus.

#### 38.12.1 Bus Diagnostic Registers

The Bus Diagnostic registers provide additional information about the health of the CAN bus:

- CxBDIAG0 contains separate error counters for receive/transmit and for nominal/data bit rates. The counters work differently than the counters in the CxTREC registers. They are simply incremented by one on every error. They are never decremented, but can be cleared by writing '0' to the register.
- CxBDIAG1 keeps track of the kind of error that occurred since the last clearing of the register. The CxBDIAG1
  register also contains the error-free message counter. The flags and the counter are cleared by writing '0' to the
  register.

#### 38.12.2 Recovery from Bus Off State

If the TEC exceeds 255, the TXBO (CxTREC[21]) and CERRIF (CxINT[13]) bits will be set. The module will go to bus off and start the bus off recovery sequence.

The bus off recovery sequence starts automatically. The module will transition out of the bus off state only after the detection of 128 Idle conditions (see "ISO11898-1:2015: Bus Off Management"). The module will set FRESET for all

# PIC18F26/46/56Q84

## CAN FD - Controller Area Network, Flexible ...

transmit FIFOs when entering the bus Off state to ensure that the module does not try to retransmit indefinitely. The application will be notified by CERRIF and has the option to queue new messages for transmission.

The module signals the exit from the bus Off state with the CERRIF bit and by setting the TXBOERR bit (CxBDIAG1[23]). Additionally, C1TREC will be Reset.

# 38.13 Register Definitions: CAN FD Control

Long bit name prefixes for the comparator peripherals are shown in the table below. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 38-14. CAN FD Long Bit Name Prefixes

Peripheral	Bit Name Prefix
CAN FD 1	C1

### 38.13.1 CxCON

Name: CxCON Offset: 0x0100

### **CAN FD Control Register**

Bit	31	30	29	28	27	26	25	24
		TXBW	/S[3:0]		ABAT		REQOP[2:0]	
Access	R/W	R/W	R/W	R/W	S/HC	R/W	R/W	R/W
Reset	0	0	0	0	0	1	0	0
Bit	23	22	21	20	19	18	17	16
		OPMOD[2:0]		TXQEN	STEF	SERRLOM	ESIGM	RTXAT
Access	R	R	R	R/W	R/W	R/W	R/W	R/W
Reset	1	0	0	1	1	0	0	0
Bit	15	14	13	12	11	10	9	8
	ON		SIDL	BRSDIS	BUSY	WFT	[1:0]	WAKFIL
Access	R/W		R/W	R/W	R	R/W	R/W	R/W
Reset	0		0	0	0	1	1	1
Bit	7	6	5	4	3	2	1	0
	CLKSEL	PXEDIS	ISOCRCEN			DNCNT[4:0]		
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	1	1	0	0	0	0	0

### Bits 31:28 - TXBWS[3:0] Transmit Bandwidth Sharing

Delay between two consecutive transmissions (in arbitration bit times)

Value	Description
1111-110	4096
0	
1011	2048
1010	1024
1001	512
1000	256
0111	128
0110	64
0101	32
0100	16
0011	8
0010	4
0001	2
0000	No delay

### Bit 27 - ABAT Abort All Pending Transmissions

	ABAT ABOTA III Origing Transmissions
Value	Description
1	Signals all transmit buffers to abort transmission
0	Module will clear this bit when all transmissions are aborted

## Bits 26:24 - REQOP[2:0] Request Operation Mode

	do.[_io]odaso.opo.aasoas
Value	Description
111	Sets Restricted Operation mode
110	Sets Normal CAN 2.0 mode; error frames on CAN FD frames
101	Sets External Loopback mode
100	Sets Configuration mode

Value	Description
011	Sets Listen Only mode
010	Sets Internal Loopback mode
001	Sets Disable mode
000	Sets Normal CAN FD mode; supports mixing of full CAN FD and Classic CAN 2.0 frames

### Bits 23:21 - OPMOD[2:0] Operation Mode Status

Value	Description
111	Module is in Restricted Operation mode
110	Module is in Normal CAN 2.0 mode; error frames on CAN FD frames
101	Module is in External Loopback mode
100	Module is in Configuration mode
011	Module is in Listen Only mode
010	Module is in Internal Loopback mode
001	Module is in Disable mode
000	Module is in Normal CAN FD mode; supports mixing of full CAN FD and Classic CAN 2.0 frames

#### Bit 20 – TXQEN Enable Transmit Queue<sup>(2)</sup>

1	/alue	Description
-	L	Enables TXQ and reserves space in RAM
(	)	Does not reserve space in RAM for TXQ

### Bit 19 – STEF Store in Transmit Event FIFO<sup>(2)</sup>

Value	Description
1	Saves transmitted messages in TEF
0	Does not save transmitted messages in TEF

### Bit 18 - SERRLOM Transition to Listen Only Mode on System Error<sup>(2)</sup>

Value	Description
1	Transitions to Listen Only mode on System Error
0	Transitions to Restricted Operation mode on System Error

### Bit 17 - ESIGM Transmit ESI in Gateway Mode<sup>(2)</sup>

	,,,,,
Value	Description
1	ESI is transmitted as recessive when the ESI of message is high or CAN controller is error passive
0	ESI reflects error status of the CAN controller

## Bit 16 – RTXAT Restrict Retransmission Attempts<sup>(2)</sup>

Value	Description
1	Restricted retransmissions attempts, uses TXAT[1:0]
0	Unlimited number of retransmission attempts, TXAT[1:0] bits will be ignored

#### Bit 15 - ON CAN Enable

Value	Description
1	CAN module is enabled
0	CAN module is disabled

## Bit 13 - SIDL CAN stop in Idle mode

Value	Description
1	Stops module operation in Idle mode
0	Does not stop module operation in Idle mode

#### Bit 12 - BRSDIS Bit Rate Switching (BRS) Disable

Value	Description
1	Bit rate switching is disabled, regardless of BRS in the transmit message object
0	Bit rate switching depends on the BRS of the transmit message object

### Bit 11 - BUSY CAN Module is Busy

1	'alue	Description
1		The CAN module is active
C		The CAN module is inactive

#### Bits 10:9 - WFT[1:0] Selectable Wake-up Filter Time

Value	Description
11	T11 Filter
10	T10 Filter
01	T01 Filter
00	T00 Filter

#### Bit 8 - WAKFIL Enable CAN Bus Line Wake-up Filter(2)

		I I I I I I I I I I I I I I I I I I
	Value	Description
ĺ	1	Uses CAN bus line filter for wake-up
	0	CAN bus line filter is not used for wake-up

#### Bit 7 - CLKSEL CAN Module Clock Source Select<sup>(2)</sup>

Value	Description
1	CAN module is run from EXTCLK
0	CAN module is run from system clock

### Bit 6 – PXEDIS Protocol Exception Event Detection Disabled<sup>(2)</sup>

A recessive "reserved bit" following a recessive FDF bit is called a "Protocol Exception"

	J
Value	Description
1	Protocol exception is treated as a form error
0	If a protocol exception is detected, CAN will enter the bus integrating state

#### Bit 5 - ISOCRCEN Enable ISO CRC in CAN FD Frames(2)

Value	Description
1	Includes stuff bit count in CRC field and uses non-zero CRC initialization vector
0	Does not include stuff bit count in CRC field and uses CRC initialization vector with all zeroes

#### Bits 4:0 - DNCNT[4:0] DeviceNet<sup>™</sup> Filter Bit Number (see Filtering on Data Bytes and Table 38-9 for more details

DIG 7.0 - D	bits 4.0 - bitott [4.0] Device tet. Thier bit Number (see Filtering on bata bytes and Table 50-5 for more details					
Value	Description					
11111-10	Invalid selection (compares up to 18 bits of data with EIDx)					
011						
10010	Compares up to Data Byte 2, bit 6 with EID17					
10001	Compares up to Data byte 2, bit 7 with EID16					
00010	Compares up to Data byte 0 bit 6 with EID1					
00001	Compares up to Data byte 0 bit 7 with EID0					
00000	Does not compare data bytes					

#### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxCONT: Accesses the top byte CON[31:24]
  - CxCONU: Accesses the upper byte CON[23:16]
  - CxCONH: Accesses the high byte CON[15:8]
  - CxCONL: Accesses the low byte CON[7:0]
- 2. These bits can only be modified in Configuration mode (OPMOD[2:0] = 100).

### 38.13.2 CxNBTCFG

Name: CxNBTCFG Offset: 0x0104

#### **CAN Nominal Bit Time Configuration Register**

Bit	31	30	29	28	27	26	25	24	
	BRP[7:0]								
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	0	0	0	0	0	0	0	0	
Bit	23	22	21	20	19	18	17	16	
				TSEG	1[7:0]				
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	0	0	1	1	1	1	1	0	
Bit	15	14	13	12	11	10	9	8	
					TSEG2[6:0]				
Access		R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset		0	0	0	1	1	1	1	
Bit	7	6	5	4	3	2	1	0	
					SJW[6:0]				
Access		R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset		0	0	0	1	1	1	1	

#### Bits 31:24 - BRP[7:0] Nominal Baud Rate Prescaler

Value	Description
11111111	$T_Q=T_{CY}/256$
0000000	$T_Q=T_{CY}/1$

#### Bits 23:16 - TSEG1[7:0] Nominal Time Segment 1 (Propagation Segment+Phase Segment 1)

	<b></b>	10101 Normal Time Cogment T (1 Topagation Cogment T hade Cogment T)
Va	llue	Description
11	.111111	Length is 256 x T <sub>Q</sub>
0.0	000000	Length is 1 x T <sub>Q</sub>

### Bits 14:8 - TSEG2[6:0] Nominal Time Segment 2 (Phase Segment 2)

1	/alue	Description
-	111111	Length is 128 x T <sub>Q</sub>
(	000000	Length is 1 x T <sub>Q</sub>

#### Bits 6:0 - SJW[6:0] Nominal Synchronization Jump Width

Value	Description	
1111111	Length is 128 x T <sub>Q</sub>	
0000000	Length is 1 x T <sub>Q</sub>	

#### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxNBTCFGT: Accesses the top byte NBTCFG[31:24]
  - CxNBTCFGU: Accesses the upper byte NBTCFG[23:16]
  - CxNBTCFGH: Accesses the high byte NBTCFG[15:8]
  - CxNBTCFGL: Accesses the low byte NBTCFG[7:0]
- 2. This register can only be modified in Configuration mode (OPMOD[2:0] = 100).

### 38.13.3 CxDBTCFG

Name: CxDBTCFG Offset: 0x0108

**CAN Data Bit Time Configuration Register** 

Bit	31	30	29	28	27	26	25	24	
	BRP[7:0]								
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	0	0	0	0	0	0	0	0	
Bit	23	22	21	20	19	18	17	16	
						TSEG1[4:0]			
Access				R/W	R/W	R/W	R/W	R/W	
Reset				0	1	1	1	0	
Bit	15	14	13	12	11	10	9	8	
						TSEG	52[3:0]		
Access					R/W	R/W	R/W	R/W	
Reset					0	0	1	1	
Bit	7	6	5	4	3	2	1	0	
				SJW[3:0]					
Access		•	•		R/W	R/W	R/W	R/W	
Reset					0	0	1	1	

#### Bits 31:24 - BRP[7:0] Data Baud Rate Prescaler

Value	Description
11111111	$T_Q=T_{CY}/256$
00000000	$T_Q = T_{CY}/1$

Bits 20:16 - TSEG1[4:0] Data Time Segment 1 (Propagation Segment+Phase Segment 1)

Bits 11:8 - TSEG2[3:0] Data Time Segment 2 (Phase Segment 2)

Bits 3:0 - SJW[3:0] Data Synchronization Jump Width

#### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxDBTCFGT: Accesses the top byte DBTCFG[31:24]
  - CxDBTCFGU: Accesses the upper byte DBTCFG[23:16]
  - CxDBTCFGH: Accesses the high byte DBTCFG[15:8]
  - CxDBTCFGL: Accesses the low byte DBTCFG[7:0]
- 2. This register can only be modified in Configuration mode (OPMOD[2:0] = 100).

### 38.13.4 CxTDC

Name: CxTDC Offset: 0x010C

**CAN Transmitter Delay Compensation Register** 

Bit	31	30	29	28	27	26	25	24
							EDGFLTEN	SID11EN
Access							R/W	R/W
Reset							0	0
Bit	23	22	21	20	19	18	17	16
							TDCMC	DD[1:0]
Access							R/W	R/W
Reset							1	0
Bit	15	14	13	12	11	10	9	8
					TDCO[6:0]			
Access		R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset		0	0	1	0	0	0	0
Bit	7	6	5	4	3	2	1	0
					TDC\	V[5:0]		
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			0	0	0	0	0	0

## Bit 25 - EDGFLTEN Enable Edge Filtering During Bus Integration State

Value	Description
1	Edge filtering is enabled according to ISO11898-1:2015
0	Edge filtering is disabled

#### Bit 24 - SID11EN Enable 12-Bit SID in CAN FD Base Format Messages

_		· - · · · · · · · · · · · · · · · · · ·	
	Value	Description	
	1	RRS is used as SID11 in CAN FD base format messages: SID[11:0]={SID[10:0],SID11}	
	0	Does not use RRS; SID[10:0]	

### Bits 17:16 - TDCMOD[1:0] Transmitter Delay Compensation Mode (Secondary Sample Point (SSP))

Value	Description
11-10	Auto: Measures delay and adds TSEG1[4:0] (CxDBTCFG[19:16]; adds TDCO[6:0]
01	Manual: Does not measure, uses TDCV[5:0] +TDCO[6:0]
00	Disables

## Bits 14:8 - TDCO[6:0] Transmitter Delay Compensation Offset (Secondary Sample Point (SSP))

Value is two's complement, offset can be positive, zero or negative

Value	Description
0000000	
11111111	-64 x T <sub>CY</sub>

## Bits 5:0 - TDCV[5:0] Transmitter Delay Compensation Value bits (Secondary Sample Point (SSP))

Value	Description
111111	63 x T <sub>CY</sub>
000000	0 x T <sub>CY</sub>

# PIC18F26/46/56Q84

# CAN FD - Controller Area Network, Flexible ...

#### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxTDCT: Accesses the top byte TDC[31:24]
  - CxTDCU: Accesses the upper byte TDC[23:16]
  - CxTDCH: Accesses the high byte TDC[15:8]
  - CxTDCL: Accesses the low byte TDC[7:0]
- 2. This register can only be modified in Configuration mode (OPMOD[2:0] = 100).

### 38.13.5 CxTBC

Name: CxTBC Offset: 0x0110

**CAN Time Base Counter Register** 

Bit	31	30	29	28	27	26	25	24
				TBC[	31:24]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	23	22	21	20	19	18	17	16
				TBC[2	23:16]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	15	14	13	12	11	10	9	8
				TBC	[15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
				TBC	[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

# Bits 31:0 - TBC[31:0] CAN Time Base Counter

This is a free-running timer that increments every TBCPRE[9:0] clock when TBCEN is set

### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxTBCT: Accesses the top byte TBC[31:24]
  - CxTBCU: Accesses the upper byte TBC[23:16]
  - CxTBCH: Accesses the high byte TBC[15:8]
  - CxTBCL: Accesses the low byte TBC[7:0]
- 2. The Time Base Counter (TBC will be stopped and reset when TBCEN = 0 to save power).
- 3. The TBC prescaler count will be reset on any write to CxTBC (TBCPREx will be unaffected).

### 38.13.6 CxTSCON

Name: CxTSCON Offset: 0x0114

**CAN Timestamp Control Register** 

Bit	31	30	29	28	27	26	25	24
Access								
Reset								
Bit	23	22	21	20	19	18	17	16
						TSRES	TSEOF	TBCEN
Access						R/W	R/W	R/W
Reset						0	0	0
Bit	15	14	13	12	11	10	9	8
							TBCPI	RE[9:8]
Access		•	•				R/W	R/W
Reset							0	0
	_	_	_		_	_		
Bit	7	6	5	4	3	2	1	0
				TBCPI	RE[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

# Bit 18 - TSRES Timestamp Reset (CAN FD frames only)

Value	Description
1	Timestamp resets at sample point of the bit following the FDF bit
0	Timestamp resets at sample point of Start-of-Frame (SOF)

# Bit 17 - TSEOF Timestamp End-of-Frame (EOF)

Value	Description
1	Timestamp when frame is taken valid (11898-1 10.7):
	RX no error until last, but one bit of EOF
	TX no error until the end of EOF
0	Timestamp at "beginning" of frame:
	Classical Frame: At sample point of SOF
	FD Frame: see TSRES bit

# Bit 16 - TBCEN Time Base Counter (TBC) Enable

Value	Description
1	Enables TBC
0	Stops and resets TBC

# Bits 9:0 - TBCPRE[9:0] CAN Time Base Counter Prescaler

	201 Kaliging Critic Films Bass Counter 1 recount
Value	Description
11111111	TBC increments every 1024 clocks
11	
00000000	TBC increments every 1 clock
00	

# PIC18F26/46/56Q84

# CAN FD - Controller Area Network, Flexible ...

### Note:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxTSCONT: Accesses the top byte TSCON[31:24]
  - CxTSCONU: Accesses the upper byte TSCON[23:16]
  - CxTSCONH: Accesses the high byte TSCON[15:8]
  - CxTSCONL: Accesses the low byte TSCON[7:0]

### 38.13.7 CxVEC

Name: CxVEC Offset: 0x0118

# **CAN Interrupt Code Register**

Bit	31	30	29	28	27	26	25	24
					RXCODE[6:0]			
Access		R	R	R	R	R	R	R
Reset		1	0	0	0	0	0	0
Bit	23	22	21	20	19	18	17	16
					TXCODE[6:0]			
Access		R	R	R	R	R	R	R
Reset		1	0	0	0	0	0	0
Bit	15	14	13	12	11	10	9	8
						FILHIT[4:0]		
Access				R	R	R	R	R
Reset				0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
					ICODE[6:0]			
Access		R	R	R	R	R	R	R
Reset		1	0	0	0	0	0	0

### Bits 30:24 - RXCODE[6:0] Receive Interrupt Flag Code

Value	Description
1111111-	Reserved
1000001	
1000000	No interrupt
0111111-	Reserved
0000100	
0000011	FIFO 3 interrupt (RFIF[3] is set)
0000010	FIFO 2 interrupt (RFIF[2] is set)
0000001	FIFO 1 interrupt (RFIF[1] is set)
0000000	Reserved; FIFO 0 cannot receive

# Bits 22:16 - TXCODE[6:0] Transmit Interrupt Flag Code

	Transmit monaper lag codo
Value	Description
1111111-	Reserved
1000001	
1000000	No interrupt
0111111-	Reserved
0000100	
0000011	FIFO 3 interrupt (TFIF[3] is set)
0000010	FIFO 2 interrupt (TFIF[2] is set)
0000001	FIFO 1 interrupt (TFIF[1] is set)
0000000	FIFO 0 interrupt (TFIF[0] is set)

# Bits 12:8 - FILHIT[4:0] Filter Hit Number

Value	Description
11111-01	Reserved
100	
01011	Filter 11

Value	Description
01010	Filter 10
00001	Filter 1
00000	Filter 0

# Bits 6:0 - ICODE[6:0] Interrupt Flag Code

Value	Description
1111111-	Reserved
1001011	
1001010	Transmit attempt interrupt (Any bit in CxTXATIF is set)
1001001	Transmit event FIFO interrupt (any bit in CxTEFSTA is set)
1001000	Invalid message occurred (IVMIF/IE)
1000111	CAN module mode change occurred (MODIF/IE)
1000110	CAN timer overflow (TBCIF/IE)
1000101	RX/TX MAB overflow/underflow (RX: Message received before previous message was saved to
	memory; TX: Can't feed TX MAB fast enough to transmit consistent data.) (SERRIF/IE)
1000100	Address error interrupt (illegal FIFO address presented to system) (SERRIF/IE)
1000011	Receive FIFO overflow interrupt (any bit in CxRXOVIF is set)
1000010	Wake-up interrupt (WAKIF/WAKIE)
1000001	Error interrupt (CERRIF/IE)
1000000	No interrupt
0111111-	Reserved
0000100	
0000011	FIFO 3 Interrupt (TFIF3 or RFIF3 is set)
0000010	FIFO 2 Interrupt (TFIF2 or RFIF2 is set)
0000001	FIFO 1 Interrupt (TFIF1 or RFIF1 is set)
0000000	FIFO 0 Interrupt (TFIF0 is set)

### Note:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxVECT: Accesses the top byte VEC[31:24]
  - CxVECU: Accesses the upper byte VEC[23:16]
  - CxVECH: Accesses the high byte VEC[15:8]
  - CxVECL: Accesses the low byte VEC[7:0]

### 38.13.8 CxINT

Name: CxINT Offset: 0x011C

# **CAN Interrupt Register**

Bit	31	30	29	28	27	26	25	24
	IVMIE	WAKIE	CERRIE	SERRIE	RXOVIE	TXATIE		
Access	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0		
Bit	23	22	21	20	19	18	17	16
				TEFIE	MODIE	TBCIE	RXIE	TXIE
Access				R/W	R/W	R/W	R/W	R/W
Reset				0	0	0	0	0
Bit	15	14	13	12	11	10	9	8
	IVMIF	WAKIF	CERRIF	SERRIF	RXOVIF	TXATIF		
Access	HS/C	HS/C	HS/C	HS/C	R	R		
Reset	0	0	0	0	0	0		
Bit	7	6	5	4	3	2	1	0
				TEFIF	MODIF	TBCIF	RXIF	TXIF
Access				R	HS/C	HS/C	R	R
Reset				0	0	0	0	0

# Bit 31 - IVMIE Invalid Message Interrupt Enable

Value	Description
1	Invalid message interrupt is enabled
0	Invalid message interrupt is disabled

### Bit 30 - WAKIE Bus Wake-up Activity Interrupt Enable

Value	Description
1	Wake-up activity interrupt is enabled
0	Wake-up activity interrupt is disabled

# Bit 29 - CERRIE CAN Bus Error Interrupt Enable

V	alue	Description
1		CAN bus error interrupt is enabled
0		CAN bus error interrupt is disabled

### Bit 28 - SERRIE System Error Interrupt Enable

Value	Description
1	System error interrupt is enabled
0	System error interrupt is disabled

### Bit 27 - RXOVIE Receive Buffer Overflow Interrupt Enable

Value	Description
1	Receive buffer overflow interrupt is enabled
0	Receive buffer overflow interrupt is disabled

# Bit 26 - TXATIE Transmit Attempt Interrupt Enable

Value	Description
1	Transmit attempt interrupt is enabled
0	Transmit attempt interrupt is disabled

### Bit 20 - TEFIE Transmit Event FIFO Interrupt Enable

Value	Description
1	Transmit event FIFO interrupt is enabled
0	Transmit event FIFO interrupt is disabled

### Bit 19 - MODIE Mode Change Interrupt Enable

Value	Description
1	Mode change interrupt is enabled
0	Mode change interrupt is disabled

### Bit 18 - TBCIE CAN Timer Interrupt Enable

Value	Description
1	CAN timer interrupt is enabled
0	CAN timer interrupt is disabled

### Bit 17 - RXIE Receive Object Interrupt Enable

Value	Description
1	Receive object interrupt is enabled
0	Receive object interrupt is disabled

### Bit 16 - TXIE Transmit Object Interrupt Enable

Value	Description
1	Transmit object interrupt is enabled
0	Transmit object interrupt is disabled

### Bit 15 - IVMIF Invalid Message Interrupt Flag(2)

	<u> </u>
Value	Description
1	Invalid message interrupt occurred
0	No invalid message interrupt

### Bit 14 - WAKIF Bus Wake-up Activity Interrupt Flag<sup>(2)</sup>

	in the Date France ap France, interrupt France
Value	Description
1	Wake-up activity interrupt occurred
0	No wake-up activity interrupt

### Bit 13 - CERRIF CAN Bus Error Interrupt Flag<sup>(2)</sup>

Value	Description
1	CAN bus error interrupt occurred
0	No CAN bus error interrupt

### Bit 12 - SERRIF System Error Interrupt Flag<sup>(2)</sup>

Value	Description				
1	System error interrupt occurred				
0	No system error interrupt				

# Bit 11 - RXOVIF Receive Buffer Overflow Interrupt Flag

Value	Description
1	Receive buffer overflow interrupt occurred
0	No receive buffer overflow interrupt

### Bit 10 - TXATIF Transmit Attempt Interrupt Flag

Value	Description					
1 Transmit attempt interrupt occurred						
0	No transmit attemp interrupt					

# Bit 4 - TEFIF Transmit Event FIFO Interrupt Flag

# CAN FD - Controller Area Network, Flexible ...

Value	Description
1	Transmit event FIFO interrupt occurred
0	No transmit event FIFO interrupt

# Bit 3 – MODIF CAN Mode Change Interrupt Flag<sup>(2)</sup>

	Value	Description
Г	1	CAN module mode change occurred (OPMOD[2:0] have changed to reflect REQOP[2:0])
	0	No mode change occurred

### Bit 2 - TBCIF CAN Timer Overflow Interrupt Flag<sup>(2)</sup>

	<u> </u>
Value	Description
1	TBC has overflowed
0	TBC has not overflowed

# Bit 1 - RXIF Receive Object Interrupt Flag

Value Description		Description			
	1	Receive object interrupt is pending			
	0	No Receive object interrupts are pending			

### Bit 0 - TXIF Transmit Object Interrupt Flag

	<u> </u>
Value	Description
1	Transmit object interrupt is pending
0	No transmit object interrupts are pending

### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxINTT: Accesses the top byte INT[31:24]
  - CxINTU: Accesses the upper byte INT[23:16]
  - CxINTH: Accesses the high byte INT[15:8]
  - CxINTL: Accesses the low byte INT[7:0]
- 2. Flag is set by hardware and cleared by application.

### 38.13.9 CxRXIF

Name: CxRXIF Offset: 0x0120

CAN Receive Interrupt Status Register

Bit	31	30	29	28	27	26	25	24
Access								
Reset								
Bit	23	22	21	20	19	18	17	16
Access								
Reset								
Neset								
				40				•
Bit	15	14	13	12	11	10	9	8
Access								
Reset								
Bit	7	6	5	4	3	2	1	0
Dit.	,			<b>-</b>		RFIF[2:0]	· '	
Access					R	R	R	
Reset					0	0	0	

### Bits 3:1 - RFIF[2:0] Receive FIFO Interrupt Pending

	• • •	
Value	Description	
1	One or more enabled receive FIFO interrupts are pending for the respective FIFO	
0	No enabled receive FIFO interrupts for the respective FIFO are pending	

### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxRXIFT: Accesses the top byte RXIF[31:24]
  - CxRXIFU: Accesses the upper byte RXIF[23:16]
  - CxRXIFH: Accesses the high byte RXIF[15:8]
  - CxRXIFL: Accesses the low byte RXIF[7:0]
- 2. RFIFx is the 'or' of all enabled RX FIFO flags (individual flags need to be cleared in the FIFO register).

### 38.13.10 CxTXIF

Name: CxTXIF Offset: 0x0124

**CAN Transmit Interrupt Status Register** 

Bit	31	30	29	28	27	26	25	24
Access								
Reset								
Bit	23	22	21	20	19	18	17	16
Access								
Reset								
Bit	15	14	13	12	11	10	9	8
Access								
Reset								
. 10001								
Bit	7	6	5	4	3	2	1	0
	,		J	<del>-</del>			[3:0]	
ا								
Access					R	R	R	R
Reset					0	0	0	0

### Bits 3:0 - TFIF[3:0] Transmit FIFO/TXQ Interrupt Pending

	• • • · · · · · · · · · · · · · · · · ·
Value	Description
1	One or more enabled transmit FIFO/TXQ interrupts are pending for the respective FIFO/TXQ
0	No enabled transmit FIFO/TXQ interrupts for the respective FIFO/TXQ are pending

### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxTXIFT: Accesses the top byte TXIF[31:24]
  - CxTXIFU: Accesses the upper byte TXIF[23:16]
  - CxTXIFH: Accesses the high byte TXIF[15:8]
  - CxTXIFL: Accesses the low byte TXIF[7:0]
- 2. TFIFx is the 'or' of all enabled TX FIFO flags (individual flags need to be cleared in the FIFO register).

### 38.13.11 CxRXOVIF

Name: CxRXOVIF Offset: 0x0128

CAN Receive Overflow Interrupt Status Register

Bit	31	30	29	28	27	26	25	24
Access								
Reset								
Bit	23	22	21	20	19	18	17	16
Access		•	•			•	•	
Reset								
Bit	15	14	13	12	11	10	9	8
Access								
Reset								
Bit	7	6	5	4	3	2	1	0
						RFOVIF[2:0]		
Access		•			R	R	R	
Reset					0	0	0	

Bits 3:1 - RFOVIF[2:0] Receive FIFO Overflow Interrupt Pending

		<u> </u>
Value	Description	
1	Interrupt is pending	
0	Interrupt is not pending	

### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxRXOVIFT: Accesses the top byte RXOVIF[31:24]
  - CxRXOVIFU: Accesses the upper byte RXOVIF[23:16]
  - CxRXOVIFH: Accesses the high byte RXOVIF[15:8]
  - CxRXOVIFL: Accesses the low byte RXOVIF[7:0]
- 2. RFOVIFx mirrors the overflow bit of its respective FIFO register, individual flags need to be cleared in said FIFO register.

### 38.13.12 CxTXATIF

Name: CxTXATIF Offset: 0x012C

**CAN Transmit Attempt Interrupt Status Register** 

Bit	31	30	29	28	27	26	25	24		
Access										
Reset										
Bit	23	22	21	20	19	18	17	16		
Access										
Reset										
Bit	15	14	13	12	11	10	9	8		
Access										
Reset										
Bit	7	6	5	4	3	2	1	0		
						TFATIF[3:0]				
Access					R	R	R	R		
Reset					0	0	0	0		

Bits 3:0 - TFATIF[3:0] Transmit FIFO/TXQ Attempt Interrup Pending

Value	Description			
1	Interrupt is pending			
0	Interrupt is not pending			

### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxTXATIFT: Accesses the top byte TXATIF[31:24]
  - CxTXATIFU: Accesses the upper byte TXATIF[23:16]
  - CxTXATIFH: Accesses the high byte TXATIF[15:8]
  - CxTXATIFL: Accesses the low byte TXATIF[7:0]
- TFATIFx mirrors the transmit attempt interrupt bit of its respective FIFO register, individual flags need to be cleared in said FIFO register.

### 38.13.13 CxTXREQ

Name: CxTXREQ Offset: 0x0130

**CAN Transmit Request Register** 

Bit	31	30	29	28	27	26	25	24		
Access										
Reset										
Bit	23	22	21	20	19	18	17	16		
Access										
Reset										
Bit	15	14	13	12	11	10	9	8		
Access										
Reset										
Bit	7	6	5	4	3	2	1	0		
						TXREQ[3:0]				
Access					R/W	R/W	R/W	R/W		
Reset					0	0	0	0		

### Bits 3:0 - TXREQ[3:0] Message Send Request

Setting each bit to '1' requests sending a message in its respective object. The bit will automatically clear when the message(s) queued in the object is (are) successfully sent. This bit can NOT be used for aborting a transmission.

### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxTXREQT: Accesses the top byte TXREQ[31:24]
  - CxTXREQU: Accesses the upper byte TXREQ[23:16]
  - CxTXREQH: Accesses the high byte TXREQ[15:8]
  - CxTXREQL: Accesses the low byte TXREQ[7:0]
- 2. These bits are only valid if the associated objects are configured as transmit objects (TXEN = 1). Otherwise, setting them has no effect.

### 38.13.14 CxTREC

Name: CxTREC Offset: 0x0134

CAN Transmit/Receive Error Count Register

Bit	31	30	29	28	27	26	25	24
Access								_
Reset								
Bit	23	22	21	20	19	18	17	16
			TXBO	TXBP	RXBP	TXWARN	RXWARN	EWARN
Access			R	R	R	R	R	R
Reset			1	0	0	0	0	0
Bit	15	14	13	12	11	10	9	8
				TERRO	NT[7:0]			
Access	R	R	R	R	R	R	R	R
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
				RERRC	NT[7:0]			
Access	R	R	R	R	R	R	R	R
Reset	0	0	0	0	0	0	0	0

Bit 21 - TXBO Transmitter in Error Bus Off State

In Configuration mode, TXBO is set since the module is not on the bus.

Bit 20 - TXBP Transmitter in Error Bus Passive State

Bit 19 - RXBP Receiver in Error Bus Passive State

Bit 18 – TXWARN Transmitter in Error Warning State

Bit 17 - RXWARN Receiver in Error Warning State

Bit 16 - EWARN Transmitter or Receiver is in Error Warning State

Bits 15:8 - TERRCNT[7:0] Transmit Error Counter

Bits 7:0 - RERRCNT[7:0] Receive Error Counter

#### Note:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxTRECT: Accesses the top byte TREC[31:24]
  - CxTRECU: Accesses the upper byte TREC[23:16]
  - CxTRECH: Accesses the high byte TREC[15:8]
  - CxTRECL: Accesses the low byte TREC[7:0]

### 38.13.15 CxBDIAG0

Name: CxBDIAG0 Offset: 0x0138

CAN Bus Diagnostics Register 0

Bit	31	30	29	28	27	26	25	24		
				DTERRO	CNT[7:0]					
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		
Bit	23	22	21	20	19	18	17	16		
	DRERRCNT[7:0]									
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		
Bit	15	14	13	12	11	10	9	8		
				NTERRO	CNT[7:0]					
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		
Bit	7	6	5	4	3	2	1	0		
				NRERR	CNT[7:0]					
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		

Bits 31:24 - DTERRCNT[7:0] Data Bit Rate Transmit Error Counter

Bits 23:16 - DRERRCNT[7:0] Data Bit Rate Receive Error Counter

Bits 15:8 - NTERRCNT[7:0] Nominal Bit Rate Transmit Error Counter

Bits 7:0 - NRERRCNT[7:0] Nominal Bit Rate Receive Error Counter

### Note:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxBDIAG0T: Accesses the top byte BDIAG0[31:24]
  - CxBDIAG0U: Accesses the upper byte BDIAG0[23:16]
  - CxBDIAG0H: Accesses the high byte BDIAG0[15:8]
  - CxBDIAG0L: Accesses the low byte BDIAG0[7:0]

### 38.13.16 CxBDIAG1

Name: CxBDIAG1 Offset: 0x013C

CAN Bus Diagnostics Register 1

Bit	31	30	29	28	27	26	25	24
	DLCMM	ESI	DCRCERR	DSTUFERR	DFORMERR		DBIT1ERR	DBIT0ERR
Access	R/W	R/W	R/W	R/W	R/W		R/W	R/W
Reset	0	0	0	0	0		0	0
Bit	23	22	21	20	19	18	17	16
	TXBOERR		NCRCERR	NSTUFERR	NFORMERR	NACKERR	NBIT1ERR	NBIT0ERR
Access	R/W		R/W	R/W	R/W	R/W	R/W	R/W
Reset	0		0	0	0	0	0	0
Bit	15	14	13	12	11	10	9	8
				EFMSG	NT[15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
				EFMSG	CNT[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

#### Bit 31 - DLCMM DLC Mismatch

During a transmission or reception, the specified DLC is larger than the PLSIZEx of the FIFO element.

### Bit 30 - ESI ESI Flag of Received CAN FD Message Set

#### Bit 29 - DCRCERR Received Message with CRC Incorrect Checksum in the Data Segment

The CRC Checksum of a received message is considered incorrect if the CRC of the incoming message does not match with the CRC calculated from the received data.

### Bit 28 - DSTUFERR Received Message with Illegal Sequence in the Data Segment

An Illegal Sequence occurs when more than five equal bits in sequence in a part of the received message where this is not allowed.

### Bit 27 - DFORMERR Received Frame with a Fixed Format Error in Data Segment

A fixed format error occurs when a part of the incoming frame with a fixed format has the wrong format.

### Bit 25 - DBIT1ERR Transmitted Message Recessive Level in Data Segment

During the data segment of a message transmission, the device wanted to send a recessive level (bit of logical value '1'), but the monitored bus value was dominant.

#### Bit 24 - DBIT0ERR Transmitted Message Dominant Level in Data Segment

During the transmission of a message, the device wanted to send a dominant level (logical value '0'), but the monitored bus value was recessive.

### Bit 23 - TXBOERR Device Went to Bus Off

### Bit 21 - NCRCERR Received Message with CRC Incorrect Checksum in Non-Data Segment

The CRC Checksum of a received message is considered incorrect if the CRC of the incoming message does not match with the CRC calculated from the received data.

# PIC18F26/46/56Q84

# CAN FD - Controller Area Network, Flexible ...

### Bit 20 - NSTUFERR Received Message with Illegal Sequence in Non-Data Segment

An Illegal Sequence occurs when more than five equal bits in sequence in a part of the received message where this is not allowed

# **Bit 19 – NFORMERR** Received Frame with a Fixed Format Error in Non-Data Segment A fixed format error occurs when a part of the incoming frame with a fixed format has the wrong format

Bit 18 - NACKERR Transmitted Message Not Acknowledged

Transmitted message was not Acknowledged

### Bit 17 - NBIT1ERR Transmitted Message Dominant Level in Non-Data Segment

During the non-data segment of a message transmission, the device wanted to send a recessive level (bit of logical value '1'), but the monitored bus value was dominant

### Bit 16 - NBIT0ERR Transmitted Message Dominant Level in Non-Data Segment

During the transmission of a message(or Acknowledge bit, or active error flag or overload flag), the device wanted to send a dominant level (logical value '0'), but the monitored bus value was recessive. During bus off recovery, this status is set each time a sequence of 11 recessive bits have been monitored. This enables the CPU to monitor the proceeding of the bus off recovery sequence (indicating the bus is not stuck at dominant or continuously disturbed).

### Bits 15:0 - EFMSGCNT[15:0] Error-Free Message Counter

#### Note:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxBDIAG1T: Accesses the top byte BDIAG1[31:24]
  - CxBDIAG1U: Accesses the upper byte BDIAG1[23:16]
  - CxBDIAG1H: Accesses the high byte BDIAG1[15:8]
  - CxBDIAG1L: Accesses the low byte BDIAG1[7:0]

### 38.13.17 CxTEFCON

Name: CxTEFCON Offset: 0x0140

# CAN Transmit Event FIFO Control Register

Bit	31	30	29	28	27	26	25	24
						FSIZE[4:0]		
Access				R/W	R/W	R/W	R/W	R/W
Reset				0	0	0	0	0
Bit	23	22	21	20	19	18	17	16
Access								
Reset								
Bit	15	14	13	12	11	10	9	8
						FRESET		UINC
Access		•	•			S/HC		S/HC
Reset						1		0
Bit	7	6	5	4	3	2	1	0
			TEFTSEN		TEFOVIE	TEFFIE	TEFHIE	TEFNEIE
Access			R/W		R/W	R/W	R/W	R/W
Reset			0		0	0	0	0

### Bits 28:24 - FSIZE[4:0] FIFO Size(2)

	. •.==[•] • •.=•
Value	Description
11111	FIFO is 32 messages deep
00010	FIFO is 3 messages deep
00001	FIFO is 2 messages deep
00000	FIFO is 1 message deep

#### Bit 10 - FRESET FIFO Reset

	THE TREE TO THE TREE TREE TO THE TREE TREE TREE TREE TREE TREE TREE
Value	Description
1	FIFO will be reset when bit is set, cleared by hardware when FIFO is reset; the user should poll
	whether this bit is clear before taking any action
0	No effect

### Bit 8 - UINC Increment Tail

	The more many ram
Value Description	
1	When this bit is set, the FIFO tail will increment by a single message
0	FIFO tail will not increment

### Bit 5 - TEFTSEN Transmit Event FIFO Timestamp Enable<sup>(2)</sup>

Value	Description
1	Timestamps elements in TEF
0	Does not timestamp elements in TEF

### Bit 3 – TEFOVIE Transmit Event FIFO Overflow Interrupt Enable

Value	Description	
1	Interrupt is enabled for overflow event	
0	Interrupt is disabled for overflow event	

### Bit 2 - TEFFIE Transmit Event FIFO Full Interrupt Enable

# CAN FD - Controller Area Network, Flexible ...

Value	Description
1	Interrupt is enabled for FIFO full
0	Interrupt is disabled for FIFO full

### Bit 1 - TEFHIE Transmit Event FIFO Half Full Interrupt Enable

Value	Description			
1	Interrupt is enabled for FIFO half full			
0	Interrupt is disabled for FIFO half full			

### Bit 0 - TEFNEIE Transmit Event FIFO Not Empty Interrupt Enable

Value	Description
1	Interrupt is enabled for FIFO not empty
0	Interrupt is disabled for FIFO not empty

#### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxTEFCONT: Accesses the top byte TEFCON[31:24]
  - CxTEFCONU: Accesses the upper byte TEFCON[23:16]
  - CxTEFCONH: Accesses the high byte TEFCON[15:8]
  - CxTEFCONL: Accesses the low byte TEFCON[7:0]
- 2. These bits can only be modified in Configuration mode (OPMOD[2:0] = 100.

### 38.13.18 CxTEFSTA

Name: CxTEFSTA Offset: 0x0144

### CAN Transmit Event FIFO Status Register

Bit	31	30	29	28	27	26	25	24
Access								
Reset								
Bit	23	22	21	20	19	18	17	16
Access								
Reset								
Bit	15	14	13	12	11	10	9	8
				· <del>-</del>				
Access								
Reset								
110301								
Bit	7	6	F	4	3	2	1	0
DIL	/	0	5	4			ı	
					TEFOVIF	TEFFIF	TEFHIF	TEFNEIF
Access					HS/C	R	R	R
Reset					0	0	0	0

### Bit 3 - TEFOVIF Transmit Event FIFO Overflow Interrupt Flag

Value	Description	
1	Overflow event has occurred	
0	No overflow event has occurred	

### Bit 2 – TEFFIF Transmit Event FIFO Full Interrupt Flag<sup>(2)</sup>

Value	Description
1	FIFO is full
0	FIFO is not full

### Bit 1 – TEFHIF Transmit Event FIFO Half Full Interrupt Flag<sup>(2)</sup>

Value	Description			
1	IFO is greater than or equal to half full			
0	FIFO is less than half full			

# Bit 0 – TEFNEIF Transmit Event FIFO Not Empty Interrupt Flag<sup>(2)</sup>

Value	Description
1	FIFO is not empty
0	FIFO is empty

### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxTEFSTAT: Accesses the top byte TEFSTA[31:24]
  - CxTEFSTAU: Accesses the upper byte TEFSTA[23:16]
  - CxTEFSTAH: Accesses the high byte TEFSTA[15:8]
  - CxTEFSTAL: Accesses the low byte TEFSTA[7:0]
- 2. These bits are read-only and reflect the status of the FIFO.

### 38.13.19 CxTEFUA

Name: CxTEFUA Offset: 0x0148

CAN Transmit Event FIFO User Address Register

Bit	31	30	29	28	27	26	25	24
				TEFUA	[31:24]			
Access	R	R	R	R	R	R	R	R
Reset	x	X	x	x	x	x	x	x
Bit	23	22	21	20	19	18	17	16
				TEFUA	[23:16]			
Access	R	R	R	R	R	R	R	R
Reset	x	X	X	X	X	X	X	X
Bit	15	14	13	12	11	10	9	8
				TEFU	A[15:8]			
Access	R	R	R	R	R	R	R	R
Reset	X	X	X	X	X	X	X	X
Bit	7	6	5	4	3	2	1	0
				TEFU	A[7:0]			
Access	R	R	R	R	R	R	R	R
Reset	x	x	x	x	x	x	x	x

# Bits 31:0 - TEFUA[31:0] Transmit Event FIFO User Address

A read of this register will return the address where the ntext event is to be read (FIFO tail).

### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxTEFUAT: Accesses the top byte TEFUA[31:24]
  - CxTEFUAU: Accesses the upper byte TEFUA[23:16]
  - CxTEFUAH: Accesses the high byte TEFUA[15:8]
  - CxTEFUAL: Accesses the low byte TEFUA[7:0]
- This register is not ensured to read correctly in Configuration mode and should only be accessed when the module is not in Configuration mode.

# 38.13.20 CxFIFOBA

Name: CxFIFOBA Offset: 0x014C

CAN Message Memory Base Address Register

Bit	31	30	29	28	27	26	25	24
				FIFOBA	\[31:24]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	23	22	21	20	19	18	17	16
				FIFOBA	A[23:16]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	15	14	13	12	11	10	9	8
				FIFOB	A[15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
				FIFOE	BA[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 31:0 – FIFOBA[31:0] Message Memory Base Address
Defines the base address for the transmit event FIFO followed by the message objects

### 38.13.21 CxTXQCON

Name: CxTXQCON Offset: 0x0150

### **CAN Transmit Queue Control Register**

Bit	31	30	29	28	27	26	25	24
		PLSIZE[2:0]				FSIZE[4:0]		
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	23	22	21	20	19	18	17	16
		TXA	Γ[1:0]			TXPRI[4:0]		
Access		R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset		1	1	0	0	0	0	0
Bit	15	14	13	12	11	10	9	8
						FRESET	TXREQ	UINC
Access						S/HC	R/W/HC	S/HC
Reset						1	0	0
Bit	7	6	5	4	3	2	1	0
	TXEN			TXATIE		TXQEIE		TXQNIE
Access	R			R/W		R/W		R/W
Reset	1			0		0		0

### Bits 31:29 - PLSIZE[2:0] Payload Size(2)

Value	Description
111	64 data bytes
110	48 data bytes
101	32 data bytes
100	24 data bytes
011	20 data bytes
010	16 data bytes
001	12 data bytes
000	8 data bytes

### Bits 28:24 - FSIZE[4:0] FIFO Size(2)

Value	Description
11111	FIFO is 32 messages deep
00010	FIFO is 3 messages deep
00001	FIFO is 2 messages deep
00000	FIFO is 1 messages deep

# Bits 22:21 - TXAT[1:0] Retransmission Attempts

This feature is enabled when RTXAT (CxCON[16]) is set

Value	Description
11	Unlimited number of retransmission attempts
10	Unlimited number of retransmission attempts
01	Three retransmission attempts
00	Disable retransmission attempts

# Bits 20:16 - TXPRI[4:0] Message Transmit Priority

Value	Description	
value	Description	
11111	Highest message priority	
T T T T T	riighest message phonty	

# CAN FD - Controller Area Network, Flexible ...

Value	Description
00000	Lowest message priority

### Bit 10 - FRESET FIFO Reset

Value	Description
1	FIFO will be reset when this bit is set, cleared by hardware when FIFO is reset; user should poll
	whether this bit is clear before taking any action
0	No effect

#### Bit 9 - TXREQ Message Send Request

Value	Description
1	Requests sending a message; the bit will automatically clear when all the messages queued in the
	TXQ are successfully sent
0	Clearing the bit to '0' while set ('1') will request a message abort.

### Bit 8 - UINC Increment Head/Tail

When this bit is set, the FIFO head will increment by a single message.

#### Bit 7 - TXEN TX Enable

Value	Description
1	The transmit message queue is always configured as a transmitter; this bit will always read as '1'

### Bit 4 - TXATIE Transmit Attempts Exhausted Interrupt Enable

	- · · - · · · · · · · · · · · · · · · ·
Value	Description
1	Enables interrupt
0	Disables interrupt

### Bit 2 - TXQEIE Transmit Queue Empty Interrupt Enable

Value	Description
1	Interrupt is enabled for TXQ empty
0	Interrupt is disabled for TXQ empty

### Bit 0 - TXQNIE Transmit QUeue Not Full Interrupt Enable

Value	Description
1	Interrupt is enabled for TXQ not full
0	Interrupt is disabled for TXQ not full

#### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxTXQCONT: Accesses the top byte TXQCON[31:24]
  - CxTXQCONU: Accesses the upper byte TXQCON[23:16]
  - CxTXQCONH: Accesses the high byte TXQCON[15:8]
  - CxTXQCONL: Accesses the low byte TXQCON[7:0]
- 2. These bits can only be modified in Configuration mode (OPMOD[2:0] = 100.

### 38.13.22 CxTXQSTA

Name: CxTXQSTA Offset: 0x0154

**CAN Transmit Queue Status Register** 

Bit	31	30	29	28	27	26	25	24
Access								_
Reset								
Bit	23	22	21	20	19	18	17	16
Access								
Reset								
Bit	15	14	13	12	11	10	9	8
						TXQCI[4:0]		
Access				R	R	R	R	R
Reset				0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
	TXABT	TXLARB	TXERR	TXATIF		TXQEIF		TXQNIF
Access	R	R	R	HS/C		R		R
Reset	0	0	0	0		1		1

### Bits 12:8 - TXQCI[4:0] Transmit Queue Message Index<sup>(2)</sup>

A read of this register will return an index to the message the FIFO will next attempt to transmit.

### Bit 7 - TXABT Message Aborted Status(3)

D.C. 17	ABI Woodage Aborton Clarac
Value	Description
1	Message was aborted
0	Message completed successfully

# Bit 6 – TXLARB Message Lost Arbitration Status<sup>(3)</sup>

Value	Description
1	Message lost arbitration while being sent
0	Message did not lose arbitration while being sent

### Bit 5 - TXERR Error Detected During Transmission(3)

Value	Description
1	A bus error occurred while the message was being sent
0	A bus error did not occur while the message was being sent

### Bit 4 - TXATIF Transmit Attempts Exhausted Interrupt Pending

Value	Description
1	Interrupt is pending
0	Interrupt is not pending

#### Bit 2 - TXQEIF Transmit Queue Empty Interrupt Flag

				_	
Value	Description				
1	TXQ is empty				
0	TXQ is not empty, at le	ast on	e messa	ge is	queued to be transmitted

### Bit 0 - TXQNIF Transmit Queue Not Full Interrupt Flag

# PIC18F26/46/56Q84

# CAN FD - Controller Area Network, Flexible ...

Value	Description
1	TXQ is not full
0	TXQ is full

#### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxTXQSTAT: Accesses the top byte TXQSTA[31:24]
  - CxTXQSTAU: Accesses the upper byte TXQSTA[23:16]
  - CxTXQSTAH: Accesses the high byte TXQSTA[15:8]
  - CxTXQSTAL: Accesses the low byte TXQSTA[7:0]
- 2. The TXQCI[4:0] bits give a zero-indexed value to the message in the TXQ. IF the TXQ is four messages deep (FSIZE = 3), TXQCIx will take on a value of 0 to 3, depending on the state of the TXQ
- 3. These bits are updated when a message completes (or aborts) or when the TXQ is reset.

### 38.13.23 CxTXQUA

Name: CxTXQUA Offset: 0x0158

CAN Transmit Queue User Address Register

Bit	31	30	29	28	27	26	25	24		
	TXQUA[31:24]									
Access	R	R	R	R	R	R	R	R		
Reset	x	X	X	X	X	X	X	X		
Bit	23	22	21	20	19	18	17	16		
				TXQUA	\[23:16]					
Access	R	R	R	R	R	R	R	R		
Reset	x	X	X	X	X	X	X	X		
Bit	15	14	13	12	11	10	9	8		
				TXQU	A[15:8]					
Access	R	R	R	R	R	R	R	R		
Reset	X	x	x	x	x	x	x	x		
Bit	7	6	5	4	3	2	1	0		
				TXQL	IA[7:0]					
Access	R	R	R	R	R	R	R	R		
Reset	x	X	x	x	x	x	X	x		

### Bits 31:0 - TXQUA[31:0] TXQ User Address

A read of this register will return the address where the next message is to be written (TXQ head)

### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxTXQUAT: Accesses the top byte TXQUA[31:24]
  - CxTXQUAU: Accesses the upper byte TXQUA[23:16]
  - CxTXQUAH: Accesses the high byte TXQUA[15:8]
  - CxTXQUAL: Accesses the low byte TXQUA[7:0]
- This register is not ensured to read correctly in Configuration mode and should only be accessed when the module is not in Configuration mode.

# **38.13.24 CxFIFOCONy**

Name: CxFIFOCONy

Offset: 0x00

CAN FIFO y Control Register

Bit	31	30	29	28	27	26	25	24
	PLSIZE[2:0]			FSIZE[4:0]				
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	23	22	21	20	19	18	17	16
		TXA	Γ[1:0]			TXPRI[4:0]		
Access		R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset		1	1	0	0	0	0	0
Bit	15	14	13	12	11	10	9	8
						FRESET	TXREQ	UINC
Access						S/HC	R/W/HC	S/HC
Reset						1	0	0
Bit	7	6	5	4	3	2	1	0
	TXEN	RTREN	RXTSEN	TXATIE	RXOVIE	TFERFFIE	TFHRFHIE	TFNRFNIE
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

### Bits 31:29 - PLSIZE[2:0] Payload Size(3)

Value	Description
111	64 data bytes
110	48 data bytes
101	32 data bytes
100	24 data bytes
011	20 data bytes
010	16 data bytes
001	12 data bytes
000	8 data bytes

# Bits 28:24 - FSIZE[4:0] FIFO Size(3)

### Bits 22:21 - TXAT[1:0] Retransmission Attempts

This feature is enabled when RTXAT (CxCON[16]) is set.

Value	Description	
11	Unlimited number of retransmission attempts	
10	Unlimited number of retransmission attempts	
01	Three retransmission attempts	
00	Disables retransmission attempts	

### Bits 20:16 - TXPRI[4:0] Message Transmit Priority

Value	Description
11111	Highest message priority
00000	Lowest message priority

# Bit 10 - FRESET FIFO Reset

Value	Description	
1	FIFO will be reset when bit is set, cleared by hardware whenever FIFO is reset, user should poll	
whether this bit is clear before taking any action		
0	No effect	

### Bit 9 - TXREQ Message Send Request

Value	Condition	Description
1	TXEN = 1(FIFO configured as a transmit FIFO)	Requests sending a message; the bit will automatically clear when all the messages queued in the FIFO are successfully sent
0	TXEN = 1(FIFO configured as a transmit FIFO)	Clearing the bit to '0' while set ('1') will request a message abort
Х	TXEN = 0(FIFO configured as a receive FIFO)	This bit has no effect

### Bit 8 - UINC Increment Head/Tail

Value	Condition	Description
1	TXEN = 1(FIFO configured as a	When this bit is set, the FIFO head will increment by a single
	transmit FIFO)	message
1	TXEN = 0(FIFO configured as a	When this bit is set, the FIFO tail will increment by a single
	receive FIFO)	message

### Bit 7 - TXEN TX/RX Buffer Selection

Value	Description
1	Transmits message object
0	Receives message object

### Bit 6 - RTREN Auto-Remove Transmit (RTR) Enable

Value	Description	
1	When a Remote Transmit is received, TXREQ will be set	
0	When a Remote Transmit is received, TXREQ will be unaffected	

### Bit 5 - RXTSEN Received Message Timestamp Enable(3)

Value	Description	
1	Captures timestamp in a received message object in RAM	
0	Does not capture time stamp	

# Bit 4 - TXATIE Transmit Attempts Exhausted Interrupt Enable

Value	Description
1	Enables interrupt
0	Disables interrupt

# Bit 3 - RXOVIE Overflow Interrupt Enable

Value Description		Description
1	1	Interrupt is enabled for overflow event
	0	Interrupt is disabled for overflow event

# Bit 2 - TFERFFIE Transmit/Receive FIFO Empty/Full Interrupt Enable

Value	Condition	Description
1	TXEN = 1(FIFO configured as a transmit FIFO)	Interrupt is enabled for FIFO empty
0	TXEN = 1(FIFO configured as a transmit FIFO)	Interrupt is disabled for FIFO empty
1	TXEN = 0(FIFO configured as a receive FIFO)	Interrupt is enabled for FIFO full
0	TXEN = 0(FIFO configured as a receive FIFO)	Interrupt is disabled for FIFO full

### Bit 1 – TFHRFHIE Transmit/Receive FIFO Half Empty/Half Full Interrupt Enable

# PIC18F26/46/56Q84

# CAN FD - Controller Area Network, Flexible ...

Value	Condition	Description
1	TXEN = 1(FIFO configured as a transmit FIFO)	Interrupt is enabled for FIFO half empty
0	TXEN = 1(FIFO configured as a transmit FIFO)	Interrupt is disabled for FIFO half empty
1	TXEN = 0(FIFO configured as a receive FIFO)	Interrupt is enabled for FIFO half full
0	TXEN = 0(FIFO configured as a receive FIFO)	Interrupt is disabled for FIFO half full

# Bit 0 - TFNRFNIE Transmit/Receive FIFO Not Full/Not Empty Interrupt Enable

Value	Condition	Description
1	TXEN = 1(FIFO configured as a transmit FIFO)	Interrupt is enabled for FIFO not full
0	TXEN = 1(FIFO configured as a transmit FIFO)	Interrupt is disabled for FIFO not full
1	TXEN = 0(FIFO configured as a receive FIFO)	Interrupt is enabled for FIFO not empty
0	TXEN = 0(FIFO configured as a receive FIFO)	Interrupt is disabled for FIFO not empty

### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxFIFOCONyT: Accesses the top byte FIFOCONy[31:24]
  - CxFIFOCONyU: Accesses the upper byte FIFOCONy[23:16]
  - CxFIFOCONyH: Accesses the high byte FIFOCONy[15:8]
  - CxFIFOCONyL: Accesses the low byte FIFOCONy[7:0]
- 2. [y] denotes FIFO number, from 1 to 3.
- 3. These bits can only be modified in Configuration mode (OPMOD[2:0] = 100.)

# **38.13.25 CxFIFOSTAy**

Name: CxFIFOSTAy

Offset: 0x00

CAN FIFO y Status Register

Bit	31	30	29	28	27	26	25	24
Access								
Reset								
Bit	23	22	21	20	19	18	17	16
Access								
Reset								
Bit	15	14	13	12	11	10	9	8
						FIFOCI[4:0]	FIFOCI[4:0]	
Access				[R	[R	[R	[R	[R
Reset				0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
	TXABT	TXLARB	TXERR	TXATIF	RXOVIF	TFERFFIF	TFHRFHIF	TFNRFNIF
Access	R	R	R	HS/C	HS/C	R	R	R
Reset	0	0	0	0	0	0	0	0

### Bits 12:8 - FIFOCI[4:0] FIFO Message Index(3)

	age maex
Condition	Description
TXEN = 1(FIFO configured as a	A read of this register will return an index to the message that the FIFO will
transmit buffer)	next attempt to transmit
TXEN = 0(FIFO configured as a	A read of this register will return an index to the message that the FIFO will
receive buffer)	use to save the next message

#### Bit 7 - TXABT Message Aborted Status<sup>(5)</sup>

DIC / 17	Moddago Abortod Otatao
Value	Description
1	Message was aborted
0	Message completed successfully

# Bit 6 - TXLARB Message Lost Arbitration Status<sup>(4)</sup>

Value	Description
1	Message lost arbitration while being sent
0	Message did not lose arbitration while being sent

# Bit 5 – TXERR Error Detected During Transmission<sup>(4)</sup>

Value	Description
1	A bus error occurred while the message was being sent
0	A bus error did not occur while the message was being sent

# Bit 4 - TXATIF Transmit Attempts Exhausted Interrupt Pending

Value	Condition	Description
1	TXEN = 1(FIFO configured as a transmit buffer)	Interrupt is pending
0	TXEN = 1(FIFO configured as a transmit buffer)	Interrupt is not pending
X	TXEN = 0(FIFO configured as a receive buffer)	Unused, reads as '0'

# Bit 3 - RXOVIF Receive FIFO Overflow Interrupt Flag

# CAN FD - Controller Area Network, Flexible ...

Value	Condition	Description
Х	TXEN = 1(FIFO configured as a transmit buffer)	Unused, reads as '0'
1	TXEN = 0(FIFO configured as a receive buffer)	Overflow event has occurred
0	TXEN = 0(FIFO configured as a receive buffer)	No overflow event occurred

### Bit 2 - TFERFFIF Transmit/Receive FIFO Empty/Full Interrupt Flag

Value	Condition	Description
1	TXEN = 1(FIFO configured as a transmit buffer)	FIFO is empty
0	TXEN = 1(FIFO configured as a transmit buffer)	FIFO is not empty, at least one message is queued to be transmitted
1	TXEN = 0(FIFO configured as a receive buffer)	FIFO is full
0	TXEN = 0(FIFO configured as a receive buffer)	FIFO is not full

### Bit 1 - TFHRFHIF Transmit/Receive FIFO Half Empty/Half Full Interrupt Flag

Value	Condition	Description
1	TXEN = 1(FIFO configured as a transmit buffer)	FIFO is less than or equal to half full
0	TXEN = 1(FIFO configured as a transmit buffer)	FIFO is greater than half full
1	TXEN = 0(FIFO configured as a receive buffer)	FIFO is greater than or equal to half full
0	TXEN = 0(FIFO configured as a receive buffer)	FIFO is less than half full

### Bit 0 - TFNRFNIF Transmit/Receive FIFO Not Full/Not Empty Interrupt Flag

Value	Condition	Description
1	TXEN = 1(FIFO configured as a transmit buffer)	FIFO is not full
0	TXEN = 1(FIFO configured as a transmit buffer)	FIFO is full
1	TXEN = 0(FIFO configured as a receive buffer)	FIFO is not empty, has at least one message
0	TXEN = 0(FIFO configured as a receive buffer)	FIFO is empty

#### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxFIFOSTAyT: Accesses the top byte FIFOSTAy[31:24]
  - CxFIFOSTAyU: Accesses the upper byte FIFOSTAy[23:16]
  - CxFIFOSTAyH: Accesses the high byte FIFOSTAy[15:8]
  - CxFIFOSTAyL: Accesses the low byte FIFOSTAy[7:0]
- 2. [y] denotes FIFO number, from 1 to 3.
- 3. FIFOCI[4:0] gives a zero-indexed value to the message in the FIFO. If the FIFO is four message deep (FSIZE = 3), FIFOCIx will take on a value of 0 to 3, depending on the state of the FIFO.
- 4. This bit is updated when a message completes (or aborts) or when the FIFO is reset.
- 5. This bit is reset on any read of this register or when the TXQ is reset.

# 38.13.26 CxFIFOUAy

Name: CxFIFOUAy Offset: 0x00

### CAN FIFO y User Address Register

Bit	31	30	29	28	27	26	25	24
				FIFOU	A[31:24]			
Access	R	R	R	R	R	R	R	R
Reset	X	X	x	X	X	x	x	X
Bit	23	22	21	20	19	18	17	16
				FIFOU	A[23:16]			
Access	R	R	R	R	R	R	R	R
Reset	X	X	X	X	X	X	X	X
Bit	15	14	13	12	11	10	9	8
				FIFOU	A[15:8]			
Access	R	R	R	R	R	R	R	R
Reset	X	X	X	X	X	X	X	X
Bit	7	6	5	4	3	2	1	0
				FIFOL	JA[7:0]			
Access	R	R	R	R	R	R	R	R
Reset	X	X	X	X	X	X	X	X

### Bits 31:0 - FIFOUA[31:0] FIFO User Address bits

Condition	Description
TXEN= 1(FIFO configured as	A read of this register will return the address where the next message is to be
transmit buffer	written (FIFO head)
TXEN= 0(FIFO configured as	A read of the register will return the address where the next message is to be
receive buffer	read (FIFO tail)

#### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxFIFOCONyT: Accesses the top byte FIFOCONy[31:24]
  - CxFIFOCONyU: Accesses the upper byte FIFOCONy[23:16]
  - CxFIFOCONyH: Accesses the high byte FIFOCONy[15:8]
  - CxFIFOCONyL: Accesses the low byte FIFOCONy[7:0]
- 2. [y] denotes FIFO number, from 1 to 3.
- 3. This register is not ensured to read correctly in Configuration mode and should only be accessed when the module is not in Configuration mode.

### 38.13.27 CxFLTCON0

Name: CxFLTCON0 Offset: 0x0180

CAN Filter Control Register 0

31	30	29	28	27	26	25	24
FLTEN3					F3BP[4:0]		
R/W			R/W	R/W	R/W	R/W	R/W
0			0	0	0	0	0
23	22	21	20	19	18	17	16
FLTEN2					F2BP[4:0]		
R/W			R/W	R/W	R/W	R/W	R/W
0			0	0	0	0	0
15	14	13	12	11	10	9	8
FLTEN1					F1BP[4:0]		
R/W			R/W	R/W	R/W	R/W	R/W
0			0	0	0	0	0
7	6	5	4	3	2	1	0
FLTEN0					F0BP[4:0]		
R/W			R/W	R/W	R/W	R/W	R/W
0			0	0	0	Ο	0
	FLTEN3 R/W 0 23 FLTEN2 R/W 0 15 FLTEN1 R/W 0 7 FLTEN0 R/W	FLTEN3  R/W 0  23  22  FLTEN2  R/W 0  15  14  FLTEN1  R/W 0  7  6  FLTEN0  R/W	FLTEN3  R/W 0  23 22 21  FLTEN2  R/W 0  15 14 13  FLTEN1  R/W 0  7 6 5  FLTEN0  R/W	FLTEN3         R/W         R/W           0         0         0           23         22         21         20           FLTEN2         R/W         0         0           15         14         13         12           FLTEN1         R/W         0         0           7         6         5         4           FLTEN0         R/W         R/W	FLTEN3         R/W         R/W         R/W           0         0         0         0           23         22         21         20         19           FLTEN2         R/W         R/W         R/W         R/W           0         0         0         0           15         14         13         12         11           FLTEN1         R/W         R/W         R/W           0         0         0         0           7         6         5         4         3           FLTEN0         R/W         R/W         R/W	FLTEN3         F3BP[4:0]           R/W         R/W         R/W         R/W           0         0         0         0           23         22         21         20         19         18           FLTEN2         F2BP[4:0]         R/W         R/W         R/W         R/W           0         0         0         0         0         0           15         14         13         12         11         10         F1BP[4:0]           R/W         R/W         R/W         R/W         R/W         0         0         0         0           7         6         5         4         3         2         ELTEN0         F0BP[4:0]         R/W         R/W	FLTEN3   R/W R/W R/W R/W R/W   R/W   O

# Bit 31 - FLTEN3 Enable Filter 3 to Accept Messages

1	/alue	Description
1	•	Filter is enabled
C	)	Filter is disabled

### Bits 28:24 - F3BP[4:0] Pointer to FIFO when Filter 3 Hits

Value	Description
11111-00	Reserved
100	
00011	Message matching filter is stored in FIFO 3
00010	Message matching filter is stored in FIFO 2
00001	Message matching filter is stored in FIFO 1
00000	Reserved, FIFO 0 is the TX Queue and cannot receive messages

### Bit 23 - FLTEN2 Enable Filter 2 to Accept Messages

Value	Description							
1	Filter is enabled							
0	Filter is disabled							

# Bits 20:16 - F2BP[4:0] Pointer to FIFO when Filter 2 Hits

Value	Description
11111-00	Reserved
100	
00011	Message matching filter is stored in FIFO 3
00010	Message matching filter is stored in FIFO 2
00001	Message matching filter is stored in FIFO 1
00000	Reserved, FIFO 0 is the TX Queue and cannot receive messages

### Bit 15 - FLTEN1 Enable Filter 1 to Accept Messages

Value	Description
1	Filter is enabled
0	Filter is disabled

### Bits 12:8 - F1BP[4:0] Pointer to FIFO when Filter 1 Hits

Value	Description
11111-00	Reserved
100	
00011	Message matching filter is stored in FIFO 3
00010	Message matching filter is stored in FIFO 2
00001	Message matching filter is stored in FIFO 1
00000	Reserved, FIFO 0 is the TX Queue and cannot receive messages

# Bit 7 - FLTEN0 Enable Filter 0 to Accept Messages

Value	Description
1	Filter is enabled
0	Filter is disabled

### Bits 4:0 - F0BP[4:0] Pointer to FIFO when Filter 0 Hits

Value	Description
11111-00	Reserved
100	
00011	Message matching filter is stored in FIFO 3
00010	Message matching filter is stored in FIFO 2
00001	Message matching filter is stored in FIFO 1
00000	Reserved, FIFO 0 is the TX Queue and cannot receive messages

### Note:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxFLTCON0T: Accesses the top byte FLTCON0[31:24]
  - CxFLTCON0U: Accesses the upper byte FLTCON0[23:16]
  - CxFLTCON0H: Accesses the high byte FLTCON0[15:8]
  - CxFLTCON0L: Accesses the low byte FLTCON0[7:0]

### 38.13.28 CxFLTCON1

Name: CxFLTCON1 Offset: 0x0184

CAN Filter Control Register 1

31	30	29	28	27	26	25	24
FLTEN7					F7BP[4:0]		
R/W			R/W	R/W	R/W	R/W	R/W
0			0	0	0	0	0
23	22	21	20	19	18	17	16
FLTEN6					F6BP[4:0]		
R/W			R/W	R/W	R/W	R/W	R/W
0			0	0	0	0	0
15	14	13	12	11	10	9	8
FLTEN5					F5BP[4:0]		
R/W			R/W	R/W	R/W	R/W	R/W
0			0	0	0	0	0
7	6	5	4	3	2	1	0
FLTEN4					F4BP[4:0]		
R/W			R/W	R/W	R/W	R/W	R/W
0			0	0	0	0	0
	FLTEN7 R/W 0 23 FLTEN6 R/W 0 15 FLTEN5 R/W 0 7 FLTEN4 R/W	FLTEN7  R/W 0  23 22  FLTEN6  R/W 0  15 14  FLTEN5  R/W 0  7 6  FLTEN4  R/W	FLTEN7  R/W 0  23 22 21  FLTEN6  R/W 0  15 14 13  FLTEN5  R/W 0  7 6 5  FLTEN4  R/W	FLTEN7         R/W         R/W           0         0         0           23         22         21         20           FLTEN6         R/W         0         0           15         14         13         12           FLTEN5         R/W         0         0           7         6         5         4           FLTEN4         R/W         R/W	FLTEN7         R/W         R/W         R/W           0         0         0         0           23         22         21         20         19           FLTEN6         R/W         R/W         R/W         R/W           0         0         0         0         0           15         14         13         12         11         11           FLTEN5         R/W         R/W         R/W         0         0         0           7         6         5         4         3         FLTEN4         R/W         R/W         R/W         R/W	FLTEN7         R/W         B         F6BP[4:0]         R/W         R/W	FLTEN7         F7BP[4:0]           R/W         R/W         R/W         R/W         R/W           0         0         0         0         0         0           23         22         21         20         19         18         17           FLTEN6         F6BP[4:0]           R/W         R/W         R/W         R/W         R/W         R/W           0         0         0         0         0         0         0         0           15         14         13         12         11         10         9         9         F5BP[4:0]         F5BP[4:0]         R/W         R/W         0

# Bit 31 - FLTEN7 Enable Filter 7 to Accept Messages

<b>V</b> alue	Description
1	Filter is enabled
)	Filter is disabled

### Bits 28:24 - F7BP[4:0] Pointer to FIFO when Filter 7 Hits

Value	Description
11111-00	Reserved
100	
00011	Message matching filter is stored in FIFO 3
00010	Message matching filter is stored in FIFO 2
00001	Message matching filter is stored in FIFO 1
00000	Reserved, FIFO 0 is the TX Queue and cannot receive messages

### Bit 23 - FLTEN6 Enable Filter 6 to Accept Messages

Value	Description	
1	Filter is enabled	
0	Filter is disabled	

# Bits 20:16 - F6BP[4:0] Pointer to FIFO when Filter 6 Hits

	· · · · · · · · · · · · · · · · · · ·
Value	Description
11111-00	Reserved
100	
00011	Message matching filter is stored in FIFO 3
00010	Message matching filter is stored in FIFO 2
00001	Message matching filter is stored in FIFO 1
00000	Reserved, FIFO 0 is the TX Queue and cannot receive messages

### Bit 15 - FLTEN5 Enable Filter 5 to Accept Messages

## CAN FD - Controller Area Network, Flexible ...

Value	Description
1	Filter is enabled
0	Filter is disabled

#### Bits 12:8 - F5BP[4:0] Pointer to FIFO when Filter 5 Hits

Value	Description
11111-00	Reserved
100	
00011	Message matching filter is stored in FIFO 3
00010	Message matching filter is stored in FIFO 2
00001	Message matching filter is stored in FIFO 1
00000	Reserved, FIFO 0 is the TX Queue and cannot receive messages

### Bit 7 - FLTEN4 Enable Filter 4 to Accept Messages

Value	Description
1	Filter is enabled
0	Filter is disabled

#### Bits 4:0 - F4BP[4:0] Pointer to FIFO when Filter 4 Hits

Value	Description
11111-00	Reserved
100	
00011	Message matching filter is stored in FIFO 3
00010	Message matching filter is stored in FIFO 2
00001	Message matching filter is stored in FIFO 1
00000	Reserved, FIFO 0 is the TX Queue and cannot receive messages

#### Note:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxFLTCON1T: Accesses the top byte FLTCON1[31:24]
  - CxFLTCON1U: Accesses the upper byte FLTCON1[23:16]
  - CxFLTCON1H: Accesses the high byte FLTCON1[15:8]
  - CxFLTCON1L: Accesses the low byte FLTCON1[7:0]

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 865

#### 38.13.29 CxFLTCON2

Name: CxFLTCON2 Offset: 0x0188

CAN Filter Control Register 2

Bit	31	30	29	28	27	26	25	24
	FLTEN11					F11BP[4:0]		
Access	R/W			R/W	R/W	R/W	R/W	R/W
Reset	0			0	0	0	0	0
Bit	23	22	21	20	19	18	17	16
	FLTEN10					F10BP[4:0]		
Access	R/W			R/W	R/W	R/W	R/W	R/W
Reset	0			0	0	0	0	0
Bit	15	14	13	12	11	10	9	8
	FLTEN9					F9BP[4:0]		
Access	R/W			R/W	R/W	R/W	R/W	R/W
Reset	0			0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
	FLTEN8					F8BP[4:0]		
Access	R/W			R/W	R/W	R/W	R/W	R/W
Reset	0			0	0	0	0	0

#### Bit 31 - FLTEN11 Enable Filter 11 to Accept Messages

1	/alue	Description
1	•	Filter is enabled
C	)	Filter is disabled

#### Bits 28:24 - F11BP[4:0] Pointer to FIFO when Filter 11 Hits

Value	Description
11111-00	Reserved
100	
00011	Message matching filter is stored in FIFO 3
00010	Message matching filter is stored in FIFO 2
00001	Message matching filter is stored in FIFO 1
00000	Reserved, FIFO 0 is the TX Queue and cannot receive messages

#### Bit 23 - FLTEN10 Enable Filter 10 to Accept Messages

	= 1 = 1 = 1 = 1 = 1 = 1 = 1 = 1 = 1 = 1		
Value	Description		
1	Filter is enabled		
0	Filter is disabled		

#### Bits 20:16 - F10BP[4:0] Pointer to FIFO when Filter 10 Hits

Value	Description
11111-00	Reserved
100	
00011	Message matching filter is stored in FIFO 3
00010	Message matching filter is stored in FIFO 2
00001	Message matching filter is stored in FIFO 1
00000	Reserved, FIFO 0 is the TX Queue and cannot receive messages

#### Bit 15 - FLTEN9 Enable Filter 9 to Accept Messages

Value	Description
1	Filter is enabled
0	Filter is disabled

#### Bits 12:8 - F9BP[4:0] Pointer to FIFO when Filter 9 Hits

	• •
Value	Description
11111-00	Reserved
100	
00011	Message matching filter is stored in FIFO 3
00010	Message matching filter is stored in FIFO 2
00001	Message matching filter is stored in FIFO 1
00000	Reserved, FIFO 0 is the TX Queue and cannot receive messages

### Bit 7 - FLTEN8 Enable Filter 8 to Accept Messages

Value	Description
1	Filter is enabled
0	Filter is disabled

#### Bits 4:0 - F8BP[4:0] Pointer to FIFO when Filter 8 Hits

Value	Description
11111-00	Reserved
100	
00011	Message matching filter is stored in FIFO 3
00010	Message matching filter is stored in FIFO 2
00001	Message matching filter is stored in FIFO 1
00000	Reserved, FIFO 0 is the TX Queue and cannot receive messages

#### Note:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxFLTCON2T: Accesses the top byte FLTCON2[31:24]
  - CxFLTCON2U: Accesses the upper byte FLTCON2[23:16]
  - CxFLTCON2H: Accesses the high byte FLTCON2[15:8]
  - CxFLTCON2L: Accesses the low byte FLTCON2[7:0]

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 867

#### 38.13.30 CxFLTOBJy

Name: CxFLTOBJy Offset: 0x00

CAN Filter y Object Register

Bit	31	30	29	28	27	26	25	24			
		EXIDE	SID11			EID[17:13]					
Access		R/W	R/W	R/W	R/W	R/W	R/W	R/W			
Reset		0	0	0	0	0	0	0			
Bit	23	22	21	20	19	18	17	16			
		EID[12:5]									
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W			
Reset	0	0	0	0	0	0	0	0			
Bit	15	14	13	12	11	10	9	8			
			EID[4:0]			SID[10:8]					
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W			
Reset	0	0	0	0	0	0	0	0			
Bit	7	6	5	4	3	2	1	0			
				SID	[7:0]						
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W			
Reset	0	0	0	0	0	0	0	0			

#### Bit 30 - EXIDE Extended Identifier Enable

Value	Condition	Description
1	MIDE = 1	Matches only messages with Extended Identifier addresses
0	MIDE = 1	Matches only messages with Standard Identifier addresses
Х	MIDE = 0	Reserved

#### Bit 29 - SID11 12th bit of Standard Identifier Filter

#### Bits 28:11 - EID[17:0] Extended Identifier Filter

In DeviceNet<sup>™</sup> mode, these are the filter its for the first two data bytes

#### Bits 10:0 - SID[10:0] Standard Identifier Filter

#### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxFLTOBJyT: Accesses the top byte FLTOBJy[31:24]
  - CxFLTOBJyU: Accesses the upper byte FLTOBJy[23:16]
  - CxFLTOBJyH: Accesses the high byte FLTOBJy[15:8]
  - CxFLTOBJyL: Accesses the low byte FLTOBJy[7:0]
- 2. [y] denotes Filter number, from 0 to 11.

## 38.13.31 CxMASKy

Name: CxMASKy Offset: 0x00

CAN Mask y Register

Bit	31	30	29	28	27	26	25	24	
		MIDE	MSID11			MEID[17:13]			
Access		R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset		0	0	0	0	0	0	0	
Bit	23	22	21	20	19	18	17	16	
				MEIC	[12:5]				
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	0	0	0	0	0	0	0	0	
Bit	15	14	13	12	11	10	9	8	
			MEID[4:0]			MSID[10:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	0	0	0	0	0	0	0	0	
Bit	7	6	5	4	3	2	1	0	
				MSII	D[7:0]				
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	0	0	0	0	0	0	0	0	

#### Bit 30 - MIDE Identifier Receive Mode

Value	Description
1	Matches only message types (standard or extended address) that correspond to the EXIDE bit of in the
	filter
0	Matches either standard or extended address message if filters match (i.e., if (Filter SID) = (Message
	SID) or if (Filter SID/EID) = (Message SID/EID))

Bit 29 - MSID11 12th bit of Standard Identifier Mask

#### Bits 28:11 - MEID[17:0] Extended Identifier Mask

In DeviceNet<sup>™</sup> mode, these are the mask bits for the first two data bytes

Bits 10:0 - MSID[10:0] Standard Identifier Mask

#### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - CxMASKyT: Accesses the top byte MASKy[31:24]
  - CxMASKyU: Accesses the upper byte MASKy[23:16]
  - CxMASKyH: Accesses the high byte MASKy[15:8]
  - CxMASKyL: Accesses the low byte MASKy[7:0]
- 2. Each Mask is associated with a filter,[y] denotes Filter number, from 0 to 11.

## 38.14 Register Summary - CAN FD

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0			
0x00													
	Reserved												
0xFF		7:0	CLKSEL	PXEDIS	ISOCRCEN			DNCNT[4:0]					
		15:8	ON	PAEDIS	SIDL	BRSDIS	BUSY		[1:0]	WAKFIL			
0x0100	C1CON	23:16	OIV	OPMOD[2:0]		TXQEN	STEF	SERRLOM	ESIGM	RTXAT			
		31:24			VS[3:0]	.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	ABAT	02.1.120	REQOP[2:0]				
		7:0			L1		SJW[6:0]						
0.0404	OANDTOEO	15:8		TSEG2[6:0]									
0x0104	C1NBTCFG	23:16				TSEG	61[7:0]						
		31:24		BRP[7:0]									
		7:0							/[3:0]				
0x0108	C1DBTCFG	15:8							62[3:0]				
0.0100	OIDDIOIG	23:16						TSEG1[4:0]					
		31:24				BRP							
		7:0					TDC	<b>√</b> [5:0]					
0x010C	C1TDC	15:8					TDCO[6:0]						
	CTIBO	23:16							TDCMC				
		31:24							EDGFLTEN	SID11EN			
		7:0					[7:0]						
0x0110	C1TBC	15:8		TBC[15:8]									
		23:16 31:24	TBC[23:16] TBC[31:24]										
		7:0				ТВСР							
		15:8				IBCFI	XE[7.0]		TBCPF	ΣΕΙΩ-Ω1			
0x0114	C1TSCON	23:16						TSRES	TSEOF	TBCEN			
		31:24						TOILLO	TOLOI	IDOLIN			
		7:0	ICODE[6:0]										
	C1VEC	15:8					100022[0:0]	FILHIT[4:0]					
0x0118		23:16	TXCODE[6:0]										
		31:24		RXCODE[6:0]									
		7:0				TEFIF	MODIF	TBCIF	RXIF	TXIF			
		15:8	IVMIF	WAKIF	CERRIF	SERRIF	RXOVIF	TXATIF					
0x011C	C1INT	23:16				TEFIE	MODIE	TBCIE	RXIE	TXIE			
		31:24	IVMIE	WAKIE	CERRIE	SERRIE	RXOVIE	TXATIE					
		7:0						RFIF[2:0]					
0x0120	C1RXIF	15:8											
0.00120	CHAIF	23:16											
		31:24											
		7:0						TFIF	[3:0]				
0x0124	C1TXIF	15:8											
	2	23:16											
		31:24											
		7:0						RFOVIF[2:0]					
0x0128	C1RXOVIF	15:8											
		23:16											
		31:24						TEAT	IE(2.01				
		7:0 15:8						IFAI	IF[3:0]				
0x012C	C1TXATIF	23:16											
		31:24											
		7:0						TYPE	[Q[3:0]				
		15:8						IARE	. <b></b> [0.0]				
0x0130	C1TXREQ	23:16											
		31:24											
		01.24											

conti	nued											
		Dit Doo	-									
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0		
		7:0				RERRO						
0x0134	C1TREC	15:8				TERRO	1					
		23:16			TXBO	TXBP	RXBP	TXWARN	RXWARN	EWARN		
		31:24										
		7:0				NRERR						
0x0138	C1BDIAG0	15:8				NTERR						
0,100	0.22	23:16					CNT[7:0]					
		31:24					CNT[7:0]					
		7:0				EFMSG						
0x013C	C1BDIAG1	15:8					NT[15:8]					
0.0100	CIDDIAGI	23:16	TXBOERR		NCRCERR	NSTUFERR	NFORMERR	NACKERR	NBIT1ERR	NBIT0ERR		
		31:24	DLCMM	ESI	DCRCERR	DSTUFERR	DFORMERR		DBIT1ERR	DBIT0ERR		
		7:0			TEFTSEN		TEFOVIE	TEFFIE	TEFHIE	TEFNEIE		
	0.47550011	15:8						FRESET		UINC		
0x0140	C1TEFCON	23:16										
		31:24						FSIZE[4:0]				
		7:0					TEFOVIF	TEFFIF	TEFHIF	TEFNEIF		
	<b>_</b> ,	15:8										
0x0144	C1TEFSTA	23:16										
		31:24										
		7:0				TEFU	A[7:0]					
		15:8										
0x0148	C1TEFUA	23:16		TEFUA[15:8] TEFUA[23:16]								
		31:24										
		7:0		TEFUA[31:24] FIFOBA[7:0]								
0x014C	C1FIFOBA	15:8				FIFOB						
		23:16					\[23:16]					
		31:24					A[31:24]					
	C1TXQCON	7:0	TXEN			TXATIE		TXQEIE		TXQNIE		
0x0150		15:8						FRESET	TXREQ	UINC		
		23:16			T[1:0]			TXPRI[4:0]				
		31:24		PLSIZE[2:0]				FSIZE[4:0]				
		7:0	TXABT	TXLARB	TXERR	TXATIF		TXQEIF		TXQNIF		
0x0154	C1TXQSTA	15:8						TXQCI[4:0]				
0,0104	CTIAQSIA	23:16										
		31:24										
		7:0				TXQL	IA[7:0]					
0x0158	C1TXQUA	15:8				TXQU	A[15:8]					
001000	CTIXQUA	23:16				TXQUA	A[23:16]					
		31:24				TXQUA	[31:24]					
		7:0	TXEN	RTREN	RXTSEN	TXATIE	RXOVIE	TFERFFIE	TFHRFHIE	TFNRFNIE		
0.0450	OAFIFC COLL:	15:8						FRESET	TXREQ	UINC		
0x015C	C1FIFOCON1	23:16		TXA	T[1:0]			TXPRI[4:0]		1		
		31:24		PLSIZE[2:0]				FSIZE[4:0]				
		7:0	TXABT	TXLARB	TXERR	TXATIF	RXOVIF	TFERFFIF	TFHRFHIF	TFNRFNIF		
		15:8						FIFOCI[4:0]				
0x0160	C1FIFOSTA1	23:16						1 11 001[1:0]				
		31:24										
		7:0				EIEOI	JA[7:0]					
		15:8				FIFOU						
0x0164	C1FIFOUA1											
		23:16					A[23:16]					
		31:24	TV=11	DTDE	DVT051	FIFOU		TEEBESIE	TELIBELIE	TEMPE		
		7:0	TXEN	RTREN	RXTSEN	TXATIE	RXOVIE	TFERFFIE	TFHRFHIE	TFNRFNIE		
0x0168	C1FIFOCON2	15:8						FRESET	TXREQ	UINC		
	<del>-</del>	23:16			T[1:0]			TXPRI[4:0]				
		31:24		PLSIZE[2:0]				FSIZE[4:0]				

conti	inued										
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0	
		7:0	TXABT	TXLARB	TXERR	TXATIF	RXOVIF	TFERFFIF	TFHRFHIF	TFNRFNIF	
0x016C	C1FIFOSTA2	15:8					:	FIFOCI[4:0]		:	
000100	CITII OSTAZ	23:16									
		31:24									
		7:0					JA[7:0]				
0x0170	C1FIFOUA2	15:8				FIFOU	IA[15:8]				
0.0170	OTH TOOK	23:16				FIFOU	A[23:16]				
		31:24				FIFOU	A[31:24]				
		7:0	TXEN	RTREN	RXTSEN	TXATIE	RXOVIE	TFERFFIE	TFHRFHIE	TFNRFNIE	
0x0174	C1FIFOCON3	15:8						FRESET	TXREQ	UINC	
0.0174	01111 000143	23:16		TXAT	Γ[1:0]			TXPRI[4:0]			
		31:24		PLSIZE[2:0]				FSIZE[4:0]			
		7:0	TXABT	TXLARB	TXERR	TXATIF	RXOVIF	TFERFFIF	TFHRFHIF	TFNRFNIF	
0x0178	C1FIFOSTA3	15:8						FIFOCI[4:0]			
0.0170	CITII OSTAS	23:16									
		31:24									
		7:0					JA[7:0]				
0x017C	C1FIFOUA3	15:8				FIFOU	IA[15:8]				
000176	CIFIFOUAS	23:16				FIFOU	A[23:16]				
		31:24				FIFOU	A[31:24]				
		7:0	FLTEN0					F0BP[4:0]			
0x0180	C1FLTCON0	15:8	FLTEN1					F1BP[4:0]			
		23:16	FLTEN2			F2BP[4:0]					
		31:24	FLTEN3					F3BP[4:0]			
		7:0	FLTEN4					F4BP[4:0]			
0,0104	O4FLTOON4	15:8	FLTEN5					F5BP[4:0]			
0x0184	C1FLTCON1	23:16	FLTEN6					F6BP[4:0]			
		31:24	FLTEN7					F7BP[4:0]			
	C4FLTCONO	7:0	FLTEN8					F8BP[4:0]			
0x0188		15:8	FLTEN9			F9BP[4:0]					
UXU 100	C1FLTCON2	23:16	FLTEN10					F10BP[4:0]			
		31:24	FLTEN11					F11BP[4:0]			
		7:0				SID	[7:0]				
0x018C	C1FLTOBJ0	15:8			EID[4:0]				SID[10:8]		
UXUTOC	CIFLIOBJU	23:16				EID[	[12:5]	-			
		31:24		EXIDE	SID11			EID[17:13]			
		7:0				MSI	D[7:0]				
0x0190	C1MASK0	15:8			MEID[4:0]				MSID[10:8]		
0.0190	CTWASKO	23:16				MEIC	[12:5]				
		31:24		MIDE	MSID11			MEID[17:13]			
		7:0				SID	[7:0]				
0x0194	C1FLTOBJ1	15:8			EID[4:0]				SID[10:8]		
0.0134	O II E I O D O I	23:16				EID[	[12:5]				
		31:24		EXIDE	SID11			EID[17:13]			
		7:0				MSI	D[7:0]				
0x0198	C1MASK1	15:8			MEID[4:0]				MSID[10:8]		
0.0190	CHMASKI	23:16				MEIC	[12:5]				
		31:24		MIDE	MSID11			MEID[17:13]			
		7:0				SID	[7:0]				
0x019C	C1FLTOBJ2	15:8			EID[4:0]				SID[10:8]		
070190	OH LIODUZ	23:16				EID[	[12:5]				
		31:24		EXIDE	SID11			EID[17:13]			
		7:0				MSI	D[7:0]				
0x01A0	C1MASK2	15:8			MEID[4:0]				MSID[10:8]		
0.01.00	OTWINGNZ	23:16				MEID	[12:5]				
		31:24		MIDE	MSID11			MEID[17:13]			

Offset         Name         Bit Pos.         7         6         5         4         3         2           0x01A4         C1FLTOBJ3         7:0         SID[7:0]         SID[7:0]           15:8         EID[4:0]         EID[12:5]         EID[12:5]           31:24         EXIDE         SID11         EID[17:13]	1 0
0x01A4 C1FLTOBJ3 7:0 SID[7:0] 15:8 EID[4:0] 23:16 EID[12:5] 31:24 EXIDE SID11 EID[17:13]	
0x01A4         C1FLTOBJ3         15:8         EID[4:0]           23:16         EID[12:5]           31:24         EXIDE         SID11         EID[17:13]	
0x01A4 C1FLTOBJ3 23:16 EID[12:5] 31:24 EXIDE SID11 EID[17:13]	SID[10:8]
31:24 EXIDE SID11 EID[17:13]	SID[10.0]
7:0 MSID[7:0]	
15:8 MEIDI4:01	MSID[10:8]
0x01A8 C1MASK3 23:16 MEID[12:5]	WeiB[10.0]
31:24 MIDE MSID11 MEID[17:13]	
7:0 SID[7:0]	
15:8 FID[4:0]	SID[10:8]
0x01AC C1FLTOBJ4 23:16 EID[12:5]	[]
31:24 EXIDE SID11 EID[17:13]	
7:0 MSID[7:0]	
15·8 MFIDI4·01	MSID[10:8]
0x01B0 C1MASK4 23:16 MEID[12:5]	
31:24 MIDE MSID11 MEID[17:13]	
7:0 SID[7:0]	
15:8 FID[4:0]	SID[10:8]
0x01B4 C1FLTOBJ5 23:16 EID[12:5]	
31:24 EXIDE SID11 EID[17:13]	
7:0 MSID[7:0]	
15.8 MFIDI4:01	MSID[10:8]
0x01B8 C1MASK5 23:16 MEID[12:5]	
31:24 MIDE MSID11 MEID[17:13]	
7:0 SID[7:0]	
15:8 FIDI4:01	SID[10:8]
0x01BC	
31:24 EXIDE SID11 EID[17:13]	
7:0 MSID[7:0]	
0x01C0 C1MASK6 15:8 MEID[4:0]	MSID[10:8]
0x01C0 C1MASK6 23:16 MEID[12:5]	
31:24 MIDE MSID11 MEID[17:13]	
7:0 SID[7:0]	
0x01C4 C1FLTOBJ7 15:8 EID[4:0]	SID[10:8]
23:16 EID[12:5]	
31:24 EXIDE SID11 EID[17:13]	
7:0 MSID[7:0]	
0x01C8	MSID[10:8]
23:16 MEID[12:5]	
31:24 MIDE MSID11 MEID[17:13]	
7:0 SID[7:0]	
0x01CC	SID[10:8]
23:16 EID[12:5]	
31:24 EXIDE SID11 EID[17:13]	
7:0 MSID[7:0]	
0x01D0	MSID[10:8]
23:16 MEID[12:5]	
31:24 MIDE MSID11 MEID[17:13]	
7:0 SID[7:0]	
0x01D4	SID[10:8]
23:16 EID[12:5]	
31:24 EXIDE SID11 EID[17:13]	
7:0 MSID[7:0]	14010140.03
0x01D8	MSID[10:8]
23:16 MEID[12:5]	
31:24 MIDE MSID11 MEID[17:13]	

continued											
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0	
		7:0		SID[7:0]							
0x01DC	C1FLTOBJ10	15:8			EID[4:0]				SID[10:8]		
	CIFLIOBJIO	23:16		EID[12:5]							
		31:24		EXIDE	SID11			EID[17:13]			
0x01E0	C1MASK10	7:0		-		MSI	D[7:0]				
		15:8			MEID[4:0]		MSID[10:8]				
OXUTEU		23:16	MEID[12:5]								
		31:24		MIDE MSID11							
		7:0	SID[7:0]								
0x01E4	C1FLTOBJ11	15:8		EID[4:0]					SID[10:8]		
0X01E4	CIFLIOBJII	23:16		EID[12:5]							
		31:24		EXIDE SID11				EID[17:13]			
		7:0				MSI	D[7:0]				
0x01E8	C1MASK11	15:8		MEID[4:0]				MSID[10:8]			
UNUTED	CHMASKII	23:16				MEID	[12:5]	-			
		31:24		MIDE	MSID11			MEID[17:13]			

## 39. JTAG Boundary Scan


As the complexity and density of board design increases, testing electrical connections between the components on fully assembled circuit boards poses many challenges. To address these challenges, the Joint Test Action Group (JTAG) developed a method for boundary scan testing that was later standardized as IEEE 1149.1-2001, "IEEE Standard Test Access Port and Boundary Scan Architecture".

The JTAG boundary scan method is the process of adding a Shift register stage adjacent to each of the component's I/O pins. This permits signals at the component boundaries to be controlled and observed, using a defined set of scan test principles. An external tester or controller provides instructions and reads the results in a serial format. The external device also provides common clock and control signals. Depending on the implementation, access to all test signals is provided through a standardized 4-pin or 5-pin interface.

In system-level applications, individual JTAG enabled components are connected through their individual testing interfaces (in addition to their more standard application-specific connections). Devices are connected in a series or daisy-chained format, with the test output of one device connected exclusively to the test input of the next device in the chain. Instructions in the JTAG boundary scan protocol allow the testing of any one device in the chain, or any combination of devices, without testing the entire chain. In this method, connections between components, as well as connections at the boundary of the application, may be tested.

A typical application incorporating the JTAG boundary scan interface is shown in Figure 39-1. In this example, a PIC microcontroller is daisy-chained to a second JTAG compliant device. Note that the TDI line from the external tester supplies data to the TDI pin of the first device in the chain (in this case, the microcontroller). The resulting test data for this two-device chain is provided from the TDO pin of the second device to the TDO line of the tester. This section describes the JTAG module and its general boundary scan use. The PIC18-Q84 JTAG module does not currently support programming over JTAG.


Figure 39-1. Overview of PIC18F-Based JTAG Compliant Application Showing Daisy-Chaining of Components



In PIC18-Q84 devices, hardware for the JTAG boundary scan is a Core Independent Peripheral (CIP) with additional integrated logic in all I/O ports. A logical block diagram of the JTAG module is shown in Figure 39-2. It consists of the following key elements:

- TAP Interface Pins (TDI, TMS, TCK and TDO)
- TAP Controller
- Instruction Shift register and Instruction Register (IR)
- Data Registers

Figure 39-2. JTAG Logical Block Diagram



## 39.1 Test Access Port (TAP) and TAP Controller

#### 39.1.1 TAP

The Test Access Port (TAP) on the PIC18-Q84 is a general-purpose port that provides test access to many built-in support functions and test logic defined in IEEE Standard 1149.1. The TAP is disabled by programming the JTAGEN bit in CONFIGx (the TAP, by default, is enabled in the bit's unprogrammed state). While enabled, the designated I/O pins become dedicated TAP pins. The PIC implements a 4-pin JTAG interface with these pins:


- · TCK (Test Clock): Provides the clock for test logic.
- TMS (Test Mode Select): Input used by the TAP to control test operations.
- · TDI (Test Data Input): Serial input for test instructions and data.
- TDO (Test Data Output): Serial output for test instructions and data.

To minimize I/O loss due to JTAG, the optional TAP Reset (TRST) input pin, specified in the standard, is not implemented on PIC18-Q84 devices. For convenience, a "soft" TAP Reset has been included in the TAP controller, using the TMS and TCK pins. To force a port Reset, apply a logic high to the TMS pin for at least five rising edges of TCK. Note that device Resets (including POR) do not automatically result in a TAP Reset; this must be done by the external JTAG controller using the soft TAP Reset.

#### 39.1.2 TAP Controller

The TAP controller on PIC18-Q84 family devices is a synchronous finite state machine that implements the standard 16 states for JTAG. Figure 39-3 shows all the module states of the TAP controller. All Boundary Scan Test (BST) instructions and test results are communicated through the TAP via the TDI pin in a serial format, Least Significant bit first.

Figure 39-3. TAP Controller Module State Diagram



By manipulating the state of TMS and the clock pulses on TCK, the TAP controller can be moved through all of the defined module states to capture, shift and update various instruction and/or data registers. Figure 39-3 shows the state changes on TMS as the controller cycles through its state machine. Figure 39-4 shows the timing of TMS and TCK while transitioning the controller through the appropriate module states for shifting in an instruction. In this example, the sequence shown demonstrates how an instruction is read by the TAP controller. All TAP controller states are entered on the rising edge of the TCK pin. In this example, the TAP controller starts in the Test-Logic Reset state. Since the state of the TAP controller is dependent on the previous instruction, and therefore could be unknown, it is good programming practice to begin in the Test-Logic Reset state.




Figure 39-4. TAP State Transitions for Shifting in an Instruction

Note

- 1: TDO pin is always in a high-impedance state, until the first falling edge of TCK, in either the Shift\_IR or Shift\_DR states.
- 2: TDO is no longer high-impedance; the initial state of the Instruction Register (IR) is shifted out on the falling edge of TCK
- 3: TDO returns to high-impedance again on the first falling edge of TCK in the Exit IR state.

When TMS is asserted low on the next rising edge of TCK, the TAP controller will move into the Run-Test/Idle state. On the next two rising edges of TCK, TMS is high; this moves the TAP controller to the Select-IR-Scan state.

On the next two rising edges of TCK, TMS is held low; this moves the TAP controller into the Shift-IR state. An instruction is shifted into the Instruction Shift register via the TDI on the next four rising edges of TCK. After the TAP controller enters this state, the TDO pin goes from a High-impedance state to Active. The controller shifts out the initial state of the Instruction Register (IR) on the TDO pin, on the falling edges of TCK, and continues to shift out the contents of the Instruction Register while in the Shift-IR state. The TDO returns to the High-impedance state on the first falling edge of TCK upon exiting the Shift state.

On the next three rising edges of TCK, the TAP controller exits the Shift-IR state, updates the Instruction Register and then moves back to the Run-Test/Idle state. Data, or another instruction, can now be shifted into the appropriate Data or Instruction Register.

## 39.2 JTAG Registers

The JTAG module uses a number of registers of various sizes as part of its operation. In terms of bit count, most of the JTAG registers are single-bit register cells, integrated into the I/O ports. Regardless of their location within the module, none of the JTAG registers are located within the device data memory space, and cannot be directly accessed by the user in normal operating modes.

#### 39.2.1 Instruction Shift Register and Instruction Register

The Instruction Shift register is a 4-bit shift register used for selecting the actions to be performed and/or what data registers to be accessed. Instructions are shifted in, Least Significant bit first, and then decoded. A list and description of implemented instructions is given in JTAG Instructions.

#### 39.2.2 Data Registers


Once an instruction is shifted in and updated into the Instruction register, the TAP controller places certain data registers between the TDI and TDO pins. Additional data values can then be shifted into these data registers as needed. The PIC18-Q84 device family supports two data registers:

- Bypass register: A single-bit register which allows the boundary scan test data to pass through the selected device to adjacent devices. The Bypass register is placed between the TDI and TDO pins when the BYPASS instruction is active.
- Device ID Register: A 32-bit part identifier. It consists of an 11-bit manufacturer ID assigned by the IEEE (29h for Microchip Technology), device part number and device revision identifier. When the IDCODE instruction is active, the Device ID register is placed between the TDI and TDO pins. The device data ID is then shifted out onto the TDO pin, on the next 32 falling edges of TCK, after the TAP controller is in the Shift-DR.

## 39.3 Boundary Scan Register (BSR)

The BSR is a large shift register that is comprised of all the I/O Boundary Scan Cells (BSCs), daisy-chained together Figure 39-5. Each I/O pin has one BSC, each containing three BSC registers: an input cell, an output cell and a control cell. When the SAMPLE/PRELOAD or EXTEST instructions are active, the BSR is placed between the TDI and TDO pins, with the TDI pin as the input and the TDO pin as the output. The size of the BSR depends on the number of I/O pins on the device. For example, the PIC18F57Q84 has 44 I/O pins. With three BSC registers for each of the 44 I/Os. this yields a Boundary Scan register length of 132 bits.

Figure 39-5. Daisy-Chained Boundary Scan Cell Registers on a PIC18F Microcontroller



#### 39.3.1 Boundary Scan Cell (BSC)

The function of the BSC is to capture and override I/O input or output data values when JTAG is active. The BSC consists of three Single-Bit Capture register cells and two Single-Bit Holding register cells. The capture cells are daisy-chained to capture the port's input, output and control (output-enable) data, as well as pass JTAG data along the Boundary Scan register. Command signals from the TAP controller determine if the port of JTAG data is captured, and how and when it is clocked out of the BSC. The first register either captures internal data destined to the output driver or provides serially scanned in data for the output driver. The second register captures internal output-enable control from the output driver and also provides serially scanned in output-enable values. The third register captures the input data from the I/O's input buffer.

Figure 39-5 shows a typical BSC and its relationship to the I/O port's structure.

**Boundary Scan Cell** Port I/O Cell JTAG Enable JTAG Clocks Capture Update Port Output **Output Buffer** I/O Pin JTAG SDI from Port Previous BSC **Output Data** Port Output Enable from Output Multiplexor Data Out <sup>I</sup>Enable JTAG SDO to Next BSC Input Buffer Port Input◀

Figure 39-6. Boundary Scan Cell and Its Relationship to the I/O Port

#### 39.4 JTAG Instructions

PIC18-Q84 family devices support the mandatory instruction set specified by IEEE 1149.1, as well as several optional public instructions defined in the specification.

The mandatory JTAG instructions are:

- BYPASS (Fh): Used for bypassing a device in a test chain; this allows the testing of off-chip circuitry and board-level interconnections.
- SAMPLE/PRELOAD (2h): Captures the I/O states of the component, providing a snapshot of its operation.
- EXTEST (6h): Allows the external circuitry and interconnections to be tested, by either forcing various test patterns on the output pins, or capturing test results from the input pins.

The optional JTAG instructions implemented in PIC18-Q84 devices are:

- IDCODE (1h): Causes the 32-bit device identification word to be shifted out on the TDO pin.
- HIGHZ (0h): Places the device into a state in which all I/O pins are in a High-impedance state (driven inactive).

### 39.5 Boundary Scan Testing

Boundary Scan Testing (BST) is the method of controlling and observing the boundary pins of the JTAG compliant device, like those of the PIC18-Q84 family, utilizing software control. BST can be used to test connectivity between devices by daisy-chaining JTAG compliant devices to form a single scan chain. Several scan chains can exist on a PCB to form multiple scan chains. These multiple scan chains can then be driven simultaneously to test many components in parallel. Scan chains can contain both JTAG compliant devices and non-JTAG compliant devices.

A key advantage of BST is that it can be implemented without physical test probes; all that is needed is a 4-wire or 5-wire interface and an appropriate test platform. Since JTAG boundary scan has been available for many years, many software tools exist for testing scan chains without the need for extensive physical probing. The main drawback to BST is that it can only evaluate digital signals and circuit continuity; it cannot measure input or output voltage levels or currents.

#### 39.5.1 Related JTAG Files

To implement BST, all JTAG test tools will require a Boundary Scan Description Language (BSDL) file. BSDL is a subset of VHDL (VHSIC Hardware Description Language), and is described as part of IEEE Std. 1149.1. The device-specific BSDL file describes how the standard is implemented on a particular device and how it operates.

The BSDL file for a particular device includes the following:

- · The pinout and package configuration for the particular device
- · The physical location of the TAP pins
- · The Device ID register and the device ID
- · The length of the Instruction Register
- · The supported BST instructions and their binary codes
- · The length and structure of the Boundary Scan register
- The boundary scan cell definition

Device-specific BSDL files are available at Microchip's web site, www.microchip.com. The name for each BSDL file is the device name and silicon revision. For example, PIC18F57Q83\_QFN.BSD, is the BSDL file for the PIC18F57Q83 in the QFN package.

#### 39.6 Effects of Reset

The JTAG Boundary Scan module is affected by all device reset sources. If a reset source is triggered during a boundary scan operation, the TAP controller state machine may reset and, therefore, the boundary scan operation may exhibit unexpected and undesirable results. Hence, all potential device resets should be avoided while performing a boundary scan operation.


© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 881

## 40. HLVD - High/Low-Voltage Detect

The HLVD module can be configured to monitor the device voltage. This is useful in battery monitoring applications. Complete control of the HLVD module is provided through the HLVDCON0 and HLVDCON1 registers.

Refer below for a simplified block diagram of the HLVD module.

Figure 40-1. HLVD Module Block Diagram



Since the HLVD can be software enabled through the EN bit, setting and clearing the enable bit does not produce a false HLVD event glitch. Each time the HLVD module is enabled, the RDY bit can be used to detect when the module is stable and ready to use.

The INTH and INTL bits determine the overall operation of the module. When INTH is set, the module monitors for rises in  $V_{DD}$  above the trip point set by the bits. When INTL is set, the module monitors for drops in  $V_{DD}$  below the trip point set by the SEL bits. When both the INTH and INTL bits are set, any changes above or below the trip point set by the SEL bits can be monitored.

The OUT bit can be read to determine if the voltage is greater than or less than the selected trip point.

## 40.1 Operation

When the HLVD module is enabled, a comparator uses an internally generated voltage reference as the set point. The set point is compared with the trip point, where each node in the resistor divider represents a trip point voltage. The "trip point" voltage is the voltage level at which the device detects a high or low-voltage event, depending on the configuration of the module.

When the supply voltage is equal to the trip point, the voltage tapped off of the resistor array is equal to the internal reference voltage generated by the voltage reference module. The comparator then generates an interrupt signal by setting the HLVDIF bit.

The trip point voltage is software programmable using the SEL bits.

### 40.2 Setup

To set up the HLVD module:

- 1. Select the desired HLVD trip point by writing the value to the SEL bits.
- Depending on the application to detect high-voltage peaks or low-voltage drops or both, set the INTH or INTL bit appropriately.
- 3. Enable the HLVD module by setting the EN bit.
- 4. Clear the HLVD interrupt flag (HLVDIF), which may have been set from a previous interrupt.
- 5. If interrupts are desired, enable the HLVD interrupt by setting the HLVDIE and GIE bits. An interrupt will not be generated until the RDY bit is set.



**Important:** Before changing any module settings (interrupts and tripping point), first disable the module (EN = 0), make the changes and re-enable the module. This prevents the generation of false HLVD events.

## 40.3 Current Consumption

When the module is enabled, the HLVD comparator and voltage divider are enabled and consume static current. The total current consumption, when enabled, is specified in the "Electrical Specification" chapter.

Depending on the application, the HLVD module does not need to operate constantly. To reduce the current consumption, the module can disabled when not in use. Refer to the "PMD - Peripheral Module Disable" chapter for more details.

#### 40.4 HLVD Start-up Time

If the HLVD or other circuits using the internal voltage reference are disabled to lower the device's current consumption, the reference voltage circuit will require time to become stable before a low or high-voltage condition can be reliably detected. This start-up time, T<sub>FVRST</sub>, is an interval that is independent of device clock speed. It is specified in electrical specification section of the device specific data sheet.

The HLVD interrupt flag is not enabled until  $T_{FVRST}$  has expired and a stable reference voltage is reached. For this reason, brief excursions beyond the set point may not be detected during this interval (see the figures below).

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 883

**HLVDIF** Cleared in Software

HLVDIF Remains Set since HLVD Condition still Exists

HLVDIF Cleared in Software,

CASE 1:

HLVDIF may not be Set

VDD

HLVDIF

EN

RDY

TFVRST

Band Gap Reference Voltage is Stable

HLVDIF


EN


RDY

HLVDIF

Band Gap Reference Voltage is Stable

Figure 40-3. High-Voltage Detect Operation (INTH = 1)






#### 40.5 **Applications**

In many applications, it is desirable to detect a drop below, or rise above, a particular voltage threshold. For example, the HLVD module could be periodically enabled to detect Universal Serial Bus (USB) attach or detach. This assumes the device is powered by a lower voltage source than the USB when detached. An attach would indicate a High-Voltage Detect from, for example, 3.3V to 5V (the voltage on USB) and vice versa for a detach. This feature could save a design a few extra components and an attach signal (input pin).

For general battery applications, the figure below shows a possible voltage curve. Over time, the device voltage decreases. When the device voltage reaches voltage, VA, the HLVD logic generates an interrupt at time, TA. The interrupt could cause the execution of an Interrupt Service Routine (ISR), which would allow the application to perform "housekeeping tasks" and a controlled shutdown before the device voltage exits the valid operating range at T<sub>B</sub>. This would give the application a time window, represented by the difference between T<sub>A</sub> and T<sub>B</sub>, to safely exit.

Figure 40-4. Typical Low-Voltage Detect Application



**Legend:** VA = HLVD trip point

VB = Minimum valid device operating

## 40.6 Operation During Sleep

When enabled, the HLVD circuitry continues to operate during Sleep. When the device voltage crosses the trip point, the HLVDIF bit will be set and the device will wake-up from Sleep. If interrupts are enabled, the device will execute code from the interrupt vector. If interrupts are disabled, the device will continue execution from the next instruction after SLEEP.

## 40.7 Operation During Idle and Doze Modes

The performance of the module is independent of the Idle and Doze modes. The module will generate the events based on the trip points. The response to these events will depend on the Doze and Idle mode settings.

#### 40.8 Effects of a Reset

A device Reset forces all registers to their Reset state. This forces the HLVD module to be turned off. User firmware has to configure the module again.

### 40.9 Register Definitions: HLVD Control

Long bit name prefixes for the HLVD peripheral is shown in the following table. Refer to the "Long Bit Names" section in the "Register and Bits Naming Conventions" chapter for more information.

Table 40-1. HLVD Long Bit Name Prefixes

Peripheral	Bit Name Prefix
HLVD	HLVD

#### 40.9.1 HLVDCON0

Name: HLVDCON0 Offset: 0x04A

High/Low-Voltage Detect Control Register 0

Bit	7	6	5	4	3	2	1	0
	EN		OUT	RDY			INTH	INTL
Access	R/W		R	R			R/W	R/W
Reset	0		X	X			0	0

#### Bit 7 - EN High/Low-voltage Detect Power Enable

Value	Description
1	Enables the HLVD module
0	Disables the HLVD module

#### Bit 5 – OUT HLVD Comparator Output

Value	Description		
1	Voltage < selected detection limit (SEL)		
0	Voltage > selected detection limit (SEL)		

#### Bit 4 - RDY Band Gap Reference Voltages Stable Status Flag

Value	Description			
1	Indicates HLVD M	odule is ready and	output is stable	
0	Indicates HLVD M	odule is not ready		

#### Bit 1 - INTH HLVD Positive going (High Voltage) Interrupt Enable

I	Value	Description
	1	HLVDIF will be set when voltage ≥ selected detection limit (SEL)
	0	HLVDIF will not be set

#### Bit 0 - INTL HLVD Negative going (Low Voltage) Interrupt Enable

Value	Description
1	HLVDIF will be set when voltage ≤ selected detection limit (SEL)
0	HLVDIF will not be set

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 887

#### 40.9.2 **HLVDCON1**

Name: **HLVDCON1** Offset: 0x04B

Low-Voltage Detect Control Register 1



Bits 3:0 - SEL[3:0] High/Low-Voltage Detection Limit Selection

**Table 40-2. HLVD Detection Limits** 

SEL	Detection Limit
1111	Reserved
1110	4.63V
1101	4.32V
1100	4.12V
1011	3.91V
1010	3.71V
1001	3.60V
1000	3.40V
0111	3.09V
0110	2.88V
0101	2.78V
0100	2.57V
0011	2.47V
0010	2.26V
0001	2.06V
0000	1.85V

Reset States: POR/BOR = 0000

All other Resets = uuuu

## 40.10 Register Summary - HLVD

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x49										
0x4A	HLVDCON0	7:0	EN		OUT	RDY			INTH	INTL
0x4B	HLVDCON1	7:0						SEL	[3:0]	

## 41. FVR - Fixed Voltage Reference

The Fixed Voltage Reference (FVR) is a stable voltage reference, independent of V<sub>DD</sub>, with 1.024V, 2.048V or 4.096V selectable output levels. The output of the FVR can be configured to supply a reference voltage to analog peripherals such as those listed below.

- · ADC input channel
- · ADC positive reference
- · Comparator input
- · Digital-to-Analog Converter (DAC)

The FVR can be enabled by setting the EN bit to '1'.

Note: Fixed Voltage Reference output cannot exceed VDD.

### 41.1 Independent Gain Amplifiers


The output of the FVR is routed through two independent programmable gain amplifiers. Each amplifier can be programmed for a gain of 1x, 2x or 4x, to produce the three possible voltage levels.

The ADFVR bits are used to enable and configure the gain amplifier settings for the reference supplied to the ADC module. Refer to the "ADCC - Analog-to-Digital Converter with Computation Module" chapter for additional information.

The CDAFVR bits are used to enable and configure the gain amplifier settings for the reference supplied to the DAC and comparator modules. Refer to the "DAC - Digital-to-Analog Converter Module" and "CMP - Comparator Module" chapters for additional information.

Refer to the figure below for block diagram of the FVR module.

Figure 41-1. Fixed Voltage Reference Block Diagram



#### 41.2 FVR Stabilization Period

When the Fixed Voltage Reference module is enabled, it requires time for the reference and amplifier circuits to stabilize. Once the circuits stabilize and are ready for use, the RDY bit will be set.

### 41.3 Register Definitions: FVR

Long bit name prefixes for the FVR peripherals are shown in the following table. Refer to the "Long Bit Names" section in the "Register and Bits Naming Conventions" chapter for more information.

**FVR - Fixed Voltage Reference** 

## Table 41-1. FVR Long bit name prefixes

Peripheral	Bit Name Prefix
FVR	FVR

#### 41.3.1 FVRCON

Name: FVRCON Offset: 0x3D7

**FVR Control Register** 



**Important:** This register is shared between the Fixed Voltage Reference (FVR) module and the Temperature Indicator module.

Bit	7	6	5	4	3	2	1	0
	EN	RDY	TSEN	TSRNG	CDAF\	/R[1:0]	ADFV	'R[1:0]
Access	R/W	R	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	q	0	0	0	0	0	0

#### Bit 7 - EN Fixed Voltage Reference Enable

Value	Description
1	Enables module
0	Disables module

#### Bit 6 - RDY Fixed Voltage Reference Ready Flag

Value	Description
1	Fixed Voltage Reference output is ready for use
0	Fixed Voltage Reference output is not ready for use or not enabled

#### Bit 5 - TSEN Temperature Indicator Enable

Value	Description
1	Temperature Indicator is enabled
0	Temperature Indicator is disabled

#### Bit 4 - TSRNG Temperature Indicator Range Selection

	Tare Tomporatare manage Colocation
Value	Description
1	V <sub>OUT</sub> = 3V <sub>T</sub> (High Range)
0	V <sub>OUT</sub> = 2V <sub>T</sub> (Low Range)

#### Bits 3:2 - CDAFVR[1:0] FVR Buffer 2 Gain Selection(1)

Value	Description
11	FVR Buffer 2 Gain is 4x, (4.096V) <sup>(3)</sup>
10	FVR Buffer 2 Gain is 2x, (2.048V) <sup>(3)</sup>
01	FVR Buffer 2 Gain is 1x, (1.024V)
00	FVR Buffer 2 is OFF

#### Bits 1:0 - ADFVR[1:0] FVR Buffer 1 Gain Selection(2)

Value	Description
11	FVR Buffer 1 Gain is 4x, (4.096V) <sup>(3)</sup>
10	FVR Buffer 1 Gain is 2x, (2.048V) <sup>(3)</sup>
01	FVR Buffer 1 Gain is 1x, (1.024V)
00	FVR Buffer 1 is OFF

#### Notes:

- 1. This output goes to the DAC and comparator modules, and to the ADC module as an input channel only.
- 2. This output goes to the ADC module as a reference and an input channel.
- Fixed Voltage Reference output cannot exceed V<sub>DD</sub>.

## 41.4 Register Summary - FVR

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x03D6										
0x03D7	FVRCON	7:0	EN	RDY	TSEN	TSRNG	CDAF	/R[1:0]	ADFV	R[1:0]

## 42. Temperature Indicator Module

This family of devices is equipped with a temperature circuit designed to measure the operating temperature of the silicon die. The temperature indicator module provides a temperature-dependent voltage that can be measured by the internal Analog-to-Digital Converter.


The circuit's range of operating temperature falls between -40°C and +125°C. The circuit may be used as a temperature threshold detector or a more accurate temperature indicator, depending on the level of calibration performed. A one-point calibration allows the circuit to indicate a temperature closely surrounding that point. A two-point calibration allows the circuit to sense the entire range of temperature more accurately.

## 42.1 Module Operation

The temperature indicator module consists of a temperature-sensing circuit that provides a voltage to the device ADC. The analog voltage output varies inversely to the device temperature. The output of the temperature indicator is referred to as V<sub>MEAS</sub>.

The following figure shows a simplified block diagram of the temperature indicator module.

Figure 42-1. Temperature Indicator Module Block Diagram



The output of the circuit is measured using the internal Analog-to-Digital Converter. A channel is reserved for the temperature circuit output. Refer to the "ADCC - Analog-to-Digital Converter with Computation Module" chapter for more details.

The ON/OFF bit for the module is located in the FVRCON register. The circuit is enabled by setting the TSEN bit. When the module is disabled, the circuit draws no current. Refer to the "FVR - Fixed Reference Voltage" chapter for more details.

#### 42.1.1 Temperature Indicator Range

The temperature indicator circuit operates in either high or low range. The high range, selected by setting the TSRNG bit, provides a wider output voltage. This provides more resolution over the temperature range. High range requires a higher bias voltage to operate and thus, a higher  $V_{DD}$  is needed. The low range is selected by clearing the TSRNG bit. The low range generates a lower sensor voltage and thus, a lower  $V_{DD}$  voltage is needed to operate the circuit.

The output voltage of the sensor is the highest value at -40°C and the lowest value at +125°C.

- **High Range:** The high range is used in applications with the reference for the ADC, V<sub>REF</sub> = 2.048V. This range may not be suitable for battery-powered applications.
- Low Range: This mode is useful in applications in which the V<sub>DD</sub> is too low for high-range operation. The V<sub>DD</sub> in
  this mode can be as low as 1.8V. However, V<sub>DD</sub> must be at least 0.5V higher than the maximum sensor voltage
  depending on the expected low operating temperature.



**Important:** The standard parameters for the Temperature Sensor for both high range and low range are stored in the DIA table. Refer to the DIA table in "**Memory Organization**" chapter for more details.

#### 42.1.2 Minimum Operating V<sub>DD</sub>

When the temperature circuit is operated in low range, the device may be operated at any operating voltage that is within the device specifications. When the temperature circuit is operated in high range, the device operating voltage,  $V_{DD}$ , must be high enough to ensure that the temperature circuit is correctly biased.

The following table shows the recommended minimum V<sub>DD</sub> vs. Range setting.

Table 42-1. RECOMMENDED V<sub>DD</sub> vs. RANGE

Min. V <sub>DD</sub> , TSRNG = 1	Min. V <sub>DD</sub> , TSRNG = 0
(High Range)	(Low Range)
≥ 2.5	≥ 1.8

#### 42.2 Temperature Calculation

This section describes the steps involved in calculating the die temperature, T<sub>MEAS</sub>:

- Obtain the ADC count value of the measured analog voltage: The analog output voltage, V<sub>MEAS</sub> is converted to a digital count value by the Analog-to-Digital Converter (ADC) and is referred to as ADC<sub>MEAS</sub>.
- Obtain the Gain value, from the DIA table. This parameter is TSLR1 for the low range setting or TSHR1 for the high range setting of the temperature indicator module. Refer to the DIA table in the "Memory Organization" chapter for more details.
- Obtain the Offset value, from the DIA table. This parameter is TSLR3 for the low range setting or TSHR3 for the high range setting of the temperature indicator module. Refer to the DIA table in the "Memory Organization" chapter for more details.

The following equation provides an estimate for the die temperature based on the above parameters:

#### Equation 42-1. Sensor Temperature (in °C)

$$T_{MEAS} = \frac{\frac{(ADC_{MEAS} \times Gain)}{256} + Offset}{10}$$

Where:

ADC<sub>MEAS</sub> = ADC reading at temperature being estimated

Gain = Gain value stored in the DIA table

Offset = Offset Value stored in the DIA table

**Note:** It is recommended to take the average of ten measurements of ADC<sub>MEAS</sub> to reduce noise and improve accuracy.

```
Example 42-1. Temperature Calculation (C)
 // offset is int16_t data type
 // gain is int16 t data type
 // ADC MEAS is uint16 t data type
 // Temp_in_C is int24_t data type
 ADC MEAS = ((ADRESH << 8) + ADRESL);
                                                // Store the ADC Result
 \overline{\text{Temp}} in C = (\text{int24 t}) (ADC MEAS) * gain;
                                                // Multiply the ADC Result by
                                                 // Gain and store the result in a
                                                 // signed variable
 Temp_in_C = Temp_in_C / 256;
                                                 // Divide (ADC Result * Gain) by 256
 Temp_in_C = Temp_in_C + offset;
Temp_in_C = Temp_in_C / 10;
                                                // Add (Offset) to the result
                                                 // Devide the result by 10 and store
                                                 // the calculated temperature
```

#### 42.2.1 Higher-Order Calibration

If the application requires more precise temperature measurement, additional calibrations steps will be necessary. For these applications, two-point or three-point calibration is recommended. For additional information on two-point

## **Temperature Indicator Module**

calibration method, refer to the following Microchip application note, available at the corporate website (www.microchip.com):

• AN2798, "Using the PIC16F/PIC18F Ground Referenced Temperature Indicator Module"

## 42.3 ADC Acquisition Time

To ensure accurate temperature measurements, the user must wait a certain minimum acquisition time (parameter TS01) after the temperature indicator output is selected as ADC input. This is required for the ADC sampling circuit to settle before the conversion is performed.

**Note:** Parameter TS01 can be found in the Temperature Indicator Requirements table of the "**Electrical Specifications**" chapter.

## 42.4 Register Definitions: Temperature Indicator

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 896

#### 42.4.1 FVRCON

Name: FVRCON Offset: 0x3D7

**FVR Control Register** 



**Important:** This register is shared between the Fixed Voltage Reference (FVR) module and the Temperature Indicator module.

Bit	7	6	5	4	3	2	1	0
	EN	RDY	TSEN	TSRNG	CDAF\	/R[1:0]	ADFV	'R[1:0]
Access	R/W	R	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	q	0	0	0	0	0	0

#### Bit 7 - EN Fixed Voltage Reference Enable

Value	Description
1	Enables module
0	Disables module

#### Bit 6 - RDY Fixed Voltage Reference Ready Flag

Value	Description
1	Fixed Voltage Reference output is ready for use
0	Fixed Voltage Reference output is not ready for use or not enabled

#### Bit 5 - TSEN Temperature Indicator Enable

Value	Description
1	Temperature Indicator is enabled
0	Temperature Indicator is disabled

#### Bit 4 - TSRNG Temperature Indicator Range Selection

Value	Description
1	V <sub>OUT</sub> = 3V <sub>T</sub> (High Range)
0	V <sub>OUT</sub> = 2V <sub>T</sub> (Low Range)

#### Bits 3:2 - CDAFVR[1:0] FVR Buffer 2 Gain Selection(1)

Value	Description
11	FVR Buffer 2 Gain is 4x, (4.096V) <sup>(3)</sup>
10	FVR Buffer 2 Gain is 2x, (2.048V) <sup>(3)</sup>
01	FVR Buffer 2 Gain is 1x, (1.024V)
00	FVR Buffer 2 is OFF

## Bits 1:0 - ADFVR[1:0] FVR Buffer 1 Gain Selection(2)

Value	Description
11	FVR Buffer 1 Gain is 4x, (4.096V) <sup>(3)</sup>
10	FVR Buffer 1 Gain is 2x, (2.048V) <sup>(3)</sup>
01	FVR Buffer 1 Gain is 1x, (1.024V)
00	FVR Buffer 1 is OFF

#### Notes:

- 1. This output goes to the DAC and comparator modules, and to the ADC module as an input channel only.
- 2. This output goes to the ADC module as a reference and an input channel.
- 3. Fixed Voltage Reference output cannot exceed V<sub>DD</sub>.

## 42.5 Register Summary - Temperature Indicator

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x03D6										
0x03D7	FVRCON	7:0	EN	RDY	TSEN	TSRNG	CDAF	/R[1:0]	ADFVR[1:0]	

# 43. ADC - Analog-to-Digital Converter with Computation and Context Module

The Analog-to-Digital Converter with Computation and Context module allows conversion of an analog input signal to a 12-bit binary representation of that signal. This device uses analog inputs that are multiplexed into a single Sample-and-Hold circuit. The output of the Sample-and-Hold (S/H) is connected to the input of the converter. The converter generates a 12-bit binary result via successive approximation and stores the conversion result into the ADC result registers.

Additionally, the following features are provided within the ADC module:

- · Acquisition Timer
- · Hardware Capacitive Voltage Divider (CVD) support:
  - Precharge timer
  - Adjustable Sample-and-Hold capacitor array
  - Guard ring digital output drive
- Automatic Repeat and Sequencing:
  - Automated double sample conversion for CVD
  - Two sets of Result registers (Current Result and Previous Result)
  - Auto-conversion trigger
  - Internal re-trigger
- · Computation Features:
  - Averaging and low-pass filter functions
  - Reference comparison
  - 2-level threshold comparison
  - Selectable interrupts
- · Automated Channel Scanning and Context Switching
  - Supports up to four unique configurations
  - Each configuration is saved as a context
  - Stop on threshold interrupt during a scan
  - Unique threshold interrupt for each configuration


The ADC Block diagram shows the block diagram of the ADC (Figure 1-1).

The ADC voltage reference is software selectable to be either internally generated or externally supplied.

The ADC can generate an interrupt upon completion of a conversion and upon threshold comparison. These interrupts can be used to wake-up the device from Sleep.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 899

Figure 43-1. ADC Block Diagram



## 43.1 ADC Configuration

When configuring the ADC the following functions must be considered:

- · Port Configuration
- · Channel Selection
- · ADC Voltage Reference Selection
- · ADC Conversion Clock Source
- Interrupt Control
- Result Formatting
- · Conversion Trigger Selection

- · ADC Acquisition Time
- · ADC Precharge Time
- Additional Sample-and-Hold Capacitor
- · Single/Double Sample Conversion
- · Guard Ring Outputs

#### 43.1.1 Port Configuration

The ADC will convert the voltage level on a pin, whether or not the ANSEL bit is set. When converting analog signals, the I/O pin should be configured for analog by setting the associated TRIS and ANSEL bits. Refer to the "I/O Ports" chapter for more information.



**Important:** Analog voltages on any pin that is defined as a digital input may cause the input buffer to conduct excess current.

#### 43.1.2 Channel Selection

The ADPCH register determines which channel is connected to the Sample-and-Hold circuit for conversion. When switching channels, it is recommended to have some acquisition time (ADACQ register) before starting the next conversion. Refer to the ADC Operation section for more information.



**Important:** To reduce the chance of measurement error, it is recommended to discharge the Sample-and-Hold capacitor when switching between ADC channels by starting a conversion on a channel connected to  $V_{SS}$  and terminating the conversion after the acquisition time has elapsed. If the ADC does not have a dedicated  $V_{SS}$  input channel, the  $V_{SS}$  selection through the DAC output channel can be used. If the DAC is in use, a free input channel can be connected to  $V_{SS}$ , and can be used in place of the DAC.

# 43.1.3 ADC Voltage Reference

The PREF bits provide control of the positive voltage reference. The NREF bit provides control of the negative voltage reference. Refer to the ADREF register for the list of available positive and negative sources.

#### 43.1.4 Conversion Clock

The conversion clock source is selected with the CS bit. When CS = 1, the ADC clock source is an internal fixed-frequency clock referred to as ADCRC. When CS = 0, the ADC clock source is derived from  $F_{OSC}$ .



**Important:** When CS = 0, the clock can be divided using the ADCLK register to meet the ADC clock period requirements.

The time to complete one bit conversion is defined as the T<sub>AD</sub>. Refer to Figure 43-2 for the complete timing details of the ADC conversion.

For correct conversion, the appropriate  $T_{AD}$  specification must be met. Refer to the ADC Timing Specifications table in the "Electrical Specifications" chapter of the device data sheet for more details. The table below gives examples of appropriate ADC clock selections.

Table 43-1. ADC Clock Period (T<sub>AD</sub>) Vs. Device Operating Frequencies<sup>(1,3)</sup>

ADC Clock	ADCLK	ADCLK ADCLK						
Source ADCLK	ADCLK	64 MHz	32 MHz	20 MHz	16 MHz	8 MHz	4 MHz	1 MHz
F <sub>OSC</sub> /2	'b000000	31.25 ns <sup>(2)</sup>	62.5 ns <sup>(2)</sup>	100 ns <sup>(2)</sup>	125 ns <sup>(2)</sup>	250 ns <sup>(2)</sup>	500 ns	2.0 µs

continued										
ADC Clock		ADC Clock Period (T <sub>AD</sub> ) for Different Device Frequency (F <sub>OSC</sub> )								
Source	ADCLK	64 MHz	32 MHz	20 MHz	16 MHz	8 MHz	4 MHz	1 MHz		
F <sub>OSC</sub> /4	'b000001	62.5 ns <sup>(2)</sup>	125 ns <sup>(2)</sup>	200 ns <sup>(2)</sup>	250 ns <sup>(2)</sup>	500 ns	1.0 µs	4.0 µs		
F <sub>OSC</sub> /6	'b000010	93.75 ns <sup>(2)</sup>	187.5 ns <sup>(2)</sup>	300 ns <sup>(2)</sup>	375 ns <sup>(2)</sup>	750 ns	1.5 µs	6.0 µs		
F <sub>OSC</sub> /8	'b000011	125 ns <sup>(2)</sup>	250 ns <sup>(2)</sup>	400 ns <sup>(2)</sup>	500 ns	1.0 µs	2.0 µs	8.0 µs		
	•••									
F <sub>OSC</sub> /16	'b000111	250 ns <sup>(2)</sup>	500 ns	800 ns	1.0 µs	2.0 µs	4.0 µs	16.0 µs <sup>(2)</sup>		
F <sub>OSC</sub> /32	'b001111	500 ns	1.0 µs	1.6 µs	2.0 µs	4.0 µs	8.0 µs	32.0 µs <sup>(2)</sup>		
							•••			
F <sub>OSC</sub> /64	'b0111111	1.0 µs	2.0 µs	3.2 µs	4.0 µs	8.0 µs	16.0 µs <sup>(2)</sup>	64.0 µs <sup>(2)</sup>		
	•••									
F <sub>OSC</sub> /128	'b111111	2.0 µs	4.0 µs	6.4 µs	8.0 µs	16.0 µs <sup>(2)</sup>	32.0 µs <sup>(2)</sup>	128.0 µs <sup>(2)</sup>		
ADCRC	CS=1	1.0-6.0 µs	1.0-6.0 µs	1.0-6.0 µs	1.0-6.0 µs	1.0-6.0 µs	1.0-6.0 µs	1.0-6.0 µs		

#### Notes:


- Refer to the "Electrical Specifications" chapter of the device data sheet to see the T<sub>AD</sub> parameter for the ADCRC source typical T<sub>AD</sub> value.
- 2. These values violate the required  $T_{AD}$  time.
- The ADC clock period (T<sub>AD</sub>) and total ADC conversion time can be minimized when the ADC clock is derived from the system clock F<sub>OSC</sub>. However, the ADCRC oscillator source must be used when conversions are to be performed with the device in Sleep mode.



## Important:

- Except for the ADCRC clock source, any changes in the system clock frequency will change the ADC clock frequency, which may adversely affect the ADC result.
- The internal control logic of the ADC runs off of the clock selected by the CS bit. When the CS bit is set to '1' (ADC runs on ADCRC), there may be unexpected delays in operation when setting the ADC control bits.

Figure 43-2. Analog-to-Digital Conversion Cycles



#### Note:

- Refer to the ADC Conversion Timing Specifications table in the "Electrical Specifications" chapter of the device data sheet for more details.
- 2. Refer to ADPRE register for more details.
- 3. Refer to ADACQ register for more details.

#### 43.1.5 Interrupts

The ADC module allows for the ability to generate an interrupt upon completion of an Analog-to-Digital Conversion. The ADC interrupt flag is the ADIF bit in the PIRx register. The ADC interrupt enable is the ADIE bit in the PIEx register. The ADIF bit must be cleared by software.



#### Important:


- The ADIF bit is set at the completion of every conversion, regardless of whether or not the ADC interrupt is enabled.
- 2. The ADC operates during Sleep only when the ADCRC oscillator is selected.

This interrupt will be generated while the device is operating and while in Sleep. If the device is in Sleep, the interrupt will wake-up the device. Upon waking from Sleep, the next instruction following the SLEEP instruction is always executed. If the user is attempting to wake-up from Sleep and resume in-line code execution, the ADIE bit and the GIEL bit must both be set and the GIE bit must be cleared. When all three of these bits are set, the execution will switch to the Interrupt Service Routine.

#### 43.1.6 Result Formatting

The ADC conversion result can be supplied in two formats, left justified or right justified. The FM bit controls the output format as shown in Figure 43-3.

Figure 43-3. 12-Bit ADC Conversion Result Format





**Important:** Writes to the ADRES register pair are always right justified, regardless of the selected format mode. Therefore, a data read after writing to ADRES when FM = 0 will be shifted left four places.

# 43.2 ADC Operation

## 43.2.1 Starting a Conversion

To enable the ADC module, the ON bit must be set to '1'. A conversion may be started by any of the following:

- Software setting the GO bit to '1'
- An external trigger (source selected by ADACT)
- · A continuous-mode retrigger (see the Continuous Sampling Mode section for more details)



**Important:** The GO bit should not be set in the same instruction that turns on the ADC. Refer to the ADC Conversion Procedure (Basic Mode) section for more details.

## 43.2.2 Completion of a Conversion

When any individual conversion is complete, the existing value in ADRES is written into ADPREV (if PSIS = 0) and the new conversion results appear in ADRES. When the conversion completes, the ADC module will:

- Clear the GO bit (unless the CONT bit is set)
- · Set the ADIF Interrupt Flag bit
- · Set the MATH bit
- Update ADACC

After every conversion when DSEN = 0, or after every other conversion when DSEN = 1, the following events occur:

- · ADERR is calculated
- ADC Channel Threshold Interrupt (ADCHxIF) is set if ADERR calculation meets threshold comparison

#### 43.2.3 ADC Operation During Sleep

The ADC module can operate during Sleep. This requires the ADC clock source to be set to the ADCRC option. When the ADCRC oscillator source is selected, the ADC waits one additional instruction before starting the

conversion. This allows the SLEEP instruction to be executed, which can reduce system noise during the conversion. If the ADC interrupt is enabled, the device will wake-up from Sleep when the conversion completes. If the ADC interrupt is disabled, the device remains in Sleep and the ADC module is turned off after the conversion completes, although the ON bit remains set.

## 43.2.4 External Trigger During Sleep

If the external trigger is received during Sleep while the ADC clock source is set to the ADCRC, the ADC module will perform the conversion and set the ADIF bit upon completion.

If an external trigger is received when the ADC clock source is something other than ADCRC, the trigger will be recorded, but the conversion will not begin until the device exits Sleep.

## 43.2.5 Auto-Conversion Trigger

The auto-conversion trigger allows periodic ADC measurements without software intervention. When a rising edge of the selected source occurs, the GO bit is set by hardware.

The auto-conversion trigger source is selected with the ACT bits.

Using the auto-conversion trigger does not ensure proper ADC timing. It is the user's responsibility to ensure that the ADC timing requirements are met.

#### 43.2.6 ADC Conversion Procedure (Basic Mode)

This is an example procedure for using the ADC to perform an Analog-to-Digital Conversion:

- Configure Port:
  - 1.1. Disable pin output driver (Refer to the TRISx register)
  - 1.2. Configure pin as analog (Refer to the ANSELx register)
- 2. Configure the ADC module:
  - 2.1. Select ADC conversion clock
  - 2.2. Configure voltage reference
  - 2.3. Select ADC input channel
  - 2.4. Configure precharge (ADPRE) and acquisition (ADACQ) time period
  - 2.5. Turn on ADC module
- Configure ADC interrupt (optional):
  - 3.1. Clear ADC interrupt flag
  - 3.2. Enable ADC interrupt
  - 3.3. Enable global interrupt (GIE bit)(1)
- 4. If ADACQ = 0, software must wait the required acquisition time<sup>(2)</sup>.
- 5. Start conversion by setting the GO bit.
- 6. Wait for ADC conversion to complete by one of the following:
  - Polling the GO bit
  - Waiting for the ADC interrupt (if interrupt is enabled)
- 7. Read ADC Result.
- 8. Clear the ADC interrupt flag (if interrupt is enabled).

#### Notes:

- 1. With global interrupts disabled (GIE = 0), the device will wake from Sleep, but will not enter an Interrupt Service Routine.
- 2. Refer to the ADC Acquisition Requirements section for more details.

```
Example 43-1. ADC Conversion (assembly)

; This code block configures the ADC for polling, Vdd and Vss references,
; ADCRC oscillator, and ANO input.
; Conversion start & polling for completion are included.

BANKSEL ADCON1 ;
clrf ADCON1 ;
```

```
ADCON2
                      ; Legacy mode, no filtering, ADRES->ADPREV
                  ; no math functions
; Vref = Vdd & Vss
         ADCON3
clrf
clrf
         ADREF
        ADACQ ; software controlled acquisition time
ADCAP ; default S&H capacitance
ADRPT ; no repeat measurements
ADACT ; auto-conversion discussions
clrf
clrf
clrf
clrf
clrf
         B'10010100'; ADC On, right-justified, ADCRC clock
movlw
movwf
         ADCONO
BANKSEL TRISA
bsf
         TRISA, 0
                      ; Set RAO to input
BANKSEL ANSEL
         ANSEL, 0; Set RAO to analog
bsf
call
         SampleTime ; Acquisiton delay
BANKSEL ADCON0
bsf
        ADCON0,GO
                      ; Start conversion
       ADCON0,GO ; Is conversion done?
bt.fsc
goto
                     ; No, test again
         $-2
BANKSEL ADRESH
                    ; Read upper byte
movf
         ADRESH, W
movwf
                    ; store in GPR space
; Read lower byte
         RESULTHI
         ADRESL, W
movf
                     ; Store in GPR space
movwf
         RESULTLO
```

#### /\*This code block configures the ADC for polling, $V_{DD}$ and $V_{SS}$ references, ADCRC oscillator and ANO input. Conversion start & polling for completion are included. void main() { //System Initialize initializeSystem(); //Setup ADC //right justify //ADCRC Clock ADCONObits.FM = 1;ADCONObits.CS = 1; //RA0 is Analog channel //Set RA0 to input ADPCH = 0x00;TRISAbits.TRISA0 = 1; ANSELAbits.ANSELA0 = 1; //Set RA0 to analog

//Turn ADC On

//Read result

ADCONObits.GO = 1; //Start conversion

resultHigh = ADRESH; //Read result

while (ADCONObits.GO); //Wait for conversion done

# 43.3 ADC Acquisition Requirements

}

while (1) {

Example 43-2. ADC Conversion (C)

ADCONObits.ON = 1;

resultLow = ADRESL;

For the ADC to meet its specified accuracy, the charge holding capacitor ( $C_{HOLD}$ ) must be allowed to fully charge to the input channel voltage level. The analog input model is shown in Figure 43-4. The source impedance ( $R_S$ ) and the internal sampling switch ( $R_{SS}$ ) impedance directly affect the time required to charge the capacitor  $C_{HOLD}$ . The sampling switch ( $R_{SS}$ ) impedance varies over the device voltage ( $V_{DD}$ ). The maximum recommended impedance for analog sources is 10 k $\Omega$ . As the source impedance is decreased, the acquisition time may be decreased. After the analog input channel is selected (or changed), an ADC acquisition time must be completed before the conversion can be started. To calculate the minimum acquisition time, Equation 43-1 may be used. This equation assumes an error of 1/2 LSb. The 1/2 LSb error is the maximum error allowed for the ADC to meet its specified resolution.

#### **Equation 43-1. Acquisition Time Example**

Assumptions: Temperature =  $50^{\circ}$ C; External impedance =  $10k\Omega$ ;  $V_{DD}$  = 5.0V

T<sub>ACO</sub> = Amplifier Settling Time + Hold Capacitor Charging Time + Temperature Coefficient

$$T_{ACO} = T_{AMP} + T_C + T_{COFF}$$

$$T_{ACQ} = 2\mu s + T_C + \left[ \left( Temperature - 25^{\circ}C \right) \left( 0.05\mu s / {^{\circ}C} \right) \right]$$

The value for T<sub>C</sub> can be approximated with the following equations:

$$V_{APPLIED} \left( 1 - \frac{1}{\left(2^{n+1}\right) - 1} \right) = V_{CHOLD}$$
; [1]  $V_{CHOLD}$  charged to within ½ lsb

$$V_{APPLIED} \! \left( 1 - e rac{-T_C}{RC} 
ight) \ = \ V_{CHOLD}$$
 ; [2]  $V_{CHOLD}$  charge response to  $V_{APPLIED}$ 

$$V_{APPLIED} \left( 1 - e^{\frac{-T_C}{RC}} \right) = V_{APPLIED} \left( 1 - \frac{1}{\left(2^{n+1}\right) - 1} \right)$$
; Combining [1] and [2]

Note: Where n = ADC resolution in bits

Solving for  $T_C$ :

$$T_C = -C_{HOLD}(R_{IC} + R_{SS} + R_S) \ln (1/8191)$$

$$T_C = -28pF(1k\Omega + 7k\Omega + 10k\Omega) \ln (0.0001221)$$

$$T_C = 4.54 \mu s$$

Therefore:

$$T_{ACQ} = 2\mu s + 4.54\mu s + \left[ \left( 50^{\circ}C - 25^{\circ}C \right) \left( 0.05\mu s/^{\circ}C \right) \right]$$


$$T_{ACO} = 7.79 \, \mu s$$



#### Important:


- The reference voltage (V<sub>REF</sub>) has no effect on the equation, since it cancels itself out.
- The charge holding capacitor (C<sub>HOLD</sub>) is not discharged after each conversion.
- The maximum recommended impedance for analog sources is 10 kΩ. This is required to meet the pin leakage specification.

Figure 43-4. Analog Input Model



1. Refer to the "Electrical Specifications" chapter of the device data sheet for more details.

Figure 43-5. ADC Transfer Function



# 43.4 ADC Charge Pump


The ADC module has a dedicated charge pump which can be controlled through the ADCP register. The primary purpose of the charge pump is to supply a constant voltage to the gates of transistor devices in the Analog-to-Digital Converter, signal and reference input pass-gates, to prevent degradation of transistor performance at low operating voltage.

The charge pump can be enabled by setting the CPON bit. Once enabled, the pump will undergo a start-up time to stabilize the charge pump output. Once the output stabilizes and is ready for use, the CPRDY bit will be set.

# 43.5 Computation Operation

The ADC module hardware is equipped with post-conversion computation features. These features provide post-processing functions such as digital filtering/averaging and threshold comparison. Based on computation results, the module can be configured to take additional samples or stop conversions and an interrupt may be asserted.

Figure 43-6. Computational Features Simplified Block Diagram



The operation of the ADC computational features is controlled by the MD bits.

The module can be operated in one of five modes:

- **Basic:** This is a legacy mode. In this mode, ADC conversion occurs on single (DSEN = 0) or double (DSEN = 1) samples. ADIF is set after each conversion is complete. ADCHxIF is set according to the calculation mode.
- **Accumulate:** With each trigger, the ADC conversion result is added to the accumulator and CNT increments. ADIF is set after each conversion. ADCHxIF is set according to the calculation mode.
- Average: With each trigger, the ADC conversion result is added to the accumulator. When the RPT number of samples have been accumulated, a threshold test is performed. Upon the next trigger, the accumulator is cleared. For the subsequent tests, additional RPT samples are required to be accumulated.
- **Burst Average:** At the trigger, the accumulator is cleared. The ADC conversion results are then collected repetitively until RPT samples are accumulated and finally the threshold is tested.
- Low-Pass Filter (LPF): With each trigger, the ADC conversion result is sent through a filter. When RPT samples have occurred, a threshold test is performed. Every trigger after that the ADC conversion result is sent through the filter and another threshold test is performed.

The five modes are summarized in the following table.

Table 43-2. Computation Modes

Register Clear Mode MD Event		Value after Cycle <sup>(1)</sup> Completion		Thi	Value at ADCHmIF Interrupt					
		ADACC and CNT	ADACC	ADCNT	Retrigger	Threshold Test	Interrupt	AOV	ADFLTR	ADCNT
Basic	0	ACLR = 1	Unchanged	Unchanged	No	Every Sample	If threshold=true	N/A	N/A	count
Accumulate	1	ACLR = 1	S1 + ADACC or (S2-S1) <sup>(2)</sup> + ADACC	If (ADCNT=0xFF): ADCNT, otherwise: ADCNT+1	No	Every Sample	If threshold=true	ADACC Overflow	ADACC/ 2 <sup>CRS</sup>	count
Average	2	ACLR = 1 or ADCNT≥ADRPT at GO set or retrigger	S1 + ADACC or (S2-S1) + ADACC	If (ADCNT=0xFF): ADCNT, otherwise: ADCNT+1	No	If ADCNT≥ADRPT	If threshold=true	ADACC Overflow	ADACC/ 2 <sup>CRS</sup>	count
Burst Average	3	ACLR = 1 or at GO set or retrigger	Each repetition: same as Average End with sum of all samples	Each repetition: same as Average End with ADCNT=ADRPT	Repeat while ADCNT <adrpt< td=""><td>If ADCNT≥ADRPT</td><td>If threshold=true</td><td>ADACC Overflow</td><td>ADACC/ 2<sup>CRS</sup></td><td>ADRPT</td></adrpt<>	If ADCNT≥ADRPT	If threshold=true	ADACC Overflow	ADACC/ 2 <sup>CRS</sup>	ADRPT
Low-pass Filter	4	ACLR = 1	S1+ADACC- ADACC/ 2 <sup>CRS</sup> or (S2- S1)+ADACC- ADACC/2 <sup>CRS</sup>	If (ADCNT=0xFF): ADCNT, otherwise: ADCNT+1	No	If ADCNT≥ADRPT	If threshold=true	ADACC Overflow	ADACC/ 2 <sup>CRS</sup> (Filtered Value)	count

#### Notes:

- 1. When DSEN = 0 then Cycle means one conversion. When DSEN = 1 then Cycle means two conversions.
- 2. S1 and S2 are abbreviations for Sample 1 and Sample 2, respectively. When DSEN = 0, S1 = ADRES; When DSEN = 1, S1 = ADPREV and S2 = ADRES.

ADC - Analog-to-Digital Converter with Com..

PIC18F26/46/56Q84

#### 43.5.1 Digital Filter/Average

The digital filter/average module consists of an accumulator with data feedback options, and control logic to determine when threshold tests need to be applied. The accumulator can be accessed through the ADACC register.

Upon each trigger event (the GO bit set or external event trigger), the ADC conversion result is added to or subtracted from the accumulator. If the accumulated value exceeds  $2^{(accumulator\_width)}_1 = 2^{18}_1 = 262143$ , the AOV overflow bit is set.

The number of samples to be accumulated is determined by the ADRPT (ADC Repeat Setting) register. Each time a sample is added to the accumulator, the ADCNT register is incremented. Once ADRPT samples are accumulated (ADCNT = ADRPT), the accumulator may be cleared automatically depending on ADC operation mode. An accumulator clear command can be issued in software by setting the ACLR bit. Setting the ACLR bit will also clear the AOV (Accumulator overflow) bit, as well as the ADCNT register. The ACLR bit is cleared by the hardware when accumulator clearing action is complete.



**Important:** When ADC is operating from ADCRC, up to five ADCRC clock cycles are required to execute the ADACC clearing operation.

The CRS bits control the data shift on the accumulator result, which effectively divides the value in the accumulator registers. For the Accumulate mode of the digital filter, the shift provides a simple scaling operation. For the Average/ Burst Average mode, the calculated average is only accurate when the number of samples agrees with the number of bits shifted. For the Low-Pass Filter mode, the shift is an integral part of the filter, and determines the cutoff frequency of the filter. Table 43-3 shows the -3 dB cutoff frequency in  $\omega T$  (radians) and the highest signal attenuation obtained by this filter at Nyquist frequency ( $\omega T = \pi$ ).

Table 43-3. Low-pass Filter -3 dB Cutoff Frequency

CRS	ωT (radians) @ -3 dB Frequency	dB @ F <sub>Nyquist</sub> =1/(2T)
1	0.72	-9.5
2	0.284	-16.9
3	0.134	-23.5
4	0.065	-29.8
5	0.032	-36.0
6	0.016	-42.0

#### 43.5.2 Basic Mode

Basic mode (MD = 'b000) disables all additional computation features. In this mode, no accumulation occurs but threshold error comparison is performed. Double sampling, Continuous mode, and all CVD features are still available, but no digital filter/average calculations are performed.

#### 43.5.3 Accumulate Mode

In Accumulate mode (MD = 'b001), after every conversion, the ADC result is added to the ADACC register. The ADACC register is right-shifted by the value of the CRS bits. This right-shifted value is copied in to the ADFLTR register. The Formatting mode does not affect the right-justification of the ADACC or ADFLTR values. Upon each sample, ADCNT is incremented, counting the number of samples accumulated. After each sample and accumulation, the ADFLTR value has a threshold comparison performed on it (see Threshold Comparison section) and the ADCHxIF interrupt may trigger.

#### 43.5.4 Average Mode

In Average mode (MD = 'b010), the ADACC registers accumulate with each ADC sample, much as in Accumulate mode, and the ADCNT register increments with each sample. The ADFLTR register is also updated with the right-shifted value of the ADACC register. The value of the CRS bits governs the number of right shifts. However, in Average mode, the threshold comparison is performed upon ADCNT being greater than or equal to a user-defined

ADRPT value. In this mode, when ADRPT =  $2^{CRS}$ , the final accumulated value will be divided by the number of samples, allowing for a threshold comparison operation on the average of all gathered samples.

## 43.5.5 Burst Average Mode

The Burst Average mode (MD = 'b011) acts the same as the Average mode in most respects. The one way it differs is that it continuously retriggers ADC sampling until the CNT value is equal to RPT, even if Continuous Sampling mode (see Continuous Sampling Mode section) is not enabled. This provides a threshold comparison on the average of a short burst of ADC samples.

#### 43.5.6 Low-Pass Filter Mode

The Low-Pass Filter mode (MD = 'b100) acts similarly to the Average mode in how it handles samples; it accumulates samples until the CNT value is greater than or equal to RPT, then triggers a threshold comparison. But, instead of a simple average, it performs a low-pass filter operation on all of the samples, reducing the effect of high-frequency noise on the total, then performs a threshold comparison on the results. In this mode, the CRS bits determine the cutoff frequency of the low-pass filter (as demonstrated by Digital Filter/Average). Refer to the Computation Operation section for a more detailed description of the mathematical operation.

For more information about Low-Pass Filter mode, refer to the following Microchip application note, available in the corporate website (www.microchip.com):

• AN2749, "PIC18 12-bit ADC2 in Low-Pass Filter Mode"

## 43.5.7 Threshold Comparison

At the end of each computation:

- · The conversion results are captured at the end-of-conversion.
- The error (ADERR) is calculated based on a difference calculation which is selected by the CALC bits. The
  value can be one of the following calculations:
  - The first derivative of single measurements
  - The CVD result when double sampling is enabled
  - The current result vs. setpoint value in the ADSTPT register
  - The current result vs. the filtered/average result
  - The first derivative of the filtered/average value
  - Filtered/average value vs. setpoint value in the ADSTPT register
- The result of the calculation (ADERR) is compared to the upper and lower thresholds, ADUTH and ADLTH
  registers, to set the UTHR and LTHR flag bits. The threshold logic is selected by the TMD bits. The threshold
  trigger option can be one of the following:
  - Never interrupt
  - Error is less than lower threshold
  - Error is greater than or equal to lower threshold
  - Error is between thresholds (inclusive)
  - Error is outside of thresholds
  - Error is less than or equal to upper threshold
  - Error is greater than upper threshold
  - Always interrupt regardless of threshold test results
  - If the threshold condition is met, the channel threshold interrupt flag ADCHxIF is set.



# Important:

- · The threshold tests are signed operations.
- If the AOV bit is set, a threshold interrupt is signaled. It is good practice for threshold interrupt handlers to verify the validity of the threshold by checking the AOV bit.

#### 43.5.8 Repetition and Sampling Options

#### 43.5.8.1 Continuous Sampling Mode

Setting the CONT bit automatically retriggers a new conversion cycle after updating the ADACC register. That means the GO bit remains set to generate automatic retriggering. If SOI = 1, a threshold interrupt condition will clear the GO bit and the conversion will stop.


#### 43.5.8.2 Double Sample Conversion

Double sampling is enabled by setting the DSEN bit. When this bit is set, two conversions are required before the module calculates the threshold error. Each conversion must be triggered separately when CONT = 0, but will repeat automatically form a single trigger when CONT = 1. The first conversion will set the MATH bit and update the ADACC register, but will not calculate ADERR or trigger ADCHxIF. When the second conversion completes, the first value is transferred to ADPREV (depending on the setting of PSIS) and the value of the second conversion is placed into ADRES. Only upon the completion of the second conversion is ADERR calculated and ADCHxIF triggered (depending on the value of CALC).

#### 43.5.9 Capacitive Voltage Divider (CVD) Features

The ADC module contains several features that allow the user to perform a relative capacitance measurement on any ADC channel using the internal ADC Sample-and-Hold capacitance as a reference. This relative capacitance measurement can be used to implement capacitive touch or proximity sensing applications. The following figure shows the basic block diagram of the CVD portion of the ADC module.

Figure 43-7. Hardware Capacitive Voltage Divider Block Diagram



This is an example to configure ADC for CVD operation:

- 1. Configure Port:
  - 1.1. Disable pin output driver (refer to the TRISx register)
  - 1.2. Configure pin as analog (refer to the ANSELx register)
- 2. Configure the ADC module:
  - 2.1. Select ADC conversion clock
  - 2.2. Configure voltage reference
  - 2.3. Select ADC input channel
  - 2.4. Configure precharge (ADPRE) and acquisition (ADACQ) time period
  - Select precharge polarity (PPOL)
  - 2.6. Enable Double Sampling (DSEN)

# PIC18F26/46/56Q84

# ADC - Analog-to-Digital Converter with Com...

- 2.7. Turn on ADC module
- Configure ADC interrupt (optional):
  - 3.1. Clear ADC interrupt flag
  - 3.2. Enable ADC interrupt
  - 3.3. Enable global interrupt (GIE bit)<sup>(1)</sup>
- 4. Start double sample conversion by setting the GO bit.
- 5. Wait for ADC conversion to complete by one of the following:
  - Polling the GO bit
  - Waiting for the ADC interrupt (if interrupt is enabled)
- 6. Second ADC conversion depends on the state of CONT:
  - 6.1. If CONT = 1, both conversion will repeat automatically form a single trigger.
  - 6.2. If CONT = 0, each conversion must be triggered separately.
- 7. ADERR register contains the CVD result
- 8. Clear the ADC interrupt flag (if interrupt is enabled).

#### Note:

1. With global interrupts disabled (GIE = 0), the device will wake from Sleep, but will not enter an Interrupt Service Routine

#### 43.5.9.1 CVD Operation

A CVD operation begins with the ADC's internal Sample-and-Hold capacitor ( $C_{HOLD}$ ) being disconnected from the path, which connects it to the external capacitive sensor node. While disconnected,  $C_{HOLD}$  is precharged to  $V_{DD}$  or discharged to  $V_{SS}$ . The sensor node is either discharged or charged to  $V_{SS}$  or  $V_{DD}$ , respectively to the opposite level of  $C_{HOLD}$ . When the precharge phase is complete, the  $V_{DD}/V_{SS}$  bias paths for the two nodes are disconnected and the paths between  $C_{HOLD}$  and the external sensor node is reconnected, at which time the acquisition phase of the CVD operation begins. During acquisition, a capacitive voltage divider is formed between the precharged  $C_{HOLD}$  and sensor nodes, which results in a final voltage level setting on  $C_{HOLD}$ , which is determined by the capacitances and precharge levels of the two nodes. After acquisition, the ADC converts the voltage level on  $C_{HOLD}$ . This process is then repeated with the selected precharge levels inverted for both the  $C_{HOLD}$  and the sensor nodes. The waveform for two CVD measurements, which is known as differential CVD measurement, is shown in the following figure.




Figure 43-8. Differential CVD Measurement Waveform

Note 1: External Capacitive Sensor voltage during the conversion phase may vary as per the configuration of the corresponding pin.

#### 43.5.9.2 Precharge Control

The precharge stage is the period of time that brings the external channel and internal Sample-and-Hold capacitor to known voltage levels. Precharge is enabled by writing a nonzero value to the ADPRE register. This stage is initiated when an ADC conversion begins, either from setting the GO bit, a Special Event Trigger, or a conversion restart from the computation functionality. If the ADPRE register is cleared when an ADC conversion begins, this stage is skipped.

During the precharge time,  $C_{HOLD}$  is disconnected from the outer portion of the sample path that leads to the external capacitive sensor and is connected to either  $V_{DD}$  or  $V_{SS}$ , depending on the value of the PPOL bit. At the same time, the port pin logic of the selected analog channel is overridden to drive a digital high or low out, in order to precharge the outer portion of the ADC's sample path, which includes the external sensor. The output polarity of this override is determined by the PPOL bit such that the external sensor cap is charged opposite that of the internal  $C_{HOLD}$  cap. The amount of time for precharge is controlled by the ADPRE register.



**Important:** The external charging overrides the TRIS/LAT/Guard outputs setting of the respective I/O pin. If there is a device attached to this pin, precharge should not be used.

## 43.5.9.3 Acquisition Control for CVD (ADPRE > 0)

The acquisition stage allows time for the voltage on the internal Sample-and-Hold capacitor to charge or discharge from the selected analog channel. This acquisition time is controlled by the ADACQ register. The acquisition stage begins when precharge stage ends.

At the start of the acquisition stage, the port pin logic of the selected analog channel is overridden to turn off the digital high/low output drivers so they do not affect the final result of the charge averaging. Also, the selected ADC

# ADC - Analog-to-Digital Converter with Com...

channel is connected to  $C_{HOLD}$ . This allows charge averaging to proceed between the precharged channel and the  $C_{HOLD}$  capacitor.



**Important:** When ADPRE > 0, setting ADACQ to '0' will set a maximum acquisition time. When precharge is disabled, setting ADACQ to '0' will disable hardware acquisition time control.

#### 43.5.9.4 Guard Ring Outputs

Figure 43-9 shows a typical guard ring circuit.  $C_{GUARD}$  represents the capacitance of the guard ring trace placed on the PCB. The user selects values for  $R_A$  and  $R_B$  that will create a voltage profile on  $C_{GUARD}$ , which will match the selected acquisition channel.


The purpose of the guard ring is to generate a signal in phase with the CVD sensing signal to minimize the effects of the parasitic capacitance on sensing electrodes. It also can be used as a mutual drive for mutual capacitive sensing. For more information about active guard and mutual drive, refer to the following Microchip application note, available on the corporate website (www.microchip.com):

AN1478, "mTouch<sup>TM</sup> Sensing Solution Acquisition Methods Capacitive Voltage Divider"

The ADC has two guard ring drive outputs, ADGRDA and ADGRDB. These outputs are routed through PPS controls to I/O pins. Refer to the "Peripheral Pin Select (PPS) Module" chapter for more details. The polarity of these outputs is controlled by the GPOL and IPEN bits.

At the start of the first precharge stage, both outputs are set to match the GPOL bit. Once the acquisition stage begins, ADGRDA changes polarity, while ADGRDB remains unchanged. When performing a double sample conversion, setting the IPEN bit causes both guard ring outputs to transition to the opposite polarity of GPOL at the start of the second precharge stage, and ADGRDA toggles again for the second acquisition. For more information on the timing of the guard ring output, refer to Figure 43-10.

Figure 43-9. Guard Ring Circuit






Figure 43-10. Differential CVD with Guard Ring Output Waveform

Note 1: External Capacitive Sensor voltage during the conversion phase may vary as per the configuration of the corresponding pin.

#### 43.5.9.5 Additional Sample-and-Hold Capacitance

Additional capacitance can be added in parallel with the internal Sample-and-Hold capacitor ( $C_{HOLD}$ ) by using the ADCAP register. This register selects a digitally programmable capacitance that is added to the ADC conversion bus, increasing the effective internal capacitance of the Sample-and-Hold capacitor in the ADC module. This is used to improve the match between internal and external capacitance for a better sensing performance. The additional capacitance does not affect analog performance of the ADC because it is not connected during conversion.

# 43.6 Channel Sequencer and Context

The channel sequencer automates context saving and channel sequencing. The channel sequencer reduces software overhead when the ADC is using multiple input channels by storing each channel's context in memory. When the sequencer is enabled, module hardware automatically transfers the active channel's context from memory into the associated ADC registers and performs the desired conversion.

#### 43.6.1 Channel Context

Channel context refers to the unique set of control, status and data register configurations that define the operation of the ADC for a specific type of conversion. For example, if the ADC is configured for Burst-Average mode, that configuration can be saved as a channel context. Up to four channel contexts can be configured for sequencing. Context information is stored in duplicated registers located in device memory and can only be accessed through the A/D Context Selection Register (ADCTX) or via Direct Memory Access (DMA).



Important: The ADCLK and ADACT registers are not included as part of a channel context.

The conversion clock rate selected by ADCLK and the auto-conversion trigger source selected by ADACT are used for all contexts. For example, if Context 1 enables the Timer1 overflow as the auto-conversion trigger source, the Timer1 overflow trigger will be used for all other contexts as well. If user software configures the auto-conversion trigger to use the Timer0 overflow as the trigger source for Context 2, Context 1 will be reconfigured in hardware to also use the Timer0 overflow as the trigger source.

The table below highlights the registers that are part of a context.

Table 43-4. ADC Context Registers

Register	Bit Pos.	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0
ADCON0 <sup>(1)</sup>	7:0	ON	CONT	CSEN	CS		FM		GO
ADCON1	7:0	PPOL	IPEN	GPOL					DSEN
ADCON2	7:0	PSIS		CRS[2:0]		ACLR		MD[2:0]	1
ADCON3	7:0			CALC[2:0]		SOI		TMD[2:0	)]
ADSTAT	7:0	AOV	UTHR	LTHR	MATH			STAT[2:0	0]
ADREF	7:0				NREF			PRE	F[1:0]
ADPCH	7:0					PCH[5	5:0]		
ADPRE	7:0				PRE[7	:0]			
ADFRE	15:8						PRE	[12:8]	
ADACQ	7:0	ADACQ[7:0]							
ADACQ	15:8						ADAC	Q[12:8]	
ADCAP	7:0					(	CAP[4:0]		
ADRPT	7:0				RPT[7	:0]			
ADCNT	7:0				CNT[7	:0]			
ADFLTR	7:0				FLTR[7	<b>7</b> :0]			
ADFLIK	15:8				FLTR[1	5:8]			
ADRES	7:0				RES[7	:0]			
ADINES	15:8		RES[15:8]		5:8]				
ADPREV	7:0				PREV[	7:0]			
ADFILEV	15:8				PREV[1	5:8]			

# ADC - Analog-to-Digital Converter with Com...

continued										
Register	Bit Pos.	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	
	7:0				ACC[7	:0]				
ADACC	15:8				ACC[1	5:8]				
	23:16							ACC	[17:16]	
ADSTPT	7:0		STPT[7:0]							
ADSTET	15:8	STPT[15:8]								
ADERR	7:0				ERR[7	:0]				
ADERK	15:8	ERR[15:8]								
ADLTH	7:0				LTH[7	:0]				
ADLIN	15:8	LTH[15:8]								
ADUTH	7:0				UTH[7	:0]				
ADUTH	15:8				UTH[1	5:8]				

#### Note:

The ADCON0 register is not included as part of a channel context with the exception of bit 6 (CONT).

The A/D Context Selection (ADCTX) register selects the context number that will be given read/write access. The A/D Context Display Select bit (CTXSW) is used to determine the read/write status of the A/D Channel Context Selection bits (CTX), which are used to determine the channel context number.

When CTXSW is set (CTXSW = 1), the CTX bits display the context number the sequencer is currently scanning, or the context number that was active when the sequencer stopped scanning due to a context threshold interrupt.



**Important:** When CTXSW is set, the CTX bits are read-only and should only be read while context sequencing is enabled (CSEN = 1).

When CTXSW is clear (CTXSW = 0), the CTX bits display the context number as selected by user software. Any context can be selected by writing the CTX bits with the desired context number.

#### 43.6.1.1 Channel Context Configuration

The following steps are used to configure channel context via the ADCTX register:

- 1. Write the desired context number into the CTX bits; hardware automatically clears CTXSW.
- 2. Configure all desired ADC registers (e.g., ADCON1, ADCON2, etc.).
- 3. Repeat steps 1 and 2 until all channel contexts have been configured.



**Remember:** The context number is always one number greater than the value written into the CTX bits. For example, when the CTX bits are written with zero (CTX = 0), Context 1 is in view.

Once the context number has been written into the CTX bits, the selected channel context is available for software access. After each ADC register is configured, the register value is copied into the associated context register.

Data can also be read from the ADC's data registers (ADFLTR, ADRES, etc.) using the same steps above. Rather than configuring the desired ADC registers in step 2, user software can instead read data from the desired data registers.



It is highly recommended to verify that the STAT bits of the ADSTAT register are clear (STAT = 0) before changing any context registers. Modifying context registers during an active conversion may lead to data corruption.

## 43.6.1.2 Channel Context Configuration Example

The code example below illustrates the configuration of four channel contexts.

## **Example 43-3. Configuring Channel Context**

```
void configADCContext(void)
    ADCTX = 0 \times 00;
                                                    // Select Context 1
    // Configure ADC registers for Context 1
    ADLTHL = 0x10;
                                                    // Lower threshold = 1000
    ADLTHH = 0x27;
    ADUTHL = 0xE8;
                                                    // Upper threshold = 10,000
    ADUTHH = 0 \times 03;
    ADSTPTL = 0 \times 00;
                                                    // Setpoint = 0
    ADSTPTH = 0 \times 00;
    ADACCU = 0 \times 00;
    ADRPT = 0 \times 10;
ADPCH = 0 \times 00;
                                                    // Accumulate 16 samples
                                                    // PCH ANA0;
    ADCON1 = 0 \times 00;
    ADCON2 = 0 \times 01;
                                                    // Accumulate mode
    ADCON3 = 0 \times 04;
    ADSTAT = 0x00;
    ADREF = 0 \times 00;
                                                    // ADNREF VSS; ADPREF VDD;
    ADCON0 = 0 \times 04;
                                                    // CONT = 0
    ADCTX = 0x01;
                                                    // Select Context 2
    // Configure ADC registers for Context 2
    ADLTHL = 0xF4;
                                                    // Lower threshold = 500
    ADLTHH = 0 \times 01;
    ADUTHL = 0 \times 88;
                                                    // Upper threshold = 5000
    ADUTHH = 0x13;
    ADSTPTL = 0 \times 00;
                                                    // Setpoint = 0
    ADSTPTH = 0 \times 00;
    ADACCU = 0 \times 00;
    ADRPT = 0x20;
                                                    // Accumulate 32 samples
    ADPCH = 0x01;
                                                    // PCH ANA1;
    ADCON1 = 0x00;
    ADCON2 = 0x52;
                                                    // Average mode; CRS = /32
    ADCON3 = 0 \times 04;
    ADSTAT = 0 \times 00;
    ADREF = 0 \times 00;
                                                    // ADNREF VSS; ADPREF VDD;
    ADCON0 = 0x04;
                                                    // CONT = 0
    ADCTX = 0x02;
                                                    // Select Context 3
    // Configure ADC registers for Context 3
    ADLTHL = 0xF4;
                                                    // Lower threshold = 500
    ADLTHH = 0 \times 01;
    ADUTHL = 0x88;
                                                    // Upper threshold = 5000
    ADUTHH = 0x13;
    ADSTPTL = 0 \times 00;
ADSTPTH = 0 \times 00;
                                                    // Setpoint = 0
    ADACCU = 0 \times 00;
    ADRPT = 0 \times 20;
ADPCH = 0 \times 02;
                                                    // Accumulate 32 samples
// PCH ANA2;
    ADCON1 = 0 \times 00;
    ADCON2 = 0x53;
                                                    // Burst Average mode; CRS = /32
    ADCON3 = 0 \times 04;
    ADSTAT = 0x00;
    ADREF = 0 \times 00;
                                                    // ADNREF VSS; ADPREF VDD;
    ADCON0 = 0 \times 04;
                                                     // CONT = 0
    ADCTX = 0x03;
                                                    // Select Context 4
    // Configure ADC registers for Context 4
    ADLTHL = 0 \times 00;
    ADLTHH = 0 \times 00;
    ADUTHL = 0 \times 00;
    ADUTHH = 0 \times 00;
```

```
ADSTPTL = 0x00;
ADSTPTH = 0 \times 00;
ADACCU = 0 \times 00;
ADRPT = 0 \times 04;
ADPCH = 0 \times 03;
                                              // PCH ANA3;
ADCON1 = 0 \times 00;
ADCON2 = 0x24;
                                              // LPF mode; CRS = 2
                                             // Context 4 interrupt always
ADCON3 = 0 \times 57;
ADSTAT = 0 \times 00:
ADREF = 0 \times 00;
                                             // ADNREF VSS; ADPREF VDD;
ADCON0 = 0x04;
                                              // CONT = 0
// Apply to all context
ADACT = 0 \times 00;
ADCLK = 0 \times 00;
                                              // No ACT
                                             // ADCS FOSC/2;
                                             // Enable ADC
ADCON0 = 0x84;
PIR2bits.ADCH1IF = 0;
                                             // Clear interrupt flags
PIR2bits.ADCH2IF = 0;
PIR2bits.ADCH3IF = 0;
PIR2bits.ADCH4IF = 0;
PIE2bits.ADCH1IE = 1;
                                            // Enable Threshold interrupts
PIE2bits.ADCH2IE = 1;
PIE2bits.ADCH3IE = 1;
PIE2bits.ADCH4IE = 1;
```

#### 43.6.2 Channel Sequencer

The channel sequencer automatically performs the operations defined by each channel context. The channel sequencer is enabled when the Context Scan Enable bit (CSEN) is set (CSEN = 1), and the scan sequence is executed when the GO bit is set by software or by the reception of an auto-conversion trigger.

The sequence includes all channel contexts that are enabled via the context's Channel Scan Enable bit (CHEN). A context channel is included in the scan sequence when the CHEN bit is set (CHEN = 1). If all context channels' CHEN bits are clear (CHEN = 0), the GO bit is immediately cleared and no conversions or interrupts will occur.

A sequence always begins with Context 1, as long as its CHEN bit is enabled. If Context 1's CONT bit is set (CONT = 1), the sequencer will scan Context 1 and continue scanning until the threshold test invokes the ADC Channel Threshold Interrupt flag (ADCHxIF). If the ADC Stop On Interrupt bit (SOI) is set (SOI = 1) and the channel threshold interrupt occurs, the scanner will proceed to check Context 1's ADC Scan Stop On Interrupt bit (SSI) to determine whether to proceed to the next channel context. If SSI is set (SSI = 1), the scanner will clear the GO bit and the scanner will stop. If the SSI bit is clear (SSI = 0), the scanner proceeds to the next channel context that has the CHEN bit set.

If Context 1's CONT bit is set, the SOI bit is clear (SOI = 0) and the scanner will repeatedly scan Context 1 until software clears the GO bit.



**Important:** If a context's CONT bit is set and both the SOI and SSI bits are clear, the scanner will repeatedly scan that context indefinitely without scanning any further channels.

If Context 1's CONT bit is clear (CONT = 0), the sequencer will scan Context 1, and when the conversion completes, the channel threshold test is performed. If ADCH1IF is set, the sequencer checks Context 1's SSI bit to determine whether to proceed to the next channel context. If SSI is set, the sequencer clears GO and the scanner stops. If the SSI bit is clear, the sequencer will proceed to the next channel that has the CHEN bit set.



**Important:** When the CONT bit is clear, the SOI bit is ignored.

The scan sequence ends when any context's channel threshold interrupt occurs and that context's SSI bit is set. If the sequencer has scanned all enabled channels and no interrupt occurs, or no context's SSI bit is set, the


sequencer will return to Context 1 (or the first enabled channel context) and repeat the scanning process until software clears the GO bit.



**Important:** The final channel in a sequence should set the Threshold Interrupt Mode Select bits (TMD) to "Interrupt regardless of the threshold test results" (TMD = 111) and set the SSI bit. These settings allow the scanner to stop after the scan sequence has completed.

The figure below illustrates the operation of the channel sequencer.

Figure 43-11. Channel Sequencer Operation



#### Notes:

- 1. If all channels are disabled (ADCSEL[1..4].CHEN = 0), the scanner stops, but the GO bit remains set. No interrupts will occur. If software relies on a hardware clear of GO to continue code execution, the program will stall indefinitely.
- 2. ADC computation modes (Average, Burst-Average, etc.) are included in the 'Perform ADC Operation' block.

## 43.6.2.1 DMA Access

The DMA can be used to access the context registers as an alternative to using the ADCTX register. The DMA allows the user to directly read and/or write to the context registers, which are not accessible through the File Select Registers (FSRs). The DMA may read/write a single register within a context, all the registers within a context or all contexts.

## 43.6.2.2 Channel Sequencer Configuration Examples

The following code examples illustrate the configuration of the channel sequencer. The first example uses software to set the GO bit and perform one complete sequence, while the second uses an auto-conversion trigger to perform sequences at a timed interval. Both examples scan Contexts 1, 2, and 4, while skipping Context 3.

```
Example 43-4. Software Sets GO
 void scanOnce(void)
      configScan124();
                                          // Configure sequencer
      ADCONObits.ON = 1;
                                           // Enable the ADC
      ADCONObits.GO = 1;
                                           // Software starts the sequencer
 void configScan124(void)
      configADCContext();
                                          // Configure channel contexts
      ADCSEL1.CHEN = 1;
                                          // Enable Context 1
     ADCSEL1.CHEN - 1;

ADCSEL1.SSI = 0;

ADCSEL2.CHEN = 1;

ADCSEL2.SSI = 0;

ADCSEL3.CHEN = 0;

ADCSEL3.SSI = 0;

ADCSEL4.CHEN = 0;

ADCSEL4.SSI = 1;
                                          // Don't stop on interrupt
                                          // Enable Context 2
// Don't stop on interrupt
                                         // Context 3 not included in scan
                                         // Don't stop on interrupt
// Enable Context 4
      ADCSEL4.SSI = 1;
                                          // Stop scan on last context
      ADCTX = 0x03;
                                          // Select Context 4
      ADCON3bits.TMD = 0b111;
ADCON0bits.CSEN = 1;
                                          // Interrupt regardless of test results
                                          // Enable the sequencer
```

# 43.7 Register Definitions: ADC Control

Long bit name prefixes for the ADC peripherals are shown in the following table. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 43-5. ADC Long bit name prefixes

Peripheral	Bit Name Prefix
ADC	AD

## 43.7.1 ADCON0

Name: ADCON0 Offset: 0x3F3

## ADC Control Register 0

Bit	7	6	5	4	3	2	1	0
	ON	CONT	CSEN	CS		FM		GO
Access	R/W	R/W	R/W	R/W		R/W		R/W/HC/HS
Reset	0	0	0	0		0		0

#### Bit 7 - ON ADC Enable

Value	Description
1	ADC is enabled
0	ADC is disabled

#### Bit 6 - CONT ADC Continuous Operation Enable

Value	Description
1	GO is retriggered upon completion of each conversion trigger until ADCHIF is set (if SOI is set) or until
	GO is cleared (regardless of the value of SOI)
0	ADC is cleared upon completion of each conversion trigger

#### Bit 5 - CSEN ADC Context Scan Enable

Value	Description
1	Automatic context scanning enabled
0	Automatic context scanning disabled

## Bit 4 - CS ADC Clock Selection

Value	Description
1	Clock supplied from ADCRC dedicated oscillator
0	Clock supplied by Fosc, divided according to ADCLK register

## Bit 2 - FM ADC results Format/alignment Selection

1	/alue	Description
-	L	ADRES and ADPREV data are right justified
(	)	ADRES and ADPREV data are left justified, zero-filled

## Bit 0 - GO ADC Conversion Status<sup>(1,2)</sup>

Value	Description				
1	ADC conversion cycle in progress. Setting this bit starts an ADC conversion cycle. The bit is cleared by				
	hardware as determined by the CONT bit				
0	ADC conversion completed/not in progress				

## Notes:

- 1. This bit requires ON bit to be set.
- If cleared by software while a conversion is in progress, the results of the conversion up to this point will be transferred to ADRES and the state machine will be reset, but the ADIF interrupt flag bit will not be set; filter and threshold operations will not be performed.

#### 43.7.2 ADCON1

Name: ADCON1 Offset: 0x3F4

ADC Control Register 1

Bit	7	6	5	4	3	2	1	0
	PPOL	IPEN	GPOL					DSEN
Access	R/W	R/W	R/W					R/W
Reset	0	0	0					0

# **Bit 7 – PPOL** Precharge Polarity Action During 1<sup>st</sup> Precharge Stage

Value	Condition	Description
Х	ADPRE = 0	Bit has no effect
1	ADPRE > 0	External analog I/O pin is connected to $V_{DD}$ Internal AD sampling capacitor ( $C_{HOLD}$ ) is connected to $V_{SS}$
0	ADPRE > 0	External analog I/O pin is connected to $V_{SS}$ Internal AD sampling capacitor ( $C_{HOLD}$ ) is connected to $V_{DD}$

#### Bit 6 - IPEN A/D Inverted Precharge Enable

Value	Condition	Description
Х	DSEN = 0	Bit has no effect
1	DSEN = 1	The precharge and guard signals in the second conversion cycle are the opposite polarity of the first cycle
0	DSEN = 1	Both Conversion cycles use the precharge and guards specified by PPOL and GPOL

#### Bit 5 - GPOL Guard Ring Polarity Selection

	zito oi					
Value	Description					
1	ADC guard Ring outputs start as digital high during Precharge stage					
0	ADC guard Ring outputs start as digital low during Precharge stage					

## Bit 0 - DSEN Double-Sample Enable

Value	Description					
1	Two conversions are processed as a pair. The selected computation is performed after every second					
	conversion.					
0	Selected computation is performed after every conversion					

DS40002259A-page 925 **Preliminary Datasheet** © 2020 Microchip Technology Inc.

## 43.7.3 ADCON2

Name: ADCON2 Offset: 0x3F5

# ADC Control Register 2

Bit	7	6	5	4	3	2	1	0
	PSIS		CRS[2:0]		ACLR		MD[2:0]	
Access	R/W	R/W	R/W	R/W	R/W/HC	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

#### Bit 7 - PSIS ADC Previous Sample Input Select

Value	Description
1	ADFLTR is transferred to ADPREV at the start of conversion
0	ADRES is transferred to ADPREV at the start of conversion

#### Bits 6:4 - CRS[2:0] ADC Accumulated Calculation Right Shift Select

Value	Condition	Description
1 to 6	MD = 'b100	Low-pass filter time constant is 2 <sup>CRS</sup> , filter gain is 1:1 <sup>(2)</sup>
1 to 6	MD = 'b011 to 'b001	The accumulated value is right-shifted by CRS (divided by 2 <sup>CRS</sup> )(1,2)
X	MD = 'b000	These bits are ignored

## Bit 3 - ACLR A/D Accumulator Clear Command<sup>(3)</sup>

Value	Description
1	Registers ADACC, ADCNT and the AOV bit are cleared
0	Clearing action is complete (or not started)

## Bits 2:0 - MD[2:0] ADC Operating Mode Selection<sup>(4)</sup>

Value	Description
111-101	Reserved
100	Low-Pass Filter mode
011	Burst Average mode
010	Average mode
001	Accumulate mode
000	Basic (Legacy) mode

# Notes:

- To correctly calculate an average, the number of samples (set in ADRPT) must be 2<sup>CRS</sup>.
- 2. CRS = 'b111 and 'b000 are reserved.
- 3. This bit is cleared by hardware when the accumulator operation is complete; depending on oscillator selections, the delay may be many instructions.
- 4. See the section for full mode descriptions.

## 43.7.4 ADCON3

Name: ADCON3 Offset: 0x3F6

ADC Control Register 3

Bit	7	6	5	4	3	2	1	0
			CALC[2:0]		SOI		TMD[2:0]	
Access		R/W	R/W	R/W	R/W/HC	R/W	R/W	R/W
Reset		0	0	0	0	0	0	0

Bits 6:4 - CALC[2:0] ADC Error Calculation Mode Select

## Table 43-6. ADC Error Calculation Mode

	AD			
CALC	DSEN = 0 Single-Sample Mode	DSEN = 1 CVD Double- Sample Mode <sup>(1)</sup>	Application	
111	Reserved	Reserved	Reserved	
110	Reserved	Reserved	Reserved	
101	ADFLTR-ADSTPT	ADFLTR-ADSTPT	Average/filtered value vs. setpoint	
100	ADPREV-ADFLTR	ADPREV-ADFLTR	First derivative of filtered value <sup>(3)</sup> (negative)	
011	Reserved	Reserved	Reserved	
010	ADRES-ADFLTR	(ADRES-ADPREV)-ADFLTR	Actual result vs. averaged/filtered value	
001	ADRES-ADSTPT	(ADRES-ADPREV)-ADSTPT	Actual result vs. setpoint	
000	ADRES-ADPREV	ADRES-ADPREV	First derivative of single measurement <sup>(2)</sup> Actual CVD result <sup>(2)</sup>	

#### Notes:

- 1. When DSEN = 1 and PSIS = 0, ADERR is computed only after every second sample.
- 2. When PSIS = 0.
- 3. When PSIS = 1.

## Bit 3 - SOI ADC Stop-on-Interrupt

Value	Condition	Description
X	CONT = 0	This bit is not used
1	CONT = 1	GO is cleared when the threshold conditions are met, otherwise the conversion is retriggered
0	CONT = 1	GO is not cleared by hardware, must be cleared by software to stop retriggers

#### Bits 2:0 - TMD[2:0] Threshold Interrupt Mode Select

Value	Description
111	Interrupt regardless of threshold test results
110	Interrupt if ADERR > ADUTH
101	Interrupt if ADERR ≤ ADUTH
100	Interrupt if ADERR < ADLTH or ADERR > ADUTH
011	Interrupt if ADERR > ADLTH and ADERR < ADUTH
010	Interrupt if ADERR ≥ ADLTH
001	Interrupt if ADERR < ADLTH
000	Never interrupt

## 43.7.5 ADSTAT

Name: ADSTAT Offset: 0x3F7

**ADC Status Register** 

Bit	7	6	5	4	3	2	1	0
	AOV	UTHR	LTHR	MATH		STAT[2:0]		
Access	R/C/HS/HC	R	R	R/W/HS		R	R	R
Reset	0	0	0	0		0	0	0

## Bit 7 - AOV ADC Accumulator Overflow

Value	Description
1	ADACC or ADFLTR or ADERR registers have overflowed
0	ADACC, ADFLTR and ADERR registers have not overflowed

#### Bit 6 - UTHR ADC Module Greater-than Upper Threshold Flag

Value	Description
1	ADERR > ADUTH
0	ADERR ≤ ADUTH

## Bit 5 - LTHR ADC Module Less-than Lower Threshold Flag

Value	Description
1	ADERR <adlth< th=""></adlth<>
0	ADERR≥ADLTH

#### Bit 4 - MATH ADC Module Computation Status

ADC Module Computation Status(1)

Value	Description
1	Registers ADACC, ADFLTR, ADUTH, ADLTH and the AOV bit are updating or have already updated
0	Associated registers/bits have not changed since this bit was last cleared

## Bits 2:0 - STAT[2:0] ADC Module Cycle Multi-Stage Status

Value	Description
111	ADC module is in 2 <sup>nd</sup> conversion stage
110	ADC module is in 2 <sup>nd</sup> acquisition stage
101	ADC module is in 2 <sup>nd</sup> precharge stage
100	ADC computation is suspended between 1st and 2nd sample; the computation results are incomplete and awaiting data from the 2nd sample <sup>(2,3)</sup>
011	ADC module is in 1st conversion stage
010	ADC module is in 1st acquisition stage
001	ADC module is in 1st precharge stage
000	ADC module is not converting


#### Notes:

- 1. MATH bit cannot be cleared by software while STAT = 'b100.
- 2. If ADC clock source is ADCRC, and  $F_{OSC}$  < ADCRC, the indicated status may not be valid.
- 3. STAT = b100 appears between the two triggers when DSEN = 1 and CONT = 0.

## 43.7.6 ADCLK

Name: ADCLK Offset: 0x3FA

ADC Clock divider Register



Bits 5:0 - CS[5:0] ADC Clock divider Select


Value	Description
n	ADC Clock frequency = F <sub>OSC</sub> /(2*(n+1))

**Note:** ADC Clock divider is only available if  $F_{OSC}$  is selected as the ADC clock source (CS = 0).

## 43.7.7 ADREF

Name: ADREF Offset: 0x3F8

ADC Reference Selection Register



Bit 4 - NREF ADC Negative Voltage Reference Selection

Value	Description
1	V <sub>REF</sub> - is connected to external V <sub>REF</sub> -
0	V <sub>REF</sub> - is connected to AV <sub>SS</sub>


# Bits 1:0 - PREF[1:0] ADC Positive Voltage Reference Selection

Value	Description
11	V <sub>REF</sub> + is connected to internal Fixed Voltage Reference (FVR) module
10	V <sub>REF</sub> + is connected to external V <sub>REF</sub> +
01	Reserved
00	V <sub>REF</sub> + is connected to V <sub>DD</sub>

## 43.7.8 ADPCH

Name: ADPCH Offset: 0x3EC

ADC Positive Channel Selection Register



Bits 5:0 - PCH[5:0] ADC Positive Input Channel Selection

## Table 43-7. ADC Positive Input Channel Selections

PCH	ADC Positive Channel Input
111111	Fixed Voltage Reference (FVR) Buffer 2 <sup>(1)</sup>
111110	Fixed Voltage Reference (FVR) Buffer 1 <sup>(1)</sup>
111101	DAC1 output <sup>(2)</sup>
111100	Temperature Indicator <sup>(3)</sup>
111011	V <sub>SS</sub> (Analog Ground)
110000-111010	Reserved. No channel connected.
101111	RF7/ANF7 <sup>(5)</sup>
101110	RF6/ANF6 <sup>(5)</sup>
101101	RF5/ANF5 <sup>(5)</sup>
101100	RF4/ANF4 <sup>(5)</sup>
101011	RF3/ANF3 <sup>(5)</sup>
101010	RF2/ANF2 <sup>(5)</sup>
101001	RF1/ANF1 <sup>(5)</sup>
101000	RF0/ANF0 <sup>(5)</sup>
100011-100111	Reserved. No channel connected.
100010	RE2/ANE2 <sup>(4)</sup>
100001	RE1/ANE1 <sup>(4)</sup>
100000	RE0/ANE0 <sup>(4)</sup>
011111	RD7/AND7 <sup>(4)</sup>
011110	RD6/AND6 <sup>(4)</sup>
011101	RD5/AND5 <sup>(4)</sup>
011100	RD4/AND4 <sup>(4)</sup>
011011	RD3/AND3 <sup>(4)</sup>
011010	RD2/AND2 <sup>(4)</sup>
011001	RD1/AND1 <sup>(4)</sup>
011000	RD0/AND0 <sup>(4)</sup>
010111	RC7/ANC7
010110	RC6/ANC6
010101	RC5/ANC5
010100	RC4/ANC4
010011	RC3/ANC3
010010	RC2/ANC2
010001	RC1/ANC1
010000	RC0/ANC0

# ADC - Analog-to-Digital Converter with Com...

continued					
PCH	ADC Positive Channel Input				
001111	RB7/ANB7				
001110	RB6/ANB6				
001101	RB5/ANB5				
001100	RB4/ANB4				
001011	RB3/ANB3				
001010	RB2/ANB2				
001001	RB1/ANB1				
001000	RB0/ANB0				
000111	RA7/ANA7				
000110	RA6/ANA6				
000101	RA5/ANA5				
000100	RA4/ANA4				
000011	RA3/ANA3				
000010	RA2/ANA2				
000001	RA1/ANA1				
000000	RA0/ANA0				


## Notes:

- 1. Refer to the "Fixed Voltage Reference Module" chapter for more details.
- 2. Refer to the "Digital-to-Analog Converter Module" chapter for more details.
- 3. Refer to the "Temperature Indicator Module" chapter for more details.
- 4. 40/44/48-pin devices only.
- 5. 48-pin devices only.

## 43.7.9 ADPRE

Name: ADPRE Ox3F1

ADC Precharge Time Control Register



Bits 12:0 - PRE[12:0] Precharge Time Select

Table 43-8. Precharge Time

ADPRE	Precharge Time			
ADFRE	CS != ADCRC	CS = ADCRC		
1 1111 1111 1111	8191 clocks of F <sub>OSC</sub>	8191 clocks of ADCRC		
1 1111 1111 1110	8190 clocks of F <sub>OSC</sub>	8190 clocks of ADCRC		
1 1111 1111 1101	8189 clocks of F <sub>OSC</sub>	8189 clocks of ADCRC		
0 0000 0000 0010	2 clocks of F <sub>OSC</sub>	2 clocks of ADCRC		
0 0000 0000 0001	1 clocks of F <sub>OSC</sub>	1 clocks of ADCRC		
0 0000 0000 0000	Not included in the data conversion cycle			

Notes: The individual bytes in this multi-byte register can be accessed with the following register names:

- ADPREH: Accesses the high byte ADPRE[12:8]
- ADPREL: Accesses the low byte ADPRE[7:0]

## 43.7.10 ADACQ

Name: ADACQ Offset: 0x3EE

ADC Acquisition Time Control Register

Bit	15	14	13	12	11	10	9	8	
					ACQ[12:8]				
Access				R/W	R/W	R/W	R/W	R/W	
Reset				0	0	0	0	0	
Bit	7	6	5	4	3	2	1	0	
	ACQ[7:0]								
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	0	0	0	0	0	0	0	0	

Bits 12:0 - ACQ[12:0] Acquisition (charge share time) Select

Table 43-9. Acquisition Time

ADACQ	Acquisition Time					
ADACQ	CS != ADCRC	CS = ADCRC				
1 1111 1111 1111	8191 clocks of F <sub>OSC</sub>	8191 clocks of ADCRC				
1 1111 1111 1110	8190 clocks of F <sub>OSC</sub>	8190 clocks of ADCRC				
1 1111 1111 1101	8189 clocks of F <sub>OSC</sub>	8189 clocks of ADCRC				
0 0000 0000 0010	2 clocks of F <sub>OSC</sub>	2 clocks of ADCRC				
0 0000 0000 0001	1 clocks of F <sub>OSC</sub>	1 clocks of ADCRC				
0 0000 0000 0000	Not included in the	data conversion cycle <sup>(1)</sup>				
Note:						
1. If ADPRE is not equal to '0', then ACQ = 0 means Acquisition Time is 8192 clocks of F <sub>OSC</sub> or ADCRC.						

Notes: The individual bytes in this multi-byte register can be accessed with the following register names:


- ADACQH: Accesses the high byte ADACQ[12:8]
- ADACQL: Accesses the low byte ADACQ[7:0]

# ADC - Analog-to-Digital Converter with Com...

## 43.7.11 ADCAP

Name: ADCAP Offset: 0x3F0

ADC Additional Sample Capacitor Selection Register



Bits 4:0 - CAP[4:0] ADC Additional Sample Capacitor Selection

Value	Description
1 to 31	Number of pF in the additional capacitance
0	No additional capacitance

# 43.7.12 ADRPT

Name: ADRPT Offset: 0x3E7

ADC Repeat Setting Register

Bit	7	6	5	4	3	2	1	0		
	RPT[7:0]									
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		

Bits 7:0 - RPT[7:0] ADC Repeat Threshold

## 43.7.13 ADCNT

Name: **ADCNT** Offset: 0x3E6

ADC Repeat Counter Register

Bit	7	6	5	4	3	2	1	0
				CNT	[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - CNT[7:0] ADC Repeat Count

#### 43.7.14 ADFLTR

Name: ADFLTR Offset: 0x3E1

**ADC Filter Register** 

Bit	15	14	13	12	11	10	9	8
				FLTR	[15:8]			
Access	R	R	R	R	R	R	R	R
Reset	x	X	X	X	X	X	X	X
Bit	7	6	5	4	3	2	1	0
				FLTF	R[7:0]			
Access	R	R	R	R	R	R	R	R
Reset	X	X	X	X	X	X	X	X

Bits 15:0 - FLTR[15:0] ADC Filter Output - Signed 2's complement

In Accumulate, Average, and Burst Average mode, this is equal to ACC right shifted by the CRS bits. In LPF mode, this is the output of the Low-Pass Filter.

- ADFLTRH: Accesses the high byte ADFLTR[15:8]
- ADFLTRL: Accesses the low byte ADFLTR[7:0]

#### 43.7.15 ADRES

Name: ADRES Offset: 0x3EA

ADC Result Register

Bit	15	14	13	12	11	10	9	8	
		RES[15:8]							
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	0	0	0	0	0	0	0	0	
Bit	7	6	5	4	3	2	1	0	
				RES	[7:0]				
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	0	0	0	0	0	0	0	0	

Bits 15:0 - RES[15:0] ADC Sample Result

- ADRESH: Accesses the high byte ADRES[15:18]
- ADRESL: Accesses the low byte ADRES[7:0]

#### 43.7.16 ADPREV

Name: ADPREV Offset: 0x3E8

## ADC Previous Result Register

Bit	15	14	13	12	11	10	9	8
				PREV	/[15:8]			
Access	R	R	R	R	R	R	R	R
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
				PRE'	V[7:0]			
Access	R	R	R	R	R	R	R	R
Reset	0	0	0	0	0	0	0	0

#### Bits 15:0 - PREV[15:0] Previous ADC Result

Va	lue	Condition	Description
n		PSIS = 1	n = ADFLTR value at the start of current ADC conversion
n		PSIS = 0	n = ADRES at the start of current ADC conversion <sup>(1)</sup>

#### Notes:

- 1. If PSIS = 0, ADPREV is formatted the same way as ADRES is, depending on the FM bit.
- 2. The individual bytes in this multi-byte register can be accessed with the following register names:
  - ADPREVH: Accesses ADPREV[15:8]
  - ADPREVL: Accesses ADPREV[7:0]

#### 43.7.17 ADACC

Name: ADACC Offset: 0x3E3



**Important:** This register contains signed 2's complement accumulator value and the upper unused bits contain copies of the sign bit.

Bit	23	22	21	20	19	18	17	16
							ACC[	17:16]
Access		•	•				R/W	R/W
Reset							X	X
Bit	15	14	13	12	11	10	9	8
				ACC	[15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	x	X	X	X	X	X	X	X
Bit	7	6	5	4	3	2	1	0
	ACC[7:0]							
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	x	X	x	x	X	X	X	x

Bits 17:0 - ACC[17:0] ADC Accumulator - Signed 2's complement

#### Notes:

- 1. This register can only be written when GO = 0.
- 2. The individual bytes in this multibyte register can be accessed with the following register names:
  - ADACCU: Accesses the upper byte ADACC[17:16]
  - ADACCH: Accesses the high byte ADACC[15:8]
  - ADACCL: Accesses the low byte ADACC[7:0]

#### 43.7.18 ADSTPT

Name: ADSTPT Offset: 0x3DF

**ADC Threshold Setpoint Register** 

Depending on CALC, may be used to determine ADERR.

Bit	15	14	13	12	11	10	9	8	
		STPT[15:8]							
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	0	0	0	0	0	0	0	0	
Bit	7	6	5	4	3	2	1	0	
	STPT[7:0]								
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	0	0	0	0	0	0	0	0	

Bits 15:0 - STPT[15:0] ADC Threshold Setpoint - Signed 2's complement

- ADSTPTH: Accesses the high byte ADSTPT[15:8]
- ADSTPTH: Accesses the low byte ADSTPT[7:0]

#### 43.7.19 ADERR

Name: ADERR Offset: 0x3DD

ADC Setpoint Error Register

ADC Setpoint Error calculation is determined by the CALC bits.

Bit	15	14	13	12	11	10	9	8
				ERR	[15:8]			
Access	R	R	R	R	R	R	R	R
Reset	X	X	X	x	X	X	x	X
Bit	7	6	5	4	3	2	1	0
				ERR	R[7:0]			
Access	R	R	R	R	R	R	R	R
Reset	X	X	X	X	X	X	X	X

Bits 15:0 - ERR[15:0] ADC Setpoint Error - Signed 2's complement

- ADERRH: Accesses the high byte ADERR[15:8]
- ADERRL: Accesses the low byte ADERR[7:0]

#### 43.7.20 ADLTH

Name: ADLTH Offset: 0x3D9

#### ADC Lower Threshold Register

ADLTH and ADUTH are compared with ADERR to set the UTHR and LTHR bits. Depending on the setting of TMD, an interrupt may be triggered by the results of this comparison.

Bit	15	14	13	12	11	10	9	8
				LTH[	15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
	LTH[7:0]							
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 15:0 - LTH[15:0] ADC Lower Threshold - Signed 2's complement

- ADLTHH: Accesses the high byte ADLTH[15:8]
- ADLTHL: Accesses the low byte ADLTH[7:0]

## 43.7.21 ADUTH

Name: ADUTH Offset: 0x3DB

#### ADC Upper Threshold Register

ADLTH and ADUTH are compared with ADERR to set the UTHR and LTHR bits. Depending on the setting of TMD, an interrupt may be triggered by the results of this comparison.

Bit	15	14	13	12	11	10	9	8
	UTH[15:8]							
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
				UTH	[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0


Bits 15:0 - UTH[15:0] ADC Upper Threshold - Signed 2's complement

- ADUTHH: Accesses the high byte ADUTH[15:8]
- ADUTHL: Accesses the low byte ADUTH[7:0]

#### 43.7.22 ADACT

Name: ADACT Offset: 0x3F9

ADC Auto Conversion Trigger Source Selection Register



Bits 5:0 – ACT[5:0] Auto-Conversion Trigger Select

## Table 43-10. ADC Auto-Conversion Trigger Sources

ACT	Auto-conversioin Trigger Source
111111	Software write to ADPCH
111110	Software read of ADRESH
111101	Software read of ADERRH
111100 to 101000	Reserved
100111	CLC8_OUT
100110	CLC7_OUT
100101	CLC6_OUT
100100	CLC5_OUT
100011	CLC4_OUT
100010	CLC3_OUT
100001	CLC2_OUT
100000	CLC1_OUT
011111	Interrupt-on-change Interrupt Flag
011110	CMP2_OUT
011101	CMP1_OUT
011100	NCO3_OUT
011011	NCO2_OUT
011010	NCO1_OUT
011001	PWM4S1P2_OUT
011000	PWM4S1P1_OUT
010111	PWM3S1P2_OUT
010110	PWM3S1P1_OUT
010101	PWM2S1P2_OUT
010100	PWM2S1P1_OUT
010011	PWM1S1P2_OUT
010010	PWM1S1P1_OUT
010001	CCP3_trigger
010000	CCP2_trigger
001111	CCP1_trigger
001110	SMT1_overflow
001101-001011	Reserved
001010	TU16B_out
001001	TU16A_out
001000	TMR6_postscaled

# PIC18F26/46/56Q84

# ADC - Analog-to-Digital Converter with Com...

continued								
ACT	Auto-conversioin Trigger Source							
000111	TMR5_overflow							
000110	TMR4_postscaled							
000101	TMR3_overflow							
000100	TMR2_postscaled							
000011	TMR1_overflow							
000010	TMR0_overflow							
000001	Pin selected by ADACTPPS							
000000	External Trigger Disabled							

# ADC - Analog-to-Digital Converter with Com...

#### 43.7.23 ADCP

Name: ADCP Offset: 0x3D8

ADC Charge Pump Control Register



# Bit 7 - CPON Charge Pump On Control

Value	Description
1	Charge Pump On when requested by the ADC
0	Charge Pump Off

## Bit 0 - CPRDY Charge Pump Ready Status

Va	alue	Description
1		Charge Pump is ready
0		Charge Pump is not ready (or never started)

#### 43.7.24 ADCTX

Name: ADCTX Offset: 0x3FB

**ADC Context Selection Register** 



#### Bit 7 - CTXSW Context Display Select

Value	Description
1	The scanner's current context number is displayed in the CTX bits; the CTX bits are read-only <sup>(2)</sup>
0	The user's current context number is displayed in the CTX bits; the CTX bits are read/write

#### Bits 1:0 - CTX[1:0] Channel Context Selection

Value	Condition	Description
n	CTXSW = 1	Scanner's current channel context number
n	CTXSW = 0	User's current channel context number

#### Notes:

- 1. The context number is always one number greater than the value written into the CTX bits. For example, when the CTX bits are written with zero (CTX = 0), Context 1 is in view.
- 2. When CTXSW is set, the CTX bits are read-only and should only be read while context sequencing is enabled (CSEN = 1).

#### 43.7.25 ADCSELx

Name: ADCSELx

Offset: 0x3FC,0x3FD,0x3FE,0x3FF

ADC Channel Sequence Control Register



## Bit 7 - CHEN ADC Channel Scan Enable

Value	Description
1	Channel Context 'x' is included in the scan sequence.
0	Channel Context 'x' is not included in the scan sequence.

#### Bit 6 - SSI ADC Stop Scan on Interrupt

Value	Description				
1	Scan sequence stops if the ADCHxIF (threshold interrupt) is set (ADCHxIF = 1). If ADCHxIF did not				
	occur, scanner continues to next enabled context.				
0	Scan sequence continues to next enabled context once current context scan completes.				

# 43.8 Register Summary - ADC

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x03D7										
0x03D8	ADCP	7:0	CPON							CPRDY
0x03D9	ADLTH	7:0					[7:0]			
		15:8					[15:8]			
0x03DB	ADUTH	7:0					1[7:0]			
		15:8					[15:8]			
0x03DD	ADERR	7:0					R[7:0]			
		15:8					[15:8]			
0x03DF	ADSTPT	7:0					T[7:0]			
		15:8					[15:8]			
0x03E1	ADFLTR	7:0					R[7:0]			
		15:8					[15:8]			
		7:0					[7:0]			
0x03E3	ADACC	15:8		1		ACC	[15:8]			
		23:16							ACC	[17:16]
0x03E6	ADCNT	7:0					[7:0]			
0x03E7	ADRPT	7:0					[7:0]			
0x03E8	ADPREV	7:0					V[7:0]			
		15:8					/[15:8]			
0x03EA	ADRES	7:0		RES[7:0]						
		15:8				RES	[15:8]			
0x03EC	ADPCH	7:0					PCH	H[5:0]		
0x03ED	Reserved									
0x03EE	ADACQ	7:0				ACC	Q[7:0]			
		15:8						ACQ[12:8]		
0x03F0	ADCAP	7:0						CAP[4:0]		
0x03F1	ADPRE	7:0				PRE	[7:0]			
		15:8						PRE[12:8]		
0x03F3	ADCON0	7:0	ON	CONT	CSEN	CS		FM		GO
0x03F4	ADCON1	7:0	PPOL	IPEN	GPOL					DSEN
0x03F5	ADCON2	7:0	PSIS		CRS[2:0]		ACLR		MD[2:0]	
0x03F6	ADCON3	7:0			CALC[2:0]		SOI		TMD[2:0]	
0x03F7	ADSTAT	7:0	AOV	UTHR	LTHR	MATH			STAT[2:0]	
0x03F8	ADREF	7:0				NREF			PRE	F[1:0]
0x03F9	ADACT	7:0						Γ[5:0]		
0x03FA	ADCLK	7:0					CS	[5:0]		
0x03FB	ADCTX	7:0	CTXSW						CTX	K[1:0]
0x03FC	ADCSEL1	7:0	CHEN	SSI						
0x03FD	ADCSEL2	7:0	CHEN	SSI						
0x03FE	ADCSEL3	7:0	CHEN	SSI						
0x03FF	ADCSEL4	7:0	CHEN	SSI						

# 44. DAC - Digital-to-Analog Converter Module


The Digital-to-Analog Converter (DAC) supplies a variable voltage reference, ratiometric with the input source, with programmable selectable output levels.

The positive and negative input references (Vsource+and Vsource-) can each be selected from several sources.

The output of the DAC (DACx\_output) can be selected as a reference voltage to several other peripherals or routed to output pins.

The Digital-to-Analog Converter (DAC) is enabled by setting the EN bit.

Figure 44-1. Digital-to-Analog Converter Block Diagram



Note 1: The output enable bits are configured so that they act as a "one-hot" system, meaning only one DAC output can be enabled at a time.

# 44.1 Output Voltage Selection

The DAC has 2<sup>n</sup> voltage level ranges, where n is the number of bits in DACR. Each level is determined by the DACxR bits. The DAC output voltage can be determined by using Equation 44-1.

#### **Equation 44-1. DAC Output Equation**

$$DACx\_output = \left( \left( V_{REF\,+} - V_{REF\,-} \right) \times \frac{DACR}{2^n} \right) + V_{REF\,-}$$

# 44.2 Ratiometric Output Level

The DAC output value is derived using a resistor ladder with each end of the ladder tied to a positive and negative voltage reference input source. If the voltage of either input source fluctuates, a similar fluctuation will result in the DAC output value.

The value of the individual resistors within the ladder can be found in the "Electrical Specifications" chapter for each respective device.

## 44.3 Operation During Sleep

When the device wakes from Sleep through an interrupt or a WWDT Time-out Reset, the contents of the DACXCON and DACXDATL registers are not affected. To minimize current consumption in Sleep mode, the voltage reference should be disabled.

#### 44.4 Effects of a Reset

A device Reset affects the following:

- · The DAC module is disabled
- The DAC output voltage is removed from the DACxOUTn pin(s)
- · The DACxR bits are cleared

## 44.5 Register Definitions: DAC Control

Long bit name prefixes for the DAC are shown in the table below. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 44-1. DAC Long Bit Name Prefixes

Peripheral	Bit Name Prefix
DAC1	DAC1

#### 44.5.1 DACxCON

Name: DACxCON Offset: 0x7F

Digital-to-Analog Converter Control Register

Bit	7	6	5	4	3	2	1	0
	EN		OE	1:0]	PSS	[1:0]		NSS
Access	R/W		R/W	R/W	R/W	R/W		R/W
Reset	0		0	0	0	0		0

#### Bit 7 - EN DAC Enable

Value	Description
1	DAC is enabled
0	DAC is disabled

#### Bits 5:4 - OE[1:0] DAC Output Enable

OE	DAC Outputs
11	DACxOUT is disabled
10	DACxOUT is enabled on pin RA2 only
01	DACxOUT is enabled on pin RB7 only
00	DACxOUT is disabled

## Bits 3:2 - PSS[1:0] DAC Positive Reference Selection

PSS	DAC Positive Reference
11	Reserved, do not use
10	FVR Buffer 2
01	V <sub>REF</sub> +
00	$V_{DD}$

# Bit 0 - NSS DAC Negative Reference Selection

NSS	DAC Negative Reference
1	V <sub>REF</sub> -
0	$V_{SS}$

#### 44.5.2 DACxDATL

Name: DACxDATL Offset: 0x7D

Digital-to-Analog Converter Data Register

Bit	7	6	5	4	3	2	1	0
				DACx	R[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - DACxR[7:0] Data Input Bits for DAC Value

# 44.6 Register Summary - DAC

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x7C										
0x7D	DAC1DATL	7:0		DAC1R[7:0]						
0x7E	Reserved									
0x7F	DAC1CON	7:0	EN		OE	[1:0]	PSS	[1:0]		NSS

# 45. CMP - Comparator Module

Comparators are used to interface analog circuits to a digital circuit by comparing two analog voltages and providing a digital indication of their relative magnitudes. Comparators are very useful mixed signal building blocks because they provide analog functionality independent of program execution.


The analog comparator module includes the following features:

- · Programmable input selection
- · Programmable output polarity
- · Rising/falling output edge interrupts
- · Wake-up from Sleep
- · Selectable voltage reference
- · ADC auto-trigger
- Inter-connections with other available modules (e.g., timer clocks)

# 45.1 Comparator Overview

A single comparator is shown in Figure 45-1 along with the relationship between the analog input levels and the digital output. When the analog voltage at  $V_{IN}$ + is less than the analog voltage at  $V_{IN}$ -, the output of the comparator is a digital low level. When the analog voltage at  $V_{IN}$ + is greater than the analog voltage at  $V_{IN}$ -, the output of the comparator is a digital high level.


Figure 45-1. Single Comparator



#### Note:

1. The black areas of the output of the comparator represent the uncertainty due to input offsets and response time.

Figure 45-2. Comparator Module Simplified Block Diagram



Note 1: When EN = 0, all multiplexer inputs are disconnected and the Comparator will produce a '0' at the output.

# 45.2 Comparator Control

Each comparator has two control registers: CMxCON0 and CMxCON1.

The CMxCON0 register contains Control and Status bits for the following:

- Enable
- Output
- Output Polarity
- Hysteresis Enable
- · Timer1 Output Synchronization

The CMxCON1 register contains Control bits for the following:

Interrupt on Positive/Negative Edge Enables

The CMxPCH and CMxNCH registers are used to select the positive and negative input channels, respectively.

#### 45.2.1 Comparator Enable

Setting the EN bit enables the comparator for operation. Clearing the EN bit disables the comparator, resulting in minimum current consumption.

#### 45.2.2 Comparator Output

The output of the comparator can be monitored in two different registers. Each output can be read individually by reading the OUT bit. Outputs of all the comparators can be collectively accessed by reading the CMOUT register.

The comparator output can also be routed to an external pin through the RxyPPS register. Refer to the "PPS - Peripheral Pin Select Module" chapter for more details. The corresponding TRIS bit must be clear to enable the pin as an output.



**Important:** The internal output of the comparator is latched with each instruction cycle. Unless otherwise specified, external outputs are not latched.

#### 45.2.3 Comparator Output Polarity

Inverting the output of the comparator is functionally equivalent to swapping the comparator inputs. The polarity of the comparator output can be inverted by setting the POL bit. Clearing the POL bit results in a non-inverted output. Table 45-1 shows the output state versus input conditions, including polarity control.

Table 45-1. COMPARATOR OUTPUT STATE VS. INPUT CONDITIONS

Input Condition	POL	OUT
CxVn > CxVp	0	0
CxVn < CxVp	0	1
CxVn > CxVp	1	1
CxVn < CxVp	1	0

# 45.3 Comparator Output Synchronization

The output from a comparator can be synchronized with Timer1 by setting the SYNC bit.

Once enabled, the comparator output is latched on the falling edge of the Timer1 source clock. If a prescaler is used with Timer1, the comparator output is latched after the prescaling function. To prevent a race condition, the comparator output is latched on the falling edge of the Timer1 clock source and Timer1 increments on the rising edge of its clock source. A simplified block diagram of the comparator module is shown in Figure 45-2. Refer to the "TMR1 - Timer1 Module with Gate Control" chapter for more details.

# 45.4 Comparator Hysteresis

A selectable amount of separation voltage can be added to the input pins of each comparator to provide a hysteresis function to the overall operation. Hysteresis is enabled by setting the HYS bit.

See Comparator Specifications for more information.

## 45.5 Comparator Interrupt

An interrupt can be generated for every rising or falling edge of the comparator output.

When either edge detector is triggered and its associated enable bit is set (INTP and/or INTN bits), the Corresponding Interrupt Flag bit (CxIF bit of the respective PIR register) will be set.

To enable the interrupt, the following bits must be set:

- EN bit
- INTP bit (for a rising edge detection)
- · INTN bit (for a falling edge detection)
- · CxIE bit of the respective PIE register
- GIE bit of the INTCON0 register

The associated interrupt flag bit, CxIF bit of the respective PIR register, must be cleared in software to successfully detect another edge.



**Important:** Although a comparator is disabled, an interrupt will be generated by changing the output polarity with the POL bit.

## 45.6 Comparator Positive Input Selection

Configuring the PCH bits direct an internal voltage reference or an analog pin to the non-inverting input of the comparator.

Any time the comparator is disabled (EN = 0), all comparator inputs are disabled.

## 45.7 Comparator Negative Input Selection

The NCH bits direct an analog input pin, internal reference voltage or analog ground to the inverting input of the comparator.



**Important:** To use CxINy+ and CxINy- pins as analog input, the appropriate bits must be set in the ANSEL register and the corresponding TRIS bits must also be set to disable the output drivers.

# 45.8 Comparator Response Time

The comparator output is indeterminate for a period of time after the change of an input source or the selection of a new reference voltage. This period is referred to as the response time. The response time of the comparator differs from the settling time of the voltage reference. Therefore, both of these times must be considered when determining the total response time to a comparator input change. See the Comparator and Voltage Reference Specifications in Comparator Specifications and Fixed Voltage Reference (FVR) Specifications for more details.

## 45.9 Analog Input Connection Considerations


A simplified circuit for an analog input is shown in Figure 45-3. Since the analog input pins share their connection with a digital input, they have reverse biased ESD protection diodes to  $V_{DD}$  and  $V_{SS}$ . The analog input, therefore, must be between  $V_{SS}$  and  $V_{DD}$ . If the input voltage deviates from this range by more than 0.6V in either direction, one of the diodes is forward biased and abnormal behavior may occur.

A maximum source impedance of 10 k $\Omega$  is recommended for the analog sources. Also, any external component connected to an analog input pin, such as a capacitor or a Zener diode, should have very little leakage current to minimize corrupting the result.

#### Notes:

- 1. When reading a PORT register, all pins configured as analog inputs will read as a '0'. Pins configured as digital inputs will convert as an analog input, according to the input specification.
- Analog levels on any pin defined as a digital input, may cause the input buffer to consume more current than is specified.

Figure 45-3. Analog Input Model



Legend: CPIN = Input Capacitance

ILEAKAGE = Leakage Current at the pin due to various junctions

RIC = Interconnect Resistance
RS = Source Impedance
VA = Analog Voltage
VT = Diode Forward Voltage

#### Note:

1. See Electrical Specification chapter.

# 45.10 Operation in Sleep Mode

The comparator module can operate during Sleep. A comparator interrupt will wake the device from Sleep. The CxIE bits of the respective PIE register must be set to enable comparator interrupts.

The comparator clock source is based on the Timer1 clock source. If the Timer1 clock source is either the system clock ( $F_{OSC}$ ) or the instruction clock ( $F_{OSC}$ /4), Timer1 will not operate during Sleep, and synchronized comparator outputs will not operate.

## 45.11 ADC Auto-Trigger Source

The output of the comparator module can be used to trigger an ADC conversion. When the ADACT register is set to trigger on a comparator output, an ADC conversion will trigger when the comparator output goes high.

#### 45.12 Register Definitions: Comparator Control

Long bit name prefixes for the comparator peripherals are shown in the table below. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 45-2. Comparator Long bit name prefixes

Peripheral	Bit Name Prefix
C1	C1
C2	C2

#### 45.12.1 CMxCON0

**Name:** CMxCON0 **Offset:** 0x070,0x074

Comparator Control Register 0

Bit	7	6	5	4	3	2	1	0
	EN	OUT		POL			HYS	SYNC
Access	R/W	R		R/W			R/W	R/W
Reset	0	0		0			0	0

### Bit 7 - EN Comparator Enable

Value	Description
1	Comparator is enabled
0	Comparator is disabled and consumes no active power

#### Bit 6 - OUT Comparator Output

Value	Condition	Description
1	If POL = 0 (non-inverted polarity):	CxVP > CxVN
0	If POL = 0 (non-inverted polarity):	CxVP < CxVN
1	If POL = 1 (inverted polarity):	CxVP < CxVN
0	If POL = 1 (inverted polarity):	CxVP > CxVN

## Bit 4 - POL Comparator Output Polarity Select

Value	Description
1	Comparator output is inverted
0	Comparator output is not inverted

#### Bit 1 - HYS Comparator Hysteresis Enable

Value	Description
1	Comparator hysteresis enabled
0	Comparator hysteresis disabled

## Bit 0 - SYNC Comparator Output Synchronous Mode

Value	Description
1	Comparator output to Timer1 and I/O pin is synchronous to changes on Timer1 clock source. Output
	updated on the falling edge of Timer1 clock source.
0	Comparator output to Timer1 and I/O pin is asynchronous

## 45.12.2 CMxCON1

Name: CMxCON1 Offset: 0x071,0x075

Comparator Control Register 1

Bit	7	6	5	4	3	2	1	0
							INTP	INTN
Access							R/W	R/W
Reset							0	0

Bit 1 - INTP Comparator Interrupt on Positive-Going Edge Enable

٧	'alue	Description						
1		The CxIF interrupt flag will be set upon a positive-going edge of the CxOUT bit						
0		No interrupt flag will be set on a positive-going edge of the CxOUT bit						


## Bit 0 - INTN Comparator Interrupt on Negative-Going Edge Enable

Value	Description
1	The CxIF interrupt flag will be set upon a negative-going edge of the CxOUT bit
0	No interrupt flag will be set on a negative-going edge of the CxOUT bit

# 45.12.3 CMxNCH

Name: CMxNCH Offset: 0x072,0x076

Comparator Inverting Channel Select Register




Bits 2:0 - NCH[2:0] Comparator Inverting Input Channel Select

NCH	Negative Input Sources
111	V <sub>SS</sub>
110	FVR_Buffer2
101	NCH not connected
100	NCH not connected
011	CxIN3-
010	CxIN2-
001	CxIN1-
000	CxIN0-

# 45.12.4 CMxPCH

Name: CMxPCH Offset: 0x073,0x077

Comparator Non-Inverting Channel Select Register



Bits 2:0 - PCH[2:0] Comparator Non-Inverting Input Channel Select

PCH	Positive Input Sources
111	$V_{SS}$
110	FVR_Buffer2
101	DAC_Output
100	PCH not connected
011	PCH not connected
010	PCH not connected
001	CxIN1+
000	CxIN0+

# 45.12.5 CMOUT

Name: CMOUT Offset: 0x06F

Comparator Output Register



Bits 0, 1 - CxOUT Mirror copy of the CMxCON0.OUT

# 45.13 Register Summary - Comparator


Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x6E										
0x6F	CMOUT	7:0							C2OUT	C1OUT
0x70	CM1CON0	7:0	EN	OUT		POL			HYS	SYNC
0x71	CM1CON1	7:0							INTP	INTN
0x72	CM1NCH	7:0							NCH[2:0]	
0x73	CM1PCH	7:0						PCH[2:0]		
0x74	CM2CON0	7:0	EN	OUT		POL			HYS	SYNC
0x75	CM2CON1	7:0							INTP	INTN
0x76	CM2NCH	7:0						NCH[2:0]		
0x77	CM2PCH	7:0							PCH[2:0]	

## 46. ZCD - Zero-Cross Detection Module

The ZCD module detects when an A/C signal crosses through the ground potential. The actual zero crossing threshold is the zero crossing reference voltage,  $Z_{CPINV}$ , which is typically 0.75V above ground.

The connection to the signal to be detected is through a series current-limiting resistor. The module applies a current source or sink to the ZCD pin to maintain a constant voltage on the pin, thereby preventing the pin voltage from forward biasing the ESD protection diodes. When the applied voltage is greater than the reference voltage, the module sinks current. When the applied voltage is less than the reference voltage, the module sources current. The current source and sink action keeps the pin voltage constant over the full range of the applied voltage. The ZCD module is shown in the following simplified block diagram.

Figure 46-1. Simplified ZCD Block Diagram



The ZCD module is useful when monitoring an A/C waveform for, but not limited to, the following purposes:

- · A/C period measurement
- · Accurate long term time measurement

- · Dimmer phase delayed drive
- · Low EMI cycle switching


#### 46.1 External Resistor Selection

The ZCD module requires a current-limiting resistor in series with the external voltage source. The impedance and rating of this resistor depends on the external source peak voltage. Select a resistor value that will drop all of the peak voltage when the current through the resistor is nominally 300  $\mu$ A. Make sure that the ZCD I/O pin internal weak pull-up is disabled so it does not interfere with the current source and sink.

#### **Equation 46-1. External Resistor**

$$R_{SERIES} = \frac{V_{PEAK}}{3 \times 10^{-4}}$$

Figure 46-2. External Voltage Source



# 46.2 ZCD Logic Output

The ZCD module includes a Status bit, which can be read to determine whether the current source or sink is active. The OUT bit is set when the current sink is active, and cleared when the current source is active. The OUT bit is affected by the polarity bit.

The OUT signal can also be used as input to other modules. This is controlled by the registers of the corresponding module.

## 46.3 ZCD Logic Polarity

The POL bit inverts the OUT bit relative to the current source and sink output. When the POL bit is set, a OUT high indicates that the current source is active, and a low output indicates that the current sink is active. The POL bit affects the ZCD interrupts.

#### 46.4 ZCD Interrupts

An interrupt will be generated upon a change in the ZCD logic output when the appropriate interrupt enables are set. The ZCD module has a rising edge detector and a falling edge detector.

The ZCDIF bit of the PIRx register will be set when either edge detector is triggered and its associated enable bit is set. The INTP enables rising edge interrupts and the INTN bit enables falling edge interrupts.

To fully enable the interrupt, the following bits must be set:

- · ZCDIE bit of the PIEx register
- · INTP bit for rising edge detection
- · INTN bit for falling edge detection
- GIEL and GIE bits of the INTCON0 register

Changing the POL bit will cause an interrupt, regardless of the level of the SEN bit.

The ZCDIF bit of the PIRx register must be cleared in software as part of the interrupt service. If another edge is detected while this flag is being cleared, the flag will still be set at the end of the sequence.

# 46.5 Correction for Z<sub>CPINV</sub> Offset

The actual voltage at which the ZCD switches is the reference voltage at the noninverting input of the ZCD op amp. For external voltage source waveforms other than square waves, this voltage offset from zero causes the zero-cross event to occur either too early or too late.

## 46.5.1 Correction by AC Coupling

When the external voltage source is sinusoidal, the effects of the  $Z_{CPINV}$  offset can be eliminated by isolating the external voltage source from the ZCD pin with a capacitor, in addition to the voltage reducing resistor. The capacitor will cause a phase shift resulting in the ZCD output switch in advance of the actual zero crossing event. The phase shift will be the same for both rising and falling zero crossings, which can be compensated for by either delaying the CPU response to the ZCD switch by a timer or other means, or selecting a capacitor value large enough that the phase shift is negligible.

To determine the series resistor and capacitor values for this configuration, start by computing the impedance, Z, to obtain a peak current of 300  $\mu$ A. Next, arbitrarily select a suitably large non-polar capacitor and compute its reactance, Xc, at the external voltage source frequency. Finally, compute the series resistor, capacitor peak voltage, and phase shift by the formulas shown below.

When this technique is used and the input signal is not present, the ZCD will tend to oscillate. To avoid this oscillation, connect the ZCD pin to  $V_{DD}$  or GND with a high-impedance resistor such as 200K.

#### Equation 46-2. R-C Equations

V<sub>PEAK</sub> = external voltage source peak voltage

f = external voltage source frequency

C = series capacitor

R = series resistor

V<sub>C</sub> = Peak capacitor voltage

Φ = Capacitor induced zero crossing phase advance in radians

 $T_{\Phi}$  = Time ZC event occurs before actual zero crossing

$$Z = \frac{V_{PEAK}}{3 \times 10^{-4}}$$

$$X_C = \frac{1}{2\pi f C}$$

$$R = \sqrt{Z^2 - X_C^2}$$

$$V_C = X_C (3 \times 10^{-4})$$

$$\Phi = \tan^{-1} \left( \frac{X_C}{R} \right)$$

$$T_{\Phi} = \frac{\Phi}{2\pi f}$$

#### Equation 46-3. R-C Calculation Example

$$V_{rms}=120\,$$

$$V_{PEAK} = V_{rms} \times \sqrt{2} = 169.7$$

$$f = 60 Hz$$

$$C = 0.1 \, \mu F$$

$$Z = \frac{V_{PEAK}}{3 \times 10^{-4}} = \frac{169.7}{3 \times 10^{-4}} = 565.7 \, k\Omega$$

$$X_C = \frac{1}{2\pi fC} = \frac{1}{2\pi \times 60 \times 10^{-7}} = 26.53 \text{ k}\Omega$$

$$R = \sqrt{Z^2 - X_C^2} = 565.1 \, k\Omega \, (computed)$$

$$R_a = 560 \, k\Omega \, (used)$$

$$Z_R = \sqrt{{R_a}^2 + {X_C}^2} = 560.6 \, k\Omega$$

$$I_{PEAK} = \frac{V_{PEAK}}{Z_R} = 302.7 \times 10^{-6} A$$

$$V_C = X_C \times I_{PEAK} = 8.0 V$$

$$\Phi = \tan^{-1} \left( \frac{X_C}{R} \right) = 0.047 radians$$

$$T_{\Phi} = \frac{\Phi}{2\pi f} = 125.6 \mu s$$

### 46.5.2 Correction By Offset Current

When the waveform is varying relative to  $V_{SS}$ , then the zero cross is detected too early as the waveform falls and too late as the waveform rises. When the waveform is varying relative to  $V_{DD}$ , then the zero cross is detected too late as the waveform rises and too early as the waveform falls. The actual offset time can be determined for sinusoidal waveforms with the corresponding equations shown below.

#### Equation 46-4. ZCD Event Offset

When External Voltage source is relative to V<sub>SS</sub>

$$T_{offset} = \frac{\sin^{-1} \left( \frac{Z_{CPINV}}{V_{PEAK}} \right)}{2\pi f}$$

When External Voltage source is relative to V<sub>DD</sub>

$$T_{offset} = \frac{\sin^{-1}\left(\frac{V_{DD} - Z_{CPINV}}{V_{PEAK}}\right)}{2\pi f}$$

This offset time can be compensated for by adding a pull-up or pull-down biasing resistor to the ZCD pin. A pull-up resistor is used when the external voltage source is varying relative to  $V_{SS}$ . A pull-down resistor is used when the voltage is varying relative to  $V_{DD}$ . The resistor adds a bias to the ZCD pin so that the target external voltage source must go to zero to pull the pin voltage to the  $Z_{CPINV}$  switching voltage. The pull-up or pull-down value can be determined with the equations shown below.

### Equation 46-5. ZCD Pull-up/Pull-down Resistor

When External Voltage source is relative to V<sub>SS</sub>

$$R_{pullup} = \frac{R_{SERIES}(V_{pullup} - Z_{CPINV})}{Z_{CPINV}}$$

When External Voltage source is relative to V<sub>DD</sub>

$$R_{pulldown} = \frac{R_{SERIES}(Z_{CPINV})}{(V_{DD} - Z_{CPINV})}$$

# 46.6 Handling V<sub>PEAK</sub> Variations

If the peak amplitude of the external voltage is expected to vary, the series resistor must be selected to keep the ZCD current source and sink below the design maximum range of  $\pm$  600  $\mu$ A and above a reasonable minimum range. A general rule of thumb is that the maximum peak voltage can be no more than six times the minimum peak voltage. To ensure that the maximum current does not exceed  $\pm$  600  $\mu$ A and the minimum is at least  $\pm$  100  $\mu$ A, compute the series resistance as shown in Equation 46-6. The compensating pull-up for this series resistance can be determined with the equations shown in Equation 46-5 because the pull-up value is independent from the peak voltage.

Equation 46-6. Series R for V range
$$R_{SERIES} = \frac{V_{MAX\_PEAK} + V_{MIN\_PEAK}}{7 \times 10^{-4}}$$

# 46.7 Operation During Sleep

The ZCD current sources and interrupts are unaffected by Sleep.

### 46.8 Effects of a Reset

The ZCD circuit can be configured to default to the Active or Inactive state on Power-on Reset (POR). When the  $\overline{\text{ZCD}}$  Configuration bit is cleared, the ZCD circuit will be active at POR. When the  $\overline{\text{ZCD}}$  Configuration bit is set, the SEN bit must be set to enable the ZCD module.

## 46.9 Disabling the ZCD Module

The ZCD module can be disabled in two ways:

- The ZCD Configuration bit disables the ZCD module when set. When this is the case then the ZCD module will be enabled by setting the SEN bit. When the ZCD bit is clear, the ZCD is always enabled and the SEN bit has no effect.
- 2. The ZCD can also be disabled using the ZCDMD bit of the PMDx register. This is subject to the status of the ZCD bit.

# 46.10 Register Summary: ZCD

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x4B										
0x4C	ZCDCON	7:0	SEN		OUT	POL			INTP	INTN

# 46.11 Register Definitions: ZCD Control

Long bit name prefixes for the ZCD peripherals are shown in the table below. Refer to the "Long Bit Names" section of the "Register and Bit Naming Conventions" chapter for more information.

Table 46-1. ZCD Long Bit Name Prefixes

Peripheral	Bit Name Prefix
ZCD	ZCD

#### 46.11.1 ZCDCON

Name: ZCDCON Offset: 0x04C

Zero-Cross Detect Control Register

Bit	7	6	5	4	3	2	1	0
	SEN		OUT	POL			INTP	INTN
Access	R/W		R	R/W			R/W	R/W
Reset	0		X	0			0	0

#### Bit 7 - SEN Zero-Cross Detect Software Enable

This bit is ignored when ZCD fuse is cleared.

Value	Condition	Description
X	ZCD Config fuse = 0	Zero-cross detect is always enabled. This bit is ignored.
1	ZCD Config fuse = 1	Zero-cross detect is enabled. ZCD pin is forced to output to source and sink current.
0	ZCD Config fuse = 1	Zero-cross detect is disabled. ZCD pin operates according to PPS and TRIS controls.

#### Bit 5 - OUT Zero-Cross Detect Data Output

Value	Condition	Description
1	POL = 0	ZCD pin is sinking current
0	POL = 0	ZCD pin is sourcing current
1	POL = 1	ZCD pin is sourcing current
0	POL = 1	ZCD pin is sinking current

#### Bit 4 - POL Zero-Cross Detect Polarity

Value	Description
1	ZCD logic output is inverted
0	ZCD logic output is not inverted

# Bit 1 – INTP Zero-Cross Detect Positive-Going Edge Interrupt Enable

Value	Description
1	ZCDIF bit is set on low-to-high ZCD_output transition
0	ZCDIF bit is unaffected by low-to-high ZCD_output transition

#### Bit 0 - INTN Zero-Cross Detect Negative-Going Edge Interrupt Enable

Value	Description
1	ZCDIF bit is set on high-to-low ZCD_output transition
0	ZCDIF bit is unaffected by high-to-low ZCD_output transition

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 974

# 47. Instruction Set Summary

The PIC18 devices incorporate the standard set of PIC18 core instructions, as well as an extended set of instructions to optimize code that is recursive or that utilizes a software stack. The extended set is discussed later in this section.

#### 47.1 Standard Instruction Set

The standard PIC18 instruction set adds many enhancements to the previous PIC® MCU instruction sets, while maintaining an easy migration from these PIC MCU instruction sets. Most instructions are a single program memory word (16 bits), but there are a few instructions that require two- or three-program memory locations.

Each single-word instruction is a 16-bit word divided into an opcode that specifies the instruction type and one or more operands, which further specifies the operation of the instruction.

The instruction set is highly orthogonal and is grouped into four basic categories:

- Byte-oriented operations
- · Bit-oriented operations
- Literal operations
- · Control operations

The PIC18 instruction set summary in Table 47-2 lists byte-oriented, bit-oriented, literal and control operations. Table 47-1 shows the opcode field descriptions.

Most byte-oriented instructions have three operands:

- 1. The file register (specified by 'f')
- 2. The destination of the result (specified by 'd')
- 3. The accessed memory (specified by 'a')

The file register designator 'f' specifies which file register is to be used by the instruction. The destination designator 'd' specifies where the result of the operation is to be placed. If 'd' is zero, the result is placed in the WREG register. If 'd' is one, the result is placed in the file register specified in the instruction.

All bit-oriented instructions have three operands:

- 1. The file register (specified by 'f')
- 2. The bit in the file register (specified by 'b')
- 3. The accessed memory (specified by 'a')

The bit field designator 'b' selects the number of the bit affected by the operation, while the file register designator 'f' represents the number of the file in which the bit is located.

The literal instructions may use some of the following operands:

- A literal value to be loaded into a file register (specified by 'k')
- The desired FSR register to load the literal value into (specified by 'f')
- No operand required (specified by '—')

The control instructions may use some of the following operands:

- · A program memory address (specified by 'n')
- The mode of the CALL or RETURN instructions (specified by 's')
- The mode of the table read and table write instructions (specified by 'm')
- No operand required (specified by '—')

All instructions are a single word, except for a few two- or three-word instructions. These instructions were made two- or three-word to contain the required information in 32 or 48 bits. In the second and third words, the four MSbs are '1's. If this second or third word is executed as an instruction (by itself), it will execute as a NOP.

All single-word instructions are executed in a single instruction cycle, unless a conditional test is true or the Program Counter is changed as a result of the instruction. In these cases, the execution takes two instruction cycles, with the additional instruction cycle(s) executed as a NOP.

The two-word instructions execute in two instruction cycles and three-word instructions execute in three instruction cycles.

One instruction cycle consists of four oscillator periods. Thus, for an oscillator frequency of 4 MHz, the normal instruction execution time is 1  $\mu$ s. If a conditional test is true, or the Program Counter is changed as a result of an instruction, the instruction execution time is 2  $\mu$ s. Two-word branch instructions (if true) would take 3  $\mu$ s.

Figure 47-1, Figure 47-2 and Figure 47-3 show the general formats that the instructions can have. All examples use the convention 'nnh' to represent a hexadecimal number.

The Instruction Set Summary, shown in Table 47-2, lists the standard instructions recognized by the Microchip MPASM<sup>TM</sup> Assembler.

Standard Instruction Set provides a description of each instruction.

Table 47-1. Opcode Field Descriptions


Field	Description
a	RAM access bit a = 0: RAM location in Access RAM (BSR register is ignored) a = 1: RAM bank is specified by BSR register (default)
ACCESS	ACCESS = 0: RAM access bit symbol
BANKED	BANKED = 1: RAM access bit symbol
bbb	Bit address within an 8-bit file register (0 to 7)
BSR	Bank Select Register (BSR). Used to select the current RAM bank.
d	Destination select bit d = 0: store result in WREG d = 1: store result in file register f (default)
dest	Destination: either the WREG register or the specified register file location
f	8-bit register file address (00h to FFh)
f <sub>n</sub>	FSR Number (0 to 2)
f <sub>s</sub>	12-bit register file address (000h to FFFh) or 14-bit register file address (0000h to 3FFFh). This is the source address.
f <sub>d</sub>	12-bit register file address (000h to FFFh) or 14-bit register file address (0000h to 3FFFh). This is the destination address.
Z <sub>S</sub>	7-bit literal offset for FSR2 to used as register file address (000h to FFFh). This is the source address.
z <sub>d</sub>	7-bit literal offset for FSR2 to used as register file address (000h to FFFh). This is the destination address.
k	Literal field, constant data or label (may be either a 6-bit, 8-bit, 12-bit or a 20-bit value)
label	Label name
mm	The mode of the TBLPTR register for the table read and table write instructions. Only used with table read and table write instructions:
*	No change to register (such as TBLPTR with table reads and writes)
*+	Post-Increment register (such as TBLPTR with table reads and writes)
*_	Post-Decrement register (such as TBLPTR with table reads and writes)
+*	Pre-Increment register (such as TBLPTR with table reads and writes)

continued	
Field	Description
n	The relative address (2's complement number) for relative branch instructions, or the direct address for call/branch and return instructions.
PRODH	Product of multiply high byte
PRODL	Product of multiply low byte
S	Fast Call/Return mode select bit s = 0: do not update into/from shadow registers (default) s = 1: certain registers loaded into/from shadow registers (Fast mode)
u	Unused or unchanged
W	W = 0: Destination select bit symbol
WREG	Working register (accumulator)
х	Don't care ('0' or '1'). The assembler will generate code with $x = 0$ . It is the recommended form of use for compatibility with all Microchip software tools.
TBLPTR	21-bit Table Pointer (points to a program memory location)
TABLAT	8-bit table latch
TOS	Top-of-stack (TOS)
PC	Program Counter
PCL	Program Counter low byte
PCH	Program Counter high byte
PCLATH	Program Counter high byte latch
PCLATU	Program Counter upper byte Latch
GIE	Global Interrupt Enable bit
WDT	Watchdog Timer
TO	Time-Out bit
PD	Power-Down bit
C, DC, Z, OV, N	ALU Status bits: Carry, Digit Carry, Zero, Overflow, Negative
{ }	Optional argument
[ ]	Indexed address
( )	Contents
< >	Register bit field
[expr] <n></n>	Specifies bit n of the register indicated by pointer expr
<b>→</b>	Assigned to
€	In the set of
italics	User defined term (font is Courier)

Figure 47-1. General Format for Byte-oriented Instructions

# Byte-oriented file register operations

# **Example Instruction**



ADDWF MYREG, W, B

d = 0 for result destination to be WREG register

d = 1 for result destination to be file register (f)


a = 0 to force Access Bank

a = 1 for BSR to select bank

f = 8-bit file register address

# Byte to Byte move operations (2-word)

# **Example Instruction**




MOVFF MYREG1, MYREG2

f = 12-bit file register address

# **Byte to Byte** move operations (3-word)

# **Example Instruction**




MOVFFL MYREG1, MYREG2

Figure 47-2. General Format for Bit-oriented and Literal Instructions

# Bit-oriented file register operations

# **Example Instruction**



BSF MYREG, bit, B

b = 3-bit position of bit in file register (f)

a = 0 to force Access Bank

a = 1 for BSR to select bank

f = 8-bit file register address

# **Literal** operations

# **Example Instruction**




MOVLW 7Fh

k = 8-bit immediate value


Figure 47-3. General Format for Control Instructions

# Control operations CALL, GOTO and Branch operations

# **Example Instruction**




k = 20-bit immediate value




k = 20-bit immediate value

s = Fast bit



n = 11-bit immediate value



n = 8-bit immediate value

Table 47-2. Standard Instruction Set

Mnemonic, Operands					16-Bit Instr	uction Word		Status	
		Description	Cycles	MSb			LSb	Affected	Notes
		ВҮТ	E-ORIENTI	ED FILE REG	ISTER INSTRU	ICTIONS			
ADDWF	f, d, a	Add WREG and f	1	0010	01da	ffff	ffff	C, DC, Z, OV, N	1
ADDWFC	f, d, a	Add WREG and Carry bit to f	1	0010	00da	ffff	ffff	C, DC, Z, OV, N	1
ANDWF	f, d, a	AND WREG with f	1	0001	01da	ffff	ffff	Z, N	1
CLRF	f, a	Clear f	1	0110	101a	ffff	ffff	Z	
COMF	f, d, a	Complement f	1	0001	11da	ffff	ffff	Z, N	1
DECF	f, d, a	Decrement f	1	0000	01da	ffff	ffff	C, DC, Z, OV, N	1
INCF	f, d, a	Increment f	1	0010	10da	ffff	ffff	C, DC, Z, OV, N	1
IORWF	f, d, a	Inclusive OR WREG with f	1	0001	00da	ffff	ffff	Z, N	1
MOVF	f, d, a	Move f to WREG or f	1	0101	00da	ffff	ffff	Z, N	1
MOVFF		Move f <sub>s</sub> (12-bit source)	2	1100	fsfsfsfs	fsfsfsfs	fsfsfsfs	None	1, 3, 4
IVIOVEE	f <sub>s</sub> , f <sub>d</sub>	to f <sub>d</sub> (12-bit destination)	2	1111	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f		
				0000	0000	0110	f <sub>s</sub> f <sub>s</sub> f <sub>s</sub> f <sub>s</sub>		
MOVFFL	f <sub>s</sub> , f <sub>d</sub>	Move f <sub>s</sub> (14-bit source) to f <sub>d</sub> (14-bit destination)	3	1111	fsfsfsfs	f <sub>s</sub> f <sub>s</sub> f <sub>s</sub> f <sub>s</sub>	f <sub>s</sub> f <sub>s</sub> f <sub>d</sub> f <sub>d</sub>	None	1, 3
		,		1111	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f		
MOVWF	f, a	Move WREG to f	1	0110	111a	ffff	ffff	None	
MULWF	f, a	Multiply WREG with f	1	0000	001a	ffff	ffff	None	1
NEGF	f, a	Negate f	1	0110	110a	ffff	ffff	C, DC, Z, OV, N	1
RLCF	f, d, a	Rotate Left f through Carry	1	0011	01da	ffff	ffff	C, Z, N	1
RLNCF	f, d, a	Rotate Left f (No Carry)	1	0100	01da	ffff	ffff	Z, N	1
RRCF	f, d, a	Rotate Right f through Carry	1	0011	00da	ffff	ffff	C, Z, N	1
RRNCF	f, d, a	Rotate Right f (No Carry)	1	0100	00da	ffff	ffff	Z, N	1
SETF	f, a	Set f	1	0110	100a	ffff	ffff	None	

continue	ed								
Mnemo					16-Bit Instr	ruction Word		Status	
Operands		Description	Cycles	MSb			LSb	Affected	Notes
SUBFWB	f, d, a	Subtract f from WREG with borrow	1	0101	01da	ffff	ffff	C, DC, Z, OV, N	1
SUBWF	f, d, a	Subtract WREG from f	1	0101	11da	ffff	ffff	C, DC, Z, OV, N	1
SUBWFB	f, d, a	Subtract WREG from f with borrow	1	0101	10da	ffff	ffff	C, DC, Z, OV, N	1
SWAPF	f, d, a	Swap nibbles in f	1	0011	10da	ffff	ffff	None	1
XORWF	f, d, a	Exclusive OR WREG with f	1	0001	10da	ffff	ffff	Z, N	1
			BYTE-OF	EIENTED SKIP	NSTRUCTIO	NS			
CPFSEQ	f, a	Compare f with WREG, skip if =	1 – 4	0110	001a	ffff	ffff	None	1, 2
CPFSGT	f, a	Compare f with WREG, skip if >	1 – 4	0110	010a	ffff	ffff	None	1, 2
CPFSLT	f, a	Compare f with WREG, skip if <	1 – 4	0110	000a	ffff	ffff	None	1, 2
DECFSZ	f, d, a	Decrement f, Skip if 0	1 – 4	0010	11da	ffff	ffff	None	1, 2
DCFSNZ	f, d, a	Decrement f, Skip if Not 0	1 – 4	0100	11da	ffff	ffff	None	1, 2
INCFSZ	f, d, a	Increment f, Skip if 0	1 – 4	0011	11da	ffff	ffff	None	1, 2
INFSNZ	f, d, a	Increment f, Skip if Not 0	1 – 4	0100	10da	ffff	ffff	None	1, 2
TSTFSZ	f, a	Test f, skip if 0	1 – 4	0110	011a	ffff	ffff	None	1, 2
		BI	T-ORIENTE	D FILE REGIS	STER INSTRUC	CTIONS			
BCF	f, b, a	Bit Clear f	1	1001	bbba	ffff	ffff	None	1
BSF	f, b, a	Bit Set f	1	1000	bbba	ffff	ffff	None	1
BTG	f, b, a	Bit Toggle f	1	0111	bbba	ffff	ffff	None	1
			BIT-ORI	ENTED SKIP	INSTRUCTION	IS			
BTFSC	f, b, a	Bit Test f, Skip if Clear	1 – 4	1011	bbba	ffff	ffff	None	1, 2

continu	ed					continued								
Mnemo				16-Bit Instruction Word			Status							
Operands		Description	Cycles	MSb			LSb	Affected	Notes					
BTFSS	f, b, a	Bit Test f, Skip if Set	1 – 4	1010	bbba	ffff	ffff	None	1, 2					
	CONTROL INSTRUCTIONS													
ВС	n	Branch if Carry	1 – 2	1110	0010	nnnn	nnnn	None	2					
BN	n	Branch if Negative	1 – 2	1110	0110	nnnn	nnnn	None	2					
BNC	n	Branch if Not Carry	1 – 2	1110	0011	nnnn	nnnn	None	2					
BNN	n	Branch if Not Negative	1 – 2	1110	0111	nnnn	nnnn	None	2					
BNOV	n	Branch if Not Overflow	1 – 2	1110	0101	nnnn	nnnn	None	2					
BNZ	n	Branch if Not Zero	1 – 2	1110	0001	nnnn	nnnn	None	2					
BOV	n	Branch if Overflow	1 – 2	1110	0100	nnnn	nnnn	None	2					
BRA	n	Branch Unconditionally	2	1101	0nnn	nnnn	nnnn	None	2					
BZ	n	Branch if Zero	1 – 2	1110	0000	nnnn	nnnn	None	2					
0411	1	O-II harastina	2	1110	110s	kkkk	kkkk	None	2.2					
CALL	k, s	Call subroutine	2	1111	kkkk	kkkk	kkkk	None	2, 3					
CALLW	_	Call subroutine using WREG	2	0000	0000	0001	0100	None	2					
GOTO	k	Go to address	2	1110	1111	kkkk	kkkk	None	3					
GOTO	K	Go to address		1111	kkkk	kkkk	kkkk	None	3					
RCALL	n	Relative Call	2	1101	1nnn	nnnn	nnnn	None	2					
RETFIE	S	Return from interrupt enable	2	0000	0000	0001	000s	INTCONx STAT bits	2					
RETLW	k	Return with literal in WREG	2	0000	1100	kkkk	kkkk	None	2					
RETURN	S	Return from Subroutine	2	0000	0000	0001	001s	None	2					
			INH	IERENT INST	RUCTIONS									
CLRWDT	_	Clear Watchdog Timer	1	0000	0000	0000	0100	TO, PD						

continued									
Mnemo				16-Bit Instruction Word				Status	
Operands		Description	Cycles	MSb			LSb	Affected	Notes
DAW	_	Decimal Adjust WREG	1	0000	0000	0000	0111	С	
NOP	_	No Operation	1	0000	0000	0000	0000	None	
NOP	_	No Operation	1	1111	xxxx	xxxx	xxxx	None	3
POP	_	Pop top of return stack (TOS)	1	0000	0000	0000	0110	None	
PUSH	_	Push top of return stack (TOS)	1	0000	0000	0000	0101	None	
RESET	_	Software device Reset	1	0000	0000	1111	1111	All	
SLEEP	_	Go into Standby mode	1	0000	0000	0000	0011	TO, PD	
			LI	TERAL INSTR	RUCTIONS				
ADDFSR	f <sub>n</sub> , k	Add FSR (f <sub>n</sub> ) with literal (k)	1	1110	1000	f <sub>n</sub> f <sub>n</sub> kk	kkkk	None	
ADDLW	k	Add literal and WREG	1	0000	1111	kkkk	kkkk	C, DC, Z, OV, N	
ANDLW	k	AND literal with WREG	1	0000	1011	kkkk	kkkk	Z, N	
IORLW	k	Inclusive OR literal with WREG	1	0000	1001	kkkk	kkkk	Z, N	
LECD	£ 1,	Load FSR(f <sub>n</sub> ) with a 14-bit		1110	1110	00f <sub>n</sub> f <sub>n</sub>	kkkk	None	2
LFSR	f <sub>n</sub> , k	literal (k)	2	1111	00kk	kkkk	kkkk	None	3
MOVLB	k	Move literal to BSR<5:0>	1	0000	0001	00kk	kkkk	None	
MOVLW	k	Move literal to WREG	1	0000	1110	kkkk	kkkk	None	
MULLW	k	Multiply literal with WREG	1	0000	1101	kkkk	kkkk	None	
RETLW	k	Return with literal in WREG	2	0000	1100	kkkk	kkkk	None	
SUBFSR	f <sub>n</sub> , k	Subtract literal (k) from FSR (f <sub>n</sub> )	1	1110	1001	f <sub>n</sub> f <sub>n</sub> kk	kkkk	None	
SUBLW	k	Subtract WREG from literal	1	0000	1000	kkkk	kkkk	C, DC, Z, OV, N	

continue	ed								
Mnemo					16-Bit Instr	ruction Word		Status	
Operar	nds	Description	Cycles	MSb			LSb	Affected	Notes
XORLW	k	Exclusive OR literal with WREG	1	0000	1010	kkkk	kkkk	Z, N	
		DATA	MEMORY -	PROGRAM N	MEMORY INST	RUCTIONS			
TBLRD*	_	Table Read	2	0000	0000	0000	1000	None	
TBLRD*+	_	Table Read with post- increment	2	0000	0000	0000	1001	None	
TBLRD*-	_	Table Read with post- decrement	2	0000	0000	0000	1010	None	
TBLRD+*	_	Table Read with pre- increment	2	0000	0000	0000	1011	None	
TBLWT*	_	Table Write	2	0000	0000	0000	1100	None	
TBLWT*+	_	Table Write with post- increment	2	0000	0000	0000	1101	None	
TBLWT*-	_	Table Write with post- decrement	2	0000	0000	0000	1110	None	
TBLWT+*	_	Table Write with pre- increment	2	0000	0000	0000	1111	None	

#### Notes:

1. When a PORT register is modified as a function of itself (e.g., MOVF PORTB, 1, 0), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as input and is driven low by an external device, the data will be written back with a '0'.

PIC18F26/46/56Q84

**Instruction Set Summary** 

- 2. If Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.
- 3. Some instructions are multi-word instructions. The extra words of these instructions will be executed as a NOP unless the first word of the instruction retrieves the information embedded in these 16 bits. This ensures that all program memory locations have a valid instruction.
- 4.  $f_s$  and  $f_d$  do not cover the full memory range. 2 MSbs of bank selection are forced to 0b00 to limit the range of these instructions to the lower 4k addressing space.

#### 47.1.1 **Standard Instruction Set**



Important: All PIC18 instructions may take an optional label argument preceding the instruction mnemonic for use in symbolic addressing. If a label is used, the instruction format then becomes: {label} instruction argument(s)

ADDFSR	ADD Literal to FSR	ADD Literal to FSR					
Syntax	ADDFSR f <sub>n</sub> , k						
Operands	$0 \le k \le 63$ $f_n \in [0, 1, 2]$						
Operation	$(FSRf_n) + k \rightarrow FSRf_n$						
Status Affected	None						
Encoding	1110	1000	f <sub>n</sub> f <sub>n</sub> kk	kkkk			
Description	The 6-bit literal 'k' is added to the contents of the FSR specified by 'f <sub>n</sub> '.						
Words	1						
Cycles	1						

# Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal 'k'	Process Data	Write to FSR

Example: ADDFSR 2, 23h

**Before Instruction FSR2** = 03FFh

After Instruction

FSR2 = 0422h

ADDLW	ADD Literal to W						
Syntax	ADDLW k						
Operands	0 ≤ k ≤ 255	0 ≤ k ≤ 255					
Operation	$(W) + k \rightarrow W$	$(W) + k \rightarrow W$					
Status Affected	N, OV, C, DC, Z						
Encoding	0000	1111	kkkk	kkkk			
Description	The contents of W are a	added to the 8-bit litera	l 'k' and the result is pla	ced in W.			
Words	1	1					
Cycles	1						

# Q Cycle Activity:

Q1 Q2	Q3	Q4
-------	----	----

Decode	Read literal 'k'	Process Data	Write to W

Example: ADDLW 15h

**Before Instruction** 

W = 10h

After Instruction

W = 25h

ADDWF	ADD W to f					
Syntax	ADDWF f {,d {,a}}					
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$	d ∈ [0, 1]				
Operation	$(W) + (f) \rightarrow dest$					
Status Affected	N, OV, C, DC, Z					
Encoding	0010	01da	ffff	ffff		
Description	Add W to register 'f'. If in register 'f' (default).	'd' is '0', the result is sto	ored in W. If 'd' is '1', the	e result is stored back		
	If 'a' is '0', the Access	Bank is selected. If 'a' is	'1', the BSR is used to	select the GPR bank.		
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.					
Words	1					
Cycles	1					

# Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination

Example: ADDWF REG, 0, 0

**Before Instruction** 

W = 17h REG = 0C2h

After Instruction

**W** = 0D9h **REG** = 0C2h

ADDWFC	ADD W and CARRY bit to f
Syntax	ADDWFC f {,d {,a}}
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$

continued	continued						
ADDWFC	ADD W and CARRY bit to f						
Syntax	ADDWFC f {,d {,a}	-}					
Operation	$(W) + (f) + (C) \rightarrow dest$						
Status Affected	N, OV, C, DC, Z						
Encoding	0010 00da ffff ffff						
Description	1	g and data memory loca aced in data memory lo		esult is stored in W. If			
	If 'a' is '0', the Access	Bank is selected. If 'a' is	1', the BSR is used to	select the GPR bank.			
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.						
Words	1						
Cycles	1						

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination

Example: ADDWFC REG, 0, 1

**Before Instruction** 

CARRY bit = 1

**REG** = 02h

W = 4Dh

**After Instruction** 

CARRY bit = 0

**REG** = 02h

W = 50h

ANDLW	AND literal with W	AND literal with W		
Syntax	ANDLW k			
Operands	0 ≤ k ≤ 255	0 ≤ k ≤ 255		
Operation	(W) .AND. $k \rightarrow W$	(W) .AND. $k \rightarrow W$		
Status Affected	N, Z			
Encoding	0000	1011	kkkk	kkkk
Description	The contents of W are A	AND'ed with the 8-bit lit	eral 'k'. The result is pla	iced in W.
Words	1			
Cycles	1			

#### Q Cycle Activity:

∩1	$\cap$ 2	<b>∩</b> 3	$\cap$ 4
Q I	QZ	QJ	Q <del>4</del>

Decode	Read literal 'k'	Process Data	Write to W

Example: ANDLW 05Fh

**Before Instruction** 

W = A3h

After Instruction

**W** = 03h

ANDWF	AND W with f			
Syntax	ANDWF f {,d {,a}}			
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$			
Operation	(W) .AND. (f) $\rightarrow$ dest			
Status Affected	N, Z			
Encoding	0001	01da	ffff	ffff
Description		AND'ed with register 'f'. back in register 'f' (defa	If 'd' is '0', the result is ult).	stored in W. If 'd' is
	If 'a' is '0', the Access	Bank is selected. If 'a' is	1', the BSR is used to	select the GPR bank.
	Literal Offset Addressi		nabled, this instruction of (5Fh). See Byte-Orie details.	•
Words	1			
Cycles	1			

# Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination

Example: ANDWF REG, 0, 0

**Before Instruction** 

**W** = 17h **REG** = C2h

After Instruction

W = 02h

REG = C2h

ВС	Branch if Carry
Syntax	BC n
Operands	-128 ≤ n ≤ 127

continued	continued			
вс	Branch if Carry	Branch if Carry		
Syntax	BC n			
Operation	If CARRY bit is '1' $(PC) + 2 + 2n \rightarrow PC$			
Status Affected	None			
Encoding	1110	0010	nnnn	nnnn
Description	added to the PC. Since	If the CARRY bit is '1', then the program will branch. The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a 2-cycle instruction.		
Words	1	1		
Cycles	1 (2)			

# If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal 'n'	Process Data	Write to PC
No operation	No operation	No operation	No operation

# If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal 'n'	Process Data	No operation

Example: HERE BC 5

Before Instruction
PC = address (HERE)

# After Instruction

If CARRY = 1; PC = address (HERE + 12)
If CARRY = 0; PC = address (HERE + 2)

BCF	Bit Clear f			
Syntax	BCF f, b {,a}			
Operands	0 ≤ f ≤ 255 0 ≤ b ≤ 7 a ∈ [0, 1]			
Operation	$0 \rightarrow f < b >$			
Status Affected	None			
Encoding	1001	bbba	ffff	ffff

continued	
BCF	Bit Clear f
Syntax	BCF f, b {,a}
Description	Bit 'b' in register 'f' is cleared.
	If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank.
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever $f \le 95$ (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.
Words	1
Cycles	1

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write register 'f'

Example: BCF FLAG\_REG, 7, 0

Before Instruction FLAG\_REG = C7h

After Instruction FLAG\_REG = 47h

BN	Branch if Negative	Branch if Negative		
Syntax	BN n			
Operands	-128 ≤ n ≤ 127	-128 ≤ n ≤ 127		
Operation	If NEGATIVE bit is '1' $(PC) + 2 + 2n \rightarrow PC$			
Status Affected	None			
Encoding	1110	0110	nnnn	nnnn
Description	If the NEGATIVE bit is '1', then the program will branch. The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a 2-cycle instruction.			
Words	1			
Cycles	1 (2)			

# Q Cycle Activity:

# If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal 'n'	Process Data	Write to PC
No operation	No operation	No operation	No operation

If No Jump:

# PIC18F26/46/56Q84

# **Instruction Set Summary**

Q1	Q2	Q3	Q4
Decode	Read literal 'n'	Process Data	No operation

Example: HERE BN Jump

Before Instruction
PC = address (HERE)

After Instruction

If NEGATIVE = 1; PC = address (Jump)

If NEGATIVE = 0; PC = address (HERE + 2)

BNC	Branch if Not Carry	Branch if Not Carry		
Syntax	BNC n			
Operands	-128 ≤ n ≤ 127			
Operation	If CARRY bit is '0' (PC) + 2 + 2n → PC			
Status Affected	None			
Encoding	1110	0011	nnnn	nnnn
Description	added to the PC. Since	If the CARRY bit is '0', then the program will branch. The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a 2-cycle instruction.		
Words	1	1		
Cycles	1 (2)			

# Q Cycle Activity:

#### If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal 'n'	Process Data	Write to PC
No operation	No operation	No operation	No operation

#### If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal 'n'	Process Data	No operation

Example: HERE BNC Jump

Before Instruction
PC = address (HERE)

After Instruction

If CARRY = 0; PC = address (Jump)
If CARRY = 1; PC = address (HERE + 2)

BNN	Branch if Not Negativ	Branch if Not Negative		
Syntax	BNN n			
Operands	-128 ≤ n ≤ 127			
Operation	If NEGATIVE bit is '0' (PC) + 2 + 2n → PC			
Status Affected	None			
Encoding	1110	0111	nnnn	nnnn
Description	If the NEGATIVE bit is '0', then the program will branch. The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a 2-cycle instruction.			
Words	1			
Cycles	1 (2)			

# If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal 'n'	Process Data	Write to PC
No operation	No operation	No operation	No operation

# If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal 'n'	Process Data	No operation

Example: HERE BNN Jump

Before Instruction
PC = address (HERE)

After Instruction

If NEGATIVE = 0; PC = address (Jump)

If NEGATIVE = 1; PC = address (HERE + 2)

BNOV	Branch if Not Overflo	Branch if Not Overflow		
Syntax	BNOV n			
Operands	-128 ≤ n ≤ 127			
Operation	If OVERFLOW bit is '0 (PC) + 2 + $2n \rightarrow PC$	If OVERFLOW bit is '0' (PC) + 2 + 2n → PC		
Status Affected	None			
Encoding	1110	0101	nnnn	nnnn
Description	If the OVERFLOW bit is '0', then the program will branch. The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a 2-cycle instruction.			

continued	continued		
BNOV	Branch if Not Overflow		
Syntax	BNOV n		
Words	1		
Cycles	1 (2)		

# If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal 'n'	Process Data	Write to PC
No operation	No operation	No operation	No operation

# If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal 'n'	Process Data	No operation

Example: HERE BNOV Jump

Before Instruction
PC = address (HERE)

After Instruction

If OVERFLOW = 0; PC = address (Jump)
If OVERFLOW = 1; PC = address (HERE + 2)

BNZ	Branch if Not Zero	Branch if Not Zero			
Syntax	BNZ n				
Operands	-128 ≤ n ≤ 127				
Operation	If ZERO bit is '0' (PC) + 2 + 2n → PC				
Status Affected	None				
Encoding	1110	0001	nnnn	nnnn	
Description	added to the PC. Since	If the ZERO bit is '0', then the program will branch. The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a 2-cycle instruction.			
Words	1				
Cycles	1 (2)				

# Q Cycle Activity:

# If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal 'n'	Process Data	Write to PC

# PIC18F26/46/56Q84

# **Instruction Set Summary**

No operation	No operation	No operation	No operation

# If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal 'n'	Process Data	No operation

Example: HERE BNZ Jump

Before Instruction
PC = address (HERE)

After Instruction

If ZERO = 0; PC = address (Jump)
If ZERO = 1; PC = address (HERE + 2)

BOV	Branch if Overflow			
Syntax	BOV n			
Operands	-128 ≤ n ≤ 127			
Operation	If OVERFLOW bit is '1' $(PC) + 2 + 2n \rightarrow PC$			
Status Affected	None			
Encoding	1110	0100	nnnn	nnnn
Description	If the OVERFLOW bit is '1', then the program will branch. The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a 2-cycle instruction.			
Words	1			
Cycles	1 (2)			

#### Q Cycle Activity:

# If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal 'n'	Process Data	Write to PC
No operation	No operation	No operation	No operation

#### If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal 'n'	Process Data	No operation

Example: HERE BOV Jump

Before Instruction
PC = address (HERE)

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 995

After Instruction

If OVERFLOW = 1; PC = address (Jump)

If OVERFLOW = 0; PC = address (HERE + 2)

BRA	Unconditional Branch			
Syntax	BRA n			
Operands	-1024 ≤ n ≤ 1023			
Operation	$(PC) + 2 + 2n \rightarrow PC$			
Status Affected	None			
Encoding	1101	0nnn	nnnn	nnnn
Description	The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is a 2-cycle instruction.			
Words	1			
Cycles	2			

# Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal 'n'	Process Data	Write to PC
No operation	No operation	No operation	No operation

Example: HERE BRA Jump

Before Instruction
PC = address (HERE)

After Instruction

PC = address (Jump)

BSF	Bit Set f			
Syntax	BSF f, b {,a}			
Operands	$0 \le f \le 255$ $0 \le b \le 7$ $a \in [0, 1]$			
Operation	1 → f <b></b>			
Status Affected	None			
Encoding	1000	bbba	ffff	ffff
Description	Bit 'b' in register 'f' is set.  If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank.  If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.			
Words	1			

continued			
BSF	Bit Set f		
Syntax	BSF f, b {,a}		
Cycles	1		

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write register 'f'

Example: BSF FLAG\_REG, 7, 1

Before Instruction FLAG\_REG = 0Ah

After Instruction
FLAG\_REG = 8Ah

BTFSC	Bit Test File, Skip if Clear			
Syntax	BTFSC f, b {,a}			
Operands	$0 \le f \le 255$ $0 \le b \le 7$ $a \in [0, 1]$			
Operation	Skip if (f <b>) = 0</b>			
Status Affected	None			
Encoding	1011	bbba	ffff	ffff
Description	If bit 'b' in register 'f' is '0', then the next instruction is skipped. If bit 'b' is '0', then the next instruction fetched during the current instruction execution is discarded and a NOP is executed instead, making this a 2-cycle instruction.			
	If 'a' is '0', the Access I	Bank is selected. If 'a' is	s '1', the BSR is used to	select the GPR bank.
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.			
Words	1			
Cycles	1 (2) Note: 3 cycles if skip and followed by a 2-word instruction. 4 cycles if skip and followed by a 3-word instruction.			

# Q Cycle Activity:

# If no skip:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation

If skip:

# **Instruction Set Summary**

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation
No operation	No operation	No operation	No operation

#### If skip and followed by 2-word instruction:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

# If skip and followed by 3-word instruction:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

#### Example:

HERE BTFSC FLAG, 1, 0 FALSE: TRUE:

#### Before Instruction

PC = address (HERE)

# After Instruction

If FLAG<1> = 0; PC = address (TRUE)
If FLAG<1> = 1; PC = address (FALSE)

BTFSS	Bit Test File, Skip if S	Bit Test File, Skip if Set		
Syntax	BTFSS f, b {,a}	BTFSS f, b {,a}		
Operands	$0 \le f \le 255$ $0 \le b \le 7$ $a \in [0, 1]$			
Operation	Skip if (f <b>) = 1</b>			
Status Affected	None	None		
Encoding	1010	bbba	ffff	ffff
Description	If bit 'b' in register 'f' is '1', then the next instruction is skipped. If bit 'b' is '1', then the next instruction fetched during the current instruction execution is discarded and a NOP is executed instead, making this a 2-cycle instruction.  If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank.  If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.			

continued			
BTFSS Bit Test File, Skip if Set			
Syntax	BTFSS f, b {,a}		
Words	1		
Cycles	1 (2) <b>Note:</b> 3 cycles if skip and followed by a 2-word instruction. 4 cycles if skip and followed by a 3-word instruction.		

# If no skip:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation

# If skip:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation
No operation	No operation	No operation	No operation

# If skip and followed by 2-word instruction:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

# If skip and followed by 3-word instruction:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

# Example:

HERE BTFSS FLAG, 1, 0 FALSE:
TRUE:

#### **Before Instruction**

PC = address (HERE)

#### After Instruction

If FLAG<1> = 0; PC = address (FALSE)
If FLAG<1> = 1; PC = address (TRUE)

BTG	Bit Toggle f				
Syntax	BTG f, b {,a}				
Operands	$0 \le f \le 255$ $0 \le b \le 7$ $a \in [0, 1]$				
Operation	$(\overline{f < b >}) \rightarrow f < b >$				
Status Affected	None				
Encoding	0111	bbba	ffff	ffff	
Description	Bit 'b' in data memory	location 'f' is inverted.			
	If 'a' is '0', the Access	Bank is selected. If 'a' is	1', the BSR is used to	select the GPR bank.	
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.				
Words	1				
Cycles	1				

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write register 'f'

Example: BTG PORTC, 4, 0

Before Instruction

**PORTC =** 0111 0101 [75h]

After Instruction

PORTC = 0110 0101 [65h]

BZ	Branch if Zero					
Syntax	BZ n					
Operands	-128 ≤ n ≤ 127					
Operation	If ZERO bit is '1' (PC) + 2 + 2n → PC					
Status Affected	None					
Encoding	1110	0000	nnnn	nnnn		
Description	added to the PC. Since	the PC will have incre	anch. The 2's compleme mented to fetch the next s then a 2-cycle instructi	instruction, the new		
Words	1					
Cycles	1 (2)					

# Q Cycle Activity:

# If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal 'n'	Process Data	Write to PC
No operation	No operation	No operation	No operation

# If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal 'n'	Process Data	No operation

Example: HERE BOV Jump

Before Instruction
PC = address (HERE)

After Instruction

If ZERO = 1; PC = address (Jump)
If ZERO = 0; PC = address (HERE + 2)

CALL	Subroutine Call				
Syntax	CALL k {,s}				
Operands	$0 \le k \le 1048575$ $s \in [0, 1]$				
Operation	$(PC) + 4 \rightarrow TOS \\ k \rightarrow PC < 20:1 > \\ \hline \frac{If \ s = 1}{(W) \rightarrow WREG\_CSHAD} \\ (STATUS) \rightarrow STATUS\_CSHAD \\ (BSR) \rightarrow BSR\_CSHAD$				
Status Affected	None				
Encoding	1110	110s	k <sub>7</sub> kkk	kkkk <sub>0</sub>	
1st word (k<7:0>) 2nd word (k<19:8>)	1111	k <sub>19</sub> kkk	kkkk	kkkk <sub>8</sub>	
Description	Subroutine call of entire 2-Mbyte memory range. First, return address (PC + 4) is pushed onto the return stack. If 's' = 1, the WREG, STATUS and BSR registers are also pushed into their respective shadow registers WREG_CSHAD, STATUS_CSHAD and BSR_CSHAD. If 's' = 0, no update occurs (default). Then, the 20-bit value 'k' is loaded into PC<20:1>. CALL is a 2-cycle instruction.				
Words	2				
Cycles	2				

# Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal 'k'<7:0>	PUSH PC to stack	Read literal 'k'<19:8> Write to PC

No energtion	No operation	No aparation	No operation
No operation	No operation	ivo operation	No operation

Example: HERE CALL THERE, 1

**Before Instruction** 

PC = address (HERE)

After Instruction

PC = address (THERE)
TOS = address (HERE + 4)
WREG\_CSHAD = (WREG)
BSR\_CSHAD = (BSR)
STATUS\_CSHAD = (STATUS)

CALLW	Subroutine Call using	y WREG			
Syntax	CALLW				
Operands	None				
Operation	$(PC) + 2 \rightarrow TOS$ $(W) \rightarrow PCL$ $(PCLATH) \rightarrow PCH$ $(PCLATU) \rightarrow PCU$				
Status Affected	None				
Encoding	0000	0000	0001	0100	
Description	First, the return address (PC + 2) is pushed onto the return stack. Next, the contents of W are written to PCL; the existing value is discarded. Then, the contents of PCLATH and PCLATU are latched into PCH and PCU respectively. The second cycle is executed as a NOP instruction while the new next instruction is fetched. Unlike CALL, there is no option to update W, STATUS or BSR.				
Words	1				
Cycles	2				

#### Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read WREG	PUSH PC to stack	No operation
No operation	No operation	No operation	No operation

Example: HERE CALLW

**Before Instruction** 

PC = address (HERE)

PCLATH = 10h

PCLATU = 00h

W = 06h

After Instruction

PC = address 001006h
TOS = address (HERE + 2)

PCLATH = 10h PCLATU = 00h W = 06h

CLRF	Clear f				
Syntax	CLRF f {,a}				
Operands	0 ≤ f ≤ 255 a ∈ [0, 1]				
Operation	$000h \rightarrow f$ $1 \rightarrow Z$				
Status Affected	Z				
Encoding	0110	101a	ffff	ffff	
Description	Clears the contents of	the specified register 'f'.			
	If 'a' is '0', the Access I	Bank is selected. If 'a' is	1', the BSR is used to	select the GPR bank.	
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.				
Words	1				
Cycles	1				

# Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write register 'f'

Example: CLRF FLAG\_REG, 1

Before Instruction FLAG\_REG = 5Ah

After Instruction FLAG\_REG = 00h

CLRWDT	Clear Watchdog Timer			
Syntax	CLRWDT			
Operands	None			
Operation	$000h \rightarrow WDT$ $1 \rightarrow \overline{TO}$ $1 \rightarrow \overline{PD}$			
Status Affected	TO, PD			
Encoding	0000	0000	0000	0100
Description	CLRWDT instruction resets the Watchdog Timer. It also resets the STATUS bits, and $\overline{\text{TO}}$ and $\overline{\text{PD}}$ are set.			
Words	1			

continued	continued				
CLRWDT	Clear Watchdog Timer				
Syntax	CLRWDT				
Cycles	1				

Q1	Q2	Q3	Q4
Decode	No operation	Process Data	No operation

Example: CLRWDT

Before Instruction WDT Counter = ?

After Instruction
WDT Counter = 00h

<u>TO</u> = 1

<del>PD</del> = 1

COMF	Complement f				
Syntax	COMF f {,d {,a}}				
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$	d ∈ [0, 1]			
Operation	$(\bar{f}) \rightarrow dest$				
Status Affected	N, Z				
Encoding	0001	11da	ffff	ffff	
Description		er 'f' are complemented. k in the register 'f' (defa	If 'd' is '0', the result is nult).	stored in W. If 'd' is '1',	
	If 'a' is '0', the Access I	Bank is selected. If 'a' is	s '1', the BSR is used to	select the GPR bank.	
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever $f \le 95$ (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.				
Words	1	1			
Cycles	1				

# Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination

Example: COMF REG0, 0, 0

Before Instruction REG = 13h After Instruction

**REG** = 13h

W = ECh

CPFSEQ	Compare f with W, skip if f = W				
Syntax	CPFSEQ f {,a}				
Operands	0 ≤ f ≤ 255 a ∈ [0, 1]				
Operation	(f) – (W), skip if (f) = (W (unsigned comparison)				
Status Affected	None				
Encoding	0110	001a	ffff	ffff	
Description	Compares the contents of data memory location 'f' to the contents of W by performing an unsigned subtraction. If the contents of 'f' are equal to the contents of WREG, then the fetched instruction is discarded and a $\mathtt{NOP}$ is executed instead, making this a 2-cycle instruction.				
	If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank.  If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.				
Words	1				
Cycles	1 (2) Note: 3 cycles if skip and followed by a 2-word instruction. 4 cycles if skip and followed by a 3-word instruction.				

# Q Cycle Activity:

# If no skip:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation

# If skip:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation
No operation	No operation	No operation	No operation

# If skip and followed by 2-word instruction:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

If skip and followed by 3-word instruction:

# **Instruction Set Summary**

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

#### Example:

HERE CPFSEQ REG, 0 NEQUAL: EQUAL:

# **Before Instruction**

PC = address (HERE)

W = ?

REG = ?

#### After Instruction

If REG = W; PC = address (EQUAL)

If REG ≠ W; PC = address (NEQUAL)

CPFSGT	Compare f with W, skip if f > W			
Syntax	CPFSGT f {,a}			
Operands	0 ≤ f ≤ 255 a ∈ [0, 1]			
Operation	(f) – (W), skip if (f) > (W) (unsigned comparison)			
Status Affected	None			
Encoding	0110	010a	ffff	ffff
Description	unsigned subtraction. I fetched instruction is dinstruction.	f the contents of 'f' are of iscarded and a NOP is e	on 'f' to the contents of N greater than the content xecuted instead, makin	s of WREG, then the g this a 2-cycle
	If 'a' is '0', the Access I	Bank is selected. If 'a' is	s '1', the BSR is used to	select the GPR bank.
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.			
Words	1			
Cycles	1 (2) Note: 3 cycles if skip a 3-word instruction.	nd followed by a 2-word	l instruction. 4 cycles if	skip and followed by a

# Q Cycle Activity:

# If no skip:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation

# If skip:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation
No operation	No operation	No operation	No operation

# If skip and followed by 2-word instruction:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

#### If skip and followed by 3-word instruction:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

#### Example:

HERE CPFSGT REG, 0 NGREATER: GREATER:

#### **Before Instruction**

PC = address (HERE)

W = ? REG = ?

#### After Instruction

If REG > W; PC = address (GREATER)
If REG  $\leq$  W; PC = address (NGREATER)

CPFSLT	Compare f with W, skip if f < W			
Syntax	CPFSLT f {,a}			
Operands	$0 \le f \le 255$ $a \in [0, 1]$			
Operation	(f) – (W), skip if (f) < (W) (unsigned comparison)			
Status Affected	None			
Encoding	0110 000a ffff ffff			

continued	
CPFSLT	Compare f with W, skip if f < W
Syntax	CPFSLT f {,a}
Description	Compares the contents of data memory location 'f' to the contents of W by performing an unsigned subtraction. If the contents of 'f' are less than the contents of WREG, then the fetched instruction is discarded and a $\mathtt{NOP}$ is executed instead, making this a 2-cycle instruction.
	If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank.
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.
Words	1
Cycles	1 (2) <b>Note:</b> 3 cycles if skip and followed by a 2-word instruction. 4 cycles if skip and followed by a 3-word instruction.

# If no skip:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation

# If skip:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation
No operation	No operation	No operation	No operation

# If skip and followed by 2-word instruction:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

# If skip and followed by 3-word instruction:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

# Example:

HERE CPFSLT REG, 1 NLESS: LESS:

#### **Before Instruction**

PC = address (HERE)

W = ?

REG = ?

#### After Instruction

If REG < W; PC = address (LESS) If REG ≥ W; PC = address (NLESS)

DAW	Decimal Adjust W Register				
Syntax	DAW				
Operands	None				
Operation	If $[(W<3:0>)>9]$ or $[DC=1]$ then $(W<3:0>)+6 \rightarrow W<3:0>$ ; else $(W<3:0>) \rightarrow W<3:0>$ ;  If $[(W<7:4>)+DC>9]$ or $[C=1]$ then $(W<7:4>)+6+DC \rightarrow W<7:4>$ ; else $(W<7:4>)+DC \rightarrow W<7:4>$				
Status Affected	С				
Encoding	0000	0000	0000	0111	
Description	DAW adjusts the 8-bit value in W, resulting from the earlier addition of two variables (each in packed BCD format) and produces a correct packed BCD result.				
Words	1				
Cycles	1				

#### Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read register W	Process Data	Write register W

#### Example 1: DAW

#### **Before Instruction**

W = A5h

C = 0

DC = 0

#### After Instruction

W = 05h

**C** = 1

**DC** = 0

Example 2: DAW

**Before Instruction** 

W = CEh

**C** = 0

**DC** = 0

After Instruction

W = 34h

**C** = 1

**DC** = 0

DECF	Decrement f				
Syntax	DECF f {,d {,a}}				
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$	d ∈ [0, 1]			
Operation	(f) – 1 → dest				
Status Affected	C, DC, N, OV, Z				
Encoding	0000	01da	ffff	ffff	
Description	_	Decrement register 'f'. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in the register 'f' (default).			
	If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bar				
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.				
Words	1	1			
Cycles	1				

# Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination

Example: DECF CNT, 1, 0

**Before Instruction** 

**CNT** = 01h

**Z** = 0

After Instruction

<u>CNT</u> = 00h

**Z** = 1

DECFSZ	Decrement f, skip if 0
Syntax	DECFSZ f {,d {,a}}
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$

continued	continued				
DECFSZ	Decrement f, skip if 0				
Syntax	DECFSZ f {,d {,a}	}			
Operation	$(f) - 1 \rightarrow dest, skip if respectively.$	esult = 0			
Status Affected	None				
Encoding	0010	11da	ffff	ffff	
Description		er 'f' are decremented. If ck in register 'f' (default)	'd' is '0', the result is pl	aced in W. If 'd' is '1',	
		ext instruction, which is ing it a 2-cycle instruction	already fetched, is disc on.	arded and a NOP is	
	If 'a' is '0', the Access I	Bank is selected. If 'a' is	s '1', the BSR is used to	select the GPR bank.	
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever $f \le 95$ (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.				
Words	1				
Cycles	1 (2) <b>Note:</b> 3 cycles if skip a 3-word instruction.	nd followed by a 2-word	I instruction. 4 cycles if	skip and followed by a	

# If no skip:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination

# If skip:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination
No operation	No operation No operation		No operation

# If skip and followed by 2-word instruction:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

# If skip and followed by 3-word instruction:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

# **Instruction Set Summary**

No operation	No operation	No operation	No operation

#### Example:

HERE DECFSZ CNT, 1, 1
GOTO LOOP
CONTINUE

#### **Before Instruction**

CNT = ?

PC = address (HERE)

# After Instruction

CNT = CNT - 1

If CNT = 0; PC = address (CONTINUE)
If CNT  $\neq$  0; PC = address (HERE + 2)

DCFSNZ	Decrement f, skip if not 0			
Syntax	DCFSNZ f {,d {,a}	}		
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$			
Operation	$(f) - 1 \rightarrow dest, skip if respectively.$	esult ≠ 0		
Status Affected	None			
Encoding	0100	11da	ffff	ffff
Description	The contents of register 'f' are decremented. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default).  If the result is not '0', the next instruction, which is already fetched, is discarded and a NOP is executed instead, making it a 2-cycle instruction.  If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank.  If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.			iscarded and a NOP select the GPR bank. perates in Indexed
Words	1			
Cycles	1 (2) Note: 3 cycles if skip and followed by a 2-word instruction. 4 cycles if skip and followed by a 3-word instruction.			

# Q Cycle Activity:

# If no skip:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination

# If skip:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination

# **Instruction Set Summary**

No operation	No operation	No operation	No operation

# If skip and followed by 2-word instruction:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

# If skip and followed by 3-word instruction:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

#### Example:

HERE DCFSNZ TEMP, 1, 0 ZERO: NZERO:

#### **Before Instruction**

TEMP = ?

PC = address (HERE)

#### After Instruction

TEMP = TEMP - 1

If TEMP = 0; PC = address (ZER0)
If TEMP ≠ 0; PC = address (NZERO)

GOTO	Unconditional Brancl	Unconditional Branch				
Syntax	GOTO k					
Operands	0 ≤ k ≤ 1048575					
Operation	k → PC<20:1>					
Status Affected	None	None				
Encoding	1110	1110   1111   k7kkk   kkkk0				
1st word (k<7:0>) 2nd word (k<19:8>)	1111	1111 k <sub>19</sub> kkk kkkk kkkk <sub>8</sub>				
Description	GOTO allows an unconditional branch anywhere within entire 2-Mbyte memory range. The 20-bit value 'k' is loaded into PC<20:1>. GOTO is always a 2-cycle instruction.					
Words	2					
Cycles	2					

# PIC18F26/46/56Q84

# **Instruction Set Summary**

Q1	Q2	Q3	Q4
Decode	Read literal 'k'<7:0>	No operation	Read literal 'k'<19:8> Write to PC
No operation	No operation	No operation	No operation

**Example:** HERE GOTO THERE

**Before Instruction** 

PC = address (HERE)

**After Instruction** 

PC = address (THERE)

INCF	Increment f			
Syntax	INCF f {,d {,a}}			
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$			
Operation	(f) + 1 → dest			
Status Affected	C, DC, N, OV, Z			
Encoding	0010	10da	ffff	ffff
Description		er 'f' are incremented. If ' k in the register 'f' (defa		ored in W. If 'd' is '1',
	If 'a' is '0', the Access	Bank is selected. If 'a' is	'1', the BSR is used to	select the GPR bank.
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.			
Words	1			
Cycles	1			

# Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination

Example: INCF CNT, 1, 0

Before Instruction

 $\mathsf{CNT} = \mathtt{FFh}$ 

**Z** = 0

C = ?

DC = ?

After Instruction

**CNT =** 00h

**Z** = 1

C = 1 DC = 1

INCFSZ	Increment f, skip if 0			
Syntax	INCFSZ f {,d {,a}	}		
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$			
Operation	(f) + 1 → dest, skip if re	esult = 0		
Status Affected	None			
Encoding	0011	11da	ffff	ffff
Description	The contents of register 'f' are incremented. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default).  If the result is '0', the next instruction, which is already fetched, is discarded and a NOP is executed instead, making it a 2-cycle instruction.  If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank.			
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.			
Words	1			
Cycles	1 (2) <b>Note:</b> 3 cycles if skip a 3-word instruction.	nd followed by a 2-word	I instruction. 4 cycles if s	skip and followed by a

# Q Cycle Activity:

# If no skip:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination

# If skip:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination
No operation	No operation	No operation	No operation

# If skip and followed by 2-word instruction:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

If skip and followed by 3-word instruction:

# **Instruction Set Summary**

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

#### Example:

HERE INCFSZ CNT, 1, 0 NZERO: ZERO:

**Before Instruction** 

CNT = ?

PC = address (HERE)

After Instruction

CNT = CNT + 1

If CNT = 0; PC = address (ZERO)
If CNT ≠ 0; PC = address (NZERO)

INFSNZ	Increment f, skip if not 0			
Syntax	INFSNZ f {,d {,a}	}		
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$			
Operation	(f) + 1 $\rightarrow$ dest, skip if re	esult ≠ 0		
Status Affected	None			
Encoding	0100	10da	ffff	ffff
Description	The contents of register 'f' are incremented. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default).  If the result is not '0', the next instruction, which is already fetched, is discarded and a NOP is executed instead, making it a 2-cycle instruction.  If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank.  If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.			
Words	1			
Cycles	1 (2) <b>Note:</b> 3 cycles if skip a 3-word instruction.	nd followed by a 2-word	d instruction. 4 cycles if s	skip and followed by a

# Q Cycle Activity:

If no skip:

Q1	Q2	Q3	Q4

# **Instruction Set Summary**

Decode	Read register 'f'	Process Data	Write to destination
			'

# If skip:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination
No operation	No operation	No operation	No operation

# If skip and followed by 2-word instruction:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

# If skip and followed by 3-word instruction:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

# Example:

HERE INFSNZ REG, 1, 0 ZERO: NZERO:

#### **Before Instruction**

REG = ?

PC = address (HERE)

#### After Instruction

REG = REG + 1

If REG = 0; PC = address (ZER0)
If REG ≠ 0; PC = address (NZERO)

IORLW	Inclusive OR literal w	Inclusive OR literal with W				
Syntax	IORLW k	IORLW k				
Operands	0 ≤ k ≤ 255	0 ≤ k ≤ 255				
Operation	(W) .OR. $k \rightarrow W$	$(W)$ .OR. $k \rightarrow W$				
Status Affected	N, Z	N, Z				
Encoding	0000	1001	kkkk	kkkk		
Description	The contents of W are	The contents of W are ORed with the 8-bit literal 'k'. The result is placed in W.				
Words	1					
Cycles	1					

Q1	Q2	Q3	Q4
Decode	Read literal 'k'	Process Data	Write to W

Example: IORLW 35h

**Before Instruction** 

W = 9Ah

After Instruction

W = B5h

IORWF	Inclusive OR W with 1	Inclusive OR W with f				
Syntax	IORWF f {,d {,a}}					
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$	d ∈ [0, 1]				
Operation	(W) .OR. (f) $\rightarrow$ dest					
Status Affected	N, Z	N, Z				
Encoding	0001	00da	ffff	ffff		
Description	Inclusive OR W with re stored back in the regis	gister 'f'. If 'd' is '0', the ster 'f' (default).	result is stored in W. If	'd' is '1', the result is		
	If 'a' is '0', the Access I	Bank is selected. If 'a' is	s '1', the BSR is used to	select the GPR bank.		
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.					
Words	1					
Cycles	1					

# Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination

Example: IORWF RESULT, 0, 1

**Before Instruction** 

RESULT = 13h

W = 91h

After Instruction

RESULT = 13h

W = 93h

LFSR	Load FSR				
Syntax	LFSR f <sub>n</sub> , k				
Operands	$0 \le f_n \le 2$ $0 \le k \le 16383$				
Operation	$k \rightarrow FSRf_n$				
Status Affected	None				
Encoding	1110	1110	00f <sub>n</sub> f <sub>n</sub>	k <sub>13</sub> kkk <sub>10</sub>	
	1111	00k <sub>9</sub> k	kkkk	kkkk <sub>0</sub>	
Description	The 14-bit literal 'k' is loaded into the File Select Register 'f <sub>n</sub> '.				
Words	2				
Cycles	2				

Q1	Q2	Q3	Q4
Decode	Read literal 'k'<13:10>	Process Data	Write literal 'k'<13:10> to FSRf <sub>n</sub> <13:10>
No operation	Read literal 'k'<9:0>	No operation	Write literal 'k'<9:0> to FSRf <sub>n</sub> <9:0>

Example: LFSR 2, 3ABh

**Before Instruction** 

FSR2H = ? FSR2L = ?

After Instruction

FSR2H = 03h FSR2L = ABh

MOVF	Move f	Move f			
Syntax	MOVF f {,d {,a}}				
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$	$d \in [0, 1]$			
Operation	$(f) \rightarrow dest$	(f) → dest			
Status Affected	N, Z	N, Z			
Encoding	0101	00da	ffff	ffff	
Description	'd' is '1', the result is st If 'a' is '0', the Access I If 'a' is '0' and the extel Literal Offset Addressir	The contents of register 'f' are moved to a destination. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in the register 'f' (default).  If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank.  If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.			

continued	
MOVF	Move f
Syntax	MOVF f {,d {,a}}
Words	1
Cycles	1

Q1	Q2	Q3	Q4	
Decode	Read register 'f'	Process Data	Write to destination	

Example: MOVF REG, 0, 0

**Before Instruction** 

**REG =** 22h

W = FFh

After Instruction

**REG =** 22h

W = 22h

MOVFF	Move f to f				
Syntax	MOVFF f <sub>s</sub> , f <sub>d</sub>				
Operands	$0 \le f_s \le 4095$ $0 \le f_d \le 4095$				
Operation	$(f_s) \rightarrow f_d$				
Status Affected	None				
Encoding	1100	$f_sf_sf_sf_s$	$f_sf_sf_sf_s$	$f_sf_sf_sf_s$	
	1111	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f <sub>d</sub>	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub>	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f	
Description	The contents of source register ' $f_s$ ' are moved to destination register ' $f_d$ '. Location of source ' $f_s$ ' can be anywhere in the 4096-byte data space (000h to FFFh) and location of destination ' $f_d$ ' can also be anywhere from 000h to FFFh.  MOVFF is particularly useful for transferring a data memory location to a peripheral register (such as the transmit buffer or an I/O port).				
	register.	cannot use the PCL, TC	DSU, TOSH or TOSL as	the destination	
	Note:  MOVFF has curtailed the source and destination range to the lower 4 Kbyte space of memory (Banks 1 through 15). For everything else, use MOVFFL.				
Words	2				
Cycles	2				

Q1	Q2	Q3	Q4

# PIC18F26/46/56Q84

# **Instruction Set Summary**

Decode	Read register 'f <sub>s</sub> '	Process Data	No operation
Decode	No operation No dummy read	No operation	Write register 'f <sub>d</sub> '

Example: MOVFF REG1, REG2

**Before Instruction** 

Address of REG1 = 100h

Address of REG2 = 200h

**REG1 =** 33h

**REG2 =** 11h

After Instruction

Address of REG1 = 100h

Address of REG2 = 200h

**REG1 =** 33h

**REG2 =** 33h

MOVFFL	Move f to f (Long Rar	Move f to f (Long Range)				
Syntax	MOVFFL f <sub>s</sub> , f <sub>d</sub>					
Operands	$0 \le f_s \le 16383$ $0 \le f_d \le 16383$					
Operation	$(f_s) \rightarrow f_d$					
Status Affected	None					
Encoding	0000	0000	0110	f <sub>s</sub> f <sub>s</sub> f <sub>s</sub> f <sub>s</sub>		
	1111	f <sub>s</sub> f <sub>s</sub> f <sub>s</sub> f <sub>s</sub>	f <sub>s</sub> f <sub>s</sub> f <sub>s</sub> f <sub>s</sub>	f <sub>s</sub> f <sub>s</sub> f <sub>d</sub> f <sub>d</sub>		
	1111	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f <sub>d</sub>	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f <sub>d</sub>	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f		
Description	'f <sub>s</sub> ' can be anywhere in destination 'f <sub>d</sub> ' can also be W (a useful special MOVFFL is particularly (such as the transmit b	The contents of source register 'f <sub>s</sub> ' are moved to destination register 'f <sub>d</sub> '. Location of source 'f <sub>s</sub> ' can be anywhere in the 16 Kbyte data space (0000h to 3FFFh) and location of destination 'f <sub>d</sub> ' can also be anywhere from 0000h to 3FFFh. Either source or destination can be W (a useful special situation).  MOVFFL is particularly useful for transferring a data memory location to a peripheral register (such as the transmit buffer or an I/O port).  The MOVFFL instruction cannot use the PCL, TOSU, TOSH or TOSL as the destination				
	register.					
Words	3	3				
Cycles	3					

Q1	Q2	Q3	Q4
Decode	No operation	No operation	No operation
Decode	Read register 'f <sub>s</sub> '	Process Data	No operation
Decode	No operation No dummy read	No operation	Write register 'f <sub>d</sub> '

Example: MOVFFL 2000h, 200Ah

**Before Instruction** 

Contents of 2000h = 33h Contents of 200Ah = 11h

After Instruction

Contents of 2000h = 33h Contents of 200Ah = 33h

MOVLB	Move literal to BSR	Move literal to BSR			
Syntax	MOVLB k				
Operands	0 ≤ k ≤ 63	0 ≤ k ≤ 63			
Operation	$k \rightarrow BSR$	$k \rightarrow BSR$			
Status Affected	None	None			
Encoding	0000	0001	00kk	kkkk	
Description		The 6-bit literal 'k' is loaded into the Bank Select Register (BSR<5:0>). The value of BSR<7:6> always remains '0'.			
Words	1				
Cycles	1				

# Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal 'k'	Process Data	Write to BSR

Example: MOVLB 5

**Before Instruction** 

**BSR =** 02h

After Instruction

**BSR** = 05h

MOVLW	Move literal to W			
Syntax	MOVLW k			
Operands	0 ≤ k ≤ 255			
Operation	$k \rightarrow W$			
Status Affected	None			
Encoding	0000	1110	kkkk	kkkk
Description	The 8-bit literal 'k' is lo	The 8-bit literal 'k' is loaded into W.		
Words	1			
Cycles	1			

-				
	Q1	Q2	Q3	Q4
	Decode	Read literal 'k'	Process Data	Write to W

Example: MOVLW 5Ah

**Before Instruction** 

W = ?

After Instruction

**W** = 5Ah

MOVWF	Move W to f	Move W to f		
Syntax	MOVWF f {,a}	MOVWF f {,a}		
Operands	$0 \le f \le 255$ $a \in [0, 1]$	· · · <del>- · ·</del>		
Operation	$(W) \rightarrow f$	$(W) \rightarrow f$		
Status Affected	None			
Encoding	0110	111a	ffff	ffff
Description	Move data from W to re	egister 'f'. Location 'f' ca	an be anywhere in the 2	56-byte bank.
	If 'a' is '0', the Access I	If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank.		
	Literal Offset Addressir	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever $f \le 95$ (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.		
Words	1	1		
Cycles	1	I		

# Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read W	Process Data	Write register 'f'

Example: MOVWF REG, 0

**Before Instruction** 

W = 4Fh

REG = FFh

After Instruction

W = 4 Fh

REG = 4Fh

MULLW	Multiply literal with W	
Syntax	MULLW k	
Operands	0 ≤ k ≤ 255	
Operation	(W) $x k \rightarrow PRODH:PRODL$	

continued	continued			
MULLW	Multiply literal with W			
Syntax	MULLW k			
Status Affected	None			
Encoding	0000 1101 kkkk kkkk			
Description	An unsigned multiplication is carried out between the contents of W and the 8-bit literal 'k'. The 16-bit result is placed in the PRODH:PRODL register pair. PRODH contains the high byte. W is unchanged.			
	None of the Status flags are affected. Note that neither overflow nor carry is possible in this operation. A zero result is possible but not detected.			
Words	1			
Cycles	1			

Q1	Q2	Q3	Q4
Decode	Read literal 'k'	Process Data	Write registers PRODH:PRODL

Example: MULLW 0C4h

**Before Instruction** 

W = E2h

PRODH = ?

PRODL = ?

After Instruction

W = E2h

PRODH = ADh

PRODL = 08h

MULWF	Multiply W with f			
Syntax	MULWF f {,a}	MULWF f {,a}		
Operands	0 ≤ f ≤ 255 a ∈ [0, 1]			
Operation	(W) x (f) $\rightarrow$ PRODH:PF	(W) $x(f) \rightarrow PRODH:PRODL$		
Status Affected	None			
Encoding	0000	001a	ffff	ffff

continued	
MULWF	Multiply W with f
Syntax	MULWF f {,a}
Description	An unsigned multiplication is carried out between the contents of W and the register file location 'f'. The 16-bit result is placed in the PRODH:PRODL register pair. PRODH contains the high byte. Both W and 'f' are unchanged.
	None of the Status flags are affected. Note that neither overflow nor carry is possible in this operation. A zero result is possible but not detected.
	If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank.
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.
Words	1
Cycles	1

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write registers PRODH:PRODL

Example: MULWF REG, 1

# **Before Instruction**

W = C4h

REG = B5h

PRODH = ?

PRODL = ?

# After Instruction

W = C4h

REG = B5h

PRODH = 8Ah

PRODL = 94h

NEGF	Negate f			
Syntax	NEGF f {,a}			
Operands	0 ≤ f ≤ 255 a ∈ [0, 1]			
Operation	$(\overline{f}) + 1 \rightarrow f$			
Status Affected	N, OV, C, DC, Z			
Encoding	0110	110a	ffff	ffff

continued	continued			
NEGF	Negate f			
Syntax	NEGF f {,a}			
Description	Location 'f' is negated using two's complement. The result is placed in the data memory location 'f'.			
	If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank.			
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.			
Words	1			
Cycles	1			

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write register 'f'

Example: NEGF REG, 1

**Before Instruction** 

**REG** = 0011 1010 [3Ah]

After Instruction

REG = 1100 0110 [C6h]

NOP	No Operation	No Operation				
Syntax	NOP					
Operands	None					
Operation	No operation	No operation				
Status Affected	None					
Encoding	0000	0000	0000	0000		
	1111	xxxx	xxxx	xxxx		
Description	No operation.			,		
Words	1					
Cycles	1					

# Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	No operation	No operation	No operation

Example: None.

POP	Pop Top of Return St	Pop Top of Return Stack				
Syntax	POP					
Operands	None					
Operation	(TOS) → bit bucket	(TOS) → bit bucket				
Status Affected	None	None				
Encoding	0000	0000	0000	0110		
Description	the previous value that enable the user to prop	The TOS value is pulled off the return stack and is discarded. The TOS value then becomes the previous value that was pushed onto the return stack. This instruction is provided to enable the user to properly manage the return stack to incorporate a software stack. (See PUSH instruction description).				
Words	1	1				
Cycles	1					

Q1	Q2	Q3	Q4
Decode	No operation	POP TOS value	No operation

### Example:

POP GOTO NEW

# **Before Instruction**

**TOS =** 0031A2h

Stack (1 level down) = 014332h

# After Instruction

TOS = 014332h
PC = address (NEW)

PUSH	Push Top of Return Stack				
Syntax	PUSH				
Operands	None				
Operation	(PC) + 2 → TOS	$(PC) + 2 \rightarrow TOS$			
Status Affected	None				
Encoding	0000	0000	0000	0101	
Description	The PC + 2 is pushed onto the top of the return stack. The previous TOS value is pushed down on the stack. This instruction allows implementing a software stack by modifying TOS and then pushing it onto the return stack. (See POP instruction description).				
Words	1				
Cycles	1				

Q1	Q2	Q3	Q4
Decode	PUSH PC + 2 onto return stack	No operation	No operation

Example: PUSH

**Before Instruction** 

**TOS =** 00345Ah

**PC =** 000124h

After Instruction

TOS = 000126h

**PC** = 000126h

Stack (1 level down) = 00345Ah

RCALL	Relative Call			
Syntax	RCALL n			
Operands	-1024 ≤ n ≤ 1023			
Operation	$(PC) + 2 \rightarrow TOS$ $(PC) + 2 + 2n \rightarrow PC$			
Status Affected	None			
Encoding	1101	1nnn	nnnn	nnnn
Description	is pushed onto the stad	ck. Then, add the 2's co ted to fetch the next inst	current location. First, re mplement number '2n' t truction, the new addres	o the PC. Since the
Words	1			
Cycles	2			

#### Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal 'n' PUSH PC to stack	Process Data	Write to PC
No operation	No operation	No operation	No operation

Example: HERE RCALL Jump

**Before Instruction** 

PC = address (HERE)

After Instruction

PC = address (Jump)

TOS = address (HERE + 2)

RESET	Reset	Reset			
Syntax	RESET				
Operands	None	None			
Operation	Reset all registers and	Reset all registers and flags that are affected by a MCLR Reset.			
Status Affected	All				
Encoding	0000	0000	1111	1111	
Description	This instruction provide	This instruction provides a way to execute a MCLR Reset by software.			
Words	1				
Cycles	1				

Q1	Q2	Q3	Q4
Decode	Start Reset	No operation	No operation

Example: RESET

**Before Instruction** All Registers = ? All Flags = ?

After Instruction
All Registers = Reset Value All Flags = Reset Value

RETFIE	Return from Interrupt				
Syntax	RETFIE {s}				
Operands	s ∈ [0, 1]				
Operation	FSR2H, FSR2L, PROI shadow registers.	DH, PRODL, PCLATH a	JS, BSR, FSR0H, FSR0 nd PCLATU registers fro gister.	, , , , , ,	
Status Affected	STAT bits in INTCONx register				
Encoding	0000	0000	0001	000s	

DS40002259A-page 1029 **Preliminary Datasheet** © 2020 Microchip Technology Inc.

continued	
RETFIE	Return from Interrupt
Syntax	RETFIE {s}
Description	Return from interrupt. Stack is popped and Top-of-Stack (TOS) is loaded into the PC. Interrupts are enabled by setting either the high or low priority Global Interrupt Enable bit.
	If 's' = 1, the contents of the shadow registers WREG_SHAD, STATUS_SHAD, BSR_SHAD, FSR0H_SHAD, FSR0L_SHAD, FSR1H_SHAD, FSR1L_SHAD, FSR2H_SHAD, FSR2L_SHAD, PRODH_SHAD, PRODL_SHAD, PCLATH_SHAD and PCLATU_SHAD are loaded into corresponding registers. There are two sets of shadow registers, main context and low context. The set retrieved on RETFIE instruction execution depends on what the state of operation of the CPU was when RETFIE was executed.  If 's' = 0, no update of these registers occurs (default).  The upper and high address latches (PCLATU/H) remain unchanged.
Words	1
Cycles	2

Q1	Q2	Q3	Q4
Decode	No operation	Process Data	POP PC from stack
No operation	No operation	No operation	No operation

Example: RETFIE 1

After Instruction

PC = (TOS)

WREG = (WREG\_SHAD)

BSR = (BSR\_SHAD)

STATUS = (STATUS SHAD)

FSR0H/L = (FSR0H/L\_SHAD)

FSR1H/L = (FSR1H/L\_SHAD) FSR2H/L = (FSR2H/L\_SHAD)

PRODH/L = (PRODH/L\_SHAD)

PCLATH/U = (PCLATH/U\_SHAD)

RETLW	Return literal to W	Return literal to W		
Syntax	RETLW k			
Operands	0 ≤ k ≤ 255	0 ≤ k ≤ 255		
Operation	$k \rightarrow W$ (TOS) $\rightarrow$ PC PCLATU, PCLATH are			
Status Affected	None			
Encoding	0000	1100	kkkk	kkkk
Description	W is loaded with the 8-bit literal 'k'. The Program Counter is loaded from the top of the stack (the return address). The upper and high address latches (PCLATU/H) remain unchanged.			
Words	1			

continued	
RETLW	Return literal to W
Syntax	RETLW k
Cycles	2

Q1	Q2	Q3	Q4
Decode	Read literal 'k'	Process Data	POP PC from stack Write to W
No operation	No operation	No operation	No operation

#### Example:

```
CALL TABLE ; W contains table offset value

BACK ; W now has table value (after RETLW)

:
:
TABLE
ADDWF PCL ; W = offset
RETLW k0 ; Begin table
RETLW k1 ;
:
RETLW kn ; End of table
```

#### **Before Instruction**

W = 07h

#### After Instruction

W = value of kn

RETURN	Return from Subrout	ine		
Syntax	RETURN {s}			
Operands	s ∈ [0, 1]			
Operation	$ \begin{split} &(\text{TOS}) \to \text{PC} \\ &\frac{\text{If s} = 1}{(\text{WREG\_CSHAD})} \to \text{WREG} \\ &(\text{STATUS\_CSHAD}) \to \text{STATUS} \\ &(\text{BSR\_CSHAD}) \to \text{BSR} \\ &\text{PCLATU, PCLATH are unchanged} \end{split} $			
Status Affected	None			
Encoding	0000	0000	0001	001s
Description	Return from subroutine. The stack is popped and the top of the stack (TOS) is loaded into the Program Counter. If 's'= $1$ , the contents of the shadow registers WREG_CSHAD, STATUS_CSHAD and BSR_CSHAD, are loaded into their corresponding registers. If 's' = $0$ , no update of these registers occurs (default). The upper and high address latches (PCLATU/H) remain unchanged.			
Words	1			
Cycles	2			

Q1	Q2	Q3	Q4
Decode	No operation	Process Data	POP PC from stack
No operation	No operation	No operation	No operation

Example: RETURN 1

After Instruction PC = (TOS) WREG = (WREG\_CSHAD)

 $BSR = (B\dot{S}R\_CSHAD)$ 

STATUS = (STATUS\_CSHAD)

RLCF	Rotate Left f through	Carry		
Syntax	RLCF f {,d {,a}}			
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$	d ∈ [0, 1]		
Operation	$(f) \rightarrow dest$ $(f<7>) \rightarrow C$ $(C) \rightarrow dest<0>$			
Status Affected	C, N, Z			
Encoding	0011	01da	ffff	ffff
Description	the result is stored in V  If 'a' is '0', the Access  If 'a' is '0' and the exte  Literal Offset Addressi	er 'f' are rotated one bit to V. If 'd' is '1', the result is Bank is selected. If 'a' is noted instruction set is eng mode whenever f ≤ 9 Literal Offset Mode for	s stored back in the reg s '1', the BSR is used to nabled, this instruction of (5Fh). See Byte-Orie	ister 'f' (default). select the GPR bank. operates in Indexed
Words	1			
Cycles	1			

# Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination

Example: RLCF REG, 0, 0

**Before Instruction** 

**REG** = 1110 0110 [E6h]

W = ?C = 0

REG = 1110 0110 [E6h] W = 1100 1100 [CCh]

**C** = 1

RLNCF	Rotate Left f (No Carr	Rotate Left f (No Carry)		
Syntax	RLNCF f {,d {,a}}			
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$	d ∈ [0, 1]		
Operation	$(f) \rightarrow dest$ $(f<7>) \rightarrow dest<0>$			
Status Affected	N, Z			
Encoding	0100	01da	ffff	ffff
Description	The contents of register 'f' are rotated one bit to the left. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in the register 'f' (default).			
	If 'a' is '0', the Access	Bank is selected. If 'a' is	1', the BSR is used to	select the GPR bank.
	Literal Offset Addressi	nded instruction set is e ng mode whenever f ≤ 9 Literal Offset Mode for regist	5 (5Fh). See Byte-Orie details.	•
Words	1			
Cycles	1			

# Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination

Example: RLNCF REG, 1, 0

**Before Instruction** 

**REG =** 1010 1011 [ABh]

After Instruction

REG = 0101 0111 [57h]

RRCF	Rotate Right f through Carry
Syntax	RRCF f {,d {,a}}
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$
Operation	$(f) \rightarrow dest$ $(f<0>) \rightarrow C$ $(C) \rightarrow dest<7>$

continued	continued			
RRCF	Rotate Right f throug	h Carry		
Syntax	RRCF f {,d {,a}}			
Status Affected	C, N, Z			
Encoding	0011	00da	ffff	ffff
Description	The contents of register 'f' are rotated one bit to the right through the CARRY flag. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in the register 'f' (default).  If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank.  If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.			
Words	1			
Cycles	1			

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination

Example: RRCF REG, 0, 0

**Before Instruction** 

**REG** = 1110 0110 [E6h]

W = ?

C = 0

After Instruction

**REG** = 1110 0110 [E6h]

W = 0111 0011 [73h]

C = 0

RRNCF	Rotate Right f (No Ca	Rotate Right f (No Carry)			
Syntax	RRNCF f {,d {,a}}	RRNCF f {,d {,a}}			
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$	$d \in [0, 1]$			
Operation	$(f) \rightarrow dest$ $(f<0>) \rightarrow dest<7>$	(f <n>) → dest<n-1> (f&lt;0&gt;) → dest&lt;7&gt;</n-1></n>			
Status Affected	N, Z				
Encoding	0100	00da	ffff	ffff	

continued		
RRNCF	Rotate Right f (No Carry)	
Syntax	RRNCF f {,d {,a}}	
Description	The contents of register 'f' are rotated one bit to the right. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in the register 'f' (default).	
	If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank.	
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.	
	register f →	
Words	1	
Cycles	1	

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination

Example 1: RRNCF REG, 1, 0

**Before Instruction** 

**REG** = 1101 0111 [D7h]

After Instruction

**REG** = 1110 1011 [EBh]

Example 2: RRNCF REG, 0, 0

**Before Instruction** 

**REG** = 1101 0111 [D7h]

W = ?

After Instruction

**REG =** 1101 0111 [D7h]

**W** = 1110 1011 [EBh]

SETF	Set f			
Syntax	SETF f {,a}			
Operands	0 ≤ f ≤ 255 a ∈ [0, 1]			
Operation	$\texttt{FFh} \to f$	$\texttt{FFh} \to f$		
Status Affected	None			
Encoding	0110	100a	ffff	ffff

continued			
SETF	Set f		
Syntax	SETF f {,a}		
Description	The contents of the specified register 'f' are set to FFh.		
	If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank.		
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.		
Words	1		
Cycles	1		

Q1	Q2	Q3	Q4	
Decode	Read register 'f'	Process Data	Write register 'f'	

Example: SETF REG, 1

Before Instruction REG = 5Ah

After Instruction REG = FFh

SLEEP	Enter Sleep mode	Enter Sleep mode			
Syntax	SLEEP				
Operands	None				
Operation	$00h \rightarrow WDT$ $1 \rightarrow \overline{TO}$ $0 \rightarrow \overline{PD}$	1 → <del>TO</del>			
Status Affected	TO, PD				
Encoding	0000	0000	0000	0011	
Description	The Power-down Status bit $(\overline{PD})$ is cleared. The Time-out Status bit $(\overline{TO})$ is set. Watchdog Timer is cleared. The processor is put into Sleep mode with the oscillator stopped.				
Words	1	1			
Cycles	1				

# Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	No operation	Process Data	Go to Sleep

Example: SLEEP

**Before Instruction** 

TO = ?

 $\overline{PD} = ?$ 

After Instruction

TO = 1 †
PD = 0

† If WDT causes wake-up, this bit is cleared.

SUBFSR	Subtract Literal from FSR			
Syntax	SUBFSR f <sub>n</sub> , k			
Operands	$0 \le k \le 63$ $f_n \in [0, 1, 2]$			
Operation	$(FSRf_n) - k \rightarrow FSRf_n$			
Status Affected	None			
Encoding	1110 1001 f <sub>n</sub> f <sub>n</sub> kk kkkk			kkkk
Description	The 6-bit literal 'k' is subtracted from the contents of the FSR specified by 'f <sub>n</sub> '.			
Words	1			
Cycles	1			

# Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal 'k'	Process Data	Write to FSR

Example: SUBFSR 2, 23h

**Before Instruction FSR2** = 03FFh

**After Instruction** 

FSR2 = 03DCh

SUBFWB	Subtract f from W with borrow			
Syntax	SUBFWB f {,d {,a}	-}		
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$			
Operation	$(W)-(f)-(\overline{C})\to dest$			
Status Affected	N, OV, C, DC, Z			
Encoding	0101	01da	ffff	ffff

continued				
SUBFWB	Subtract f from W with borrow			
Syntax	SUBFWB f {,d {,a}}			
Description	Subtract register 'f' and CARRY flag (borrow) from W (2's complement method). If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in the register 'f' (default).			
	If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank.			
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.			
Words	1			
Cycles	1			

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination

Example 1: SUBFWB REG, 1, 0

#### **Before Instruction**

**REG** = 03h

W = 02h

C = 1

# After Instruction

REG = FFh (2's complement)

W = 02h

C = 0

**Z** = 0

N = 1 (result is negative)

Example 2: SUBFWB REG, 0, 0

### **Before Instruction**

**REG** = 02h

W = 05h

**C** = 1

#### After Instruction

**REG =** 02h

W = 03h

**C** = 1

**Z** = 0

N = 0 (result is positive)

Example 3: SUBFWB REG, 1, 0

#### **Before Instruction**

**REG** = 01h

W = 02h

C = 0

**REG** = 00h

W = 02h

**C** = 1

Z = 1 (result is zero)

N = 0

SUBLW	Subtract W from litera	Subtract W from literal				
Syntax	SUBLW k					
Operands	0 ≤ k ≤ 255	0 ≤ k ≤ 255				
Operation	$k - (W) \rightarrow W$	$k - (W) \rightarrow W$				
Status Affected	N, OV, C, DC, Z	N, OV, C, DC, Z				
Encoding	0000	1000	kkkk	kkkk		
Description	W is subtracted from the	W is subtracted from the 8-bit literal 'k'. The result is placed in W.				
Words	1					
Cycles	1					

# Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal 'k'	Process Data	Write to W

Example 1: SUBLW 02h

# **Before Instruction**

W = 01h

C = ?

#### After Instruction

W = 01h

C = 1 (result is positive)

**Z** = 0

**N** = 0

Example 2: SUBLW 02h

#### **Before Instruction**

W = 02h

C = ?

# After Instruction

W = 00h

**C** = 1

Z = 1 (result is zero)

N = 0

# Example 3: SUBLW 02h

#### **Before Instruction**

W = 03h

C = ?

W = FFh (2's complement)

C = 0

**Z** = 0

N = 1 (result is negative)

SUBWF	Subtract W from f			
Syntax	SUBWF f {,d {,a}}			
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$			
Operation	$(f) - (W) \rightarrow dest$			
Status Affected	N, OV, C, DC, Z			
Encoding	0101	11da	ffff	ffff
Description		er 'f' (2's complement m ored back in the registe		esult is stored in W. If
	If 'a' is '0', the Access	Bank is selected. If 'a' is	1', the BSR is used to	select the GPR bank.
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever $f \le 95$ (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.			
Words	1			
Cycles	1			

#### Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination

Example 1: SUBWF REG, 1, 0

**Before Instruction** 

**REG** = 03h

W = 02h

C = ?

After Instruction

REG = 01h (2's complement)

W = 02h

C = 1 (result is positive)

**Z** = 0

N = 0

Example 2: SUBWF REG, 0, 0

**Before Instruction** 

**REG =** 02h

W = 02h

C = ?

**REG** = 02h

W = 00h

**C** = 1

Z = 1 (result is zero)

N = 0

Example 3: SUBWF REG, 1, 0

**Before Instruction** 

**REG** = 01h

W = 02h

C = ?

After Instruction

REG = FFh (2's complement)

W = 02h

C = 0

**Z** = 0

N = 1 (result is negative)

SUBWFB	Subtract W from f wit	h Borrow		
Syntax	SUBWFB f {,d {,a}	-}		
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$			
Operation	$(f) - (W) - (\overline{C}) \rightarrow dest$			
Status Affected	N, OV, C, DC, Z			
Encoding	0101	10da	ffff	ffff
Description		ARRY flag (borrow) from in W. If 'd' is '1', the res		
	If 'a' is '0', the Access	Bank is selected. If 'a' is	1', the BSR is used to	select the GPR bank.
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Inde Literal Offset Addressing mode whenever $f \le 95$ (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.			
Words	1			
Cycles	1			

# Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination

Example 1: SUBWFB REG, 1, 0

**Before Instruction** 

REG = 19h (0001 1001)

W = 0Dh (0000 1101)

**C** = 1

REG = 0Ch (0000 1100)

W = 0Dh (0000 1101)

C = 1 (result is positive)

**Z** = 0

N = 0

# Example 2: SUBWFB REG, 0, 0

# **Before Instruction**

REG = 1Bh (0001 1011)

W = 1Ah (0001 1010)

C = 0

# After Instruction

**REG** = 1Bh (0001 1011)

W = 00h

**C** = 1

Z = 1 (result is zero)

N = 0

# Example 3: SUBWFB REG, 1, 0

#### **Before Instruction**

REG = 03h (0000 0011)

W = 0Eh (0000 1110)

C = 1

#### After Instruction

REG = F5h (1111 0101) (2's complement)

W = 0Eh (0000 1110)

C = 0

Z = 0

N = 1 (result is negative)

SWAPF	Swap f			
Syntax	SWAPF f {,d {,a}}			
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$			
Operation	(f<3:0>) → dest<7:4> (f<7:4>) → dest<3:0>			
Status Affected	None			
Encoding	0011	10da	ffff	ffff
Description	The upper and lower nibbles of register 'f' are exchanged. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in the register 'f' (default). If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank. If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever $f \le 95$ (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.			
Words	1			

continued	
SWAPF	Swap f
Syntax	SWAPF f {,d {,a}}
Cycles	1

Q1	Q2	Q3	Q4	
Decode	Read register 'f'	Process Data	Write to destination	

Example: SWAPF REG, 1, 0

Before Instruction REG = 53h

After Instruction

**REG** = 35h

TBLRD	Table Read					
Syntax	TBLRD * TBLRD *+ TBLRD *- TBLRD +*					
Operands	None					
Operation	TBLPTR – No Change  If TBLRD *+  (Prog Mem (TBLPTR))  (TBLPTR) + 1 $\rightarrow$ TBLF  If TBLRD *-  (Prog Mem (TBLPTR))  (TBLPTR) – 1 $\rightarrow$ TBLF  If TBLRD +*  (TBLPTR) + 1 $\rightarrow$ TBLF	(Prog Mem (TBLPTR)) → TABLAT TBLPTR – No Change  If TBLRD *+ (Prog Mem (TBLPTR)) → TABLAT (TBLPTR) + 1 → TBLPTR  If TBLRD *- (Prog Mem (TBLPTR)) → TABLAT (TBLPTR) - 1 → TBLPTR				
Status Affected	None					
Encoding	0000	0000	0000	10mm mm=0 * mm=1 *+ mm=2 *- mm=3 +*		

continued				
TBLRD	Table Read			
Syntax	TBLRD * TBLRD *+ TBLRD *- TBLRD +*			
Description	This instruction is used to read the contents of Program Memory. To address the program memory, a pointer called Table Pointer (TBLPTR) is used.			
	The TBLPTR (a 21-bit pointer) points to each byte in the program memory. TBLPTR has a 2-Mbyte address range.			
	TBLPTR[0] = 0: Least Significant Byte of Program Memory Word  TBLPTR[0] = 1: Most Significant Byte of Program Memory Word			
	The TBLRD instruction can modify the value of TBLPTR as follows:			
	no change (TBLRD *)			
	post-increment (TBLRD *+)			
	post-decrement (TBLRD *-)			
	pre-increment (TBLRD +*)			
Words	1			
Cycles	2			

Q1	Q2	Q3	Q4
Decode	No operation	No operation	No operation
No operation	No operation (Read Program Memory)	No operation	No operation (Write TABLAT)

Example 1: TBLRD \*+

**Before Instruction** 

TABLAT = 55h

**TBLPTR** = 00A356h

MEMORY (00A356h) = 34h

After Instruction

TABLAT = 34h

**TBLPTR** = 00A357h

Example 2: TBLRD +\*

**Before Instruction** 

TABLAT = AAh

TBLPTR = 01A357h

MEMORY (01A357h) = 12h

MEMORY (01A358h) = 34h

**After Instruction** 

TABLAT = 34h

TBLPTR = 01A358h

Syntax $ \begin{array}{c} \mathtt{TBLWT} & \star \\ \end{array} $ Operands $ \begin{array}{c} \mathtt{None} \\ \mathtt{Operation} \\ \\ & \underbrace{\begin{array}{c} \mathtt{If} \ \mathtt{TBLWT} \ \star \\ \mathtt{(TABLAT)} \rightarrow \mathtt{Holding} \ \mathtt{Register} \\ \mathtt{TBLPTR} - \mathtt{No} \ \mathtt{Change} \\ \\ & \underbrace{\begin{array}{c} \mathtt{If} \ \mathtt{TBLWT} \ \star + \\ \mathtt{(TABLAT)} \rightarrow \mathtt{Holding} \ \mathtt{Register} \\ \mathtt{(TBLPTR)} + 1 \rightarrow \mathtt{TBLPTR} \\ \end{array} } $					
Operation  If TBLWT *  (TABLAT) → Holding Register TBLPTR - No Change  If TBLWT *+  (TABLAT) → Holding Register					
(TABLAT) → Holding Register TBLPTR – No Change  If TBLWT *+ (TABLAT) → Holding Register					
If TBLWT *-  (TABLAT) → Holding Register  (TBLPTR) - 1 → TBLPTR  If TBLWT +*  (TBLPTR) + 1 → TBLPTR  (TABLAT) → Holding Register	(TABLAT) → Holding Register  TBLPTR – No Change  If TBLWT *+  (TABLAT) → Holding Register  (TBLPTR) + 1 → TBLPTR  If TBLWT *-  (TABLAT) → Holding Register  (TABLAT) → Holding Register  (TBLPTR) – 1 → TBLPTR  If TBLWT +*  (TBLPTR) + 1 → TBLPTR				
Status Affected None					
mm=1 mm=2	1 *+ 2 *- 3 +*				
registers the TABLAT is written to. The holding registers are used to program the Program Memory. (Refer to the "Program Flash Memory" section for additional de programming Flash memory.)  The TBLPTR (a 21-bit pointer) points to each byte in the program memory. TBLPT	The TBLPTR (a 21-bit pointer) points to each byte in the program memory. TBLPTR has a 2-Mbyte address range. The LSb of the TBLPTR selects which byte of the program memory location to access.  TBLPTR[0] = 0: Least Significant Byte of Program Memory Word  TBLPTR[0] = 1: Most Significant Byte of Program Memory Word  The TBLWT instruction can modify the value of TBLPTR as follows:  • no change (TBLWT *)  • post-increment (TBLWT *+)  • post-decrement (TBLWT *-)				
Words 1					
Cycles 2					

Q1	Q2	Q3	Q4
Decode	No operation	No operation	No operation

No operation No operation (Read TABLAT)	No operation	No operation (Write to Holding Register)
---	--------------	---

Example 1: TBLWT \*+

Before Instruction

TABLAT = 55h

**TBLPTR** = 00A356h

HOLDING REGISTER (00A356h) = FFh

After Instruction (table write completion)

TABLAT = 55h

**TBLPTR** = 00A357h

HOLDING REGISTER (00A356h) = 55h

Example 2: TBLWT +\*

**Before Instruction** 

TABLAT = 34h

**TBLPTR** = 01389Ah

HOLDING REGISTER (01389Ah) = FFh

HOLDING REGISTER (01389Bh) = FFh

After Instruction (table write completion)

TABLAT = 34h

**TBLPTR** = 01389Bh

HOLDING REGISTER (01389Ah) = FFh

HOLDING REGISTER (01389Bh) = 34h

TSTFSZ	Test f, skip if 0				
Syntax	TSTFSZ f {,a}				
Operands	$0 \le f \le 255$ $a \in [0, 1]$				
Operation	Skip if f = 0				
Status Affected	None				
Encoding	0110	011a	ffff	ffff	
Description	If 'f' = 0, the next instruction fetched during the current instruction execution is discarded and a NOP is executed, making this a 2-cycle instruction.  If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank.  If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.				
Words	1				
Cycles	1 (2) Note: 3 cycles if skip and followed by a 2-word instruction. 4 cycles if skip and followed by a 3-word instruction.				

### Q Cycle Activity:

If no skip:

## **Instruction Set Summary**

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation

#### If skip:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation
No operation	No operation	No operation	No operation

### If skip and followed by 2-word instruction:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

### If skip and followed by 3-word instruction:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation
No operation	No operation	No operation	No operation

#### Example:

HERE TSTFSZ CNT, 1 NZERO: ZERO:

### **Before Instruction**

PC = address (HERE)

### After Instruction

If CNT = 0; PC = address (ZERO)
If CNT ≠ 0; PC = address (NZERO)

XORLW	Exclusive OR literal w	Exclusive OR literal with W				
Syntax	XORLW k	XORLW k				
Operands	0 ≤ k ≤ 255	0 ≤ k ≤ 255				
Operation	(W) .XOR. $k \rightarrow W$	(W) .XOR. $k \rightarrow W$				
Status Affected	N, Z	N, Z				
Encoding	0000	1010	kkkk	kkkk		
Description	The contents of W are 2	KORed with the 8-bit lit	eral 'k'. The result is plac	ed in W.		
Words	1	1				
Cycles	1					

Q1	Q2	Q3	Q4
Decode	Read literal 'k'	Process Data	Write to W

Example: XORLW 0AFh

**Before Instruction** 

W = B5h

After Instruction

W = 1Ah

XORWF	Exclusive OR W with	f			
Syntax	XORWF f {,d {,a}}				
Operands	$0 \le f \le 255$ $d \in [0, 1]$ $a \in [0, 1]$	d ∈ [0, 1]			
Operation	(W) .XOR. (f) $\rightarrow$ dest				
Status Affected	N, Z	N, Z			
Encoding	0001	10da	ffff	ffff	
Description		ents of W with register 'i back in the register 'f' (o	f'. If 'd' is '0', the result indefault).	s stored in W. If 'd' is	
	If 'a' is '0', the Access I	Bank is selected. If 'a' is	s '1', the BSR is used to	select the GPR bank.	
	Literal Offset Addressir	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.			
Words	1				
Cycles	1				

### Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination

Example: XORWF REG, 1, 0

**Before Instruction** 

REG = AFh W = B5h

After Instruction

REG = 1Ah

W = B5h

#### 47.2 Extended Instruction Set

In addition to the standard instruction set, PIC18 devices also provide an optional extension to the core CPU functionality. The added features include additional instructions that augment Indirect and Indexed Addressing operations and the implementation of Indexed Literal Offset Addressing mode for many of the standard PIC18 instructions.

The additional features of the extended instruction set are disabled by default. To enable them, users must set the XINST Configuration bit.

The instructions in the extended set can all be classified as literal operations, which either manipulate the File Select registers, or use them for Indexed Addressing. Two of the standard instructions, ADDFSR and SUBFSR, each have an additional special instantiation for using FSR2 as extended instructions. These versions (ADDULNK and SUBULNK) allow for automatic return after execution.

The extended instructions are specifically implemented to optimize re-entrant program code (that is, code that is recursive or that uses a software stack) written in high-level languages, particularly C. Among other things, they allow users working in high-level languages to perform certain operations on data structures more efficiently. These include:

- Dynamic allocation and deallocation of software stack space when entering and leaving subroutines
- · Function pointer invocation
- Software Stack Pointer manipulation
- · Manipulation of variables located in a software stack

A summary of the instructions in the extended instruction set is provided in 47.2.1 Extended Instruction Syntax. Detailed descriptions are provided in 47.2.2 Extended Instruction Set. The opcode field descriptions in Table 47-1 apply to both the standard and extended PIC18 instruction sets.



**Important:** The instruction set extension and the Indexed Literal Offset Addressing mode were designed for optimizing applications written in C; the user may likely never use these instructions directly in assembler. The syntax for these commands is provided as a reference for users who may be reviewing code that has been generated by a compiler.



**Important:** Enabling the PIC18 instruction set extension may cause legacy applications to behave erratically or fail entirely. Refer to 47.2.3 Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode for details.

#### 47.2.1 Extended Instruction Syntax

Most of the extended instructions use indexed arguments, using one of the File Select registers and some offset to specify a source or destination register. When an argument for an instruction serves as part of Indexed Addressing, it is enclosed in square brackets ("[ ]"). This is done to indicate that the argument is used as an index or offset. MPASM Assembler will flag an error if it determines that an index or offset value is not bracketed.

When the extended instruction set is enabled, brackets are also used to indicate index arguments in byte-oriented and bit-oriented instructions. This is in addition to other changes in their syntax. For more details, see 47.2.3.1 Extended Instruction Syntax with Standard PIC18 Commands.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 1049

Table 47-3. Extensions to the PIC18 Instruction Set

ic,			16-Bit Instruction Word			Status		
ds	Description	Cycles	MSb			LSb	Affected	Notes
k	Add literal to FSR2 and return	2	1110	1000	11kk	kkkk	None	1, 3
-, f	Move z <sub>s</sub> (12-bit source)	2	1110	1011	0z <sub>s</sub> z <sub>s</sub> z <sub>s</sub>	Z <sub>S</sub> Z <sub>S</sub> Z <sub>S</sub> Z <sub>S</sub>	None	2, 3, 4
$\begin{array}{c c} MOVSF & z_s, f_d \end{array}$	to f <sub>d</sub> (12-bit destination)	2	1111	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f <sub>d</sub>	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f <sub>d</sub>	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f <sub>d</sub>	ivone	۷, ۵, 4
	Move $z_s$ (14-bit source) to $f_d$ (14-bit destination)		0000	0000	0000	0010	None	
MOVSFL z <sub>s</sub> , f <sub>d</sub>		3	1111	XXXZs	Z <sub>S</sub> Z <sub>S</sub> Z <sub>S</sub> Z <sub>S</sub>	$z_s z_s f_d f_d$		2, 3
			1111	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f <sub>d</sub>	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f <sub>d</sub>	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f <sub>d</sub>		
	Move z <sub>s</sub> (source)	2	1110	1011	1z <sub>s</sub> z <sub>s</sub> z <sub>s</sub>	Z <sub>S</sub> Z <sub>S</sub> Z <sub>S</sub> Z <sub>S</sub>	Nama	0.0
Z <sub>S</sub> , Z <sub>d</sub>	to z <sub>d</sub> (destination)	2	1111	xxxx	xz <sub>d</sub> z <sub>d</sub> z <sub>d</sub>	$z_d z_d z_d z_d$	none	2, 3
k	Store literal at FSR2, decrement FSR2	1	1110	1010	kkkk	kkkk	None	3
k	Subtract literal from FSR2 and return	2	1110	1001	11kk	kkkk	None	1, 3
	k  Z <sub>s</sub> , f <sub>d</sub> Z <sub>s</sub> , z <sub>d</sub> k	$\begin{array}{cccc} & & & & & \\ & & & & \\ & & & & \\ & & & & \\ & & & \\ & & & \\ & & & \\ & $	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$

#### Notes:

- 1. If Program Counter (PC) is modified or a conditional test is true, the instruction requires an additional cycle. The extra cycle is executed as a NOP.
- 2. Some instructions are multi-word instructions. The extra words of these instructions will be decoded as a NOP, unless the first word of the instruction retrieves the information embedded in these 16-bits. This ensures that all program memory locations have a valid instruction.
- 3. Only available when extended instruction set is enabled.
- 4. f<sub>s</sub> and f<sub>d</sub> do not cover the full memory range. 2 MSbs of bank selection are forced to 0b00 to limit the range of these instructions to lower 4k addressing space.

PIC18F26/46/56Q8

Instruction Set Summary

#### 47.2.2 Extended Instruction Set



**Important:** All PIC18 instructions may take an optional label argument preceding the instruction mnemonic for use in symbolic addressing. If a label is used, the instruction format then becomes: {label} instruction argument(s)

ADDULNK	Add Literal to FSR2 and Return					
Syntax	ADDULNK k	ADDULNK k				
Operands	0 ≤ k ≤ 63					
Operation	$(FSR2) + k \rightarrow FSR2$ $(TOS) \rightarrow PC$					
Status Affected	None					
Encoding	1110	1000	11kk	kkkk		
Description	The 6-bit literal 'k' is added to the contents of FSR2. A RETURN is then executed by loading the PC with the TOS. The instruction takes two cycles to execute; a NOP is performed during the second cycle. This may be thought of as a special case of the ADDFSR instruction, where $f_n = 3$ (binary '11'); it operates only on FSR2.					
Words	1					
Cycles	2					

#### Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal 'k'	Process Data	Write to destination
No operation	No operation	No operation	No operation

Example: ADDULNK 23h

Before Instruction FSR2 = 03FFh PC = 0100h

After Instruction FSR2 = 0422h PC = (TOS)

MOVSF	Move Indexed to f					
Syntax	MOVSF [z <sub>s</sub> ], f <sub>d</sub>					
Operands	$0 \le z_s \le 127$ $0 \le f_d \le 4095$					
Operation	$((FSR2) + z_s) \rightarrow f_d$	$((FSR2) + z_s) \rightarrow f_d$				
Status Affected	None	None				
Encoding	1110	1011	0 z <sub>s</sub> z <sub>s</sub> z <sub>s</sub>	$Z_S Z_S Z_S Z_S$		
	1111	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f <sub>d</sub>	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f <sub>d</sub>	$f_d f_d f_d f_d$		

continued	
MOVSF	Move Indexed to f
Syntax	MOVSF [z <sub>s</sub> ], f <sub>d</sub>
Description	The contents of the source register are moved to destination register ' $f_d$ '. The actual address of the source register is determined by adding the 7-bit literal offset ' $z_s$ ' in the first word to the value of FSR2. The address of the destination register is specified by the 12-bit literal ' $f_d$ ' in the second word. Both addresses can be anywhere in the 4096-byte data space (000h to FFFh).  Note:  MOVSF has curtailed the destination range to the lower 4 Kbyte space in memory (Banks 1
	through 15). For everything else, use MOVSFL.
Words	2
Cycles	2

Q1	Q2	Q3	Q4
Decode	Determine source address	Determine source address	Read source register
Decode	No operation No dummy read	No operation	Write register 'f <sub>d</sub> '

Example: MOVSF [05h], REG2

**Before Instruction** 

**FSR2 =** 80h

Contents of 85h = 33h

**REG2** = 11h

Address of REG2 = 100h

After Instruction

**FSR2 =** 80h

Contents of 85h = 33h

**REG2** = 33h

Address of REG2 = 100h

MOVSFL	Move Indexed to f (Long Range)				
Syntax	MOVSFL [z <sub>s</sub> ], f <sub>d</sub>				
Operands	$0 \le z_s \le 127$ $0 \le f_d \le 16383$				
Operation	$((FSR2) + z_s) \rightarrow f_d$	$((FSR2) + z_s) \rightarrow f_d$			
Status Affected	None				
Encoding	0000	0000	0110	0010	
	1111	XXXZ <sub>S</sub>	$Z_S Z_S Z_S Z_S$	$z_s z_s f_d f_d$	
	1111	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub> f	f <sub>d</sub> f <sub>d</sub> f <sub>d</sub>	

continued	continued				
MOVSFL	Move Indexed to f (Long Range)				
Syntax	MOVSFL [z <sub>s</sub> ], f <sub>d</sub>				
Description	The contents of the source register are moved to destination register 'f <sub>d</sub> '. The actual address of the source register is determined by adding the 7-bit literal offset 'z <sub>s</sub> ' in the first word to the value of FSR2 (14 bits). The address of the destination register is specified by the 14-bit literal 'f <sub>d</sub> ' in the second word. Both addresses can be anywhere in the 16 Kbyte data space (0000h to 3FFFh). The MOVSFL instruction cannot use the PCL, TOSU, TOSH or TOSL as the destination register. If the resultant source address points to an indirect addressing register, the value returned will be 00h.				
Words	3				
Cycles	3				

Q1	Q2	Q3	Q4
Decode	No operation	No operation	No operation
Decode	Read source register	Process Data	No operation
Decode	No operation No dummy read	No operation	Write register 'f <sub>d</sub> '

Example: MOVSFL [05h], REG2

**Before Instruction** 

**FSR2** = 2080h

Contents of 2085h = 33h

**REG2** = 11h

Address of REG2 = 2000h

After Instruction

FSR2 = 2080h

Contents of 2085h = 33h

**REG2** = 33h

Address of REG2 = 2000h

MOVSS	Move Indexed to Indexed				
Syntax	MOVSS [z <sub>s</sub> ], [z <sub>d</sub> ]				
Operands	$0 \le z_s \le 127$ $0 \le z_d \le 127$				
Operation	$((FSR2) + z_s) \rightarrow ((FSR)$	2) + z <sub>d</sub> )			
Status Affected	None				
Encoding	1110	1011	$1z_sz_sz_s$	$Z_SZ_SZ_SZ_S$	
	1111	XXXX	xz <sub>d</sub> z <sub>d</sub> z <sub>d</sub>	z <sub>d</sub> z <sub>d</sub> z <sub>d</sub> z <sub>d</sub>	

continued	
MOVSS	Move Indexed to Indexed
Syntax	MOVSS [z <sub>s</sub> ], [z <sub>d</sub> ]
Description	The contents of the source register are moved to the destination register. The addresses of the source and destination registers are determined by adding the 7-bit literal offsets 'z <sub>s</sub> ' or 'z <sub>d</sub> ' respectively to the value of FSR2. Both registers can be located anywhere in the 16 Kbyte data memory space (0000h to 3FFFh).
	The MOVSS instruction cannot use the PCL, TOSU, TOSH or TOSL as the destination register.
	If the resultant source address points to an indirect addressing register, the value returned will be $00h$ . If the resultant destination address points to an indirect addressing register, the instruction will execute as a NOP.
Words	2
Cycles	2

Q1	Q2	Q3	Q4
Decode	Determine source address	Determine source address	Read source register
Decode	Determine destination address	Determine destination address	Write to destination register

Example: MOVSS [05h], [06h]

**Before Instruction** 

**FSR2** = 80h

Contents of 85h = 33h

Contents of 86h = 11h

After Instruction

**FSR2** = 80h

Contents of 85h = 33h

Contents of 86h = 33h

PUSHL	Store Literal at FSR2,	Store Literal at FSR2, Decrement FSR2				
Syntax	PUSHL k					
Operands	0 ≤ k ≤ 255					
Operation	$k \rightarrow FSR2$ (FSR2) – 1 $\rightarrow$ FSR2	· · · · · ·				
Status Affected	None					
Encoding	1111	1010	kkkk	kkkk		
Description			y address specified by truction allows users to			
Words	1					
Cycles	1					

Q1	Q2	Q3	Q4
Decode	Read literal 'k'	Process Data	Write to destination

Example: PUSHL 08h

**Before Instruction** 

FSR2 = 01ECh

Contents of 01ECh = 00h

After Instruction

FSR2 = 01EBh

Contents of 01ECh = 08h

SUBULNK	Subtract Literal from	Subtract Literal from FSR2 and Return				
Syntax	SUBULNK k					
Operands	0 ≤ k ≤ 63					
Operation	$ (FSR2) - k \rightarrow FSR2 $ $ (TOS) \rightarrow PC $					
Status Affected	None	None				
Encoding	1110	1001	11kk	kkkk		
Description	loading the PC with the performed during the s	e TOS. The instruction to	nts of FSR2. A RETURN akes two cycles to execute thought of as a specious only on FSR2.	ute; a NOP is		
Words	1					
Cycles	2					

## Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal 'k'	Process Data	Write to destination
No operation	No operation	No operation	No operation

Example: SUBULNK 23h

**Before Instruction** 

**FSR2** = 03FFh

**PC** = 0100h

After Instruction

FSR2 = 03DCh

PC = (TOS)

#### 47.2.3 Byte-Oriented and

#### **Bit-Oriented Instructions in Indexed Literal Offset Mode**



**Important:** Enabling the PIC18 instruction set extension may cause legacy applications to behave erratically or fail entirely.

In addition to the new commands in the extended set, enabling the extended instruction set also enables Indexed Literal Offset Addressing mode (Section "Indexed Addressing with Literal Offset" in "Memory Organization"). This has a significant impact on the way that many commands of the standard PIC18 instruction set are interpreted.

When the extended set is disabled, addresses embedded in opcodes are treated as literal memory locations: either as a location in the Access Bank ('a' = 0), or in a GPR bank designated by the BSR ('a' = 1). When the extended instruction set is enabled and 'a' = 0, however, a file register argument of 5 Fh or less is interpreted as an offset from the pointer value in FSR2 and not as a literal address. For practical purposes, this means that all instructions that use the Access RAM bit as an argument – that is, all byte-oriented and bit-oriented instructions, or almost half of the core PIC18 instructions – may behave differently when the extended instruction set is enabled.

When the content of FSR2 is 00h, the boundaries of the Access RAM are essentially remapped to their original values. This may be useful in creating backward compatible code. If this technique is used, it may be necessary to save the value of FSR2 and restore it when moving back and forth between C and assembly routines in order to preserve the Stack Pointer. Users must also keep in mind the syntax requirements of the extended instruction set (see 47.2.3.1 Extended Instruction Syntax with Standard PIC18 Commands).

Although the Indexed Literal Offset Addressing mode can be very useful for dynamic stack and pointer manipulation, it can also be very annoying if a simple arithmetic operation is carried out on the wrong register. Users who are accustomed to the PIC18 programming must keep in mind that, when the extended instruction set is enabled, register addresses of 5Fh or less are used for Indexed Literal Offset Addressing.

Representative examples of typical byte-oriented and bit-oriented instructions in the Indexed Literal Offset Addressing mode are provided in the following section 47.2.4 Considerations when Enabling the Extended Instruction Set to show how execution is affected. The operand conditions shown in the examples are applicable to all instructions of these types.

#### **Related Links**

9.6 Data Memory and the Extended Instruction Set

#### 47.2.3.1 Extended Instruction Syntax with Standard PIC18 Commands

When the extended instruction set is enabled, the file register argument, 'f', in the standard byte-oriented and bit-oriented commands is replaced with the literal offset value, 'k'. As already noted, this occurs only when 'f' is less than or equal to 5Fh. When an offset value is used, it must be indicated by square brackets ("[ ]"). As with the extended instructions, the use of brackets indicates to the compiler that the value is to be interpreted as an index or an offset. Omitting the brackets, or using a value greater than 5Fh within brackets, will generate an error in the MPASM assembler.

If the index argument is properly bracketed for Indexed Literal Offset Addressing, the Access RAM argument is never specified; it will automatically be assumed to be '0'. This is in contrast to standard operation (extended instruction set disabled) when 'a' is set on the basis of the target address. Declaring the Access RAM bit in this mode will also generate an error in the MPASM assembler.

The destination argument, 'd', functions as before.

In the latest versions of the MPASM $^{\text{TM}}$  assembler, language support for the extended instruction set must be explicitly invoked. This is done with either the command-line option, / y, or the PE directive in the source listing.

#### **Related Links**

9.6 Data Memory and the Extended Instruction Set

#### 47.2.4 Considerations when Enabling the Extended Instruction Set

It is important to note that the extensions to the instruction set may not be beneficial to all users. In particular, users who are not writing code that uses a software stack may not benefit from using the extensions to the instruction set.

Additionally, the Indexed Literal Offset Addressing mode may create issues with legacy applications written to the PIC18 assembler. This is because instructions in the legacy code may attempt to address registers in the Access Bank below 5Fh. Since these addresses are interpreted as literal offsets to FSR2 when the instruction set extension is enabled, the application may read or write to the wrong data addresses.

When porting an application to a PIC18 device supporting extensions to the instruction set, it is very important to consider the type of code. A large, re-entrant application that is written in 'C' and would benefit from efficient compilation will do well when using the instruction set extensions. Legacy applications that heavily use the Access Bank will most likely not benefit from using the extended instruction set.

ADDWF	ADD W to Indexed (In	ADD W to Indexed (Indexed Literal Offset mode)				
Syntax	ADDWF [k] {,d}					
Operands	$0 \le k \le 95$ $d \in [0, 1]$					
Operation	(W) + ((FSR2) + k) → c	(W) + ((FSR2) + k) → dest				
Status Affected	N, OV, C, DC, Z					
Encoding	0010	01d0	kkkk	kkkk		
Description			of the register indicated to find its '1', the result is sto			
Words	1					
Cycles	1					

#### Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal 'k'	Process Data	Write to destination

Example: ADDWF [OFST] , 0

**Before Instruction** 

W = 17h

OFST = 2Ch

**FSR2** = 0A00h

Contents of OA2Ch = 20h

After Instruction

W = 37h

Contents of OA2Ch = 20h

BSF	Bit Set Indexed (Indexed Literal Offset mode)
Syntax	BSF [k], b
Operands	$0 \le k \le 95$ $0 \le b \le 7$
Operation	1 → ((FSR2) + k) <b></b>

continued						
BSF	Bit Set Indexed (Inde	xed Literal Offset mod	e)			
Syntax	BSF [k], b	BSF [k], b				
Status Affected	None	None				
Encoding	1000	0ddd	kkkk	kkkk		
Description	Bit 'b' of the register in	dicated by FSR2, offset	by the value 'k', is set.			
Words	1					
Cycles	1					

Q1	Q2	Q3	Q4
Decode	Read literal 'k'	Process Data	Write to destination

Example: BSF [FLAG\_OFST], 7

Before Instruction

FLAG\_OFST = 0Ah FSR2 = 0A00h

Contents of OAOAh = 55h

After Instruction

Contents of OAOAh = D5h

SETF	Set Indexed (Indexed Literal Offset mode)				
Syntax	SETF [k]				
Operands	0 ≤ k ≤ 95				
Operation	$\texttt{FFh} \rightarrow ((\texttt{FSR2}) + \texttt{k})$	$\texttt{FFh} \rightarrow ((\texttt{FSR2}) + \texttt{k})$			
Status Affected	None				
Encoding	0110	1000	kkkk	kkkk	
Description	The contents of the reg	gister indicated by FSR2	2, offset by the value 'k',	are set to FFh.	
Words	1				
Cycles	1				

### Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal 'k'	Process Data	Write to destination

Example: SETF [OFST]

**Before Instruction** 

OFST = 2Ch

**FSR2** = 0A00h

Contents of OA2Ch = OOh

After Instruction

Contents of OA2Ch = FFh

## 47.2.5 Special Considerations with Microchip MPLAB® IDE Tools

The latest versions of Microchip's software tools have been designed to fully support the extended instruction set on the PIC18 devices. This includes the MPLAB XC8 C compiler, MPASM assembler and MPLAB X Integrated Development Environment (IDE).

When selecting a target device for software development, MPLAB X IDE will automatically set default Configuration bits for that device. The default setting for the XINST Configuration bit is '0', disabling the extended instruction set and Indexed Literal Offset Addressing mode. For proper execution of applications developed to take advantage of the extended instruction set, XINST must be set during programming.

To develop software for the extended instruction set, the user must enable support for the instructions and the Indexed Addressing mode in their language tool(s). Depending on the environment being used, this may be done in several ways:

- A menu option, or dialog box within the environment, that allows the user to configure the language tool and its settings for the project
- · A command-line option
- · A directive in the source code

These options vary between different compilers, assemblers and development environments. Users are encouraged to review the documentation accompanying their development systems for the appropriate information.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 1059

## 48. ICSP™ - In-Circuit Serial Programming™

ICSP programming allows customers to manufacture circuit boards with unprogrammed devices. Programming can be done after the assembly process, allowing the device to be programmed with the most recent firmware or a custom firmware. Five pins are needed for ICSP programming:

- ICSPCLK
- ICSPDAT
- MCLR/V<sub>PP</sub>
- V<sub>DD</sub>
- Vss

In Program/Verify mode the program memory, User IDs and the Configuration bits are programmed through serial communications. The ICSPDAT pin is a bidirectional I/O used for transferring the serial data and the ICSPCLK pin is the clock input. For more information on ICSP refer to the "Family Programming Specification"

### 48.1 High-Voltage Programming Entry Mode

The device is placed into High-Voltage Programming Entry mode by holding the ICSPCLK and ICSPDAT pins low then raising the voltage on  $\overline{MCLR}/V_{PP}$  to  $V_{IHH}$ .

### 48.2 Low-Voltage Programming Entry Mode

The Low-Voltage Programming Entry mode allows the  $PIC^{\oplus}$  Flash MCUs to be programmed using  $V_{DD}$  only, without high voltage. When the LVP Configuration bit is set to '1', the low-voltage ICSP programming entry is enabled. To disable the Low-Voltage ICSP mode, the LVP bit must be programmed to '0'.

Entry into the Low-Voltage Programming Entry mode requires the following steps:

- 1. MCLR is brought to Vil.
- 2. A 32-bit key sequence is presented on ICSPDAT, while clocking ICSPCLK.

Once the key sequence is complete,  $\overline{MCLR}$  must be held at  $V_{IL}$  for as long as Program/Verify mode is to be maintained.

If low-voltage programming is enabled (LVP = 1), the  $\overline{MCLR}$  Reset function is automatically enabled and cannot be disabled. See the  $\overline{MCLR}$  Section for more information.


The LVP bit can only be reprogrammed to '0' by using the High-Voltage Programming mode.

## 48.3 Common Programming Interfaces

Connection to a target device is typically done through an ICSP header. A commonly found connector on development tools is the RJ-11 in the 6P6C (6-pin, 6-connector) configuration. See Figure 48-1.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 1060

Figure 48-1. ICD RJ-11 Style Connector Interface



Pin Description


- $1 = V_{PP} / \overline{MCLR}$
- 2 = V<sub>DD</sub> Target
- $3 = V_{SS}$  (ground)
- 4 = ICSPDAT
- 5 = ICSPCLK
- 6 = No Connect

Another connector often found in use with the PICkit<sup>™</sup> programmers is a standard 6-pin header with 0.1 inch spacing. Refer to Figure 48-2.

For additional interface recommendations, refer to the specific device programmer manual prior to PCB design.

It is recommended that isolation devices be used to separate the programming pins from other circuitry. The type of isolation is highly dependent on the specific application and may include devices such as resistors, diodes, or even jumpers. See Figure 48-3 for more information.

Figure 48-2. PICkit<sup>™</sup> Programmer Style Connector Interface



Pin Description(1):

 $1 = V_{PP} / \overline{MCLR}$ 

 $2 = V_{DD}$  Target

 $3 = V_{SS}$  (ground)

4 = ICSPDAT


5 = ICSPCLK

6 = No Connect

#### Note:

1. The 6-pin header (0.100" spacing) accepts 0.025" square pins.

Figure 48-3. Typical Connection for ICSP™ Programming



\* Isolation devices (as required).

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
00	U2ERRIE	7:0	TXMTIE	PERIE	ABDOVE	CERIE	FERIE	RXBKIE	RXFOIE	TXCIE
0x01										
	Reserved									
0x37	DOCTOR		DDOUT	DOOTDONE					5.4	20
0x38	BOOTREG	7:0	BPOUT	BOOTDONE		DO	4.01		B1	В0
0x39 0x3A	CLKRCON	7:0 7:0	EN			DC[	1:0]	CL K[4:0]	DIV[2:0]	
0x3A 0x3B	CLRRCLR	7.0						CLK[4:0]		
	Reserved									
0x3F	110001100									
0x40	NVMCON0	7:0								GO
0x41	NVMCON1	7:0	WRERR						NVMCMD[2:0]	
0x42	NVMLOCK	7:0				NVMLO	CK[7:0]			
		7:0				NVMAI				
0x43	NVMADR	15:8				NVMAD				
		23:16					NVMAD	R[21:16]		
0x46	NVMDAT	7:0				NVMD.	AT[7:0]			
0.00	INVIVIDAT	15:8				NVMDA	AT[15:8]			
0x48	VREGCON	7:0			PMSY	'S[1:0]			VREG	PM[1:0]
0x49	BORCON	7:0	SBOREN							BORRDY
0x4A	HLVDCON0	7:0	EN		OUT	RDY			INTH	INTL
0x4B	HLVDCON1	7:0						SEL	[3:0]	
0x4C	ZCDCON	7:0	SEN		OUT	POL			INTP	INTN
0x4D										
 0x5F	Reserved									
0x60	PMD0	7:0	SYSCMD	FVRMD	HLVDMD	CRCMD	SCANMD		CLKRMD	IOCMD
0x61	PMD1	7:0	SMT1MD	TMR6MD	TMR5MD	TMR4MD	TMR3MD	TMR2MD	TMR1MD	TMR0MD
0x62	PMD2	7:0	CANMD						TU16BMD	TU16AMD
0x63	PMD3	7:0	ACTMD	DAC1MD	ADCMD			C2MD	C1MD	ZCDMD
0x64	PMD4	7:0		CWG3MD	CWG2MD	CWG1MD	DSM1MD	NCO3MD	NCO2MD	NCO1MD
0x65	PMD5	7:0	PWM4MD	PWM3MD	PWM2MD	PWM1MD		CCP3MD	CCP2MD	CCP1MD
0x66	PMD6	7:0	U5MD	U4MD	U3MD	U2MD	U1MD	SPI2MD	SPI1MD	I2C1MD
0x67	PMD7	7:0	CLC8MD	CLC7MD	CLC6MD	CLC5MD	CLC4MD	CLC3MD	CLC2MD	CLC1MD
0x68	PMD8	7:0	DM88MD	DMA7MD	DMA6MD	DMA5MD	DMA4MD	DMA3MD	DMA2MD	DMA1MD
0x69	Reserved		=,,		0117	0001				517
0x6A	MD1CON0	7:0	EN		OUT	OPOL			OL DOL	BIT
0x6B	MD1CON1	7:0 7:0			CHPOL	CHSYNC	MSI	F.01	CLPOL	CLSYNC
0x6C 0x6D	MD1SRC MD1CARL	7:0					IVIS	CL[4:0]		
0x6E	MD1CARL MD1CARH	7:0						CL[4:0] CH[4:0]		
0x6E	CMOUT	7:0						Oi 1[4.0]	C2OUT	C1OUT
0x01	CM1CON0	7:0	EN	OUT		POL			HYS	SYNC
0x70	CM1CON1	7:0	_,,	331		. 72			INTP	INTN
0x72	CM1NCH	7:0							NCH[2:0]	
0x73	CM1PCH	7:0							PCH[2:0]	
0x74	CM2CON0	7:0	EN	OUT		POL			HYS	SYNC
0x75	CM2CON1	7:0							INTP	INTN
0x76	CM2NCH	7:0							NCH[2:0]	
0x77	CM2PCH	7:0							PCH[2:0]	
0x78	WDTCON0	7:0					PS[4:0]			SEN
0x79	WDTCON1	7:0	CS[2:0] WINDOW[2:0]							
0x7A	WDTPSL	7:0				PSCN <sup>-</sup>	TL[7:0]			
0x7B	WDTPSH	7:0		PSCNTH[7:0]						
0x7C	WDTTMR	7:0			TMR[4:0]			STATE	PSCNT	[17:16]
0x7D	DAC1DATL	7:0				DAC1	R[7:0]			

cont	inued									
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x7E	Reserved									
0x7F	DAC1CON	7:0	EN		OE	[1:0]	PSS	6[1:0]		NSS
0x80	SPI1RXB	7:0					[7:0]			
0x81	SPI1TXB	7:0				TXB	[7:0]			
0x82	SPI1TCNT	7:0				TCNT	L[7:0]			
		15:8							TCNTH[2:0]	
0x84	SPI1CON0	7:0	EN					LSBF	MST	BMODE
0x85	SPI1CON1	7:0	SMP	CKE	CKP	FST		SSP	SDIP	SDOP
0x86	SPI1CON2	7:0	BUSY	SSFLT				SSET	TXR	RXR
0x87	SPI1STATUS	7:0	TXWE		TXBE		RXRE	CLB	TIMED THE O	RXBF
0x88 0x89	SPI1TWIDTH SPI1BAUD	7:0 7:0				BAUI	7(7:0)		TWIDTH[2:0]	
0x8A	SPITIBAUD	7:0	SRMTIF	TCZIF	SOSIF	EOSIF	[0.1]	RXOIF	TXUIF	
0x8B	SPITINTE	7:0	SRMTIE	TCZIE	SOSIE	EOSIE		RXOIF	TXUIE	
0x8C	SPI1CLK	7:0	SIXWITE	TOZIL	303IL	LOSIL		CLKSEL[4:0]	TAUL	
0x8D	SPI2RXB	7:0				RXF	3[7:0]	OLINOLL[4.0]		
0x8E	SPI2TXB	7:0					[7:0]			
		7:0				TCNT				
0x8F	SPI2TCNT	15:8							TCNTH[2:0]	
0x91	SPI2CON0	7:0	EN					LSBF	MST	BMODE
0x92	SPI2CON1	7:0	SMP	CKE	CKP	FST		SSP	SDIP	SDOP
0x93	SPI2CON2	7:0	BUSY	SSFLT				SSET	TXR	RXR
0x94	SPI2STATUS	7:0	TXWE		TXBE		RXRE	CLB		RXBF
0x95	SPI2TWIDTH	7:0							TWIDTH[2:0]	
0x96	SPI2BAUD	7:0				BAUI	D[7:0]			
0x97	SPI2INTF	7:0	SRMTIF	TCZIF	SOSIF	EOSIF		RXOIF	TXUIF	
0x98	SPI2INTE	7:0	SRMTIE	TCZIE	SOSIE	EOSIE		RXOIE	TXUIE	
0x99	SPI2CLK	7:0						CLKSEL[4:0]		
0x9A 	Reserved									
0xAB	reserved									
0xAC	ACTCON	7:0	ACTEN	ACTUD			ACTLOCK		ACTORS	
0xAD	OSCCON1	7:0			NOSC[2:0]			NDI\	/[3:0]	
0xAE	OSCCON2	7:0			COSC[2:0]				/[3:0]	
0xAF	OSCCON3	7:0	CSWHOLD	SOSCPWR		ORDY	NOSCR			
0xB0	OSCTUNE	7:0					TUN	N[5:0]		
0xB1	OSCFRQ	7:0						FRC	[3:0]	
0xB2	OSCSTAT	7:0	EXTOR	HFOR	MFOR	LFOR	SOR	ADOR		PLLR
0xB3	OSCEN	7:0	EXTOEN	HFOEN	MFOEN	LFOEN	SOSCEN	ADOEN		PLLEN
0xB4	PRLOCK	7:0								PRLOCKED
0xB5	SCANPR	7:0							PR[2:0]	
0xB6	DMA1PR	7:0							PR[2:0]	
0xB7	DMA2PR	7:0							PR[2:0]	
0xB8 0xB9	DMA3PR DMA4PR	7:0 7:0							PR[2:0]	
0xB9		7:0							PR[2:0]	
0xBA 0xBB	DMA5PR DMA6PR	7:0							PR[2:0] PR[2:0]	
0xBC	DMA7PR	7:0							PR[2:0]	
0xBC 0xBD	DMA8PR	7:0							PR[2:0]	
0xBE	MAINPR	7:0							PR[2:0]	
0xBE	ISRPR	7:0							PR[2:0]	
0xC0	ION IX	7.0							1 1 1 2.0]	
	Reserved									
0xD3										
0xD4	CLCDATA	7:0	CLC8OUT	CLC7OUT	CLC6OUT	CLC5OUT	CLC4OUT	CLC3OUT	CLC2OUT	CLC10UT
0xD5	CLCSELECT	7:0							SLCT[2:0]	-
0xD6	CLCnCON	7:0	EN		OUT	INTP	INTN		MODE[2:0]	
0xD7	CLCnPOL	7:0	POL				G4POL	G3POL	G2POL	G1POL
0xD8	CLCnSEL0	7:0				D18	[7:0]	1	1	

conti	inued									
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0xD9	CLCnSEL1	7:0				D2S				
0xD9	CLCnSEL2	7:0				D3S				
0xDR	CLCnSEL3	7:0				D4S				
0xDC	CLCnGLS0	7:0	G1D4T	G1D4N	G1D3T	G1D3N	G1D2T	G1D2N	G1D1T	G1D1N
0xDD	CLCnGLS1	7:0	G2D4T	G2D4N	G2D3T	G2D3N	G2D2T	G2D2N	G2D1T	G2D1N
0xDE	CLCnGLS2	7:0	G3D4T	G3D4N	G3D3T	G3D3N	G3D2T	G3D2N	G3D1T	G3D1N
0xDF	CLCnGLS3	7:0	G4D4T	G4D4N	G4D3T	G4D3N	G4D2T	G4D2N	G4D1T	G4D1N
0xE0										
 0xE7	Reserved									
0xE8	DMASELECT	7:0							SLCT[2:0]	
0xE9	DMAnBUF	7:0				BUF				
0xEA	DMAnDCNT	7:0				DCN	Γ[7:0]			
UXLA	DIVIANDON	15:8						DCN	T[11:8]	
0xEC	DMAnDPTR	7:0				DPT				
OXEO		15:8				DPTR				
0xEE	DMAnDSZ	7:0				DSZ	[7:0]			
		15:8						DSZ	[11:8]	
0xF0	DMAnDSA	7:0				DSA				
		15:8				DSA				
0xF2	DMAnSCNT	7:0				SCN.	1[7:0]	001	T(44.01	
		15:8				CDT	217.01	SCN	Τ[11:8]	
0.4	DMASCRID	7:0 15:8				SPTF				
0xF4	DMAnSPTR	23:16				SPTR		[21:16]		
		7:0				SSZ		[21.10]		
0xF7	DMAnSSZ	15:8				332	[7.0]	997	[11:8]	
		7:0				SSA	[7:0]	002	[11.0]	
0xF9	DMAnSSA	15:8				SSA				
07.1. 0		23:16						21:16]		
0xFC	DMAnCON0	7:0	EN	SIRQEN	DGO			AIRQEN		XIP
0xFD	DMAnCON1	7:0	DMOI	DE[1:0]	DSTP	SMF	R[1:0]	SMOI	DE[1:0]	SSTP
0xFE	DMAnAIRQ	7:0				AIRC				
0xFF	DMAnSIRQ	7:0				SIRC	Q[7:0]			
		7:0	CLKSEL	PXEDIS	ISOCRCEN			DNCNT[4:0]		
0x0100	C1CON	15:8	ON		SIDL	BRSDIS	BUSY	WF	Γ[1:0]	WAKFIL
000100	CICON	23:16		OPMOD[2:0]		TXQEN	STEF	SERRLOM	ESIGM	RTXAT
		31:24		TXBV	VS[3:0]		ABAT		REQOP[2:0]	
		7:0					SJW[6:0]			
0x0104	C1NBTCFG	15:8					TSEG2[6:0]			
-		23:16				TSEG				
		31:24				BRP	[7:0]	2	VFO 01	
		7:0							V[3:0]	
0x0108	C1DBTCFG	15:8							G2[3:0]	
		23:16				DDD	[7:0]	TSEG1[4:0]		
		31:24 7:0				BRP		V(E·01		
		15:8					TDC0[6:0]	V[5:0]		
0x010C	C1TDC	23:16					1000[6:0]		TDCM	)D[1·0]
		31:24							EDGFLTEN	SID11EN
		7:0				TBC	[7:0]		LDOI LILIN	CIDITEIN
		15:8				TBC				
0x0110	C1TBC	23:16				TBC[2				
		31:24				TBC[3				
		7:0				TBCPF				
		15:8							ТВСРЕ	RE[9:8]
0.044:	0470000									
0x0114	C1TSCON	23:16						TSRES	TSEOF	TBCEN

# **Register Summary**

DS40002259A-page 1066

conti	nued									
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
		7:0					ICODE[6:0]			
00440	04)/50	15:8						FILHIT[4:0]		
0x0118	C1VEC	23:16					TXCODE[6:0]			
		31:24					RXCODE[6:0]			
		7:0				TEFIF	MODIF	TBCIF	RXIF	TXIF
0.0440	CAINIT	15:8	IVMIF	WAKIF	CERRIF	SERRIF	RXOVIF	TXATIF		
0x011C	C1INT	23:16				TEFIE	MODIE	TBCIE	RXIE	TXIE
		31:24	IVMIE	WAKIE	CERRIE	SERRIE	RXOVIE	TXATIE		
		7:0						RFIF[2:0]		
0x0120	CARVIE	15:8								
0X0120	C1RXIF	23:16								
		31:24								
		7:0						TFIF	[3:0]	
0x0124	C1TXIF	15:8								
0X0124	CTIXIF	23:16								
		31:24								
		7:0						RFOVIF[2:0]		
0x0128	C1RXOVIF	15:8								
0.0120	OTICKOVII	23:16								
		31:24								
		7:0						TFAT	IF[3:0]	
0x012C	C1TXATIF	15:8								
0.0120	OTIAATII	23:16								
		31:24								
		7:0						TXRE	Q[3:0]	
0x0130	C1TXREQ	15:8								
0.0100	OTTAILL	23:16								
		31:24								
		7:0				RERRO	NT[7:0]			
0x0134	C1TREC	15:8					NT[7:0]			
OXO TO T	OTTILE	23:16			TXBO	TXBP	RXBP	TXWARN	RXWARN	EWARN
		31:24								
		7:0					CNT[7:0]			
0x0138	C1BDIAG0	15:8					CNT[7:0]			
0,10100	0.125	23:16					CNT[7:0]			
		31:24					CNT[7:0]			
		7:0					CNT[7:0]			
0x013C	C1BDIAG1	15:8					CNT[15:8]			
		23:16	TXBOERR		NCRCERR		NFORMERR	NACKERR	NBIT1ERR	NBIT0ERR
		31:24	DLCMM	ESI	DCRCERR	DSTUFERR	DFORMERR		DBIT1ERR	DBIT0ERR
		7:0			TEFTSEN		TEFOVIE	TEFFIE	TEFHIE	TEFNEIE
0x0140	C1TEFCON	15:8						FRESET		UINC
		23:16						FOIZELL OF		
		31:24					TEE0\ "E	FSIZE[4:0]	TEE! !!	TEE
		7:0					TEFOVIF	TEFFIF	TEFHIF	TEFNEIF
0x0144	C1TEFSTA	15:8								
		23:16								
		31:24				TE 5.	IA [7.0]			
		7:0					IA[7:0]			
0x0148	C1TEFUA	15:8					A[15:8]			
		23:16					A[23:16]			
		31:24					A[31:24]			
		7:0					BA[7:0]			
0x014C	C1FIFOBA	15:8					A[15:8]			
		23:16					A[23:16]			
		31:24				FIFOB	A[31:24]			

conti	nued									
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
		7:0	TXEN			TXATIE		TXQEIE		TXQNIE
0.0450	0.477/0.001	15:8						FRESET	TXREQ	UINC
0x0150	C1TXQCON	23:16		TXA	Γ[1:0]			TXPRI[4:0]		
		31:24		PLSIZE[2:0]				FSIZE[4:0]		
		7:0	TXABT	TXLARB	TXERR	TXATIF		TXQEIF		TXQNIF
0.0454	0.471/0.074	15:8						TXQCI[4:0]		
0x0154	C1TXQSTA	23:16								
		31:24								
		7:0				TXQL	IA[7:0]			
0.0450	0.477/0114	15:8				TXQU	A[15:8]			
0x0158	C1TXQUA	23:16				TXQUA				
		31:24					\[31:24]			
		7:0	TXEN	RTREN	RXTSEN	TXATIE	RXOVIE	TFERFFIE	TFHRFHIE	TFNRFNIE
		15:8						FRESET	TXREQ	UINC
0x015C	C1FIFOCON1	23:16		TXA	Γ[1:0]			TXPRI[4:0]		
		31:24		PLSIZE[2:0]	,			FSIZE[4:0]		
		7:0	TXABT	TXLARB	TXERR	TXATIF	RXOVIF	TFERFFIF	TFHRFHIF	TFNRFNIF
		15:8					1.2 ***	FIFOCI[4:0]		
0x0160	C1FIFOSTA1	23:16						55.[6]		
		31:24								
		7:0				FIFOL	IA[7·0]			
		15:8					A[15:8]			
0x0164	C1FIFOUA1	23:16					A[23:16]			
		31:24					A[31:24]			
		7:0	TXEN	RTREN	RXTSEN	TXATIE	RXOVIE	TFERFFIE	TFHRFHIE	TFNRFNIE
		15:8	IXLIN	IXIIXLIX	TOCTOLIN	IXAIIL	TOTOVIL	FRESET	TXREQ	UINC
0x0168	C1FIFOCON2	23:16		TXA	Γ[1·Ω]			TXPRI[4:0]	IXILQ	UNC
		31:24		PLSIZE[2:0]	1[1.0]			FSIZE[4:0]		
		7:0	TXABT	TXLARB	TXERR	TXATIF	RXOVIF	TFERFFIF	TFHRFHIF	TFNRFNIF
		15:8	IXADI	IXLAND	IXLITI	IZATII	TOOVII	FIFOCI[4:0]	11111311111	TI INIXI INII
0x016C	C1FIFOSTA2	23:16						111 OCI[4.0]		
		31:24								
		7:0				FIFOL	IA [7:0]			
		15:8					A[15:8]			
0x0170	C1FIFOUA2	23:16					A[23:16]			
		31:24					A[31:24]			
		7:0	TXEN	RTREN	RXTSEN	TXATIE	RXOVIE	TFERFFIE	TFHRFHIE	TFNRFNIE
			IALIN	KIKEN	KATSEN	IAAIIE	KAOVIE			
0x0174	C1FIFOCON3	15:8		TVAT	F[4.0]			FRESET	TXREQ	UINC
		23:16 31:24		TXA	1[1:0]			TXPRI[4:0]		
			TVADT	PLSIZE[2:0]	TVEDD	TXATIF	RXOVIF	FSIZE[4:0]	TELIDELIIE	TFNRFNIF
		7:0 15:8	TXABT	TALARB	TXERR	TXATIF	RXOVIF		TFHRFHIF	IFINKFINIF
0x0178	C1FIFOSTA3	23:16						FIFOCI[4:0]		
		31:24				FIFOI	LA [7:0]			
		7:0					JA[7:0]			
0x017C	C1FIFOUA3	15:8					A[15:8]			
		23:16					A[23:16]			
		31:24	CI TCNO			FIFUU/	A[31:24]	EODD(4:03		
		7:0	FLTEN0					F0BP[4:0]		
0x0180	C1FLTCON0	15:8	FLTEN1					F1BP[4:0]		
		23:16	FLTEN2					F2BP[4:0]		
		31:24	FLTEN3					F3BP[4:0]		
		7:0	FLTEN4					F4BP[4:0]		
0x0184	C1FLTCON1	15:8	FLTEN5					F5BP[4:0]		
		23:16	FLTEN6					F6BP[4:0]		
		31:24	FLTEN7					F7BP[4:0]		

conti	nued							
Offset	Name	Bit Pos.	7	6	5	4 3	2 1	0
Oliset	Name			•	3	3		
		7:0	FLTEN8				F8BP[4:0]	
0x0188	C1FLTCON2	15:8	FLTEN9				F9BP[4:0]	
		23:16	FLTEN10				F10BP[4:0]	
		31:24	FLTEN11				F11BP[4:0]	
		7:0				SID[7:0]		
0x018C	C1FLTOBJ0	15:8			EID[4:0]		SID[10:8]	
		23:16				EID[12:5]		
		31:24		EXIDE	SID11		EID[17:13]	
		7:0				MSID[7:0]		
0x0190	C1MASK0	15:8			MEID[4:0]		MSID[10:8]	
		23:16				MEID[12:5]		
		31:24		MIDE	MSID11		MEID[17:13]	
		7:0				SID[7:0]		
0x0194	C1FLTOBJ1	15:8			EID[4:0]		SID[10:8]	
		23:16				EID[12:5]		
		31:24		EXIDE	SID11		EID[17:13]	
		7:0				MSID[7:0]		
0x0198	C1MASK1	15:8			MEID[4:0]		MSID[10:8]	
0.0100	O IIIII COTT	23:16				MEID[12:5]		
		31:24		MIDE	MSID11		MEID[17:13]	
		7:0				SID[7:0]		
0x019C	C1FLTOBJ2	15:8			EID[4:0]		SID[10:8]	
0.0190	CII LIOB32	23:16				EID[12:5]		
		31:24		EXIDE	SID11		EID[17:13]	
		7:0				MSID[7:0]		
0.0140	CAMACKO	15:8			MEID[4:0]		MSID[10:8]	
0x01A0	C1MASK2	23:16				MEID[12:5]	'	
		31:24		MIDE	MSID11		MEID[17:13]	
		7:0				SID[7:0]		
00444	O4ELTOD IO	15:8			EID[4:0]		SID[10:8]	
0x01A4	C1FLTOBJ3	23:16				EID[12:5]	<u> </u>	
		31:24		EXIDE	SID11		EID[17:13]	
		7:0				MSID[7:0]		
0.0440	0.111.0140	15:8			MEID[4:0]		MSID[10:8]	
0x01A8	C1MASK3	23:16				MEID[12:5]	<u> </u>	
		31:24		MIDE	MSID11		MEID[17:13]	
		7:0				SID[7:0]		
0.0440	045170014	15:8			EID[4:0]		SID[10:8]	
0x01AC	C1FLTOBJ4	23:16				EID[12:5]	<u> </u>	
		31:24		EXIDE	SID11		EID[17:13]	
		7:0				MSID[7:0]		
0.0450	048480144	15:8			MEID[4:0]		MSID[10:8]	
0x01B0	C1MASK4	23:16				MEID[12:5]		
		31:24		MIDE	MSID11		MEID[17:13]	
		7:0				SID[7:0]		
		15:8			EID[4:0]		SID[10:8]	
0x01B4	C1FLTOBJ5	23:16				EID[12:5]		
		31:24		EXIDE	SID11		EID[17:13]	
		7:0			1	MSID[7:0]	<u> </u>	
		15:8			MEID[4:0]	1 1	MSID[10:8]	
0x01B8	C1MASK5	23:16			J	MEID[12:5]	[]	
		31:24		MIDE	MSID11	-[:-:-]	MEID[17:13]	
		7:0		5_		SID[7:0]	[1	
		15:8			EID[4:0]	5.5[1.0]	SID[10:8]	
0x01BC	C1FLTOBJ6	23:16				EID[12:5]	SID[10.0]	
		31:24		EXIDE	SID11	[12.0]	EID[17:13]	
		01.27		LAIDL	CIDIT			

conti	nuod								
Offset	Name	Bit Pos.	7	6	5	4 3	2	1	0
		7:0				MSID[7:0]			
0x01C0	C1MASK6	15:8			MEID[4:0]			MSID[10:8]	
one rec		23:16				MEID[12:5]			
		31:24		MIDE	MSID11		MEID[17:13]		
		7:0				SID[7:0]			
0x01C4	C1FLTOBJ7	15:8			EID[4:0]	EID[40.5]		SID[10:8]	
		23:16 31:24		EVIDE	CID44	EID[12:5]	EID[47,40]		
		7:0		EXIDE	SID11	MSID[7:0]	EID[17:13]		
		15:8			MEID[4:0]	[0.1]UISINI		MSID[10:8]	
0x01C8	C1MASK7	23:16			WILID[4.0]	MEID[12:5]		WOID[10.0]	
		31:24		MIDE	MSID11	WILID[12.0]	MEID[17:13]		
		7:0		WIIDE	WOIDTT	SID[7:0]	WEID[17:10]		
		15:8			EID[4:0]	0.0[1.0]		SID[10:8]	
0x01CC	C1FLTOBJ8	23:16			2.5[0]	EID[12:5]		0.5[.0.0]	
		31:24		EXIDE	SID11	[]	EID[17:13]		
		7:0				MSID[7:0]			
00450	O4MA OKO	15:8			MEID[4:0]			MSID[10:8]	
0x01D0	C1MASK8	23:16				MEID[12:5]			
		31:24		MIDE	MSID11		MEID[17:13]		
		7:0				SID[7:0]			
0x01D4	C1FLTOBJ9	15:8			EID[4:0]			SID[10:8]	
030104	CIFLIODJ9	23:16				EID[12:5]			
		31:24		EXIDE	SID11		EID[17:13]		
		7:0				MSID[7:0]			
0x01D8	C1MASK9	15:8			MEID[4:0]			MSID[10:8]	
0.00.20		23:16				MEID[12:5]			
		31:24		MIDE	MSID11		MEID[17:13]		
		7:0			EIDI ( A)	SID[7:0]		OID! 10 01	
0x01DC	C1FLTOBJ10	15:8			EID[4:0]	EID[40.5]		SID[10:8]	
		23:16 31:24		EXIDE	SID11	EID[12:5]	EID[17:13]		
		7:0		LAIDL	SIDTI	MSID[7:0]	LID[17.13]		
		15:8			MEID[4:0]	נס. זן טוטואו		MSID[10:8]	
0x01E0	C1MASK10	23:16				MEID[12:5]			
		31:24		MIDE	MSID11	1 -1	MEID[17:13]		
		7:0				SID[7:0]			
00454	CAELTOD IAA	15:8			EID[4:0]			SID[10:8]	
0x01E4	C1FLTOBJ11	23:16				EID[12:5]			
		31:24		EXIDE	SID11		EID[17:13]		
		7:0				MSID[7:0]			
0x01E8	C1MASK11	15:8			MEID[4:0]			MSID[10:8]	
0.10.120		23:16				MEID[12:5]			
		31:24		MIDE	MSID11		MEID[17:13]		
0x01EC									
 0x01FF	Reserved								
0x0200	PPSLOCK	7:0							PPSLOCKED
0x0200	RA0PPS	7:0				RA0PPS[6:0	01		. I SESSIVED
0x0201	RA1PPS	7:0				RA1PPS[6:0	-		
0x0203	RA2PPS	7:0				RA2PPS[6:0			
0x0204	RA3PPS	7:0				RA3PPS[6:0			
0x0205	RA4PPS	7:0				RA4PPS[6:0			
0x0206	RA5PPS	7:0				RA5PPS[6:0			
0x0207	RA6PPS	7:0				RA6PPS[6:0	0]		
0x0208	RA7PPS	7:0				RA7PPS[6:0	0]		
0x0209	RB0PPS	7:0				RB0PPS[6:0			
0x020A	RB1PPS	7:0				RB1PPS[6:0			
0x020B	RB2PPS	7:0				RB2PPS[6:0	0]		

conti	nuod									
			_							
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x020C	RB3PPS	7:0					RB3PPS[6:0]			
0x020D	RB4PPS	7:0					RB4PPS[6:0]			
0x020E	RB5PPS	7:0					RB5PPS[6:0]			
0x020F	RB6PPS	7:0					RB6PPS[6:0]			
0x0210	RB7PPS	7:0					RB7PPS[6:0]			
0x0211	RC0PPS	7:0					RC0PPS[6:0]			
0x0212	RC1PPS	7:0					RC1PPS[6:0]			
0x0213	RC2PPS	7:0					RC2PPS[6:0]			
0x0214	RC3PPS	7:0					RC3PPS[6:0]			
0x0215	RC4PPS	7:0					RC4PPS[6:0]			
0x0216	RC5PPS	7:0					RC5PPS[6:0]			
0x0217	RC6PPS	7:0					RC6PPS[6:0]			
0x0218	RC7PPS	7:0					RC7PPS[6:0]			
0x0219	RD0PPS	7:0					RD0PPS[6:0]			
0x021A	RD1PPS	7:0					RD1PPS[6:0]			
0x021B	RD2PPS	7:0					RD2PPS[6:0]			
0x021C	RD3PPS	7:0					RD3PPS[6:0]			
0x021D	RD4PPS	7:0					RD4PPS[6:0]			
0x021E	RD5PPS	7:0					RD5PPS[6:0]			
0x021F	RD6PPS	7:0					RD6PPS[6:0]			
0x0220	RD7PPS	7:0					RD7PPS[6:0]			
0x0221	RE0PPS	7:0					RE0PPS[6:0]			
0x0222	RE1PPS	7:0					RE1PPS[6:0]			
0x0223	RE2PPS	7:0					RE2PPS[6:0]			
0x0224										
	Reserved									
0x0228										
0x0229	RF0PPS	7:0					RF0PPS[6:0]			
0x022A	RF1PPS	7:0					RF1PPS[6:0]			
0x022B	RF2PPS	7:0					RF2PPS[6:0]			
0x022C	RF3PPS	7:0					RF3PPS[6:0]			
0x022D	RF4PPS	7:0					RF4PPS[6:0]			
0x022E	RF5PPS	7:0					RF5PPS[6:0]			
0x022F	RF6PPS	7:0					RF6PPS[6:0]			
0x0230	RF7PPS	7:0					RF7PPS[6:0]			
0x0231	107110	7.0					14 71 1 0[0.0]			
	Reserved									
0x023C	110001700									
0x023D	CANRXPPS	7:0				PORT[2:0]			PIN[2:0]	
0x023E	INT0PPS	7:0				. 5.11.[2.0]	PORT		PIN[2:0]	
0x023F	INT1PPS	7:0				PORT			PIN[2:0]	
0x0231	INT2PPS	7:0				PORT[2:0]	. [ ]		PIN[2:0]	
0x0240	TOCKIPPS	7:0				PORT[2:0]			PIN[2:0]	
0x0241	T1CKIPPS	7:0				PORT[2:0]			PIN[2:0]	
0x0242 0x0243	T1GPPS	7:0				PORT	Γ[1:0]		PIN[2:0]	
0x0243	T3CKIPPS	7:0				PORT[2:0]	.[1.0]		PIN[2:0] PIN[2:0]	
0x0244 0x0245	T3GPPS	7:0				PORT[2:0]	Γ[1:0]		PIN[2:0] PIN[2:0]	
0x0245 0x0246	T5CKIPPS	7:0				PORT[2:0]	1[1.0]		PIN[2:0] PIN[2:0]	
0x0246 0x0247	T5GPPS	7:0					Γ[1:0]		PIN[2:0] PIN[2:0]	
	T2INPPS					PORT				
0x0248		7:0				PORT			PIN[2:0]	
0x0249	T4INPPS	7:0				PORT			PIN[2:0]	
0x024A	T6INPPS	7:0				PORT	[0:1]		PIN[2:0]	
0x024B										
	Reserved									
0x024C	TUNISTED	7.0				DODT'S ST			DIATE OF	
0x024D	TUIN0PPS	7:0				PORT[2:0]			PIN[2:0]	
0x024E	TUIN1PPS	7:0				PORT[2:0]			PIN[2:0]	
0x024F	CCP1PPS	7:0				PORT[2:0]			PIN[2:0]	
0x0250	CCP2PPS	7:0				PORT[2:0]			PIN[2:0]	

continued										
Offset	Name	Bit Pos.	7	6	5	4 3	2	1	0	
				•	3					
0x0251	CCP3PPS	7:0				PORT[1:0]		PIN[2:0]		
0x0252 0x0253	Reserved PWM1ERSPPS	7:0				PORT[1:0]		PIN[2:0]		
0x0253	PWM2ERSPPS	7:0				PORT[2:0]		PIN[2:0]		
0x0254 0x0255	PWM3ERSPPS	7:0				PORT[1:0]		PIN[2:0]		
0x0255	PWM4ERSPPS	7:0				PORT[2:0]		PIN[2:0]		
0x0250	PWMIN0PPS	7:0				PORT[2:0]		PIN[2:0]		
0x0257	PWMIN1PPS	7:0				PORT[2:0]		PIN[2:0]		
0x0259	SMT1WINPPS	7:0				PORT[2:0]		PIN[2:0]		
0x025A	SMT1SIGPPS	7:0				PORT[2:0]		PIN[2:0]		
0x025B	CWG1PPS	7:0				PORT[1:0]		PIN[2:0]		
0x025C	CWG2PPS	7:0				PORT[1:0]		PIN[2:0]		
0x025D	CWG3PPS	7:0				PORT[1:0]		PIN[2:0]		
0x025E	MD1CARLPPS	7:0				PORT[1:0]		PIN[2:0]		
0x025F	MD1CARHPPS	7:0				PORT[1:0]		PIN[2:0]		
0x0260	MD1SRCPPS	7:0				PORT[1:0]		PIN[2:0]		
0x0261	CLCIN0PPS	7:0				PORT[1:0]		PIN[2:0]		
0x0262	CLCIN1PPS	7:0				PORT[1:0]		PIN[2:0]		
0x0263	CLCIN2PPS	7:0				PORT[1:0]		PIN[2:0]		
0x0264	CLCIN3PPS	7:0				PORT[1:0]		PIN[2:0]		
0x0265	CLCIN4PPS	7:0				PORT[1:0]		PIN[2:0]		
0x0266	CLCIN5PPS	7:0				PORT[1:0]		PIN[2:0]		
0x0267	CLCIN6PPS	7:0				PORT[1:0]		PIN[2:0]		
0x0268	CLCIN7PPS	7:0				PORT[1:0]		PIN[2:0]		
0x0269	ADACTPPS	7:0				PORT[1:0]		PIN[2:0]		
0x026A	SPI1SCKPPS	7:0				PORT[1:0]		PIN[2:0]		
0x026B	SPI1SDIPPS	7:0				PORT[1:0]		PIN[2:0]		
0x026C	SPI1SSPPS	7:0				PORT[1:0]		PIN[2:0]		
0x026D 0x026E	SPI2SCKPPS SPI2SDIPPS	7:0 7:0				PORT[1:0] PORT[1:0]		PIN[2:0] PIN[2:0]		
0x026E	SPI2SSPPS	7:0				PORT[1:0]		PIN[2:0]		
0x0201	I2C1SDAPPS	7:0				PORT[1:0]		PIN[2:0]		
0x0270	I2C1SCLPPS	7:0				PORT[1:0]		PIN[2:0]		
0x0272	U1RXPPS	7:0				PORT[2:0]		PIN[2:0]		
0x0273	U1CTSPPS	7:0				PORT[2:0]		PIN[2:0]		
0x0274	U2RXPPS	7:0				PORT[1:0]		PIN[2:0]		
0x0275	U2CTSPPS	7:0				PORT[1:0]		PIN[2:0]		
0x0276	U3RXPPS	7:0				PORT[2:0]		PIN[2:0]		
0x0277	U3CTSPPS	7:0				PORT[2:0]		PIN[2:0]		
0x0278	U4RXPPS	7:0				PORT[1:0]		PIN[2:0]		
0x0279	U4CTSPPS	7:0				PORT[1:0]		PIN[2:0]		
0x027A	U5RXPPS	7:0				PORT[2:0]		PIN[2:0]		
0x027B	U5CTSPPS	7:0				PORT[2:0]		PIN[2:0]		
0x027C										
	Reserved									
0x0285 0x0286	RC4I2C	7:0	CI EV	\/[1.0]	Dilit	1.01		TIL	[1:0]	
0x0286 0x0287	RC4I2C RC3I2C	7:0		N[1:0] N[1:0]	PU[ PU[	-			[1:0] [1:0]	
0x0287	RB2I2C	7:0		N[1:0]	PU[	-			[1:0]	
0x0288	RB1I2C	7:0		N[1:0]	PU[				[1:0]	
0x0289	I2C1RXB	7:0	OLLV		1 0[	RXB[7:0]		111		
0x028B	I2C1TXB	7:0				TXB[7:0]				
		7:0				CNT[7:0]				
0x028C	I2C1CNT	15:8				CNT[15:8]				
0x028E	I2C1ADB0	7:0				ADB[7:0]				
0x028F	I2C1ADB1	7:0				ADB[7:0]				
	I2C1ADR0	7:0				ADR[7:0]				
0x0290	1201710110	1.0								
0x0290 0x0291	I2C1ADR1	7:0				ADR[6:0]				

contii	nuad									
	nuea									
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x0293	I2C1ADR3	7:0				ADR[6:0]	,			
0x0294	I2C1CON0	7:0	EN	RSEN	S	CSTR	MDR		MODE[2:0]	
0x0295	I2C1CON1	7:0	ACKCNT	ACKDT	ACKSTAT	ACKT	Р	RXO	TXU	CSD
0x0296	I2C1CON2	7:0	ACNT	GCEN	FME	ABD	SDAH	T[1:0]	BFRE	T[1:0]
0x0297	I2C1ERR	7:0		BTOIF	BCLIF	NACKIF		BTOIE	BLCIE	NACKIE
0x0298	I2C1STAT0	7:0	BFRE	SMA	MMA	R	D			
0x0299	I2C1STAT1	7:0	TXWE		TXBE		RXRE	CLRBF		RXBF
0x029A	I2C1PIR	7:0	CNTIF	ACKTIF		WRIF	ADRIF	PCIF	RSCIF	SCIF
0x029B	I2C1PIE	7:0	CNTIE	ACKTIE		WRIE	ADRIE	PCIE	RSCIE	SCIE
0x029C	I2C1BTO	7:0	TOREC	TOBY32			TOTIN	1E[5:0]		
0x029D	I2C1BAUD	7:0				BAUI	D[7:0]	01.1414.01		
0x029E	I2C1CLK	7:0					I	CLK[4:0]	0[0.0]	
0x029F	I2C1BTOC	7:0						вю	C[3:0]	
0x02A0	Reserved	7.0				DVE	17.01			
0x02A1 0x02A2	U1RXB U1RXCHK	7:0 7:0					[7:0]			
0x02A2 0x02A3	U1TXB	7:0					IK[7:0] [7:0]			
0x02A3 0x02A4	U1TXCHK	7:0					IK[7:0]			
UAUZA4	OTIACHK	7:0					7:0]			
0x02A5	U1P1	15:8				FIL	ر ۰.۰۱			P1[8]
		7:0				Pol	7:0]			1 1[0]
0x02A7	U1P2	15:8				rzį	اد. ،			P2[8]
		7:0				P3I	7:0]			1 2[0]
0x02A9	U1P3	15:8				. 0[	, ,			P3[8]
0x02AB	U1CON0	7:0	BRGS	ABDEN	TXEN	RXEN		MOD	E[3:0]	. 0[0]
0x02AC	U1CON1	7:0	ON	7.00 2.11	.,	WUE	RXBIMD	02	BRKOVR	SENDB
0x02AD	U1CON2	7:0	RUNOVF	RXPOL	STE	P[1:0]	COEN	TXPOL	FLO	
		7:0					[7:0]			[]
0x02AE	U1BRG	15:8					[15:8]			
0x02B0	U1FIFO	7:0	TXWRE	STPMD	TXBE	TXBF	RXIDL	XON	RXBE	RXBF
0x02B1	U1UIR	7:0	WUIF	ABDIF				ABDIE		
0x02B2	U1ERRIR	7:0	TXMTIF	PERIF	ABDOVF	CERIF	FERIF	RXBKIF	RXFOIF	TXCIF
0x02B3	U1ERRIE	7:0	TXMTIE	PERIE	ABDOVE	CERIE	FERIE	RXBKIE	RXFOIE	TXCIE
0x02B4	U2RXB	7:0				RXE	[7:0]			
0x02B5	U2RXCHK	7:0				RXCH	IK[7:0]			
0x02B6	U2TXB	7:0				TXB	[7:0]			
0x02B7	U2TXCHK	7:0				TXCH	IK[7:0]			
0x02B8	U2P1	7:0				P1[	7:0]			
0.0200	021 1	15:8								P1[8]
0x02BA	U2P2	7:0				P2[	7:0]			
UNUZEDI (	<u> </u>	15:8								P2[8]
0x02BC	U2P3	7:0				P3[	7:0]			_
		15:8								P3[8]
0x02BE	U2CON0	7:0	BRGS	ABDEN	TXEN	RXEN		MOD	E[3:0]	
0x02BF	U2CON1	7:0	ON	D)/5-5:		WUE	RXBIMD	TVE 5:	BRKOVR	SENDB
0x02C0	U2CON2	7:0	RUNOVF	RXPOL	STF	P[1:0]	C0EN	TXPOL	FLO	[1:0]
0x02C1	U2BRG	7:0					[7:0]			
0,0000	LIDEIEO	15:8	TVMDE	QTDMD	TVDF		[15:8]	VON	פעטר	DVDF
0x02C3 0x02C4	U2FIFO U2UIR	7:0	TXWRE WUIF	STPMD ABDIF	TXBE	TXBF	RXIDL	XON ABDIE	RXBE	RXBF
0x02C4 0x02C5	U2ERRIR	7:0 7:0	TXMTIF	PERIF	ABDOVF	CERIF	FERIF	RXBKIF	RXFOIF	TXCIF
0x02C5 0x02C6	U2ERRIE	7:0	TXMTIE	PERIF	ABDOVE	CERIF	FERIE	RXBKIE	RXFOIE	TXCIE
0x02C6 0x02C7	UZERRIE U3RXB	7:0	I AIVI I IE	FERIE	ADDUVE		FERIE   [7:0]	LVDVIE	KAPUIE	IAGIE
0x02C7	Reserved	7.0				IVAE	ر، .uj			
0x02C8	U3TXB	7:0				TYR	[7:0]			
0x02C9	Reserved	7.0				1 AL				
		7:0				P11	7:0]			
0x02CB	U3P1	15:8				. 1	-1			
		10.0								

conti	nued									
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x02CD	U3P2	7:0				P2	[7:0]			
		15:8 7:0				D3	[7:0]			
0x02CF	U3P3	15:8				гэ	[7.0]			
0x02D1	U3CON0	7:0	BRGS	ABDEN	TXEN	RXEN		MOD	E[3:0]	
0x02D2	U3CON1	7:0	ON			WUE	RXBIMD		BRKOVR	SENDB
0x02D3	U3CON2	7:0	RUNOVF	RXPOL	STP	[1:0]		TXPOL	FLO	[1:0]
0x02D4	U3BRG	7:0				BRO	G[7:0]			
0.002.04	ОЗЫКО	15:8				BRG	[15:8]			
0x02D6	U3FIFO	7:0	TXWRE	STPMD	TXBE	TXBF	RXIDL	XON	RXBE	RXBF
0x02D7	U3UIR	7:0	WUIF	ABDIF				ABDIE		
0x02D8	U3ERRIR	7:0	TXMTIF	PERIF	ABDOVF	CERIF	FERIF	RXBKIF	RXFOIF	
0x02D9	U3ERRIE	7:0	TXMTIE	PERIE	ABDOVE	CERIE	FERIE	RXBKIE	RXFOIE	
0x02DA	U4RXB	7:0				RXI	3[7:0]			
0x02DB 0x02DC	Reserved U4TXB	7:0				TVE	B[7:0]			
0x02DC 0x02DD	Reserved	7.0				IAL	[0.7]			
		7:0				P1	[7:0]			
0x02DE	U4P1	15:8					[]			
		7:0				P2	[7:0]			
0x02E0	U4P2	15:8								
0.000	LIADS	7:0				P3	[7:0]		'	
0x02E2	U4P3	15:8								
0x02E4	U4CON0	7:0	BRGS	ABDEN	TXEN	RXEN		MOD	E[3:0]	•
0x02E5	U4CON1	7:0	ON			WUE	RXBIMD		BRKOVR	SENDB
0x02E6	U4CON2	7:0	RUNOVF	RXPOL	STP	[1:0]		TXPOL	FLO	[1:0]
0x02E7	U4BRG	7:0				BRO	G[7:0]			
		15:8					[15:8]			
0x02E9	U4FIFO	7:0	TXWRE	STPMD	TXBE	TXBF	RXIDL	XON	RXBE	RXBF
0x02EA	U4UIR	7:0	WUIF	ABDIF				ABDIE		
0x02EB	U4ERRIR	7:0	TXMTIF	PERIF	ABDOVF	CERIF	FERIF	RXBKIF	RXFOIF	
0x02EC	U4ERRIE	7:0	TXMTIE	PERIE	ABDOVE	CERIE	FERIE	RXBKIE	RXFOIE	
0x02ED	U5RXB	7:0				RXI	3[7:0]	I		
0x02EE	Reserved					T) /5				
0x02EF	U5TXB	7:0				TXE	3[7:0]	I		
0x02F0	Reserved	7:0				D1	[7:0]			
0x02F1	U5P1	15:8				ГІ	[7.0]			
		7:0				P2	[7:0]			
0x02F3	U5P2	15:8				12	[7.0]			
		7:0				P3	[7:0]			
0x02F5	U5P3	15:8				. •	[]			
0x02F7	U5CON0	7:0	BRGS	ABDEN	TXEN	RXEN		MOD	E[3:0]	
0x02F8	U5CON1	7:0	ON			WUE	RXBIMD		BRKOVR	SENDB
0x02F9	U5CON2	7:0	RUNOVF	RXPOL	STP	[1:0]		TXPOL	FLO	[1:0]
0.0054	LIEDDO	7:0				BRO	G[7:0]		'	
0x02FA	U5BRG	15:8				BRG	G[15:8]			
0x02FC	U5FIFO	7:0	TXWRE	STPMD	TXBE	TXBF	RXIDL	XON	RXBE	RXBF
0x02FD	U5UIR	7:0	WUIF	ABDIF				ABDIE		
0x02FE	U5ERRIR	7:0	TXMTIF	PERIF	ABDOVF	CERIF	FERIF	RXBKIF	RXFOIF	
0x02FF	U5ERRIE	7:0	TXMTIE	PERIE	ABDOVE	CERIE	FERIE	RXBKIE	RXFOIE	
		7:0					R[7:0]			
0x0300	SMT1TMR	15:8					R[15:8]			
		23:16					[23:16]			
		7:0					₹[7:0]			
0x0303	SMT1CPR	15:8					[15:8]			
		23:16				CPR	[23:16]			

conti	nued											
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0		
Oliset	Name		′	, °	5				' '	<u> </u>		
		7:0					V[7:0]					
0x0306	SMT1CPW	15:8					/[15:8]					
		23:16					[23:16]					
		7:0					[7:0]					
0x0309	SMT1PR	15:8			PR[15:8]							
		23:16				PR[2	23:16]					
0x030C	SMT1CON0	7:0	EN		STP	WPOL	SPOL	CPOL	PS	[1:0]		
0x030D	SMT1CON1	7:0	GO	REPEAT				MOD	E[3:0]			
0x030E	SMT1STAT	7:0	CPRUP	CPWUP		RST		TS	WS	AS		
0x030F	SMT1CLK	7:0						CSE	L[3:0]			
0x0310	SMT1SIG	7:0					SSEL					
0x0311	SMT1WIN	7:0					WSEL	[5:0]				
0x0312												
	Reserved											
0x0317												
0x0318	TMR0L	7:0				TMR	DL[7:0]					
0x0319	TMR0H	7:0				TMR	)H[7:0]					
0x031A	T0CON0	7:0	EN		OUT	MD16		OUTF	PS[3:0]			
0x031B	T0CON1	7:0		CS[2:0]		ASYNC			S[3:0]			
		7:0					1[7:0]					
0x031C	TMR1	15:8					1[15:8]					
0x031E	T1CON	7:0			CKPS			SYNC	RD16	ON		
0x031F	T1GCON	7:0	GE	GPOL	GTM	GSPM	GGO/DONE	GVAL	1,2.0	0.1		
0x0320	T1GATE	7:0	<u> </u>	OI OL	01111	001 111	GSS[					
0x0321	T1CLK	7:0					000[	CS[4:0]				
0x0321	T2TMR	7:0				TOTA	IR[7:0]	00[4.0]				
0x0322	T2PR	7:0					R[7:0]					
	T2CON	7:0	ON	l	CKPS[2:0]	1271	<u> </u>	OUT	PS[3:0]			
0x0324				ODOL					28[3:0]			
0x0325	T2HLT	7:0	PSYNC	CPOL	CSYNC			MODE[4:0]				
0x0326	T2CLKCON	7:0						CS[4:0]				
0x0327	T2RST	7:0					RSEL	[5:0]				
0x0328	TMR3	7:0					3[7:0]					
		15:8					3[15:8]					
0x032A	T3CON	7:0			CKPS			SYNC	RD16	ON		
0x032B	T3GCON	7:0	GE	GPOL	GTM	GSPM	GGO/DONE	GVAL				
0x032C	T3GATE	7:0					GSS[	-				
0x032D	T3CLK	7:0						CS[4:0]				
0x032E	T4TMR	7:0					IR[7:0]					
0x032F	T4PR	7:0				T4P	R[7:0]					
0x0330	T4CON	7:0	ON		CKPS[2:0]			OUTF	PS[3:0]			
0x0331	T4HLT	7:0	PSYNC	CPOL	CSYNC			MODE[4:0]				
0x0332	T4CLKCON	7:0						CS[4:0]				
0x0333	T4RST	7:0					RSEL	[5:0]				
0x0334	TMR5	7:0				TMR	5[7:0]					
UXU334	TIVIRS	15:8				TMR	5[15:8]					
0x0336	T5CON	7:0			CKPS	S[1:0]		SYNC	RD16	ON		
0x0337	T5GCON	7:0	GE	GPOL	GTM	GSPM	GGO/DONE	GVAL				
0x0338	T5GATE	7:0					GSS[					
0x0339	T5CLK	7:0						CS[4:0]				
0x033A	T6TMR	7:0				T6TM	IR[7:0]	[ ~ ]				
0x033B	T6PR	7:0					R[7:0]					
0x033C	T6CON	7:0	ON		CKPS[2:0]	101		OLITE	PS[3:0]			
0x033D	T6HLT	7:0	PSYNC	CPOL	CSYNC			MODE[4:0]	J[0.0]			
		7:0	FOING	GFUL	COTING							
0x033E	T6CLKCON						DOE	CS[4:0]				
0x033F	T6RST	7:0				007	RSEL	[0:0]				
0x0340	CCPR1	7:0					R[7:0]					
		15:8			01:=		R[15:8]					
0x0342 0x0343	CCP1CON	7:0	EN		OUT	FMT			E[3:0]			
	CCP1CAP	7:0						CTS	S[3:0]			

cont	inuea									
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x0344	CCPR2	7:0				CCPF	R[7:0]			
000044	COFICE	15:8				CCPR	[15:8]			
0x0346	CCP2CON	7:0	EN		OUT	FMT			E[3:0]	
0x0347	CCP2CAP	7:0						CTS	8[3:0]	
0x0348	CCPR3	7:0				CCPF				
0x034A	CORROON	15:8	EN		OUT	CCPR	[15:8]	MOD	T[2.0]	
0x034A 0x034B	CCP3CON CCP3CAP	7:0 7:0	EN		OUT	FMT			E[3:0] S[3:0]	
0x034B	CCPTMRS0	7:0			CSTSI	EL[1:0]	Cate	EL[1:0]	C1TSE	EL [1·0]
0x034C	CCI TWINGO	7.0			03101		0210	LL[1.0]	CTTOL	_L[1.0]
	Reserved									
0x034E										
		7:0				CRCDA	ΓAL[7:0]			
0x034F	CDCDATA	15:8				CRCDAT	TAH[7:0]			
UXU34F	CRCDATA	23:16				CRCDAT	TAU[7:0]			
		31:24				CRCDA	ΓΑΤ[7:0]			
		7:0				CRCOU				
0x0353	CRCOUT	15:8				CRCOU				
		23:16				CRCOU				
		31:24				CRCOU				
		7:0 15:8				CRCSHI				
0x0353	CRCSHIFT	23:16				CRCSHII				
		31:24				CRCSHII				
		7:0				CRCXO				
		15:8				CRCXO				
0x0353	CRCXOR	23:16				CRCXO				
		31:24				CRCXO				
0x0357	CRCCON0	7:0	EN	GO	BUSY	ACCM	SETU	JP[1:0]	SHIFTM	FULL
0x0358	CRCCON1	7:0						PLEN[4:0]		
0x0359	CRCCON2	7:0						DLEN[4:0]		
0x035A										
	Reserved									
0x035F	COANCONO	7.0	- FN	TDIOEN	SGO			MDEC	DUDGTMD	DUCY
0x0360 0x0361	SCANCON0 SCANTRIG	7:0 7:0	EN	TRIGEN	SGO			MREG TSEL[4:0]	BURSTMD	BUSY
0x0361	IPR0	7:0	IOCIP	CANIP	CLC1IP	TU16AIP	CSWIP	OSFIP	HLVDIP	SWINTIP
0x0363	IPR1	7:0	SMT1PWAIP	SMT1PRAIP	SMT1IP	CM1IP	ACTIP	ADIP	ZCDIP	INTOIP
0x0364	IPR2	7:0	DMA1AIP		DMA1DCNTIP		ADCH4IP	ADCH3IP	ADCH2IP	ADCH1IP
0x0365	IPR3	7:0	TMR0IP	CCP1IP	TMR1GIP	TMR1IP	TMR2IP	SPI1IP	SPI1TXIP	SPI1RXIP
0x0366	IPR4	7:0	PWM1IP	PWM1PIP	CANTIP	CANRIP	U1IP	U1EIP	U1TXIP	U1RXIP
0x0367	IPR5	7:0	PWM2IP	PWM2PIP	TMR3GIP	TMR3IP	TU16BIP	SPI2IP	SPI2TXIP	SPI2RXIP
0x0368	IPR6	7:0	DMA2AIP	DMA2ORIP	DMA2DCNTIP	DMA2SCNTIP	NCO1IP	CWG1IP	CLC2IP	INT1IP
0x0369	IPR7	7:0	PWM3IP	PWM3PIP	CLC3IP		I2C1EIP	I2C1IP	I2C1TXIP	I2C1RXIP
0x036A	IPR8	7:0	SCANIP	CCP2IP	TMR5GIP	TMR5IP	U2IP	U2EIP	U2TXIP	U2RXIP
0x036B	IPR9	7:0	PWM4IP	PWM4PIP	CLC4IP		U3IP	U3EIP	U3TXIP	U3RXIP
0x036C	IPR10	7:0	DMA3AIP	DMA3ORIP	DMA3DCNTIP		NCO2IP	CWG2IP	CLC5IP	INT2IP
0x036D	IPR11	7:0	DMA4AIP		DMA4DCNTIP		TMR4IP	CWG3IP	CLC6IP	CCP3IP
0x036E 0x036F	IPR12 IPR13	7:0 7:0	DMA5AIP DMA6AIP		DMA5DCNTIP		U4IP U5IP	U4EIP U5EIP	U4TXIP U5TXIP	U4RXIP U5RXIP
0x036F 0x0370	IPR13	7:0	DMA7AIP		DMA7DCNTIP		NCO3IP	CM2IP	CLC7IP	USKAIP
0x0370	IPR15	7:0	DMA8AIP		DMA8DCNTIP		TMR6IP	CRCIP	CLC7IP CLC8IP	NVMIP
0x0371	Reserved	7.5	/ W	2 (00) (11)	ODOITH	55514111		31.011	520011	
0x0373	STATUS_CSHAD	7:0		TO	PD	N	OV	Z	DC	С
0x0374	WREG_CSHAD	7:0		-	1	WREC		I	-	-
0x0375	BSR_CSHAD	7:0						R[5:0]		
0x0376	SHADCON	7:0								SHADLO
0x0377	STATUS_SHAD	7:0		TO	PD	N	OV	Z	DC	С
0x0378	WREG_SHAD	7:0				WREC	G[7:0]			

conti	inued												
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0			
0x0379	BSR_SHAD	7:0					BSR						
0x0379	Reserved	7.0					ВОК	.[3.0]					
		7:0				PCLAT	 ГН[7:0]						
0x037B	PCLAT_SHAD	15:8					[]	PCLATU[4:0]					
		7:0		FSRL[7:0]									
0x037D	FSR0_SHAD	15:8		FSRH[5:0]									
0.0075	E0D4 0114D	7:0		FSRL[7:0]									
0x037F	FSR1_SHAD	15:8		FSRH[5:0]									
0x0381	FSR2_SHAD	7:0		FSRL[7:0]									
000001	F3RZ_3HAD	15:8					FSRI	H[5:0]					
0x0383	PROD_SHAD	7:0				PROI							
	11100_011/10	15:8				PROD	[15:8]						
0x0385													
	Reserved												
0x0386													
0x0387	TU16ACON0	7:0	ON	CPOL	OM	OPOL	RDSEL	PRIE	ZIE	CIE			
0x0388	TU16ACON1	7:0	RUN	OSEN	CLR	LIMIT	CAPT	PRIF	ZIF	CIF			
0x0389	TU16AHLT	7:0	EPOL	CSYNC	STAR		RESE	: [1:0]	STOR	·[1:0]			
0x038A	TU16APS	7:0				PS[	-						
0x038B	TU16ATMR	7:0 15:8				TMR							
				TMR[15:8]									
0x038B	TU16ACR	15:8	7:0 CR[7:0]										
		7:0		CR[15:8] PR[7:0]									
0x038D	TU16APR	15:8				PR[							
0x038F	TU16ACLK	7:0				PRI	15.0]	CLK[4:0]					
0x036F	TU16ACLK TU16AERS	7:0					ERS						
0x0390 0x0391	TOTOALKS	7.0					ERO	[5.0]					
	Reserved												
 0x0392	reserved												
0x0393	TU16BCON0	7:0	ON	CPOL	OM	OPOL	RDSEL	PRIE	ZIE	CIE			
0x0394	TU16BCON1	7:0	RUN	OSEN	CLR	LIMIT	CAPT	PRIF	ZIF	CIF			
0x0395	TU16BHLT	7:0	EPOL	CSYNC									
0x0396					START[1:0] RESET[1:0] STOP[1:0]								
	1016825	7:0											
l	TU16BPS	7:0 7:0				PS[	7:0]						
0x0397	TU16BTMR	7:0 7:0 15:8				PS[ TMR	7:0] R[7:0]						
	TU16BTMR	7:0				PS[ TMR TMR	7:0] R[7:0] [15:8]						
0x0397		7:0 15:8				PS[ TMR	7:0] [7:0] [15:8] [7:0]						
0x0397	TU16BTMR TU16BCR	7:0 15:8 7:0				PS[ TMR TMR CR	7:0] [7:0] [15:8] 7:0]						
	TU16BTMR	7:0 15:8 7:0 15:8				PS[ TMR TMR CR[ CR[	7:0] 2[7:0] [15:8] 7:0] 15:8] 7:0]						
0x0397	TU16BTMR TU16BCR	7:0 15:8 7:0 15:8 7:0				PS[ TMR TMR CR[ CR[	7:0] 2[7:0] [15:8] 7:0] 15:8] 7:0]	CLK[4:0]					
0x0397 0x0399	TU16BTMR  TU16BCR  TU16BPR	7:0 15:8 7:0 15:8 7:0 15:8				PS[ TMR TMR CR[ CR[	7:0] 2[7:0] [15:8] 7:0] 15:8] 7:0]						
0x0397 0x0399 0x039B	TU16BTMR  TU16BCR  TU16BPR  TU16BCLK  TU16BERS	7:0 15:8 7:0 15:8 7:0 15:8 7:0				PS[ TMR TMR CR[ CR[	7:0] [7:0] [15:8] 7:0] 15:8] 7:0] 15:8]						
0x0397 0x0399 0x039B 0x039C 0x039D 	TU16BTMR  TU16BCR  TU16BPR  TU16BCLK	7:0 15:8 7:0 15:8 7:0 15:8 7:0				PS[ TMR TMR CR[ CR[	7:0] [7:0] [15:8] 7:0] 15:8] 7:0] 15:8]						
0x0397 0x0399 0x039B 0x039C 0x039D  0x03BA	TU16BTMR  TU16BCR  TU16BPR  TU16BCLK  TU16BERS  Reserved	7:0 15:8 7:0 15:8 7:0 15:8 7:0 7:0				PS[ TMR TMR CR[ CR[	7:0] [7:0] [15:8] 7:0] 15:8] 7:0] 15:8]						
0x0397 0x0399 0x039B 0x039C 0x039D  0x03BA 0x03BB	TU16BTMR  TU16BCR  TU16BPR  TU16BCLK  TU16BERS  Reserved  TUCHAIN	7:0 15:8 7:0 15:8 7:0 15:8 7:0 7:0 7:0				PS[ TMR TMR CR[ CR[	7:0] [7:0] [15:8] 7:0] 15:8] 7:0] 15:8]			CH16AB			
0x0397 0x0399 0x039B 0x039C 0x039D  0x03BA 0x03BB 0x03BC	TU16BTMR  TU16BCR  TU16BPR  TU16BCLK  TU16BERS  Reserved  TUCHAIN  CWG1CLK	7:0 15:8 7:0 15:8 7:0 15:8 7:0 7:0 7:0				PS[ TMR TMR CR[ CR[	7:0] [7:0] [15:8] 7:0] 15:8] 7:0] 15:8]	[5:0]		CH16AB CS			
0x0397 0x0399 0x039B 0x039C 0x039D  0x03BA 0x03BB 0x03BC 0x03BD	TU16BTMR  TU16BCR  TU16BPR  TU16BCLK  TU16BERS  Reserved  TUCHAIN  CWG1CLK  CWG1ISM	7:0 15:8 7:0 15:8 7:0 15:8 7:0 7:0 7:0 7:0				PS[ TMR TMR CR[ CR[	7:0] [7:0] [15:8] 7:0] 15:8] 7:0] 15:8] ERS	[5:0] ISM[4:0]					
0x0397  0x0399  0x039B  0x039C  0x039D   0x03BA  0x03BB  0x03BC  0x03BD  0x03BD	TU16BTMR  TU16BCR  TU16BPR  TU16BCLK  TU16BERS  Reserved  TUCHAIN  CWG1CLK  CWG1ISM  CWG1DBR	7:0 15:8 7:0 15:8 7:0 15:8 7:0 7:0 7:0 7:0 7:0 7:0				PS[ TMR TMR CR[ CR[	7:0] [7:0] [7:0] [15:8] 7:0] [15:8] 7:0] [15:8] ERS	[5:0] ISM[4:0] :[5:0]					
0x0397  0x0399  0x039B  0x039C  0x039D   0x03BA  0x03BB  0x03BC  0x03BD  0x03BD	TU16BTMR  TU16BCR  TU16BPR  TU16BCLK  TU16BERS  Reserved  TUCHAIN  CWG1CLK  CWG1ISM  CWG1DBR  CWG1DBF	7:0 15:8 7:0 15:8 7:0 15:8 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0				PS[ TMR TMR CR[ CR[	7:0] [7:0] [15:8] 7:0] 15:8] 7:0] 15:8] ERS	[5:0] ISM[4:0] :[5:0]	MODETO CL				
0x0397  0x0399  0x039B  0x039C  0x039D   0x03BA  0x03BB  0x03BC  0x03BD  0x03BD  0x03BE  0x03BF  0x03CO	TU16BTMR  TU16BCR  TU16BPR  TU16BCLK  TU16BERS  Reserved  TUCHAIN  CWG1CLK  CWG1ISM  CWG1DBR  CWG1DBF  CWG1CON0	7:0 15:8 7:0 15:8 7:0 15:8 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0	EN	LD		PS[ TMR TMR CR[ CR[	7:0] [7:0] [7:0] [15:8] 7:0] [15:8] 7:0] [15:8] ERS	ISM[4:0] :[5:0]	MODE[2:0]	CS			
0x0397  0x0399  0x039B  0x039C  0x039D   0x03BA  0x03BB  0x03BC  0x03BD  0x03BD  0x03BE  0x03BF  0x03CO  0x03C1	TU16BTMR  TU16BCR  TU16BPR  TU16BCLK  TU16BERS  Reserved  TUCHAIN  CWG1CLK  CWG1ISM  CWG1DBR  CWG1DBF  CWG1CON0  CWG1CON1	7:0 15:8 7:0 15:8 7:0 15:8 7:0 15:8 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0			IN	PS[ TMF TMR CR[ CR[ PR[	7:0] [7:0] [7:0] [15:8] [7:0] [15:8] [7:0] [15:8]  ERS  DBR DBF	ISM[4:0]  [5:0]  [5:0]  POLC	MODE[2:0] POLB				
0x0397  0x0399  0x039B  0x039C  0x039D   0x03BA  0x03BB  0x03BC  0x03BD  0x03BD  0x03BF  0x03C1  0x03C2	TU16BTMR  TU16BCR  TU16BPR  TU16BCLK  TU16BERS  Reserved  TUCHAIN  CWG1CLK  CWG1ISM  CWG1DBR  CWG1DBF  CWG1CON0  CWG1CON1  CWG1AS0	7:0 15:8 7:0 15:8 7:0 15:8 7:0 15:8 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0	SHUTDOWN	REN	LSBE	PS[ TMF TMR CR[ CR[ PR[	7:0] [7:0] [7:0] [15:8] [7:0] [15:8] [7:0] [15:8]  ERS  DBR  DBR  DBF  POLD  LSAG	[5:0]  ISM[4:0]  [5:0]  POLC  C[1:0]	POLB	CS			
0x0397  0x0399  0x039B  0x039C  0x039D   0x03BA  0x03BB  0x03BC  0x03BD  0x03BE  0x03BF  0x03C1  0x03C2  0x03C3	TU16BTMR  TU16BCR  TU16BPR  TU16BCLK  TU16BERS  Reserved  TUCHAIN  CWG1CLK  CWG1ISM  CWG1DBR  CWG1DBF  CWG1CON0  CWG1CON1  CWG1AS0  CWG1AS1	7:0 15:8 7:0 15:8 7:0 15:8 7:0 15:8 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0	SHUTDOWN AS7E	REN AS6E	LSBE AS5E	PS[ TMF TMR CR[ CR[ PR[ PR[	7:0] [7:0] [7:0] [15:8] [7:0] [15:8] [7:0] [15:8]  ERS  DBR  DBR  DBF  POLD  LSAC  AS3E	ISM[4:0]  ISM[4:0]  [5:0]  POLC  C[1:0]  AS2E	POLB AS1E	POLA AS0E			
0x0397  0x0399  0x039B  0x039C  0x039D   0x03BA  0x03BB  0x03BC  0x03BD  0x03BE  0x03BF  0x03C1  0x03C2  0x03C3  0x03C4	TU16BTMR  TU16BCR  TU16BPR  TU16BCLK  TU16BERS  Reserved  TUCHAIN  CWG1CLK  CWG1SM  CWG1DBR  CWG1DBF  CWG1CON0  CWG1CON1  CWG1AS0  CWG1AS1  CWG1STR	7:0 15:8 7:0 15:8 7:0 15:8 7:0 15:8 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0	SHUTDOWN	REN	LSBE	PS[ TMF TMR CR[ CR[ PR[	7:0] [7:0] [7:0] [15:8] [7:0] [15:8] [7:0] [15:8]  ERS  DBR  DBR  DBF  POLD  LSAG	[5:0]  ISM[4:0]  [5:0]  POLC  C[1:0]	POLB	POLA AS0E STRA			
0x0397  0x0399  0x039B  0x039C  0x039D   0x03BA  0x03BB  0x03BC  0x03BD  0x03BF  0x03C1  0x03C2  0x03C3  0x03C4  0x03C5	TU16BTMR  TU16BCR  TU16BPR  TU16BCLK  TU16BERS  Reserved  TUCHAIN  CWG1CLK  CWG1ISM  CWG1DBR  CWG1DBF  CWG1CON0  CWG1CON1  CWG1AS0  CWG1AS1  CWG1STR  CWG2CLK	7:0 15:8 7:0 15:8 7:0 15:8 7:0 15:8 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0	SHUTDOWN AS7E	REN AS6E	LSBE AS5E	PS[ TMF TMR CR[ CR[ PR[ PR[	7:0] [7:0] [7:0] [15:8] [7:0] [15:8] [7:0] [15:8]  ERS  DBR  DBR  DBF  POLD  LSAC  AS3E	ISM[4:0] [5:0] [5:0] [5:0] POLC C[1:0] AS2E STRC	POLB AS1E	POLA AS0E			
0x0397  0x0399  0x039B  0x039C  0x039D   0x03BA  0x03BB  0x03BC  0x03BD  0x03BF  0x03BF  0x03C1  0x03C2  0x03C3  0x03C4  0x03C5  0x03C6	TU16BTMR  TU16BCR  TU16BPR  TU16BCLK  TU16BERS  Reserved  TUCHAIN  CWG1CLK  CWG1SM  CWG1DBR  CWG1CON0  CWG1CON1  CWG1AS0  CWG1AS1  CWG1STR  CWG2CLK  CWG2ISM	7:0 15:8 7:0 15:8 7:0 15:8 7:0 15:8 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0	SHUTDOWN AS7E	REN AS6E	LSBE AS5E	PS[ TMF TMR CR[ CR[ PR[ PR[	7:0] [7:0] [7:0] [15:8] [7:0] [15:8] [7:0] [15:8]  ERS  DBR  DBR  DBF  POLD  LSAC  AS3E  STRD	ISM[4:0]  ISM[4:0]  [5:0]  POLC  C[1:0]  AS2E  STRC  ISM[4:0]	POLB AS1E	POLA AS0E STRA			
0x0397  0x0399  0x039B  0x039C  0x039D   0x03BA  0x03BB  0x03BC  0x03BD  0x03BF  0x03C1  0x03C2  0x03C3  0x03C4  0x03C5	TU16BTMR  TU16BCR  TU16BPR  TU16BCLK  TU16BERS  Reserved  TUCHAIN  CWG1CLK  CWG1ISM  CWG1DBR  CWG1DBF  CWG1CON0  CWG1CON1  CWG1AS0  CWG1AS1  CWG1STR  CWG2CLK	7:0 15:8 7:0 15:8 7:0 15:8 7:0 15:8 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0 7:0	SHUTDOWN AS7E	REN AS6E	LSBE AS5E	PS[ TMF TMR CR[ CR[ PR[ PR[	7:0] [7:0] [7:0] [15:8] [7:0] [15:8] [7:0] [15:8]  ERS  DBR  DBR  DBF  POLD  LSAC  AS3E	ISM[4:0]  ISM[4:0]  [5:0]  POLC  C[1:0]  AS2E  STRC  ISM[4:0]	POLB AS1E	POLA AS0E STRA			

Offset  0x03C9  0x03CA  0x03CB  0x03CC  0x03CC	Name CWG2CON0	Bit Pos.	7	6	5	4	3	2			
0x03C9 0x03CA 0x03CB 0x03CC	CWG2CON0		7	6	5	A	2				
0x03CA 0x03CB 0x03CC						, ,	"	4	1	0	
0x03CB 0x03CC	CIMICOCONIA	7:0	EN	LD					MODE[2:0]		
0x03CC	CWG2CON1	7:0			IN		POLD	POLC	POLB	POLA	
	CWG2AS0	7:0	SHUTDOWN	REN	LSBI	D[1:0]	LSA	C[1:0]			
0x03CD	CWG2AS1	7:0	AS7E	AS6E	AS5E	AS4E	AS3E	AS2E	AS1E	AS0E	
	CWG2STR	7:0	OVRD	OVRC	OVRB	OVRA	STRD	STRC	STRB	STRA	
0x03CE	CWG3CLK	7:0								CS	
0x03CF	CWG3ISM	7:0						ISM[4:0]			
0x03D0	CWG3DBR	7:0					DBF	R[5:0]			
0x03D1	CWG3DBF	7:0					DBF	[5:0]			
0x03D2	CWG3CON0	7:0	EN	LD					MODE[2:0]		
0x03D3	CWG3CON1	7:0			IN		POLD	POLC	POLB	POLA	
0x03D4	CWG3AS0	7:0	SHUTDOWN	REN	LSBI	D[1:0]	LSA	C[1:0]			
0x03D5	CWG3AS1	7:0	AS7E	AS6E	AS5E	AS4E	AS3E	AS2E	AS1E	AS0E	
0x03D6	CWG3STR	7:0	OVRD	OVRC	OVRB	OVRA	STRD	STRC	STRB	STRA	
0x03D7	FVRCON	7:0	EN	RDY	TSEN	TSRNG		VR[1:0]	ADFV		
0x03D8	ADCP	7:0	CPON							CPRDY	
		7:0				ITH	[7:0]				
0x03D9	ADLTH	15:8					15:8]				
		7:0				UTH					
0x03DB	ADUTH	15:8				UTH					
		7:0									
0x03DD	ADERR	15:8		ERR[7:0]  ERR[15:8]							
		7:0				STP					
0x03DF	ADSTPT	15:8				STPT					
		7:0				FLTF					
0x03E1	ADFLTR	15:8									
		7:0	FLTR[15:8]								
0,0252	ADACC	15:8	ACC[7:0] ACC[15:8]								
0x03E3						ACC	[15:8]		1004	47.401	
00050	ADCNT	23:16 7:0				ONT	77.01		ACC[	17:16]	
0x03E6		7:0				CNT					
0x03E7	ADRPT						[7:0]				
0x03E8	ADPREV	7:0	PREV[7:0] PREV[15:8]								
		15:8									
0x03EA	ADRES	7:0				RES					
0.0050	ADDOLL	15:8			I	KES	[15:8]	155 01			
0x03EC	ADPCH	7:0					PCF	·[5:0]			
0x03ED	Reserved	7.0				100	17.01				
0x03EE	ADACQ	7:0				ACC	ι[ <i>τ</i> :U]	ACO[40:03			
0,0050	ADOAD	15:8						ACQ[12:8]			
0x03F0	ADCAP	7:0				555	77.01	CAP[4:0]			
0x03F1	ADPRE	7:0				PRE	[7:0]	DDE!40.03			
0.0050		15:8	0	00117	00711			PRE[12:8]		60	
0x03F3	ADCON0	7:0	ON	CONT	CSEN	CS		FM		GO	
0x03F4	ADCON1	7:0	PPOL	IPEN	GPOL OF		401-		Mara	DSEN	
0x03F5	ADCON2	7:0	PSIS		CRS[2:0]		ACLR		MD[2:0]		
0x03F6	ADCON3	7:0			CALC[2:0]		SOI		TMD[2:0]		
0x03F7	ADSTAT	7:0	AOV	UTHR	LTHR	MATH			STAT[2:0]		
0x03F8	ADREF	7:0				NREF			PRE	-[1:0]	
0x03F9	ADACT	7:0						[5:0]			
0x03FA	ADCLK	7:0					CS	[5:0]			
0x03FB	ADCTX	7:0	CTXSW						СТХ	[1:0]	
0x03FC	ADCSEL1	7:0	CHEN	SSI							
0x03FD	ADCSEL2	7:0	CHEN	SSI							
0x03FE	ADCSEL3	7:0	CHEN	SSI							
0x03FF	ADCSEL4	7:0	CHEN	SSI							
0x0400	ANSELA	7:0	ANSELA7	ANSELA6	ANSELA5	ANSELA4	ANSELA3	ANSELA2	ANSELA1	ANSELA0	
	WPUA	7:0	WPUA7	WPUA6	WPUA5	WPUA4	WPUA3	WPUA2	WPUA1	WPUA0	
0x0401		7:0	ODCA7	ODCA6	ODCA5	ODCA4	ODCA3	ODCA2	ODCA1	ODCA0	
0x0401 0x0402	ODCONA	7.0	ODONI	000,10	000/10	000/14	000/10	ODONE	OBOATI	020/10	

contii	nued											
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0		
0x0404	INLVLA	7:0	INLVLA7	INLVLA6	INLVLA5	INLVLA4	INLVLA3	INLVLA2	INLVLA1	INLVLA0		
0x0405	IOCAP	7:0	IOCAP7	IOCAP6	IOCAP5	IOCAP4	IOCAP3	IOCAP2	IOCAP1	IOCAP0		
0x0406	IOCAN	7:0	IOCAN7	IOCAN6	IOCAN5	IOCAN4	IOCAN3	IOCAN2	IOCAN1	IOCAN0		
0x0407	IOCAF	7:0	IOCAF7	IOCAF6	IOCAF5	IOCAF4	IOCAF3	IOCAF2	IOCAF1	IOCAF0		
0x0408	ANSELB WPUB	7:0	ANSELB7	ANSELB6 WPUB6	ANSELB5	ANSELB4 WPUB4	ANSELB3	ANSELB2	ANSELB1	ANSELB0		
0x0409 0x040A	ODCONB	7:0 7:0	WPUB7 ODCB7	ODCB6	WPUB5 ODCB5	ODCB4	WPUB3 ODCB3	WPUB2 ODCB2	WPUB1 ODCB1	WPUB0 ODCB0		
0x040A 0x040B	SLRCONB	7:0	SLRB7	SLRB6	SLRB5	SLRB4	SLRB3	SLRB2	SLRB1	SLRB0		
0x040B	INLVLB	7:0	INLVLB7	INLVLB6	INLVLB5	INLVLB4	INLVLB3	INLVLB2	INLVLB1	INLVLB0		
0x040C	IOCBP	7:0	IOCBP7	IOCBP6	IOCBP5	IOCBP4	IOCBP3	IOCBP2	IOCBP1	IOCBP0		
0x040E	IOCBN	7:0	IOCBN7	IOCBN6	IOCBN5	IOCBN4	IOCBN3	IOCBN2	IOCBN1	IOCBN0		
0x040F	IOCBF	7:0	IOCBF7	IOCBF6	IOCBF5	IOCBF4	IOCBF3	IOCBF2	IOCBF1	IOCBF0		
0x0410	ANSELC	7:0	ANSELC7	ANSELC6	ANSELC5	ANSELC4	ANSELC3	ANSELC2	ANSELC1	ANSELC0		
0x0411	WPUC	7:0	WPUC7	WPUC6	WPUC5	WPUC4	WPUC3	WPUC2	WPUC1	WPUC0		
0x0412	ODCONC	7:0	ODCC7	ODCC6	ODCC5	ODCC4	ODCC3	ODCC2	ODCC1	ODCC0		
0x0413	SLRCONC	7:0	SLRC7	SLRC6	SLRC5	SLRC4	SLRC3	SLRC2	SLRC1	SLRC0		
0x0414	INLVLC	7:0	INLVLC7	INLVLC6	INLVLC5	INLVLC4	INLVLC3	INLVLC2	INLVLC1	INLVLC0		
0x0415	IOCCP	7:0	IOCCP7	IOCCP6	IOCCP5	IOCCP4	IOCCP3	IOCCP2	IOCCP1	IOCCP0		
0x0416	IOCCN	7:0	IOCCN7	IOCCN6	IOCCN5	IOCCN4	IOCCN3	IOCCN2	IOCCN1	IOCCN0		
0x0417	IOCCF	7:0	IOCCF7	IOCCF6	IOCCF5	IOCCF4	IOCCF3	IOCCF2	IOCCF1	IOCCF0		
0x0418	ANSELD	7:0	ANSELD7	ANSELD6	ANSELD5	ANSELD4	ANSELD3	ANSELD2	ANSELD1	ANSELD0		
0x0419	WPUD	7:0	WPUD7	WPUD6	WPUD5	WPUD4	WPUD3	WPUD2	WPUD1	WPUD0		
0x041A	ODCOND	7:0	ODCD7	ODCD6	ODCD5	ODCD4	ODCD3	ODCD2	ODCD1	ODCD0		
0x041B	SLRCOND	7:0	SLRD7	SLRD6	SLRD5	SLRD4	SLRD3	SLRD2	SLRD1	SLRD0		
0x041C	INLVLD	7:0	INLVLD7	INLVLD6	INLVLD5	INLVLD4	INLVLD3	INLVLD2	INLVLD1	INLVLD0		
0x041D												
	Reserved											
0x041F												
0x0420	ANSELE	7:0						ANSELE2	ANSELE1	ANSELE0		
0x0421	WPUE	7:0					WPUE3	WPUE2	WPUE1	WPUE0		
0x0422	ODCONE	7:0						ODCE2	ODCE1	ODCE0		
0x0423	SLRCONE	7:0						SLRE2	SLRE1	SLRE0		
0x0424	INLVLE	7:0					INLVLE3	INLVLE2	INLVLE1	INLVLE0		
0x0425	IOCEP	7:0					IOCEP3					
0x0426	IOCEN	7:0					IOCEN3					
0x0427	IOCEF	7:0					IOCEF3					
0x0428	ANSELF	7:0	ANSELF7	ANSELF6	ANSELF5	ANSELF4	ANSELF3	ANSELF2	ANSELF1	ANSELF0		
0x0429	WPUF	7:0	WPUF7	WPUF6	WPUF5	WPUF4	WPUF3	WPUF2	WPUF1	WPUF0		
0x042A	ODCONF	7:0	ODCF7	ODCF6	ODCF5	ODCF4	ODCF3	ODCF2	ODCF1	ODCF0		
0x042B	SLRCONF	7:0	SLRF7	SLRF6	SLRF5	SLRF4	SLRF3	SLRF2	SLRF1	SLRF0		
0x042C	INLVLF	7:0	INLVLF7	INLVLF6	INLVLF5	INLVLF4	INLVLF3	INLVLF2	INLVLF1	INLVLF0		
0x042D	Reserved											
0x043F	Reserved											
0.0401		7:0				ACC	[7:0]					
0x0440	NCO1ACC	15:8					[15:8]					
0,0440	11001/100	23:16				7.00	[10.0]	ACCI	19:16]			
		7:0				INC	[7·0]	7,00[	10.10]			
0x0443	NCO1INC			INC[7:0] INC[15:8]								
0,0440	NOOTINO	23:16				1140[	10.0]	INCI	19:16]			
0x0446	NCO1CON	7:0	EN		OUT	POL		1140[		PFM		
0x0447	NCO1CLK	7:0	_,,	PWS[2:0]				CKS[4:0]				
	55.561	7:0				ACC	[7:0]	[0]				
0x0448	NCO2ACC	15:8					[15:8]					
55170	502/100	23:16				7.00		ACCI	19:16]			
		7:0				INC	[7:0]	,,,,,,				
0x044B	NCO2INC	15:8					15:8]					
		23:16				10[	,	INCI	19:16]			
0x044E	NCO2CON	7:0	EN		OUT	POL			•,	PFM		
			_, ,									

# **Register Summary**

DS40002259A-page 1079

a a mati	aad										
conti	nuea										
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0	
0x044F	NCO2CLK	7:0		PWS[2:0]	,		,	CKS[4:0]	,		
	NCO3ACC	7:0				ACC					
0x0450		15:8				ACC	[15:8]				
		23:16						ACC[	19:16]		
		7:0				INC	[7:0]				
0x0453	NCO3INC	15:8				INC[	15:8]				
		23:16				INC[19:16]					
0x0456	NCO3CON	7:0	EN		OUT	POL				PFM	
0x0457	NCO3CLK	7:0		PWS[2:0]				CKS[4:0]			
0x0458	FSCMCON	7:0			FSCMSFI	FSCMSEV	FSCMPFI	FSCMPEV	FSCMFFI	FSCMFEV	
0x0459	IVTLOCK	7:0								IVTLOCKED	
		7:0				IVTAD					
0x045A	IVTAD	15:8				IVTAD	)H[7:0]				
		23:16						IVTADU[4:0]			
		7:0				IVTBAS					
0x045D	IVTBASE	15:8				IVTBAS	SEH[7:0]				
		23:16						IVTBASEU[4:0			
0x0460	PWM1ERS	7:0						ERS[4:0]			
0x0461	PWM1CLK	7:0						CLK[4:0]			
0x0462	PWM1LDS	7:0						LDS[4:0]			
0x0463	PWM1PR	7:0					[7:0]				
0.0403	1 VVIVITI IX	15:8				PR[	15:8]				
0x0465	PWM1CPRE	7:0				CPRI	E[7:0]				
0x0466	PWM1PIPOS	7:0				PIPO	S[7:0]				
0x0467	PWM1GIR	7:0							S1P2	S1P1	
0x0468	PWM1GIE	7:0							S1P2	S1P1	
0x0469	PWM1CON	7:0	EN					LD	ERSPOL	ERSNOW	
0x046A	PWM1S1CFG	7:0	POL2	POL1			PPEN		MODE[2:0]		
0x046B	PWM1S1P1	7:0				P1[	7:0]				
000400	T WWITO II I	15:8	P1[15:8]								
0x046D	PWM1S1P2	7:0				P2[	7:0]				
ОХОЧОВ	1 *************************************	15:8				P2[1	15:8]				
0x046F	PWM2ERS	7:0						ERS[4:0]			
0x0470	PWM2CLK	7:0						CLK[4:0]			
0x0471	PWM2LDS	7:0						LDS[4:0]			
0x0472	PWM2PR	7:0					[7:0]				
		15:8					15:8]				
0x0474	PWM2CPRE	7:0				CPRI					
0x0475	PWM2PIPOS	7:0				PIPO	S[7:0]				
0x0476	PWM2GIR	7:0							S1P2	S1P1	
0x0477	PWM2GIE	7:0							S1P2	S1P1	
0x0478	PWM2CON	7:0	EN					LD	ERSPOL	ERSNOW	
0x0479	PWM2S1CFG	7:0	POL2	POL1			PPEN		MODE[2:0]		
0x047A	PWM2S1P1	7:0		P1[7:0] P1[15:8]							
		15:8									
0x047C	PWM2S1P2	7:0					7:0]				
0.0475	DWWACEDO	15:8				P2[1	15:8]	EDOM O			
0x047E	PWM3ERS	7:0						ERS[4:0]			
0x047F	PWM3CLK	7:0						CLK[4:0]			
0x0480	PWM3LDS	7:0				DC.	7.01	LDS[4:0]			
0x0481	PWM3PR	7:0					[7:0]				
		15:8					15:8]				
0x0483	PWM3CPRE	7:0				CPRI					
0x0484	PWM3PIPOS	7:0				PIPO	<b>၁</b> [/:U]		C4D0	0404	
0x0485	PWM3GIR	7:0							S1P2	S1P1	
0x0486	PWM3GIE	7:0	- KI					1.5	S1P2	S1P1	
0x0487	PWM3CON	7:0	EN	DOL 4			DDCN	LD	ERSPOL MODE(2:01	ERSNOW	
0x0488	PWM3S1CFG	7:0	POL2	POL1			PPEN		MODE[2:0]		

© 2020 Microchip Technology Inc.

conti	nued												
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0			
		7:0				P1[	7:01						
0x0489	PWM3S1P1	15:8				P1[1							
		7:0				P2[							
0x048B	PWM3S1P2	15:8				P2[1							
0x048D	PWM4ERS	7:0						ERS[4:0]					
0x048E	PWM4CLK	7:0		CLK[4:0]									
0x048F	PWM4LDS	7:0						LDS[4:0]					
		7:0				PR[	7:01						
0x0490	PWM4PR	15:8				PR[′							
0x0492	PWM4CPRE	7:0				CPR							
0x0493	PWM4PIPOS	7:0				PIPO							
0x0494	PWM4GIR	7:0							S1P2	S1P1			
0x0495	PWM4GIE	7:0							S1P2	S1P1			
0x0496	PWM4CON	7:0	EN					LD	ERSPOL	ERSNOW			
0x0497	PWM4S1CFG	7:0	POL2	POL1			PPEN		MODE[2:0]				
		7:0		-		P1[							
0x0498	PWM4S1P1	15:8				P1[1							
		7:0				P2[							
0x049A	PWM4S1P2	15:8				P2[1							
0x049C	PWMLOAD	7:0					MPWM4LD	MPWM3LD	MPWM2LD	MPWM1LD			
0x049D	PWMEN	7:0					MPWM4EN	MPWM3EN	MPWM2EN	MPWM1EN			
0x049E	PIE0	7:0	IOCIE	CANIE	CLC1IE	TU16AIE	CSWIE	OSFIE	HLVDIE	SWINTIE			
0x049F	PIE1	7:0	SMT1PWAIE	SMT1PRAIE	SMT1IE	CM1IE	ACTIE	ADIE	ZCDIE	INTOIE			
0x04A0	PIE2	7:0	DMA1AIE		DMA1DCNTIE			ADCH3IE	ADCH2IE	ADCH1IE			
0x04A1	PIE3	7:0	TMR0IE	CCP1IE	TMR1GIE	TMR1IE	TMR2IE	SPI1IE	SPI1TXIE	SPI1RXIE			
0x04A2	PIE4	7:0	PWM1IE	PWM1PIE	CANTIE	CANRIE	U1IE	U1EIE	U1TXIE	U1RXIE			
0x04A3	PIE5	7:0	PWM2IE	PWM2PIE	TMR3GIE	TMR3IE	TU16BIE	SPI2IE	SPI2TXIE	SPI2RXIE			
0x04A4	PIE6	7:0	DMA2AIE	DMA2ORIE		DMA2SCNTIE	NCO1IE	CWG1IE	CLC2IE	INT1IE			
0x04A5	PIE7	7:0	PWM3IE	PWM3PIE	CLC3IE	J.I.J. 12.5 G.T.T.	I2C1EIE	I2C1IE	I2C1TXIE	I2C1RXIE			
0x04A6	PIE8	7:0	SCANIE	CCP2IE	TMR5GIE	TMR5IE	U2IE	U2EIE	U2TXIE	U2RXIE			
0x04A7	PIE9	7:0	PWM4IE	PWM4PIE	CLC4IE		U3IE	U3EIE	U3TXIE	U3RXIE			
0x04A8	PIE10	7:0	DMA3AIE	DMA3ORIE	DMA3DCNTIE	DMA3SCNTIE	NCO2IE	CWG2IE	CLC5IE	INT2IE			
0x04A9	PIE11	7:0	DMA4AIE		DMA4DCNTIE		TMR4IE	CWG3IE	CLC6IE	CCP3IE			
0x04AA	PIE12	7:0	DMA5AIE		DMA5DCNTIE		U4IE	U4EIE	U4TXIE	U4RXIE			
0x04AB	PIE13	7:0	DMA6AIE		DMA6DCNTIE		USIE	U5EIE	U5TXIE	U5RXIE			
0x04AC	PIE14	7:0	DMA7AIE	DMA7ORIE	DMA7DCNTIE		NCO3IE	CM2IE	CLC7IE				
0x04AD	PIE15	7:0	DMA8AIE		DMA8DCNTIE	_	TMR6IE	CRCIE	CLC8IE	NVMIE			
0x04AE	PIR0	7:0	IOCIF	CANIF	CLC1IF	TU16AIF	CSWIF	OSFIF	HLVDIF	SWIF			
0x04AF	PIR1	7:0	SMT1PWAIF	SMT1PRAIF	SMT1IF	CM1IF	ACTIF	ADIF	ZCDIF	INTOIF			
0x04B0	PIR2	7:0	DMA1AIF		DMA1DCNTIF		ADCH4IF	ADCH3IF	ADCH2IF	ADCH1IF			
0x04B1	PIR3	7:0	TMR0IF	CCP1IF	TMR1GIF	TMR1IF	TMR2IF	SPI1IF	SPI1TXIF	SPI1RXIF			
0x04B2	PIR4	7:0	PWM1IF	PWM1PIF	CANTIF	CANRIF	U1IF	U1EIF	U1TXIF	U1RXIF			
0x04B3	PIR5	7:0	PWM2IF	PWM2PIF	TMR3GIF	TMR3IF	TU16BIF	SPI2IF	SPI2TXIF	SPI2RXIF			
0x04B4	PIR6	7:0	DMA2AIF	DMA2ORIF		DMA2SCNTIF	NCO1IF	CWG1IF	CLC2IF	INT1IF			
0x04B5	PIR7	7:0	PWM3IF	PWM3PIF	CLC3IF		I2C1EIF	I2C1IF	I2C1TXIF	I2C1RXIF			
0x04B6	PIR8	7:0	SCANIF	CCP2IF	TMR5GIF	TMR5IF	U2IF	U2EIF	U2TXIF	U2RXIF			
0x04B7	PIR9	7:0	PWM4IF	PWM4PIF	CLC4IF		U3IF	U3EIF	U3TXIF	U3RXIF			
0x04B8	PIR10	7:0	DMA3AIF	DMA3ORIF	DMA3DCNTIF	DMA3SCNTIF	NCO2IF	CWG2IF	CLC5IF	INT2IF			
0x04B0	PIR11	7:0	DMA4AIF		DMA4DCNTIF		TMR4IF	CWG2II CWG3IF	CLC6IF	CCP3IF			
0x04B9	PIR12	7:0	DMA5AIF		DMA5DCNTIF		U4IF	U4EIF	U4TXIF	U4RXIF			
0x04BA 0x04BB	PIR13	7:0	DMA6AIF		DMA6DCNTIF			U5EIF	U5TXIF	U5RXIF			
0x04BB	PIR14	7:0	DMA7AIF	DMA70RIF		DMA7SCNTIF	NCO3IF	CM2IF	CLC7IF	OUIVIII			
0x04BC 0x04BD	PIR15	7:0	DMA8AIF		DMA8DCNTIF		TMR6IF	CRCIF	CLC7II	NVMIF			
0x04BD 0x04BE	LATA	7:0	LATA7	LATA6	LATA5	LATA4	LATA3	LATA2	LATA1	LATA0			
0x04BE 0x04BF	LATB	7:0	LATB7	LATB6	LATB5	LATB4	LATB3	LATB2	LATB1	LATB0			
0x04BF 0x04C0	LATC		LATC7	LATC6	LATC5	LATC4	LATC3	LATC2	LATC1	LATC0			
0x04C0 0x04C1	LATD	7:0 7:0	LATD7	LATC6	LATD5	LATD4	LATC3	LATD2	LATD1	LATC0			
0x04C1		7:0	LAIDI	LAIDO	LAIDS	LAID4	LAIDS	LATE2	LATE1				
	LATE		I ATE7	LATER	LATES	I ATEA	I ATE2			LATEO			
0x04C3	LATF	7:0	LATF7	LATF6	LATF5	LATF4	LATF3	LATF2	LATF1	LATF0			

conti	continued										
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0	
	IVallic	Dit 1 03.			,						
0x04C4	Reserved										
0x04C5	Reserved										
0x04C6	TRISA	7:0	TRISA7	TRISA6	TRISA5	TRISA4	TRISA3	TRISA2	TRISA1	TRISA0	
0x04C7	TRISB	7:0	TRISB7	TRISB6	TRISB5	TRISB4	TRISB3	TRISB2	TRISB1	TRISB0	
0x04C8	TRISC	7:0	TRISC7	TRISC6	TRISC5	TRISC4	TRISC3	TRISC2	TRISC1	TRISC0	
0x04C9	TRISD	7:0	TRISD7	TRISD6	TRISD5	TRISD4	TRISD3	TRISD2	TRISD1	TRISD0	
0x04CA	TRISE	7:0					Reserved	TRISE2	TRISE1	TRISE0	
0x04CB	TRISF	7:0	TRISF7	TRISF6	TRISF5	TRISF4	TRISF3	TRISF2	TRISF1	TRISF0	
0x04CC											
	Reserved										
0x04CD	DODTA	7.0	DAZ	DAG	DAF	DA4	DAS	DAG	DA4	BAO	
0x04CE 0x04CF	PORTA PORTB	7:0 7:0	RA7 RB7	RA6 RB6	RA5 RB5	RA4 RB4	RA3 RB3	RA2 RB2	RA1 RB1	RA0 RB0	
0x04CF 0x04D0	PORTC	7:0	RC7	RC6	RC5	RC4	RC3	RC2	RC1	RC0	
0x04D0	PORTD	7:0	RD7	RD6	RD5	RD4	RD3	RD2	RD1	RD0	
0x04D2	PORTE	7:0	1107	1120	1120	1101	RE3	RE2	RE1	RE0	
0x04D3	PORTF	7:0	RF7	RF6	RF5	RF4	RF3	RF2	RF1	RF0	
0x04D4											
	Reserved										
0x04D5											
0x04D6	INTCON0	7:0	GIE/GIEH	GIEL	IPEN			INT2EDG	INT1EDG	INT0EDG	
0x04D7	INTCON1	7:0	STAT	<u> </u>							
0x04D8	STATUS	7:0		TO	PD	N	OV	Z	DC	С	
0x04D9	FSR2	7:0		FSRL[7:0]							
0.0455	DI LIOINO	15:8		FSRH[5:0]							
0x04DB	PLUSW2	7:0					W[7:0]				
0x04DC 0x04DD	PREINC2 POSTDEC2	7:0 7:0					IC[7:0] EC[7:0]				
0x04DD 0x04DE	POSTDEC2 POSTINC2	7:0					NC[7:0]				
0x04DE	INDF2	7:0					F[7:0]				
0x04E0	BSR	7:0				III		2[5:0]			
		7:0				FSR	L[7:0]	.[0.0]			
0x04E1	FSR1	15:8						H[5:0]			
0x04E3	PLUSW1	7:0				PLUS	W[7:0]				
0x04E4	PREINC1	7:0				PREIN	IC[7:0]				
0x04E5	POSTDEC1	7:0					EC[7:0]				
0x04E6	POSTINC1	7:0				POSTI	NC[7:0]				
0x04E7	INDF1	7:0					[7:0]				
0x04E8	WREG	7:0					G[7:0]				
0x04E9	FSR0	7:0				FSR	L[7:0]	ITE 01			
		15:8				DI LIO		H[5:0]			
0x04EB 0x04EC	PLUSW0 PREINC0	7:0 7:0					W[7:0] IC[7:0]				
0x04EC 0x04ED	POSTDEC0	7:0					EC[7:0]				
0x04EB	POSTINC0	7:0					NC[7:0]				
0x04EE	INDF0	7:0					[7:0]				
0x04F0	PCON0	7:0	STKOVF	STKUNF	WDTWV	RWDT	RMCLR	RI	POR	BOR	
0x04F1	PCON1	7:0	5	5			· ·····OLI	RVREG	MEMV	RCM	
0x04F2	CPUDOZE	7:0	IDLEN	DOZEN	ROI	DOE			DOZE[2:0]		
		7:0					D[7:0]				
0x04F3	PROD	15:8					D[15:8]				
0x04F5	TABLAT	7:0				TABLA	AT[7:0]				
		7:0				TBLP	ΓR[7:0]				
0x04F6	TBLPTR	15:8				TBLPT	R[15:8]				
		23:16			TBLPTR21			TBLPTR[20:16			
0x04F9	PCL	7:0					[7:0]				
0x04FA	PCLAT	7:0	PCLATH[7:0]								
1		15:8	PCLATU[4:0]								

# PIC18F26/46/56Q84

# **Register Summary**

cont	inued										
		D'' D	_								
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0	
0x04FC	STKPTR	7:0					STKPTR[6:0]				
		7:0				TOS					
0x04FD	TOS	15:8				TOS	[15:8]				
		23:16						TOS[20:16]			
0x0500											
	Reserved										
0x2FFFFF				DOTO ON O							
300000	CONFIG1	7:0		RSTOSC[2:0] FEXTOSC[2:0]							
300001	CONFIG2	7:0	FCMENS	FCMENP	FCMEN	JTAGEN	CSWEN		PR1WAY	CLKOUTEN	
300002	CONFIG3	7:0	BORE	N[1:0]	LPBOREN	IVT1WAY	MVECEN		ΓS[1:0]	MCLRE	
300003	CONFIG4	7:0	XINST		LVP	STVREN	PPS1WAY	ZCD	BOR	V[1:0]	
300004	CONFIG5	7:0		WDT	E[1:0]			WDTCPS[4:0]			
300005	CONFIG6	7:0				WDTCCS[2:0]			WDTCWS[2:0]		
300006	CONFIG7	7:0			DEBUG	SAFEN	BBEN		BBSIZE[2:0]		
300007	CONFIG8	7:0	WRTAPP				WRTSAF	WRTD	WRTC	WRTB	
300008	CONFIG9	7:0			ODCON	BPEN			BOOTPIN	NSEL[1:0]	
300009	CONFIG10	7:0								CP	
30000A30 000A	CONFIG11	7:0	BOOTPOR	COE	CFGSCEN	DATSCEN	SAFSCEN	APPSCEN	BOOTCOE	BOOTSCEN	
		7:0					OL[7:0]				
30000B30	CRC Boot	15:8				BCRCP	OL[15:8]				
000B	Polynomial	23:16				BCRCPC	DL[23:16]				
		31:24		BCRCPOL[31:24]							
		7:0				BCRCSI					
30000F30	CRC Boot Seed	15:8				BCRCSE	ED[15:8]				
000F	CRC Boot Seed	23:16				BCRCSE	ED[23:16]				
		31:24				BCRCSE	ED[31:24]				
		7:0				BCRCE	RES[7:0]				
30001330	CRC Boot Expected	15:8				BCRCEF	RES[15:8]				
0013	Value	23:16				BCRCER					
		31:24				BCRCER					
		7:0				CRCP					
30001730	CRC Polynomial	15:8				CRCPC	DL[15:8]				
0017	Cito i diyildililai	23:16				CRCPO					
		31:24				CRCPO					
		7:0				CRCSE	ED[7:0]				
30001B30	CRC Seed	15:8				CRCSE	ED[15:8]				
001B	Onto ocea	23:16					D[23:16]				
		31:24					ED[31:24]				
		7:0				CRCER	RES[7:0]				
30001F30	CRC Expected	15:8		CRCERES[15:8]							
001F	Value	23:16				CRCERE	ES[23:16]				
		31:24				CRCERE	ES[31:24]				
0x300023 	Reserved										
0x3FFFFB											
0x3FFFFC	REVISIONID	7:0	MJRRE	EV[1:0]			MNRR	EV[5:0]			
2.0.1110		15:8	1010[3:0] MJRREV[5:2]								
0x3FFFFE	DEVICEID	7:0	DEV[7:0]								
		15:8		DEV[15:8]							

# 50. Electrical Specifications

### 50.1 Absolute Maximum Ratings(†)

Parameter		Rating
Ambient temperature under bias		-40°C to +125°C
Storage temperature		-65°C to +150°C
Voltage on pins with respect to V <sub>SS</sub>		
• on V <sub>DD</sub> pin:		-0.3V to +6.5V
• on MCLR pin:		-0.3V to +9.0V
on all other pins:		$-0.3V$ to $(V_{DD} + 0.3V)$
Maximum current <sup>(1)</sup>		
• on V <sub>SS</sub> pin	$-40$ °C $\leq$ T <sub>A</sub> $\leq$ $+85$ °C	350 mA
	$85^{\circ}\text{C} < \text{T}_{A} \le +125^{\circ}\text{C}$	120 mA
<ul> <li>on V<sub>DD</sub> pin (28-pin devices)</li> </ul>	$-40$ °C $\leq$ T <sub>A</sub> $\leq$ $+85$ °C	250 mA
	$85^{\circ}\text{C} < \text{T}_{A} \le +125^{\circ}\text{C}$	85 mA
<ul> <li>on V<sub>DD</sub> pin (40-pin devices)</li> </ul>	$-40$ °C $\leq$ T <sub>A</sub> $\leq$ $+85$ °C	350 mA
	$85^{\circ}\text{C} < \text{T}_{A} \le +125^{\circ}\text{C}$	120 mA
on any standard I/O pin		±50 mA
Clamp current, I <sub>K</sub> (V <sub>PIN</sub> < 0 or V <sub>PIN</sub> > V <sub>DD</sub> )		±20 mA
Total power dissipation <sup>(2)</sup>		800 mW

#### Notes:

- Maximum current rating requires even load distribution across I/O pins. Maximum current rating may be limited
  by the device package power dissipation characterizations, see Thermal Characteristics section to calculate
  device specifications.
- 2. Power dissipation is calculated as follows:  $P_{DIS} = V_{DD} x \{I_{DD} \Sigma I_{OH}\} + \Sigma \{(V_{DD} V_{OH}) x I_{OH}\} + \Sigma (V_{OI} x I_{OL})$

† NOTICE: Stresses above those listed under "**Absolute Maximum Ratings**" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at those or any other conditions above those indicated in the operation listings of this specification is not implied. Exposure above maximum rating conditions for extended periods may affect device reliability.

#### 50.2 Standard Operating Conditions

The standard operating conditions for any device are defined as:


Operating Voltage:  $V_{DDMIN} \le V_{DD} \le V_{DDMAX}$ Operating Temperature:  $T_{A\ MIN} \le T_{A} \le T_{A\ MAX}$ 

Parameter		Ratings
V <sub>DD</sub> — Operating Supply Voltage <sup>(1)</sup>	$V_{\text{DDMIN}}$	+1.8V
	$V_{DDMAX}$	+5.5V
T <sub>A</sub> — Operating Ambient Temperature Range		
Industrial Temperature	$T_{A\_MIN}$	-40°C
	$T_{A\_MAX}$	+85°C
Extended Temperature	$T_{A\_MIN}$	-40°C
	$T_{A\_MAX}$	+125°C

#### Note:

1. See Parameter Supply Voltage in the "DC Characteristics" chapter for more details.

Figure 50-1. Voltage Frequency Graph, -40°C ≤ T<sub>A</sub> ≤ +125°C



#### Notes:

- The shaded region indicates the permissible combinations of voltage and frequency.
- Refer to "External Clock/Oscillator Timing Requirements" table in the "AC Characteristics" chapter for each Oscillator mode's supported frequencies.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 1084

#### 50.3 DC Characteristics

#### 50.3.1 Supply Voltage

Table 50-1.

Davana Na	Cross	Charactariatia	B.ff.i.e	T 4	Max	Huita	Conditions
Param. No.	Sym.	Characteristic	Min.	Typ.†	Max.	Units	Conditions
Supply Volta	age						
D002	V <sub>DD</sub>		1.8	_	5.5	V	
RAM Data R	etention <sup>(1)</sup>						
D003	V <sub>DR</sub>		1.7	_	_	V	Device in Sleep mode
Power-on Re	eset Release	Voltage <sup>(2)</sup>					
D004	V <sub>POR</sub>		_	1.6	_	V	BOR and LPBOR disabled <sup>(3)</sup>
Power-on Re	eset Rearm Vo	oltage <sup>(2)</sup>					
D005	V <sub>PORR</sub>		_	1	_	V	BOR and LPBOR disabled <sup>(3)</sup>
V <sub>DD</sub> Rise Ra	te to ensure i	nternal Power-on Re	set signal <sup>(z</sup>	2)			
D006	S <sub>VDD</sub>		0.05	_	_	V/ms	BOR and LPBOR disabled <sup>(3)</sup>


 $<sup>\</sup>dagger$  Data in "Typ." column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### Notes:

- 1. This is the limit to which  $V_{DD}$  can be lowered in Sleep mode without losing RAM data.
- 2. See the following figure, POR and POR REARM with Slow Rising  $V_{DD}$ .
- 3. See Reset, WDT, Oscillator Start-up Timer, Brown-Out Reset and Low-Power Brown-Out Reset Specifications for BOR and LPBOR trip point information.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 1085

Figure 50-2. POR and POR Rearm with Slow Rising  $\ensuremath{V_{DD}}$ 



#### Notes:

- 1. When NPOR is low, the device is held in Reset.
- 2.  $T_{POR}$  1  $\mu s$  typical.
- 3. T<sub>VLOW</sub> 2.7 μs typical.

## 50.3.2 Supply Current (I<sub>DD</sub>)<sup>(1,2,4)</sup>

#### Table 50-2.

Standard (	Operating Co	nditions (unless otherv	vise stated	d)				
Param.	Sym.	Device	Min.	Typ.†	Max.	Units	Cor	nditions
No.		Characteristics					V <sub>DD</sub>	Note
D100	$I_{DD_{XT4}}$	XT = 4 MHz	_	750	870	μΑ	3.0V	
D100A	I <sub>DD<sub>XT4</sub></sub>	XT = 4 MHz	_	570	700	μA	3.0V	PMD's all 1's
D101	I <sub>DDHFO16</sub>	HFINTOSC = 16 MHz	_	2.3	2.9	mA	3.0V	
D101A	I <sub>DDHFO16</sub>	HFINTOSC = 16 MHz	_	1.6	2.1	mA	3.0V	PMD's all 1's
D102	I <sub>DDHFOPLL</sub>	HFINTOSC = 64 MHz	_	7.7	9	mA	3.0V	
D102A	I <sub>DD<sub>HFOPLL</sub></sub>	HFINTOSC = 64 MHz	_	4.9	6	mA	3.0V	PMD's all 1's
D103	I <sub>DD<sub>HSPLL64</sub></sub>	HS+PLL = 64 MHz	_	7.5	13.8	mA	3.0V	
D103A	I <sub>DD<sub>HSPLL64</sub></sub>	HS+PLL = 64 MHz	_	4.7	11.5	mA	3.0V	PMD's all 1's
D104	I <sub>DDIDLE</sub>	Idle mode, HFINTOSC = 16 MHz	_	1.6	2.5	mA	3.0V	
D105	I <sub>DDDOZE</sub> (3)	Doze mode, HFINTOSC = 16 MHz, Doze Ratio = 16	_	1.7	2.6	mA	3.0V	

continued Standard Operating Conditions (unless otherwise stated)								
Param.	Sym.	Device	Min.	Typ.†	Max.	Units	Con	ditions
No.		Characteristics					V <sub>DD</sub>	Note

† Data in "Typ." column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### Notes:

- 1. The test conditions for all I<sub>DD</sub> measurements in Active Operation mode are: OSC1 = external square wave,
  - rail-to-rail; all I/O pins are outputs driven low;  $\overline{MCLR} = V_{DD}$ ; WDT disabled.
- The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O pin loading and switching rate, oscillator type, internal code execution pattern and temperature, also have an impact on the current consumption.
- $I_{\text{DD}_{\text{DOZE}}} = [I_{\text{DD}_{\text{IDLE}}}^*(\text{N-1})/\text{N}] + I_{\text{DD}_{\text{HFO}}} 16/\text{N}$  where N = Doze Ratio (see **CPUDOZE** register). PMD bits are all in the Default state, no modules are disabled.

#### 50.3.3 Power-Down Current (I<sub>PD</sub>)<sup>(1,2)</sup>

#### Table 50-3.

Standar	d Operating C	onditions (unless	otherw	∕ise stat	ed)					
Param.	Sym.	Device	Min.	Typ.†	Max.	Max.	Units		Conditio	ns
No.		Characteristics			+85°C	+125°C		V <sub>DD</sub>	VREGPM	Note
D200	I <sub>PD</sub>	I <sub>PD</sub> Base	_	1.4	5	7	μA	3.0V	'b11	
			_	1.2	15	50	μA	3.0V	'b10	
			_	38.3	55	95	μA	3.0V	'b01	
			_	170	215	220	μA	3.0V	'b00	
D201	I <sub>PD_WDT</sub>	Low-Frequency Internal Oscillator/WDT	_	1.7	5.5	7.5	μA	3.0V	'b11	
D202	I <sub>PD_SOSC</sub>	Secondary Oscillator (S <sub>OSC</sub> )	_	2.4	4.6	7.9	μA	3.0V	'b11	
D203	I <sub>PD_LPBOR</sub>	Low-Power Brown-out Reset (LPBOR)	_	1.6	5.2	7.2	μA	3.0V	'b11	
D204	I <sub>PD_FVR_BUF1</sub>	FVR Buffer 1 (ADC)	_	186	230	240	μA	3.0V	'b11	
D204A	I <sub>PD_FVR_BUF2</sub>	FVR Buffer 2 (DAC/CMP)	_	59	85	120	μA	3.0V	'bx1 or 'b10	
D205	I <sub>PD_BOR</sub>	Brown-out Reset (BOR)	_	17.4	25	25.5	μA	3.0V	'b11	
D206	I <sub>PD_HLVD</sub>	High/Low Voltage Detect (HLVD)	_	18.2	25	25.5	μA	3.0V	'b11	
D207	I <sub>PD_ADCA</sub>	ADC - Active	_	560	789	790	μA	3.0V	'bx1 or 'b10	ADC is converting (Note 4)

со	continued										
Standard Operating Conditions (unless otherwise stated)											
Param. Sym. Device Min. Typ.† Max. Max. Units Conditions							ns				
No.		Characteristics			+85°C	+125°C		V <sub>DD</sub>	VREGPM	Note	
D208	I <sub>PD_CMP</sub>	Comparator	_	62	84.2	120	μΑ	3.0V	'b11		

<sup>\*</sup> These parameters are characterized but not tested.

† Data in "Typ." column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### Notes:

- 1. The peripheral current is the sum of the base  $I_{DD}$  and the additional current consumed when this peripheral is enabled. The peripheral  $\Delta$  current can be determined by subtracting the base  $I_{DD}$  or  $I_{PD}$ current from this limit. Max. values should be used when calculating total current consumption.
- 2. The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode with all I/O pins in high-impedance state and tied to V<sub>SS</sub>.
- 3. All peripheral currents listed are on a per-peripheral basis if more than one instance of a peripheral is available.
- 4. ADC clock source is ADCRC.

#### 50.3.4 I/O Ports

#### Table 50-4.

Standard O	perating C	onditions (unless othe	rwise state	d)			
Param. No.	Sym.	Device Characteristics	Min.	Typ.†	Max.	Units	Conditions
Input Low V	oltage						
	$V_{IL}$	I/O PORT:					
D300		with TTL buffer	_	_	0.8	V	$4.5 \text{V} \le \text{V}_{\text{DD}} \le 5.5 \text{V}$
D301			_	_	0.15 V <sub>DD</sub>	V	$1.8V \le V_{DD} < 4.5V$
D302		with Schmitt     Trigger buffer	_	<del></del>	0.2 V <sub>DD</sub>	V	$2.0V \le V_DD \le 5.5V$
D303		with I <sup>2</sup> C levels	_	_	0.3 V <sub>DD</sub>	V	$2.0 \text{V} \le \text{V}_{\text{DD}} \le 5.5 \text{V}$
D304	_	with SMBus 2.0	_	_	8.0	V	$2.7V \le V_{DD} \le 5.5V$
D305		with SMBus 3.0	_	_	8.0	V	
D306		MCLR	_	_	0.2 V <sub>DD</sub>	V	
High Low Vo	oltage						
	$V_{IH}$	I/O PORT:					
D320		with TTL buffer	2.0	_	_	V	$4.5V \le V_{DD} \le 5.5V$
D321			0.25 V <sub>DD</sub> + 0.8	_	_	V	$1.8V \le V_{DD} < 4.5V$
D322		with Schmitt     Trigger buffer	0.8 V <sub>DD</sub>	_	_	V	$2.0V \le V_{DD} \le 5.5V$
D323	_	with I <sup>2</sup> C levels	0.7 V <sub>DD</sub>	_	_	V	
D324		with SMBus 2.0	2.1	_	_	V	$2.7 \text{V} \le \text{V}_{\text{DD}} \le 5.5 \text{V}$
D325		with SMBus 3.0	1.35	_	_	V	
D326		MCLR	0.7 V <sub>DD</sub>	_	_	V	

contii Standard O		onditions (unless othe	rwise state	d)			
Param. No.	Sym.	Device Characteristics	Min.	Typ.†	Max.	Units	Conditions
Input Leaka	ge Curren	t <sup>(1)</sup>					
D340	I <sub>IL</sub>	I/O PORTS	_	±5	±125	nA	V <sub>SS</sub> ≤ V <sub>PIN</sub> ≤ V <sub>DD</sub> , Pin at high- impedance, 85°C
D341			_	±5	±1000	nA	V <sub>SS</sub> ≤ V <sub>PIN</sub> ≤ V <sub>DD</sub> , Pin at high- impedance, 125°C
D342		MCLR <sup>(2)</sup>	_	±50	±200	nA	$V_{SS} \le V_{PIN} \le V_{DD}$ , Pin at high- impedance, 85°C
Weak Pull-u	p Current						
D350	I <sub>PUR</sub>		80	140	200	μА	$V_{DD} = 3.0V,$ $V_{PIN} = V_{SS}$
Output Low	Voltage						
D360	V <sub>OL</sub>	I/O PORTS	_	_	0.6	V	I <sub>OL</sub> = 10.0 mA, V <sub>PIN</sub> = 3.0V
Output High	Voltage						
D370	V <sub>OH</sub>	I/O PORTS	V <sub>DD</sub> - 0.7	_	_	V	I <sub>OH</sub> = 6.0 mA, V <sub>PIN</sub> = 3.0V
All I/O Pins							
D380	C <sub>IO</sub>		_	5	50	pF	

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### Notes:

- 1. Negative current is defined as current sourced by the pin.
- 2. The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.

#### 50.3.5 Memory Programming Specifications

#### Table 50-5.

Standar	Standard Operating Conditions (unless otherwise stated)										
Param No.	Sym.	Device Characteristics	Min.	Тур†	Max.	Units	Conditions				
Data EE	Data EEPROM Memory Specifications										
MEM20	E <sub>D</sub>	DataEE Byte Endurance	100k	_	_	E/W	-40°C ≤ T <sub>A</sub> ≤ +85°C				
MEM21	T <sub>D_RET</sub>	Characteristic Retention	_	40	_	Year	Provided no other specifications are violated				
MEM23	$V_{D\_RW}$	V <sub>DD</sub> for Read or Erase/Write operation	V <sub>DDMIN</sub>	_	$V_{DDMAX}$	V					
MEM24	MEM24 T <sub>D_BEW</sub> Byte Erase and Write Cycle Time — — 11 ms										
Program	Program Flash Memory Specifications										

co	ntinued						
Standar	d Operat	ing Conditions (unless otherwise s	stated)				
Param No.	Sym.	Device Characteristics	Min.	Тур†	Max.	Units	Conditions
MEM30	E <sub>P</sub>	Flash Memory Cell Endurance	10k	_	_	E/W	-40°C ≤ T <sub>A</sub> ≤ +85°C (Note 1)
MEM32	T <sub>P_RET</sub>	Characteristic Retention	_	40	_	Year	Provided no other specifications are violated
МЕМ33	$V_{P\_RD}$	V <sub>DD</sub> for Read operation	$V_{DDMIN}$	_	$V_{DDMAX}$	V	
MEM34	$V_{P\_REW}$	V <sub>DD</sub> for Row Erase or Write operation	V <sub>DDMIN</sub>	_	$V_{DDMAX}$	V	
MEM35	T <sub>P_REW</sub>	Self-Timed Page Write	_	_	10	ms	
MEM36	T <sub>SE</sub>	Self-Timed Page Erase	_	_	11	ms	
MEM37	T <sub>P_WRD</sub>	Self-Timed Word Write	_	_	75	μs	

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### Note:

#### 50.3.6 Thermal Characteristics

#### Table 50-6.

Standard Op	perating	Conditions (unless otherwise stated)			
Param No.	Sym.	Characteristic	Тур.	Units	Conditions
TH01	$\theta_{JA}$	Thermal Resistance Junction to Ambient	60	°C/W	28-pin SPDIP package
			80	°C/W	28-pin SOIC package
			90	°C/W	28-pin SSOP package
			27.5	°C/W	28-pin VQFN 4x4 mm package
			47.2	°C/W	40-pin PDIP package
			29	°C/W	40-pin QFN package
			46	°C/W	44-pin TQFP package
			62.8	°C/W	48-pin TQFP package
			24.8	°C/W	48-pin VQFN package
TH02	T <sub>JMAX</sub>	Maximum Junction Temperature	150	°C	
Noto:					


#### Note:

1. See "Absolute Maximum Ratings" for total power dissipation.

Flash Memory Cell Endurance for the Flash memory is defined as: One Row Erase operation and one Self-Timed Write.

#### 50.4 AC Characteristics


#### Figure 50-3. Load Conditions



Legend: CL=50 pF for all pins

#### 50.4.1 External Clock/Oscillator Timing Requirements

Figure 50-4. Clock Timing



Note: See table below.

Table 50-7.

Standard O	Standard Operating Conditions (unless otherwise stated)											
Param No.	Sym.	Characteristic	Min.	Тур. †	Max.	Units	Conditions					
ECL Oscilla	itor											
OS1	F <sub>ECL</sub>	Clock Frequency	_	_	1	MHz						
OS2	T <sub>ECL_DC</sub>	Clock Duty Cycle	40	_	60	%						
ECM Oscilla	ator											
OS3	F <sub>ECM</sub>	Clock Frequency	_	_	16	MHz						
OS4	T <sub>ECM_DC</sub>	Clock Duty Cycle	40	_	60	%						
ECH Oscilla	ator											
OS5	F <sub>ECH</sub>	Clock Frequency	_	_	64	MHz						
OS6	T <sub>ECH_DC</sub>	Clock Duty Cycle	40	_	60	%						
LP Oscillate	or											
OS7	F <sub>LP</sub>	Clock Frequency	_	_	100	kHz	(Note 4)					
XT Oscillate	or											
OS8	F <sub>XT</sub>	Clock Frequency	_	_	4	MHz	(Note 4)					
HS Oscillat	or											
OS9	F <sub>HS</sub>	Clock Frequency	_	_	20	MHz	V <sub>DD</sub> > 2.5V (Note 4)					

contir	nued										
Standard Operating Conditions (unless otherwise stated)											
Param No.	Sym.	Characteristic	Min.	Typ. †	Max.	Units	Conditions				
Secondary	Oscillator			,	,						
OS10	F <sub>SEC</sub>	Clock Frequency	32.4	32.768	33.1	kHz	(Note 4)				
System Osc	cillator						•				
OS20	Fosc	System Clock Frequency	_	_	64	MHz	(Note 2, Note 3)				
OS21	F <sub>CY</sub>	Instruction Frequency	_	F <sub>OSC</sub> /4	_	MHz					
OS22	T <sub>CY</sub>	Instruction Period	62.5	1/F <sub>CY</sub>	_	ns					

#### Notes:

- 1. Instruction cycle period (TCY) equals four times the input oscillator time base period. All specified values are based on characterization data for that particular oscillator type under standard operating conditions with the device executing code. Exceeding these specified limits may result in an unstable oscillator operation and/or higher than expected current consumption. All devices are tested to operate at "min" values with an external clock applied to OSC1 pin. When an external clock input is used, the "max" cycle time limit is "DC" (no clock) for all devices.
- 2. The system clock frequency (F<sub>OSC</sub>) is selected by the "main clock switch controls" as described in the "Power Saving Operation Modes" section.
- 3. The system clock frequency (F<sub>OSC</sub>) must meet the voltage requirements defined in the "Standard Operating Conditions" section.
- 4. LP, XT and HS oscillator modes require an appropriate crystal or resonator to be connected to the device. For clocking the device with the external square wave, one of the EC mode selections must be used.

# 50.4.2 Internal Oscillator Parameters<sup>(1)</sup>

#### Table 50-8.

Standard O	perating Cond	itions (unless otherwi	se stated)				
Param No.	Sym.	Characteristic	Min.	Typ. †	Max.	Units	Conditions
OS50	F <sub>HFOSC</sub>	Precision Calibrated HFINTOSC Frequency	_	4 8 12 16 32 48 64	_	MHz	(Note 2)
OS51	FHFOSCLP	Low-Power Optimized HFINTOSC Frequency	_	1 2	_	MHz MHz	Fundamental Freq.1 MHz Fundamental Freq. 2 MHz
OS52	F <sub>MFOSC</sub>	Internal Calibrated MFINTOSC Frequency	_	500	_	kHz	


contii	nued						
Standard O	perating Cond	itions (unless otherwi	ise stated)				
Param No.	Sym.	Characteristic	Min.	Typ. †	Max.	Units	Conditions
OS53*	F <sub>LFOSC</sub>	Internal LFINTOSC Frequency	_	31	_	kHz	
OS54*	T <sub>HFOSCST</sub>	HFINTOSC Wake- up from Sleep Start- up Time	_	30 100	40 —	μs μs	VREGPM = 0x VREGPM = 1x System Clock at 4 MHz
OS56	T <sub>LFOSCST</sub>	LFINTOSC Wake-up from Sleep Start-up Time	_	0.3	_	ms	

<sup>\*</sup> These parameters are characterized but not tested.

#### Notes:

- 1. To ensure these oscillator frequency tolerances,  $V_{DD}$  and  $V_{SS}$  must be capacitively decoupled as close to the device as possible. 0.1  $\mu$ F and 0.01  $\mu$ F values in parallel are recommended.
- 2. See the figure below.

Figure 50-5. Precision Calibrated HFINTOSC Frequency Accuracy Over Device  $V_{\text{DD}}$  and Temperature



## 50.4.3 PLL Specifications

Table 50-9.

Standard Operating Conditions (unless otherwise stated)										
Param No.	Sym.	Characteristic	Min.	Тур. †	Max.	Units	Conditions			
PLL01	F <sub>PLLIN</sub>	PLL Input Frequency Range	4	_	16	MHz				

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

continu	continued										
Standard Operating Conditions (unless otherwise stated)											
Param No.	Sym.	Characteristic	Min.	Тур. †	Max.	Units	Conditions				
PLL02	F <sub>PLLOUT</sub>	PLL Output Frequency Range	16	_	64	MHz	(Note 1)				
PLL03*	F <sub>PLLST</sub>	PLL Lock Time	_	200	_	μs					
PLL04*	F <sub>PLLJIT</sub>	PLL Output Frequency Stability	-0.25	_	0.25	%					

<sup>\*</sup> These parameters are characterized but not tested.

† Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### Note:

1. The output frequency of the PLL must meet the  $F_{\mbox{\scriptsize OSC}}$  requirements listed in Parameter D002.

#### 50.4.4 I/O and CLKOUT Timing Specifications

Figure 50-6. CLKOUT and I/O Timing





Table 50-10. I/O and CLKOUT Timing Specifications

Standard C	Standard Operating Conditions (unless otherwise stated)											
Param No.	Sym.	Characteristic	Min.	Typ. †	Max.	Units	Conditions					
IO1*	T <sub>CLKOUTH</sub>	CLKOUT rising edge delay (rising edge F <sub>OSC</sub> (Q1 cycle) to falling edge CLKOUT	_	_	70	ns						
IO2*	T <sub>CLKOUTL</sub>	CLKOUT falling edge delay (rising edge F <sub>OSC</sub> (Q3 cycle) to rising edge CLKOUT	_	_	72	ns						
IO3*	T <sub>IO_VALID</sub>	Port output valid time (rising edge F <sub>OSC</sub> (Q1 cycle) to port valid)	_	50	70	ns						
IO4*	T <sub>IO_SETUP</sub>	Port input setup time (Setup time before rising edge F <sub>OSC</sub> – Q2 cycle)	20	_	_	ns						
IO5*	T <sub>IO_HOLD</sub>	Port input hold time (Hold time after rising edge F <sub>OSC</sub> – Q2 cycle)	50	_	_	ns						
IO6*	T <sub>IOR_SLREN</sub>	Port I/O rise time, slew rate enabled	_	25	_	ns	V <sub>DD</sub> = 3.0V					

Standard Operating Conditions (unless otherwise stated)										
Param No.	Sym.	Characteristic	Min.	Typ. †	Max.	Units	Conditions			
IO7*	T <sub>IOR_SLRDIS</sub>	Port I/O rise time, slew rate disabled	_	5	_	ns	V <sub>DD</sub> = 3.0V			
IO8*	T <sub>IOF_SLREN</sub>	Port I/O fall time, slew rate enabled	_	25	_	ns	V <sub>DD</sub> = 3.0V			
IO9*	T <sub>IOF_SLRDIS</sub>	Port I/O fall time, slew rate disabled	_	5	_	ns	V <sub>DD</sub> = 3.0V			
IO10*	T <sub>INT</sub>	INT pin high or low time to trigger an interrupt	25	_	_	ns				
IO11*	T <sub>IOC</sub>	Interrupt-on-Change minimum high or low time to trigger interrupt	25	<u> </u>	_	ns				

# 50.4.5 Reset, WDT, Oscillator Start-up Timer, Power-up Timer, Brown-Out Reset and Low-Power Brown-Out Reset Specifications


Figure 50-7. Reset, Watchdog Timer, Oscillator Start-up Timer and Power-up Timer Timing



#### Note:

1. Asserted low.

Figure 50-8. Brown-out Reset Timing and Characteristics



#### Note:

1. Only if  $\overline{PWRTE}$  Configuration bit is programmed to '1'; 2 ms delay if  $\overline{PWRTE}$  = 0.

Table 50-11.

Standard Op	erating Con	ditions (unless otherwis	e stated)				
Param No.	Sym.	Characteristic	Min.	Typ. †	Max.	Units	Conditions
RST01*	T <sub>MCLR</sub>	MCLR Pulse Width Low to ensure Reset	_	_	_	μs	
RST02*	T <sub>IOZ</sub>	I/O high-impedance from Reset detection	_		2	μs	
RST03	T <sub>WDT</sub>	Watchdog Timer Time- out Period	_	16	_	ms	<b>WDTCPS =</b> 00100
RST04*	T <sub>PWRT</sub>	Power-up Timer Period	_	65	_	ms	
RST05	T <sub>OST</sub>	Oscillator Start-up Timer Period <sup>(1,2)</sup>	_	1024		T <sub>OSC</sub>	
RST06	$V_{BOR}$	Brown-out Reset	2.7	2.85	3.0	V	BORV = 00
		Voltage	2.55	2.7	2.85	V	BORV = 01
			2.3	2.45	2.6	V	BORV = 10
			1.8	1.9	2.1	V	BORV = 11
RST07	V <sub>BORHYS</sub>	Brown-out Reset Hysteresis	_	60		mV	BORV = 00
RST08	T <sub>BORDC</sub>	Brown-out Reset Response Time	_	3	_	μs	
RST09	$V_{LPBOR}$	Low-Power Brown-out Reset Voltage	1.8	1.9	2.2	V	

<sup>\*</sup> These parameters are characterized but not tested.

† Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### Notes:

- 1. By design, the Oscillator Start-up Timer (OST) counts the first 1024 cycles, independent of frequency.
- 2. To ensure these voltage tolerances,  $V_{DD}$  and  $V_{SS}$  must be capacitively decoupled as close to the device as possible. 0.1  $\mu$ F and 0.01  $\mu$ F values in parallel are recommended.

# 50.4.6 High/Low-Voltage Detect Characteristics

Table 50-12.

Standard Ope	erating Con	ditions (unless other	wise stated)				
Param No.	Sym.	Characteristic	Min.	Тур.	Max.	Units	Conditions
HLVD01	$V_{DET}$	Voltage Detect	1.73 <sup>(1)</sup>	1.90	2.07	V	HLVDSEL = 0000
			1.91	2.10	2.29	V	HLVDSEL = 0001
			2.05	2.25	2.45	V	HLVDSEL = 0010
			2.28	2.50	2.73	V	HLVDSEL = 0011
			2.37	2.60	2.83	V	HLVDSEL = 0100
		2.5	2.75	3.00	V	HLVDSEL = 0101	
			2.64	2.90	3.16	V	HLVDSEL = 0110
			2.87	3.15	3.43	V	HLVDSEL = 0111
			3.05	3.35	3.65	V	HLVDSEL = 1000
			3.28	3.60	3.92	V	HLVDSEL = 1001
			3.41	3.75	4.09	V	HLVDSEL = 1010
			3.64	4.00	4.36	V	HLVDSEL = 1011
			3.82	4.20	4.58	V	HLVDSEL = 1100
			3.96	4.35	4.74	V	HLVDSEL = 1101
			4.23	4.65	5.07	V	HLVDSEL = 1110

<sup>\*</sup> These parameters are characterized but not tested.

#### Note:

1. Device operation below  $V_{DD} = 1.8 \text{ V}$  is not recommended.

# 50.4.7 Analog-to-Digital Converter (ADC) Accuracy Specifications<sup>(1,2)</sup> Table 50-13.

#### **Standard Operating Conditions (unless otherwise stated)** $V_{DD} = 3.0V, T_A = 25^{\circ}C, T_{AD} = 500ns$ Param No. Sym. Characteristic Min. Typ. † Max. Units **Conditions** AD01 $N_{\mathsf{R}}$ Resolution 12 bit AD02 $E_{IL}$ Integral Non-Linearity Error ±0.1 ±2.0 LSb $ADC_{REF} + = 3.0V$ $ADC_{REF} = 0V$ AD03 Differential Non-Linearity Error ±0.1 ±1.0 LSb $ADC_{REF} + = 3.0V$ $E_{DL}$ $ADC_{RFF} = 0V$ AD04 Offset Error 0.5 6.0 LSb $ADC_{REF}$ + = 3.0V, **E**OFF $ADC_{REF} = 0V$ $ADC_{REF}$ + = 3.0V, AD05 Gain Error ±6.0 LSb $E_{GN}$ ±0.2 $ADC_{RFF}$ = 0VAD06 $V_{ADREF}$ ADC Reference Voltage (ADREF+ -1.8 $V_{DD}$ V AD<sub>REF</sub>-) AD07 Full-Scale Range V AD<sub>REF</sub>-AD<sub>REF</sub>+ $V_{AIN}$

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### .....continued Standard Operating Conditions (unless otherwise stated) $V_{DD} = 3.0V, T_A = 25^{\circ}C, T_{AD} = 500ns$ Param No. Sym. Characteristic Min. Typ. † Max. **Units** Conditions AD08 $Z_{\text{AIN}}$ Recommended Impedance of Analog 1 kΩ Voltage Source AD09 ADC Voltage Reference Ladder 50 kΩ (Note 3) **R**VREF Impedance

† Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### Notes:

- 1. Total Absolute Error is the sum of the offset, gain and integral nonlinearity (INL) errors.
- 2. The ADC conversion result never decreases with an increase in the input and has no missing codes.
- 3. This is the impedance seen by the V<sub>REF</sub> pads when the external reference pads are selected.

# 50.4.8 Analog-to-Digital Converter (ADC) Conversion Timing Specifications Table 50-14.

Standard O	Standard Operating Conditions (unless otherwise stated)											
Param No.	Sym.	Characteristic	Min.	Typ. †	Max.	Units	Conditions					
AD20	T <sub>AD</sub>	ADC Clock Period	0.5	_	9	μs	Using F <sub>OSC</sub> as the ADC clock source ADOCS = 0					
			_	2	_	μs	Using ADCRC as the ADC clock source ADOCS = 1					
AD21	T <sub>CNV</sub>	Conversion Time	_	14 T <sub>AD</sub> +2T <sub>CY</sub>	_	_	Using F <sub>OSC</sub> as the ADC clock source ADOCS = 0					
			_	16 T <sub>AD</sub> +2T <sub>CY</sub>	_	_	Using ADCRC as the ADC clock source ADOCS = 1					
AD22	T <sub>HCD</sub>	Sample-and-Hold Capacitor Disconnect Time	_	2 T <sub>AD</sub> +1T <sub>CY</sub>	_	_	Using F <sub>OSC</sub> as the ADC clock source ADOCS = 0					
			_	3 T <sub>AD</sub> +2T <sub>CY</sub>	_	_	Using ADCRC as the ADC clock source ADOCS = 1					

<sup>\*</sup> These parameters are characterized but not tested.

© 2020 Microchip Technology Inc. Preliminary Datasheet DS40002259A-page 1098

<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

DS40002259A-page 1099

Figure 50-9. ADC Conversion Timing (ADC Clock F<sub>OSC</sub>-Based)





Figure 50-10. ADC Conversion Timing (ADC Clock from ADCRC)



Note 1: If the ADC dock source is selected as ADCRC, a time of 1 TCY is added before the ADC clock starts. This allows the SLEEP instruction to be executed, if any.

#### 50.4.9 Comparator Specifications

Table 50-15.

Standard Operating Conditions (unless otherwise stated) $V_{DD}$ = 3.0V, $T_A$ = 25°C										
Param No.	Sym.	Characteristic	Min.	Тур. †	Max.	Units	Conditions			
CM01	V <sub>IOFF</sub>	Input Offset Voltage	_	_	±50	mV	$V_{ICM} = V_{DD}/2$			
CM02	V <sub>ICM</sub>	Input Common Mode Range	GND	_	$V_{DD}$	V				
CM03 CMRR Common Mode Input — 50 — dB Rejection Ratio										

# .....continued

**Standard Operating Conditions (unless otherwise stated)** 

 $V_{DD} = 3.0V, T_A = 25^{\circ}C$ 

Param No.	Sym.	Characteristic	Min.	Typ. †	Max.	Units	Conditions
CM04	V <sub>HYST</sub>	Comparator Hysteresis	10	25	45	mV	
CM05	T <sub>RESP</sub> (1)	Response Time, Rising Edge	_	300	600	ns	
		Response Time, Falling Edge	_	220	500	ns	

<sup>\*</sup> These parameters are characterized but not tested.

† Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### Note:

1. Response time measured with one comparator input at  $V_{DD}/2$ , while the other input transitions from  $V_{SS}$  to  $V_{DD}$ .

#### 50.4.10 8-Bit DAC Specifications

#### Table 50-16.

Standard Ope	Standard Operating Conditions (unless otherwise stated)V <sub>DD</sub> = 3.0V, T <sub>A</sub> = 25°C											
Param No.	Sym.	Characteristic	Min.	Typ. †	Max.	Units	Conditions					
DSB01	$V_{LSB}$	Step Size	_	(V <sub>DACREF</sub> +- V <sub>DACREF</sub> -)/256	_	V						
DSB02	V <sub>ACC</sub>	Absolute Accuracy	_	_	±0.5	LSb						
DSB03*	R <sub>UNIT</sub>	Unit Resistor Value	_	20	_	kΩ						
DSB04*	T <sub>ST</sub>	Settling Time <sup>(1)</sup>	_	10	_	μs						
DSB05*	$V_{DBO}$	DAC Buffer Offset	_	20	45	mV						

<sup>\*</sup> These parameters are characterized but not tested.

#### Note:

1. Settling time measured while DACR[7:0] transitions from 'b00000000 to 'b11111111

#### 50.4.11 Fixed Voltage Reference (FVR) Specifications

#### Table 50-17.

Standard Operating Conditions (unless otherwise stated)									
Param No.	Sym.	Characteristic	Min.	Тур. †	Max.	Units	Conditions		
FVR01	V <sub>FVR</sub> 1	1x Gain (1.024V)	-4	_	+4	%	V <sub>DD</sub> ≥ 2.5V, -40°C to 85°C		
FVR02	V <sub>FVR</sub> 2	2x Gain (2.048V)	-4	_	+4	%	V <sub>DD</sub> ≥ 2.5V, -40°C to 85°C		
FVR03	V <sub>FVR</sub> 4	4x Gain (4.096V)	-5	_	+5	%	V <sub>DD</sub> ≥ 4.75V, -40°C to 85°C		
FVR04	T <sub>FVRST</sub>	FVR Start-up Time	_	25	_	μs			

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

## 50.4.12 Zero-Cross Detect (ZCD) Specifications

Table 50-18.

Standard Operating Conditions (unless otherwise stated) $V_{DD}$ = 3.0V, $T_A$ = 25°C										
Param No.	Sym.	Characteristic	Min.	Тур. †	Max.	Units	Conditions			
ZC01	V <sub>PINZC</sub>	Voltage on Zero Cross Pin	_	0.9	_	V				
ZC02	I <sub>ZCD_MAX</sub>	Maximum source or sink current	_	_	600	μA				
ZC03	T <sub>RESPH</sub>	Response Time, Rising Edge	_	1	_	μs				
	T <sub>RESPL</sub>	Response Time, Falling Edge	_	1	_	μs				

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

# 50.4.13 Timer0 and Timer1 External Clock Requirements

Table 50-19.

Standard	Operating Co	onditions (unle	ss otherwise stated					
Operating	Temperature	e: -40°C≤T <sub>A</sub> ≤+1	25°C					
Param No.	Sym.	Cha	aracteristic	Min.	Тур. †	Max.	Units	Conditions
40*	T <sub>T</sub> 0H	T0CKI High	No Prescaler	0.5T <sub>CY</sub> +20	_	_	ns	
		Pulse Width	With Prescaler	10	_	_	ns	
41*	T <sub>T</sub> 0L	T0CKI Low	No Prescaler	0.5T <sub>CY</sub> +20	_	_	ns	
		Pulse Width	With Prescaler	10	_	_	ns	
42*	T <sub>T</sub> 0P	T0CKI Period	I	Greater of: 20 or (T <sub>CY</sub> +40)/N		_	ns	N = Prescale value
45*	T <sub>T</sub> 1H	T1CKI High Time	Synchronous, No Prescaler	0.5T <sub>CY</sub> +20	_	_	ns	
			Synchronous, with Prescaler	15	_	_	ns	
			Asynchronous	30	_	_	ns	
46*	T <sub>T</sub> 1L	T1CKI Low Time	Synchronous, No Prescaler	0.5T <sub>CY</sub> +20	_	_	ns	
			Synchronous, with Prescaler	15	_	_	ns	
			Asynchronous	30	_	_	ns	

#### .....continued **Standard Operating Conditions (unless otherwise stated)** Operating Temperature: -40°C≤T<sub>A</sub>≤+125°C Param Sym. Characteristic Min. Typ. † Max. Units Conditions No. 47\* T<sub>T</sub>1P T1CKI Input Synchronous Greater of: N = Prescale ns Period 30 or (T<sub>CY</sub> value +40)/N Asynchronous 60 ns 49\* TCKEZ<sub>TMR</sub>1 Delay from External Clock Edge 2 Tosc 7 Tosc Timers in Sync to Timer Increment mode

TOCKI

TICKI

TIMRO or TMR1

Figure 50-11. Timer0 and Timing1 External Clock Timings

#### 50.4.14 Capture/Compare/PWM Requirements (CCP)

Table 50-20.

	Standard Operating Conditions (unless otherwise stated)											
Operating Temperature: -40°C ≤ T <sub>A</sub> ≤ +125°C												
Param No.	Param No. Sym. Characteristic Min. Typ. † Max. Units Conditions											
CC01*	T <sub>CC</sub> L	CCPx Input	No Prescaler	0.5T <sub>CY</sub> +20	_	_	ns					
	Low Time		With Prescaler	20	_	_	ns					
CC02*	T <sub>CC</sub> H	CCPx Input	No Prescaler	0.5T <sub>CY</sub> +20	_	_	ns					
		High Time	With Prescaler	20	_	_	ns					
CC03*	CC03* T <sub>CC</sub> P CCPx Input Period (3T <sub>CY</sub> +40)/N — ns N = Prescale value											


<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

# Standard Operating Conditions (unless otherwise stated) Operating Temperature: -40°C ≤ T<sub>A</sub> ≤ +125°C Param No. Sym. Characteristic Min. Typ. † Max. Units Conditions

† Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Figure 50-12. Capture/Compare/PWM Timings (CCP)



Note: Refer to Load Conditions for more details.

#### 50.4.15 SPI Mode Requirements

#### Table 50-21. SPI MASTER MODE

Standard	Standard Operating Conditions (unless otherwise stated)										
Param No.	Sym.	Characteristic	Min.	Тур. †	Max.	Units	Conditions				
			61	_	_	ns	Transmit only				
	T <sub>SCK</sub>	SCK Cycle Time (2x	_	16 <sup>(1)</sup>	_	MHz	mode				
	ISCK	Prescaled)	95	_	_	ns	Full-Duplex				
			_	10 <sup>(1)</sup>	_	MHz	mode				
SP70*	T <sub>SS</sub> L2 <sub>SC</sub> H,	SDO to SCK↓ or	T <sub>SCK</sub>	_	_	ns	<b>FST =</b> 0				
	T <sub>SS</sub> L2 <sub>SC</sub> L	SCK↑ input	0	_	_	ns	FST = 1				
SP71*	T <sub>SC</sub> H	SCK output high time	0.5 T <sub>SCK</sub> - 12	_	0.5 T <sub>SCK</sub> + 12	ns					
SP72*	T <sub>SC</sub> L	SCK output low time	0.5 T <sub>SCK</sub> - 12	_	0.5 T <sub>SCK</sub> + 12	ns					
SP73*	T <sub>DI</sub> V2 <sub>SC</sub> H, T <sub>DI</sub> V2 <sub>SC</sub> L	Setup time of SDI data input to SCK edge	85	_	_	ns					
SP74*	T <sub>SC</sub> H2 <sub>DI</sub> L, T <sub>SC</sub> L2 <sub>DI</sub> L	Hold time of SDI data input to SCK edge	0	_	_	ns					
	ЗС Ы	Hold time of SDI data input to final SCK	0.5 T <sub>SCK</sub>			ns	CKE = 0, SMP = 1				
SP75*	T <sub>DO</sub> R	SDO data output rise time	_	10	25	ns	C <sub>L</sub> = 50 pF				
SP76*	T <sub>DO</sub> F	SDO data output fall time	_	10	25	ns	C <sub>L</sub> = 50 pF				
SP78*	T <sub>SC</sub> R	SCK output rise time	_	10	25	ns	C <sub>L</sub> = 50 pF				

<sup>\*</sup> These parameters are characterized but not tested.

cont	continued										
Standard Operating Conditions (unless otherwise stated)											
Param No.	Sym.	Characteristic	Min.	Тур. †	Max.	Units	Conditions				
SP79*	T <sub>SC</sub> F	SCK output fall time	_	10	25	ns	C <sub>L</sub> = 50 pF				
SP80*	$T_{SC}H2_{DO}V$ , $T_{SC}L2_{DO}V$	SDO data output valid after SCK edge	-15	_	15	ns	C <sub>L</sub> = 50 pF				
SP81*	$T_{DO}V2_{SC}H$ , $T_{DO}V2_{SC}L$	SDO data output valid to first SCK edge	T <sub>SCK</sub> - 10	_	_	ns	C <sub>L</sub> = 50 pF CKE = 1				
SP82*	T <sub>SS</sub> L2 <sub>DO</sub> V	SDO data output valid after SS↓ edge	_	_	50	ns	C <sub>L</sub> = 20 pF				
SP83*	T <sub>SC</sub> H2 <sub>SS</sub> H, T <sub>SC</sub> L2 <sub>SS</sub> H	SS ↑ after last SCK edge	T <sub>SCK</sub> - 10	_	_	ns					
SP84*	T <sub>SS</sub> H2 <sub>SSL</sub>	SS ↑ to SS↓ edge	T <sub>SCK</sub> - 10	_	_	ns					

<sup>\*</sup> These parameters are characterized but not tested.

#### Note:

1. SMP bit in the SPIxCON1 register must be set and the slew rate control must be disabled on the clock and data pins (clear the corresponding bits in SLRCONx register) for SPI to operate over 4 MHz.

Table 50-22. SPI SLAVE MODE

Standard C	Standard Operating Conditions (unless otherwise stated)										
Param No.	Sym.	Characteristic	Min.	Тур. †	Max.	Units	Conditions				
	T <sub>SCK</sub>	SCK Total Cycle Time	47	_	_	ns	Receive Only				
			<del>_</del>	20 <sup>(1)</sup>	_	MHz	mode				
			95	_	_	ns	Full-Duplex				
			_	10 <sup>(1)</sup>	_	MHz	mode				
SP70*	T <sub>SS</sub> L2 <sub>SC</sub> H,	SS↓ to SCK↓ or SCK↑	0	_	_	ns	<b>CKE =</b> 0				
	T <sub>SS</sub> L2 <sub>SC</sub> L	input	25	_	_	ns	CKE = 1				
SP71*	T <sub>SC</sub> H	SCK input high time	20	_	_	ns					
SP72*	T <sub>SC</sub> L	SCK input low time	20	_	_	ns					
SP73*	T <sub>DI</sub> V2 <sub>SC</sub> H, T <sub>DI</sub> V2 <sub>SC</sub> L	Setup time of SDI data input to SCK edge	10	_	_	ns					
SP74*	T <sub>SC</sub> H2 <sub>DI</sub> L, T <sub>SC</sub> L2 <sub>DI</sub> L	Hold time of SDI data input to SCK edge	0	_	_	ns					
SP75*	T <sub>DO</sub> R	SDO data output rise time	_	10	25	ns	C <sub>L</sub> = 50 pF				

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

conti	nued									
Standard Operating Conditions (unless otherwise stated)										
Param No.	Sym.	Characteristic	Min.	Typ. †	Max.	Units	Conditions			
SP76*	T <sub>DO</sub> F	SDO data output fall time	_	10	25	ns	C <sub>L</sub> = 50 pF			
SP77*	T <sub>SS</sub> H2 <sub>DO</sub> Z	SS↑ to SDO output high-impedance			85	ns				
SP80*	$T_{SC}H2_{DO}V$ , $T_{SC}L2_{DO}V$	SDO data output valid after SCK edge	_	_	85	ns				
SP82*	T <sub>SS</sub> L2 <sub>DO</sub> V	SDO data output valid after SS↓ edge			85	ns				
SP83*	T <sub>SC</sub> H2 <sub>SS</sub> H, T <sub>SC</sub> L2 <sub>SS</sub> H	SS ↑ after SCK edge	20	_	_	ns				
SP84*	T <sub>SS</sub> H2 <sub>SSL</sub>	SS ↑ to SS↓ edge	47	_	_	ns				

<sup>\*</sup> These parameters are characterized but not tested.

#### Note:

1. SMP bit in the SPIxCON1 register must be set and the slew rate control must be disabled on the clock and data pins (clear the corresponding bits in SLRCONx register) for SPI to operate over 4 MHz.


SS SP81 (CKP = 0) SP72 SP78 SCK (CKP = 1)SP79 SP78 SP80 -SDO MSb LSb → <del>←</del> SP75. SP76 SDI MSb In LSb In - SP74 SP73

Figure 50-13. SPI Master Mode Timing (CKE = 0, SMP = 0)

Note: Refer to Load Conditions for more details.


<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Figure 50-14. SPI Master Mode Timing (CKE = 1, SMP = 1)




Note: Refer to Load Conditions for more details.

Figure 50-15. SPI Slave Mode Timing (CKE = 0)




Note: Refer to Load Conditions for more details.



Note: Refer to Load Conditions for more details.

# 50.4.16 I<sup>2</sup>C Bus Start/Stop Bits Requirements Table 50-23.

Standard Operating Conditions (unless otherwise stated)									
Param. No.	Sym.	Characteristic			Typ. †	Max.	Units	Conditions	
SP90*	T <sub>SU:STA</sub>	Start condition	100 kHz mode	4700	_	_	ns	Only relevant for Repeated Start condition	
		Setup time	400 kHz mode	600	_	_			
			1 MHz mode	260	_	_			
SP91*	T <sub>HD:STA</sub>	Start condition	100 kHz mode	4000	_	_	ns	After this period, the first clock	
		Hold time	400 kHz mode	600	_	_		pulse is generated	
			1 MHz mode	260	_	_			
SP92*	T <sub>SU:STO</sub>	Stop condition Setup time	100 kHz mode	4000	_	_	ns		
			400 kHz mode	600	_	_			
			1 MHz mode	260	_	_			
SP93*	T <sub>HD:STO</sub>	Stop condition	100 kHz mode	4700	_	_	ns		
		Hold time	400 kHz mode	1300	_	_			
			1 MHz mode	500	_	_			
* These para	meters a	re characterized	but not tested.						



Note: Refer to Load Conditions for more details.

# 50.4.17 I<sup>2</sup>C Bus Data Requirements

Table 50-24.

Standard Operating Conditions (unless otherwise stated)								
Param. No.	Sym.	Characte	eristic	Min.	Max.	Units	Conditions	
SP100*	T <sub>HIGH</sub>	Clock high time	100 kHz mode	4000	_	ns	Device must operate at a minimum of 1.5 MHz	
			400 kHz mode	600	_	ns	Device must operate at a minimum of 10 MHz	
			1 MHz mode	260	_	ns	Device must operate at a minimum of 10 MHz	
SP101*	T <sub>LOW</sub>	Clock low time	100 kHz mode	4700	_	ns	Device must operate at a minimum of 1.5 MHz	
			400 kHz mode	1300	_	ns	Device must operate at a minimum of 10 MHz	
			1 MHz mode	500	_	ns	Device must operate at a minimum of 10 MHz	
SP102*	T <sub>R</sub>	SDA and SCL rise time	100 kHz mode	_	1000	ns		
			400 kHz mode	20	300	ns	C <sub>B</sub> is specified to be from 10-400 pF	
			1 MHz mode	_	120			

continued Standard Operating Conditions (unless otherwise stated)								
Param. No.	Sym.	m. Characteristic Min. Max. Units C					Conditions	
SP103*	T <sub>F</sub>	SDA and SCL fall time	100 kHz mode	_	250	ns		
			400 kHz mode	20 × (V <sub>DD</sub> / 5.5V)	250	ns	C <sub>B</sub> is specified to be from 10-400 pF	
			1 MHz mode	20 × (V <sub>DD</sub> / 5.5V)	120	ns		
SP106*	T <sub>HD:DAT</sub>	Data input hold time	100 kHz mode	0	_	ns		
			400 kHz mode	0		ns		
			1 MHz mode	0	_	ns		
SP107*	T <sub>SU:DAT</sub>	Data input setup time	100 kHz mode	250		ns	(Note 2)	
			400 kHz mode	100		ns		
			1 MHz mode	50	_	ns		
SP109*	T <sub>AA</sub>	Output valid from clock	100 kHz mode	_	3450	ns	(Note 1)	
			400 kHz mode	_	900	ns		
			1 MHz mode		450	ns		
SP110*	T <sub>BUF</sub>	Bus free time	100 kHz mode	4700	_	ns	Time the bus must be free before a	
			400 kHz mode	1300	_	ns	new transmission can start	
			1 MHz mode	500	<u>—</u>	ns		
SP111	Св	Bus capacitive loading	100 kHz mode	_	400	pF		
			400 kHz mode	_	400	pF		
			1 MHz mode		26	pF	(Note 3)	


continued								
Standard Op	Standard Operating Conditions (unless otherwise stated)							
Param. No.	Sym.	Characteristic	Min.	Max.	Units	Conditions		

<sup>\*</sup> These parameters are characterized but not tested.

#### Notes:

- 1. As a transmitter, the device must provide this internal minimum delay time to bridge the undefined region (min. 300 ns) of the falling edge of SCL to avoid unintended generation of Start or Stop conditions.
- 2. A Fast mode (400 kHz) I<sup>2</sup>C bus device can be used in a Standard mode (100 kHz) I<sup>2</sup>C bus system, but the requirement T<sub>SU:DAT</sub> ≥ 250 ns must then be met. This will automatically be the case if the device does not stretch the low period of the SCL signal. If such a device does stretch the low period of the SCL signal, it must output the next data bit to the SDA line TR max. + T<sub>SU:DAT</sub> = 1000 + 250 = 1250 ns (according to the Standard mode I<sup>2</sup>C bus specification), before the SCL line is released.
- 3. Using internal I<sup>2</sup>C pull-ups. For greater bus capacitance use external pull-ups.

Figure 50-18. I<sup>2</sup>C Bus Data Timing



Note: Refer to Load Conditions for more details.

# 50.4.18 Configurable Logic Cell (CLC) Characteristics Table 50-25.

#### **Standard Operating Conditions (unless otherwise stated)** Operating Temperature: -40°C≤T<sub>A</sub>≤+125°C Units Conditions Param No. Sym. Characteristic Min. Typ. † Max. CLC01\* CLC input time 7 105 (Note 1) T<sub>CI CIN</sub> ns CI C02\* CLC module input to output 24 $V_{DD} = 1.8V$ T<sub>CLC</sub> ns propagation time $V_{DD} > 3.6V$ 12 ns CLC03\* CLC output time Rise Time 106 (Note 1) T<sub>CLCOUT</sub> Fall Time **IO8** (Note 1) CLC04\* **OS20** CLC maximum switching F<sub>CLCMAX</sub> frequency


#### Note:

1. See "I/O and CLKOUT Timing Specifications" section for IO5, IO6 and IO8 rise and fall times.

<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Figure 50-19. CLC Propagation Timing



#### 50.4.19 Temperature Indicator Requirements

Table 50-26.

Standard Operating Conditions (unless otherwise stated)									
Param No.	Sym.	Characte	eristic	Min.	Typ. †	Max.	Units	Conditions	
TS01*	T <sub>ACQMIN</sub>	Minimum ADC Acquisition Time Delay		_	25	_	μs		
TS02*	M <sub>V</sub> Voltage Sensitivity		High Range	_	-3.75	_	mV/°C	TSRNG = 1	
		Sensitivity	Low Range	_	-2.75	_	mV/°C	TSRNG = 0	

<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

# 51. DC and AC Characteristics Graphs and Tables

Graphs and tables are not available at this time.

## 52. Packaging Information


Package Marking Information

Legend: XX...X Customer-specific information or Microchip part number
Y Year code (last digit of calendar year)
YY Year code (last 2 digits of calendar year)
WW Week code (week of January 1 is week '01')
NNN Alphanumeric traceability code


b-free JEC ® designator for Matte Tin (Sn)
This package is Pb-free. The Pb-free JEDEC designator (@3)
can be found on the outer packaging for this package.

In the event the full Microchip part number cannot be marked on one line, it will be carried over to the next line, thus limiting the number of available characters for customer-specific information.


28-Lead SPDIP (.300")









28-Lead SOIC (7.50 mm)




Example




28-Lead SSOP (5.30 mm)




Example




28-Lead VQFN (6x6x1 mm)



Example




40-Lead PDIP (600 mil)



Example




44-Lead TQFP (10x10x1 mm)




Example




48-Lead VQFN (6x6x0.9 mm)




Example



48-Lead TQFP (7x7x1 mm)



Example




## 52.1 Package Details

The following sections give the technical details of the packages.

#### 28-Lead Skinny Plastic Dual In-Line (SP) - 300 mil Body [SPDIP]

**lote:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units			INCHES			
	Dimension Limits			MAX			
Number of Pins	N		28				
Pitch	е		.100 BSC				
Top to Seating Plane	A	_	-	.200			
Molded Package Thickness	A2	.120	.135	.150			
Base to Seating Plane	A1	.015	-	-			
Shoulder to Shoulder Width	E	.290	.310	.335			
Molded Package Width	E1	.240	.285	.295			
Overall Length	D	1.345	1.365	1.400			
Tip to Seating Plane	L	.110	.130	.150			
Lead Thickness	С	.008	.010	.015			
Upper Lead Width	b1	.040	.050	.070			
Lower Lead Width	b	.014	.018	.022			
Overall Row Spacing §	eB	-	-	.430			

#### Notes:


- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. § Significant Characteristic.
- 3. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.


Microchip Technology Drawing C04-070B

# 28-Lead Plastic Small Outline (SO) - Wide, 7.50 mm Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging









Microchip Technology Drawing C04-052C Sheet 1 of 2  $\,$ 

## 28-Lead Plastic Small Outline (SO) - Wide, 7.50 mm Body [SOIC]

For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging





Units		MILLIMETERS			
Dimensior	Limits	MIN	NOM	MAX	
Number of Pins	N		28		
Pitch	е		1.27 BSC		
Overall Height	Α	•	-	2.65	
Molded Package Thickness	A2	2.05	-	-	
Standoff §	A1	0.10	-	0.30	
Overall Width	Е	10.30 BSC			
Molded Package Width	E1	7.50 BSC			
Overall Length	D	17.90 BSC			
Chamfer (Optional)	h	0.25	-	0.75	
Foot Length	L	0.40	-	1.27	
Footprint	L1		1.40 REF		
Lead Angle	Θ	0°	-	ı	
Foot Angle	$\varphi$	0°	-	8°	
Lead Thickness	С	0.18	-	0.33	
Lead Width	b	0.31	-	0.51	
Mold Draft Angle Top	α	5°	-	15°	
Mold Draft Angle Bottom	β	5°	-	15°	


#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. § Significant Characteristic
- 3. Dimension D does not include mold flash, protrusions or gate burrs, which shall not exceed 0.15 mm per end. Dimension E1 does not include interlead flash or protrusion, which shall not exceed 0.25 mm per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M
  - BSC: Basic Dimension. Theoretically exact value shown without tolerances.
  - REF: Reference Dimension, usually without tolerance, for information purposes only.
- 5. Datums A & B to be determined at Datum H.

Microchip Technology Drawing C04-052C Sheet 2 of 2

28-Lead Plastic Small Outline (SO) - Wide, 7.50 mm Body [SOIC]

For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



#### RECOMMENDED LAND PATTERN

	N	<b>IILLIMETER</b>	S	
Dimension Limits		MIN	NOM	MAX
Contact Pitch	Е	1.27 BSC		
Contact Pad Spacing	С		9.40	
Contact Pad Width (X28)	Х			0.60
Contact Pad Length (X28)	Υ			2.00
Distance Between Pads	Gx	0.67		
Distance Between Pads	G	7.40		

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2052A

# 28-Lead Plastic Shrink Small Outline (SS) - 5.30 mm Body [SSOP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging






Microchip Technology Drawing C04-073 Rev C Sheet 1 of 2

## 28-Lead Plastic Shrink Small Outline (SS) - 5.30 mm Body [SSOP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Units		MILLIMETERS			
Dimension Limits		MIN	NOM	MAX	
Number of Pins	N		28		
Pitch	е		0.65 BSC		
Overall Height	Α	-	-	2.00	
Molded Package Thickness	A2	1.65	1.75	1.85	
Standoff	A1	0.05	-	-	
Overall Width	Е	7.40	7.80	8.20	
Molded Package Width	E1	5.00	5.30	5.60	
Overall Length	D	9.90	10.20	10.50	
Foot Length	L	0.55	0.75	0.95	
Footprint	L1	1.25 REF			
Lead Thickness	С	0.09	-	0.25	
Foot Angle	φ	0°	4°	8°	
Lead Width	b	0.22	-	0.38	

### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.20mm per side.
- 3. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-073 Rev C Sheet 2 of 2

# 28-Lead Plastic Shrink Small Outline (SS) - 5.30 mm Body [SSOP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



#### RECOMMENDED LAND PATTERN

Units		MILLIMETERS		
Dimension Limits		MIN	NOM	MAX
Contact Pitch	Е	0.65 BSC		
Contact Pad Spacing	С		7.00	
Contact Pad Width (X28)	X1			0.45
Contact Pad Length (X28)	Y1			1.85
Contact Pad to Center Pad (X26)	G1	0.20		


#### Notes:

- Dimensioning and tolerancing per ASME Y14.5M
   BSC: Basic Dimension. Theoretically exact value shown without tolerances.
- 2. For best soldering results, thermal vias, if used, should be filled or tented to avoid solder loss during reflow process

Microchip Technology Drawing C04-2073 Rev B

# 28-Lead Very Thin Plastic Quad Flat, No Lead Package (5N) - 6x6x1.0 mm Body [VQFN] 4.10x4.10 mm Exposed Pad, Wettable Flanks (Stepped)


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Microchip Technology Drawing  $\,$  C04-401C Sheet 1 of 2  $\,$ 

## 28-Lead Very Thin Plastic Quad Flat, No Lead Package (5N) - 6x6x1.0 mm Body [VQFN] 4.10x4.10 mm Exposed Pad, Wettable Flanks (Stepped)

For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Units		MILLIMETERS			
Dimension	Dimension Limits		NOM	MAX	
Number of Terminals	Ν		28		
Pitch	е		0.65 BSC		
Overall Height	Α	0.80	0.90	1.00	
Standoff	A1	0.00	0.02	0.05	
Terminal Thickness	A3	0.20 REF			
Step Height	A4	0.05	0.12	0.19	
Overall Width	Е	6.00 BSC			
Exposed Pad Width	E2	4.00	4.10	4.20	
Overall Length	D		6.00 BSC		
Exposed Pad Length	D2	4.00	4.10	4.20	
Terminal Width	р	0.25	0.30	0.35	
Terminal Length	L	0.50	0.60	0.70	
Step Length	L1	0.035	0.060	0.085	
Terminal-to-Exposed Pad	K		0.35 REF		

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Package is saw singulated
- 3. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-401C Sheet 2 of 2

# 28-Lead Very Thin Plastic Quad Flat, No Lead Package (5N) - 6x6x1.0 mm Body [VQFN] 4.10x4.10 mm Exposed Pad, Wettable Flanks (Stepped)

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



### RECOMMENDED LAND PATTERN

	MILLIMETERS			
Dimension Limits		MIN	NOM	MAX
Contact Pitch	E		0.65 BSC	
Optional Center Pad Width	X2			3.80
Optional Center Pad Length	Y2			3.80
Contact Pad Spacing	C1		5.90	
Contact Pad Spacing	C2		5.90	
Contact Pad Width (X28)	X1			0.35
Contact Pad Length (X28)	Y1			0.85
Contact Pad to Center Pad (X28)	G1	0.20		
Thermal Via Diameter	V		0.30	
Thermal Via Pitch	EV		1.00	

#### Notes:


- Dimensioning and tolerancing per ASME Y14.5M
   BSC: Basic Dimension. Theoretically exact value shown without tolerances.
- For best soldering results, thermal vias, if used, should be filled or tented to avoid solder loss during reflow process

Microchip Technology Drawing C04-2401B

DS40002259A-page 1125

## 40-Lead Plastic Dual In-Line (P) - 600 mil Body [PDIP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units		INCHES	
Dimensi	on Limits	MIN	NOM	MAX
Number of Pins	N		40	
Pitch	е		.100 BSC	
Top to Seating Plane	Α	_	_	.250
Molded Package Thickness	A2	.125	_	.195
Base to Seating Plane	A1	.015	_	_
Shoulder to Shoulder Width	Е	.590	_	.625
Molded Package Width	E1	.485	_	.580
Overall Length	D	1.980	_	2.095
Tip to Seating Plane	L	.115	_	.200
Lead Thickness	С	.008	_	.015
Upper Lead Width	b1	.030	_	.070
Lower Lead Width	b	.014	_	.023
Overall Row Spacing §	eВ	-	_	.700

#### Notes:


- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. § Significant Characteristic.
- 3. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M.

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing C04-016B

# 40-Lead Very Thin Plastic Quad Flat, No Lead Package (NHX) - 5x5 mm Body [VQFN] With 3.7x3.7 mm Exposed Pad and Wettable Flanks


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Microchip Technology Drawing C04-425A Sheet 1 of 2

# 40-Lead Very Thin Plastic Quad Flat, No Lead Package (NHX) - 5x5 mm Body [VQFN] With 3.7x3.7 mm Exposed Pad and Wettable Flanks

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Units		MILLIMETERS			
Dimension	Dimension Limits		NOM	MAX	
Number of Terminals	N		40		
Pitch	е		0.40 BSC		
Overall Height	Α	0.80	0.85	0.90	
Standoff	A1	0.00	0.02	0.05	
Terminal Thickness	A3	0.203 REF			
Overall Length	D	5.00 BSC			
Exposed Pad Length	D2	3.60	3.70	3.80	
Overall Width	Е		5.00 BSC		
Exposed Pad Width	E2	3.60	3.70	3.80	
Terminal Width	b	0.15 0.20 0.25			
Terminal Length	L	0.30	0.40	0.50	
Terminal-to-Exposed-Pad	K		0.25 REF		

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Package is saw singulated
- 3. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-425A Sheet 2 of 2

## 40-Lead Very Thin Plastic Quad Flat, No Lead Package (NHX) - 5x5 mm Body [VQFN] With 3.7x3.7 mm Exposed Pad and Wettable Flanks

Note: For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



#### RECOMMENDED LAND PATTERN

Units		MILLIMETERS		
Dimension Limits		MIN	NOM	MAX
Contact Pitch	Е		0.40 BSC	
Optional Center Pad Width	X2			3.80
Optional Center Pad Length	Y2			3.80
Chamfer	CH		0.38	
Contact Pad Spacing	C1		5.00	
Contact Pad Spacing	C2		5.00	
Contact Pad Width (X40)	X1			0.20
Contact Pad Length (X40)	Y1			0.80
Contact Pad to Pad (X36)	G1	0.20		
Contact Pad to Center Pad (X40)	G2	0.20		
Thermal Via Diameter	V		0.30	
Thermal Via Pitch	EV		1.00	


#### Notes:

- 1. Dimensioning and tolerancing per ASME Y14.5M
  - BSC: Basic Dimension. Theoretically exact value shown without tolerances.
- 2. For best soldering results, thermal vias, if used, should be filled or tented to avoid solder loss during reflow process

Microchip Technology Drawing C04-2425A

## 44-Lead Plastic Thin Quad Flatpack (PT) - 10x10x1.0 mm Body [TQFP]


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Microchip Technology Drawing C04-076C Sheet 1 of 2

## 44-Lead Plastic Thin Quad Flatpack (PT) - 10x10x1.0 mm Body [TQFP]

For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Units		MILLIMETERS			
Dimension Limits		MIN	NOM	MAX	
Number of Leads	N		44		
Lead Pitch	е		0.80 BSC		
Overall Height	Α	-	-	1.20	
Standoff	A1	0.05	-	0.15	
Molded Package Thickness	A2	0.95	1.00	1.05	
Overall Width	Е	12.00 BSC			
Molded Package Width	E1	10.00 BSC			
Overall Length	D		12.00 BSC		
Molded Package Length	D1		10.00 BSC		
Lead Width	b	0.30	0.37	0.45	
Lead Thickness	С	0.09	-	0.20	
Lead Length	Ĺ	0.45	0.60	0.75	
Footprint	L1	1.00 REF			
Foot Angle	θ	0°	3.5°	7°	

#### Notes

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Exact shape of each corner is optional.
- 3. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-076C Sheet 2 of 2

# 44-Lead Plastic Thin Quad Flatpack (PT) - 10X10X1 mm Body, 2.00 mm Footprint [TQFP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



RECOMMENDED LAND PATTERN

Units		MILLIMETERS			
Dimension Limits		MIN	NOM	MAX	
Contact Pitch	Е	E 0.80 BSC			
Contact Pad Spacing	C1		11.40		
Contact Pad Spacing	C2		11.40		
Contact Pad Width (X44)	X1			0.55	
Contact Pad Length (X44)	Y1			1.50	
Distance Between Pads	G	0.25			

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2076B

# 48-Lead Very Thin Plastic Quad Flat, No Lead Package (6MX) - 6x6 mm Body [VQFN] With 4.1x4.1 mm Exposed Pad and Stepped Wettable Flanks


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Microchip Technology Drawing C04-504 Rev A Sheet 1 of 2

# 48-Lead Very Thin Plastic Quad Flat, No Lead Package (6MX) - 6x6 mm Body [VQFN] With 4.1x4.1 mm Exposed Pad and Stepped Wettable Flanks

For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Units		MILLIMETERS			
Dimension Limits		MIN	NOM	MAX	
Number of Terminals	N		48		
Pitch	е		0.40 BSC		
Overall Height	Α	0.80	0.85	0.90	
Standoff	A1	0.00	0.02	0.05	
Terminal Thickness	A3	0.20 REF			
Overall Length	D	6.00 BSC			
Exposed Pad Length	D2	4.00	4.10	4.20	
Overall Width	Е		6.00 BSC		
Exposed Pad Width	E2	4.00	4.10	4.20	
Exposed Pad Corner Chamfer	CH		0.35 REF		
Terminal Width	b	0.15	0.20	0.25	
Terminal Length	L	0.30	0.40	0.50	
Terminal-to-Exposed-Pad	K	0.55 REF			
Wettable Flank Step Length	D3	-	-	0.085	
Wettable Flank Step Height	A4	0.10	-	0.19	

#### Notes:

Note:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Package is saw singulated
- 3. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-504 Rev A Sheet 2 of 2

# 48-Lead Very Thin Plastic Quad Flat, No Lead Package (6MX) - 6x6 mm Body [VQFN] With 4.1x4.1 mm Exposed Pad and Stepped Wettable Flanks

**lote:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



## RECOMMENDED LAND PATTERN

Units		MILLIMETERS		
Dimension Limits		MIN	NOM	MAX
Contact Pitch	Е	0.40 BSC		
Optional Center Pad Width	X2	4.20		
Optional Center Pad Length	Y2	4.20		
Contact Pad Spacing	C1		5.90	
Contact Pad Spacing	C2		5.90	
Contact Pad Width (X48)	X1			0.20
Contact Pad Length (X48)	Y1			0.85
Contact Pad to Center Pad (X48)	G1	0.20		
Contact Pad to Contact Pad (X44)	G2	0.20		
Thermal Via Diameter	V		0.30	
Thermal Via Pitch	EV	1.00		


#### Notes:

- 1. Dimensioning and tolerancing per ASME Y14.5M
  - ${\it BSC: Basic Dimension. Theoretically exact value shown without tolerances.}$
- For best soldering results, thermal vias, if used, should be filled or tented to avoid solder loss during reflow process

Microchip Technology Drawing C04-2504 Rev A

## 48-Lead Thin Quad Flatpack (PT) - 7x7x1.0 mm Body [TQFP] With Exposed Pad


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Microchip Technology Drawing C04-183A Sheet 1 of 2

## 48-Lead Thin Quad Flatpack (PT) - 7x7x1.0 mm Body [TQFP] With Exposed Pad

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Units		MILLIMETERS		
Dimension Limits		MIN	NOM	MAX
Number of Leads	N	48		
Lead Pitch	е	0.50 BSC		
Overall Height	Α	1.20		
Standoff	A1	0.05 - 0.15		
Molded Package Thickness	A2	0.95 1.00 1.05		
Foot Length	L	0.45	0.60	0.75
Footprint	L1	1.00 REF		
Foot Angle	ф	0°	3.5°	7°
Overall Width	Е	9.00 BSC		
Overall Length	D	9.00 BSC		
Molded Package Width	E1	7.00 BSC		
Molded Package Length	D1	7.00 BSC		
Exposed Pad Width	E2	3.50 BSC		
Exposed Pad Length	D2	3.50 BSC		
Lead Thickness	С	0.09	-	0.16
Lead Width	b	0.17	0.22	0.27
Mold Draft Angle Top	α	11°	12°	13°
Mold Draft Angle Bottom	β	11°	12°	13°

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Chamfers at corners are optional; size may vary.
- 3. Dimensions D1 and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.25mm per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-183A Sheet 2 of 2

## 48-Lead Thin Quad Flatpack (PT) - 7x7x1.0 mm Body [TQFP] With Thermal Tab

Note: For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



## **RECOMMENDED LAND PATTERN**

Units		MILLIMETERS		
Dimension Limits		MIN	NOM	MAX
Contact Pitch	Е	0.50 BSC		
Optional Center Tab Width	X2		3.50	
Optional Center Tab Length	Y2		3.50	
Contact Pad Spacing	C1		8.40	
Contact Pad Spacing	C2		8.40	
Contact Pad Width (X48)	X1			0.30
Contact Pad Length (X48)	Y1			1.50

#### Notes:

1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2183A

**Appendix A: Revision History** 

# 53. Appendix A: Revision History

Doc Rev.	Date	Comments
Α	10/2020	Initial document release.

# The Microchip Website

Microchip provides online support via our website at <a href="www.microchip.com/">www.microchip.com/</a>. This website is used to make files and information easily available to customers. Some of the content available includes:

- **Product Support** Data sheets and errata, application notes and sample programs, design resources, user's guides and hardware support documents, latest software releases and archived software
- General Technical Support Frequently Asked Questions (FAQs), technical support requests, online discussion groups, Microchip design partner program member listing
- Business of Microchip Product selector and ordering guides, latest Microchip press releases, listing of seminars and events, listings of Microchip sales offices, distributors and factory representatives

# **Product Change Notification Service**

Microchip's product change notification service helps keep customers current on Microchip products. Subscribers will receive email notification whenever there are changes, updates, revisions or errata related to a specified product family or development tool of interest.

To register, go to www.microchip.com/pcn and follow the registration instructions.

# **Customer Support**

Users of Microchip products can receive assistance through several channels:


- · Distributor or Representative
- · Local Sales Office
- Embedded Solutions Engineer (ESE)
- · Technical Support

Customers should contact their distributor, representative or ESE for support. Local sales offices are also available to help customers. A listing of sales offices and locations is included in this document.

Technical support is available through the website at: www.microchip.com/support

# **Product Identification System**

To order or obtain information, e.g., on pricing or delivery, refer to the factory or the listed sales office.



Device:	PIC18F26Q84, PIC18F46Q84, PIC18F56Q84		
Tape & Reel Option:	Blank	= Tube	
	Т	= Tape and Reel	
Temperature Range:	1	= -40°C to +85°C (Industrial)	
	E	= -40°C to +125°C (Extended)	
Package:	SP	= 28-lead SPDIP	
	SO	= 28-lead SOIC	
	SS	= 28-lead SSOP	
	STX	= 28-lead VQFN	
	P	= 40-lead PDIP	
	NHX	= 40-lead VQFN	
	PT	= 44-lead TQFP	
	PT	= 48-lead TQFP	
	VSX	= 48-lead VQFN	

#### Examples:

- PIC18F26Q84 T-E/SP: Tape and Reel, Extended temperature, 28-lead SPDIP
- PIC18F46Q84 T-I/PT: Tape and Reel, Industrial temperature, 44-lead TQFP
- PIC18F56Q84 T-I/VSX: Tape and Reel, Industrial temperature, 48-lead VQFN

#### Notes:

- Tape and Reel identifier only appears in the catalog part number description. This identifier is used for ordering purposes and is not printed on the device package. Check with your Microchip Sales Office for package availability with the Tape and Reel option.
- 2. Small form-factor packaging options may be available. Please check www.microchip.com/packaging for small-form factor package availability, or contact your local Sales Office.

# **Microchip Devices Code Protection Feature**

Note the following details of the code protection feature on Microchip devices:

- · Microchip products meet the specifications contained in their particular Microchip Data Sheet.
- Microchip believes that its family of products is secure when used in the intended manner and under normal conditions.
- There are dishonest and possibly illegal methods being used in attempts to breach the code protection features
  of the Microchip devices. We believe that these methods require using the Microchip products in a manner
  outside the operating specifications contained in Microchip's Data Sheets. Attempts to breach these code
  protection features, most likely, cannot be accomplished without violating Microchip's intellectual property rights.
- Microchip is willing to work with any customer who is concerned about the integrity of its code.

Neither Microchip nor any other semiconductor manufacturer can guarantee the security of its code. Code
protection does not mean that we are guaranteeing the product is "unbreakable." Code protection is constantly
evolving. We at Microchip are committed to continuously improving the code protection features of our products.
Attempts to break Microchip's code protection feature may be a violation of the Digital Millennium Copyright Act.
If such acts allow unauthorized access to your software or other copyrighted work, you may have a right to sue
for relief under that Act.

# **Legal Notice**

Information contained in this publication is provided for the sole purpose of designing with and using Microchip products. Information regarding device applications and the like is provided only for your convenience and may be superseded by updates. It is your responsibility to ensure that your application meets with your specifications.

THIS INFORMATION IS PROVIDED BY MICROCHIP "AS IS". MICROCHIP MAKES NO REPRESENTATIONS OR WARRANTIES OF ANY KIND WHETHER EXPRESS OR IMPLIED, WRITTEN OR ORAL, STATUTORY OR OTHERWISE, RELATED TO THE INFORMATION INCLUDING BUT NOT LIMITED TO ANY IMPLIED WARRANTIES OF NON-INFRINGEMENT, MERCHANTABILITY, AND FITNESS FOR A PARTICULAR PURPOSE OR WARRANTIES RELATED TO ITS CONDITION, QUALITY, OR PERFORMANCE.

IN NO EVENT WILL MICROCHIP BE LIABLE FOR ANY INDIRECT, SPECIAL, PUNITIVE, INCIDENTAL OR CONSEQUENTIAL LOSS, DAMAGE, COST OR EXPENSE OF ANY KIND WHATSOEVER RELATED TO THE INFORMATION OR ITS USE, HOWEVER CAUSED, EVEN IF MICROCHIP HAS BEEN ADVISED OF THE POSSIBILITY OR THE DAMAGES ARE FORESEEABLE. TO THE FULLEST EXTENT ALLOWED BY LAW, MICROCHIP'S TOTAL LIABILITY ON ALL CLAIMS IN ANY WAY RELATED TO THE INFORMATION OR ITS USE WILL NOT EXCEED THE AMOUNT OF FEES, IF ANY, THAT YOU HAVE PAID DIRECTLY TO MICROCHIP FOR THE INFORMATION. Use of Microchip devices in life support and/or safety applications is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless Microchip from any and all damages, claims, suits, or expenses resulting from such use. No licenses are conveyed, implicitly or otherwise, under any Microchip intellectual property rights unless otherwise stated.

## **Trademarks**

The Microchip name and logo, the Microchip logo, Adaptec, AnyRate, AVR, AVR logo, AVR Freaks, BesTime, BitCloud, chipKIT, chipKIT logo, CryptoMemory, CryptoRF, dsPIC, FlashFlex, flexPWR, HELDO, IGLOO, JukeBlox, KeeLoq, Kleer, LANCheck, LinkMD, maXStylus, maXTouch, MediaLB, megaAVR, Microsemi, Microsemi logo, MOST, MOST logo, MPLAB, OptoLyzer, PackeTime, PIC, picoPower, PICSTART, PIC32 logo, PolarFire, Prochip Designer, QTouch, SAM-BA, SenGenuity, SpyNIC, SST, SST Logo, SuperFlash, Symmetricom, SyncServer, Tachyon, TimeSource, tinyAVR, UNI/O, Vectron, and XMEGA are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

AgileSwitch, APT, ClockWorks, The Embedded Control Solutions Company, EtherSynch, FlashTec, Hyper Speed Control, HyperLight Load, IntelliMOS, Libero, motorBench, mTouch, Powermite 3, Precision Edge, ProASIC, ProASIC Plus, ProASIC Plus logo, Quiet-Wire, SmartFusion, SyncWorld, Temux, TimeCesium, TimeHub, TimePictra, TimeProvider, WinPath, and ZL are registered trademarks of Microchip Technology Incorporated in the U.S.A.

Adjacent Key Suppression, AKS, Analog-for-the-Digital Age, Any Capacitor, Anyln, AnyOut, Augmented Switching, BlueSky, BodyCom, CodeGuard, CryptoAuthentication, CryptoAutomotive, CryptoCompanion, CryptoController, dsPICDEM, dsPICDEM.net, Dynamic Average Matching, DAM, ECAN, Espresso T1S, EtherGREEN, IdealBridge, In-Circuit Serial Programming, ICSP, INICnet, Intelligent Paralleling, Inter-Chip Connectivity, JitterBlocker, maxCrypto, maxView, memBrain, Mindi, MiWi, MPASM, MPF, MPLAB Certified logo, MPLIB, MPLINK, MultiTRAK, NetDetach, Omniscient Code Generation, PICDEM, PICDEM.net, PICkit, PICtail, PowerSmart, PureSilicon, QMatrix, REAL ICE, Ripple Blocker, RTAX, RTG4, SAM-ICE, Serial Quad I/O, simpleMAP, SimpliPHY, SmartBuffer, SMART-I.S., storClad, SQI, SuperSwitcher, SuperSwitcher II, Switchtec, SynchroPHY, Total Endurance, TSHARC, USBCheck, VariSense, VectorBlox, VeriPHY, ViewSpan, WiperLock, XpressConnect, and ZENA are trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

SQTP is a service mark of Microchip Technology Incorporated in the U.S.A.

The Adaptec logo, Frequency on Demand, Silicon Storage Technology, and Symmcom are registered trademarks of Microchip Technology Inc. in other countries.

GestIC is a registered trademark of Microchip Technology Germany II GmbH & Co. KG, a subsidiary of Microchip Technology Inc., in other countries.

All other trademarks mentioned herein are property of their respective companies.

© 2020, Microchip Technology Incorporated, Printed in the U.S.A., All Rights Reserved.

ISBN: 978-1-5224-6806-6

# **Quality Management System**

For information regarding Microchip's Quality Management Systems, please visit www.microchip.com/quality.



# **Worldwide Sales and Service**

AMERICAS	ASIA/PACIFIC	ASIA/PACIFIC	EUROPE
Corporate Office	Australia - Sydney	India - Bangalore	Austria - Wels
2355 West Chandler Blvd.	Tel: 61-2-9868-6733	Tel: 91-80-3090-4444	Tel: 43-7242-2244-39
Chandler, AZ 85224-6199	China - Beijing	India - New Delhi	Fax: 43-7242-2244-393
Tel: 480-792-7200	Tel: 86-10-8569-7000	Tel: 91-11-4160-8631	Denmark - Copenhagen
Fax: 480-792-7277	China - Chengdu	India - Pune	Tel: 45-4485-5910
Technical Support:	Tel: 86-28-8665-5511	Tel: 91-20-4121-0141	Fax: 45-4485-2829
www.microchip.com/support	China - Chongqing	Japan - Osaka	Finland - Espoo
Web Address:	Tel: 86-23-8980-9588	Tel: 81-6-6152-7160	Tel: 358-9-4520-820
www.microchip.com	China - Dongguan	Japan - Tokyo	France - Paris
Atlanta	Tel: 86-769-8702-9880	Tel: 81-3-6880- 3770	Tel: 33-1-69-53-63-20
Duluth, GA	China - Guangzhou	Korea - Daegu	Fax: 33-1-69-30-90-79
Tel: 678-957-9614	Tel: 86-20-8755-8029	Tel: 82-53-744-4301	Germany - Garching
Fax: 678-957-1455	China - Hangzhou	Korea - Seoul	Tel: 49-8931-9700
Austin, TX	Tel: 86-571-8792-8115	Tel: 82-2-554-7200	Germany - Haan
Tel: 512-257-3370	China - Hong Kong SAR	Malaysia - Kuala Lumpur	Tel: 49-2129-3766400
Boston	Tel: 852-2943-5100	Tel: 60-3-7651-7906	Germany - Heilbronn
Westborough, MA	China - Nanjing	Malaysia - Penang	Tel: 49-7131-72400
Tel: 774-760-0087	Tel: 86-25-8473-2460	Tel: 60-4-227-8870	Germany - Karlsruhe
Fax: 774-760-0088	China - Qingdao	Philippines - Manila	Tel: 49-721-625370
Chicago	Tel: 86-532-8502-7355	Tel: 63-2-634-9065	Germany - Munich
Itasca, IL	China - Shanghai	Singapore	Tel: 49-89-627-144-0
Tel: 630-285-0071	Tel: 86-21-3326-8000	Tel: 65-6334-8870	Fax: 49-89-627-144-44
Fax: 630-285-0075	China - Shenyang	Taiwan - Hsin Chu	Germany - Rosenheim
Dallas	Tel: 86-24-2334-2829	Tel: 886-3-577-8366	Tel: 49-8031-354-560
Addison, TX	China - Shenzhen	Taiwan - Kaohsiung	Israel - Ra'anana
Tel: 972-818-7423	Tel: 86-755-8864-2200	Tel: 886-7-213-7830	Tel: 972-9-744-7705
Fax: 972-818-2924	China - Suzhou	Taiwan - Taipei	Italy - Milan
Detroit	Tel: 86-186-6233-1526	Tel: 886-2-2508-8600	Tel: 39-0331-742611
Novi, MI	China - Wuhan	Thailand - Bangkok	Fax: 39-0331-466781
Tel: 248-848-4000	Tel: 86-27-5980-5300	Tel: 66-2-694-1351	Italy - Padova
Houston, TX	China - Xian	Vietnam - Ho Chi Minh	Tel: 39-049-7625286
Tel: 281-894-5983	Tel: 86-29-8833-7252	Tel: 84-28-5448-2100	Netherlands - Drunen
Indianapolis	China - Xiamen	1500 21 22 21 10 21 10 2	Tel: 31-416-690399
Noblesville, IN	Tel: 86-592-2388138		Fax: 31-416-690340
Tel: 317-773-8323	China - Zhuhai		Norway - Trondheim
Fax: 317-773-5453	Tel: 86-756-3210040		Tel: 47-72884388
Tel: 317-536-2380	1.50.000.000		Poland - Warsaw
Los Angeles			Tel: 48-22-3325737
Mission Viejo, CA			Romania - Bucharest
Tel: 949-462-9523			Tel: 40-21-407-87-50
Fax: 949-462-9608			Spain - Madrid
Tel: 951-273-7800			Tel: 34-91-708-08-90
Raleigh, NC			Fax: 34-91-708-08-91
Tel: 919-844-7510			Sweden - Gothenberg
New York, NY			Tel: 46-31-704-60-40
Tel: 631-435-6000			Sweden - Stockholm
San Jose, CA			Tel: 46-8-5090-4654
Tel: 408-735-9110			UK - Wokingham
Tel: 408-436-4270			Tel: 44-118-921-5800
Canada - Toronto			Fax: 44-118-921-5820
Tel: 905-695-1980			1 ax. 44-110-521-0020
Fax: 905-695-2078			
I AA. 300-030-2070			